Drawing Index

These sheets are a document set and should not be separated. Electrical information and references are contained on all sheets.

SITE READINESS

C1

EQUIPMENT LAYOUT

(Equipment locations, heat loads, component weights, environmental specs)

STRUCTURAL LAYOUT

S1

(Structural support/mounting locations for floor/wall/ceiling, wall support elevations)

STRUCTURAL DETAILS

S2

(Floor and Ceiling loading information)

ELECTRICAL LAYOUT

(Contractor supplied wiring, interconnect methods, junction point locations and descriptions)

ELECTRICAL SPECIFICATIONS

(Maximum wiring run lengths, interconnect diagram, system power specifications)

ELECTRICAL DETAILS

E3

MECHANICAL LAYOUT (Chiller information)

M 1

EQUIPMENT DETAILS

D1 THRU D2

These equipment IS drawings indicate the placement and interconnection of the listed equipment components. These drawings are not construction or site preparation drawings. Customer remains ultimately responsible for preparing the site to accommodate the IS and operation of such equipment in compliance with GE Healthcare's written specifications and all applicable federal, state, and/or local requirements.

* REQUIRED REFERENCE *

Optima MR450w

Pre Installation Manual

5670001

A mandatory component of this drawing set is the GE Healthcare Pre Installation manual. Failure to reference the preIS manual will result in incomplete documentation required for site design and preparation.

Pre Installation documents for GE Healthcare products can be accessed on the web at:

www.gehealthcare.com/siteplanning

GE Healthcare



MRi Site Planning



Customer Site Readiness Requirements

- Any deviation from these drawings must be communicated in writing to and reviewed by your local GE Healthcare Installation Project Manager prior to making changes.
- Make arrangements for any rigging, special handling, or facility modifications that must be made to deliver the equipment to the installation site. If desired, your local GE Healthcare Installation Project Manager can supply a reference list of rigging contractors.
- New construction requires the following; 1. Secure area for equipment,
 2. Power for drills and other test equipment,
 3. Capability for image analysis,
 4. Restrooms.
- Provide for refuse removal and disposal (e.g. crates, cartons, packing)
- It is the customer's responsibility to contract a vibration consultant/engineer to implement site design modifications to meet the GE vibration specification. Refer to the system preinstallation manual for the vibration specification.

GE Equipment Delivery Requirements

The items on the GE Healthcare Site Readiness Checklist are REQUIRED to facilitate equipment delivery to the IS site. Equipment will not be delivered if these requirements are not satisfied.

	GE Healthcare Site Readines	s Cl	he	cklist	Rev	v 19
Before using this document ensure you have the latest Rev from MyWorkshop on DOC0422752 GEHC Global Order # : Customer:						
	GEHC PMI: FE / Installer: The customer is responsible for proper site preparation regardless of any GEHC measurements/inspections/assessments.					
	Inspection Date:	Storage Is item	ready?	PMI Is item ready?	FE Is item	Comments If "N", enter comments or action plan
1	MR Magnet Delivery Requirements: Ensure cryogen venting system is available for magnet connection as defined by GEHC Pre-Installation Manual (PIM) requirements, exhaust fan system is installed and operational, 480V power, and chilled water supply is available 24x7 that meets system cooling requirements. External connectivity is available for magnet monitoring and phone service is available during delivery. Surface mount vibromat installed where required. Magnet room final flooring is in place.	,				
2	MR RF Screen Room Requirements: RF Screen Room is tested with copy of Test Report, emailed to ISAdminCOEMB@ge.com, that it is compliant with GEHC specifications. Dock Bolt and magnet anchors (if applicable) installed using 2 part anchor. For HDx systems, blower box mount bolts installed by RF vendor using 2 part anchors					
3	State Regulatory Requirements: Facility registration number provided for states of Ill, KY, HI, RI, SC, TX. X-ray shielding plan and state acknowledgment letter provided to installer for AR, DC, NC, SC, CO & WA. Site Drawing Requirements: Final version of equipment network and antenna, installation drawings (including red lined versions) verified to match actual room and has been provided to installer.					
4	Surface Penetration Requirements: Customer/Contractor scheduled to provide required drilling or cutting into floors, ceilings, and walls; OR surface penetration permit available and posted in the room when GEHC will perform the work.					
	Pre-Delivery Route Requirements: The equipment delivery route from the truck to the final destination within the facility has been reviewed with all key stakeholders to safely meet the minimum requirements for equipment access, and all communications/notifications have occurred. Arrangements have been made for special handling (elevator, rigging, floor protection, fork lift, rollback truck, etc).					
6	Finished Room Requirements: Rooms that will contain equipment, including storage areas not in scan suite, are dust free. Provisions taken to maintain a dust free room. Precautions must be taken to prevent dust from entering rooms containing equipment when construction is incomplete in adjacent areas. All walls primed (final coat not needed on Day 1). Shielding, doors, and windows are to be installed. No contractor work being done during or after the installation that will cause dust in the installation areas or potential equipment damage. Room security to prevent unauthorized access and theft has been discussed with customer. The customer is aware of these security issues, implications and responsibility. For Storage: Room must meet PIM requirements for storage.					
7	Electrical Requirements: Lockable (LOTO) Main Disconnect Panel (MDP) is installed per GE guidelines and system power is available. Conduits, electrical cable ducting/dividers/cable trays, and access flooring is installed in proper location and height. Surface floor duct and load-side wires can be installed at time of system installation. Validate outlet location and requirements meet specifications for device/equipment.					
3	HVAC Requirements: The HVAC/Chilled Water systems designed to maintain the environment per spec/PIM is at running state and appears to provide the desired environmental conditions including location of vents, temperature and humidity for system operation.					
9	Flooring Requirements: Floor is clean and prepared for final floor covering. Floor levelness/flatness is measured and within tolerance, and there are no visible defects per GEHC specifications. Confirm customer anchoring plan aligns with designed floor thickness. Final flooring installed where required for network racks.					
0	Ceiling Requirements: Unistrut (or equivalent) location, levelness and spacing is measured (or vendor confirmed) and consistent with the requirement of the installation drawings. Ensure unistrut and rails are not used as mounting surfaces. Ceiling grid is installed. Permanent lighting is installed and operational. HVAC diffusers are installed and connected to ductwork. Ceiling tiles installed per PMI discretion.					
1	Staging Requirements: Space has been identified to support the active installation process only. This area meets PIM/project book requirements. Storage space has been identified, if needed. This secured space would be used to store equipment indefinitely. If offsite, transportation plan has been developed at customer expense. This space must meet PIM requirements.					
2	Network Connectivity: Hardwire for network connectivity(network drop) is in place prior to delivery with specified network firewall configuration where required. Site Surveys for wireless mobile XR units have been completed.					
3	Medical Gases Requirements: Systems (hard piped or portable) in place to allow testing and calibration of equipment (anesthesia), including ventilation.					

E Healthcare

Services Des

90

SITE READINESS

TIMA MR450w GEM

SUGGEST LOCATION OF GE HEALTHCARE EQUIPMENT
ELECTRICAL WIRING DETAILS AND ROOM ARRANGEMEN
ERY EFFORT HAS BEEN MADE TO CONFORM DETAILS
STED TO BE INSTALLED. IT IS NOT TO BE USED FOR DOSES, HOWEVER, AND THE COMPANY CANNOT ACCEPT

MODALITY TYPE: OPTIM.

THIS PLAN IS SUBMITTED TO SUGGES
AND ASSOCIATED APPARATUS, ELECTRI
IN PREPARING THIS PLAN, EVERY EFF

8-230F TYPICAL LAYOUT

PROJECT REVISION
8-230F 02

DATE: 11.Apr.14

DRAWN BY: PMN
CHECKED BY: TMS

REVISION HISTORY:

SHEET C. 1

SCALE: 1/4" = 1'-0'

EQUIPMENT LAYOUT

RECOMMENDED CEILING HEIGHT = 8'-9''

This equipment layout indicates the placement and interconnection of the indicated equipment components. There may be federal, state, and/or local requirements that could impact the placement of these components. It remains the Customer's responsibility for ensuring the site and final equipment placement complies with all applicable federal, state, and/or local requirements.

MRI SITE PLANNING REMINDERS

PLEASE REFER TO PRE-INSTALLATION CHECKLIST IN PRE-INSTALLATION MANUAL LISTED ON SHEET C1 FOR ITEMS CRITICAL TO IMAGE QUALITY.

THE LAYOUT SHOULD BE ARRANGED SO THAT THE 5G LINE IS CONTAINED TO THE MAGNET ROOM. IF NO POSSIBLE, A BARRIER IS RECOMMENDED TO PREVENT ENTRY TO THE 5G FIELD AREA.

- 3G, 1G, AND .5G FIELDS. REFER TO THE PROXIMITY LIMIT CHART IN THE MR PRE-INSTALLATION MANUAL FOR MOVING METAL, THE RESTRICTION LINES TYPICALLY EXTEND OUTSIDE OF THE MRI SPACE. PLEASE
- CONFIRM THERE ARE NO MOVING METAL CONCERNS WITHIN THESE AREAS. AN EMI STUDY IS RECOMMENDED IF THE RESTRICTION LINES ARE VIOLATED.
- FOR VIBRATION ANALYSIS TO BE COMPLETED AS REQUIRED PER PRE-INSTALLATION MANUAL.
- FOR EMI, REVIEW THE SITE FOR THE LOCATION OF THE MAIN ELECTRICAL FEEDERS, AC DEVICES, OR DISTRIBUTION SYSTEMS. AN EMI STUDY IS RECOMMENDED IF LARGE AC SYSTEMS ARE NEARBY.
- DETAILS OF THE FLOOR BELOW THE MAGNET MUST BE REVIEWED. THE STRUCTURAL ENGINEER MUST VERIFY THAT THE QUANTITY OF STEEL IN THE VOLUME 10FT [3.1M] X 10FT [3.1M] X 1FT [.3M] DEEP (BELOW THE MAGNET) DOES NOT EXCEED THE ALLOWABLE STEEL CONTENT AS GIVEN IN THE MR PRE-INSTALLATION MANUAL REFERENCED ON SHEET C1.

RESPONSIBILITY FOR THE COORDINATION, DESIGN, ENGINEERING, AND SITE PREPARATION RESIDES WITH THE CUSTOMER AND THEIR PROJECT ARCHITECTS AND CONTRACTORS. GE DOES NOT, BY PROVIDING REVIEWS AND FURNISHING COMMENTS AND ASSISTANCE, ACCEPT ANY RESPONSIBILITY BEYOND ITS OBLIGATIONS AS DEFINED IN THE MR SYSTEM, SALE/PURCHASE AGREEMENT.

EQUIPMENT

LOCATED ELSEWHERE

ROOM

BY OTHERS LOCATED ELSEWHERE

IMAGE QUALITY CONSIDERATIONS

BROADBAND RF NOISE IS A SINGLE TRANSIENT OR CONTINUOUS SERIES OF TRANSIENT DISTURBANCES CAUSED BY AN ELECTRICAL DISCHARGE. LOW HUMIDIT ENVIRONMENTAL CONDITIONS WILL HAVE HIGHER PRO- BABILITY OF ELECTRICAL DISCHARGE. THE ELECTRICAL DISCHARGE CAN OCCUR DUE TO ELECTRICAL ARCING (MICRO ARCING) OR MERELY STATIC DISCHARGE. SOME POTENTIAL SOURCES CAPABLE OF PRODUCING ELEC- TRICAL DISCHARGE INCLUDE:

- LOOSE HARDWARE/FASTENERS VIBRATION OR MOVEMENT (ELECTRICAL CONTUNUITY MUST ALWAYS BE MAINTAINED)
- FLOORING MATERIAL INCLUDING RAISED ACCESS FLOORING (PANELS & SUPPORT HARDWARE) AND CARPETING

ELECTRICAL FIXTURES (i.e. LIGHTING FIXTURES, TRACK LIGHTING,

- EMERGENCY LIGHTING, BATTERY CHARGERS, OUTLETS) DUCTING FOR HVAC AND CABLE ROUTING
- RF SHIELD SEALS (WALLS, DOORS, WINDOWS ETC.)

- 11**'-**10"

FOR ADDITIONAL INFORMATION REGARDING IMAGE QUALITY, REFER TO THE PRE-INSTALLATION MANUAL LISTED ON SHEET C1

NOTE: VERIFY DELIVERY ROUTE FOR MAGNET, EQUIPMENT, AND SERVICE

EQUIPMENT PRIOR TO DELIVERY.

ROOM/

∕CONTROL

ROOM

CRITICAL ITEMS FOR MAGNET DELIVERY

- ☐ 24/7 CHILLED WATER AND 480V POWER FOR SHIELD/CRYO COOLER
- ☐ 24/7 120V POWER FOR THE MAGNET MONITOR
- ☐ PHONE LINES FOR MAGNET MONITORING AND EMERGENCY USE ☐ MAGNET ROOM EXHAUST FAN
- CRYOGEN VENTING (IF ROOF HATCH, COMPLETED WITHIN 24 HRS) ☐ MAGNET ANCHORS INSTALLED AND TESTED
- THIS IS ONLY A PARTIAL LIST OF ITEMS REQUIRED FOR DELIVERY

OF THE MAGNET. FOR A COMPLETE CHECKLIST REFER TO THE PRE-INSTALLATION MANUAL REFERENCED ON SHEET C1.

* THE ISOGAUSS CONTOUR PLOTS DEPICTED ON THIS DRAWING REPRESENT MAGNETIC FRINGE FIELDS RESULTING FROM THE NORMAL OPERATION OF THE MAGNET PROVIDED WITH THE MR SYSTEM THE ACTUAL MAGNETIC FIFLD INTENSITY AT ANY POINT IN T VICINITY OF THE MAGNET WHEN INSTALLED MAY VARY FROM THE CONTOUR PLOTS TO FACTORS SUCH AS THE CONCENTRATING EFFECTS OF NEARBY FERROUS OBJECTS AMBIENT MAGNETIC FIELDS, INCLUDING THE EARTH'S MAGNETIC FIELD. THEREFORE, THE CONTOURS SHOWN ARE ONLY APPROXIMATIONS OF ACTUAL FIELD INTENSITIES FOUND AT A CORRESPONDING DISTANCE FROM THE MAGNET'S ISOCENTER.

ANCILLARY ITEMS

CUSTOMER/CONTRACTOR SUPPLIED AND INSTALLED ITEMS

ITEM DESCRIPTION (* INDICATES EXISTING)

MINIMUM DOOR OPENING FOR EQUIPMENT DELIVERY IS 43 IN, W \times 82 IN, H [1092mm \times 2083mm], CONTINGENT ON A 96 IN, [2438mm] CORRIDOR WIDTH

RF FILTERS - LOCATE WITHIN 40 in. [1016 mm] OF THE RF COMMON GROUND STUD

PIPING FOR COOLING SYSTEM

RF SCREEN, INCLUSIVE OF WALLS, FLOOR, DOOR, ETC. GROUND IMPEDANCE GREATER THAN 1000 OHMS. ATTENUATION 100dB AT 100MHz +/-10MHz PLANEWAVE (RECOMMENDED 100dB AT 150MHz +/-10MHz PLANEWAVE)

MINIMUM 9 FT.-O IN. [2743 mm] x 9 FT.-O IN. [2743 mm] removable wall section for magnet delivery/removal. LOUVERED DOORS - OPENING WILL NEED TO BE 6 FT. TOTAL

BASE CABINET FOR STORAGE OF: SURFACE COILS, PATIENT POSITIONING PADS, PHANTOMS, ETC. AIR CONDITIONING, (VIBRATION ISOLATION IS RECOMMENDED AT SUPPORTS OF EACH UNIT TO BE INSTALLED.)

MAGNET ROOM EXHAUST FAN COUNTERTOP WITH DRAWERS FOR MISCELLANEOUS ITEMS.

THE FOLLOWING ITEMS ARE AVAILABLE FROM GE HEALTHCARE TECHNOLOGIES. CONTACT YOUR LOCAL GE HEALTHCARE SERVICE REPRESENTATIVE FOR PRICING AND AVAILABILITY.

MANUAL CRYDGEN COMPRESSOR WATER Bypass panel cat no. E8911cg

WATER FILTER

DIMPLEX 5000 CHILLER (CAT. NO. E8912CA/CB/CC/CD) 4001 lbs. (1851 kg) 167300 BTU/HR (49019 W) REMOTE GRAPHIC DISPLAY

DC LIGHTING CONTROL PANEL 155 lbs (70 kg) 1024 BTU/HR. (300W) (CAT. NO. E4502SC/SE — BASIC SYSTEM)

DC LIGHTING AUTO TRANSFORMER 60 lbs [27 kg] 171 btu/hr (50W)

(PART OF VARIABLE DIMMER SYSTEM)
(CAT. NO. E4502SD/SF INCLUDES BASIC SYSTEM) METAL DETECTOR (HAND HELD)

WORKSTATION TABLE CAT. NO. M1000MW OPERATOR'S CHAIR CAT. NO. E8803BE

GENERAL SPECIFICATIONS

- THE REQUIRED CEILING HEIGHT INDICATED ON THESE PLANS IS TO ENSURE EQUIPMENT FUNCTION IS NOT INHIBITED. CONSULT WITH YOUR LOCAL GEHC IS SPECIALIST REGARDING ACCEPTABILITY OF OTHER CEILING HEIGHTS.
- CHECK ALL DOOR OPENINGS AND HALLWAYS FROM DELIVERY LOCATION TO WHERE EQUIPMENT IS TO BE INSTALLED TO ENSURE THE ROUTE PHYSICALLY AND STRUCTURALLY WILL ACCOMODATE THE EQUIPMENT AS SHIPPED.
- RADIATION PROTECTION REQUIREMENTS ARE NOT INDICATED ON THIS PLAN. WHERE NEEDED PER NATIONAL OR LOCAL CODE THEY SHALL BE SPECIFIED BY A QUALIFIED RADIOLOGICAL PHYSICIST.
- THE DEVELOPMENT OF THE EQUIPMENT LAYOUT, ROOM DIMENSIONS, MECHANICAL AND ELECTRICAL SUGGESTIONS IS PREDICATED UPON THE BEST INFORMATION OBTAINABLE FROM THE SITE, COUPLED WITH THE CUSTOMER'S KNOWN DESIRES. ARCHITECTURAL OR ELECTRICAL CHANGES INCLUDING RELOCATION OF EQUIPMENT ILLUSTRATED ON THIS DRAWING IS ALLOWED ONLY WITH NOTIFICATION, IN WRITING, AND REVIEW BY GEHC SERVICE DEPARTMENT. EQUIPMENT OPERATION, SERVICEABILITY, AND RESTRICTING CABLE LENGTHS, ETC., MAKE THIS ESSENTIAL FOR A PROPER IS. GEHC RESERVES THE RIGHT TO MAKE ON THE JOB CHANGES BECAUSE OF CUSTOMER REQUIREMENTS AND/OR OBSTACLES IN CONSTRUCTION, ETC...
- ALL WORK TO BE IN COMPLIANCE WITH NATIONAL AND LOCAL BUILDING SAFETY CODES.
- DIMENSIONS ARE TO FINISHED SURFACES OF ROOM

SITE ENVIRONMENT SPECIFICATIONS

- AMBIENT OPERATING TEMPERATURE: CONTROL AND EQUIPMENT ROOMS ARE 59-89.6 DEG (F) [15-32 (C)], MAGNET ROOM IS 59-69.8 DEG (F) [15-21 (C)]. MAXIMUM ALLOWABLE TEMPERATURE CHANGE OF 5 DEG (F)/HR [3 (C)/HR]. MAXIMUM ROOM TEMPERATURE GRADIENT 5 DEG (F) [3 (C)].
- HUMIDITY: CONTROL AND EQUIPMENT ROOMS ARE 30 TO 70 PERCENT NON-CONDENSING, MAGNET ROOM IS 30 TO 60 PERCENT NON-CONDENSING, MAXIMUM ALLOWABLE CHANGE
- OF 5 PERCENT/HOUR.
- ENVIRONMENTAL RESTRICTIONS ABOVE MUST NOT BE EXCEEDED FOR THE ELECTRONICS. DO NOT RESTRICT THE AIR INTAKE OR AIR EXHAUST OF THE SYSTEM COMPONENTS.
- ENVIRONMENTAL CONDITIONS LISTED ABOVE MUST BE MAINTAINED AT ALL TIMES INCLUDING FOR EXAMPLE OVERNIGHT, WEEKENDS, AND HOLIDAYS. 24 HOUR POWER AND HVAC MUST BE AVAILABLE UPON MAGNET DELIVERY.
- [THIS WILL INCLUDE CHILLED WATER SUPPLY] CRYOGEN VENTING AND EMERGENCY EXHAUST SYSTEMS MUST BE COMPLETED IN THE MAGNET ROOM PRIOR TO DELIVERY.

MAGNETIC INTERFERENCE SPECIFICATIONS

FLUORESCENT LIGHTING, SCR DIMMERS OR RHEOSTATS ARE NOT ALLOWED IN THE MAGNET

- THE CUSTOMER MUST ESTABLISH PROTOCOLS TO PREVENT PERSONS WITH CARDIAC PACEMAKERS, NEUROSTIMULATORS, AND BIOSTIMULATION DEVICES FROM ENTERING
- MAGNETIC FIELDS OF GREATER THAN 5 GAUSS (EXCLUSTION ZONE).
- MAIN POWER TRANSFORMERS MUST REMAIN OUTSIDE THE 3 GAUSS FIELD. EMI < 20mG RMS AC. EMI < 5.87mG DC.
- POTENTIAL EXISTS UNDER FAULT CONDITIONS THAT THE 5 GAUSS LINE MAY EXPAND RADIALLY TO 9.35 FT. [2.85 m] AND AXIALLY TO 14.27 FT. [4.35 m] FOR 1 SECONDS OR LESS. I SHOULD BE NOTED THAT NORMAL RAMPDOWNS OR MRU (MAGNET RUNDOWN UNIT) INITIATED QUENCHES WILL NOT CAUSE THE MAGNETIC FIELD TO EXPAND.
- IT IS RECOMMENDED EVERY SITE CONSIDER THE EVENT OF A QUENCH AND PLAN ACCORDINGLY (SUCH AS PLACING 5 GAUSS WARNING SIGNS AT EXPANDED LOCATIONS).
- THE FERROUS METAL OBJECTS LISTED BELOW MUST NOT MOVE INTO OR INSIDE OF THE MOVING METAL SENSITIVITY LINE DURING SCANS.

TYPCIAL MOVING MAGNETIC MASS	DISTANCE RADIALLY	DISTANCE AXIALLY
CARTS, GURNEYS 100-400 lbs [45-182 kg]	3 GAUSS LINE	3 GAUSS LINE
FORKLIFTS, SMALL ELEVATOR, CARS, MINIVANS VANS, PICKUP TRUCKS, AMBULANCES (OBJECTS GREATER THAN 400 lbs [182 kg])	15.5 ft. [4.72 m]	24.6 ft. [7.5 m]
BUSES AND TRUCKS (DUMP, TRACTOR TRAILER, UTILITY, FIRE TRUCKS)	18.1 ft. [5.52 m]	28.75 ft. [8.76 m]

THIS SHEET IS PART OF THE DOCUMENT SET LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED

AYOU⁻ 9 Ó QUIPME


 $\overline{\bigcirc}$

M \triangleleft

PROJECT REVISION

8-230F 02 11.Apr.14 DRAWN BY: PMM CHECKED BY: TMS

REVISION HISTORY:



SUPPORT DETAIL M05 - 15GOPERATOR WORKSPACE FLOOR MOUNTING REV. 00: 01/23/08 -(4) 5/8" [15.9mm] THRU MOUNTINGHOLES FOR 3/8" [9.5mm] ANCHORS 12.7" [323mm] 13.6 [345mm] 47.24" [1200mm] - 51.0" [1297mm] PLAN VIEW DETAIL NOT TO SCALE

ACOUSTICS AND VIBRATION GUIDELINES: MAGNET

SYSTEM ACOUSTIC NOISE LEVELS

ANY GE FACTORY-INSTALLED PROTOCOL CAN BE MODIFIED BY OPERATORS, WHICH CAN INCREASE OR DECREASE ACOUSTIC SPL (SOUND PRESSURE LEVEL); OR OPERATORS MAY CREATE THIER OWN PROTOCOL WHICH COULD PRODUCE A HIGHER OR LOWER ACOUSTIC SPL AS STATED UNDER OPERATING CONDITIONS CONDITION 1 BELOW. TYPICAL SCANS GENERATE ACOUSTIC LEVELS AS STATED UNDER OPERATING CONDITIONS CONDITION 2 BELOW. IN ADDITION, THE EXPOSURE TIMES ARE COMPLETELY UNDER OPERATOR CONTROL. CONSEQUENTLY, HEARING PROTECTION IS REQUIRED FOR ALL PEOPLE IN THE MAGNET ROOM DURING SCANS TO PREVENT HEARING IMPAIRMENT, ACOUSTIC LEVELS MAY EXCEED 99 dBA. AGAIN, FOR MORE INFORMATION ABOUT RECOMMENDED SAFETY PROCEDURES REGARDING PATIENT EXPOSURE TO MR-GENERATED ACOUSTIC NOISE, SEE THE MR SAFETY GUIDE INCLUDED IN THE USER MANUAL.

AMBIENT CONDITIONS

TO REDUCE ANY BACKGROUND NOISE DUE TO CABINET BLOWERS, ETC., ACOUSTICAL CEILINGS, WALLS, AND FLOORS ARE RECOMMENDED. THE FOLLOWING ARE TYPICAL NOISE LEVEL READINGS:

62 dBA o OPERATOR AREA 80 dBA EQUIPMENT ROOM

OPERATING CONDITIONS

MR SCANNERS OPERATING CONDITIONS, COULD GENERATE ACOUSTIC LEVELS (AS MEASURED AT THE MAGNET ISO-CENTER) AS FOLLOWS:

SPL = SOUND PRESSURE LEVEL AVERAGE SPL 127 dBA FREQUENCY RANGE 20 TO 20k Hz

VIBRATION

- O THE MAGNET MAY BE SENSITIVE TO VIBRATIONS IN THE FREQUENCY RANGE OF 0.5 TO 45 Hz DEPENDING ON THE AMPLITUDE OF THE VIBRATION. IN THE PHYSICAL AREA WHERE THE MR SYSTEM IS TO BE LOCATED, EVERY PRECAUTION MUST BE TAKEN TO ENSURE THAT THE VIBRATION IS MINIMIZED. IN THE MAGNET SITING AREA, THE STRUCTURAL STABILITY AND BEHAVIORAL CHARACTERISTICS CAN BE ASSESSED. THE VIBRATION TESTS OUTLINED CAN BE USED TO ASSESS THE VIBRATION ENVIRONMENT. SITES WHICH CURRENTLY PASS THE VIBRATION STABILITY CRITERIA MAY PROCEED WITH INSTALLATION. SITES WHICH HAVE MARGINAL VIBRATION STABILITY REQUIRE SOURCE ISOLATION OR STRUCTURAL MODIFICATIONS. THEN IT IS THE CUSTOMER'S RESPONSIBLITY TO CONTRACT A VIBRATION CONSULTANT OR QUALIFIED ENGINEER TO IMPLEMENT DESIGN MODIFICATIONS TO MEET THE SPECIFIED LIMITS. WITH THE VIBRATION CONSULTANT PRESENT, LOCAL GE FIELD SERVICE AND/OR INSTALLATION SPECIALIST MUST VERIFY THE ELIMINATION/REDUCTION OF ALL IDENTIFIED SOURCES DO IMPROVE THE VIBRATION ENVIRONMENT. GE CAN ASSIST IN INTERPRETING MARGINAL SITE TEST RESULTS AND PREDICTING THE IMPACT ON SYSTEM PERFORMANCE. ULTIMATELY IT REMAINS THE CUSTOMER/ARCHITECT/ENGINEER RESPONSIBLITY TO DESIGN SITE SOLUTION.
- TO MINIMIZE THE INTERFERENCE, THE MAGNET SHOULD BE PLACED ON A SOLID FLOOR, LOCATED AS FAR AS POSSIBLE FROM THE VIBRATION SOURCES, SUCH AS PARKING LOTS, ROADWAYS, SUBWAYS, TRAINS, HALLWAYS, ELEVATORS, HELIPORTS AND HOSPITAL PHYSICAL PLANTS CONTAINING PUMPS, MOTORS, AIR HANDLING EQUIPMENT, OR AIR CONDITIONING EQUIPMENT.

PLEASE NOTE THAT OTHER ITEMS NOT LISTED COULD ALSO BE POTENTIAL SOURCES OF VIBIRATION. VIBRATION ISOLATION IS RECOMMENDED AT FLOOR CONNECTION POINTS OF THE AIR CONDITIONING UNIT(S) TO BE INSTALLED FOR THE PURPOSE OF COOLING THE MR SUITE. ISOLATION OF THE MR MAGNET IS NOT A RECOMMEDED SOLUTION FOR REDUCING ENVIRONMENTAL VIBRATION.

VIBRATION MEASUREMENTS SHOULD BE MADE WHEN THE PROPOSED SITE IS LOCATED NEAR ANY OF THE SOURCES LISTED HERE. MEASUREMENTS SHOULD BE MADE USING A SPECTRUM ANALYZER CAPABLE OF PERFORMING THE TEST GUIDELINES.

o TIME HISTORY VIBRATION LEVELS (WITH ALL STEADY STATE VIBRATION SOURCES POWERED DOWN) EXCEEDING TRIGGER OF 0.0005 q, ZERO TO PEAKUST BE FULLY ANALYZED TO ASSESS THE POTENTIAL IMPACT TO THE BUILDING STRUCTURE. THE BUILDING (SPECTRAL) RESPONSE IMMEDIATELY FOLLOWING THE 0.0005 g, ZERO TO PEAK TRIGGER LEVEL (ENDING AT THE DECAY OF THE VIBRATION SIGNAL) MUST NOT CAUSE THE SITE ENVIRONMENT TO EXCEED THE STEADY STATE VIBRATION ELS DEFINDED BELOW.

STEADY STATE VIBRATION

- O THE MAXIMUM STEADY STATE VIBRATION TRANSMITTED THROUGH THE FLOOR MUST NOT EXCEED THE FOLLOWING (ABOVE AMBIENT BASELINE):
 - o 5×10^{-5} g rms at 0 Hz ramping to 10 x 10 g at 20 Hz
 - o 10 x 10 ⁻⁵g rms 20-40 Hz o 25×10^{-5} g rms 40-50 Hz

IN ORDER TO ENSURE THAT ANY DISCRETE SIGNAL REPRESENTS A REAL MECHANICAL VIBRATION SOURCE, THE SIGNAL MUST HAVE A BANDWIDTH THAT TYPIFIES DYNAMIC SYSTEM RESPONSE

TEST MEASUREMENTS (1.1)

VIBRATION MEASUREMENTS ARE IN THE RANGE OF 10^{-6} g. TEST EQUIPMENT MUST HAVE THE REQUIRED SENSITIVITY TO

M66 - 15G2

REV. DATE: 27.APR.13

INSTRUMENTATION IS RECOMMENDED TO HAVE A LOW TOLERANCE TO TEMPERATURE EFFECTS AS MANY TIMES THE LOW

IT IS HIGHLY RECOMMENDED ALL MEASURED DATA IS REAL TIME DATA ACQUISITION. RECORDING THE VIBRATION DATA WILL NOT ALLOW FOR A PROPER SITE SURVEY, SPECIFICALLY WHEN STUDYING TRANSIENT VIBRATION AND WHEN SEARCHING FOR

ALL ANALYSES ARE TO BE NARROWBAND FAST FOURIER TRANSFORMS (FFT'S) OVER THE FREQUENCY BANDS LISTED BELOW:

FREQUENCYBAND FREQUENCY RESOLUTION 0.2 TO 50 HZ $\Delta f = 0.125$ HZ

TIME HISTORIES OF THE VIBRATION MUST BE RECORDED AS ACCELERATION LEVELS VS. TIME. THE RESOLUTION OF THE TIME HISTORY MUST BE ADJUSTED TO CLEARLY CAPTURE THE TRANSIENT EVENT. THE ANALYZER SET-UP WILL BE SITE DEPENDENT AND, IN SPECIAL CASES, VIBRATION RESPONSE DEPENDENT. IT IS THE RESPONSIBILITY OF THE VIBRATION CONSULTANT TO STUDY THE TRANSIENT ENVIRONMENT, CAPTURE DATA TO CONFIRM TRANSIENT ACTIVITY EXCEEDS THE TRIGGER LEVEL, THEN EXPAND THE TIME HISTORY DATA TO EXHIBIT THE STRUCTURAL RESPONSE.

EQUIPMENT (SPECTRAL ANALYZER) SET-UP (1.2)

FREQUENCY THERMAL DRIFT MAY INFLUENCE THE MEASUREMENTS.

- o FREQUENCY AVERAGE A MINIMUM OF 20 LINEAR AVERAGES. DO NOT USE PEAK HOLD OR 1/3 OCTAVE ANALYSIS.
- o AVERAGE AND STORE A MINIMUM OF 10 PLOTS TO SUPPORT THE SITE VIBRATIONS CONSISTENCY.
- O HANNING WINDOW MUST BE APPLIED TO THE ENTIRE SPECTRA

SPECTRUM ANALYZERS CAPABLE OF THESE MEASUREMENTS ARE READILY AVAILABLE FOR PURCHASE OR RENTAL. MODELS SUCH AS THE HP 3560A, NICOLET PHASZER, B&K PULSE, AND HP 35670 ARE ALL CAPABLE OF MAKING THE SITE VIBRATION MEASUREMENTS. ACCELEROMETERS MUST HAVE THE CAPABILITY TO MEASURE FROM 0.2 Hz BEYOND 50 Hz. TIME HISTORIES CAN BE RECORDED USING ANY OF THE ANALYZERS LISTED ABOVE. PLEASE NOTE THAT THE EQUIPMENT MENTIONED ARE FOR EXAMPLE ONLY. IT IS THE RESPONSIBILITY OF THE ENGINEERING TEST FIRM TO PROVIDE EQUIPMENT THAT WILL ALLOW MEASUREMENTS COMPLIANT WITH THIS GUIDELINE.

DATA COLLECTIONS (1.3)

AMBIENT BASELINE CONDITION:

ALL OF THE MEASUREMENTS DEFINED IN 1.1 AND 1.2 (ABOVE) MUST BE MADE IN A 'QUIET' ENVIRONMENT. THAT IS, IN AREAS WHERE EXCESSIVE TRAFFIC, SUBWAY TRAINS, ETC. EXISTS. A VIBRATION MEASUREMENT MUST ALSO BE MADE DURING PERIODS WITHOUT TRAFFIC OR DURING PERIODS OF LIGHT TRAFFIC. MEASUREMENTS MUST DEFINE THE LOWEST LEVELS OF VIBRATION POSSIBLE AT THE SITE.

THE SOURCE OF ANY STEADY STATE VIBRATION WHOSE LEVELS EXCEED THE SPECIFICATIONS MUST BE IDENTIFIED AS TO THE SOURCE OF THE VIBRATION DISTURBANCE. A SECOND MEASUREMENT SHOULD BE MADE WITH ALL OF THE IDENTIFIED CONTRIBUTORS POWERED DOWN IF POSSIBLE. IN SITUATIONS WHERE IT IS NOT POSSIBLE TO POWER DOWN EQUIPMENT, VIBRATION DATA MUST BE COLLECTED TO IDENTIFY SPECIFIC SOURCE OF THE VIBRATION CONCERN. THE MAJORITY OF STEADY STATE VIBRATION PROBLEMS CAN BE NEGATED BY ISOLATING THE VIBRATION

NORMAL CONDITION

ALL OF THE VIBRATION MEASUREMENTS LISTED ABOVE MUST BE REPEATED DURING PERIODS OF 'NORMAL' ENVIRONMENTAL CONDITIONS INCLUDING THE FFT'S AND TIME HISTORIES. THE TRANSIENT MEASUREMENTS MUST BE PROVIDED TO DEFINE THE DYNAMIC DISTURBANCES THE MR SYSTEM MIGHT BE EXPOSED TO. TRANSIENT ANALYSIS IS REQUIRED FOR A TRUE ASSESSMENT OF THE SITE.

SPEICAL ATTENTION MUST BE PAID TO THE SITE ASSESSMENT DURING THE ENTIRE ANALYSIS. SINCE TRANSIENT VIBRATION IS NOT EASILY ADDRESSED ONCE THE MR SUITE IS FULLY CONSTRUCTED, THE TEST CONSULTANT MUST FULLY UNDERSTAND THE NEEDS FOR THIS ANALYSIS. THE SOURCE OF ANY TRANSIENT MUST BE IDENTIFIED AND SUPPORTED WITH VIBRATION PLOTS. IF THE SOURCE OF ANY TRANSIENT IS NOT ABLE TO BE LOCATED, IT IS RECOMMENDED THAT THE CUSTOMER SHOULD HAVE AN ALTERNATE LOCATION IDENTIFIED AND VIBRATION STUDIED

TRANSIENT VIBRATION IS DIFFICULT TO ASSESS IF THE DETAILS OF THE TRANSIENT VIBRATION IS NOT UNDERSTOOD. THE 0.0005 q, ZERO TO PEAK TRIGGER LEVELA STARTING POINT TO BEGIN UNDERSTANDING THE VIBRATION STABILITY. THE TRANSIENT VIBRATION PEAK AMPLITUDE, STRUCTURAL (TIME VARIANT) RESPONSE, DECAY RATE AND AN ESTIMATE OF THE NUMBER OF EVENTS PER UNIT TIME WOULD CONSTITUTE A COMPLETÉ TRANSIENT ANALYSIS. ALL TRANSIENT FAILURES MUST BE SUPPORTED BY TIME HISTORY PLOTS. THE PLOTS MUST CLEARLY SHOW THE STRUCTURAL RESPONSE, THE FREQUENCY OF THE SIGNATURE AND THE DECAY RATE. FROM THIS DATA, GE CAN HELP DETERMINE COMPLIANCE TO THE

TEST CONSULTANT MUST PROVE DESIGN RECOMMENDATIONS FOR ALL SITES/BUILDING STRUCTURES WHICH ARE FOUND TO EXCEED THE SPECIFICATIONS.

PRESENTATION/INTERPRETATION OF RESULTS (1.4)

THE RECOMMENDED FORMAT FOR SITE VIBRATION DATA COLLECTION, PRESENTATION, AND ANALYSIS IS ILLUSTRATED IN THE EXAMPLES SHOWN IN ILLUSTRATIONS 1.1 THROUGH 1.4. IN THE PRE-INSTALLATION MANUAL. PRESENTATION OF THE DATA IN ANY OTHER FORMAT (LINEAR UNITS ONLY) MAY RESULT IN AN INCORRECT INTERPRETATION AND DIAGNOSIS OF THE SITE. ADDITIONAL DATA COLLECTION OR PRESENTATION METHODS IS AT THE OPTION OF THE VIBRATION TESTING SERVICE.

IT IS THE RESPONSIBILITY OF THE CUSTOMER'S VIBRATION TESTING SERVICE TO INTERPRET THE RESULTS AND DETERMINE IF THAT SITE MEETS GE'S SPECIFICATIONS. ILLUSTRATIONS A-1 AND A-2 ARE EXAMPLES PROVIDED TO ASSIST A TEST CONSULTANT IN THE USE OF GE STEADY STATE SPECIFICATIONS (VIBRATION SPECIFICATIONS ABOVE AMBIENT BASELINE). IF THE VIBRATION LEVELS ARE TOO HIGH, ADDITIONAL DATA ACQUISITION MAY BE

NECESSARY TO: o DETERMINE THE SOURCE OF THE VIBRATION o PROPOSE A SOLUTION TO THE PROBLEM o FIND AN ALTERNATE SITE LOCATION.

ILLUSTRATIONS A−3 AND A−4 IN THE PRE-INSTALLATION MANUAL ARE EXAMPLES PROVIDED TO ASSIST A TEST CONSULTAN IN THE USE OF GE TRANSIENT SPECIFICATIONS. THE 500 MICRO-G, ZERO TO PEAK TRIGGER LEWEENTIFIES DATA COLLECTION TO BEGIN ASSESSMENT OF THE SITE VIBRATION ANALYSIS. THE RESPONSE OF THE TRANSIENT MUST BE ASSESSED RELATIVE TO THE STEADY STATE VIBRATION SPECIFICATIONS IN SECTION SPECIFICATIONS. ANY QUESTIONS REGARDING TEST EQUIPMENT REQUIREMENTS, TEST PARAMETERS, OR GENERAL QUESTIONS SHOULD BE DISCUSSED WITH YOUR GE PROJECT MANAGER.

FLOOR MOUNTING DETAIL: MAGNET

TABLE DOCK
REBAR FREE

0.43" [11mm] MOUNTING

HOLE FOR TABLE DOCK.
ANCHOR TO WITHSTAND A

CLAMPING/TENSION FORCE OF

600 lbs [2669 N].

STEEL REBAR MUST NOT BE POSITIONED IN

SHADED AREAS NOTED AS "REBAR FREE" TO

MAGNET MOUNTING AND ANCHOR HARDWARE

PREVENT INTERFERENCE WITH MOUNTING BOLTS.

REQUIREMENTS ARE THE CUSTOMER/CONTRACTOR

DOCK ASSEMBLY ANCHOR BOLTS SHOULD BE

2.25 IN ±0.5 IN [60 MM ±13 MM]
ABOVE THE FINISHED FLOOR.

[102mm]

GENERAL NOTES:

RESPONSIBILITY.

THRU-BOLT

PLAN VIEW

[80.5mm]

(4) 1.5" [38mm]

SEISMIC ANCHOR HOLES

(4) MOUNTING HOLES

FOR MOUNTING FEET

TO VIBROACCOUSTIC

MATS AFTER SPACER

MAGNET

- - - - - - - -

[2327mm]

REAR

BLOCKS ARE REMOVED

MAGNET

TABLE DOCK HOLE DRILLED ONLY AFTER THE MAGNET INSTALLATION

VIBROACOUSTIC

DAMPING MATS

FEMALE ANCHOR

MAGNET

FRONT

TABLE DOCK ATTACHMENT METHODS

REMOVABLE ANCHOR

ROD MALE INSERT

- CLAMP BRACKET

- FINISHED FLOOR

FILLER BOARD

CONDUCTIVE FIBEROUS

WASHER (RF SEAL)

-CONCRETE-

THREADED ROD/NUT. IT IS PROVIDED/INSTALLED BY THE RF VENDOR AFTER THE MAGNET IS DELIVERED.

THE DOCK ANCHOR MUST BE A COMMERCIALLY AVAILABLE TWO PART ASSEMBLY WITH A REMOVABLE BOLT OR

OR GROUT

FINISHED -

FLOOR

MAGNET ROOM

REFER TO SHEET A1 FOR ACTUAL MAGNET ORIENTATION

[349.5mm]

[610mmT

[557mm]

[1225mm]

18.2"

[462mm]

[69.3mm]

21.93"

[557mm]

M6640

REV. DATE: 22.JAN.14

[1651mm]

-CRYOGEN VENT TO MAGNET CENTER

[411.5mm]

MAGNET

ALIGNMENT REFERENCE

STRUC⁻ OPTIMA ign

Healthcar

(96) (96)

ETAIL

TURAL

GEM

0

5 $\langle |$

REVISION 8-230F 02

11.Apr.14 DRAWN BY: CHECKED BY:

THIS SHEET IS PART OF THE DOCUMENT SET LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED

ENVIRONMENTAL STEEL LIMITS


A STATIC MAGNETIC FIELD EXTENDS IN A THREE-DIMENSIONAL SPACE AROUND THE MAGNET ISOCENTER. ENVIRONMENTAL STEEL WITHIN THE STATIC MAGNETIC FIELD AFFECTS THE UNIFORMITY (OR HOMOGENEITY) OF THE FIELD. FIELD UNIFORMITY IS CRITICAL TO BOTH IMAGE QUALITY AND CHEMICAL SHIFT ANALYSIS (SPECTROSCOPY). AN ANALYSIS OF THE ENVIRONMENTAL STEEL IS REQUIRED WITHIN A 5 FEET (1.524 METERS) SPHERICAL RADIUS OF THE MAGNET ISOCENTER. ENVIRONMENTAL STEEL INCLUDES PIPES, BEAMS, CONCRETE REBAR, OR ANY OTHER STRUCTURAL STEEL IN THE FLOORS, WALLS, OR CEILING. LIMITS OF STEEL MASS DISTANCE FROM


DISTANCE BELOW TOP MAGNET TYPE LBS/SQ FT MAGNET ISOCENTER SURFACE OF FLOOR [KG/SQ M] IN [MM] IN [MM] 0-45 [0-1143] 0-3 [0-76] 45-47 [1143-1194] 3-5 [76-127] 47-52 [1194-1321] 5-10 [127-254] 8 39.2 52-55 [1321-1397] 10-13 [254-330] 20 [98.0] 55+ [1397+] 13+ [330+]

NOTE THE FOLLOWING ITEMS MUST BE LIMITED PER THE ABOVE TABLE 1. NON-MOVABLE STEEL CONSTRUCTION MATERIAL SUCH AS WALL STUDS OR HVAC COMPONENTS. 3 STEEL IN THE FLOOR IN A 10 FOOT BY 10 FOOT (3.1 METER BY 3.1 METER) AREA DIRECTLY BELOW THE MAGNET.

SHEET

REVISION HISTORY





POWER SPECIFICATIONS

DISCOVERY/OPTIMA MR

(REV. DATE 12.FEB.14)

PRIMARY SOURCE IS REQUIRED FOR ALL INSTALLATIONS. RANGE OF LINE VOLTAGES: NOMINAL LINE VOLTAGE OF 380 TO 480, 3 PHASE, 50 OR 60 Hz. RECOMMENDED POWER SUPPLY: WYE-CONNECTED OR DELTA-

CONNECTED (GROUNDED DELTA). MAXIMUM DAILY VOLTAGE VARIATION MUST FALL WITHIN ONE OF THE RANGES IN TABLE A.

TABLE A ALLOWABLE INPUT VOLTAGES, CURRENT DEMAND

NOMINAL	ABSOLUTE	CURRENT	(AMPS)	
VOLTAGE	RANGE	MAX MOMENTARY	CONTINUOUS	
380	335-418	187	151	
400	352-440	178	143	
415	366-456	171	138	
480	423-528	148	119	

** OVERCURRENT PROTECTION SIZED FOR 125% CONTINUOUS CURRENT. (CALCULATIONS BASED UPON NOMINAL VOLTAGE)

BALANCE.

PHASE—TO—PHASE VOLTAGES MUST BE WITHIN 2 PERCENT OF THE LOWEST PHASE—TO—PHASE VOLTAGE. MAXIMUM ALLOWABLE TRANSIENT VOLTAGE EXCURSIONS ABOVE OR BELOW NOMINAL WAVESHAPE FORM NOT TO EXCEED 200V AT A MAXIMUM VOLTAGE TRANSIENT OR IMPULSE ON THE INCOMING POWER MUST BE HELD TO A MINIMUM. TRANSIENTS CAUSED BY LIGHTNING, SURGES, LOAD SWITCHING, STATIC ELECTRICITY ETC. CAN CAUSE SCAN ABORTS OR, IN EXTREME INSTANCES, COMPONENT FAILURE IN THE COMPUTER SUBSYSTEM.

MAXIMUM POWER DEMAND AVERAGED OVER 5 SECONDS = 123 KVA.

SYSTEM EQUIPMENT POWER DEMAND PDU 5 SECOND POWER (IN PGR) 103 kVA HEC CONTINUOUS POWER (INCLUDING CRY) 20 kVA CRYO COMPRESSOR CONTINUOUS POWER (CRY) 9 kVA

TABLE B MAXIMUM POWER DEMAND.

DEMAND	DISCOVERY, OPTIMA
kVa* POWER FACTOR AT	123 0.9

* DEMAND INCLUDES POWER FOR ENTIRE MR SYSTEM. Line voltage regulation at maximum power demand must be less than or equal to 2 percent or 4 percent from power source.

TRANSFORMER

FOR A SINGLE UNIT INSTALLATION, THE MINIMUM TRANSFORMER SIZE IS 225 KVA. REGULATED TRANSFORMER IS NOT REQUIRED UNLESS VOLTAGE CHANGES EXCEED ±10% OVER A PERIOD OF 1 HOUR OR LONGER.

REFER TO DIRECTION LISTED ON C1 FOR ADDITIONAL INFORMATION.

ELECTRICAL NOTES

- NOTE 1: ALL WIRES SPECIFIED SHALL BE COPPER STRANDED, FLEXIBLE, THERMO-PLASTIC, COLOR CODED, CUT 10 FOOT LONG AT OUTLET BOXES, DUCT TERMINATION POINTS OR STUBBED CONDUIT ENDS. ALL CONDUCTORS, POWER, SIGNAL AND GROUND, MUST BE RUN IN A CONDUIT OR DUCT SYSTEM. ELECTRICAL CONTRACTOR SHALL RING OUT AND TAG ALL WIRES AT BOTH ENDS. WIRE RUNS MUST BE CONTINUOUS COPPER STRANDED AND FREE FROM SPLICES. ALUMINUM OR SOLID WIRES ARE NOT ALLOWED.
- NOTE 2: WIRE SIZES GIVEN ARE FOR USE OF EQUIPMENT. LARGER SIZES MAY BE REQUIRED BY LOCAL CODES.
- NOTE 3: IT IS RECOMMENDED THAT ALL WIRES BE COLOR CODED, AS REQUIRED IN ACCORDANCE WITH NATIONAL AND LOCAL
- NOTE 4: CONDUIT SIZES SHALL BE VERIFIED BY THE ARCHITECT, ELECTRICAL ENGINEER OR CONTRACTOR, IN ACCORDANCE WITH LOCAL OR NATIONAL CODES.
- NOTE 5: CONVENIENCE OUTLETS ARE NOT ILLUSTRATED. THEIR NUMBER AND LOCATION ARE TO BE SPECIFIED BY OTHERS. LOCATE AT LEAST ONE CONVENIENCE OUTLET CLOSE TO THE SYSTEM CONTROL, THE POWER DISTRITBUTION UNIT AND ONE ON EACH WALL OF THE PROCEDURE ROOM. USE HOSPITAL APPROVED OUTLET OR EQUIVALENT.
- NOTE 6: GENERAL ROOM ILLUMINATION IS NOT ILLUSTRATED. CAUTION SHOULD BE TAKEN TO AVOID EXCESSIVE HEAT FROM OVERHEAD SPOTLIGHTS. DAMAGE CAN OCCUR TO CEILING MOUNTING COMPONENTS AND WIRING IF HIGH WATTAGE BULBS ARE USED. RECOMMEND LOW WATTAGE BULBS NO HIGHER THAN 75 WATTS AND USE DIMMER CONTROLS (EXCEPT MR). DO NOT MOUNT LIGHTS DIRECTLY ABOVE AREAS WHERE CEILING MOUNTED ACCESSORIES WILL BE PARKED.
- NOTE 7: ROUTING OF CABLE DUCTWORK, CONDUITS, ETC., MUST RUN DIRECT AS POSSIBLE OTHERWISE MAY RESULT IN THE NEED FOR GREATER THAN STANDARD CABLE LENGTHS (REFER TO THE INTERCONNECTION DIAGRAM FOR MAXIMUM USABLE LENGTHS POINT TO POINT).
- NOTE 8: CONDUIT TURNS TO HAVE LARGE, SWEEPING BENDS WITH MINIMUM RADIUS IN ACCORDANCE WITH NATIONAL AND LOCAL ELECTRICAL CODES.
- NOTE 9: A SPECIAL GROUNDING SYSTEM IS REQUIRED IN ALL PROCEDURE ROOMS BY SOME NATIONAL AND LOCAL CODES. IT IS RECOMMENDED IN AREAS WHERE PATIENTS MIGHT BE EXAMINED OR TREATED UNDER PRESENT, FUTURE, OR EMERGENCY CONDITIONS. CONSULT THE GOVERNING ELECTRICAL CODE AND CONFER WITH APPROPRIATE CUSTOMER ADMINISTRATIVE PERSONNEL TO DETERMINE THE AREAS REQUIRING THIS TYPE OF GROUNDING SYSTEM.
- NOTE 10: THE MAXIMUM POINT TO POINT DISTANCES ILLUSTRATED ON THIS DRAWING MUST NOT BE EXCEEDED.
- NOTE 11: PHYSICAL CONNECTION OF PRIMARY POWER TO GE EQUIPMENT IS TO BE MADE BY CUSTOMERS ELECTRICAL CONTRACTOR WITH THE SUPERVISION OF A GE REPRESENTATIVE. THE GE REPRESENTATIVE WOULD BE REQUIRED TO IDENTIFY THE PHYSICAL CONNECTION LOCATION, AND INSURE PROPER HANDLING OF GE EQUIPMENT.
- NOTE 12: GEHC CONDUCTS POWER AUDITS TO VERIFY QUALITY OF POWER BEING DELIVERED TO THE SYSTEM. THE CUSTOMER'S ELECTRICAL CONTRACTOR IS REQUIRED TO BE AVAILABLE TO SUPPORT THIS ACTIVITY.

DIAGRAM KEY

———— CUSTOMER/CONTRACTOR SUPPLIED WIRING. ROUTE IN

ADEQUATE CONDUIT OR RACEWAY. GE FURNISHED CABLE RUNS. ROUTE IN EMPTY CONDUIT OR RACEWAY. 59' [18M] MAXIMUM RUN LENGTH BETWEEN JUNCTION POINTS.

THIS SHEET IS PART OF THE DOCUMENT SET LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED

OPTIMA


SPECIFICATIONS 8450w GEM


 \sim - \triangleleft


PROJECT | REVISION 8-230F 02 DATE: 11.Apr.14

DRAWN BY: PMM CHECKED BY: TMS

REVISION HISTORY:











EQUIPMENT DETAIL


ELECTRICAL DETAIL
























GEM **DETAIL ≫** OPTIMA

ign

Healthcare

 \sim \sim \triangleleft $\mathbb{Q} \otimes \mathbb{Q}$

REVISION 8-230F 02 11.Apr.14 DRAWN BY: PMM CHECKED BY: REVISION HISTORY



THIS SHEET IS PART OF THE DOCUMENT SET LISTED ON SHEET C1 AND SHOULD NOT BE SEPARATED

