emWin

Graphic Library with Graphic User Interface

User Guide & Reference Manual

Document: UM03001
Software Version: 6.12
Revision: 0
Date: April 7, 2020



A product of SEGGER Microcontroller GmbH

www.segger.com

Disclaimer

Specifications written in this document are believed to be accurate, but are not guaranteed to be entirely free of error. The information in this manual is subject to change for functional or performance improvements without notice. Please make sure your manual is the latest edition. While the information herein is assumed to be accurate, SEGGER Microcontroller GmbH (SEGGER) assumes no responsibility for any errors or omissions. SEGGER makes and you receive no warranties or conditions, express, implied, statutory or in any communication with you. SEGGER specifically disclaims any implied warranty of merchantability or fitness for a particular purpose.

Copyright notice

You may not extract portions of this manual or modify the PDF file in any way without the prior written permission of SEGGER. The software described in this document is furnished under a license and may only be used or copied in accordance with the terms of such a license.

© 2020 SEGGER Microcontroller GmbH, Monheim am Rhein / Germany

Trademarks

Names mentioned in this manual may be trademarks of their respective companies.

Brand and product names are trademarks or registered trademarks of their respective holders.

Contact address

SEGGER Microcontroller GmbH

Ecolab-Allee 5
D-40789 Monheim am Rhein

Germany

Tel.	+49 2173-99312-0
Fax.	+49 2173-99312-28
E-mail:	support@segger.com*
Internet:	www.segger.com

*By sending us an email your (personal) data will automatically be processed. For further information please refer to our privacy policy which is available at https://www.segger.com/legal/privacy-policy/.

Manual versions

This manual describes the current software version. If you find an error in the manual or a problem in the software, please inform us and we will try to assist you as soon as possible. Contact us for further information on topics or functions that are not yet documented.

Print date: April 7, 2020

Software	Revision	Date	By	Description
6.12	0	200408	FO	Chapter '2-D Graphic Library' updated. • New function GUI_QR_CreateFramed() added. Chapter 'Widgets (Window objects)' updated. • New GAUGE widget added. • New function GAUGE_CreateIndirect() added. • New function GAUGE_CreateUser() added. • New function GAUGE_GetValue() added. • New function GAUGE_SetAlign() added. • New function GAUGE_SetBkColor() added. • New function GAUGE_SetColor() added. • New function GAUGE_SetOffset() added. • New function GAUGE_SetRadius() added. • New function GAUGE_SetRange() added. • New function GAUGE_SetRoundedEnd() added. • New function GAUGE_SetRoundedValue() added. • New function GAUGE_SetValue() added. • New function GAUGE_SetValueRange() added. • New function GAUGE_SetWidth() added. • New QRCODE widget added. • New function QRCODE_CreateIndirect() added. • New function QRCODE_CreateUser() added. • New function QRCODE_SetEccLevel() added. • New function QRCODE_SetNumModules() added. • New function QRCODE_SetPixelSize() added. • New function QRCODE_SetText() added. • New function QRCODE_SetWiFiText() added.
6.10	4	200318	FO	Chapter 'AppWizard' updated. • New function APPW_GetFont() added. Chapter 'Widgets' updated. • New function RADIO_GetImage() added. • New function LISTVIEW_GetLBorder() added. • New function LISTVIEW_GetRBorder() added. • New function LISTVIEW_GetTextAlign() added. • New function LISTVIEW_RowIsDisabled() added. • New function IMAGE_SetTiled() added. • New function IMAGE_GetImageSize() added. • New function GRAPH_SetGridOffY() added. • New function CHECKBOX_GetDefaultAlign() added. • New function CHECKBOX_SetDefaultAlign() added. • New function CALENDAR_ShowDate() added. • New function CALENDAR_GetWeekday() added. Chapter 'Language Support' updated. • Updated section 'Thai language support'. • New function GUI_UC_EnableThai() added.
6.10	3	200313	FO	Chapter 'Displaying Text' updated. • Added parameter to GUI_GetCharFromPos() to save character index. Chapter 'Fonts' updated. • New function GUI_GetStringDistXEx() added. Chapter 'Movies' updated. • New function GUI_MOVIE_GetInfoH() added. • New function GUI_MOVIE_GetNumFrames() added. Fixed a bug with GUI_DrawBitmapEx() where transparency wasn't drawn correctly. Chapter 'Widgets' updated. • Added the functionality of HOME and END keys to EDIT widget. • Added automatic horizontal text scrolling to EDIT widget. • New function TEXT_GetRotation() added. • New function TEXT_SetRotation() added. • New function TEXT_SetDefaultRotation() added. • New function TEXT_GetDefaultRotation() added. • New function TEXT_GetTextOffset() added. • New function TEXT_SetTextOffset() added.
6.10	2	200218	FO	Chapter 'Simulation' updated.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• Screenshots updated. • SIM_GUI_SetCompositeSize() and SIM_GUI_ShowDevice() enhanced. • Added 'Data structures' section to Device simulation API. • Added 'Defines' section to Device simulation API. Chapter 'Viewer' updated. • Screenshots updated. Chapter 'AppWizard' updated. • Screenshots updated. Chapter 'emWinSPY' updated. • Screenshots updated. Chapter 'Displaying text' updated. • Added 'Defines' section to Text API. • Added 'Enumerations' section to Text API. Chapter '2-D Graphic Library' updated. • New function GUI_DrawRoundedRectEx() added. • New function GUI_DrawRoundedFrameEx() added. • Added 'Data structures' section to Graphic API. • Added 'Defines' section to Graphic API. Chapter 'Displaying bitmap files' updated. • Added 'Data structures' section to JPEG API. • Added 'Data structures' section to GIF API. Chapter 'Bitmap Converter' updated. • Screenshots updated. Chapter 'Language Support' updated. • References to BiDi removed even if emWin is compiled with GUI_SUPPORT_BIDI. Calling of GUI_UC_EnableBIDI() now is mandatory. Chapter 'Fonts' updated. • Added 'Data structures' section to Font API. • Added 'Defines' section to Font API. Chapter 'Font Converter' updated. • Screenshots updated. Chapter 'Movies' updated. • Screenshot updated. • Added 'Data structures' section to Movie API. • Added 'Defines' section to Movie API. Chapter 'Animations' updated. • Added section 'Using a delete callback function'. • Added 'Data structures' section to Animation API. • Added 'Defines' section to Animation API. Chapter 'Colors' updated. • Screenshot updated. Chapter 'Memory Devices' • Added 'Defines' section to Memory Device API. Chapter 'The Window Manager (WM)' updated. • Added 'Data structures' section to WM API. • Added 'Defines' section to WM API. Chapter 'Widgets (window objects)' updated. • Added 'Defines' section to BUTTON API. • Added 'Defines' section to CHECKBOX API. • Added 'Defines' section to DROPDOWN API. • Added 'Defines' section to EDIT API. • Added 'Defines' section to FRAMEWIN API. • Added 'Defines' section to GRAPH API. • New function GRAPH_DATA_XY_Clear() added. • New function GRAPH_DATA_XY_GetLineVis() added. • New function GRAPH_DATA_XY_GetPointVis() added. • New function GRAPH_DATA_XY_SetLineVis() added. • New function GRAPH_DATA_XY_SetPointVis() added. • New function HEADER_DeleteItem() added. • New function HEADER_GetSel() added. • New function HEADER_SetFixed() added. • New function HEADER_SetScrollPos() added. • Added 'Defines' section to ICONVIEW API. • Added 'Defines' section to IMAGE API. • Added 'Defines' section to LISTBOX API. • Added 'Defines' section to LISTVIEW API. • Added 'Defines' section to LISTWHEEL API. • Added 'Data structures' section to MENU API. • Added 'Defines' section to MENU API. • Added 'Defines' section to MULTIEDIT API. • Added 'Defines' section to MULTIPAGE API. • Added 'Defines' section to RADIO API. • New function RADIO_GetNumItems() added.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• New function RADIO_GetSpacing() added. • New function RADIO_SetSpacing() added. • Added 'Defines' section to SCROLLBAR API. • Added 'Defines' section to SLIDER API. • Added 'Defines' section to SPINBOX API. • Added 'Defines' section to SWIPELIST API. • Added 'Defines' section to SWITCH API. Chapter 'Dialogs' updated. • Added 'Data structures' section to CALENDAR API. • Added 'Defines' section to CALENDAR API. • Added 'Defines' section to CHOOSECOLOR API. • Added 'Data structures' section to CHOOSEFILE API. • Added 'Defines' section to CHOOSEFILE API. Chapter 'MultiLayer / MultiDisplay support' updated. • Added 'Data structures' section to MultiLayer API. Chapter 'MultiTouch support (MT)' updated. • Added 'Data structures' section to Basic buffer access API. • Added 'Defines' section to Basic buffer access API. Chapter 'Cursors' updated. • Added 'Data structures' section to Cursor API. Chapter 'VNC Server' updated. • Added 'Data structures' section to VNC Server API. Chapter 'Indexes' updated. • Added 'Types' index for data structures.
6.10	1	200203	JE	Chapter 'Display Drivers' • GUIDRV_SPage supports Sitronix ST7571, GUIDRV_SPage_Set1510()
6.10	0	200106	FO	New chapter 'AppWizard' • New function APPW_SetVarData() added. • New function APPW_GetVarData() added. Chapter 'Displaying Text' • New function GUI_GetCharFromPos() added. Chapter '2-D Graphic Library' • New function GUI_BARCODE_Draw() added. • New function GUI_BARCODE_GetXSize() added. • New function GUI_DrawGradientVEx() added. • New function GUI_DrawGradientHEx() added. • New function GUI_DrawGradientMVEx() added. • New function GUI_DrawGradientMHEx() added. • New function GUI_DrawGradientRoundedVEx() added. • New function GUI_DrawGradientRoundedHEx() added. • New function GUI_FillRoundedRectEx() added. • New function GUI_YUV_Create() added. • New function GUI_YUV_CreateEx() added. • New function GUI_YUV_Delete() added. • New function GUI_YUV_DeleteEx() added. • New function GUI_YUV_GetpData() added. • New function GUI_YUV_GetpDataEx() added. • New function GUI_YUV_InvalidateArea() added. • New function GUI_YUV_SetPeriodEx() added. • New function GUI_YUV_SetPeriod() added. Chapter 'Animations' • New function GUI_ANIM_DeleteAll() added. • New function GUI_ANIM_GetFirst() added. • New function GUI_ANIM_GetNext() added. • New function GUI_ANIM_GetData() added. • New function GUI_ANIM_IsRunning() added. • New function GUI_ANIM_GetNumItems() added. • New function GUI_ANIM_GetItemData() added. Chapter 'Widgets' • New ROTARY widget added. • New SWITCH widget added. • New function EDIT_GetCharAtPixel() added. • New function EDIT_GetSel() added. • New function EDIT_GetSelText() added. • New function GRAPH_DATA_YT_SetColor() added. • New function GRAPH_DATA_XY_SetColor() added. • New function HEADER_GetColumnFromPos() added. • New function LISTBOX_EnableMotion() added. • New function LISTVIEW_EnableMotion() added. • New function MULTIEDIT_GetNumChars() added. • New function MULTIEDIT_GetTextFromLine() added. • New function MULTIEDIT_GetTextFromPos() added.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• New function MULTIPAGE_GetTabHeight() added. • New function MULTIPAGE_GetTabWidth() added. • New function MULTIPAGE_GetNumTabs() added. • New function SWIPELIST_IsSepItem() added. • Fixed a bug with the LISTVIEW widget where column headers would not move in fixed mode. • Fixed a bug with LISTWHEEL_SetItemData() that would cause a crash. • Fixed a bug where if SKINFLEX_PROPS where set only for the SPINBOX_SKINFLEX_PI_FOCUSED state, the lower button wasn't drawn correctly. • Fixed a bug where if DROPDOWN was collapsed it was possible to select disabled item by keyboard. • Fixed a bug where some widgets in a MULTIPAGE widget wouldn't get the focus. Chapter 'Sprites' • Fixed a bug where sprites weren't working with 1bpp bitmaps. Chapter 'Anti-aliasing' • Fixed a bug where GUI_AA_DrawLine() didn't draw a line in a window properly, added missing WM_ADDORG(x1, y1). Chapter 'Display Drivers' • GUIDRV_FlexColor supports UC1698, GUIDRV_FlexColor_Func66725 Chapter 'VNC Server' • emVNC is now available for MacOS and Linux. • New functions such as managing last connections, zooming in and out and fullscreen mode.
5.50	1	191015	FO	Various corrections and improvements.
5.50	0	190528	SC	Chapter 'Displaying Text' • New function GUI_ShowMissingCharacters() added. Chapter '2-D Graphic Library' • New function GUI_DrawGradientMH() added. • New function GUI_DrawGradientMV() added. Chapter 'Memory Devices' • New function GUI_MEMDEV_CreateCopy() added. Chapter 'Window Manager' • New function WM_SetUntouchable() added. Chapter 'Widgets' • New function GRAPH_InvertScrollBar() added. • New function GRAPH_DATA_YT/XY_SetColor() added. • New function KNOB_SetInvert() added. • New function KNOB_SetRotateHQ() added. • New function KNOB_SetRotateLQ() added. • New function SLIDER_EnableFocusRect() added. • New function SLIDER_SetInvertDir() added. • New function SPINBOX_SetTimerPeriod() added. Chapter 'Display Drivers' • New driver GUIDRV_SLinEPD added. • New driver GUIDRV_SSD1322 added. Chapter 'Configuration' • New function GUI_AlphaEnableFillRectHW() added.
5.48	0	180611	SC	Chapter 'Displaying Text' • New function GUI_SetClearTextRectMode() added. Chapter 'Window Manager' • New function WM_Rect2Screen() added. • New function WM_Rect2Client() added. • New function WM_XY2Screen() added. • New function WM_XY2Client() added. Chapter 'Widgets' • New function LISTBOX_SetFixedScrollPos() added. Chapter 'Language Support' • New function GUI_UC_SetEncodeSJIS() added. Chapter 'Display Drivers' • New function GUIDRV_FlexColor_SetOrientation() added. • New function GUIDRV_S1D13781_SetOrientation() added. • New function GUIDRV_S1D13L01_SetOrientation() added. • New fucntion LCD_Refresh() added. • New function LCD_RefreshEx() added. • New function LCD_ROTATE_AddDriver() added. • New function LCD_ROTATE_AddDriverEx() added. • New function LCD_ROTATE_DecSel() added. • New function LCD_ROTATE_DecSelEx() added. • New function LCD_ROTATE_IncSel() added. • New function LCD_ROTATE_IncSelEx() added.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• New function LCD_ROTATE_SetCallback() added. • New function LCD_ROTATE_SetSel() added. • New function LCD_ROTATE_SetSelEx() added. • GUIDRV_FlexColor support for SSD1353 added. Chapter 'Configuration' • New function GUI_ALLOC_GetMemInfo() added. • New function GUI_AA_SetFuncFillCircle() added. • New function GUI_AA_SetFuncFillPolygon() added. • New function GUI_AA_SetFuncDrawCircle() added. • New function GUI_AA_SetFuncDrawLine() added. • New function GUI_AA_SetFuncDrawPolyOutline() added. • New function GUI_AA_SetFuncDrawArc() added. • New function GUI_AA_SetpfStrcmp() added. • New function GUI_AA_SetpfStrcpy() added. • New function GUI_AA_SetpfStrlen() added.
5.46	0	171212	SC	Chapter 'Introduction to emWin' • Support of 64 bit data models added. Chapter 'Bitmap Converter' • Description of DTA files added. Chapter 'The Window Manager (WM)' • New message WM_SET_CALLBACK added. • Desktop window (WM_HBKWIN) is able to get user data now. Chapter 'Widgets (window objects)' • New functon CHECKBOX_GetImage() added. • New function HEADER_GetItemText() added. Chapter 'Display drivers' • New function LCD_GetVRAMAddr() added. • New function LCD_GetVRAMAddrEx() added. • GUIDRV_FlexColor support for HX8367 added. • GUIDRV_SPage support for UC1628 added. • GUIDRV_SPage support for ST75320 added. • GUIDRV_SPage support for SSD1309 added. Chapter 'Timing- and execution-related functions' • renamed GUI_Error() to GUI_ErrorOut().
5.44	1	171115	SC	Fixed table description.
5.44	0	171020	SC	Chapter 'emWin SPY' • New function GUI_SPY_StartServerEx() added. Chapter '2-D Graphic Library' • New function GUI_SPLINE_Create() added. • New function GUI_SPLINE_Draw() added. • New function GUI_SPLINE_Delete() added. • New function GUI_SPLINE_GetY() added. • New function GUI_SPLINE_GetXSize() added. • New function GUI_SPLINE_DrawAA() added. Chapter 'Displaying bitmap files' • New function GUI_JPEG_SetpfDrawEx() added. Chapter 'Movies' • New function GUI_MOVIE_SetpfNotify() added. • New functionality of displaying AVI files added. Chapter 'The Window Manager (WM)' • New message WM_USER_DATA added. Chapter 'Widgets' • New function EDIT_GetTextAlign() added. Chapter 'Anti-aliasing' • New function GUI_AA_DrawCircle() added. Chapter 'Display drivers' • New driver GUIDRV_SH_MEM_3 added. • GUIDRV_FlexColor support for ST7775 added. • New function GUIDRV_SPage_SetUC1610() added. • GUIDRV_1611 removed, covered by GUIDRV_SPage. Chapter 'Configuration' • New function GUI_ALLOC_GetMaxUsedBytes() added. • New function GUI_RegisterAfterInitHook() added. • New functionality, interface for JPEG hardware support.
5.42	0	170731	SC	Chapter 'Displaying Text' • New function GUI_DispStringInRectWrapEx() added. • New function GUI_SetStrikeWidth() added. Chapter '2-D Graphic Library' • New function GUI_AddRect() added. Chapter 'Bitmap Converter' • Description about options dialog

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				Chapter 'Widgets' • New function CHECKBOX_GetBkColor() added. • New function CHECKBOX_GetBoxBkColor() added. • New function CHECKBOX_GetFocusColor() added. • New function CHECKBOX_GetFont() added. • New function CHECKBOX_GetTextAlign() added. • New function CHECKBOX_GetTextColor() added. • New function DROPDOWN_GetBkColor() added. • New function DROPDOWN_GetColor() added. • New function DROPDOWN_GetFont() added. • New function DROPDOWN_GetTextColor() added. • New function GRAPH_GetColor() added. • New function HEADER_GetFont() added. • New function ICONVIEW_GetBkColor() added. • New function ICONVIEW_GetFont() added. • New function ICONVIEW_GetTextColor() added. • New function ICONVIEW_GetReleasedItem() added. • New function LISTBOX_GetBkColor() added. • New function LISTBOX_GetTextColor() added. • New function MENU_GetBkColor() added. • New function MENU_GetFont() added. • New function MENU_GetTextColor() added. • New function MULTIEDIT_GetBkColor() added. • New function MULTIEDIT_GetFont() added. • New function MULTIEDIT_GetTextColor() added. • New function MULTIEDIT_ShowCursor() added. • New function MULTIPAGE_GetBkColor() added. • New function MULTIPAGE_GetTextColor() added. • New function PROGBAR_GetBarColor() added. • New function PROGBAR_GetFont() added. • New function RADIO_GetBkColor() added. • New function RADIO_GetFocusColor() added. • New function RADIO_GetFont() added. • New function RADIO_GetTextColor() added. • New function SCROLLBAR_GetColor() added. • New function SPINBOX_GetFont() added. • New function SPINBOX_GetTextColor() added. • New function TEXT_SetDec() added. Chapter 'Dialogs' • New function CALENDAR_AddKey() added. Chapter 'Display Drivers' • 16bpp support for GUIDRV_S1D13L01 added. • 16bpp support for GUIDRV_S1D13781 added. • New function LCD_SetBufferPtr() added. • New function LCD_SetBufferPtrEx() added.
5.40	2	170524	JE	Chapter 'Displaying bitmap files' • Download link to PNG library changed. Chapter 'Fonts' • Download link to iType and iTypeSpark glue code changed. • Download link to Freetype library changed. • Description of XBF format added.
5.40	1	170508	JE	Chapter 'Display Drivers' • New driver GUIDRV_S1D13L01 added • New driver GUIDRV_S1D13L02 added • New driver GUIDRV_S1D13L04 added
5.40	0	170302	JE	Chapter 'Simulation' • Function SIM_GUI_SaveCompositeBMP() added. Chapter 'Displaying Text' • Function GUI_WrapSetSeparators() added. • Function GUI_WrapGetPositions() added. Chapter 'Movies' • Function GUI_MOVIE_DrawFrame() added. Chapter 'Widgets' • Function ICONVIEW_GetItemBitmap() added. • Function ICONVIEW_SetOwnerDraw() added. • Function MULTIEDIT_SetCursorCharPos() added. • Function MULTIEDIT_SetCursorPixelPos() added. • Function WIDGET_SetFocusable() added. • Function WIDGET_EnableStreamAuto() added. Chapter 'Bitmap Converter' • Bitmap Converter now supports JPEG files. • New command line option 'reducecolors' added.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• New command line option 'hide' added. • New command line option 'scale' added. Chapter 'Window Manager' • Function WM_GetNumInvalidWindows() added. • Function WM_MOTION_SetThreshold() added. • 'Overlapping' support added to WM_MOTION. • New variables added to WM_MOTION_INFO. Chapter 'Display Drivers' • Function LCD_On() and LCD_OnEx() added. • Function LCD_Off() and LCD_OffEx() added. Chapter 'Configuration' • Function GUI_SetpfMemset() added. • Function GUI_SetpfMemcpy() added.
5.38	0	161124	JE SC	Chapter 'Simulation' • Function SIM_GUI_Delay() added. • Function SIM_GUI_ExecIdle() added. • Function SIM_GUI_GetTime() added. Chapter '2-D Graphic Library' • Function GUI_GCACHE_4_Create() added. • Function GUI_GCACHE_4_CreateEx() added. Chapter 'Fonts' • Function GUI_GetDefaultFont() added. Chapter 'Animations' • Function GUI_ANIM_StartEx() added. • Function GUI_ANIM_Stop() added. Chapter 'Colors' • Function GUI_GetDefaultBkColor() added. • Function GUI_GetDefaultColor() added. • Function GUI_SetDefaultBkColor() added. • Function GUI_SetDefaultColor() added. Chapter 'Memory Devices' • Function GUI_MEMDEV_MULTIBUF_Enable() added. Chapter 'Window Manager' • Explanation how to work with WM and multiple layers added. Chapter 'Widgets' • MULTIEDIT: GUI_KEY_PGUP and GUI_KEY_PGDOWN added Chapter 'Pointer Input Devices' • Function GUI_PID_SetHook() added. Chapter 'Display Drivers' • LCD_DEVFUNC_DRAWBMP_32BPP added to LCD_SetDevFunc(). • New driver GUIDRV_S1D13513 added. • GUIDRV_FlexColor: 24bpp mode added to F66720. Chapter 'VNC Server' • Function GUI_VNC_SetRetryCount() added. Chapter 'Timing and execution related functions' • Function GUI_GetTimeSlice() added. • Function GUI_SetTimeSlice() added. Chapter 'Configuration' • Explanation added how to work with a frame buffer and DCACHE • Function GUI_SetFuncDrawAlpha() added. • Function GUI_DCACHE_Clear() added. • Function GUI_DCACHE_SetClearCacheHook() added.
5.36	2	160906	JE	Chapter 'Performance and Resource usage' • Performance values for ARM Cortex-M4 and A9 added • Image performance values recalculated
5.36	1	160901	JE	Chapter 'Display Drivers' • GUIDRV_FlexColor: 24bpp mode added
5.36	0	160829	JE	Chapter 'Widgets' • Function SWIPELIST_GetThreshold() added. • Function SWIPELIST_SetThreshold() added. • Function SWIPELIST_SetDefaultThreshold() added. • Function SWIPELIST_GetDefaultThreshold() added. • Function GRAPH_DATA_YT_GetValue() added. • Function GRAPH_DATA_XY_GetPoint() added. Chapter 'Antialiasing' • Function GUI_AA_EnableGammaAA4() added. • Function GUI_AA_SetGammaAA4() added. • Function GUI_AA_GetGammaAA4() added. Chapter 'Language Support' • Explanation of Unicode standard compatibility added. • Function GUI_UC_SetBaseDir() added.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				Chapter 'Display Drivers' • Support for Sitronix ST7796 added to GUIDRV_FlexColor. • Support for LDT LD7138 added to GUIDRV_FlexColor. • Support for SP9230 added to GUIDRV_FlexColor. • Support for IST3501 added to GUIDRV_SPage. • Support for Sitronix ST7570 added to GUIDRV_SPage.
5.34	2	160621	JE	Chapter 'Introduction' • Compiler limitation added: 'char' needs to be 8 bit
5.34	1	160517	JE	Chapter 'Display Drivers' • GUIDRV_SH_MEM: LS013B7DH06 removed, only b/w supported
5.34	0	160425	JE	Chapter 'Getting Started' • Function GUI_IsInitialized() added. Chapter 'Simulation' • Function SIM_GUI_SaveBMP() added. • Function SIM_GUI_SaveBMPEx added. Chapter '2-D Graphic Library' • Function GUI_QR_Create() added. • Function GUI_QR_Delete() added. • Function GUI_QR_Draw() added. • Function GUI_QR_GetInfo() added. • Function GUI_SetControlHook() added. Chapter 'Displaying bitmap files' • Function GUI_BMP_EnableAlpha() added. Chapter 'Fonts' • Support for iTypeSpark® font engine added. Chapter 'Widgets' • Function LISTBOX_GetOwner() added. Chapter 'Pointer Input Devices' • Function GUI_PID_SetInitFunc() added. Chapter 'Display Drivers' • New display driver for Sharp Memory LCDs added Chapter 'VNC Server' • File transfer capabilities added. Chapter 'Configuration' • Macro GUI_POST_INIT added.
5.32	0	150930	JE	Chapter 'Simulation' • Function SIM_GUI_GetCompositeTouch() added. • Function SIM_GUI_SetCompositeTouch() added. Chapter 'emWinSPY' • RTT connection added. Chapter 'Widgets' • New widget 'SWIPELIST' added. • Function LISTVIEW_SetSelCol() added. • Function SLIDER_GetRange() added. • Function EDIT_EnableInversion() added. Chapter 'Language Support' • Function GUI_LANG_GetLang() added. Chapter 'Display Drivers' • Commands added to LCD_X_DisplayDriver(): • LCD_X_SHOWBUFFER, LCD_X_SETVIS, LCD_X_SETPOS, LCD_X_SETSIZE, LCD_X_SETALPHA
5.30	0	150706	JE AS	Chapter '2-D Graphic Library' • Function GUI_PreserveTrans() added. • Function GUI_SetAlphaMask8888() added. Chapter 'Bitmap Converter' • Saving of PNGs now supported. • New bitmap format M8888I supported. Chapter 'Font Converter' • Loading of Adobe (B)itmap (D)istribution (F)ormat (BDF) added. Chapter 'Animations' • Function GUI_ANIM_AddItem() added. • Function GUI_ANIM_Create() added. • Function GUI_ANIM_Delete() added. • Function GUI_ANIM_Exec() added. • Function GUI_ANIM_Start() added. Chapter 'Colors' • New logical color mode ARGB added. Chapter 'Memory Devices' • Function GUI_MEMDEV_WriteOpaque() added. • Function GUI_MEMDEV_WriteOpaqueAt() added. Chapter 'Window Manager'

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• Explanation of tiling algorithm added. Chapter 'Widgets' • Function LISTWHEEL_IsMoving() added. • Function PROGBAR_GetMinMax() added. • Function PROGBAR_GetValue() added. • Function TEXT_GetBkColor() added. • Function TEXT_GetFont() added. • Function TEXT_GetTextAlign() added. • Function TEXT_GetTextColor() added. • Function TEXT_GetWrapMode() added. • Function TEXT_GetDefaultTextColor() added. • Function TEXT_GetDefaultWrapMode() added. Chapter 'Display Drivers' • Support for HX8369 added to GUIDRV_FlexColor. • Support for ST7715 added to GUIDRV_FlexColor. • Support for SSD1325 added to GUIDRV_SLin.
5.28	1	150206	JE	Licensing information of TTF and PNG support changed.
5.28	0	150128	JE AS	Chapter 'Simulation' • Function SIM_GUI_SetTransMode() added. New Chapter 'emWinSPY' • New tool emWinSPY added: • Function GUI_SPY_Process() added. • Function GUI_SPY_SetMemHandler() added. • Function GUI_SPY_StartServer() added. • Function GUI_SPY_X_StartServer() added. Chapter '2-D Graphic Library' • Function GUI_SetRefreshHook() added. Chapter 'Fonts' • Commas added to standard digit fonts. Chapter 'Widgets' • Some new default values added to FRAMEWIN and WINDOW. • Function LISTBOX_EnableWrapMode() added. Chapter 'Multi layer / multi display support' • Softlayers added: • Function GUI_SOFTLAYER_Enable() added. • Function GUI_SOFTLAYER_MULTIBUF_Enable() added. • Function GUI_SOFTLAYER_Refresh() added. • Function GUI_SOFTLAYER_SetCompositeColor() added. Chapter 'Sprites' • Sprites now support true color bitmaps with alpha blending. Chapter 'Display drivers' • LCD_DEVFUNC_DRAWBMP_8BPP added to LCD_SetDevFunc(). • Support for ST7789 added to GUIDRV_FlexColor. • Support for UC1638 added to GUIDRV_SPage • Support for Avant Electronics SBN0064G added to GUIDRV_SPage • New display driver GUIDRV_7528 added Chapter 'Configuration' • Function GUITASK_GetMaxTask() added. • Function GUICC_M1555I_SetCustColorConv() added. • Function GUICC_M565_SetCustColorConv() added. • Function GUICC_M4444I_SetCustColorConv() added. • Function GUICC_M888_SetCustColorConv() added. • Function GUICC_M8888I_SetCustColorConv() added. • Function GUI_SetFuncAlphaBlending() added. • Function GUI_SetFuncGetpPalConvTable() added. • Function GUI_SetFuncMixColors() added. • Function GUI_SetFuncMixColorsBulk() added. • Function GUI_AA_SetpfDrawCharAA4() added. • Function GUI_MEMDEV_SetDrawMemdev16bppFunc() added.
5.26	2	141128	AS	Various corrections.
5.26	1	140821	JE AS	Chapter 'Widgets' • Function MULTIPAGE_SetDefaultBorderSizeX() added. • Function MULTIPAGE_SetDefaultBorderSizeY() added. Various corrections.
5.26	0	140805	JE AS	Chapter '2-D Graphic Library' • Function GUI_DIRTYDEVICE_Create() added. • Function GUI_DIRTYDEVICE_CreateEx() added. • Function GUI_DIRTYDEVICE_Delete() added. • Function GUI_DIRTYDEVICE_DeleteEx() added. • Function GUI_DIRTYDEVICE_Fetch() added.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• Function GUI_DIRTYDEVICE_FetchEx() added. Chapter 'Bitmap Converter' • Dithering added. Chapter 'Memory Devices' • Function GUI_MEMDEV_FadeOutDevices() added. • Function GUI_MEMDEV_RotateHQAlpha() added. • Function GUI_MEMDEV_RotateAlpha() added. • Function GUI_MEMDEV_Dither32() added. Chapter 'The Window Manager (WM)' • Function WM_GetScrollbarH() added. • Function WM_GetScrollbarV() added. • Function WM_SetModalLayer() added. • Function WM_GetModalLayer() added. Chapter 'Widgets' • Function LISTVIEW_EnableCellSelect() added. • Function LISTVIEW_GetItemRect() added. • Function LISTVIEW_SetItemTextSorted() added. • Function MULTIPAGE_EnableScrollBar() added. • Function MULTIPAGE_SetBitmap() added. • Function MULTIPAGE_SetBitmapEx() added. • Function MULTIPAGE_SetTabHeight() added. • Function MULTIPAGE_SetTabWidth() added. • Function MULTIPAGE_SetTextAlign() added. Chapter 'Antialiasing' • Function GUI_AA_FillEllipse() added. Chapter 'Display drivers' • Support for LGDP4525 added to GUIDRV_FlexColor. • Support for Ilitek ILI9488 added to GUIDRV_FlexColor. • Support for Himax HX8357 added to GUIDRV_FlexColor. • Support for Raio RA8875 added to GUIDRV_FlexColor. • Support for OriseTech SPLC502B added to GUIDRV_SPage.
5.24	2	140429	SC AS	Table titles were added for all tables except "Permitted values". Chapter 'Colors' • Structure 'LCD_PHYSPALETTE' added. • Section 'Look-up table API' added. • Function 'LCD_SetLUT()' added. • Function 'LCD_SetLUTEx()' added. • Function 'LCD_SetLUTEntryEx()' added.
5.24	1	140225	SC AS	Various corrections.
5.24	0	130801	JE	Chapter '2-D Graphic Library' • New function GUI_CreateBitmapFromStreamA555() added. • New function GUI_CreateBitmapFromStreamAM555() added. • New function GUI_CreateBitmapFromStreamA565() added. • New function GUI_CreateBitmapFromStreamAM565() added. • New function GUI_DrawStreamedBitmapA555Ex() added. • New function GUI_DrawStreamedBitmapAM555Ex() added. • New function GUI_DrawStreamedBitmapA565Ex() added. • New function GUI_DrawStreamedBitmapAM565Ex() added. Chapter 'Bitmap Converter' • New bitmap formats added: 16bpp + 8 bit alpha channel. Chapter 'Fonts' • New function GUI_TTF_CreateFontAA() added. Chapter 'Memory Devices' • New function GUI_MEMDEV_ClearAlpha() added. • New function GUI_MEMDEV_CreateFixed32() added. • New function GUI_MEMDEV_BlendColor32() added. Chapter 'Window Manager' • Circular motion support added. Chapter 'Widgets' • New widget "KNOB" added. • New function LISTWHEEL_SetDeceleration() added. • New function DROPDOWN_SetListHeight() added. • New function LISTVIEW_OwnerDraw() added. • New function LISTVIEW_SetOwnerDraw() added. • New function LISTVIEW_GetWrapMode() added. • New function MULTIPAGE_GetPageText() added. • New function SPINBOX_SetEditMode() added. • New function SPINBOX_SetStep() added. New Chapter 'MultiTouch' added. • New function GUI_MTOUCH_Enable() added.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• New function GUI_MTOUCH_GetEvent() added. • New function GUI_MTOUCH_GetTouchInput() added. • New function GUI_MTOUCH_IsEmpty() added. • New function GUI_MTOUCH_SetOrientation() added. • New function GUI_MTOUCH_SetOrientationEx() added. • New function GUI_MTOUCH_StoreEvent() added. • New function WM_EnableGestures() added. Chapter 'Antialiasing' • New function GUI_AA_PreserveTrans() added. Chapter 'Language Support' • Remark that Devanagari transitions are not supported. Chapter 'Display Drivers' • New function LCD_SetChromaEx() added. • New function LCD_SetChromaModeEx() added. • New function LCD_SetAlpha() added. • New function LCD_SetAlphaModeEx() added. • New function LCD_SetVisEx() added. • Support for Ilitek ILI9163 added to GUIDRV_FlexColor. • Support for RAIO8870 added to GUIDRV_FlexColor. • Support for Solomon SSD1351 added to GUIDRV_FlexColor. • Support for RAIO 8835 added to GUIDRV_SLin. • Support for Samsung S6B0108 added to GUIDRV_SPage. • Support for Hitachi HD61202 added to GUIDRV_SPage. Chapter 'Touch drivers' • New multi touch driver added for PIXCIR TangoC32. Chapter 'Performance and Resource Usage' • New sub chapter 'Optimizing Footprint' added.
5.22	2	140108	AS	GUIDRV_CompactColor_16: • Support for Samsung S6D0128 added to 66772. • Support for Sitronix ST7789 added to 66717.
5.22	1	130801	AS	Various corrections.
5.22	0	130625	JE AS	New Chapter 'Movies' added. Chapter 'Colors' • New color conversion GUICC_8 added. Chapter 'Memory Devices' • New function GUI_MEMDEV_BlendWinBk() added. • New function GUI_MEMDEV_BlurAndBlendWinBk() added. • New function GUI_MEMDEV_BlurWinBk() added. • New function GUI_MEMDEV_CreateBlurredDevice32() added. • New function GUI_MEMDEV_CreateBlurredDevice32HQ() added. • New function GUI_MEMDEV_CreateBlurredDevice32LQ() added. • New function GUI_MEMDEV_PunchOutDevice() added. • New function GUI_MEMDEV_RotateHQHR() added. • New function GUI_MEMDEV_RotateHR() added. • New function GUI_MEMDEV_SetBlurHQ() added. • New function GUI_MEMDEV_SetBlurLQ() added. Chapter 'Widgets' • Added notification messages sent by the IMAGE widget. • Added notification messages sent by the TEXT widget. • New function GRAPH_SetAutoScrollbar() added. • New function GRAPH_GetScrollValue() added. • New function GRAPH_SetScrollValue() added. • New function ICONVIEW_SetIconAlign() added. • New function LISTWHEEL_GetItemFromPos() added. • New function MULTIEDIT_SetFocussable() added. • New function MULTIPAGE_GetPageText() added. • New function TREEVIEW_ScrollToSel() added. • New section 16.1.2 'Custom widgets' added. Chapter 'Sprites' • New function GUI_SPRITE_SetLoop() added. • New function GUI_SPRITE_StartAnim() added. • New function GUI_SPRITE_StopAnim() added. Chapter 'Antialiasing' • New function GUI_AA_FillRoundedRect() added. • New function GUI_AA_FillRoundedRectEx() added. • New function GUI_AA_DrawRoundedRect() added. • New function GUI_AA_DrawRoundedRectEx() added. Chapter 'Display drivers' • New display driver GUIDRV_UC1698G added. • Support for Solomon SSD1306 added to GUIDRV_SPage. Chapter 'Timing- and execution-related functions'

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• New function GUI_TIMER_Create() added. • New function GUI_TIMER_Delete() added. • New function GUI_TIMER_Restart() added. • New function GUI_TIMER_SetPeriod() added.
5.20	4	130409	AS	GUIDRV_SPage: • Support for Solomon SSD1305 added to 1510.
5.20	3	130409	AS	Various corrections / improvements.
5.20	2	130308	AS	Chapter 'Language Support' • New function GUI_LANG_GetTextBuffered() added. • New function GUI_LANG_GetTextBufferedEx() added.
5.20	1	130305	AS	Chapter 'Skinning' • New function CHECKBOX_GetSkinFlexButtonSize() added. • New function CHECKBOX_SetSkinFlexButtonSize() added.
5.20	0	130218	JE	Chapter 'Fonts' • Support for iType® fonts of Monotype Imaging added. Chapter 'Colors' • New color conversions added: GUICC_M8888I, GUICC_M1555I, GUICC_M4444I, GUICC_1616I, GUICC_88666I Chapter 'Dialogs' • CALENDAR dialog and functions added: • CALENDAR_Create() • CALENDAR_GetDate() • CALENDAR_GetSel() • CALENDAR_SetDate() • CALENDAR_SetSel() • CALENDAR_SetDefaultBkColor() • CALENDAR_SetDefaultColor() • CALENDAR_SetDefaultDays() • CALENDAR_SetDefaultFont() • CALENDAR_SetDefaultMonths() • CALENDAR_SetDefaultSize() Chapter 'Sprites' • New function GUI_SPRITE_CreateHidden() added. • New function GUI_SPRITE_CreateHiddenEx() added. Chapter 'Display Drivers' • GUIDRV_FlexColor: • Support for Himax HX8340 added to 66712. • New module 66772 added with support for: Hitachi HD66772, Samsung S6D0117, Sitronix ST7712, Himax HX8301, Ilitek ILI9220 and ILI9221 • GUIDRV_SLin: Support for Epson S1D13305 added. Chapter 'VNC-Server' • New function GUI_VNC_SetLockFrame() added. Chapter 'Timing and execution' • New function GUI_Error() added. Chapter 'Configuration' • New function GUI_SetOnErrorFunc() added.
5.18	0	120917	JE AS	Chapter 'Displaying bitmap files' • New function GUI_BMP_SerializeExBpp() added. Chapter 'Bitmap Converter' • New functions added to create animated sprites and cursors out of animated GIF files. Chapter 'Memory Devices' • New function GUI_MEMDEV_SerializeBMP() added. Chapter 'The Window Manager (WM)' • New function WM_SetCaptureMove() added. • New function WM_Screen2hWin() added. • New function WM_Screen2hWinEx() added. Chapter 'Window Objects (Widgets)' • New functions added: • TEXT_GetText() • LISTVIEW_SetWrapMode() Chapter 'Antialiasing' • New function GUI_AA_SetDrawMode() added. Chapter 'Foreign Language Support' • New feature "Text • and language resource files" added. Chapter 'Display drivers' • GUIDRV_FlexColor: • Function GUIDRV_FlexColor_SetInterface66709_B16() replaced by the function GUIDRV_FlexColor_SetReadFunc66709_B16().

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• Function GUIDRV_FlexColor_SetInterface66720_B16() replaced by the function GUIDRV_FlexColor_SetReadFunc66720_B16(). • New module 66702 added: Solomon SSD1284, SSD1289, SSD1298 • New module 66715 added: Himax HX8352B • Recommended calling sequence for configuration functions added. • GUIDRV_S1D13781: • Additional information about initialized registers added.
5.16	2	120809	AS	Chapter 'Window Objects (Widgets)' • New function SPINBOX_SetRange() added. Various corrections.
5.16	1	120628	AS	Chapter 'The Window Manager (WM)' • Descriptions of the following functions reworked: • WM_GetScrollPosH() • WM_GetScrollPosV() • WM_SetScrollPosH() • WM_SetScrollPosV() • Preface, About and Chapter 'Introduction' reworked.
5.16	0	120605	JE AS	Chapter 'Colors' • New color conversion routine added to support 1bpp at different color depths. Chapter 'Memory Devices' • New function GUI_MEMDEV_RotateHQT() added. Chapter 'The Window Manager (WM)' • Support for ToolTips added. • New functions added: • WM_TOOLTIP_AddTool() • WM_TOOLTIP_Create() • WM_TOOLTIP_Delete() • WM_TOOLTIP_SetDefaultFont() • WM_TOOLTIP_SetDefaultColor() • WM_TOOLTIP_SetDefaultPeriod() Chapter 'Window Objects (Widgets)' • New functions added: • BUTTON_SetReactOnTouch() • DROPDOWN_SetUpMode() • ICONVIEW_EnableStreamAuto() Changed function SPINBOX_SetButtonSize(): • New option SPINBOX_EDGE_CENTER. Chapter 'Dialogs' • CHOOSECOLOR dialog and functions added: • CHOOSECOLOR_Create() • CHOOSECOLOR_GetSel() • CHOOSECOLOR_SetSel() • CHOOSECOLOR_SetDefaultColor() • CHOOSECOLOR_SetDefaultSpace() • CHOOSECOLOR_SetDefaultBorder() • CHOOSECOLOR_SetDefaultButtonSize() • CHOOSEFILE_EnableToolTips() • CHOOSEFILE_SetButtonText() • CHOOSEFILE_SetDefaultButtonText() • CHOOSEFILE_SetToolTips() • CHOOSEFILE_SetTopMode() Chapter 'Pointer Input Devices' • New function GUI_PID_IsPressed() added. Chapter 'Keyboard Input' • New function GUI_GetKeyState() added. Chapter 'Foreign Language Support' • New function GUI_LANG_GetNumItems() added. Chapter 'Foreign Language Support' • New function GUI_LANG_GetText() added. • New function GUI_LANG_GetTextEx() added. • New function GUI_LANG_LoadCSV() added. • New function GUI_LANG_LoadCSVEx() added. • New function GUI_LANG_LoadText() added. • New function GUI_LANG_LoadTextEx() added. • New function GUI_LANG_SetLang() added. • New function GUI_LANG_SetMaxNumLang() added. • New function GUI_LANG_SetSep() added. Chapter 'Display drivers' • New display controller supported by • GUIDRV_SPage, GUIDRV_SPage_Set1510:

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• Epson S1D15605, S1D15606, S1D15607, S1D15608, S1D15705, S1D15710, S1D15714 • Integrated Solutions Technology IST3020 • New Japan Radio Company NJU6676 • Novatek NT7502, NT7534, NT7538, NT75451 • Samsung S6B0719, S6B0713, S6B0724, S6B1713 • Sino Wealth SH1101A • Sitronix ST7522, ST7565, ST7567 • Solomon SSD1303, SSD1805, SSD1815, SSD1821 • Sunplus SPLC501C • UltraChip UC1608, UC1701, UC1601, UC1606 • GUIDRV_SPage_Set1512: • Epson S1D15E05, S1D15E06, S1D15719, S1D15721 • GUIDRV_SPage_SetST7591: Sitronix ST7591 • New display controllers supported by GUIDRV_FlexColor: • 66708: Ilitek ILI9335 • 66709: Ilitek ILI9338, ILI9340, ILI9341, ILI9342 • 66719: Samsung S6E63D6 • New function LCD_SetMaxNumColors() added. • Support for 1bpp added to GUIDRV_SPage. • Function GUIDRV_SPage_SetS1D15() obsolete, replaced by GUIDRV_SPage_Set1512 • New variants GUIDRV_Lin added: • GUIDRV_LIN_OX_8 • GUIDRV_LIN_OXY_8 • New driver GUIDRV_S1D13781 added. New Chapter 'Touch drivers' added. • New driver GUITDRV_ADS7846 added.
5.14	3	120202	AS	Chapter 'Display drivers' • New display controller supported by GUIDRV_FlexColor: • 66709: Ilitek ILI9340 • New display controllers supported by GUIDRV_SPage: • Epson S1D15605, S1D15606, S1D15607, S1D15608, S1D15705, S1D15710, S1D15714 • Integrated Solutions Technology IST3020 • New Japan Radio Company NJU6676 • Novatek NT7502, NT7534, NT7538, NT75451 • Samsung S6B0719, S6B0713, S6B0724, S6B1713 • Sino Wealth SH1101A • Sitronix ST7522, ST7565, ST7567 • Solomon SSD1805, SSD1303, SSD1815 • UltraChip UC1608, UC1701, UC1601, UC1606 • Sunplus SPLC501C • New function GUIDRV_SPage_Set1510 added. • New function GUIDRV_SPage_Set1512 added.
5.14	2	120201	AS	Chapter 'Displaying bitmaps files' • Improved description of the 'GetData'-function. Chapter 'Display drivers' • GUIDRV_SPage now supports 1bpp. • New display controllers supported by GUIDRV_SPage: • Epson S1D15E05, S1D15E06, S1D15719, S1D15721 • Sitronix ST7591 • New function GUIDRV_SPage_SetST7591 added.
5.14	1	120124	AS	Chapter 'Window Objects (Widgets)' • New function EDIT_GetTextColor(). • New function SPINBOX_GetEditHandle().
5.14	0	120111	JE AS	Chapter 'Simulation' • New function SIM_GUI_Enable() added. Chapter '2D Graphic Library' • New functions added: • GUI_DrawStreamedBitmapAuto() • GUI_DrawStreamedBitmapExAuto() • GUI_DrawStreamedBitmap24Ex() • GUI_DrawStreamedBitmap555Ex() • GUI_DrawStreamedBitmap565Ex() • GUI_DrawStreamedBitmapM555Ex() • GUI_DrawStreamedBitmapM565Ex() Chapter 'Font Converter' • Functions to size, shift and move characters added. Chapter 'Colors' • Sub chapter 'Gamma correction' added.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				Chapter 'The Window Manager (WM)' • Change of the WM_MOVE message to transmit position changes. • New functions added: • WM_MOTION_Enable() • WM_MOTION_SetMovement() • WM_MOTION_SetDeceleration() • WM_MOTION_SetDefaultPeriod() • WM_MOTION_SetMotion() • WM_MOTION_SetMoveable() • WM_MOTION_SetSpeed() Chapter 'Window Objects (Widgets)' • New widget "SPINBOX" added. • New widget "IMAGE" added. • Return values added to the following functions: • BUTTON_SetText() • TEXT_SetText() • New function DROPDOWN_GetItemText() added. • New function EDIT_GetBkColor() added. • New function EDIT_SetBkColor() added. • New function EDIT_SetFocussable() added. • New function EDIT_GetFont() added. • New function GUI_EditFloat() added. • Listing of widget IDs added. Chapter 'Sprites' • New function GUI_SPRITE_CreateAnim() added. • New function GUI_SPRITE_CreateExAnim() added. Chapter 'Cursors' • New function GUI_CURSOR_SelectAnim() added. Chapter 'Display drivers' • New display controllers supported by GUIDRV_FlexColor: • 66708: FocalTech FT1509 • 66709: Renesas R61526 • 66709: Ilitek ILI9342 • 66712: Himax HX8347 • 66712: Himax HX8352 • New display controllers supported by GUIDRV_CompactColor_16: • 66708: FocalTech FT1509 • 66709: Renesas R61526 • 66709: Ilitek ILI9342
5.12	1	111021	AS	Font Converter documentation added as chapter 11. • New function GUIDRV_FlexColor_SetFunc66712() added. • New function GUIDRV_FlexColor_SetInterface66712B16() added. • New display controller supported by GUIDRV_07X1: • 741: Novatek NT7508 • New display controller supported by GUIDRV_Page1bpp: • 1510: Solomon SSD1821 • GUIDRV_Lin 'Using the Lin driver in systems with cache memory' changed.
5.12	0	110621	AS JE	Chapter 'Window Objects (Widgets)' • New function LISTVIEW_SetHeaderHeight() added. • New function ICONVIEW_AddStreamedBitmapItem() added. • New function ICONVIEW_GetItemText() added. • New function ICONVIEW_GetItemUserData() added. • New function ICONVIEW_GetNumItems() added. • New function ICONVIEW_InsertBitmapItem() added. • New function ICONVIEW_InsertStreamedBitmapItem() added. • New function ICONVIEW_SetBitmapItem() added. • New function ICONVIEW_SetFrame() added. • New function ICONVIEW_SetItemText() added. • New function ICONVIEW_SetItemUserData() added. • New function ICONVIEW_SetSpace() added. • New function ICONVIEW_SetStreamedBitmapItem() added. • New function ICONVIEW_SetTextAlign() added. • New function TEXT_GetNumLines() added. Chapter 'Display Drivers' • New display drivers added: • GUIDRV_Dist • GUIDRV_SPage • New display controller supported by GUIDRV_CompactColor_16: • 66709: Solomon SSD1961 • LCD_SetDevFunc(): LCD_DEVFUNC_COPYRECT added. • GUIDRV_Lin: Support for LCD_DEVFUNC_COPYRECT added.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
5.10	1	110531	AS JE	Chapter 'Display Drivers' • New display driver: GUIDRV_FlexColor
5.10	0	110329	AS JE	Chapter 'Memory Devices' • Default for GUI_USE_MEMDEV_1BPP_FOR_SCREEN set to 1. • New function GUI_MEMDEV_MarkDirty() added. New chapter 'GUIBuilder' added. Chapter 'Display Drivers' • New display controllers supported by GUIDRV_CompactColor_16: • 66708: Ilitek ILI9328 • 66709: Sitronix ST7715 • 66772: Ilitek ILI9221 • New function GUIDRV_BitPlains_Config() added.
5.08	0	110112	AS JE	Chapter '2D Graphic Library' • New function GUI_CreateBitmapFromStreamRLEAlpha() added. • New function GUI_CreateBitmapFromStreamRLE32() added. • Function GUI_CreateBitmapFromStream() supports additional formats. Chapter 'Bitmap Converter' • New format 'Alpha channel, compressed' added. • New format 'True color with alpha channel, compressed' added. • New function 'Image/Convert Into/Best Palette + transparency' added. Chapter 'Memory Devices' • New functions GUI_MEMDEV_SetAnimationCallback() added. • New functions GUI_MEMDEV_ShiftInWindow() added. • New functions GUI_MEMDEV_ShiftOutWindow() added. Chapter 'Execution Model' • New function GUI_SetSignalEventFunc() added. • New function GUI_SetWaitEventFunc() added. • New function GUI_SetWaitEventTimedFunc() added. • Definitions of configuration macros changed. Chapter 'Window Manager' • New function WM_MULTIBUF_Enable() added. • New messages WM_PRE_PAINT and WM_POST_PAINT added. Chapter 'Widgets' • LISTVIEW_SetUserData() renamed in LISTVIEW_SetUserDataRow(). • LISTVIEW_GetUserData() renamed in LISTVIEW_GetUserDataRow(). • New function <WIDGET>_SetUserData() added for all widgets. • New function <WIDGET>_GetUserData() added for all widgets. • New function <WIDGET>_CreateUser() added for all widgets. • New function BUTTON_GetTextAlign() added. • New function BUTTON_SetReactOnLevel() added. • New function ICONVIEW_CreateIndirect() added. • New function ICONVIEW_DeleteItem() added. • New function LISTWHEEL_CreateIndirect() added. • New function SCROLLBAR_SetThumbSizeMin() added. • New function SCROLLBAR_GetThumbSizeMin() added. • New function TREEVIEW_ITEM_CollapseAll() added. • New function TREEVIEW_ITEM_ExpandAll() added. Chapter 'Skinning' • New configuration macro WIDGET_USE_FLEX_SKIN added. • New message WIDGET_ITEM_GET_RADIUS added to frame window skin. Chapter 'Multiple Buffering'. • New function GUI_MULTIBUF_Begin() added. • New function GUI_MULTIBUF_End() added. • New function GUI_MULTIBUF_Config() added. Chapter 'Foreign Language Support' • New function GUI_UC_EnableBIDI() added.
5.06	0	100907	JE	Chapter 'Fonts': • New function GUI_SetDefaultFont() added. Chapter 'Memory Devices': • New function GUI_MEMDEV_FadeDevices() added. Chapter 'Widgets': • New function BUTTON_SetReactOnLevel() added. • New function GRAPH_DATA_XY_SetOwnerDraw() added. • New function LISTVIEW_SetItemBitmap() added. • New function LISTWHEEL_SetPos() added. • New function SCROLLBAR_GetNumItems() added. • New function SCROLLBAR_GetPageSize() added. New Chapter 'Skinning': • Skinning for the most common widgets added. Chapter 'Display Driver':

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				• New function GUI_SetOrientation() added. • New OXY-orientations for 16, 24 and 32 bpp added to GUIDRV_Lin.
5.04	2	100526	AS	Chapter 'Widgets': • New function GRAPH_DATA_XY_SetOwnerDraw() added. • New function LISTVIEW_SetItemBitmap() added. Chapter 'Fonts': • New function GUI_SetDefaultFont() added. Chapter '2-D Graphic Library': • New function GUI_GetPixelIndex() added. Chapter 'Execution Model': • GUITASK_SetMaxTask() • GUIDRV_CompactColor_16: • Support for the following display controllers added: • Himax HX8353 • LGDP4551 • Orisetech SPFD54124C • Renesas R61505 • Sitronix ST7735, ST7787 • Solomon SSD1284, SSD2119 • Added driver macros to each driver which uses them.
5.04	1	100505	AS	New Drivers 'GUIDRV_S1D15G00' and 'GUIDRV_SLin' added. Various corrections Chapter '2-D Graphic Library': • New function GUI_DrawGradientRoundedV() • New function GUI_DrawGradientRoundedH() • New function GUI_DrawRoundedFrame() Chapter 'Memory Devices': • New function GUI_MEMDEV_MoveInWindow() • New function GUI_MEMDEV_MoveOutWindow() • New function GUI_MEMDEV_FadeInWindow() • New function GUI_MEMDEV_FadeOutWindow() Chapter 'Simulation' • New function SIM_GUI_SetCallback() • New function SIM_GUI_ShowDevice()
5.04	0	100104	JE	Chapter 'Displaying Text': • New function GUI_DispStringInRectWrap() added. • New function GUI_WrapGetNumLines() added. Chapter '2-D Graphic Library': • New function GUI_EnableAlpha() added. • New function GUI_RestoreUserAlpha() added. • New function GUI_SetUserAlpha() added. • New function GUI_CreateBitmapFromStream() added. • New function GUI_DrawStreamedBitmapEx() added. • New function GUI_GetStreamedBitmapInfo() added. • New function GUI_GetStreamedBitmapInfoEx() added. • New function GUI_SetStreamedBitmapHook() added. • New function GUI_CreateBitmapFromStreamIDX() added. • New function GUI_CreateBitmapFromStreamRLE4() added. • New function GUI_CreateBitmapFromStreamRLE8() added. • New function GUI_CreateBitmapFromStream565() added. • New function GUI_CreateBitmapFromStreamM565() added. • New function GUI_CreateBitmapFromStream555() added. • New function GUI_CreateBitmapFromStreamM555() added. • New function GUI_CreateBitmapFromStreamRLE16() added. • New function GUI_CreateBitmapFromStreamRLEM16() added. • New function GUI_CreateBitmapFromStream24() added. • New function GUI_CreateBitmapFromStreamAlpha() added. Chapter 'Fonts': • New font F20F_ASCII (framed) added. • New fonts F6x8_ASCII and F6x8_1 added. • New fonts F8x8_ASCII and F8x8_1 added. • New fonts F8x16_ASCII and F8x16_1 added. • Support for new font formats extended AA2 and extended AA4 added. Chapter 'Memory Devices': • Considerations for multiple layers/displays added. Chapter 'Window Manager': • WM_DeleteWindow() now also deletes any associated timer. Chapter 'Widgets': • New function WINDOW_SetBkColor() added. Chapter 'Pointer Input Devices': • PID buffer added. • Explanation of touch calibration revised.

 © 2020 SEGGER Microcontroller GmbH

Software	Revision	Date	By	Description
				Chapter 'Keyboard': • Keyboard buffer added. Chapter 'Display Driver': • New driver GUIDRV_BitPlains added. • New driver GUIDRV_SLin added. • New driver GUIDRV_SSD1926 added. • Driver GUIDRV_1611 added. • Driver GUIDRV_6331 added. • Driver GUIDRV_7529 added. • Driver GUIDRV_Page1bpp added. • GUIDRV_CompactColor_16: • Support for the following display controllers added: • Himax HX8340, HX8352 • Solomon SSD1298, SSD1355, SSD1963 • Epson S1D19122 • Orisetech SPFD5414D • Ilitek ILI9320, ILI9326 Chapter 'VNC Server': • New function GUI_VNC_EnableKeyboardInput() • New function GUI_VNC_GetNumConnections() • New function GUI_VNC_SetPassword() • New function GUI_VNC_SetProgName() • New function GUI_VNC_SetSize() • New function GUI_VNC_RingBell()
5.00	1	090409	JE	Chapter 'Simulator': • Completely revised. Chapter 'Displaying bitmap files' • PNG support added.
5.00	0	090409	JE	Software has been completely revised. For the version history of earlier versions, refer to older documents.

 © 2020 SEGGER Microcontroller GmbH

About this document

Assumptions

This document assumes that you already have a solid knowledge of the following:

- The software tools used for building your application (assembler, linker, C compiler).
- The C programming language.
- The target processor.
- DOS command line.

If you feel that your knowledge of C is not sufficient, we recommend *C: A Reference Manual* by Harbison and Steele (ISBN 0--13--089592X). This book provides a complete description of the C language, the run-time libraries, and a style of C programming that emphasizes correctness, portability, and maintainability.

How to use this manual

This manual explains all the functions and macros that the product offers. It assumes you have a working knowledge of the C language. Knowledge of assembly programming is not required.

Typographic conventions for syntax

This manual uses the following typographic conventions:

Style	Used for
Body	Body text.
`Parameter`	Parameters in API functions.
`Sample`	Sample code in program examples.
`Sample comment`	Comments in program examples.
`User Input`	Text entered at the keyboard by a user in a session transcript.
`Secret Input`	Text entered at the keyboard by a user, but not echoed (e.g. password entry), in a session transcript.
Reference	Reference to chapters, sections, tables and figures.
Emphasis	Very important sections.
SEGGER home page	A hyperlink to an external document or web site.

 © 2020 SEGGER Microcontroller GmbH

 © 2020 SEGGER Microcontroller GmbH

Table of contents

1 Introduction to emWin 84

1.1 Purpose of this document 85
1.2 Requirements 86
1.2.1 Target system (hardware) 86
1.2.2 Development environment (compiler) 86
1.3 Features 87
1.4 Examples and demos 89
1.5 Starter kits 90
1.6 Screen and coordinates 91
1.7 How to connect the display to the microcontroller 92
1.8 Data types 93

2 Getting Started 94

2.1 Recommended project structure 95
2.2 Subdirectories 96
2.2.1 Include directories 96
2.3 Adding emWin to the target program 97
2.4 Creating a library 98
2.4.1 Adapting the library batch files to a different system 99
2.5 C files to include in the project 101
2.6 Configuring emWin 102
2.7 Initializing emWin 103
2.7.1 GUI_Init() 104
2.7.2 GUI_IsInitialized() 105
2.7.3 GUI_Exit() 106
2.8 Using emWin with target hardware 107
2.9 The "Hello world" example program 108

3 Simulation 109

3.1 Using the simulation 110
3.1.1 Rotating and mirroring the screen 110
3.1.2 Using the simulation with the trial version of emWin 110
3.1.2.1 Directory structure 110
3.1.2.2 Visual C++ workspace 111
3.1.2.3 Compiling the demo program 111
3.1.2.4 Compiling the samples 111
3.1.3 Using the simulation with the emWin source 112
3.1.3.1 Directory structure 112
3.1.3.2 Visual C++ workspace 113

 © 2020 SEGGER Microcontroller GmbH

3.1.3.3 Compiling the application ... 113
3.1.4 Advanced features of the simulation ... 114
3.1.4.1 Pause and Resume ... 114
3.1.4.2 View system info ... 114
3.1.4.3 Copy to clipboard ... 114
3.2 Device simulation ... 115
3.2.1 Generated frame view ... 115
3.2.2 Custom bitmap view ... 116
3.2.3 Window view ... 117
3.3 Device simulation API ... 118
3.3.1 Functions ... 120
3.3.1.1 SIM_GUI_Delay() ... 120
3.3.1.2 SIM_GUI_ExecIdle() ... 121
3.3.1.3 SIM_GUI_GetCompositeTouch() ... 122
3.3.1.4 SIM_GUI_GetTime() ... 123
3.3.1.5 SIM_GUI_SaveBMP() ... 124
3.3.1.6 SIM_GUI_SaveBMPEx() ... 125
3.3.1.7 SIM_GUI_SaveCompositeBMP() ... 126
3.3.1.8 SIM_GUI_SetCallback() ... 127
3.3.1.9 SIM_GUI_SetCompositeColor() ... 128
3.3.1.10 SIM_GUI_SetCompositeSize() ... 129
3.3.1.11 SIM_GUI_SetCompositeTouch() ... 130
3.3.1.12 SIM_GUI_SetLCDColorBlack() ... 131
3.3.1.13 SIM_GUI_SetLCDColorWhite() ... 131
3.3.1.14 SIM_GUI_SetLCDPos() ... 133
3.3.1.15 SIM_GUI_SetMag() ... 134
3.3.1.16 SIM_GUI_SetTransColor() ... 135
3.3.1.17 SIM_GUI_SetTransMode() ... 136
3.3.1.18 SIM_GUI_ShowDevice() ... 137
3.3.1.19 SIM_GUI_UseCustomBitmaps() ... 138
3.3.2 Data structures ... 139
3.3.2.1 SIM_GUI_INFO ... 139
3.3.3 Defines ... 140
3.3.3.1 Transparency modes ... 140
3.4 Hardkey simulation ... 141
3.4.1 Hardkey simulation API ... 141
3.4.1.1 SIM_HARDKEY_GetNum() ... 142
3.4.1.2 SIM_HARDKEY_GetState() ... 143
3.4.1.3 SIM_HARDKEY_SetCallback() ... 144
3.4.1.4 SIM_HARDKEY_SetMode() ... 145
3.4.1.5 SIM_HARDKEY_SetState() ... 146
3.5 Integrating the emWin simulation into an existing simulation ... 147
3.5.1 Directory structure ... 147
3.5.2 Using the simulation library ... 147
3.5.2.1 Modifying WinMain ... 147
3.5.2.2 Example application ... 148
3.5.3 Integration into the embOS Simulation ... 149
3.5.3.1 SIM_OS.c ... 149
3.5.3.2 Target program (main) ... 150
3.5.4 GUI simulation API ... 151
3.5.4.1 SIM_GUI_CreateLCDInfoWindow() ... 152
3.5.4.2 SIM_GUI_CreateLCDWindow() ... 153
3.5.4.3 SIM_GUI_Enable() ... 154
3.5.4.4 SIM_GUI_Exit() ... 155
3.5.4.5 SIM_GUI_Init() ... 156
3.5.4.6 SIM_GUI_SetLCDWindowHook() ... 157

4 Viewer ... 158
4.1 Using the viewer ... 159

 © 2020 SEGGER Microcontroller GmbH

4.1.1 Using the simulation and the viewer 159
4.1.2 Using the viewer with virtual pages 160
4.1.3 Always on top 160
4.1.4 Open further windows of the display output 160
4.1.5 Zooming 161
4.1.6 Copy the output to the clipboard 161
4.1.7 Using the viewer with multiple displays 161
4.1.8 Using the viewer with multiple layers 162

5 AppWizard 164

5.1 About the AppWizard 165
5.2 AppWizard API 166
5.2.1 APPW_GetFont() 167
5.2.2 APPW_GetVarData() 168
5.2.3 APPW_SetVarData() 169

6 emWinSPY 170

6.1 Introduction 171
6.1.1 Requirements 171
6.1.2 Availability 171
6.2 Starting the emWinSPY server... 172
6.2.1 ...in the simulation environment 172
6.2.2 ...on the target hardware 172
6.2.3 GUI_SPY_X_StartServer 172
6.3 The emWinSPY viewer 173
6.3.1 The screen 173
6.3.1.1 Status area 173
6.3.1.2 History area 174
6.3.1.3 Windows area 174
6.3.1.4 Input area 175
6.3.2 Connecting to target 175
6.3.3 Configuration options 176
6.3.4 Taking a screenshot from the target 177
6.4 emWinSPY API 178
6.4.1 GUI_SPY_Process() 179
6.4.2 GUI_SPY_SetMemHandler() 180
6.4.3 GUI_SPY_StartServer() 181
6.4.4 GUI_SPY_StartServerEx() 182
6.4.5 GUI_SPY_X_StartServer() 183

7 Displaying Text 184

7.1 Basic routines 185
7.2 Drawing modes 186
7.3 Position 188
7.4 Text API 189
7.4.1 Displaying text 191
7.4.1.1 GUI_DispCEOL() 191
7.4.1.2 GUI_DispChar() 192
7.4.1.3 GUI_DispCharAt() 193
7.4.1.4 GUI_DispChars() 194
7.4.1.5 GUI_DispString() 195
7.4.1.6 GUI_DispStringAt() 196
7.4.1.7 GUI_DispStringAtCEOL() 197
7.4.1.8 GUI_DispStringHCenterAt() 198
7.4.1.9 GUI_DispStringInRect() 199
7.4.1.10 GUI_DispStringInRectEx() 200
7.4.1.11 GUI_DispStringInRectWrap() 201
7.4.1.12 GUI_DispStringInRectWrapEx() 202

 © 2020 SEGGER Microcontroller GmbH

7.4.1.13 GUI_DispStringLen() 203
7.4.1.14 GUI_GetCharFromPos() 204
7.4.1.15 GUI_ShowMissingCharacters() 205
7.4.1.16 GUI_WrapGetNumLines() 206
7.4.2 Drawing modes 207
7.4.2.1 GUI_GetTextMode() 207
7.4.2.2 GUI_SetClearTextRectMode() 208
7.4.2.3 GUI_SetTextMode() 209
7.4.2.4 GUI_SetTextStyle() 210
7.4.3 Alignment 211
7.4.3.1 GUI_GetTextAlign() 211
7.4.3.2 GUI_SetLBorder() 212
7.4.3.3 GUI_SetTextAlign() 213
7.4.4 Position 214
7.4.4.1 GUI_DispNextLine() 214
7.4.4.2 GUI_GotoXY() 215
7.4.4.3 GUI_GotoX() 215
7.4.4.4 GUI_GotoY() 215
7.4.4.5 GUI_GetDispPosX() 216
7.4.4.6 GUI_GetDispPosY() 217
7.4.5 Defines 218
7.4.5.1 Text alignment flags 218
7.4.5.2 Text drawing modes 219
7.4.5.3 Text rotation modes 220
7.4.5.4 Text style flags 221
7.4.6 Enumerations 222
7.4.6.1 GUI_WRAPMODE 222

8 Displaying Values 223

8.1 Value API 224
8.1.1 Displaying decimal values 225
8.1.1.1 GUI_DispDec() 225
8.1.1.2 GUI_DispDecAt() 226
8.1.1.3 GUI_DispDecMin() 227
8.1.1.4 GUI_DispDecShift() 228
8.1.1.5 GUI_DispDecSpace() 229
8.1.1.6 GUI_DispSDec() 230
8.1.1.7 GUI_DispSDecShift() 231
8.1.2 Displaying floating point values 232
8.1.2.1 GUI_DispFloat() 232
8.1.2.2 GUI_DispFloatFix() 234
8.1.2.3 GUI_DispFloatMin() 235
8.1.2.4 GUI_DispSFloatFix() 236
8.1.2.5 GUI_DispSFloatMin() 237
8.1.3 Displaying binary values 238
8.1.3.1 GUI_DispBin() 238
8.1.3.2 GUI_DispBinAt() 239
8.1.4 Displaying hexadecimal values 240
8.1.4.1 GUI_DispHex() 240
8.1.4.2 GUI_DispHexAt() 241
8.1.5 GUI_GetVersionString() 242

9 2-D Graphic Library 243

9.1 Graphic API 244
9.1.1 Drawing related functions 251
9.1.1.1 GUI_AddRect() 251
9.1.1.2 GUI_GetClientRect() 252
9.1.1.3 GUI_GetClipRect() 253
9.1.1.4 GUI_GetDrawMode() 254

 © 2020 SEGGER Microcontroller GmbH

9.1.1.5 GUI_GetPenSize() 255
9.1.1.6 GUI_GetPixelIndex() 256
9.1.1.7 GUI_SetClipRect() 257
9.1.1.8 GUI_SetDrawMode() 258
9.1.1.9 GUI_SetPenSize() 259
9.1.2 Basic drawing routines 260
9.1.2.1 GUI_Clear() 260
9.1.2.2 GUI_ClearRect() 261
9.1.2.3 GUI_CopyRect() 262
9.1.2.4 GUI_DrawGradientH() 263
9.1.2.5 GUI_DrawGradientHEx() 264
9.1.2.6 GUI_DrawGradientV() 265
9.1.2.7 GUI_DrawGradientVEx() 266
9.1.2.8 GUI_DrawGradientRoundedH() 267
9.1.2.9 GUI_DrawGradientRoundedHEx() 268
9.1.2.10 GUI_DrawGradientRoundedV() 269
9.1.2.11 GUI_DrawGradientRoundedVEx() 270
9.1.2.12 GUI_DrawGradientMH() 271
9.1.2.13 GUI_DrawGradientMV() 271
9.1.2.14 GUI_DrawGradientMHEx() 272
9.1.2.15 GUI_DrawGradientMVEx() 272
9.1.2.16 GUI_DrawPixel() 273
9.1.2.17 GUI_DrawPoint() 274
9.1.2.18 GUI_DrawRect() 275
9.1.2.19 GUI_DrawRectEx() 276
9.1.2.20 GUI_DrawRoundedFrame() 277
9.1.2.21 GUI_DrawRoundedFrameEx() 278
9.1.2.22 GUI_DrawRoundedRect() 279
9.1.2.23 GUI_DrawRoundedRectEx() 280
9.1.2.24 GUI_FillRect() 281
9.1.2.25 GUI_FillRectEx() 282
9.1.2.26 GUI_FillRoundedRect() 283
9.1.2.27 GUI_FillRoundedRectEx() 284
9.1.2.28 GUI_InvertRect() 285
9.1.3 Alpha blending 286
9.1.3.1 GUI_EnableAlpha() 287
9.1.3.2 GUI_PreserveTrans() 288
9.1.3.3 GUI_RestoreUserAlpha() 289
9.1.3.4 GUI_SetAlpha() 290
9.1.3.5 GUI_SetUserAlpha() 291
9.1.4 Drawing bitmaps 292
9.1.4.1 GUI_DrawBitmap() 292
9.1.4.2 GUI_DrawBitmapEx() 293
9.1.4.3 GUI_DrawBitmapMag() 294
9.1.4.4 GUI_SetAlphaMask8888() 295
9.1.5 Drawing streamed bitmaps 296
9.1.5.1 GUI_CreateBitmapFromStream() 298
9.1.5.2 GUI_CreateBitmapFromStreamIDX() 299
9.1.5.3 GUI_CreateBitmapFromStreamRLE4() 299
9.1.5.4 GUI_CreateBitmapFromStreamRLE8() 299
9.1.5.5 GUI_CreateBitmapFromStream444_12() 299
9.1.5.6 GUI_CreateBitmapFromStream444_12_1() 299
9.1.5.7 GUI_CreateBitmapFromStreamM444_12() 299
9.1.5.8 GUI_CreateBitmapFromStreamM444_12_1() 299
9.1.5.9 GUI_CreateBitmapFromStream444_16() 299
9.1.5.10 GUI_CreateBitmapFromStreamM444_16() 299
9.1.5.11 GUI_CreateBitmapFromStreamA555() 299
9.1.5.12 GUI_CreateBitmapFromStreamAM555() 299
9.1.5.13 GUI_CreateBitmapFromStreamA565() 299
9.1.5.14 GUI_CreateBitmapFromStreamAM565() 299

 © 2020 SEGGER Microcontroller GmbH

9.1.5.15 GUI_CreateBitmapFromStream565() 299
9.1.5.16 GUI_CreateBitmapFromStreamM565() 299
9.1.5.17 GUI_CreateBitmapFromStream555() 299
9.1.5.18 GUI_CreateBitmapFromStreamM555() 299
9.1.5.19 GUI_CreateBitmapFromStreamRLE16() 299
9.1.5.20 GUI_CreateBitmapFromStreamRLEM16() 299
9.1.5.21 GUI_CreateBitmapFromStream24() 299
9.1.5.22 GUI_CreateBitmapFromStreamAlpha() 299
9.1.5.23 GUI_CreateBitmapFromStreamRLEAlpha() 299
9.1.5.24 GUI_CreateBitmapFromStreamRLE32() 299
9.1.5.25 GUI_DrawStreamedBitmap() 302
9.1.5.26 GUI_DrawStreamedBitmapAuto() 303
9.1.5.27 GUI_DrawStreamedBitmapEx() 304
9.1.5.28 GUI_DrawStreamedBitmapExAuto() 305
9.1.5.29 GUI_DrawStreamedBitmapA555Ex() 306
9.1.5.30 GUI_DrawStreamedBitmapAM555Ex() 306
9.1.5.31 GUI_DrawStreamedBitmapA565Ex() 306
9.1.5.32 GUI_DrawStreamedBitmapAM565Ex() 306
9.1.5.33 GUI_DrawStreamedBitmap555Ex() 306
9.1.5.34 GUI_DrawStreamedBitmapM555Ex() 306
9.1.5.35 GUI_DrawStreamedBitmap565Ex() 306
9.1.5.36 GUI_DrawStreamedBitmapM565Ex() 306
9.1.5.37 GUI_DrawStreamedBitmap24Ex() 306
9.1.5.38 GUI_GetStreamedBitmapInfo() 307
9.1.5.39 GUI_GetStreamedBitmapInfoEx() 308
9.1.5.40 GUI_SetStreamedBitmapHook() 309
9.1.6 Drawing lines 310
9.1.6.1 GUI_DrawHLine() 311
9.1.6.2 GUI_DrawLine() 312
9.1.6.3 GUI_DrawLineRel() 313
9.1.6.4 GUI_DrawLineTo() 314
9.1.6.5 GUI_DrawPolyLine() 315
9.1.6.6 GUI_DrawVLine() 316
9.1.6.7 GUI_GetLineStyle() 317
9.1.6.8 GUI_MoveRel() 318
9.1.6.9 GUI_MoveTo() 319
9.1.6.10 GUI_SetLineStyle() 320
9.1.7 Drawing polygons 321
9.1.7.1 GUI_DrawPolygon() 321
9.1.7.2 GUI_EnlargePolygon() 322
9.1.7.3 GUI_FillPolygon() 323
9.1.7.4 GUI_MagnifyPolygon() 324
9.1.7.5 GUI_RotatePolygon() 326
9.1.8 Drawing circles 328
9.1.8.1 GUI_DrawCircle() 328
9.1.8.2 GUI_FillCircle() 329
9.1.9 Drawing ellipses 330
9.1.9.1 GUI_DrawEllipse() 330
9.1.9.2 GUI_DrawEllipseXL() 331
9.1.9.3 GUI_FillEllipse() 332
9.1.10 Drawing arcs 333
9.1.10.1 GUI_DrawArc() 333
9.1.11 Drawing graphs 335
9.1.11.1 GUI_DrawGraph() 335
9.1.12 Drawing barcodes 336
9.1.12.1 GUI_BARCODE_Draw() 336
9.1.12.2 GUI_BARCODE_GetXSize() 338
9.1.13 Drawing QR codes 339
9.1.13.1 GUI_QR_Create() 339
9.1.13.2 GUI_QR_CreateFramed() 340

 © 2020 SEGGER Microcontroller GmbH

9.1.13.3 GUI_QR_Delete() 341
9.1.13.4 GUI_QR_Draw() 342
9.1.13.5 GUI_QR_GetInfo() 343
9.1.14 Drawing pie charts 344
9.1.14.1 GUI_DrawPie() 344
9.1.15 Drawing splines 345
9.1.15.1 GUI_SPLINE_Create() 345
9.1.15.2 GUI_SPLINE_Delete() 346
9.1.15.3 GUI_SPLINE_Draw() 347
9.1.15.4 GUI_SPLINE_DrawAA() 348
9.1.15.5 GUI_SPLINE_GetY() 349
9.1.15.6 GUI_SPLINE_GetXSize() 350
9.1.16 Saving and restoring the GUI context 351
9.1.16.1 GUI_RestoreContext() 351
9.1.16.2 GUI_SaveContext() 352
9.1.17 Info about screen changes 353
9.1.17.1 GUI_DIRTYDEVICE_Create() 353
9.1.17.2 GUI_DIRTYDEVICE_CreateEx() 354
9.1.17.3 GUI_DIRTYDEVICE_Delete() 355
9.1.17.4 GUI_DIRTYDEVICE_DeleteEx() 356
9.1.17.5 GUI_DIRTYDEVICE_Fetch() 357
9.1.17.6 GUI_DIRTYDEVICE_FetchEx() 358
9.1.18 YUV device 359
9.1.18.1 GUI_YUV_Create() 359
9.1.18.2 GUI_YUV_CreateEx() 360
9.1.18.3 GUI_YUV_Delete() 361
9.1.18.4 GUI_YUV_DeleteEx() 362
9.1.18.5 GUI_YUV_GetpData() 363
9.1.18.6 GUI_YUV_GetpDataEx() 364
9.1.18.7 GUI_YUV_InvalidateArea() 365
9.1.18.8 GUI_YUV_SetPeriod() 366
9.1.18.9 GUI_YUV_SetPeriodEx() 367
9.1.19 Cache with color reducer 368
9.1.19.1 GUI_GCACHE_4_Create() 368
9.1.19.2 GUI_GCACHE_4_CreateEx() 369
9.1.20 Setting hook functions 370
9.1.20.1 GUI_SetAfterInitHook() 370
9.1.20.2 GUI_SetControlHook() 371
9.1.20.3 GUI_SetRefreshHook() 372
9.1.21 Data structures 373
9.1.21.1 GUI_ALPHA_STATE 373
9.1.21.2 GUI_BITMAPSTREAM_INFO 374
9.1.21.3 GUI_BITMAPSTREAM_PARAM 375
9.1.21.4 GUI_DIRTYDEVICE_INFO 376
9.1.21.5 GUI_GRADIENT_INFO 377
9.1.21.6 GUI_POINT 378
9.1.21.7 GUI_QR_INFO 379
9.1.21.8 GUI_RECT 380
9.1.22 Defines 381
9.1.22.1 Barcode types 381
9.1.22.2 Drawing modes 382
9.1.22.3 ECC levels for QR codes 383
9.1.22.4 Line styles 384

10 Displaying bitmap files 385

10.1 BMP file support 386
10.1.1 Supported formats 386
10.1.2 BMP API 386
10.1.2.1 GUI_BMP_Draw() 387

 © 2020 SEGGER Microcontroller GmbH

10.1.2.2 GUI_BMP_DrawEx() 388
10.1.2.3 GUI_BMP_DrawScaled() 389
10.1.2.4 GUI_BMP_DrawScaledEx() 390
10.1.2.5 GUI_BMP_EnableAlpha() 391
10.1.2.6 GUI_BMP_GetXSize() 392
10.1.2.7 GUI_BMP_GetXSizeEx() 393
10.1.2.8 GUI_BMP_GetYSize() 394
10.1.2.9 GUI_BMP_GetYSizeEx() 395
10.1.2.10 GUI_BMP_Serialize() 396
10.1.2.11 GUI_BMP_SerializeEx() 397
10.1.2.12 GUI_BMP_SerializeExBpp() 398
10.2 JPEG file support 399
10.2.1 Supported JPEG compression methods 399
10.2.2 Converting a JPEG file to C source 399
10.2.3 Displaying JPEG files 399
10.2.4 Hardware support for decoding JPEG files 400
10.2.5 Memory usage 400
10.2.6 Progressive JPEG files 400
10.2.7 JPEG API 400
10.2.7.1 Functions 402
10.2.7.1.1 GUI_JPEG_Draw() 402
10.2.7.1.2 GUI_JPEG_DrawEx() 403
10.2.7.1.3 GUI_JPEG_DrawScaled() 404
10.2.7.1.4 GUI_JPEG_DrawScaledEx() 405
10.2.7.1.5 GUI_JPEG_GetInfo() 406
10.2.7.1.6 GUI_JPEG_GetInfoEx() 407
10.2.7.2 Data structures 408
10.2.7.2.1 GUI_JPEG_INFO 408
10.3 GIF file support 409
10.3.1 Converting a GIF file to C source 409
10.3.2 Displaying GIF files 409
10.3.3 Memory usage 409
10.3.4 GIF API 409
10.3.4.1 Functions 411
10.3.4.1.1 GUI_GIF_Draw() 411
10.3.4.1.2 GUI_GIF_DrawEx() 412
10.3.4.1.3 GUI_GIF_DrawSub() 413
10.3.4.1.4 GUI_GIF_DrawSubEx() 414
10.3.4.1.5 GUI_GIF_DrawSubScaled() 415
10.3.4.1.6 GUI_GIF_DrawSubScaledEx() 416
10.3.4.1.7 GUI_GIF_GetComment() 417
10.3.4.1.8 GUI_GIF_GetCommentEx() 418
10.3.4.1.9 GUI_GIF_GetImageInfo() 419
10.3.4.1.10 GUI_GIF_GetImageInfoEx() 420
10.3.4.1.11 GUI_GIF_GetInfo() 421
10.3.4.1.12 GUI_GIF_GetInfoEx() 422
10.3.4.1.13 GUI_GIF_GetXSize() 423
10.3.4.1.14 GUI_GIF_GetXSizeEx() 424
10.3.4.1.15 GUI_GIF_GetYSize() 425
10.3.4.1.16 GUI_GIF_GetYSizeEx() 426
10.3.4.2 Data structures 427
10.3.4.2.1 GUI_GIF_IMAGE_INFO 427
10.3.4.2.2 GUI_GIF_INFO 428
10.4 PNG file support 429
10.4.1 Converting a PNG file to C source 429
10.4.2 Displaying PNG files 429
10.4.3 Memory usage 429
10.4.4 PNG API 429
10.4.4.1 GUI_PNG_Draw() 430
10.4.4.2 GUI_PNG_DrawEx() 431

 © 2020 SEGGER Microcontroller GmbH

10.4.4.3 GUI_PNG_GetXSize() ... 432
10.4.4.4 GUI_PNG_GetXSizeEx() ... 433
10.4.4.5 GUI_PNG_GetYSize() ... 434
10.4.4.6 GUI_PNG_GetYSizeEx() ... 435
10.5 Getting data with the ...Ex() functions ... 436

11 Bitmap Converter ... 438

11.1 What it does ... 439
11.2 Loading a bitmap ... 440
11.2.1 Supported input file formats ... 440
11.2.2 Loading from a file ... 440
11.2.3 Using the clipboard ... 440
11.3 Color conversion ... 441
11.4 Dithering ... 442
11.5 Using a custom palette ... 443
11.5.1 Saving a palette file ... 443
11.5.2 Palette file format ... 443
11.5.3 Palette files for fixed palette modes ... 443
11.5.4 Converting a bitmap ... 444
11.6 Generating C files from bitmaps ... 445
11.6.1 Supported bitmap formats ... 445
11.6.2 Palette information ... 446
11.6.3 Transparency ... 446
11.6.4 Alpha blending ... 446
11.6.5 Selecting the best format ... 448
11.6.6 Saving the file ... 448
11.7 Generating C stream files ... 451
11.8 Compressed bitmaps ... 453
11.9 Creating animated sprites / cursors ... 454
11.9.1 Animated Sprite example ... 454
11.9.2 Animated Cursor example ... 455
11.9.3 Additional information ... 456
11.10 Command line usage ... 457
11.10.1 Format for commands ... 457
11.10.2 Command line options ... 457
11.11 Options ... 460
11.12 Example of a converted bitmap ... 461

12 Fonts ... 463

12.1 Introduction ... 464
12.2 Font types ... 465
12.3 Font formats ... 467
12.3.1 C file format ... 467
12.3.2 System Independent Font (SIF) format ... 467
12.3.3 External Bitmap Font (XBF) format ... 467
12.3.4 iType and iTypeSpark font engine support ... 469
12.3.5 TrueType Font (TTF) format ... 470
12.4 Converting a TTF file to C source ... 471
12.5 Declaring custom fonts ... 472
12.6 Selecting a font ... 473
12.7 Font API ... 474
12.7.1 SIF file related font functions ... 476
12.7.1.1 GUI_SIF_CreateFont() ... 476
12.7.1.2 GUI_SIF_DeleteFont() ... 477
12.7.2 TTF file related functions ... 478
12.7.2.1 GUI_TTF_CreateFont() ... 478
12.7.2.2 GUI_TTF_CreateFontAA() ... 480
12.7.2.3 GUI_TTF_DestroyCache() ... 481
12.7.2.4 GUI_TTF_Done() ... 482

 © 2020 SEGGER Microcontroller GmbH

12.7.2.5 GUI_TTF_GetFamilyName() 483
12.7.2.6 GUI_TTF_GetStyleName() 484
12.7.2.7 GUI_TTF_SetCacheSize() 485
12.7.3 XBF file related font functions 486
12.7.3.1 GUI_XBF_CreateFont() 486
12.7.3.2 GUI_XBF_DeleteFont() 488
12.7.3.3 GUI_GetCharDistX() 489
12.7.3.4 GUI_GetDefaultFont() 490
12.7.3.5 GUI_GetFont() 491
12.7.3.6 GUI_GetFontDistY() 492
12.7.3.7 GUI_GetFontInfo() 493
12.7.3.8 GUI_GetFontSizeY() 494
12.7.3.9 GUI_GetLeadingBlankCols() 495
12.7.3.10 GUI_GetStringDistX() 496
12.7.3.11 GUI_GetStringDistXEx() 497
12.7.3.12 GUI_GetTextExtend() 498
12.7.3.13 GUI_GetTrailingBlankCols() 499
12.7.3.14 GUI_GetYDistOfFont() 500
12.7.3.15 GUI_GetYSizeOfFont() 501
12.7.3.16 GUI_IsInFont() 502
12.7.3.17 GUI_SetDefaultFont() 503
12.7.3.18 GUI_SetFont() 504
12.7.4 Data structures 505
12.7.4.1 GUI_FONTINFO 505
12.7.4.2 GUI_TTF_CS 506
12.7.4.3 GUI_TTF_DATA 507
12.7.5 Defines 508
12.7.5.1 Font info flags 508
12.7.5.2 SIF font types 509
12.7.5.3 XBF font types 510
12.8 Character sets 511
12.8.1 ASCII 511
12.8.2 ISO 8859-1 Western Latin character set 511
12.8.3 Unicode 513
12.9 Standard fonts 514
12.9.1 Font identifier naming convention 514
12.9.2 Font file naming convention 515
12.9.3 Measurement, ROM-size and character set of fonts 515
12.9.4 Proportional fonts 515
12.9.4.1 Overview 515
12.9.4.2 Font details 516
12.9.4.3 Characters 518
12.9.5 Proportional fonts, framed 524
12.9.5.1 Overview 524
12.9.5.2 Font details 524
12.9.5.3 Characters 524
12.9.6 Monospaced fonts 524
12.9.6.1 Overview 524
12.9.6.2 Font details 525
12.9.6.3 Characters 525
12.9.7 Digit fonts (proportional) 529
12.9.7.1 Overview 529
12.9.7.2 Font details 530
12.9.7.3 Characters 530
12.9.8 Digit fonts (monospaced) 531
12.9.8.1 Overview 531
12.9.8.2 Font details 532
12.9.8.3 Characters 532

 © 2020 SEGGER Microcontroller GmbH

13 Font Converter 534
13.1 Requirements 535
13.2 Creating an emWin font file from a Windows font 536
13.3 Font generation options dialog 539
13.3.1 Type of font to generate 539
13.3.2 Encoding 539
13.3.3 Antialiasing 540
13.4 Font Dialog 541
13.4.1 Font, Font Style, and Size 541
13.4.2 Script 541
13.4.3 Unit of Size 541
13.5 User Interface 542
13.5.1 Selecting the current character 542
13.5.2 Toggling character status 542
13.5.3 Selecting pixels 542
13.5.4 Modifying character bits 543
13.5.5 Operations 543
13.5.5.1 Modifying the viewing mode 545
13.6 Options 546
13.7 Saving the font 548
13.7.1 Creating a C file 548
13.7.2 Creating a System Independent Font (SIF) 548
13.7.3 Creating an External Binary Font (XBF) 548
13.8 Loading and modifying a C font file 549
13.9 Loading Glyph (B)itmap (D)istribution (F)ormat 550
13.10 Merging fonts with existing C font files 551
13.11 Pattern files 553
13.11.1 Creating pattern files using Notepad 553
13.11.2 Creating pattern files using the Font Converter 553
13.11.3 Enabling characters using a pattern file 553
13.12 Command line options 554
13.12.1 Table of commands 554
13.12.2 Load an existing font file 555
13.12.3 Execution examples 555
13.13 Font Examples 556
13.13.1 Resulting C code, standard mode 556
13.13.2 Resulting C code, 2 bpp anti-aliased mode 557
13.13.3 Resulting C code, 4 bpp anti-aliased mode 558
13.13.4 Resulting C code, extended mode 559
13.14 Troubleshooting 561

14 Movies 562
14.1 Introduction 563
14.2 Requirements 564
14.3 Creating JPEG files with FFmpeg.exe 565
14.4 Creating an EMF file 566
14.5 Creating an AVI file 568
14.6 Modifying the conversion result 569
14.7 Using JPEG2Movie 570
14.8 emWin Movie Player 571
14.9 Movies API 572
14.9.1 Functions 573
14.9.1.1 GUI_MOVIE_Create() 573
14.9.1.2 GUI_MOVIE_CreateEx() 574
14.9.1.3 GUI_MOVIE_Delete() 575
14.9.1.4 GUI_MOVIE_DrawFrame() 576
14.9.1.5 GUI_MOVIE_GetFrameIndex() 577
14.9.1.6 GUI_MOVIE_GetInfo() 578
14.9.1.7 GUI_MOVIE_GetInfoEx() 579

 © 2020 SEGGER Microcontroller GmbH

14.9.1.8 GUI_MOVIE_GetInfoH() 580
14.9.1.9 GUI_MOVIE_GetNumFrames() 581
14.9.1.10 GUI_MOVIE_GetPos() 582
14.9.1.11 GUI_MOVIE_GotoFrame() 583
14.9.1.12 GUI_MOVIE_Pause() 584
14.9.1.13 GUI_MOVIE_Play() 585
14.9.1.14 GUI_MOVIE_SetPeriod() 586
14.9.1.15 GUI_MOVIE_SetpfNotify() 587
14.9.1.16 GUI_MOVIE_SetPos() 588
14.9.1.17 GUI_MOVIE_Show() 589
14.9.2 Data structures 590
14.9.2.1 GUI_MOVIE_INFO 590
14.9.3 Defines 591
14.9.3.1 Movie notifications 591

15 Animations 592

15.1 Introduction 593
15.2 Creating an animation object 594
15.3 Adding items to an animation 595
15.4 Position calculation 596
15.4.1 Custom defined position calculation 597
15.5 Executing an animation 598
15.5.1 Using a slice callback function 598
15.5.2 Animation item 598
15.5.3 Using a delete callback function 599
15.6 Animations API 600
15.6.1 Functions 601
15.6.1.1 GUI_ANIM_AddItem() 601
15.6.1.2 GUI_ANIM_Create() 602
15.6.1.3 GUI_ANIM_Delete() 603
15.6.1.4 GUI_ANIM_DeleteAll() 604
15.6.1.5 GUI_ANIM_Exec() 605
15.6.1.6 GUI_ANIM_GetData() 606
15.6.1.7 GUI_ANIM_GetFirst() 607
15.6.1.8 GUI_ANIM_GetItemData() 608
15.6.1.9 GUI_ANIM_GetNext() 609
15.6.1.10 GUI_ANIM_GetNumItems() 610
15.6.1.11 GUI_ANIM_IsRunning() 611
15.6.1.12 GUI_ANIM_Start() 612
15.6.1.13 GUI_ANIM_StartEx() 613
15.6.1.14 GUI_ANIM_Stop() 614
15.6.2 Data structures 615
15.6.2.1 GUI_ANIM_INFO 615
15.6.3 Defines 616
15.6.3.1 Animation states 616

16 Colors 617

16.1 Color management 618
16.2 Logical colors 619
16.3 Switching to ARGB 620
16.3.1 Configuration 620
16.3.2 Required changes in existing applications 620
16.3.3 Configuring the BitmapConverter 621
16.4 Predefined colors 622
16.5 The color bar test routine 623
16.6 Fixed palette modes 624
16.7 Detailed fixed palette mode description 626
16.7.1 GUICC_1: 1 bpp (black and white) 626
16.7.2 GUICC_2: 2 bpp (4 grayscales) 626

 © 2020 SEGGER Microcontroller GmbH

16.7.3 GUICC_4: 4 bpp (16 grayscales) 626
16.7.4 GUICC_5: 5 bpp (32 grayscales) 626
16.7.5 GUICC_111: 3 bpp (2 levels per color) 627
16.7.6 GUICC_M111: 3 bpp (2 levels per color), red and blue swapped 627
16.7.7 GUICC_16: 4 bpp (16 colors) 627
16.7.8 GUICC_1616I: 8 bpp (16 colors + 4 bits alpha mask) 627
16.7.9 GUICC_222: 6 bpp (4 levels per color) 628
16.7.10 GUICC_M222: 6 bpp (4 levels per color), red and blue swapped 628
16.7.11 GUICC_8: 8 bpp (256 grayscales) 628
16.7.12 GUICC_233: 8 bpp 629
16.7.13 GUICC_M233: 8 bpp, red and blue swapped 629
16.7.14 GUICC_323: 8 bpp 630
16.7.15 GUICC_M323: 8 bpp, red and blue swapped 630
16.7.16 GUICC_332: 8 bpp 631
16.7.17 GUICC_M332: 8 bpp, red and blue swapped 631
16.7.18 GUICC_444_12: 632
16.7.19 GUICC_444_16: 632
16.7.20 GUICC_M444_12: red and blue swapped 632
16.7.21 GUICC_M444_16: red and blue swapped 633
16.7.22 GUICC_M444_12_1: 633
16.7.23 GUICC_M4444I: 12 bits colors + 4 bits alpha mask 633
16.7.24 GUICC_555: 15 bpp 634
16.7.25 GUICC_M555: 15 bpp, red and blue swapped 634
16.7.26 GUICC_M1555I: 15 bits colors + 1 bit transparency 634
16.7.27 GUICC_565: 16 bpp 634
16.7.28 GUICC_M565: 16 bpp, red and blue swapped 635
16.7.29 GUICC_666: 18 bpp 635
16.7.30 GUICC_M666: 18 bpp, red and blue swapped 635
16.7.31 GUICC_666_9: 18 bpp 635
16.7.32 GUICC_M666_9: 18 bpp, red and blue swapped 635
16.7.33 GUICC_822216: 8 bpp, 2 levels per color + 8 grayscales + 16 levels of alpha blending 636
16.7.34 GUICC_84444: 8 bpp, 4 levels per color + 16 grayscales + 4(3) levels of alpha blending 636
16.7.35 GUICC_8666: 8bpp, 6 levels per color + 16 grayscales 637
16.7.36 GUICC_8666_1: 8bpp, 6 levels per color + 16 grayscales + transparency 637
16.7.37 GUICC_88666I: 16bpp - 8 bits color (6 levels per color + 16 grayscales) + 8 bits alpha blending 638
16.7.38 GUICC_888: 24 bpp 638
16.7.39 GUICC_M888: 24 bpp, red and blue swapped 638
16.7.40 GUICC_8888: 32 bpp 639
16.7.41 GUICC_M8888: 32 bpp, red and blue swapped 639
16.7.42 GUICC_M8888I: 32 bpp, red and blue swapped 639
16.7.43 GUICC_0: Custom palette mode 640
16.7.44 GUICC_1_2, GUICC_1_4, ... GUICC_1_24 640
16.8 Application defined color conversion 641
16.9 Custom palette mode 642
16.9.1 Look-up table API 642
16.9.1.1 LCD_SetLUT() 643
16.9.1.2 LCD_SetLUTEx() 644
16.9.1.3 LCD_SetLUTEntryEx() 645
16.10 Gamma correction 646
16.11 Color API 647
16.11.1 Basic functions 648
16.11.1.1 GUI_GetBkColor() 648
16.11.1.2 GUI_GetBkColorIndex() 649
16.11.1.3 GUI_GetColor() 650
16.11.1.4 GUI_GetColorIndex() 651
16.11.1.5 GUI_GetDefaultColor() 652

 © 2020 SEGGER Microcontroller GmbH

16.11.1.6 GUI_GetDefaultBkColor() 653
16.11.1.7 GUI_SetBkColor() 654
16.11.1.8 GUI_SetBkColorIndex() 655
16.11.1.9 GUI_SetColor() 656
16.11.1.10 GUI_SetColorIndex() 657
16.11.1.11 GUI_SetDefaultColor() 658
16.11.1.12 GUI_SetDefaultBkColor() 659
16.11.2 Conversion functions 660
16.11.2.1 GUI_CalcColorDist() 660
16.11.2.2 GUI_CalcVisColorError() 661
16.11.2.3 GUI_Color2Index() 662
16.11.2.4 GUI_Color2VisColor() 663
16.11.2.5 GUI_ColorIsAvailable() 664
16.11.2.6 GUI_Index2Color() 665

17 Memory Devices 666

17.1 Using Memory Devices: Illustration 667
17.2 Supported color depth (bpp) 668
17.3 Memory Devices and the Window Manager 669
17.4 Memory Devices and multiple layers 670
17.5 Memory requirements 671
17.6 Performance 672
17.7 Basic functions 673
17.8 In order to be able to use Memory Devices... 674
17.9 MultiLayer / MultiDisplay configuration 675
17.10 Configuration options 676
17.11 Memory Device API 677
17.11.1 Basic functions 681
17.11.1.1 GUI_MEMDEV_Clear() 681
17.11.1.2 GUI_MEMDEV_ClearAlpha() 682
17.11.1.3 GUI_MEMDEV_CopyFromLCD() 684
17.11.1.4 GUI_MEMDEV_CopyToLCD() 685
17.11.1.5 GUI_MEMDEV_CopyToLCDAA() 686
17.11.1.6 GUI_MEMDEV_CopyToLCDAt() 687
17.11.1.7 GUI_MEMDEV_Create() 688
17.11.1.8 GUI_MEMDEV_CreateCopy() 689
17.11.1.9 GUI_MEMDEV_CreateEx() 690
17.11.1.10 GUI_MEMDEV_CreateFixed() 691
17.11.1.11 GUI_MEMDEV_CreateFixed32() 692
17.11.1.12 GUI_MEMDEV_Delete() 693
17.11.1.13 GUI_MEMDEV_DrawPerspectiveX() 694
17.11.1.14 GUI_MEMDEV_GetDataPtr() 696
17.11.1.15 GUI_MEMDEV_GetXSize() 697
17.11.1.16 GUI_MEMDEV_GetYSize() 698
17.11.1.17 GUI_MEMDEV_MarkDirty() 699
17.11.1.18 GUI_MEMDEV_PunchOutDevice() 700
17.11.1.19 GUI_MEMDEV_ReduceYSize() 702
17.11.1.20 GUI_MEMDEV_Rotate() 703
17.11.1.21 GUI_MEMDEV_RotateAlpha() 703
17.11.1.22 GUI_MEMDEV_RotateHQ() 703
17.11.1.23 GUI_MEMDEV_RotateHQAlpha() 703
17.11.1.24 GUI_MEMDEV_RotateHQHR() 703
17.11.1.25 GUI_MEMDEV_RotateHQT() 703
17.11.1.26 GUI_MEMDEV_RotateHR() 703
17.11.1.27 GUI_MEMDEV_Select() 708
17.11.1.28 GUI_MEMDEV_SerializeBMP() 709
17.11.1.29 GUI_MEMDEV_SetOrg() 710
17.11.1.30 GUI_MEMDEV_Write() 711
17.11.1.31 GUI_MEMDEV_WriteAlpha() 712

 © 2020 SEGGER Microcontroller GmbH

17.11.1.32 GUI_MEMDEV_WriteAlphaAt() 713
17.11.1.33 GUI_MEMDEV_WriteAt() 714
17.11.1.34 GUI_MEMDEV_WriteEx() 715
17.11.1.35 GUI_MEMDEV_WriteExAt() 716
17.11.1.36 GUI_MEMDEV_WriteOpaque() 717
17.11.1.37 GUI_MEMDEV_WriteOpaqueAt() 718
17.11.1.38 GUI_SelectLCD() 719
17.11.2 Example for using a Memory Device 720
17.11.3 Banding Memory Device 721
17.11.3.1 GUI_MEMDEV_Draw() 721
17.11.3.2 Example for using a banding Memory Device 722
17.11.4 Auto device object functions 723
17.11.4.1 GUI_MEMDEV_CreateAuto() 723
17.11.4.2 GUI_MEMDEV_DeleteAuto() 724
17.11.4.3 GUI_MEMDEV_DrawAuto() 725
17.11.4.4 Example for using an auto device object 726
17.11.5 Measurement device object functions 727
17.11.5.1 GUI_MEASDEV_ClearRect() 727
17.11.5.2 GUI_MEASDEV_Create() 728
17.11.5.3 GUI_MEASDEV_Delete() 729
17.11.5.4 GUI_MEASDEV_GetRect() 730
17.11.5.5 GUI_MEASDEV_Select() 731
17.11.6 Animation functions 732
17.11.6.1 GUI_MEMDEV_FadeInDevices() 732
17.11.6.2 GUI_MEMDEV_FadeOutDevices() 733
17.11.6.3 GUI_MEMDEV_SetAnimationCallback() 734
17.11.6.4 GUI_MEMDEV_SetTimePerFrame() 735
17.11.7 Animation functions (Window Manager required) 736
17.11.7.1 GUI_MEMDEV_FadeInWindow() 736
17.11.7.2 GUI_MEMDEV_FadeOutWindow() 736
17.11.7.3 GUI_MEMDEV_MoveInWindow() 737
17.11.7.4 GUI_MEMDEV_MoveOutWindow() 737
17.11.7.5 GUI_MEMDEV_ShiftInWindow() 739
17.11.7.6 GUI_MEMDEV_ShiftOutWindow() 739
17.11.7.7 GUI_MEMDEV_SwapWindow() 740
17.11.8 Blending, Blurring and Dithering functions 741
17.11.8.1 GUI_MEMDEV_BlendColor32() 741
17.11.8.2 GUI_MEMDEV_CreateBlurredDevice32() 742
17.11.8.3 GUI_MEMDEV_CreateBlurredDevice32HQ() 744
17.11.8.4 GUI_MEMDEV_CreateBlurredDevice32LQ() 745
17.11.8.5 GUI_MEMDEV_Dither32() 746
17.11.8.6 GUI_MEMDEV_SetBlurHQ() 747
17.11.8.7 GUI_MEMDEV_SetBlurLQ() 748
17.11.9 Blending and Blurring functions (Window Manager required) 749
17.11.9.1 GUI_MEMDEV_BlendWinBk() 749
17.11.9.2 GUI_MEMDEV_BlurAndBlendWinBk() 750
17.11.9.3 GUI_MEMDEV_BlurWinBk() 751
17.11.10 Setting up multiple buffering for animation functions 752
17.11.10.1 GUI_MEMDEV_MULTIBUF_Enable() 752
17.11.11 Defines 753
17.11.11.1 Color conversion routines 753
17.11.11.2 Direction symbols 754
17.11.11.3 Memory device color depths 755
17.11.11.4 Memory device flags 756

18 Execution Model: Single Task / Multitask 757

18.1 Supported execution models 758
18.2 Single task system (super loop) 759
18.2.1 Description 759

 © 2020 SEGGER Microcontroller GmbH

18.2.2 Superloop example (without emWin) 759
18.2.3 Advantages 759
18.2.4 Disadvantages 759
18.2.5 Using emWin 759
18.2.6 Superloop example (with emWin) 759
18.3 Multitask system: one task calling emWin 761
18.3.1 Description 761
18.3.2 Advantages 761
18.3.3 Using emWin 761
18.4 Multitask system: multiple tasks calling emWin 762
18.4.1 Description 762
18.4.2 Advantages 762
18.4.3 Using emWin 762
18.4.4 Recommendations 762
18.4.5 Example 762
18.5 Configuration functions for multitasking support 764
18.5.1 GUI_SetSignalEventFunc() 765
18.5.2 GUI_SetWaitEventFunc() 766
18.5.3 GUI_SetWaitEventTimedFunc() 767
18.5.4 GUI_WaitEvent() 768
18.6 Configuration macros for multitasking support 769
18.6.1 GUI_MAXTASK 769
18.6.2 GUI_OS 769
18.6.3 GUI_X_SIGNAL_EVENT 769
18.6.4 GUI_X_WAIT_EVENT 770
18.6.5 GUI_X_WAIT_EVENT_TIMED 770
18.7 Kernel interface API 771
18.7.1 GUI_X_GetTaskId() 772
18.7.2 GUI_X_InitOS() 773
18.7.3 GUI_X_Lock() 774
18.7.4 GUI_X_SignalEvent() 775
18.7.5 GUI_X_Unlock() 776
18.7.6 GUI_X_WaitEvent() 777
18.7.7 GUI_X_WaitEventTimed() 778
18.8 Examples 779

19 The Window Manager (WM) 781

19.1 Description of terms 782
19.2 Callback mechanism, invalidation, rendering and keyboard input 785
19.2.1 Rendering using callbacks 785
19.2.2 Overwriting callback functions 786
19.2.3 Background window redrawing and callback 787
19.2.4 Invalidation 787
19.2.5 Tiling mechanism 787
19.2.6 Rendering of transparent windows 789
19.2.7 Automatic use of Memory Devices 789
19.2.8 Automatic use of multiple frame buffers 789
19.2.9 Automatic use of display driver cache 789
19.2.10 Keyboard input 789
19.3 Motion support 790
19.3.1 Enabling motion support of the WM 790
19.3.2 Basic motion support for a window 790
19.3.2.1 Using creation flags 790
19.3.2.2 Using API function 790
19.3.3 Motion processing by application 790
19.3.3.1 WM_MOTION message and WM_MOTION_INFO 791
19.3.4 Motion support for circular moves 792
19.4 Window manager and multiple layers 793
19.4.1 Drawing operations 793

 © 2020 SEGGER Microcontroller GmbH

19.4.2 Window relationship 793
19.4.3 Semi-Transparency 793
19.4.4 Touch input 793
19.4.5 Memory devices 793
19.5 ToolTips 794
19.5.1 How they work 794
19.5.2 Creating ToolTips 794
19.5.2.1 Creating ToolTips for dialog items 794
19.5.2.2 Creating ToolTips for simple windows 795
19.6 Messages 796
19.6.1 Message structure 796
19.6.2 List of messages 796
19.6.3 System-defined messages 796
19.6.3.1 WM_CREATE 796
19.6.3.2 WM_DELETE 796
19.6.3.3 WM_GET_ID 796
19.6.3.4 WM_GET_INSIDE_RECT 797
19.6.3.5 WM_INIT_DIALOG 797
19.6.3.6 WM_KEY 797
19.6.3.7 WM_MOVE 797
19.6.3.8 WM_NOTIFY_PARENT 797
19.6.3.9 WM_NOTIFY_VIS_CHANGED 798
19.6.3.10 WM_PAINT 798
19.6.3.11 WM_POST_PAINT 798
19.6.3.12 WM_PRE_PAINT 799
19.6.3.13 WM_SET_CALLBACK 799
19.6.3.14 WM_SET_FOCUS 799
19.6.3.15 WM_SET_ID 799
19.6.3.16 WM_SIZE 799
19.6.3.17 WM_TIMER 799
19.6.3.18 WM_USER_DATA 800
19.6.4 Pointer input device (PID) messages 800
19.6.4.1 WM_MOTION 800
19.6.4.2 WM_MOUSEOVER 800
19.6.4.3 WM_MOUSEOVER_END 800
19.6.4.4 WM_PID_STATE_CHANGED 801
19.6.4.5 WM_TOUCH 801
19.6.4.6 WM_TOUCH_CHILD 801
19.6.4.7 Example 801
19.6.5 System-defined notification codes 802
19.6.6 Application-defined messages 802
19.7 Configuration options 804
19.7.1 WM_SUPPORT_NOTIFY_VIS_CHANGED 804
19.7.2 WM_SUPPORT_TRANSPARENCY 804
19.8 WM API 805
19.8.1 Using the WM API functions 810
19.8.2 Basic functions 811
19.8.2.1 WM_Activate() 811
19.8.2.2 WM_AttachWindow() 812
19.8.2.3 WM_AttachWindowAt() 813
19.8.2.4 WM_BringToBottom() 814
19.8.2.5 WM_BringToTop() 815
19.8.2.6 WM_BroadcastMessage() 816
19.8.2.7 WM_ClrHasTrans() 817
19.8.2.8 WM_CreateWindow() 818
19.8.2.9 WM_CreateWindowAsChild() 819
19.8.2.10 WM_Deactivate() 820
19.8.2.11 WM_DefaultProc() 821
19.8.2.12 WM_DeleteWindow() 822
19.8.2.13 WM_DetachWindow() 823

 © 2020 SEGGER Microcontroller GmbH

19.8.2.14 WM_DisableWindow() 824
19.8.2.15 WM_EnableWindow() 825
19.8.2.16 WM_Exec() 826
19.8.2.17 WM_Exec1() 827
19.8.2.18 WM_ForEachDesc() 828
19.8.2.19 WM_GetActiveWindow() 830
19.8.2.20 WM_GetCallback() 831
19.8.2.21 WM_GetClientRect() 832
19.8.2.22 WM_GetClientRectEx() 833
19.8.2.23 WM_GetDesktopWindow() 834
19.8.2.24 WM_GetDesktopWindowEx() 835
19.8.2.25 WM_GetDialogItem() 836
19.8.2.26 WM_GetFirstChild() 837
19.8.2.27 WM_GetFocusedWindow() 838
19.8.2.28 WM_GetHasTrans() 839
19.8.2.29 WM_GetInvalidRect() 840
19.8.2.30 WM_GetModalLayer() 841
19.8.2.31 WM_GetModalWindow() 842
19.8.2.32 WM_GetNextSibling() 843
19.8.2.33 WM_GetNumInvalidWindows() 844
19.8.2.34 WM_GetOrgX() 845
19.8.2.35 WM_GetOrgY() 845
19.8.2.36 WM_GetParent() 846
19.8.2.37 WM_GetPrevSibling() 847
19.8.2.38 WM_GetStayOnTop() 848
19.8.2.39 WM_GetUserData() 849
19.8.2.40 WM_GetWindowOrgX() 850
19.8.2.41 WM_GetWindowOrgY() 850
19.8.2.42 WM_GetWindowRect() 851
19.8.2.43 WM_GetWindowRectEx() 852
19.8.2.44 WM_GetWindowSizeX() 853
19.8.2.45 WM_GetWindowSizeY() 853
19.8.2.46 WM_HasCaptured() 854
19.8.2.47 WM_HasFocus() 855
19.8.2.48 WM_HideWindow() 856
19.8.2.49 WM_InvalidateArea() 857
19.8.2.50 WM_InvalidateRect() 858
19.8.2.51 WM_InvalidateWindow() 859
19.8.2.52 WM_IsCompletelyCovered() 860
19.8.2.53 WM_IsCompletelyVisible() 861
19.8.2.54 WM_IsEnabled() 862
19.8.2.55 WM_IsVisible() 863
19.8.2.56 WM_IsWindow() 864
19.8.2.57 WM_MakeModal() 865
19.8.2.58 WM_MoveChildTo() 866
19.8.2.59 WM_MoveTo() 867
19.8.2.60 WM_MoveWindow() 868
19.8.2.61 WM_NotifyParent() 869
19.8.2.62 WM_Paint() 870
19.8.2.63 WM_PaintWindowAndDescs() 871
19.8.2.64 WM_Rect2Client() 872
19.8.2.65 WM_Rect2Screen() 873
19.8.2.66 WM_ReleaseCapture() 874
19.8.2.67 WM_ResizeWindow() 875
19.8.2.68 WM_Screen2hWin() 876
19.8.2.69 WM_Screen2hWinEx() 877
19.8.2.70 WM_SelectWindow() 878
19.8.2.71 WM_SendMessage() 879
19.8.2.72 WM_SendMessageNoPara() 880
19.8.2.73 WM_SendToParent() 881

 © 2020 SEGGER Microcontroller GmbH

19.8.2.74 WM_SetCallback() 882
19.8.2.75 WM_SetCapture() 883
19.8.2.76 WM_SetCaptureMove() 884
19.8.2.77 WM_SetCreateFlags() 885
19.8.2.78 WM_SetDesktopColor() 886
19.8.2.79 WM_SetDesktopColorEx() 887
19.8.2.80 WM_SetEnableState() 888
19.8.2.81 WM_SetFocus() 889
19.8.2.82 WM_SetHasTrans() 890
19.8.2.83 WM_SetId() 891
19.8.2.84 WM_SetModalLayer() 892
19.8.2.85 WM_SetpfPollPID() 893
19.8.2.86 WM_SetSize() 894
19.8.2.87 WM_SetUntouchable() 895
19.8.2.88 WM_SetWindowPos() 896
19.8.2.89 WM_SetXSize() 897
19.8.2.90 WM_SetYSize() 898
19.8.2.91 WM_SetStayOnTop() 899
19.8.2.92 WM_SetTransState() 900
19.8.2.93 WM_SetUserClipRect() 901
19.8.2.94 WM_SetUserData() 902
19.8.2.95 WM_ShowWindow() 903
19.8.2.96 WM_Update() 904
19.8.2.97 WM_UpdateWindowAndDescs() 905
19.8.2.98 WM_ValidateRect() 906
19.8.2.99 WM_ValidateWindow() 907
19.8.2.100 WM_XY2Screen() 908
19.8.2.101 WM_XY2Client() 909
19.8.3 Motion support 910
19.8.3.1 WM_MOTION_Enable() 910
19.8.3.2 WM_MOTION_SetDeceleration() 911
19.8.3.3 WM_MOTION_SetDefaultPeriod() 912
19.8.3.4 WM_MOTION_SetMotion() 913
19.8.3.5 WM_MOTION_SetMoveable() 914
19.8.3.6 WM_MOTION_SetMovement() 915
19.8.3.7 WM_MOTION_SetSpeed() 916
19.8.3.8 WM_MOTION_SetThreshold() 917
19.8.4 ToolTip related functions 918
19.8.4.1 WM_TOOLTIP_AddTool() 918
19.8.4.2 WM_TOOLTIP_Create() 919
19.8.4.3 WM_TOOLTIP_Delete() 920
19.8.4.4 WM_TOOLTIP_SetDefaultColor() 921
19.8.4.5 WM_TOOLTIP_SetDefaultFont() 922
19.8.4.6 WM_TOOLTIP_SetDefaultPeriod() 923
19.8.5 Multiple Buffering support 924
19.8.5.1 WM_MULTIBUF_Enable() 924
19.8.6 Memory Device support (optional) 925
19.8.6.1 WM_DisableMemdev() 925
19.8.6.2 WM_EnableMemdev() 926
19.8.7 Timer related 927
19.8.7.1 WM_CreateTimer() 927
19.8.7.2 WM_DeleteTimer() 928
19.8.7.3 WM_GetTimerId() 929
19.8.7.4 WM_RestartTimer() 930
19.8.8 Widget related functions 931
19.8.8.1 WM_GetClientWindow() 931
19.8.8.2 WM_GetId() 932
19.8.8.3 WM_GetInsideRect() 933
19.8.8.4 WM_GetInsideRectEx() 934
19.8.8.5 WM_GetScrollbarH() 935

 © 2020 SEGGER Microcontroller GmbH

19.8.8.6 WM_GetScrollbarV() 936
19.8.8.7 WM_GetScrollPosH() 937
19.8.8.8 WM_GetScrollPosV() 938
19.8.8.9 WM_GetScrollState() 939
19.8.8.10 WM_SetScrollPosH() 940
19.8.8.11 WM_SetScrollPosV() 941
19.8.8.12 WM_SetScrollState() 942
19.8.9 Data structures 943
19.8.9.1 GUI_PID_STATE 943
19.8.9.2 TOOLTIP_INFO 944
19.8.9.3 WM_KEY_INFO 945
19.8.9.4 WM_MESSAGE 946
19.8.9.5 WM_MOTION_INFO 947
19.8.9.6 WM_MOVE_INFO 948
19.8.9.7 WM_PID_STATE_CHANGED_INFO 949
19.8.9.8 WM_SCROLL_STATE 950
19.8.10 Defines 951
19.8.10.1 Message IDs 951
19.8.10.2 Motion flags 953
19.8.10.3 Motion messages 954
19.8.10.4 Notification codes 955
19.8.10.5 ToolTip color indexes 956
19.8.10.6 ToolTip period indexes 957
19.8.10.7 Window create flags 958
19.9 Example 961

20 Widgets (window objects) 963

20.1 Some basics 964
20.1.1 Available widgets 964
20.1.2 Custom widget types 966
20.1.3 Understanding the redrawing mechanism 966
20.1.4 How to use widgets 966
20.2 Configuration options 969
20.3 Widget IDs 971
20.4 General widget API 972
20.4.1 WM routines used for widgets 972
20.4.2 Common routines 972
20.4.2.1 <WIDGET>_Callback() 973
20.4.2.2 <WIDGET>_CreateIndirect() 974
20.4.2.3 <WIDGET>_CreateUser() 975
20.4.2.4 <WIDGET>_GetUserData() 976
20.4.2.5 <WIDGET>_SetUserData() 977
20.4.2.6 WIDGET_EnableStreamAuto() 978
20.4.2.7 WIDGET_GetDefaultEffect() 979
20.4.2.8 WIDGET_SetDefaultEffect() 980
20.4.2.9 WIDGET_SetEffect() 981
20.4.2.10 WIDGET_SetFocusable() 982
20.4.3 User drawn widgets 983
20.5 BUTTON: Button widget 985
20.5.1 Configuration options 985
20.5.1.1 BUTTON_REACT_ON_LEVEL 985
20.5.1.2 BUTTON_BKCOLOR0_DEFAULT, BUTTON_BKCOLOR1_DEFAULT 986
20.5.2 Predefined IDs 986
20.5.3 Notification codes 986
20.5.4 Keyboard reaction 986
20.5.5 BUTTON API 987
20.5.5.1 Functions 989
20.5.5.1.1 BUTTON_Create() 989
20.5.5.1.2 BUTTON_CreateAsChild() 990

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.3 BUTTON_CreateEx() 991
20.5.5.1.4 BUTTON_CreateIndirect() 992
20.5.5.1.5 BUTTON_CreateUser() 993
20.5.5.1.6 BUTTON_GetBitmap() 994
20.5.5.1.7 BUTTON_GetBkColor() 995
20.5.5.1.8 BUTTON_GetDefaultBkColor() 996
20.5.5.1.9 BUTTON_GetDefaultFont() 997
20.5.5.1.10 BUTTON_GetDefaultTextAlign() 998
20.5.5.1.11 BUTTON_GetDefaultTextColor() 999
20.5.5.1.12 BUTTON_GetFont() 1000
20.5.5.1.13 BUTTON_GetText() 1001
20.5.5.1.14 BUTTON_GetTextAlign() 1002
20.5.5.1.15 BUTTON_GetTextColor() 1003
20.5.5.1.16 BUTTON_GetUserData() 1004
20.5.5.1.17 BUTTON_IsPressed() 1005
20.5.5.1.18 BUTTON_SetBitmap() 1006
20.5.5.1.19 BUTTON_SetBitmapEx() 1007
20.5.5.1.20 BUTTON_SetBkColor() 1008
20.5.5.1.21 BUTTON_SetBMP() 1009
20.5.5.1.22 BUTTON_SetBMPEx() 1010
20.5.5.1.23 BUTTON_SetDefaultBkColor() 1011
20.5.5.1.24 BUTTON_SetDefaultFocusColor() 1012
20.5.5.1.25 BUTTON_SetDefaultFont() 1013
20.5.5.1.26 BUTTON_SetDefaultTextAlign() 1014
20.5.5.1.27 BUTTON_SetDefaultTextColor() 1015
20.5.5.1.28 BUTTON_SetFocusColor() 1016
20.5.5.1.29 BUTTON_SetFocusable() 1017
20.5.5.1.30 BUTTON_SetFont() 1018
20.5.5.1.31 BUTTON_SetFrameColor() 1019
20.5.5.1.32 BUTTON_SetPressed() 1020
20.5.5.1.33 BUTTON_SetReactOnLevel() 1021
20.5.5.1.34 BUTTON_SetReactOnTouch() 1022
20.5.5.1.35 BUTTON_SetStreamedBitmap() 1023
20.5.5.1.36 BUTTON_SetStreamedBitmapEx() 1024
20.5.5.1.37 BUTTON_SetText() 1025
20.5.5.1.38 BUTTON_SetTextAlign() 1026
20.5.5.1.39 BUTTON_SetTextColor() 1027
20.5.5.1.40 BUTTON_SetTextOffset() 1028
20.5.5.1.41 BUTTON_SetUserData() 1029
20.5.5.2 Defines 1030
20.5.5.2.1 BUTTON bitmap indexes 1030
20.5.5.2.2 BUTTON color indexes 1031
20.5.6 Examples 1032
20.6 CHECKBOX: Checkbox widget 1033
20.6.1 Configuration options 1033
20.6.2 Predefined IDs 1034
20.6.3 Notification codes 1034
20.6.4 Keyboard reaction 1034
20.6.5 CHECKBOX API 1034
20.6.5.1 Functions 1037
20.6.5.1.1 CHECKBOX_Check() 1037
20.6.5.1.2 CHECKBOX_Create() 1038
20.6.5.1.3 CHECKBOX_CreateEx() 1039
20.6.5.1.4 CHECKBOX_CreateIndirect() 1040
20.6.5.1.5 CHECKBOX_CreateUser() 1041
20.6.5.1.6 CHECKBOX_GetBkColor() 1042
20.6.5.1.7 CHECKBOX_GetBoxBkColor() 1043
20.6.5.1.8 CHECKBOX_GetDefaultAlign() 1044
20.6.5.1.9 CHECKBOX_GetDefaultBkColor() 1045
20.6.5.1.10 CHECKBOX_GetDefaultFont() 1046

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.11 CHECKBOX_GetDefaultSpacing() 1047
20.6.5.1.12 CHECKBOX_GetDefaultTextAlign() 1048
20.6.5.1.13 CHECKBOX_GetDefaultTextColor() 1049
20.6.5.1.14 CHECKBOX_GetFocusColor() 1050
20.6.5.1.15 CHECKBOX_GetFont() 1051
20.6.5.1.16 CHECKBOX_GetImage() 1052
20.6.5.1.17 CHECKBOX_GetState() 1053
20.6.5.1.18 CHECKBOX_GetText() 1054
20.6.5.1.19 CHECKBOX_GetTextAlign() 1055
20.6.5.1.20 CHECKBOX_GetTextColor() 1056
20.6.5.1.21 CHECKBOX_GetUserData() 1057
20.6.5.1.22 CHECKBOX_IsChecked() 1058
20.6.5.1.23 CHECKBOX_SetBkColor() 1059
20.6.5.1.24 CHECKBOX_SetBoxBkColor() 1060
20.6.5.1.25 CHECKBOX_SetDefaultAlign() 1061
20.6.5.1.26 CHECKBOX_SetDefaultBkColor() 1062
20.6.5.1.27 CHECKBOX_SetDefaultFocusColor() 1063
20.6.5.1.28 CHECKBOX_SetDefaultFont() 1064
20.6.5.1.29 CHECKBOX_SetDefaultImage() 1065
20.6.5.1.30 CHECKBOX_SetDefaultSpacing() 1066
20.6.5.1.31 CHECKBOX_SetDefaultTextAlign() 1067
20.6.5.1.32 CHECKBOX_SetDefaultTextColor() 1068
20.6.5.1.33 CHECKBOX_SetFocusColor() 1069
20.6.5.1.34 CHECKBOX_SetFont() 1070
20.6.5.1.35 CHECKBOX_SetImage() 1071
20.6.5.1.36 CHECKBOX_SetNumStates() 1072
20.6.5.1.37 CHECKBOX_SetSpacing() 1073
20.6.5.1.38 CHECKBOX_SetState() 1074
20.6.5.1.39 CHECKBOX_SetText() 1075
20.6.5.1.40 CHECKBOX_SetTextAlign() 1076
20.6.5.1.41 CHECKBOX_SetTextColor() 1077
20.6.5.1.42 CHECKBOX_SetUserData() 1078
20.6.5.1.43 CHECKBOX_Uncheck() 1079
20.6.5.2 Defines 1080
20.6.5.2.1 CHECKBOX bitmap indexes 1080
20.6.5.2.2 CHECKBOX color indexes 1081
20.6.6 Example 1082
20.7 DROPDOWN: Dropdown widget 1083
20.7.1 Configuration options 1083
20.7.2 Predefined IDs 1084
20.7.3 Notification codes 1084
20.7.4 Keyboard reaction 1084
20.7.5 DROPDOWN API 1084
20.7.5.1 Functions 1087
20.7.5.1.1 DROPDOWN_AddString() 1087
20.7.5.1.2 DROPDOWN_Collapse() 1088
20.7.5.1.3 DROPDOWN_Create() 1089
20.7.5.1.4 DROPDOWN_CreateEx() 1090
20.7.5.1.5 DROPDOWN_CreateIndirect() 1091
20.7.5.1.6 DROPDOWN_CreateUser() 1092
20.7.5.1.7 DROPDOWN_DecSel() 1093
20.7.5.1.8 DROPDOWN_DecSelExp() 1094
20.7.5.1.9 DROPDOWN_DeleteItem() 1095
20.7.5.1.10 DROPDOWN_Expand() 1096
20.7.5.1.11 DROPDOWN_GetBkColor() 1097
20.7.5.1.12 DROPDOWN_GetColor() 1098
20.7.5.1.13 DROPDOWN_GetDefaultFont() 1099
20.7.5.1.14 DROPDOWN_GetFont() 1100
20.7.5.1.15 DROPDOWN_GetItemDisabled() 1101
20.7.5.1.16 DROPDOWN_GetItemText() 1102

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.17 DROPDOWN_GetListbox() 1103
20.7.5.1.18 DROPDOWN_GetNumItems() 1104
20.7.5.1.19 DROPDOWN_GetSel() 1105
20.7.5.1.20 DROPDOWN_GetSelExp() 1106
20.7.5.1.21 DROPDOWN_GetTextColor() 1107
20.7.5.1.22 DROPDOWN_GetUserData() 1108
20.7.5.1.23 DROPDOWN_IncSel() 1109
20.7.5.1.24 DROPDOWN_IncSelExp() 1110
20.7.5.1.25 DROPDOWN_InsertString() 1111
20.7.5.1.26 DROPDOWN_SetAutoScroll() 1112
20.7.5.1.27 DROPDOWN_SetBkColor() 1113
20.7.5.1.28 DROPDOWN_SetColor() 1114
20.7.5.1.29 DROPDOWN_SetDefaultColor() 1115
20.7.5.1.30 DROPDOWN_SetDefaultFont() 1116
20.7.5.1.31 DROPDOWN_SetDefaultScrollbarColor() 1117
20.7.5.1.32 DROPDOWN_SetFont() 1118
20.7.5.1.33 DROPDOWN_SetItemDisabled() 1119
20.7.5.1.34 DROPDOWN_SetItemSpacing() 1120
20.7.5.1.35 DROPDOWN_SetListHeight() 1121
20.7.5.1.36 DROPDOWN_SetScrollbarColor() 1122
20.7.5.1.37 DROPDOWN_SetScrollbarWidth() 1123
20.7.5.1.38 DROPDOWN_SetSel() 1124
20.7.5.1.39 DROPDOWN_SetSelExp() 1125
20.7.5.1.40 DROPDOWN_SetTextAlign() 1126
20.7.5.1.41 DROPDOWN_SetTextColor() 1127
20.7.5.1.42 DROPDOWN_SetTextHeight() 1128
20.7.5.1.43 DROPDOWN_SetUpMode() 1129
20.7.5.1.44 DROPDOWN_SetUserData() 1130
20.7.5.2 Defines 1131
20.7.5.2.1 DROPDOWN color indexes 1131
20.7.5.2.2 DROPDOWN create flags 1132
20.7.6 Example 1133
20.8 EDIT: Edit widget 1134
20.8.1 Configuration options 1134
20.8.2 Predefined IDs 1134
20.8.3 Notification codes 1135
20.8.4 Keyboard reaction 1135
20.8.5 EDIT API 1135
20.8.5.1 Functions 1138
20.8.5.1.1 EDIT_AddKey() 1138
20.8.5.1.2 EDIT_Create() 1139
20.8.5.1.3 EDIT_CreateAsChild() 1140
20.8.5.1.4 EDIT_CreateEx() 1141
20.8.5.1.5 EDIT_CreateIndirect() 1142
20.8.5.1.6 EDIT_CreateUser() 1143
20.8.5.1.7 EDIT_EnableBlink() 1144
20.8.5.1.8 EDIT_EnableInversion() 1145
20.8.5.1.9 EDIT_GetBkColor() 1146
20.8.5.1.10 EDIT_GetBorderSize() 1147
20.8.5.1.11 EDIT_GetCharAtPixel() 1148
20.8.5.1.12 EDIT_GetCursorCharPos() 1149
20.8.5.1.13 EDIT_GetCursorPixelPos() 1150
20.8.5.1.14 EDIT_GetDefaultBkColor() 1151
20.8.5.1.15 EDIT_GetDefaultFont() 1152
20.8.5.1.16 EDIT_GetDefaultTextAlign() 1153
20.8.5.1.17 EDIT_GetDefaultTextColor() 1154
20.8.5.1.18 EDIT_GetFloatValue() 1155
20.8.5.1.19 EDIT_GetFont() 1156
20.8.5.1.20 EDIT_GetNumChars() 1157
20.8.5.1.21 EDIT_GetSel() 1158

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.22 EDIT_GetSelText() 1159
20.8.5.1.23 EDIT_GetText() 1160
20.8.5.1.24 EDIT_GetTextAlign() 1161
20.8.5.1.25 EDIT_GetTextColor() 1162
20.8.5.1.26 EDIT_GetUserData() 1163
20.8.5.1.27 EDIT_GetValue() 1164
20.8.5.1.28 EDIT_SetBinMode() 1165
20.8.5.1.29 EDIT_SetBkColor() 1166
20.8.5.1.30 EDIT_SetCursorAtChar() 1167
20.8.5.1.31 EDIT_SetCursorAtPixel() 1168
20.8.5.1.32 EDIT_SetDecMode() 1169
20.8.5.1.33 EDIT_SetDefaultBkColor() 1170
20.8.5.1.34 EDIT_SetDefaultFont() 1171
20.8.5.1.35 EDIT_SetDefaultTextAlign() 1172
20.8.5.1.36 EDIT_SetDefaultTextColor() 1173
20.8.5.1.37 EDIT_SetFloatMode() 1174
20.8.5.1.38 EDIT_SetFloatValue() 1175
20.8.5.1.39 EDIT_SetFocusable() 1176
20.8.5.1.40 EDIT_SetFont() 1177
20.8.5.1.41 EDIT_SetHexMode() 1178
20.8.5.1.42 EDIT_SetInsertMode() 1179
20.8.5.1.43 EDIT_SetMaxLen() 1180
20.8.5.1.44 EDIT_SetpfAddKeyEx() 1181
20.8.5.1.45 EDIT_SetSel() 1182
20.8.5.1.46 EDIT_SetText() 1183
20.8.5.1.47 EDIT_SetTextAlign() 1184
20.8.5.1.48 EDIT_SetTextColor() 1185
20.8.5.1.49 EDIT_SetTextMode() 1186
20.8.5.1.50 EDIT_SetValue() 1187
20.8.5.1.51 EDIT_SetUlongMode() 1188
20.8.5.1.52 EDIT_SetUserData() 1189
20.8.5.1.53 GUI_EditBin() 1190
20.8.5.1.54 GUI_EditDec() 1191
20.8.5.1.55 GUI_EditFloat() 1192
20.8.5.1.56 GUI_EditHex() 1193
20.8.5.1.57 GUI_EditString() 1194
20.8.5.2 Defines 1195
20.8.5.2.1 EDIT color indexes 1195
20.8.5.2.2 EDIT flags 1196
20.8.6 Examples 1197
20.9 FRAMEWIN: Frame window widget 1198
20.9.1 Structure of the frame window 1199
20.9.2 Configuration options 1200
20.9.3 Keyboard reaction 1200
20.9.4 FRAMEWIN API 1200
20.9.4.1 Functions 1203
20.9.4.1.1 FRAMEWIN_AddButton() 1203
20.9.4.1.2 FRAMEWIN_AddCloseButton() 1204
20.9.4.1.3 FRAMEWIN_AddMaxButton() 1205
20.9.4.1.4 FRAMEWIN_AddMenu() 1206
20.9.4.1.5 FRAMEWIN_AddMinButton() 1207
20.9.4.1.6 FRAMEWIN_Create() 1208
20.9.4.1.7 FRAMEWIN_CreateAsChild() 1209
20.9.4.1.8 FRAMEWIN_CreateEx() 1210
20.9.4.1.9 FRAMEWIN_CreateIndirect() 1211
20.9.4.1.10 FRAMEWIN_CreateUser() 1212
20.9.4.1.11 FRAMEWIN_GetActive() 1213
20.9.4.1.12 FRAMEWIN_GetBarColor() 1214
20.9.4.1.13 FRAMEWIN_GetBorderSize() 1215
20.9.4.1.14 FRAMEWIN_GetDefaultBarColor() 1216

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.15 FRAMEWIN_GetDefaultBorderSize() 1217
20.9.4.1.16 FRAMEWIN_GetDefaultClientColor() 1218
20.9.4.1.17 FRAMEWIN_GetDefaultFont() 1219
20.9.4.1.18 FRAMEWIN_GetDefaultTextColor() 1220
20.9.4.1.19 FRAMEWIN_GetDefaultTitleHeight() 1221
20.9.4.1.20 FRAMEWIN_GetFont() 1222
20.9.4.1.21 FRAMEWIN_GetText() 1223
20.9.4.1.22 FRAMEWIN_GetTextAlign() 1224
20.9.4.1.23 FRAMEWIN_GetTitleHeight() 1225
20.9.4.1.24 FRAMEWIN_GetUserData() 1226
20.9.4.1.25 FRAMEWIN_IsMinimized() 1227
20.9.4.1.26 FRAMEWIN_IsMaximized() 1228
20.9.4.1.27 FRAMEWIN_Maximize() 1229
20.9.4.1.28 FRAMEWIN_Minimize() 1230
20.9.4.1.29 FRAMEWIN_OwnerDraw() 1231
20.9.4.1.30 FRAMEWIN_Restore() 1232
20.9.4.1.31 FRAMEWIN_SetActive() 1233
20.9.4.1.32 FRAMEWIN_SetBarColor() 1234
20.9.4.1.33 FRAMEWIN_SetBorderSize() 1235
20.9.4.1.34 FRAMEWIN_SetClientColor() 1236
20.9.4.1.35 FRAMEWIN_SetDefaultBarColor() 1237
20.9.4.1.36 FRAMEWIN_SetDefaultBorderSize() 1238
20.9.4.1.37 FRAMEWIN_SetDefaultClientColor() 1239
20.9.4.1.38 FRAMEWIN_SetDefaultFont() 1240
20.9.4.1.39 FRAMEWIN_SetDefaultTextColor() 1241
20.9.4.1.40 FRAMEWIN_SetDefaultTitleHeight() 1242
20.9.4.1.41 FRAMEWIN_SetFont() 1243
20.9.4.1.42 FRAMEWIN_SetMoveable() 1244
20.9.4.1.43 FRAMEWIN_SetOwnerDraw() 1245
20.9.4.1.44 FRAMEWIN_SetResizeable() 1247
20.9.4.1.45 FRAMEWIN_SetText() 1248
20.9.4.1.46 FRAMEWIN_SetTextAlign() 1249
20.9.4.1.47 FRAMEWIN_SetTextColor() 1250
20.9.4.1.48 FRAMEWIN_SetTextColorEx() 1251
20.9.4.1.49 FRAMEWIN_SetTitleHeight() 1252
20.9.4.1.50 FRAMEWIN_SetTitleVis() 1253
20.9.4.1.51 FRAMEWIN_SetUserData() 1254
20.9.4.2 Defines 1255
20.9.4.2.1 FRAMEWIN button flags 1255
20.9.4.2.2 FRAMEWIN create flags 1256
20.9.4.2.3 FRAMEWIN states 1257
20.9.5 Example 1258
20.10 GAUGE: Gauge widget 1259
20.10.1 Configuration options 1259
20.10.2 Predefined IDs 1259
20.10.3 Notification codes 1259
20.10.4 Keyboard reaction 1260
20.10.5 GAUGE API 1260
20.10.5.1 Functions 1261
20.10.5.1.1 GAUGE_CreateIndirect() 1261
20.10.5.1.2 GAUGE_CreateUser() 1262
20.10.5.1.3 GAUGE_GetValue() 1263
20.10.5.1.4 GAUGE_SetAlign() 1264
20.10.5.1.5 GAUGE_SetBkColor() 1265
20.10.5.1.6 GAUGE_SetColor() 1266
20.10.5.1.7 GAUGE_SetOffset() 1267
20.10.5.1.8 GAUGE_SetRadius() 1268
20.10.5.1.9 GAUGE_SetRange() 1269
20.10.5.1.10 GAUGE_SetRoundedEnd() 1270
20.10.5.1.11 GAUGE_SetRoundedValue() 1271

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.12 GAUGE_SetValue() 1272
20.10.5.1.13 GAUGE_SetValueRange() 1273
20.10.5.1.14 GAUGE_SetWidth() 1274
20.10.5.2 Defines 1275
20.10.5.2.1 GAUGE curved flags 1275
20.11 GRAPH: Graph widget 1276
20.11.1 Structure of the graph widget 1276
20.11.2 Creating and deleting a graph widget 1277
20.11.3 Drawing process 1277
20.11.4 Supported types of curves 1277
20.11.4.1 GRAPH_DATA_XY 1278
20.11.4.2 GRAPH_DATA_YT 1278
20.11.5 Configuration options 1278
20.11.5.1 Graph widget 1278
20.11.5.2 Scale object 1278
20.11.6 Predefined IDs 1279
20.11.7 Keyboard reaction 1279
20.11.8 GRAPH API 1279
20.11.8.1 Common routines 1282
20.11.8.1.1 GRAPH_AttachData() 1282
20.11.8.1.2 GRAPH_AttachScale() 1283
20.11.8.1.3 GRAPH_CreateEx() 1284
20.11.8.1.4 GRAPH_CreateIndirect() 1285
20.11.8.1.5 GRAPH_CreateUser() 1286
20.11.8.1.6 GRAPH_DetachData() 1287
20.11.8.1.7 GRAPH_DetachScale() 1288
20.11.8.1.8 GRAPH_GetColor() 1289
20.11.8.1.9 GRAPH_GetScrollValue() 1290
20.11.8.1.10 GRAPH_GetUserData() 1291
20.11.8.1.11 GRAPH_InvertScrollbar() 1292
20.11.8.1.12 GRAPH_SetAutoScrollbar() 1293
20.11.8.1.13 GRAPH_SetBorder() 1294
20.11.8.1.14 GRAPH_SetColor() 1295
20.11.8.1.15 GRAPH_SetGridDistX() 1296
20.11.8.1.16 GRAPH_SetGridDistY() 1296
20.11.8.1.17 GRAPH_SetGridFixedX() 1297
20.11.8.1.18 GRAPH_SetGridOffX() 1298
20.11.8.1.19 GRAPH_SetGridOffY() 1299
20.11.8.1.20 GRAPH_SetGridVis() 1300
20.11.8.1.21 GRAPH_SetLineStyleH() 1301
20.11.8.1.22 GRAPH_SetLineStyleV() 1301
20.11.8.1.23 GRAPH_SetScrollValue() 1302
20.11.8.1.24 GRAPH_SetUserData() 1303
20.11.8.1.25 GRAPH_SetUserDraw() 1304
20.11.8.1.26 GRAPH_SetVSizeX() 1306
20.11.8.1.27 GRAPH_SetVSizeY() 1306
20.11.8.2 GRAPH_DATA_YT related routines 1308
20.11.8.2.1 GRAPH_DATA_YT_AddValue() 1308
20.11.8.2.2 GRAPH_DATA_YT_Clear() 1309
20.11.8.2.3 GRAPH_DATA_YT_Create() 1310
20.11.8.2.4 GRAPH_DATA_YT_Delete() 1311
20.11.8.2.5 GRAPH_DATA_YT_GetValue() 1312
20.11.8.2.6 GRAPH_DATA_YT_MirrorX() 1313
20.11.8.2.7 GRAPH_DATA_YT_SetAlign() 1314
20.11.8.2.8 GRAPH_DATA_YT_SetColor() 1315
20.11.8.2.9 GRAPH_DATA_YT_SetOffY() 1316
20.11.8.3 GRAPH_DATA_XY related routines 1317
20.11.8.3.1 GRAPH_DATA_XY_AddPoint() 1317
20.11.8.3.2 GRAPH_DATA_XY_Clear() 1318
20.11.8.3.3 GRAPH_DATA_XY_Create() 1319

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.4 GRAPH_DATA_XY_Delete() 1320
20.11.8.3.5 GRAPH_DATA_XY_GetLineVis() 1321
20.11.8.3.6 GRAPH_DATA_XY_GetPoint() 1322
20.11.8.3.7 GRAPH_DATA_XY_GetPointVis() 1323
20.11.8.3.8 GRAPH_DATA_XY_SetColor() 1324
20.11.8.3.9 GRAPH_DATA_XY_SetLineStyle() 1325
20.11.8.3.10 GRAPH_DATA_XY_SetLineVis() 1326
20.11.8.3.11 GRAPH_DATA_XY_SetOffX() 1327
20.11.8.3.12 GRAPH_DATA_XY_SetOffY() 1327
20.11.8.3.13 GRAPH_DATA_XY_SetOwnerDraw() 1328
20.11.8.3.14 GRAPH_DATA_XY_SetPenSize() 1329
20.11.8.3.15 GRAPH_DATA_XY_SetPointVis() 1330
20.11.8.4 Scale related routines 1331
20.11.8.4.1 GRAPH_SCALE_Create() 1331
20.11.8.4.2 GRAPH_SCALE_Delete() 1332
20.11.8.4.3 GRAPH_SCALE_SetFactor() 1333
20.11.8.4.4 GRAPH_SCALE_SetFont() 1334
20.11.8.4.5 GRAPH_SCALE_SetNumDecs() 1335
20.11.8.4.6 GRAPH_SCALE_SetOff() 1336
20.11.8.4.7 GRAPH_SCALE_SetPos() 1337
20.11.8.4.8 GRAPH_SCALE_SetTextColor() 1338
20.11.8.4.9 GRAPH_SCALE_SetTickDist() 1339
20.11.8.5 Defines 1340
20.11.8.5.1 GRAPH alignment flags 1340
20.11.8.5.2 GRAPH color indexes 1341
20.11.8.5.3 GRAPH create flags 1342
20.11.8.5.4 GRAPH user draw stages 1343
20.11.8.5.5 SCALE create flags 1344
20.11.9 Examples 1345
20.12 HEADER: Header widget 1346
20.12.1 Configuration options 1346
20.12.2 Notification codes 1347
20.12.3 Keyboard reaction 1347
20.12.4 HEADER API 1347
20.12.4.1 HEADER_AddItem() 1350
20.12.4.2 HEADER_Create() 1351
20.12.4.3 HEADER_CreateAttached() 1352
20.12.4.4 HEADER_CreateEx() 1353
20.12.4.5 HEADER_CreateIndirect() 1354
20.12.4.6 HEADER_CreateUser() 1355
20.12.4.7 HEADER_DeleteItem() 1356
20.12.4.8 HEADER_GetBkColor() 1357
20.12.4.9 HEADER_GetColumnFromPos() 1358
20.12.4.10 HEADER_GetDefaultBkColor() 1359
20.12.4.11 HEADER_GetDefaultBorderH() 1360
20.12.4.12 HEADER_GetDefaultBorderV() 1361
20.12.4.13 HEADER_GetDefaultCursor() 1362
20.12.4.14 HEADER_GetDefaultFont() 1363
20.12.4.15 HEADER_GetDefaultTextColor() 1364
20.12.4.16 HEADER_GetFont() 1365
20.12.4.17 HEADER_GetHeight() 1366
20.12.4.18 HEADER_GetItemText() 1367
20.12.4.19 HEADER_GetItemWidth() 1368
20.12.4.20 HEADER_GetNumItems() 1369
20.12.4.21 HEADER_GetSel() 1370
20.12.4.22 HEADER_GetTextColor() 1371
20.12.4.23 HEADER_GetUserData() 1372
20.12.4.24 HEADER_SetBitmap() 1373
20.12.4.25 HEADER_SetBitmapEx() 1374
20.12.4.26 HEADER_SetBkColor() 1375

 © 2020 SEGGER Microcontroller GmbH

20.12.4.27 HEADER_SetBMP() 1376
20.12.4.28 HEADER_SetBMPEx() 1377
20.12.4.29 HEADER_SetDefaultBkColor() 1378
20.12.4.30 HEADER_SetDefaultBorderH() 1379
20.12.4.31 HEADER_SetDefaultBorderV() 1380
20.12.4.32 HEADER_SetDefaultCursor() 1381
20.12.4.33 HEADER_SetDefaultFont() 1382
20.12.4.34 HEADER_SetDefaultTextColor() 1383
20.12.4.35 HEADER_SetDragLimit() 1384
20.12.4.36 HEADER_SetFixed() 1385
20.12.4.37 HEADER_SetFont() 1386
20.12.4.38 HEADER_SetHeight() 1387
20.12.4.39 HEADER_SetItemText() 1388
20.12.4.40 HEADER_SetItemWidth() 1389
20.12.4.41 HEADER_SetScrollPos() 1390
20.12.4.42 HEADER_SetStreamedBitmap() 1391
20.12.4.43 HEADER_SetStreamedBitmapEx() 1392
20.12.4.44 HEADER_SetTextAlign() 1393
20.12.4.45 HEADER_SetTextColor() 1394
20.12.4.46 HEADER_SetUserData() 1395
20.12.5 Example 1396
20.13 ICONVIEW: Icon view widget 1397
20.13.1 Configuration options 1397
20.13.2 Predefined IDs 1398
20.13.3 Notification codes 1398
20.13.4 Keyboard reaction 1398
20.13.5 ICONVIEW API 1398
20.13.5.1 Functions 1401
20.13.5.1.1 ICONVIEW_AddBitmapItem() 1401
20.13.5.1.2 ICONVIEW_AddStreamedBitmapItem() 1402
20.13.5.1.3 ICONVIEW_CreateEx() 1403
20.13.5.1.4 ICONVIEW_CreateIndirect() 1404
20.13.5.1.5 ICONVIEW_CreateUser() 1405
20.13.5.1.6 ICONVIEW_DeleteItem() 1406
20.13.5.1.7 ICONVIEW_EnableStreamAuto() 1407
20.13.5.1.8 ICONVIEW_GetBkColor() 1408
20.13.5.1.9 ICONVIEW_GetFont() 1409
20.13.5.1.10 ICONVIEW_GetItemBitmap() 1410
20.13.5.1.11 ICONVIEW_GetItemText() 1411
20.13.5.1.12 ICONVIEW_GetItemUserData() 1412
20.13.5.1.13 ICONVIEW_GetNumItems() 1413
20.13.5.1.14 ICONVIEW_GetReleasedItem() 1414
20.13.5.1.15 ICONVIEW_GetSel() 1415
20.13.5.1.16 ICONVIEW_GetTextColor() 1416
20.13.5.1.17 ICONVIEW_GetUserData() 1417
20.13.5.1.18 ICONVIEW_InsertBitmapItem() 1418
20.13.5.1.19 ICONVIEW_InsertStreamedBitmapItem() 1419
20.13.5.1.20 ICONVIEW_OwnerDraw() 1420
20.13.5.1.21 ICONVIEW_SetBitmapItem() 1421
20.13.5.1.22 ICONVIEW_SetBkColor() 1422
20.13.5.1.23 ICONVIEW_SetFont() 1423
20.13.5.1.24 ICONVIEW_SetFrame() 1424
20.13.5.1.25 ICONVIEW_SetIconAlign() 1425
20.13.5.1.26 ICONVIEW_SetItemText() 1426
20.13.5.1.27 ICONVIEW_SetItemUserData() 1427
20.13.5.1.28 ICONVIEW_SetOwnerDraw() 1428
20.13.5.1.29 ICONVIEW_SetSel() 1429
20.13.5.1.30 ICONVIEW_SetSpace() 1430
20.13.5.1.31 ICONVIEW_SetStreamedBitmapItem() 1431
20.13.5.1.32 ICONVIEW_SetTextAlign() 1432

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.33 ICONVIEW_SetTextColor() 1433
20.13.5.1.34 ICONVIEW_SetUserData() 1434
20.13.5.1.35 ICONVIEW_SetWrapMode() 1435
20.13.5.2 Defines 1436
20.13.5.2.1 ICONVIEW alignment flags 1436
20.13.5.2.2 ICONVIEW color indexes 1437
20.13.5.2.3 ICONVIEW create flags 1438
20.13.6 Example 1439
20.14 IMAGE: Image widget 1440
20.14.1 Configuration options 1440
20.14.2 Predefined IDs 1440
20.14.3 Notification codes 1440
20.14.4 IMAGE API 1440
20.14.4.1 Functions 1442
20.14.4.1.1 IMAGE_CreateEx() 1442
20.14.4.1.2 IMAGE_CreateIndirect() 1443
20.14.4.1.3 IMAGE_CreateUser() 1444
20.14.4.1.4 IMAGE_GetImageSize() 1445
20.14.4.1.5 IMAGE_GetUserData() 1446
20.14.4.1.6 IMAGE_SetBitmap() 1447
20.14.4.1.7 IMAGE_SetBMP() 1448
20.14.4.1.8 IMAGE_SetDTA() 1448
20.14.4.1.9 IMAGE_SetGIF() 1448
20.14.4.1.10 IMAGE_SetJPEG() 1448
20.14.4.1.11 IMAGE_SetPNG() 1448
20.14.4.1.12 IMAGE_SetBMPEx() 1449
20.14.4.1.13 IMAGE_SetDTAEx() 1449
20.14.4.1.14 IMAGE_SetGIFEx() 1449
20.14.4.1.15 IMAGE_SetJPEGEx() 1449
20.14.4.1.16 IMAGE_SetPNGEx() 1449
20.14.4.1.17 IMAGE_SetTiled() 1450
20.14.4.1.18 IMAGE_SetUserData() 1451
20.14.4.2 Defines 1452
20.14.4.2.1 IMAGE create flags 1452
20.15 KNOB: Knob widget (obsolete) 1453
20.15.1 Requirements 1453
20.15.2 Configuration options 1454
20.15.3 Predefined IDs 1454
20.15.4 Notification codes 1454
20.15.5 Keyboard reaction 1454
20.15.6 KNOB API 1454
20.15.6.1 KNOB_AddValue() 1456
20.15.6.2 KNOB_CreateEx() 1457
20.15.6.3 KNOB_CreateIndirect() 1458
20.15.6.4 KNOB_CreateUser() 1459
20.15.6.5 KNOB_GetUserData() 1460
20.15.6.6 KNOB_GetValue() 1461
20.15.6.7 KNOB_SetBkColor() 1462
20.15.6.8 KNOB_SetBkDevice() 1463
20.15.6.9 KNOB_SetDevice() 1464
20.15.6.10 KNOB_SetInvert() 1465
20.15.6.11 KNOB_SetKeyValue() 1466
20.15.6.12 KNOB_SetOffset() 1467
20.15.6.13 KNOB_SetPeriod() 1468
20.15.6.14 KNOB_SetPos() 1469
20.15.6.15 KNOB_SetRange() 1470
20.15.6.16 KNOB_SetRotateHQ() 1471
20.15.6.17 KNOB_SetRotateLQ() 1471
20.15.6.18 KNOB_SetSnap() 1472
20.15.6.19 KNOB_SetTickSize() 1473

 © 2020 SEGGER Microcontroller GmbH

20.15.6.20 KNOB_SetUserData() 1474
20.16 LISTBOX: List box widget 1475
20.16.1 Configuration options 1475
20.16.2 Predefined IDs 1475
20.16.3 Notification codes 1475
20.16.4 Keyboard reaction 1476
20.16.5 LISTBOX API 1476
20.16.5.1 Functions 1479
20.16.5.1.1 LISTBOX_AddString() 1479
20.16.5.1.2 LISTBOX_Create() 1480
20.16.5.1.3 LISTBOX_CreateAsChild() 1481
20.16.5.1.4 LISTBOX_CreateEx() 1482
20.16.5.1.5 LISTBOX_CreateIndirect() 1483
20.16.5.1.6 LISTBOX_CreateUser() 1484
20.16.5.1.7 LISTBOX_DecSel() 1485
20.16.5.1.8 LISTBOX_DeleteItem() 1486
20.16.5.1.9 LISTBOX_EnableMotion() 1487
20.16.5.1.10 LISTBOX_EnableWrapMode() 1488
20.16.5.1.11 LISTBOX_GetBkColor() 1489
20.16.5.1.12 LISTBOX_GetDefaultBkColor() 1490
20.16.5.1.13 LISTBOX_GetDefaultFont() 1491
20.16.5.1.14 LISTBOX_GetDefaultScrollStepH() 1492
20.16.5.1.15 LISTBOX_GetDefaultTextAlign() 1493
20.16.5.1.16 LISTBOX_GetDefaultTextColor() 1494
20.16.5.1.17 LISTBOX_GetFont() 1495
20.16.5.1.18 LISTBOX_GetItemDisabled() 1496
20.16.5.1.19 LISTBOX_GetItemSel() 1497
20.16.5.1.20 LISTBOX_GetItemSpacing() 1498
20.16.5.1.21 LISTBOX_GetItemText() 1499
20.16.5.1.22 LISTBOX_GetMulti() 1500
20.16.5.1.23 LISTBOX_GetNumItems() 1501
20.16.5.1.24 LISTBOX_GetOwner() 1502
20.16.5.1.25 LISTBOX_GetScrollStepH() 1503
20.16.5.1.26 LISTBOX_GetSel() 1504
20.16.5.1.27 LISTBOX_GetTextAlign() 1505
20.16.5.1.28 LISTBOX_GetTextColor() 1506
20.16.5.1.29 LISTBOX_GetUserData() 1507
20.16.5.1.30 LISTBOX_IncSel() 1508
20.16.5.1.31 LISTBOX_InsertString() 1509
20.16.5.1.32 LISTBOX_InvalidateItem() 1510
20.16.5.1.33 LISTBOX_OwnerDraw() 1511
20.16.5.1.34 LISTBOX_SetAutoScrollH() 1512
20.16.5.1.35 LISTBOX_SetAutoScrollV() 1513
20.16.5.1.36 LISTBOX_SetBkColor() 1514
20.16.5.1.37 LISTBOX_SetDefaultBkColor() 1515
20.16.5.1.38 LISTBOX_SetDefaultFont() 1516
20.16.5.1.39 LISTBOX_SetDefaultScrollStepH() 1517
20.16.5.1.40 LISTBOX_SetDefaultTextAlign() 1518
20.16.5.1.41 LISTBOX_SetDefaultTextColor() 1519
20.16.5.1.42 LISTBOX_SetFixedScrollPos() 1520
20.16.5.1.43 LISTBOX_SetFont() 1521
20.16.5.1.44 LISTBOX_SetItemDisabled() 1522
20.16.5.1.45 LISTBOX_SetItemSel() 1523
20.16.5.1.46 LISTBOX_SetItemSpacing() 1524
20.16.5.1.47 LISTBOX_SetMulti() 1525
20.16.5.1.48 LISTBOX_SetOwnerDraw() 1526
20.16.5.1.49 LISTBOX_SetScrollbarColor() 1528
20.16.5.1.50 LISTBOX_SetScrollbarWidth() 1529
20.16.5.1.51 LISTBOX_SetScrollStepH() 1530
20.16.5.1.52 LISTBOX_SetSel() 1531

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.53 LISTBOX_SetString() 1532
20.16.5.1.54 LISTBOX_SetTextAlign() 1533
20.16.5.1.55 LISTBOX_SetTextColor() 1534
20.16.5.1.56 LISTBOX_SetUserData() 1535
20.16.5.2 Defines 1536
20.16.5.2.1 LISTBOX color indexes 1536
20.16.5.2.2 LISTBOX fixed scroll mode flags 1537
20.16.6 Examples 1538
20.17 LISTVIEW: Listview widget 1539
20.17.1 Configuration options 1540
20.17.2 Predefined IDs 1540
20.17.3 Notification codes 1540
20.17.4 Keyboard reaction 1541
20.17.5 LISTVIEW API 1541
20.17.5.1 Functions 1545
20.17.5.1.1 LISTVIEW_AddColumn() 1545
20.17.5.1.2 LISTVIEW_AddRow() 1546
20.17.5.1.3 LISTVIEW_CompareDec() 1547
20.17.5.1.4 LISTVIEW_CompareText() 1548
20.17.5.1.5 LISTVIEW_Create() 1549
20.17.5.1.6 LISTVIEW_CreateAttached() 1550
20.17.5.1.7 LISTVIEW_CreateEx() 1551
20.17.5.1.8 LISTVIEW_CreateIndirect() 1552
20.17.5.1.9 LISTVIEW_CreateUser() 1553
20.17.5.1.10 LISTVIEW_DecSel() 1554
20.17.5.1.11 LISTVIEW_DeleteAllRows() 1555
20.17.5.1.12 LISTVIEW_DeleteColumn() 1556
20.17.5.1.13 LISTVIEW_DeleteRow() 1557
20.17.5.1.14 LISTVIEW_DisableRow() 1558
20.17.5.1.15 LISTVIEW_DisableSort() 1559
20.17.5.1.16 LISTVIEW_EnableCellSelect() 1560
20.17.5.1.17 LISTVIEW_EnableMotion() 1561
20.17.5.1.18 LISTVIEW_EnableRow() 1562
20.17.5.1.19 LISTVIEW_EnableSort() 1563
20.17.5.1.20 LISTVIEW_GetBkColor() 1564
20.17.5.1.21 LISTVIEW_GetFont() 1565
20.17.5.1.22 LISTVIEW_GetHeader() 1566
20.17.5.1.23 LISTVIEW_GetItemRect() 1567
20.17.5.1.24 LISTVIEW_GetItemText() 1568
20.17.5.1.25 LISTVIEW_GetItemTextLen() 1569
20.17.5.1.26 LISTVIEW_GetItemTextSorted() 1570
20.17.5.1.27 LISTVIEW_GetLBorder() 1571
20.17.5.1.28 LISTVIEW_GetNumColumns() 1572
20.17.5.1.29 LISTVIEW_GetNumRows() 1573
20.17.5.1.30 LISTVIEW_GetRBorder() 1574
20.17.5.1.31 LISTVIEW_GetSel() 1575
20.17.5.1.32 LISTVIEW_GetSelCol() 1576
20.17.5.1.33 LISTVIEW_GetSelUnsorted() 1577
20.17.5.1.34 LISTVIEW_GetTextAlign() 1578
20.17.5.1.35 LISTVIEW_GetTextColor() 1579
20.17.5.1.36 LISTVIEW_GetUserData() 1580
20.17.5.1.37 LISTVIEW_GetUserDataRow() 1581
20.17.5.1.38 LISTVIEW_GetWrapMode() 1582
20.17.5.1.39 LISTVIEW_IncSel() 1583
20.17.5.1.40 LISTVIEW_InsertRow() 1584
20.17.5.1.41 LISTVIEW_OwnerDraw() 1585
20.17.5.1.42 LISTVIEW_RowIsDisabled() 1586
20.17.5.1.43 LISTVIEW_SetAutoScrollH() 1587
20.17.5.1.44 LISTVIEW_SetAutoScrollV() 1588
20.17.5.1.45 LISTVIEW_SetBkColor() 1589

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.46 LISTVIEW_SetColumnWidth() 1590
20.17.5.1.47 LISTVIEW_SetCompareFunc() 1591
20.17.5.1.48 LISTVIEW_SetDefaultBkColor() 1593
20.17.5.1.49 LISTVIEW_SetDefaultFont() 1594
20.17.5.1.50 LISTVIEW_SetDefaultGridColor() 1595
20.17.5.1.51 LISTVIEW_SetDefaultTextColor() 1596
20.17.5.1.52 LISTVIEW_SetFixed() 1597
20.17.5.1.53 LISTVIEW_SetFont() 1598
20.17.5.1.54 LISTVIEW_SetGridVis() 1599
20.17.5.1.55 LISTVIEW_SetHeaderHeight() 1600
20.17.5.1.56 LISTVIEW_SetItemBitmap() 1601
20.17.5.1.57 LISTVIEW_SetItemBkColor() 1602
20.17.5.1.58 LISTVIEW_SetItemText() 1603
20.17.5.1.59 LISTVIEW_SetItemTextColor() 1604
20.17.5.1.60 LISTVIEW_SetItemTextSorted() 1605
20.17.5.1.61 LISTVIEW_SetLBorder() 1606
20.17.5.1.62 LISTVIEW_SetOwnerDraw() 1607
20.17.5.1.63 LISTVIEW_SetRBorder() 1608
20.17.5.1.64 LISTVIEW_SetRowHeight() 1609
20.17.5.1.65 LISTVIEW_SetSel() 1610
20.17.5.1.66 LISTVIEW_SetSelCol() 1611
20.17.5.1.67 LISTVIEW_SetSelUnsorted() 1612
20.17.5.1.68 LISTVIEW_SetSort() 1613
20.17.5.1.69 LISTVIEW_SetTextAlign() 1614
20.17.5.1.70 LISTVIEW_SetTextColor() 1615
20.17.5.1.71 LISTVIEW_SetUserData() 1616
20.17.5.1.72 LISTVIEW_SetUserDataRow() 1617
20.17.5.1.73 LISTVIEW_SetWrapMode() 1618
20.17.5.2 Defines 1619
20.17.5.2.1 LISTVIEW color indexes 1619
20.17.6 Example 1620
20.18 LISTWHEEL: Listwheel widget 1621
20.18.1 Configuration options 1621
20.18.2 Predefined IDs 1621
20.18.3 Notification codes 1622
20.18.4 Keyboard reaction 1622
20.18.5 LISTWHEEL API 1622
20.18.5.1 Functions 1624
20.18.5.1.1 LISTWHEEL_AddString() 1624
20.18.5.1.2 LISTWHEEL_CreateEx() 1625
20.18.5.1.3 LISTWHEEL_CreateIndirect() 1626
20.18.5.1.4 LISTWHEEL_CreateUser() 1627
20.18.5.1.5 LISTWHEEL_GetBkColor() 1628
20.18.5.1.6 LISTWHEEL_GetFont() 1629
20.18.5.1.7 LISTWHEEL_GetItemFromPos() 1630
20.18.5.1.8 LISTWHEEL_GetItemText() 1631
20.18.5.1.9 LISTWHEEL_GetLBorder() 1632
20.18.5.1.10 LISTWHEEL_GetLineHeight() 1633
20.18.5.1.11 LISTWHEEL_GetNumItems() 1634
20.18.5.1.12 LISTWHEEL_GetPos() 1635
20.18.5.1.13 LISTWHEEL_GetRBorder() 1636
20.18.5.1.14 LISTWHEEL_GetSel() 1637
20.18.5.1.15 LISTWHEEL_GetSnapPosition() 1638
20.18.5.1.16 LISTWHEEL_GetTextAlign() 1639
20.18.5.1.17 LISTWHEEL_GetTextColor() 1640
20.18.5.1.18 LISTWHEEL_GetUserData() 1641
20.18.5.1.19 LISTWHEEL_IsMoving() 1642
20.18.5.1.20 LISTWHEEL_MoveToPos() 1643
20.18.5.1.21 LISTWHEEL_OwnerDraw() 1644
20.18.5.1.22 LISTWHEEL_SetBkColor() 1645

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.23 LISTWHEEL_SetDeceleration() 1646
20.18.5.1.24 LISTWHEEL_SetFont() 1647
20.18.5.1.25 LISTWHEEL_SetLBorder() 1648
20.18.5.1.26 LISTWHEEL_SetLineHeight() 1649
20.18.5.1.27 LISTWHEEL_SetOwnerDraw() 1650
20.18.5.1.28 LISTWHEEL_SetPos() 1651
20.18.5.1.29 LISTWHEEL_SetRBorder() 1652
20.18.5.1.30 LISTWHEEL_SetSel() 1653
20.18.5.1.31 LISTWHEEL_SetSnapPosition() 1654
20.18.5.1.32 LISTWHEEL_SetText() 1655
20.18.5.1.33 LISTWHEEL_SetTextAlign() 1656
20.18.5.1.34 LISTWHEEL_SetTextColor() 1657
20.18.5.1.35 LISTWHEEL_SetTimerPeriod() 1658
20.18.5.1.36 LISTWHEEL_SetUserData() 1659
20.18.5.1.37 LISTWHEEL_SetVelocity() 1660
20.18.5.2 Defines 1661
20.18.5.2.1 LISTWHEEL color indexes 1661
20.19 MENU: Menu widget 1662
20.19.1 Menu messages 1662
20.19.1.1 WM_MENU 1663
20.19.2 Configuration options 1663
20.19.3 Keyboard reaction 1664
20.19.4 MENU API 1665
20.19.4.1 Functions 1667
20.19.4.1.1 MENU_AddItem() 1667
20.19.4.1.2 MENU_Attach() 1668
20.19.4.1.3 MENU_CreateEx() 1669
20.19.4.1.4 MENU_CreateIndirect() 1670
20.19.4.1.5 MENU_CreateUser() 1671
20.19.4.1.6 MENU_DeleteItem() 1672
20.19.4.1.7 MENU_DisableItem() 1673
20.19.4.1.8 MENU_EnableItem() 1674
20.19.4.1.9 MENU_GetBkColor() 1675
20.19.4.1.10 MENU_GetDefaultBkColor() 1676
20.19.4.1.11 MENU_GetDefaultBorderSize() 1677
20.19.4.1.12 MENU_GetDefaultEffect() 1678
20.19.4.1.13 MENU_GetDefaultFont() 1679
20.19.4.1.14 MENU_GetDefaultTextColor() 1680
20.19.4.1.15 MENU_GetFont() 1681
20.19.4.1.16 MENU_GetItem() 1682
20.19.4.1.17 MENU_GetItemText() 1683
20.19.4.1.18 MENU_GetNumItems() 1684
20.19.4.1.19 MENU_GetOwner() 1685
20.19.4.1.20 MENU_GetTextColor() 1686
20.19.4.1.21 MENU_GetUserData() 1687
20.19.4.1.22 MENU_InsertItem() 1688
20.19.4.1.23 MENU_Popup() 1689
20.19.4.1.24 MENU_SetBkColor() 1690
20.19.4.1.25 MENU_SetBorderSize() 1691
20.19.4.1.26 MENU_SetDefaultBkColor() 1692
20.19.4.1.27 MENU_SetDefaultBorderSize() 1693
20.19.4.1.28 MENU_SetDefaultEffect() 1694
20.19.4.1.29 MENU_SetDefaultFont() 1695
20.19.4.1.30 MENU_SetDefaultTextColor() 1696
20.19.4.1.31 MENU_SetFont() 1697
20.19.4.1.32 MENU_SetItem() 1698
20.19.4.1.33 MENU_SetOwner() 1699
20.19.4.1.34 MENU_SetSel() 1700
20.19.4.1.35 MENU_SetTextColor() 1701
20.19.4.1.36 MENU_SetUserData() 1702

 © 2020 SEGGER Microcontroller GmbH

20.19.4.2 Data structures 1703
20.19.4.2.1 MENU_ITEM_DATA 1703
20.19.4.2.2 MENU_MSG_DATA 1704
20.19.4.3 Defines 1705
20.19.4.3.1 MENU border indexes 1705
20.19.4.3.2 MENU color indexes 1706
20.19.4.3.3 MENU create flags 1707
20.19.4.3.4 MENU item flags 1708
20.19.4.3.5 MENU message types 1709
20.19.5 Example 1710
20.20 MULTIEDIT: Multi line text widget 1711
20.20.1 Configuration options 1711
20.20.2 Predefined IDs 1711
20.20.3 Notification codes 1712
20.20.4 Keyboard reaction 1712
20.20.5 MULTIEDIT API 1712
20.20.5.1 Functions 1715
20.20.5.1.1 MULTIEDIT_AddKey() 1715
20.20.5.1.2 MULTIEDIT_AddText() 1716
20.20.5.1.3 MULTIEDIT_Create() 1717
20.20.5.1.4 MULTIEDIT_CreateEx() 1718
20.20.5.1.5 MULTIEDIT_CreateIndirect() 1719
20.20.5.1.6 MULTIEDIT_CreateUser() 1720
20.20.5.1.7 MULTIEDIT_EnableBlink() 1721
20.20.5.1.8 MULTIEDIT_GetBkColor() 1722
20.20.5.1.9 MULTIEDIT_GetCursorCharPos() 1723
20.20.5.1.10 MULTIEDIT_GetCursorPixelPos() 1724
20.20.5.1.11 MULTIEDIT_GetFont() 1725
20.20.5.1.12 MULTIEDIT_GetNumChars() 1726
20.20.5.1.13 MULTIEDIT_GetPrompt() 1727
20.20.5.1.14 MULTIEDIT_GetText() 1728
20.20.5.1.15 MULTIEDIT_GetTextColor() 1729
20.20.5.1.16 MULTIEDIT_GetTextFromLine() 1730
20.20.5.1.17 MULTIEDIT_GetTextFromPos() 1731
20.20.5.1.18 MULTIEDIT_GetTextSize() 1732
20.20.5.1.19 MULTIEDIT_GetUserData() 1733
20.20.5.1.20 MULTIEDIT_SetAutoScrollH() 1734
20.20.5.1.21 MULTIEDIT_SetAutoScrollV() 1735
20.20.5.1.22 MULTIEDIT_SetBkColor() 1736
20.20.5.1.23 MULTIEDIT_SetBufferSize() 1737
20.20.5.1.24 MULTIEDIT_SetCursorCharPos() 1738
20.20.5.1.25 MULTIEDIT_SetCursorOffset() 1739
20.20.5.1.26 MULTIEDIT_SetCursorPixelPos() 1740
20.20.5.1.27 MULTIEDIT_SetFocusable() 1741
20.20.5.1.28 MULTIEDIT_SetFont() 1742
20.20.5.1.29 MULTIEDIT_SetHBorder() 1743
20.20.5.1.30 MULTIEDIT_SetInsertMode() 1744
20.20.5.1.31 MULTIEDIT_SetMaxNumChars() 1745
20.20.5.1.32 MULTIEDIT_SetPasswordMode() 1746
20.20.5.1.33 MULTIEDIT_SetPrompt() 1747
20.20.5.1.34 MULTIEDIT_SetReadOnly() 1748
20.20.5.1.35 MULTIEDIT_SetText() 1749
20.20.5.1.36 MULTIEDIT_SetTextAlign() 1750
20.20.5.1.37 MULTIEDIT_SetTextColor() 1751
20.20.5.1.38 MULTIEDIT_SetUserData() 1752
20.20.5.1.39 MULTIEDIT_SetWrapChar() 1753
20.20.5.1.40 MULTIEDIT_SetWrapNone() 1754
20.20.5.1.41 MULTIEDIT_SetWrapWord() 1755
20.20.5.1.42 MULTIEDIT_ShowCursor() 1756
20.20.5.2 Defines 1757

 © 2020 SEGGER Microcontroller GmbH

20.20.5.2.1 MULTIEDIT color indexes 1757
20.20.5.2.2 MULTIEDIT create flags 1758
20.20.6 Example 1759
20.21 MULTIPAGE: Multiple page widget 1760
20.21.1 Configuration options 1761
20.21.2 Predefined IDs 1761
20.21.3 Notification codes 1761
20.21.4 Keyboard reaction 1762
20.21.5 MULTIPAGE API 1762
20.21.5.1 Functions 1765
20.21.5.1.1 MULTIPAGE_AddEmptyPage() 1765
20.21.5.1.2 MULTIPAGE_AddPage() 1766
20.21.5.1.3 MULTIPAGE_AttachWindow() 1767
20.21.5.1.4 MULTIPAGE_CreateEx() 1768
20.21.5.1.5 MULTIPAGE_CreateIndirect() 1769
20.21.5.1.6 MULTIPAGE_CreateUser() 1770
20.21.5.1.7 MULTIPAGE_DeletePage() 1771
20.21.5.1.8 MULTIPAGE_DisablePage() 1772
20.21.5.1.9 MULTIPAGE_EnablePage() 1773
20.21.5.1.10 MULTIPAGE_EnableScrollbar() 1774
20.21.5.1.11 MULTIPAGE_GetBkColor() 1775
20.21.5.1.12 MULTIPAGE_GetDefaultAlign() 1776
20.21.5.1.13 MULTIPAGE_GetDefaultBkColor() 1777
20.21.5.1.14 MULTIPAGE_GetDefaultFont() 1778
20.21.5.1.15 MULTIPAGE_GetDefaultTextColor() 1779
20.21.5.1.16 MULTIPAGE_GetFont() 1780
20.21.5.1.17 MULTIPAGE_GetNumTabs() 1781
20.21.5.1.18 MULTIPAGE_GetPageText() 1782
20.21.5.1.19 MULTIPAGE_GetSelection() 1783
20.21.5.1.20 MULTIPAGE_GetTabHeight() 1784
20.21.5.1.21 MULTIPAGE_GetTabWidth() 1785
20.21.5.1.22 MULTIPAGE_GetTextColor() 1786
20.21.5.1.23 MULTIPAGE_GetUserData() 1787
20.21.5.1.24 MULTIPAGE_GetWindow() 1788
20.21.5.1.25 MULTIPAGE_IsPageEnabled() 1789
20.21.5.1.26 MULTIPAGE_SelectPage() 1790
20.21.5.1.27 MULTIPAGE_SetAlign() 1791
20.21.5.1.28 MULTIPAGE_SetBitmap() 1792
20.21.5.1.29 MULTIPAGE_SetBitmapEx() 1793
20.21.5.1.30 MULTIPAGE_SetBkColor() 1794
20.21.5.1.31 MULTIPAGE_SetDefaultAlign() 1795
20.21.5.1.32 MULTIPAGE_SetDefaultBkColor() 1796
20.21.5.1.33 MULTIPAGE_SetDefaultBorderSizeX() 1797
20.21.5.1.34 MULTIPAGE_SetDefaultBorderSizeY() 1798
20.21.5.1.35 MULTIPAGE_SetDefaultFont() 1799
20.21.5.1.36 MULTIPAGE_SetDefaultTextColor() 1800
20.21.5.1.37 MULTIPAGE_SetFont() 1801
20.21.5.1.38 MULTIPAGE_SetRotation() 1802
20.21.5.1.39 MULTIPAGE_SetTabHeight() 1803
20.21.5.1.40 MULTIPAGE_SetTabWidth() 1804
20.21.5.1.41 MULTIPAGE_SetText() 1805
20.21.5.1.42 MULTIPAGE_SetTextAlign() 1806
20.21.5.1.43 MULTIPAGE_SetTextColor() 1807
20.21.5.1.44 MULTIPAGE_SetUserData() 1808
20.21.5.2 Defines 1809
20.21.5.2.1 MULTIPAGE alignment flags 1809
20.21.5.2.2 MULTIPAGE bitmap indexes 1810
20.21.5.2.3 MULTIPAGE color indexes 1811
20.21.5.2.4 MULTIPAGE create flags 1812
20.21.6 Example 1813

 © 2020 SEGGER Microcontroller GmbH

20.22 PROGBAR: Progress bar widget 1814
20.22.1 Configuration options 1814
20.22.2 Predefined IDs 1814
20.22.3 Keyboard reaction 1814
20.22.4 PROGBAR API 1814
20.22.4.1 Functions 1816
20.22.4.1.1 PROGBAR_Create() 1816
20.22.4.1.2 PROGBAR_CreateAsChild() 1817
20.22.4.1.3 PROGBAR_CreateEx() 1818
20.22.4.1.4 PROGBAR_CreateIndirect() 1819
20.22.4.1.5 PROGBAR_CreateUser() 1820
20.22.4.1.6 PROGBAR_GetBarColor() 1821
20.22.4.1.7 PROGBAR_GetFont() 1822
20.22.4.1.8 PROGBAR_GetMinMax() 1823
20.22.4.1.9 PROGBAR_GetTextColor() 1824
20.22.4.1.10 PROGBAR_GetUserData() 1825
20.22.4.1.11 PROGBAR_GetValue() 1826
20.22.4.1.12 PROGBAR_SetBarColor() 1827
20.22.4.1.13 PROGBAR_SetFont() 1828
20.22.4.1.14 PROGBAR_SetMinMax() 1829
20.22.4.1.15 PROGBAR_SetText() 1830
20.22.4.1.16 PROGBAR_SetTextAlign() 1831
20.22.4.1.17 PROGBAR_SetTextColor() 1832
20.22.4.1.18 PROGBAR_SetTextPos() 1833
20.22.4.1.19 PROGBAR_SetUserData() 1834
20.22.4.1.20 PROGBAR_SetValue() 1835
20.22.4.2 Defines 1836
20.22.4.2.1 PROGBAR create flags 1836
20.22.5 Examples 1837
20.23 QRCODE: QR code widget 1838
20.23.1 Configuration options 1838
20.23.2 Predefined IDs 1838
20.23.3 Keyboard reaction 1838
20.23.4 QRCODE API 1838
20.23.4.1 Functions 1840
20.23.4.1.1 QRCODE_CreateIndirect() 1840
20.23.4.1.2 QRCODE_CreateUser() 1841
20.23.4.1.3 QRCODE_SetEccLevel() 1842
20.23.4.1.4 QRCODE_SetNumModules 1843
20.23.4.1.5 QRCODE_SetPixelSize() 1844
20.23.4.1.6 QRCODE_SetText() 1845
20.23.4.1.7 QRCODE_SetWiFiText() 1846
20.23.4.2 Defines 1847
20.23.4.2.1 QRCODE WiFi encryption types 1847
20.24 RADIO: Radio button widget 1848
20.24.1 Configuration options 1848
20.24.2 Predefined IDs 1848
20.24.3 Notification codes 1849
20.24.4 Keyboard reaction 1849
20.24.5 RADIO API 1849
20.24.5.1 Functions 1851
20.24.5.1.1 RADIO_Create() 1851
20.24.5.1.2 RADIO_CreateEx() 1852
20.24.5.1.3 RADIO_CreateIndirect() 1853
20.24.5.1.4 RADIO_CreateUser() 1854
20.24.5.1.5 RADIO_Dec() 1855
20.24.5.1.6 RADIO_GetBkColor() 1856
20.24.5.1.7 RADIO_GetDefaultFont() 1857
20.24.5.1.8 RADIO_GetDefaultTextColor() 1858
20.24.5.1.9 RADIO_GetFocusColor() 1859

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.10 RADIO_GetFont() 1860
20.24.5.1.11 RADIO_GetImage() 1861
20.24.5.1.12 RADIO_GetNumItems() 1862
20.24.5.1.13 RADIO_GetSpacing() 1863
20.24.5.1.14 RADIO_GetText() 1864
20.24.5.1.15 RADIO_GetTextColor() 1865
20.24.5.1.16 RADIO_GetUserData() 1866
20.24.5.1.17 RADIO_GetValue() 1867
20.24.5.1.18 RADIO_Inc() 1868
20.24.5.1.19 RADIO_SetBkColor() 1869
20.24.5.1.20 RADIO_SetDefaultFocusColor() 1870
20.24.5.1.21 RADIO_SetDefaultFont() 1871
20.24.5.1.22 RADIO_SetDefaultImage() 1872
20.24.5.1.23 RADIO_SetDefaultTextColor() 1873
20.24.5.1.24 RADIO_SetFocusColor() 1874
20.24.5.1.25 RADIO_SetFont() 1875
20.24.5.1.26 RADIO_SetGroupId() 1876
20.24.5.1.27 RADIO_SetImage() 1877
20.24.5.1.28 RADIO_SetSpacing() 1878
20.24.5.1.29 RADIO_SetText() 1879
20.24.5.1.30 RADIO_SetTextColor() 1880
20.24.5.1.31 RADIO_SetUserData() 1881
20.24.5.1.32 RADIO_SetValue() 1882
20.24.5.2 Defines 1883
20.24.5.2.1 RADIO bitmap indexes 1883
20.24.6 Examples 1884
20.25 ROTARY: Rotary widget 1885
20.25.1 Configuration options 1885
20.25.2 Predefined IDs 1885
20.25.3 Notification codes 1886
20.25.4 Keyboard reaction 1886
20.25.5 ROTARY API 1886
20.25.5.1 ROTARY_AddAngle() 1888
20.25.5.2 ROTARY_AddValue() 1889
20.25.5.3 ROTARY_CreateEx() 1890
20.25.5.4 ROTARY_CreateIndirect() 1891
20.25.5.5 ROTARY_CreateUser() 1892
20.25.5.6 ROTARY_GetAngle() 1893
20.25.5.7 ROTARY_GetImageSize() 1894
20.25.5.8 ROTARY_GetMarkerSize() 1895
20.25.5.9 ROTARY_GetUserData() 1896
20.25.5.10 ROTARY_GetValue() 1897
20.25.5.11 ROTARY_SetAngle() 1898
20.25.5.12 ROTARY_SetBitmap() 1899
20.25.5.13 ROTARY_SetDoRotate() 1900
20.25.5.14 ROTARY_SetMarker() 1901
20.25.5.15 ROTARY_SetOffset() 1902
20.25.5.16 ROTARY_SetPeriod() 1903
20.25.5.17 ROTARY_SetRadius() 1904
20.25.5.18 ROTARY_SetRange() 1905
20.25.5.19 ROTARY_SetSnap() 1906
20.25.5.20 ROTARY_SetTickSize() 1907
20.25.5.21 ROTARY_SetUserData() 1908
20.25.5.22 ROTARY_SetValue() 1909
20.25.5.23 ROTARY_SetValueRange() 1910
20.26 SCROLLBAR: Scroll bar widget 1911
20.26.1 Configuration options 1911
20.26.2 Predefined IDs 1911
20.26.3 Notification codes 1911
20.26.4 Keyboard reaction 1912

 © 2020 SEGGER Microcontroller GmbH

20.26.5 SCROLLBAR API 1912
20.26.5.1 Functions 1914
20.26.5.1.1 SCROLLBAR_AddValue() 1914
20.26.5.1.2 SCROLLBAR_Create() 1915
20.26.5.1.3 SCROLLBAR_CreateAttached() 1916
20.26.5.1.4 SCROLLBAR_CreateEx() 1917
20.26.5.1.5 SCROLLBAR_CreateIndirect() 1918
20.26.5.1.6 SCROLLBAR_CreateUser() 1919
20.26.5.1.7 SCROLLBAR_Dec() 1920
20.26.5.1.8 SCROLLBAR_GetColor() 1921
20.26.5.1.9 SCROLLBAR_GetDefaultWidth() 1922
20.26.5.1.10 SCROLLBAR_GetNumItems() 1923
20.26.5.1.11 SCROLLBAR_GetPageSize() 1924
20.26.5.1.12 SCROLLBAR_GetThumbSizeMin() 1925
20.26.5.1.13 SCROLLBAR_GetUserData() 1926
20.26.5.1.14 SCROLLBAR_GetValue() 1927
20.26.5.1.15 SCROLLBAR_Inc() 1928
20.26.5.1.16 SCROLLBAR_SetColor() 1929
20.26.5.1.17 SCROLLBAR_SetDefaultColor() 1930
20.26.5.1.18 SCROLLBAR_SetDefaultWidth() 1931
20.26.5.1.19 SCROLLBAR_SetNumItems() 1932
20.26.5.1.20 SCROLLBAR_SetPageSize() 1933
20.26.5.1.21 SCROLLBAR_SetState() 1934
20.26.5.1.22 SCROLLBAR_SetThumbSizeMin() 1935
20.26.5.1.23 SCROLLBAR_SetUserData() 1936
20.26.5.1.24 SCROLLBAR_SetValue() 1937
20.26.5.1.25 SCROLLBAR_SetWidth() 1938
20.26.5.2 Defines 1939
20.26.5.2.1 SCROLLBAR color indexes 1939
20.26.5.2.2 SCROLLBAR create flags 1940
20.26.6 Example 1941
20.27 SLIDER: Slider widget 1942
20.27.1 Configuration options 1942
20.27.2 Predefined IDs 1942
20.27.3 Notification codes 1942
20.27.3.1 Keyboard reaction 1943
20.27.4 SLIDER API 1943
20.27.4.1 Functions 1945
20.27.4.1.1 SLIDER_Create() 1945
20.27.4.1.2 SLIDER_CreateEx() 1946
20.27.4.1.3 SLIDER_CreateIndirect() 1947
20.27.4.1.4 SLIDER_CreateUser() 1948
20.27.4.1.5 SLIDER_Dec() 1949
20.27.4.1.6 SLIDER_EnableFocusRect() 1950
20.27.4.1.7 SLIDER_GetBkColor() 1951
20.27.4.1.8 SLIDER_GetFocusColor() 1952
20.27.4.1.9 SLIDER_GetRange() 1953
20.27.4.1.10 SLIDER_GetUserData() 1954
20.27.4.1.11 SLIDER_GetValue() 1955
20.27.4.1.12 SLIDER_Inc() 1956
20.27.4.1.13 SLIDER_SetBkColor() 1957
20.27.4.1.14 SLIDER_SetDefaultFocusColor() 1958
20.27.4.1.15 SLIDER_SetFocusColor() 1959
20.27.4.1.16 SLIDER_SetInvertDir() 1960
20.27.4.1.17 SLIDER_SetNumTicks() 1961
20.27.4.1.18 SLIDER_SetRange() 1962
20.27.4.1.19 SLIDER_SetUserData() 1963
20.27.4.1.20 SLIDER_SetValue() 1964
20.27.4.1.21 SLIDER_SetWidth() 1965
20.27.4.2 Defines 1966

 © 2020 SEGGER Microcontroller GmbH

20.27.4.2.1 SLIDER create flags 1966
20.27.5 Example 1967
20.28 SPINBOX: Spinning box widget 1968
20.28.1 Configuration options 1968
20.28.2 Predefined IDs 1969
20.28.3 Notification codes 1969
20.28.4 Keyboard reaction 1970
20.28.5 SPINBOX API 1970
20.28.5.1 Functions 1972
20.28.5.1.1 SPINBOX_CreateEx() 1972
20.28.5.1.2 SPINBOX_CreateIndirect() 1973
20.28.5.1.3 SPINBOX_CreateUser() 1974
20.28.5.1.4 SPINBOX_EnableBlink() 1975
20.28.5.1.5 SPINBOX_GetBkColor() 1976
20.28.5.1.6 SPINBOX_GetButtonBkColor() 1977
20.28.5.1.7 SPINBOX_GetDefaultButtonSize() 1978
20.28.5.1.8 SPINBOX_GetEditHandle() 1979
20.28.5.1.9 SPINBOX_GetFont() 1980
20.28.5.1.10 SPINBOX_GetTextColor() 1981
20.28.5.1.11 SPINBOX_GetUserData() 1982
20.28.5.1.12 SPINBOX_GetValue() 1983
20.28.5.1.13 SPINBOX_SetBkColor() 1984
20.28.5.1.14 SPINBOX_SetButtonBkColor() 1985
20.28.5.1.15 SPINBOX_SetButtonSize() 1986
20.28.5.1.16 SPINBOX_SetDefaultButtonSize() 1987
20.28.5.1.17 SPINBOX_SetEdge() 1988
20.28.5.1.18 SPINBOX_SetEditMode() 1989
20.28.5.1.19 SPINBOX_SetFont() 1990
20.28.5.1.20 SPINBOX_SetRange() 1991
20.28.5.1.21 SPINBOX_SetStep() 1992
20.28.5.1.22 SPINBOX_SetTextColor() 1993
20.28.5.1.23 SPINBOX_SetTimerPeriod() 1994
20.28.5.1.24 SPINBOX_SetUserData() 1995
20.28.5.1.25 SPINBOX_SetValue() 1996
20.28.5.2 Defines 1997
20.28.5.2.1 SPINBOX color indexes 1997
20.28.5.2.2 SPINBOX edge flags 1998
20.28.5.2.3 SPINBOX edit mode flags 1999
20.28.5.2.4 SPINBOX timer indexes 2000
20.28.6 Example 2001
20.29 SWIPELIST: Swipelist widget 2002
20.29.1 Structure of the SWIPELIST widget 2002
20.29.2 Difference between separator items and items 2005
20.29.3 Configuration options 2005
20.29.4 Predefined IDs 2006
20.29.5 Notification codes 2006
20.29.6 SWIPELIST API 2007
20.29.6.1 Functions 2010
20.29.6.1.1 SWIPELIST_AddItem() 2010
20.29.6.1.2 SWIPELIST_AddItemText() 2011
20.29.6.1.3 SWIPELIST_AddSepItem() 2012
20.29.6.1.4 SWIPELIST_CreateEx() 2013
20.29.6.1.5 SWIPELIST_CreateIndirect() 2014
20.29.6.1.6 SWIPELIST_CreateUser() 2015
20.29.6.1.7 SWIPELIST_DeleteItem() 2016
20.29.6.1.8 SWIPELIST_GetBitmap() 2017
20.29.6.1.9 SWIPELIST_GetBitmapSpace() 2018
20.29.6.1.10 SWIPELIST_GetBkColor() 2019
20.29.6.1.11 SWIPELIST_GetBorderSize() 2020
20.29.6.1.12 SWIPELIST_GetDefaultBitmapSpace() 2021

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.13 SWIPELIST_GetDefaultBkColor() 2022
20.29.6.1.14 SWIPELIST_GetDefaultBorderSize() 2023
20.29.6.1.15 SWIPELIST_GetDefaultFont() 2024
20.29.6.1.16 SWIPELIST_GetDefaultSepColor() 2025
20.29.6.1.17 SWIPELIST_GetDefaultSepSize() 2026
20.29.6.1.18 SWIPELIST_GetDefaultTextColor() 2027
20.29.6.1.19 SWIPELIST_GetDefaultTextAlign() 2028
20.29.6.1.20 SWIPELIST_GetDefaultThreshold() 2029
20.29.6.1.21 SWIPELIST_GetFont() 2030
20.29.6.1.22 SWIPELIST_GetItemSize() 2031
20.29.6.1.23 SWIPELIST_GetItemUserData() 2032
20.29.6.1.24 SWIPELIST_GetNumItems() 2033
20.29.6.1.25 SWIPELIST_GetNumText() 2034
20.29.6.1.26 SWIPELIST_GetReleasedItem() 2035
20.29.6.1.27 SWIPELIST_GetScrollPos() 2036
20.29.6.1.28 SWIPELIST_GetSelItem() 2037
20.29.6.1.29 SWIPELIST_GetSepColor() 2038
20.29.6.1.30 SWIPELIST_GetSepSize() 2039
20.29.6.1.31 SWIPELIST_GetText() 2040
20.29.6.1.32 SWIPELIST_GetTextAlign() 2041
20.29.6.1.33 SWIPELIST_GetTextColor() 2042
20.29.6.1.34 SWIPELIST_GetThreshold() 2043
20.29.6.1.35 SWIPELIST_GetUserData() 2044
20.29.6.1.36 SWIPELIST_IsSepItem() 2045
20.29.6.1.37 SWIPELIST_ItemAttachWindow() 2046
20.29.6.1.38 SWIPELIST_ItemDetachWindow() 2047
20.29.6.1.39 SWIPELIST_OwnerDraw() 2048
20.29.6.1.40 SWIPELIST_SetAttachedWindowPos() 2049
20.29.6.1.41 SWIPELIST_SetBitmap() 2050
20.29.6.1.42 SWIPELIST_SetBitmapSpace() 2051
20.29.6.1.43 SWIPELIST_SetBkColor() 2052
20.29.6.1.44 SWIPELIST_SetBorderSize() 2053
20.29.6.1.45 SWIPELIST_SetDefaultBitmapSpace() 2054
20.29.6.1.46 SWIPELIST_SetDefaultBkColor() 2055
20.29.6.1.47 SWIPELIST_SetDefaultBorderSize() 2056
20.29.6.1.48 SWIPELIST_SetDefaultFont() 2057
20.29.6.1.49 SWIPELIST_SetDefaultSepColor() 2058
20.29.6.1.50 SWIPELIST_SetDefaultSepSize() 2059
20.29.6.1.51 SWIPELIST_SetDefaultTextColor() 2060
20.29.6.1.52 SWIPELIST_SetDefaultTextAlign() 2061
20.29.6.1.53 SWIPELIST_SetDefaultThreshold() 2062
20.29.6.1.54 SWIPELIST_SetFont() 2063
20.29.6.1.55 SWIPELIST_SetItemSize() 2064
20.29.6.1.56 SWIPELIST_SetItemUserData() 2065
20.29.6.1.57 SWIPELIST_SetOwnerDraw() 2066
20.29.6.1.58 SWIPELIST_SetScrollPos() 2067
20.29.6.1.59 SWIPELIST_SetScrollPosItem() 2068
20.29.6.1.60 SWIPELIST_SetSepColor() 2069
20.29.6.1.61 SWIPELIST_SetSepSize() 2070
20.29.6.1.62 SWIPELIST_SetText() 2071
20.29.6.1.63 SWIPELIST_SetTextAlign() 2072
20.29.6.1.64 SWIPELIST_SetTextColor() 2073
20.29.6.1.65 SWIPELIST_SetThreshold() 2074
20.29.6.1.66 SWIPELIST_SetUserData() 2075
20.29.6.2 Defines 2076
20.29.6.2.1 SWIPELIST background color indexes 2076
20.29.6.2.2 SWIPELIST bitmap alignment flags 2077
20.29.6.2.3 SWIPELIST border indexes 2078
20.29.6.2.4 SWIPELIST font indexes 2079
20.29.6.2.5 SWIPELIST item color indexes 2080

 © 2020 SEGGER Microcontroller GmbH

20.29.7 Examples 2081
20.30 SWITCH: Switch widget 2082
20.30.1 Configuration options 2082
20.30.2 Predefined IDs 2082
20.30.3 Notification codes 2082
20.30.4 SWITCH API 2083
20.30.4.1 Functions 2084
20.30.4.1.1 SWITCH_AnimState() 2084
20.30.4.1.2 SWITCH_CreateIndirect() 2085
20.30.4.1.3 SWITCH_CreateUser() 2086
20.30.4.1.4 SWITCH_GetDefaultFont() 2087
20.30.4.1.5 SWITCH_GetDefaultPeriod() 2088
20.30.4.1.6 SWITCH_GetDefaultTextColor() 2089
20.30.4.1.7 SWITCH_GetState() 2090
20.30.4.1.8 SWITCH_GetUserData() 2091
20.30.4.1.9 SWITCH_SetBitmap() 2092
20.30.4.1.10 SWITCH_SetDefaultFont() 2093
20.30.4.1.11 SWITCH_SetDefaultPeriod() 2094
20.30.4.1.12 SWITCH_SetDefaultTextColor() 2095
20.30.4.1.13 SWITCH_SetFont() 2096
20.30.4.1.14 SWITCH_SetMode() 2097
20.30.4.1.15 SWITCH_SetPeriod() 2098
20.30.4.1.16 SWITCH_SetState() 2099
20.30.4.1.17 SWITCH_SetText() 2100
20.30.4.1.18 SWITCH_SetTextColor() 2101
20.30.4.1.19 SWITCH_SetUserData() 2102
20.30.4.1.20 SWITCH_Toggle() 2103
20.30.4.2 Defines 2104
20.30.4.2.1 SWITCH bitmap indexes 2104
20.30.4.2.2 SWITCH color indexes 2105
20.30.4.2.3 SWITCH modes 2106
20.30.4.2.4 SWITCH text indexes 2107
20.30.4.2.5 SWITCH states 2108
20.31 TEXT: Text widget 2109
20.31.1 Configuration options 2109
20.31.2 Predefined IDs 2109
20.31.3 Notification codes 2109
20.31.4 Keyboard reaction 2110
20.31.5 TEXT API 2110
20.31.5.1 Functions 2112
20.31.5.1.1 TEXT_Create() 2112
20.31.5.1.2 TEXT_CreateAsChild() 2113
20.31.5.1.3 TEXT_CreateEx() 2114
20.31.5.1.4 TEXT_CreateIndirect() 2115
20.31.5.1.5 TEXT_CreateUser() 2116
20.31.5.1.6 TEXT_GetBkColor() 2117
20.31.5.1.7 TEXT_GetDefaultFont() 2118
20.31.5.1.8 TEXT_GetDefaultRotation() 2119
20.31.5.1.9 TEXT_GetDefaultTextColor() 2120
20.31.5.1.10 TEXT_GetDefaultWrapMode() 2121
20.31.5.1.11 TEXT_GetFont() 2122
20.31.5.1.12 TEXT_GetNumLines() 2123
20.31.5.1.13 TEXT_GetRotation() 2124
20.31.5.1.14 TEXT_GetText() 2125
20.31.5.1.15 TEXT_GetTextAlign() 2126
20.31.5.1.16 TEXT_GetTextColor() 2127
20.31.5.1.17 TEXT_GetTextOffset() 2128
20.31.5.1.18 TEXT_GetUserData() 2129
20.31.5.1.19 TEXT_GetWrapMode() 2130
20.31.5.1.20 TEXT_SetBkColor() 2131

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.21 TEXT_SetDec() 2132
20.31.5.1.22 TEXT_SetDefaultFont() 2133
20.31.5.1.23 TEXT_SetDefaultRotation() 2134
20.31.5.1.24 TEXT_SetDefaultTextColor() 2135
20.31.5.1.25 TEXT_SetDefaultWrapMode() 2136
20.31.5.1.26 TEXT_SetFont() 2137
20.31.5.1.27 TEXT_SetRotation() 2138
20.31.5.1.28 TEXT_SetText() 2139
20.31.5.1.29 TEXT_SetTextAlign() 2140
20.31.5.1.30 TEXT_SetTextColor() 2141
20.31.5.1.31 TEXT_SetTextOffset() 2142
20.31.5.1.32 TEXT_SetUserData() 2143
20.31.5.1.33 TEXT_SetWrapMode() 2144
20.31.5.2 Defines 2145
20.31.5.2.1 TEXT create flags 2145
20.31.6 Examples 2146
20.32 TREEVIEW: Treeview widget 2147
20.32.1 Description of terms 2148
20.32.2 Configuration options 2148
20.32.3 Predefined IDs 2149
20.32.4 Notification codes 2149
20.32.5 Keyboard reaction 2149
20.32.6 TREEVIEW API 2150
20.32.6.1 Common routines 2153
20.32.6.1.1 TREEVIEW_AttachItem() 2153
20.32.6.1.2 TREEVIEW_CreateEx() 2154
20.32.6.1.3 TREEVIEW_CreateIndirect() 2155
20.32.6.1.4 TREEVIEW_CreateUser() 2156
20.32.6.1.5 TREEVIEW_DecSel() 2157
20.32.6.1.6 TREEVIEW_GetDefaultBkColor() 2158
20.32.6.1.7 TREEVIEW_GetDefaultFont() 2159
20.32.6.1.8 TREEVIEW_GetDefaultLineColor() 2160
20.32.6.1.9 TREEVIEW_GetDefaultTextColor() 2161
20.32.6.1.10 TREEVIEW_GetItem() 2162
20.32.6.1.11 TREEVIEW_GetSel() 2163
20.32.6.1.12 TREEVIEW_GetUserData() 2164
20.32.6.1.13 TREEVIEW_IncSel() 2165
20.32.6.1.14 TREEVIEW_InsertItem() 2166
20.32.6.1.15 TREEVIEW_ScrollToSel() 2167
20.32.6.1.16 TREEVIEW_SetAutoScrollH() 2168
20.32.6.1.17 TREEVIEW_SetAutoScrollV() 2169
20.32.6.1.18 TREEVIEW_SetBitmapOffset() 2170
20.32.6.1.19 TREEVIEW_SetBkColor() 2171
20.32.6.1.20 TREEVIEW_SetDefaultBkColor() 2172
20.32.6.1.21 TREEVIEW_SetDefaultFont() 2173
20.32.6.1.22 TREEVIEW_SetDefaultLineColor() 2174
20.32.6.1.23 TREEVIEW_SetDefaultTextColor() 2175
20.32.6.1.24 TREEVIEW_SetFont() 2176
20.32.6.1.25 TREEVIEW_SetHasLines() 2177
20.32.6.1.26 TREEVIEW_SetImage() 2178
20.32.6.1.27 TREEVIEW_SetIndent() 2179
20.32.6.1.28 TREEVIEW_SetLineColor() 2180
20.32.6.1.29 TREEVIEW_SetOwnerDraw() 2181
20.32.6.1.30 TREEVIEW_SetSel() 2182
20.32.6.1.31 TREEVIEW_SetSelMode() 2183
20.32.6.1.32 TREEVIEW_SetTextColor() 2184
20.32.6.1.33 TREEVIEW_SetTextIndent() 2185
20.32.6.1.34 TREEVIEW_SetUserData() 2186
20.32.6.2 Item related routines 2187
20.32.6.2.1 TREEVIEW_ITEM_Collapse() 2187

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.2 TREEVIEW_ITEM_CollapseAll() 2188
20.32.6.2.3 TREEVIEW_ITEM_Create() 2189
20.32.6.2.4 TREEVIEW_ITEM_Delete() 2190
20.32.6.2.5 TREEVIEW_ITEM_Detach() 2191
20.32.6.2.6 TREEVIEW_ITEM_Expand() 2192
20.32.6.2.7 TREEVIEW_ITEM_ExpandAll() 2193
20.32.6.2.8 TREEVIEW_ITEM_GetInfo() 2194
20.32.6.2.9 TREEVIEW_ITEM_GetText() 2195
20.32.6.2.10 TREEVIEW_ITEM_GetUserData() 2196
20.32.6.2.11 TREEVIEW_ITEM_SetImage() 2197
20.32.6.2.12 TREEVIEW_ITEM_SetText() 2198
20.32.6.2.13 TREEVIEW_ITEM_SetUserData() 2199
20.32.6.3 Data structures 2200
20.32.6.3.1 TREEVIEW_ITEM_INFO 2200
20.32.6.4 Defines 2201
20.32.6.4.1 TREEVIEW bitmap indexes 2201
20.32.6.4.2 TREEVIEW color indexes 2202
20.32.6.4.3 TREEVIEW create flags 2203
20.32.6.4.4 TREEVIEW item flags 2204
20.32.6.4.5 TREEVIEW position flags (get) 2205
20.32.6.4.6 TREEVIEW position flags (insert) 2206
20.32.6.4.7 TREEVIEW selection modes 2207
20.32.7 Example 2208
20.33 WINDOW: Window widget 2209
20.33.1 Configuration options 2209
20.33.2 Keyboard reaction 2209
20.33.3 WINDOW API 2209
20.33.3.1 WINDOW_CreateEx() 2210
20.33.3.2 WINDOW_CreateIndirect() 2211
20.33.3.3 WINDOW_CreateUser() 2212
20.33.3.4 WINDOW_GetUserData() 2213
20.33.3.5 WINDOW_SetBkColor() 2214
20.33.3.6 WINDOW_SetDefaultBkColor() 2215
20.33.3.7 WINDOW_SetUserData() 2216

21 GUI Builder 2217

21.1 Introduction 2218
21.2 Getting started 2219
21.3 Creating a dialog 2220
21.3.1 Selecting a parent widget 2220
21.3.2 Resizing and positioning in the editor 2220
21.3.3 Modifying the widget properties 2220
21.3.4 Adding additional functions to a widget 2221
21.3.5 Deleting a widget property 2222
21.3.6 Deleting a widget 2222
21.3.7 Deleting a widget 2222
21.4 Saving the current dialog(s) 2223
21.5 Output of the GUIBuilder 2224
21.6 Modifying the C files 2227
21.7 How to use the C files 2228

22 Dialogs 2229

22.1 Dialog basics 2230
22.2 Creating a dialog 2231
22.2.1 Resource table 2231
22.2.2 Dialog procedure 2231
22.2.2.1 Initializing the dialog 2232
22.2.3 Defining dialog behavior 2233
22.3 Dialog API 2235

 © 2020 SEGGER Microcontroller GmbH

22.3.1 GUI_CreateDialogBox() 2236
22.3.2 GUI_ExecCreatedDialog() 2237
22.3.3 GUI_ExecDialogBox() 2238
22.3.4 GUI_EndDialog() 2239
22.4 Common dialogs 2240
22.4.1 CALENDAR 2240
22.4.1.1 Notification codes 2240
22.4.1.2 Keyboard reaction 2240
22.4.1.3 CALENDAR_API 2241
22.4.1.3.1 Functions 2242
22.4.1.3.2 Data structures 2257
22.4.1.3.3 Defines 2258
22.4.2 CHOOSECOLOR 2261
22.4.2.1 Notification codes 2261
22.4.2.2 Keyboard reaction 2261
22.4.2.3 CHOOSECOLOR API 2261
22.4.2.3.1 Functions 2263
22.4.2.3.2 Defines 2270
22.4.3 CHOOSEFILE 2271
22.4.3.1 Configurating options 2271
22.4.3.2 Keyboard reaction 2271
22.4.3.3 Path- and file names 2271
22.4.3.4 CHOOSEFILE API 2271
22.4.3.4.1 Functions 2273
22.4.3.4.2 Data structures 2282
22.4.3.4.3 CHOOSEFILE_INFO 2282
22.4.3.4.4 Defines 2284
22.4.4 MESSAGEBOX 2285
22.4.4.1 Configuration options 2285
22.4.4.2 Keyboard reaction 2285
22.4.4.3 MESSAGEBOX API 2285
22.4.4.3.1 GUI_MessageBox() 2286
22.4.4.3.2 MESSAGEBOX_Create() 2287

23 Skinning 2288

23.1 What is a 'skin' 2289
23.2 From using API functions to skinning 2290
23.3 Skinnable widgets 2292
23.4 Using a skin 2293
23.4.1 Runtime configuration 2293
23.4.2 Compile time configuration 2293
23.5 Simple changes to the look of the 'Flex' skin 2295
23.6 Major changes to the 'Flex' skin 2296
23.6.1 The skinning callback mechanism 2296
23.6.2 Changing the look of the default skin 2296
23.6.3 List of commands 2298
23.7 General Skinning API 2299
23.7.1 <WIDGET>_DrawSkinFlex() 2300
23.7.2 <WIDGET>_GetSkinFlexProps() 2301
23.7.3 <WIDGET>_SetDefaultSkin() 2302
23.7.4 <WIDGET>_SetDefaultSkinClassic() 2303
23.7.5 <WIDGET>_SetSkin() 2304
23.7.6 <WIDGET>_SetSkinClassic() 2305
23.7.7 <WIDGET>_SetSkinFlexProps() 2306
23.8 BUTTON_SKIN_FLEX 2307
23.8.1 Configuration structure 2307
23.8.2 Configuration options 2307
23.8.3 Skinning API 2308
23.8.3.1 BUTTON_SetSkinFlexProps() 2309

 © 2020 SEGGER Microcontroller GmbH

23.8.4 List of commands 2310
23.8.4.1 WIDGET_ITEM_CREATE 2310
23.8.4.2 WIDGET_ITEM_DRAW_BACKGROUND 2310
23.8.4.3 WIDGET_ITEM_DRAW_BITMAP 2310
23.8.4.4 WIDGET_ITEM_DRAW_TEXT 2311
23.9 CHECKBOX_SKIN_FLEX 2312
23.9.1 Configuration structure 2312
23.9.2 Configuration options 2312
23.9.3 Skinning API 2313
23.9.3.1 CHECKBOX_GetSkinFlexButtonSize() 2314
23.9.3.2 CHECKBOX_SetSkinFlexButtonSize() 2315
23.9.3.3 CHECKBOX_SetSkinFlexProps() 2316
23.9.4 List of commands 2317
23.9.4.1 WIDGET_ITEM_CREATE 2317
23.9.4.2 WIDGET_ITEM_DRAW_BUTTON 2317
23.9.4.3 WIDGET_ITEM_DRAW_BITMAP 2317
23.9.4.4 WIDGET_ITEM_DRAW_FOCUS 2317
23.9.4.5 WIDGET_ITEM_DRAW_TEXT 2318
23.10 DROPDOWN_SKIN_FLEX 2319
23.10.1 Configuration structure 2319
23.10.2 Configuration options 2320
23.10.3 Skinning API 2320
23.10.3.1 DROPDOWN_SetSkinFlexProps() 2321
23.10.4 List of commands 2322
23.10.4.1 WIDGET_ITEM_CREATE 2322
23.10.4.2 WIDGET_ITEM_DRAW_ARROW 2322
23.10.4.3 WIDGET_ITEM_DRAW_BACKGROUND 2322
23.10.4.4 WIDGET_ITEM_DRAW_TEXT 2322
23.11 FRAMEWIN_SKIN_FLEX 2324
23.11.1 Configuration structure 2324
23.11.2 Configuration options 2325
23.11.3 Skinning API 2325
23.11.3.1 FRAMEWIN_SetSkinFlexProps() 2326
23.11.4 List of commands 2327
23.11.4.1 WIDGET_ITEM_CREATE 2327
23.11.4.2 WIDGET_ITEM_DRAW_BACKGROUND 2327
23.11.4.3 WIDGET_ITEM_DRAW_FRAME 2328
23.11.4.4 WIDGET_ITEM_DRAW_TEXT 2328
23.11.4.5 WIDGET_ITEM_GET_BORDERSIZE_L 2328
23.11.4.6 WIDGET_ITEM_GET_BORDERSIZE_R 2328
23.11.4.7 WIDGET_ITEM_GET_BORDERSIZE_T 2328
23.11.4.8 WIDGET_ITEM_GET_BORDERSIZE_B 2328
23.12 HEADER_SKIN_FLEX 2329
23.12.1 Configuration structure 2329
23.12.2 Configuration options 2329
23.12.3 Skinning API 2330
23.12.3.1 HEADER_SetSkinFlexProps() 2331
23.12.4 List of commands 2332
23.12.4.1 WIDGET_ITEM_CREATE 2332
23.12.4.2 WIDGET_ITEM_DRAW_ARROW 2332
23.12.4.3 WIDGET_ITEM_DRAW_BACKGROUND 2332
23.12.4.4 WIDGET_ITEM_DRAW_BITMAP 2332
23.12.4.5 WIDGET_ITEM_DRAW_OVERLAP 2333
23.12.4.6 Widget_ITEM_DRAW_TEXT 2333
23.13 MENU_SKIN_FLEX 2334
23.13.1 Configuration structure 2335
23.13.2 Configuration options 2335
23.13.3 Skinning API 2336
23.13.3.1 MENU_SetSkinFlexProps() 2337
23.13.3.2 MENU_SkinEnableArrow() 2338

 © 2020 SEGGER Microcontroller GmbH

23.13.4 List of commands 2339
23.13.4.1 WIDGET_ITEM_CREATE 2339
23.13.4.2 WIDGET_ITEM_DRAW_ARROW 2339
23.13.4.3 WIDGET_ITEM_DRAW_BACKGROUND 2339
23.13.4.4 WIDGET_ITEM_DRAW_FRAME 2340
23.13.4.5 WIDGET_ITEM_DRAW_TEXT 2340
23.14 MULTIPAGE_SKIN_FLEX 2341
23.14.1 Configuration structure 2341
23.14.2 Configuration options 2342
23.14.3 Skinning API 2342
23.14.3.1 MULTIPAGE_SetSkinFlexProps() 2343
23.14.4 List of commands 2344
23.14.4.1 WIDGET_ITEM_CREATE 2345
23.14.4.2 WIDGET_ITEM_DRAW_BACKGROUND 2345
23.14.4.3 WIDGET_ITEM_DRAW_FRAME 2345
23.14.4.4 WIDGET_ITEM_DRAW_TEXT 2345
23.15 PROGBAR_SKIN_FLEX 2346
23.15.1 Configuration structure 2346
23.15.2 Configuration options 2347
23.15.3 Skinning API 2347
23.15.3.1 PROGBAR_SetSkinFlexProps() 2348
23.15.4 List of commands 2349
23.15.4.1 WIDGET_ITEM_CREATE 2349
23.15.4.2 WIDGET_ITEM_DRAW_BACKGROUND 2349
23.15.4.3 WIDGET_ITEM_DRAW_FRAME 2350
23.15.4.4 WIDGET_ITEM_DRAW_TEXT 2350
23.16 RADIO_SKIN_FLEX 2351
23.16.1 Configuration structure 2351
23.16.2 Configuration options 2352
23.16.3 Skinning API 2352
23.16.3.1 RADIO_SetSkinFlexProps() 2353
23.16.4 List of commands 2354
23.16.4.1 WIDGET_ITEM_DRAW_FOCUS 2354
23.16.4.2 WIDGET_ITEM_DRAW_TEXT 2355
23.16.4.3 WIDGET_ITEM_GET_BUTTONSIZE 2355
23.17 SCROLLBAR_SKIN_FLEX 2356
23.17.1 Configuration structure 2356
23.17.2 Configuration options 2357
23.17.3 Skinning API 2357
23.17.3.1 SCROLLBAR_SetSkinFlexProps() 2358
23.17.4 List of commands 2359
23.17.4.1 WIDGET_ITEM_DRAW_BUTTON_L 2359
23.17.4.2 WIDGET_ITEM_DRAW_BUTTON_R 2359
23.17.4.3 WIDGET_ITEM_DRAW_OVERLAP 2360
23.17.4.4 WIDGET_ITEM_DRAW_SHAFT_L 2360
23.17.4.5 WIDGET_ITEM_DRAW_SHAFT_R 2360
23.17.4.6 WIDGET_ITEM_DRAW_THUMB 2361
23.17.4.7 WIDGET_ITEM_GET_BUTTONSIZE 2361
23.18 SLIDER_SKIN_FLEX 2362
23.18.1 Configuration structure 2362
23.18.2 Configuration options 2363
23.18.3 Skinning API 2363
23.18.3.1 SLIDER_SetSkinFlexProps() 2364
23.18.4 List of commands 2365
23.18.4.1 WIDGET_ITEM_CREATE 2365
23.18.4.2 WIDGET_ITEM_DRAW_FOCUS 2365
23.18.4.3 WIDGET_ITEM_DRAW_SHAFT 2365
23.18.4.4 WIDGET_ITEM_DRAW_THUMB 2366
23.18.4.5 WIDGET_ITEM_DRAW_TICKS 2366
23.19 SPINBOX_SKIN_FLEX 2367

 © 2020 SEGGER Microcontroller GmbH

23.19.1 Configuration options 2368
23.19.2 Skinning API 2368
23.19.2.1 SPINBOX_SetSkinFlexProps() 2369
23.19.3 List of commands 2370
23.19.3.1 WIDGET_ITEM_CREATE 2370
23.19.3.2 WIDGET_ITEM_DRAW_BACKGROUND 2370
23.19.3.3 WIDGET_ITEM_DRAW_BUTTON_U 2370
23.19.3.4 WIDGET_ITEM_DRAW_BUTTON_D 2370

24 Multiple Buffering 2372

24.1 How it works 2373
24.1.1 Double Buffering 2373
24.1.2 Triple Buffering 2373
24.2 Requirements 2375
24.3 Limitations 2376
24.4 Configuration 2377
24.4.1 LCD_X_Config() 2377
24.4.2 LCD_X_DisplayDriver() 2378
24.5 Automatic use of multiple buffers with the WM 2380
24.6 Multiple Buffering API 2381
24.6.1 GUI_MULTIBUF_Begin() 2382
24.6.2 GUI_MULTIBUF_BeginEx() 2383
24.6.3 GUI_MULTIBUF_Config() 2384
24.6.4 GUI_MULTIBUF_ConfigEx() 2385
24.6.5 GUI_MULTIBUF_Confirm() 2386
24.6.6 GUI_MULTIBUF_ConfirmEx() 2387
24.6.7 GUI_MULTIBUF_End() 2388
24.6.8 GUI_MULTIBUF_EndEx() 2389
24.6.9 GUI_MULTIBUF_GetNumBuffers() 2390
24.6.10 GUI_MULTIBUF_GetNumBuffersEx() 2391
24.6.11 GUI_MULTIBUF_UseSingleBuffer() 2392

25 Virtual screens / Virtual pages 2393

25.1 Introduction 2394
25.2 Requirements 2395
25.3 Configuration 2396
25.3.1 LCD_SetVSizeEx() 2397
25.4 Examples 2398
25.4.1 Basic example 2398
25.4.2 Real time example using the Window Manager 2398
25.4.3 Dialog example using the Window Manager 2399
25.4.4 Virtual screen API 2401
25.4.4.1 GUI_GetOrg() 2402
25.4.4.2 GUI_SetOrg() 2403

26 MultiLayer / MultiDisplay support 2404

26.1 Introduction 2405
26.1.1 Selecting a layer for drawing operations 2405
26.1.2 Selecting a layer for a window 2405
26.1.2.1 Moving a window from one layer to another 2406
26.2 Using MultiLayer support 2408
26.2.1 Transparency 2408
26.2.2 Alpha blending 2409
26.2.3 Hardware cursors 2410
26.2.4 MultiLayer example 2410
26.2.5 Configuring MultiLayer support 2411
26.3 Using MultiDisplay support 2412
26.3.1 Enabling MultiDisplay support 2412

 © 2020 SEGGER Microcontroller GmbH

26.3.2 Run-time screen rotation 2412
26.3.3 MultiDisplay example 2412
26.3.4 Configuring MultiDisplay support 2413
26.4 Using SoftLayers 2414
26.4.1 Using SoftLayers within a simulation environment 2414
26.4.2 Memory requirements 2415
26.4.3 Configuring SoftLayers 2415
26.5 MultiLayer API 2417
26.5.1 General MultiLayer functions 2418
26.5.1.1 GUI_AssignCursorLayer() 2418
26.5.1.2 GUI_GetLayerPosEx() 2419
26.5.1.3 GUI_SelectLayer() 2420
26.5.1.4 GUI_SetLayerAlphaEx() 2421
26.5.1.5 GUI_SetLayerPosEx() 2422
26.5.1.6 GUI_SetLayerSizeEx() 2423
26.5.1.7 GUI_SetLayerVisEx() 2424
26.5.1.8 LCD_GetNumLayers() 2425
26.5.2 SoftLayer specific functions 2426
26.5.2.1 GUI_SOFTLAYER_Enable() 2426
26.5.2.2 GUI_SOFTLAYER_Refresh() 2427
26.5.2.3 GUI_SOFTLAYER_SetCompositeColor() 2428
26.5.2.4 GUI_SOFTLAYER_MULTIBUF_Enable() 2429
26.5.3 Data structures 2430
26.5.3.1 GUI_SOFTLAYER_CONFIG 2430

27 Pointer Input Devices 2431

27.1 Description 2432
27.2 Pointer input device API 2433
27.2.1 GUI_PID_GetCurrentState() 2434
27.2.2 GUI_PID_GetState() 2435
27.2.3 GUI_PID_IsEmpty() 2436
27.2.4 GUI_PID_IsPressed() 2437
27.2.5 GUI_PID_SetHook() 2438
27.2.6 GUI_PID_StoreState() 2439
27.3 Mouse driver 2440
27.3.1 Generic mouse driver API 2440
27.3.1.1 GUI_MOUSE_GetState() 2441
27.3.1.2 GUI_MOUSE_StoreState() 2442
27.3.2 PS2 mouse driver 2443
27.3.2.1 Using the PS2 mouse driver 2443
27.3.2.2 PS2 mouse driver API 2443
27.3.2.2.1 GUI_MOUSE_DRIVER_PS2_Init() 2444
27.3.2.2.2 GUI_MOUSE_DRIVER_PS2_OnRx() 2445
27.4 Touch screen driver 2446
27.4.1 Generic touch screen API 2446
27.4.1.1 GUI_TOUCH_GetState() 2447
27.4.1.2 GUI_TOUCH_StoreState() 2448
27.4.1.3 GUI_TOUCH_StoreStateEx() 2449
27.4.2 The analog touch screen driver 2450
27.4.2.1 Setting up the analog touch screen 2450
27.4.2.2 Runtime calibration 2452
27.4.2.3 Hardware routines 2453
27.4.2.3.1 GUI_TOUCH_X_ActivateX() 2454
27.4.2.3.2 GUI_TOUCH_X_ActivateY() 2454
27.4.2.3.3 GUI_TOUCH_X_MeasureX() 2455
27.4.2.3.4 GUI_TOUCH_X_MeasureY() 2455
27.4.2.4 Driver API for analog touch screens 2457
27.4.2.4.1 GUI_TOUCH_Calibrate() 2458
27.4.2.4.2 GUI_TOUCH_Exec() 2459

 © 2020 SEGGER Microcontroller GmbH

27.4.2.4.3 GUI_TOUCH_GetxPhys() 2460
27.4.2.4.4 GUI_TOUCH_GetyPhys() 2460
27.4.2.4.5 GUI_TOUCH_SetOrientation() 2461
27.4.2.5 Configuring the analog touch-screen driver 2462
27.5 Touch screen Calibration 2463
27.5.1 Using calibration with the analog touch screen driver 2464
27.5.2 Using calibration with a custom touch screen driver 2464
27.5.3 Calibration API 2464
27.5.3.1 GUI_TOUCH_CalcCoefficients() 2466
27.5.3.2 GUI_TOUCH_CalibratePoint() 2467
27.5.3.3 GUI_TOUCH_EnableCalibration() 2468
27.5.3.4 GUI_TOUCH_TransformPoint() 2469
27.6 Joystick input example 2470

28 MultiTouch support (MT) 2472

28.1 Introduction 2473
28.2 Getting started 2474
28.3 Using basic buffer access 2475
28.4 Using gestures 2477
28.5 Window animation 2479
28.6 Basic buffer access API 2480
28.6.1 Functions 2481
28.6.1.1 GUI_MTOUCH_Enable() 2481
28.6.1.2 GUI_MTOUCH_GetEvent() 2482
28.6.1.3 GUI_MTOUCH_GetTouchInput() 2483
28.6.1.4 GUI_MTOUCH_IsEmpty() 2484
28.6.1.5 GUI_MTOUCH_SetOrientation() 2485
28.6.1.6 GUI_MTOUCH_StoreEvent() 2486
28.6.2 Data structures 2487
28.6.2.1 GUI_MTOUCH_EVENT 2487
28.6.2.2 GUI_MTOUCH_INPUT 2488
28.6.2.3 WM_GESTURE_INFO 2489
28.6.2.4 WM_ZOOM_INFO 2490
28.6.3 Defines 2491
28.6.3.1 MultiTouch flags 2491
28.6.3.2 MultiTouch gesture flags 2492

29 Keyboard Input 2493

29.1 Description 2494
29.2 Driver layer API 2495
29.2.1 GUI_StoreKeyMsg() 2496
29.2.2 GUI_SendKeyMsg() 2497
29.3 Application layer API 2498
29.3.1 GUI_ClearKeyBuffer() 2499
29.3.2 GUI_GetKey() 2500
29.3.3 GUI_GetKeyState() 2501
29.3.4 GUI_StoreKey() 2502
29.3.5 GUI_WaitKey() 2503

30 Sprites 2504

30.1 Introduction 2505
30.2 Sprite API 2506
30.2.1 GUI_SPRITE_Create() 2507
30.2.2 GUI_SPRITE_CreateAnim() 2508
30.2.3 GUI_SPRITE_CreateEx() 2509
30.2.4 GUI_SPRITE_CreateExAnim() 2510
30.2.5 GUI_SPRITE_CreateHidden() 2511
30.2.6 GUI_SPRITE_CreateHiddenEx() 2512

 © 2020 SEGGER Microcontroller GmbH

30.2.7 GUI_SPRITE_Delete() 2513
30.2.8 GUI_SPRITE_GetState() 2514
30.2.9 GUI_SPRITE_Hide() 2515
30.2.10 GUI_SPRITE_SetBitmap() 2516
30.2.11 GUI_SPRITE_SetBitmapAndPosition() 2517
30.2.12 GUI_SPRITE_SetLoop() 2518
30.2.13 GUI_SPRITE_SetPosition() 2519
30.2.14 GUI_SPRITE_Show() 2520
30.2.15 GUI_SPRITE_StartAnim() 2521
30.2.16 GUI_SPRITE_StopAnim() 2522

31 Cursors 2523

31.1 Available cursors 2524
31.2 Cursor API 2525
31.2.1 Functions 2526
31.2.1.1 GUI_CURSOR_GetState() 2526
31.2.1.2 GUI_CURSOR_Hide() 2527
31.2.1.3 GUI_CURSOR_Select() 2528
31.2.1.4 GUI_CURSOR_SelectAnim() 2529
31.2.1.5 GUI_CURSOR_SetPosition() 2530
31.2.1.6 GUI_CURSOR_Show() 2531
31.2.2 Data structures 2532
31.2.2.1 GUI_CURSOR_ANIM 2532

32 Anti-aliasing 2533

32.1 Introduction 2534
32.2 Quality of anti-aliasing 2535
32.3 Anti-aliased fonts 2536
32.3.1 Character representation in font files 2536
32.3.2 Gamma correction 2536
32.4 High-resolution coordinates 2537
32.5 Anti-aliasing API 2539
32.5.1 Control functions 2540
32.5.1.1 GUI_AA_DisableHiRes() 2540
32.5.1.2 GUI_AA_EnableHiRes() 2541
32.5.1.3 GUI_AA_GetFactor() 2542
32.5.1.4 GUI_AA_PreserveTrans() 2543
32.5.1.5 GUI_AA_SetFactor() 2544
32.5.2 Drawing functions 2545
32.5.2.1 GUI_AA_DrawArc() 2545
32.5.2.2 GUI_AA_DrawCircle() 2546
32.5.2.3 GUI_AA_DrawLine() 2547
32.5.2.4 GUI_AA_DrawPolyOutline() 2548
32.5.2.5 GUI_AA_DrawPolyOutlineEx() 2549
32.5.2.6 GUI_AA_DrawRoundedRect() 2550
32.5.2.7 GUI_AA_DrawRoundedRectEx() 2551
32.5.2.8 GUI_AA_FillCircle() 2552
32.5.2.9 GUI_AA_FillEllipse() 2553
32.5.2.10 GUI_AA_FillPolygon() 2554
32.5.2.11 GUI_AA_FillRoundedRect() 2555
32.5.2.12 GUI_AA_FillRoundedRectEx() 2556
32.5.2.13 GUI_AA_SetDrawMode() 2557
32.5.3 Gamma correction 2558
32.5.3.1 GUI_AA_EnableGammaAA4() 2558
32.5.3.2 GUI_AA_GetGammaAA4() 2559
32.5.3.3 GUI_AA_SetGammaAA4() 2560
32.6 Examples 2561
32.6.1 Different anti-aliasing factors 2561
32.6.2 Lines placed on high-resolution coordinates 2562

 © 2020 SEGGER Microcontroller GmbH

32.6.3 Moving pointer using high-resolution anti-aliasing 2563

33 Language Support 2566

33.1 Unicode 2567
33.1.1 UTF-8 encoding 2567
33.1.2 Unicode characters 2568
33.1.3 UTF-8 strings 2568
33.1.3.1 Using U2C.exe to convert UTF-8 text into C code 2568
33.1.4 Unicode API 2569
33.1.4.1 UTF-8 functions 2570
33.1.4.1.1 GUI_UC_ConvertUC2UTF8() 2570
33.1.4.1.2 GUI_UC_ConvertUTF82UC() 2571
33.1.4.1.3 GUI_UC_EnableBIDI() 2572
33.1.4.1.4 GUI_UC_EnableThai() 2573
33.1.4.1.5 GUI_UC_Encode() 2574
33.1.4.1.6 GUI_UC_GetBaseDir() 2575
33.1.4.1.7 GUI_UC_GetCharCode() 2576
33.1.4.1.8 GUI_UC_GetCharSize() 2577
33.1.4.1.9 GUI_UC_SetBaseDir() 2578
33.1.4.1.10 GUI_UC_SetEncodeSJIS() 2579
33.1.4.1.11 GUI_UC_SetEncodeNone() 2580
33.1.4.1.12 GUI_UC_SetEncodeUTF8() 2581
33.1.4.2 Double byte functions 2582
33.1.4.2.1 GUI_UC_DispString() 2582
33.2 Text- and language resource files 2583
33.2.1 Unicode support 2583
33.2.2 Loading files from RAM 2583
33.2.3 Loading files from non addressable areas 2583
33.2.4 Rules for CSV files 2583
33.2.5 Rules for text files 2583
33.2.6 Text- and language resource file API 2584
33.2.6.1 Text file functions 2585
33.2.6.1.1 GUI_LANG_LoadText() 2585
33.2.6.1.2 GUI_LANG_LoadTextEx() 2586
33.2.6.2 CSV file functions 2587
33.2.6.2.1 GUI_LANG_LoadCSV() 2587
33.2.6.2.2 GUI_LANG_LoadCSVEx() 2588
33.2.6.3 Common functions 2589
33.2.6.3.1 GUI_LANG_Clear() 2589
33.2.6.3.2 GUI_LANG_GetLang() 2590
33.2.6.3.3 GUI_LANG_GetNumItems() 2591
33.2.6.3.4 GUI_LANG_GetText() 2592
33.2.6.3.5 GUI_LANG_GetTextBuffered() 2593
33.2.6.3.6 GUI_LANG_GetTextBufferedEx() 2594
33.2.6.3.7 GUI_LANG_GetTextEx() 2595
33.2.6.3.8 GUI_LANG_GetTextLen() 2596
33.2.6.3.9 GUI_LANG_GetTextLenEx() 2597
33.2.6.3.10 GUI_LANG_SetLang() 2598
33.2.6.3.11 GUI_LANG_SetMaxNumLang() 2599
33.2.6.3.12 GUI_LANG_SetSep() 2600
33.3 Right to left- and bidirectional text 2601
33.3.1 Bidirectional text algorithm 2601
33.3.2 Basic text direction 2601
33.3.3 Mirroring 2601
33.3.4 Requirements 2601
33.4 Arabic support 2602
33.4.1 Notation forms 2602
33.4.2 Ligatures 2603
33.4.3 How to enable Arabic support 2604

 © 2020 SEGGER Microcontroller GmbH

33.4.4 Example 2604
33.4.5 Font files used with Arabic text 2604
33.5 Thai language support 2605
33.5.1 Requirements 2605
33.5.2 How to enable Thai support 2605
33.5.3 Example 2605
33.5.4 Font files used with Thai text 2605
33.6 Shift JIS support 2606
33.6.1 Creating Shift JIS fonts 2606
33.7 Limitations 2607

34 Display drivers 2608

34.1 Available display drivers 2609
34.1.1 Driver file naming convention 2609
34.1.2 Run-time configurable drivers 2609
34.1.3 Compile-time configurable drivers 2610
34.1.4 Special purpose drivers 2611
34.2 CPU / Display controller interface 2613
34.2.1 Direct interface 2613
34.2.2 Indirect interface - Parallel bus 2613
34.2.2.1 Example routines for connection to I/O pins 2614
34.2.3 Indirect interface - 4 pin SPI 2614
34.2.3.1 Example routines for connection to I/O pins 2614
34.2.4 Indirect interface - 3 pin SPI 2614
34.2.4.1 Example routines for connection to I/O pins 2615
34.2.5 Indirect interface - I2C bus 2615
34.2.5.1 Example routines for connection to I/O pins 2615
34.3 Hardware interface configuration 2616
34.3.1 Direct interface 2616
34.3.2 Indirect interface 2616
34.3.2.1 Run-time configuration 2616
34.3.2.1.1 Elements of structure GUI_PORT_API 2616
34.3.2.2 Compile-time configuration 2619
34.3.2.2.1 LCD_READ_A0 2620
34.3.2.2.2 LCD_READ_A1 2620
34.3.2.2.3 LCD_WRITE_A0 2620
34.3.2.2.4 LCD_WRITE_A1 2621
34.3.2.2.5 LCD_WRITEM_A1 2621
34.3.2.2.6 LCD_WRITE 2621
34.3.2.2.7 LCD_WRITEM 2621
34.4 Non readable displays 2623
34.5 Display orientation 2624
34.5.1 Driver based configuration of display orientation 2624
34.5.1.1 Run-time configuration 2624
34.5.1.2 Compile-time configuration 2624
34.5.2 Runtime rotation 2625
34.5.2.1 LCD_ROTATE_AddDriver() 2626
34.5.2.2 LCD_ROTATE_AddDriverEx() 2627
34.5.2.3 LCD_ROTATE_DecSel() 2628
34.5.2.4 LCD_ROTATE_DecSelEx() 2629
34.5.2.5 LCD_ROTATE_IncSel() 2630
34.5.2.6 LCD_ROTATE_IncSelEx() 2631
34.5.2.7 LCD_ROTATE_SetCallback() 2632
34.5.2.8 LCD_ROTATE_SetSel() 2633
34.5.2.9 LCD_ROTATE_SetSelEx() 2634
34.5.3 Function based configuration of display orientation 2635
34.5.3.1 GUI_SetOrientation() 2636
34.5.3.2 GUI_SetOrientationEx() 2637
34.5.4 Orientation flags 2638

 © 2020 SEGGER Microcontroller GmbH

34.6 Display driver callback function 2639
34.6.1 Commands passed to the callback function 2639
34.6.1.1 LCD_X_INITCONTROLLER 2639
34.6.1.2 LCD_X_ON 2639
34.6.1.3 LCD_X_OFF 2639
34.6.1.4 LCD_X_SETALPHA 2639
34.6.1.5 LCD_X_SETLUTENTRY 2640
34.6.1.6 LCD_X_SETORG 2640
34.6.1.7 LCD_X_SETPOS 2640
34.6.1.8 LCD_X_SETSIZE 2641
34.6.1.9 LCD_X_SETVIS 2641
34.6.1.10 LCD_X_SETVRAMADDR 2642
34.6.1.11 LCD_X_SHOWBUFFER 2642
34.7 Detailed display driver descriptions 2643
34.7.1 GUIDRV_BitPlains 2643
34.7.1.1 Supported hardware 2643
34.7.1.2 Driver selection 2643
34.7.1.3 Display data RAM organization 2644
34.7.1.4 RAM requirements 2644
34.7.1.5 Hardware configuration 2644
34.7.1.6 Additional run-time configuration 2644
34.7.1.7 GUIDRV_BitPlains_Config() 2646
34.7.2 GUIDRV_DCache 2647
34.7.2.1 Supported hardware 2647
34.7.2.2 Driver selection 2647
34.7.2.3 RAM requirements 2647
34.7.2.4 Run-time configuration 2647
34.7.2.5 Configuration API 2648
34.7.2.5.1 GUIDRV_DCache_AddDriver() 2649
34.7.2.5.2 GUIDRV_DCache_SetMode1bpp() 2650
34.7.3 GUIDRV_Dist 2651
34.7.3.1 Supported hardware 2651
34.7.3.2 Driver selection 2651
34.7.3.3 RAM requirements 2651
34.7.3.4 Run-time configuration 2651
34.7.3.5 GUIDRV_Dist_AddDriver() 2652
34.7.4 GUIDRV_FlexColor 2653
34.7.4.1 Supported hardware 2653
34.7.4.2 Driver selection 2653
34.7.4.3 Display data RAM organization 2653
34.7.4.4 RAM requirements 2654
34.7.4.5 Run-time configuration API 2654
34.7.4.6 Commands supported by LCD_SetDevFunc 2654
34.7.4.7 Configuration API 2655
34.7.4.7.1 GUIDRV_FlexColor_SetFunc() 2657
34.7.4.7.2 GUIDRV_FlexColor_Config() 2661
34.7.4.7.3 GUIDRV_FlexColor_SetOrientation() 2662
34.7.4.7.4 GUIDRV_FlexColor_SetInterface66712_B9() 2663
34.7.4.7.5 GUIDRV_FlexColor_SetInterface66715_B9() 2663
34.7.4.7.6 GUIDRV_FlexColor_SetInterface66712_B18() 2664
34.7.4.7.7 GUIDRV_FlexColor_SetInterface66715_B18() 2664
34.7.4.7.8 GUIDRV_FlexColor_SetReadFunc66709_B16() 2665
34.7.4.7.9 GUIDRV_FlexColor_SetReadFunc66712_B9() 2667
34.7.4.7.10 GUIDRV_FlexColor_SetReadFunc66715_B9() 2667
34.7.4.7.11 GUIDRV_FlexColor_SetReadFunc66712_B16() 2668
34.7.4.7.12 GUIDRV_FlexColor_SetReadFunc66715_B16() 2668
34.7.4.7.13 GUIDRV_FlexColor_SetReadFunc66720_B16() 2670
34.7.4.7.14 GUIDRV_FlexColor_SetReadFunc66772_B8() 2671
34.7.4.7.15 GUIDRV_FlexColor_SetReadFunc66772_B16() 2672
34.7.5 GUIDRV_IST3088 2673

 © 2020 SEGGER Microcontroller GmbH

34.7.5.1 Supported hardware 2673
34.7.5.2 Driver selection 2673
34.7.5.3 Display data RAM organization 2673
34.7.5.4 RAM requirements 2673
34.7.5.5 Run-time configuration 2674
34.7.5.5.1 GUIDRV_IST3088_SetBus16() 2675
34.7.5.6 Required GUI_PORT_API routines 2675
34.7.5.7 Special requirements 2675
34.7.6 GUIDRV_Lin 2676
34.7.6.1 Supported hardware 2676
34.7.6.2 Color depth and display orientation 2676
34.7.6.3 Driver selection 2677
34.7.6.4 Display data RAM organization 2678
34.7.6.5 RAM requirements 2679
34.7.6.6 Compile-time configuration 2679
34.7.6.7 Run-time configuration 2679
34.7.6.8 Commands supported by LCD_SetDevFunc() 2679
34.7.6.9 Configuration example 2679
34.7.6.10 Using the Lin driver in systems with cache memory 2680
34.7.7 GUIDRV_S1D13L04 2681
34.7.8 GUIDRV_S1D13513 2681
34.7.8.1 Supported hardware 2681
34.7.8.2 Driver selection 2681
34.7.8.3 Display data RAM organization 2682
34.7.8.4 RAM requirements 2682
34.7.8.5 Basic function 2682
34.7.8.6 Run-time configuration 2682
34.7.8.6.1 GUIDRV_S1D13L04_Config() 2683
34.7.8.6.2 GUIDRV_S1D13513_Config() 2683
34.7.8.6.3 GUIDRV_S1D13L04_SetBus16() 2684
34.7.8.6.4 GUIDRV_S1D13513_SetBus16() 2684
34.7.9 GUIDRV_S1D13L02 2685
34.7.10 GUIDRV_S1D13748 2685
34.7.10.1 Supported hardware 2685
34.7.10.2 Basic function 2685
34.7.10.3 Driver selection 2685
34.7.10.4 Display data RAM organization 2686
34.7.10.5 RAM requirements 2686
34.7.10.6 Run-time configuration 2686
34.7.10.6.1 GUIDRV_S1D13L02_Config() 2687
34.7.10.6.2 GUIDRV_S1D13748_Config() 2687
34.7.10.6.3 GUIDRV_S1D13L02_SetBus16() 2688
34.7.10.6.4 GUIDRV_S1D13748_SetBus16() 2688
34.7.10.7 Required GUI_PORT_API routines 2688
34.7.10.8 Special requirements 2688
34.7.11 GUIDRV_S1D13L01 2689
34.7.12 GUIDRV_S1D13781 2689
34.7.12.1 Supported hardware 2689
34.7.12.2 Display orientation 2689
34.7.12.3 Driver selection 2689
34.7.12.4 Display data RAM organization 2690
34.7.12.5 RAM requirements 2690
34.7.12.6 Run-time configuration 2690
34.7.12.6.1 GUIDRV_S1D13L01_Config() 2692
34.7.12.6.2 GUIDRV_S1D13781_Config() 2692
34.7.12.6.3 GUIDRV_S1D13L01_SetBusSPI() 2693
34.7.12.6.4 GUIDRV_S1D13781_SetBusSPI() 2693
34.7.12.6.5 GUIDRV_S1D13L01_SetOrientation() 2694
34.7.12.6.6 GUIDRV_S1D13781_SetOrientation() 2694
34.7.12.7 Required GUI_PORT_API routines 2694

 © 2020 SEGGER Microcontroller GmbH

34.7.12.8 Optional functions 2694
34.7.12.9 Additional information 2695
34.7.13 GUIDRV_S1D15G00 2696
34.7.13.1 Supported hardware 2696
34.7.13.2 Driver selection 2696
34.7.13.3 Display data RAM organization 2696
34.7.13.4 RAM requirements 2696
34.7.13.5 Run-time configuration 2697
34.7.13.5.1 GUIDRV_S1D15G00_Config() 2698
34.7.13.5.2 GUIDRV_S1D15G00_SetBus8() 2699
34.7.13.6 Required GUI_PORT_API routines 2699
34.7.13.7 Configuration example 2699
34.7.14 GUIDRV_SH_MEM 2700
34.7.14.1 Supported hardware 2700
34.7.14.2 Display orientation 2700
34.7.14.3 Driver selection 2701
34.7.14.4 Display data RAM organization 1bpp 2701
34.7.14.5 Display data RAM organization 3bpp 2701
34.7.14.6 RAM requirements 2701
34.7.14.7 Run-time configuration 2701
34.7.14.7.1 GUIDRV_SH_MEM_Config() 2703
34.7.14.7.2 GUIDRV_SH_MEM_3_Config() 2703
34.7.14.7.3 GUIDRV_SH_MEM_SetBus8() 2704
34.7.14.7.4 GUIDRV_SH_MEM_3_SetBus8() 2704
34.7.14.8 Required GUI_PORT_API routines 2705
34.7.14.9 Configuration Example 2705
34.7.15 GUIDRV_SLin 2706
34.7.15.1 Supported hardware 2706
34.7.15.2 Color depth and display orientation 2706
34.7.15.3 Driver selection 2707
34.7.15.4 Display data RAM organization 2707
34.7.15.5 RAM requirements 2707
34.7.15.6 Run-time configuration 2707
34.7.15.6.1 GUIDRV_SLin_Config() 2709
34.7.15.6.2 GUIDRV_SLin_SetBus8() 2710
34.7.15.6.3 GUIDRV_SLin_SetS1D13700() 2711
34.7.15.6.4 GUIDRV_SLin_SetSSD1325() 2712
34.7.15.6.5 GUIDRV_SLin_SetSSD1848() 2713
34.7.15.6.6 GUIDRV_SLin_SetT6963() 2714
34.7.15.6.7 GUIDRV_SLin_SetUC1617() 2715
34.7.15.7 Configuration example 2716
34.7.16 GUIDRV_SLinEPD 2717
34.7.16.1 Description 2717
34.7.16.2 Supported hardware 2717
34.7.16.3 Color depth and display orientation 2717
34.7.16.4 Driver selection 2718
34.7.16.5 Display data RAM organization 2718
34.7.16.6 RAM requirements 2718
34.7.16.7 Run-time configuration 2718
34.7.16.7.1 GUIDRV_SLinEPD_Config() 2720
34.7.16.7.2 GUIDRV_SLinEPD_EnablePartialMode() 2721
34.7.16.7.3 GUIDRV_SLinEPD_SetBus8() 2722
34.7.16.7.4 GUIDRV_SLinEPD_SetSSD1673() 2723
34.7.16.8 Configuration example 2724
34.7.17 GUIDRV_SPage 2725
34.7.17.1 Supported hardware 2725
34.7.17.2 Color depth and display orientation 2725
34.7.17.3 Driver selection 2726
34.7.17.4 Display data RAM organization 2727
34.7.17.5 RAM requirements 2727

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6 Run-time configuration 2727
34.7.17.6.1 GUIDRV_SPage_Config() 2729
34.7.17.6.2 GUIDRV_SPage_SetBus8() 2730
34.7.17.6.3 GUIDRV_SPage_Set1502() 2731
34.7.17.6.4 GUIDRV_SPage_Set1510() 2732
34.7.17.6.5 GUIDRV_SPage_Set1512() 2733
34.7.17.6.6 GUIDRV_SPage_SetST75256() 2734
34.7.17.6.7 GUIDRV_SPage_SetST75320() 2735
34.7.17.6.8 GUIDRV_SPage_SetST7591() 2736
34.7.17.6.9 GUIDRV_SPage_SetUC1610() 2737
34.7.17.6.10 GUIDRV_SPage_SetUC1611() 2738
34.7.17.6.11 GUIDRV_SPage_SetUC1628() 2739
34.7.17.6.12 GUIDRV_SPage_SetUC1638() 2740
34.7.17.7 Configuration Example 2741
34.7.18 GUIDRV_SSD1322 2742
34.7.18.1 Supported hardware 2742
34.7.18.2 Driver selection 2742
34.7.18.3 Display data RAM organization 2742
34.7.18.4 RAM requirements 2742
34.7.18.5 Run-time configuration 2742
34.7.18.5.1 GUIDRV_SSD1322_Config() 2743
34.7.18.5.2 GUIDRV_SSD1322_SetBus8() 2744
34.7.18.6 Required GUI_PORT_API routines 2745
34.7.18.7 Configuration example 2745
34.7.19 GUIDRV_SSD1926 2746
34.7.19.1 Supported hardware 2746
34.7.19.2 Color depth and display orientation 2746
34.7.19.3 Driver selection 2746
34.7.19.4 Display data RAM organization 2746
34.7.19.5 RAM requirements 2747
34.7.19.6 Run-time configuration 2747
34.7.19.6.1 GUIDRV_SSD1926_Config() 2748
34.7.19.6.2 GUIDRV_SSD1926_SetBus16() 2749
34.7.19.7 Required GUI_PORT_API routines 2749
34.7.19.8 Configuration Example 2749
34.7.20 GUIDRV_UC1698G 2751
34.7.20.1 Supported Hardware 2751
34.7.20.2 Color depth and display orientation 2751
34.7.20.3 Driver selection 2751
34.7.20.4 Display data RAM organization 2752
34.7.20.5 RAM requirements 2752
34.7.20.6 Run-time configuration 2752
34.7.20.6.1 GUIDRV_UC1698G_Config() 2753
34.7.20.6.2 GUIDRV_UC1698G_SetBus8() 2754
34.7.20.6.3 GUIDRV_UC1698G_SetBus16() 2755
34.7.20.7 Required GUI_PORT_API routines 2756
34.7.21 GUIDRV_CompactColor_16 2757
34.7.21.1 Supported Hardware 2757
34.7.21.2 Driver selection and configuration 2757
34.7.21.3 Display data RAM organization 2758
34.7.21.4 RAM requirements 2758
34.7.21.5 Compile-time configuration 2758
34.7.21.6 Additional configuration switches 2760
34.7.21.7 Configuration example 2760
34.7.22 GUIDRV_Fujitsu_16 2762
34.7.22.1 Supported hardware 2762
34.7.22.2 Driver selection and configuration 2762
34.7.22.3 Available configuration macros (compile time configuration) .. 2762
34.7.22.4 Display data RAM organization 2762
34.7.22.5 RAM requirements 2762

 © 2020 SEGGER Microcontroller GmbH

34.7.22.6 Hardware configuration 2763
34.7.22.7 Additional configuration switches 2763
34.7.23 GUIDRV_Page1bpp 2764
34.7.23.1 Supported hardware 2764
34.7.23.2 Driver selection and configuration 2764
34.7.23.3 Compile-time configuration 2764
34.7.23.4 RAM requirements 2765
34.7.23.5 Additional driver functions 2765
34.7.23.6 Hardware configuration 2766
34.7.23.7 Additional configuration switches 2766
34.7.24 GUIDRV_07X1 2767
34.7.24.1 Supported hardware 2767
34.7.24.2 Driver selection and configuration 2767
34.7.24.3 Display data RAM organization 2768
34.7.24.4 RAM requirements 2768
34.7.24.5 Additional driver functions 2768
34.7.24.6 Hardware configuration 2768
34.7.24.7 Additional configuration switches 2769
34.7.25 GUIDRV_6331 2770
34.7.25.1 Supported hardware 2770
34.7.25.2 Driver selection and configuration 2770
34.7.25.3 Display data RAM organization 2771
34.7.25.4 RAM requirements 2771
34.7.25.5 Hardware configuration 2771
34.7.25.6 Additional configuration switches 2771
34.7.25.7 Special requirements 2772
34.7.26 GUIDRV_7528 2773
34.7.26.1 Supported hardware 2773
34.7.26.2 Driver selection and configuration 2773
34.7.26.3 Display data RAM organization 2774
34.7.26.4 RAM requirements 2774
34.7.26.5 Hardware configuration 2774
34.7.26.6 Additional configuration switches 2775
34.7.27 GUIDRV_7529 2776
34.7.27.1 Supported hardware 2776
34.7.27.2 Driver selection and configuration 2776
34.7.27.3 Display data RAM organization 2777
34.7.27.4 RAM requirements 2777
34.7.27.5 Hardware configuration 2778
34.7.27.6 Additional configuration switches 2778
34.7.28 GUIDRV_Template - Template for a new driver 2779
34.8 LCD layer and display driver API 2780
34.8.1 Display driver API 2780
34.8.1.1 "Get" group 2782
34.8.1.1.1 LCD_GetBitsPerPixel() 2782
34.8.1.1.2 LCD_GetBitsPerPixelEx() 2783
34.8.1.1.3 LCD_GetNumColors() 2784
34.8.1.1.4 LCD_GetNumColorsEx() 2785
34.8.1.1.5 LCD_GetPosEx() 2786
34.8.1.1.6 LCD_GetVRAMAddr() 2787
34.8.1.1.7 LCD_GetVRAMAddrEx() 2788
34.8.1.1.8 LCD_GetVXSize() 2789
34.8.1.1.9 LCD_GetVYSize() 2789
34.8.1.1.10 LCD_GetVXSizeEx() 2790
34.8.1.1.11 LCD_GetVYSizeEx() 2790
34.8.1.1.12 LCD_GetXMag() 2791
34.8.1.1.13 LCD_GetYMag() 2791
34.8.1.1.14 LCD_GetXMagEx() 2792
34.8.1.1.15 LCD_GetYMagEx() 2792
34.8.1.1.16 LCD_GetXSize() 2793

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.17 LCD_GetYSize() 2793
34.8.1.1.18 LCD_GetXSizeEx() 2794
34.8.1.1.19 LCD_GetYSizeEx() 2794
34.8.1.2 "Set" group 2795
34.8.1.2.1 LCD_SetAlphaEx() 2795
34.8.1.2.2 LCD_SetAlphaModeEx() 2796
34.8.1.2.3 LCD_SetChromaEx() 2797
34.8.1.2.4 LCD_SetChromaModeEx() 2798
34.8.1.2.5 LCD_SetPosEx() 2799
34.8.1.2.6 LCD_SetVisEx() 2800
34.8.1.3 Configuration group 2801
34.8.1.3.1 LCD_SetBufferPtr() 2801
34.8.1.3.2 LCD_SetBufferPtrEx() 2802
34.8.1.3.3 LCD_Off() 2803
34.8.1.3.4 LCD_OffEx() 2804
34.8.1.3.5 LCD_On() 2805
34.8.1.3.6 LCD_OnEx() 2806
34.8.1.3.7 LCD_Refresh() 2807
34.8.1.3.8 LCD_RefreshEx() 2808
34.8.1.3.9 LCD_SetDevFunc() 2809
34.8.1.3.10 LCD_SetMaxNumColors() 2813
34.8.1.3.11 LCD_SetSizeEx() 2814
34.8.1.3.12 LCD_SetVRAMAddrEx() 2815
34.8.1.3.13 LCD_SetVSizeEx() 2816
34.8.1.4 Cache group 2817
34.8.1.4.1 LCD_ControlCache() 2817

35 Touch drivers 2818

35.1 GUIMTDRV_TangoC32 2819
35.1.1 Supported hardware 2819
35.1.2 Driver initialization 2819
35.1.3 GUIMTDRV_TangoC32 API 2819
35.1.3.1 GUIMTDRV_TangoC32_Init() 2820
35.2 GUITDRV_ADS7846 2822
35.2.1 Supported hardware 2822
35.2.2 Driver initialization 2822
35.2.3 GUITDRV_ADS7846 API 2822
35.2.3.1 GUITDRV_ADS7846_Config() 2823
35.2.3.2 GUITDRV_ADS7846_Exec() 2825
35.2.3.3 GUITDRV_ADS7846_GetLastVal() 2826

36 VNC Server 2827

36.1 Introduction 2828
36.1.1 Filetransfer 2828
36.1.2 Requirements 2828
36.1.3 Notes on this implementation 2828
36.2 emVNC - client 2830
36.2.1 How to connect to a VNC-server 2830
36.2.2 Opening the file transfer dialog 2830
36.2.3 The file transfer window 2831
36.3 emWin VNC server 2833
36.3.1 Starting the emWin VNC server 2833
36.3.2 Enabling file transfer support 2833
36.3.3 Starting the VNC server in the simulation 2833
36.3.4 Example of starting the VNC server on the target system 2833
36.4 RAM and ROM requirements 2834
36.5 VNC Server API 2835
36.5.1 Functions 2836
36.5.1.1 GUI_VNC_AttachToLayer() 2836

 © 2020 SEGGER Microcontroller GmbH

36.5.1.2 GUI_VNC_EnableFileTransfer() 2837
36.5.1.3 GUI_VNC_EnableKeyboardInput() 2838
36.5.1.4 GUI_VNC_GetNumConnections() 2839
36.5.1.5 GUI_VNC_Process() 2840
36.5.1.6 GUI_VNC_RingBell() 2841
36.5.1.7 GUI_VNC_SetFS_API() 2842
36.5.1.8 GUI_VNC_SetLockFrame() 2843
36.5.1.9 GUI_VNC_SetPassword() 2844
36.5.1.10 GUI_VNC_SetProgName() 2845
36.5.1.11 GUI_VNC_SetRetryCount() 2846
36.5.1.12 GUI_VNC_SetSize() 2847
36.5.1.13 GUI_VNC_X_StartServer() 2848
36.5.1.14 GUI_VNC_X_StartServerFT() 2849
36.5.2 Data structures 2850
36.5.2.1 IP_FS_API 2850

37 Timing- and execution-related functions 2852

37.1 Timing and execution API 2853
37.1.1 GUI_Delay() 2854
37.1.2 GUI_ErrorOut() 2855
37.1.3 GUI_Exec() 2856
37.1.4 GUI_Exec1() 2857
37.1.5 GUI_GetTime() 2858
37.1.6 GUI_GetTimeSlice() 2859
37.1.7 GUI_SetTimeSlice() 2860
37.2 Timer API 2861
37.2.1 GUI_TIMER_Create() 2862
37.2.2 GUI_TIMER_Delete() 2863
37.2.3 GUI_TIMER_Restart() 2864
37.2.4 GUI_TIMER_SetPeriod() 2865

38 Performance and Resource Usage 2866

38.1 Performance 2867
38.1.1 Driver benchmark 2867
38.1.2 Image drawing performance 2868
38.2 Memory requirements 2870
38.2.1 Memory requirements of the GUI components 2870
38.2.2 Stack requirements 2871
38.3 Memory requirements of example applications 2872
38.4 Optimizing Footprint 2873
38.4.1 Optimizing RAM requirement 2873
38.4.2 Optimizing ROM requirement 2873
38.4.3 Features with appreciable additional RAM requirement 2874

39 Configuration 2875

39.1 What needs to be configured? 2876
39.2 Run-time- and compile-time configuration 2877
39.3 Initialization process of emWin 2878
39.4 Run-time configuration 2879
39.4.1 Customizing GUIConf.c 2879
39.4.1.1 API functions to be used in GUI_X_Config() 2879
39.4.1.1.1 GUI_ALLOC_AssignMemory() 2880
39.4.1.1.2 GUI_RegisterAfterInitHook() 2881
39.4.1.1.3 GUI_SetOnErrorFunc() 2882
39.4.1.1.4 GUITASK_GetMaxTask() 2883
39.4.1.1.5 GUITASK_SetMaxTask() 2884
39.4.2 Customizing LCDConf.c 2885
39.4.2.1 LCD_X_Config() 2886

 © 2020 SEGGER Microcontroller GmbH

39.4.2.2 LCD_X_DisplayDriver() 2887
39.4.2.3 API functions to be used in LCD_X_Config() 2888
39.4.2.3.1 GUI_DEVICE_CreateAndLink() 2889
39.4.3 Customizing GUI_X.c 2890
39.4.3.1 Timing routines 2890
39.4.3.1.1 GUI_X_Delay() 2890
39.4.3.1.2 GUI_X_ExecIdle() 2891
39.4.3.1.3 GUI_X_GetTime() 2892
39.4.3.2 Debug routines 2893
39.4.3.2.1 GUI_X_ErrorOut() 2893
39.4.3.2.2 GUI_X_Warn() 2893
39.4.3.2.3 GUI_X_Log() 2893
39.4.3.3 Kernel interface routines 2894
39.4.4 Function replacement 2894
39.4.4.1 GUI_SetpfMemcpy() 2895
39.4.4.2 GUI_SetpfMemset() 2896
39.4.4.3 GUI_SetpfStrcmp() 2897
39.4.4.4 GUI_SetpfStrcpy() 2898
39.4.4.5 GUI_SetpfStrlen() 2899
39.5 Compile time configuration 2900
39.5.1 Customizing GUIConf.h 2900
39.5.1.1 Configuring the available features of emWin 2900
39.5.1.2 Default font and default color configuration 2900
39.5.1.3 Advanced GUI configuration options 2901
39.5.1.3.1 GUI_MEMCPY (obsolete) 2901
39.5.1.3.2 GUI_MEMSET (obsolete) 2902
39.5.1.3.3 GUI_POST_INIT 2902
39.5.1.3.4 GUI_TRIAL_VERSION 2902
39.5.2 Customizing LCDConf.h 2902
39.6 Hardware acceleration 2903
39.6.1 Using ChromeART accelerator 2903
39.6.2 Available API functions 2903
39.6.3 Color conversion 2905
39.6.3.1 GUICC_M1555I_SetCustColorConv() 2905
39.6.3.2 GUICC_M565_SetCustColorConv() 2905
39.6.3.3 GUICC_M4444I_SetCustColorConv() 2905
39.6.3.4 GUICC_M888_SetCustColorConv() 2905
39.6.3.5 GUICC_M8888I_SetCustColorConv() 2905
39.6.4 Filling, copy operations and bitmap drawing 2906
39.6.5 Alpha blending 2907
39.6.5.1 GUI_AlphaEnableFillRectHW() 2907
39.6.5.2 GUI_SetFuncAlphaBlending() 2908
39.6.5.3 GUI_SetFuncDrawAlpha() 2909
39.6.6 Mixing colors 2910
39.6.6.1 GUI_SetFuncMixColors() 2910
39.6.6.2 GUI_SetFuncMixColorsBulk() 2911
39.6.7 Alpha text drawing 2912
39.6.7.1 GUI_AA_SetpfDrawCharAA4() 2912
39.6.8 Palette conversion 2913
39.6.8.1 GUI_SetFuncGetpPalConvTable() 2913
39.6.9 Drawing bitmaps within memory devices 2914
39.6.9.1 GUI_MEMDEV_SetDrawMemdev16bppFunc() 2914
39.7 Hardware JPEG decoding 2915
39.7.1 Using hardware JPEG decoding 2915
39.7.2 Available API functions 2915
39.7.2.1 GUI_JPEG_SetpfDrawEx() 2916
39.7.2.1.1 pfDrawEx() 2916
39.8 Drawing AA shapes with hardware 2917
39.8.1 How to use it 2917
39.8.2 Available API functions 2917

 © 2020 SEGGER Microcontroller GmbH

39.8.2.1 GUI_AA_SetFuncFillCircle() 2918
39.8.2.2 GUI_AA_SetFuncFillPolygon() 2919
39.8.2.3 GUI_AA_SetFuncDrawCircle() 2920
39.8.2.4 GUI_AA_SetFuncDrawLine() 2921
39.8.2.5 GUI_AA_SetFuncDrawPolyOutline() 2922
39.8.2.6 GUI_AA_SetFuncDrawArc() 2923
39.9 Framebuffer located in data cache area of CPU 2924
39.9.1 Requirements 2924
39.9.2 Using multiple buffers and a data cache 2924
39.9.2.1 How it works 2924
39.9.2.2 Animations and multiple buffering 2924
39.9.2.3 Memory device animation functions 2925
39.9.3 Available API-functions 2925
39.9.3.1 GUI_DCACHE_Clear() 2926
39.9.3.2 GUI_DCACHE_SetClearCacheHook() 2927
39.10 Memory management 2928
39.10.1 Usage 2928
39.10.2 Block management 2928
39.10.3 Available API functions 2928
39.10.3.1 GUI_ALLOC_GetMaxUsedBytes() 2929
39.10.3.2 GUI_ALLOC_GetNumFreeBytes() 2930
39.10.3.3 GUI_ALLOC_GetMemInfo() 2931
39.10.3.4 GUI_ALLOC_GetNumUsedBytes() 2932

40 Support 2933

40.1 Problems with tool chain (compiler, linker) 2934
40.1.1 Compiler crash 2934
40.1.2 Compiler warnings 2934
40.1.3 Compiler errors 2934
40.1.4 Linker problems 2935
40.2 Problems with hardware/driver 2936
40.3 Problems with API functions 2937
40.4 Problems with the performance 2938
40.5 Contacting support 2939
40.6 FAQ 2940

41 Indexes 2941

41.1 Function index 2942
41.2 Type index 2968

 © 2020 SEGGER Microcontroller GmbH

Chapter 1

Introduction to emWin

This introduction gives some information about this document. It also gives an overview of what features emWin consists of and what it requires.

 © 2020 SEGGER Microcontroller GmbH

1.1 Purpose of this document

This guide describes how to install, configure and use the emWin graphical user interface for embedded applications. It also explains the internal structure of the software and all the functions which are offered by emWin and intended for direct use (API, Application Programming Interface). Before actually using emWin, you should read or at least glance through this manual in order to become familiar with the software. The following steps are recommended:

- Copy the emWin files to your computer.
- Go through the chapter *Getting Started* on page 94
- Use the simulator in order to become more familiar with what the software can do (refer to the chapter *Simulation* on page 109).
- Expand your program using the rest of the manual for reference.

 © 2020 SEGGER Microcontroller GmbH

1.2 Requirements

A target system is not required in order to develop software with emWin; most of the software can be developed using the simulator. However, the final purpose is usually to be able to run the software on a target system.

1.2.1 Target system (hardware)

Your target system must:

- Have a CPU (16/32 bits)
- Have a CPU with 64 bits (LP64 and LLP64 data model)
- Have a minimum of RAM and ROM
- Have a full graphic display (any type and any resolution)

The RAM needs to be 8-, 16- and 32-bit accessible. Memory requirements vary depending on which parts of the software are used and how efficient your target compiler is. It is therefore not possible to specify precise values, but the following applies to typical systems.

Small systems (no Window Manager)

- RAM: 100 Bytes
- Stack: 600 Bytes
- ROM: 10-25 KBytes (depending on the functionality used)

Big systems (including Window Manager and widgets)

- RAM: 2-6 KB (depending on number of windows required)
- Stack: 1200-1800 bytes (depending on the functionality used)
- ROM: 30-60 KB (depending on the functionality used)

ROM requirements increase according to the number of fonts used in the application. All values are rough estimates and cannot be guaranteed. Detailed information can be found in the chapter *Performance and Resource Usage* on page 2866.

1.2.2 Development environment (compiler)

The CPU used is of no importance; only an ANSI-compliant C compiler complying with at least one of the following international standard is required:

- ISO/IEC/ANSI 9899:1990 (C90) with support for C++ style comments (//)
- ISO/IEC 9899:1999 (C99)
- ISO/IEC 14882:1998 (C++)

If your compiler has some limitations, let us know and we will inform you if these will be a problem when compiling the software. Any compiler for 16/32-bit CPUs or DSPs that we know of can be used. A C++ compiler is not required, but can be used. The application program can therefore also be programmed in C++ if desired.

Limitation

The code of emWin requires a ’char’ type of 8 bits. If a ’char’ is 16 bits the code of emWin does not work right.

 © 2020 SEGGER Microcontroller GmbH

1.3 Features

emWin is designed to provide an efficient, processor- and display controller-independent graphical user interface for any application that operates with a graphical display. It is compatible with single-task and multitask environments, with a proprietary operating system or with any commercial RTOS. emWin is shipped as C source code. It may be adapted to any size physical and virtual display with any display controller and CPU. Its features include the following:

General

- Any (monochrome, grayscale or color) display with any controller supported (if the right driver is available).
- Any interface supported using configuration macros.
- May work without display controller on smaller displays.
- Display-size configurable.
- Characters and bitmaps may be written at any point on the display, not just on even-numbered byte addresses.
- Routines are optimized for both size and speed.
- Compile time switches allow for different optimizations.
- For slower display controllers, display can be cached in memory, reducing access to a minimum and resulting in very high speed.
- Clear structure.
- Virtual display support; the virtual display can be larger than the actual display.

Graphic library

- Bitmaps of different color depths supported.
- Bitmap Converter available.
- Absolutely no floating-point usage.
- Fast line/point drawing (without floating-point usage).
- Very fast drawing of circles/polygons.
- Different drawing modes.

Fonts

- A variety of different fonts are shipped with the basic software: 4×6, 6×8, 6×9, 8×8, 8×9, 8×16, 8×17, 8×18, 24×32, and proportional fonts with pixel-heights of 8, 10, 13, 16. For more information, see chapter *Fonts* on page 463.
- New fonts can be defined and simply linked in.
- Only the fonts used by the application are actually linked to the resulting executable, resulting in minimum ROM usage.
- Using the Font Converter, any font available on the host system (that is, Microsoft Windows) can be converted for use in emWin.
- Scalable iType and TTF fonts are supported.

String/value output routines

- Routines to show values in decimal, binary, hexadecimal, any font.
- Routines to edit values in decimal, binary, hexadecimal, any font.

Window Manager (WM)

- Complete window management including clipping. Overwriting of areas outside a window’s client area is impossible.
- Windows can be moved and resized.
- Callback routines supported (usage optional).
- WM uses minimum RAM (approx. 50 bytes per window).

Optional widgets for PC look and feel

- Widgets (window objects, also known as controls) are available. They generally operate automatically and are simple to use.

 © 2020 SEGGER Microcontroller GmbH

Touch-screen & mouse support

- For window objects such as the button widget, emWin offers touch-screen and mouse support.

PC tools

- Simulation library for WIN32-Environments. The source code may be purchased additionally.
- emWinView.
- Bitmap Converter.
- Font Converter.
- GUIBuilder.

 © 2020 SEGGER Microcontroller GmbH

1.4 Examples and demos

To give you a better idea of what emWin can do, we have different demos available as "ready-to-use" simulation executables that you can find here.
The source of the sample applications is located in the folder `Sample`. The folder `Sample\Application\GUIDemo` contains an application program showing many features of emWin. All examples are also available at www.segger.com. Example code in this documentation is provided as code snippet, which might require further modifications.

 © 2020 SEGGER Microcontroller GmbH

1.5 Starter kits

Complete starter kits including a demo board with a display, a C compiler and an example project are available. For more details, take a look at our website at www.segger.com.

 © 2020 SEGGER Microcontroller GmbH

1.6 Screen and coordinates



The screen consists of many dots that can be controlled individually. These dots are called pixels. Most of the text and drawing functions that emWin offers in its API to the user program can write or draw on any specified pixel. The horizontal scale is called the X-axis, whereas the vertical scale is called the Y-axis. Coordinates are denoted as a pair consisting of an X- and a Y-value (X, Y). The X-coordinate is always first in routines that require X and Y coordinates. The upper left corner of the display (or a window) has per default the coordinates (0,0). Positive X-values are always to the right; positive Y-values are always down. The above graph illustrates the coordinate system and directions of the X- and Y- axes. All coordinates passed to an API function are always specified in pixels.

 © 2020 SEGGER Microcontroller GmbH

1.7 How to connect the display to the microcontroller

emWin handles all access to the display. Virtually any display controller can be supported, independently of how it is accessed. For details, refer to the chapter *Configuration* on page 620. Also, get in contact with us if your display controller is not supported. We are currently writing drivers for all display controllers available on the market and may already have a proven driver for the display controller that you intend to use. It is usually very simple to write the routines (or macros) used to access the display in your application SEGGER Microcontroller GmbH offers the service of making these customizations for you, if necessary with your target hardware. It does not really matter how the display is connected to the system as long as it is somehow accessible by software, which may be accomplished in a variety of ways. Most of these interfaces are supported by a driver which is supplied in source code form. This driver does not normally require modifications, but is configured for your hardware by making changes in the file `LCDConf.h`. Details about how to customize a driver to your hardware as necessary are provided in the chapter *Display drivers* on page 2608. The most common ways to access the display are described as follows. If you simply want to understand how to use emWin, you may skip this section.

Display with memory-mapped display controller:

The display controller is connected directly to the data bus of the system, which means the controller can be accessed just like a RAM. This is a very efficient way of accessing the display controller and is most recommended. The display addresses are defined to the segment LCDSEG, and in order to be able to access the display the linker/locator simply needs to be told where to locate this segment. The location must be identical to the access address in physical address space. Drivers are available for this type of interface and for different display controllers.

Display with display controller connected to port / buffer

For slower display controllers used on fast processors, the use of port-lines may be the only solution. This method of accessing the display has the disadvantage of being somewhat slower than direct bus-interface but, particularly with a cache that minimizes the accesses to the display, the display update is not slowed down significantly. All that needs to be done is to define routines or macros which set or read the hardware ports/buffers that the display is connected to. This type of interface is also supported by different drivers for the different display controllers.

Proprietary solutions: display without display controller

The display can also be connected without an display controller. In this case, the display data is usually supplied directly by the controller via a 4- or 8-bit shift register. These proprietary hardware solutions have the advantage of being inexpensive, but the disadvantage of using up much of the available computation time. Depending on the CPU, this can be anything between 20 and almost 100 percent; with slower CPUs, it is really not possible at all. This type of interface does not require a specific display driver because emWin simply places all the display data into the display cache. You yourself must write the hardware-dependent portion that periodically transfers the data in the cache memory to your display. Example code for transferring the video image into the display is available in both C and optimized assembler for M16C and M16C/80.

 © 2020 SEGGER Microcontroller GmbH

1.8 Data types

Since C does not provide data types of fixed lengths which are identical on all platforms, emWin uses, in most cases, its own data types as shown in the table below:

Data type	Definition	Description
I8	signed char	8-bit signed value
U8	unsigned char	8-bit unsigned value
I16	signed short	16-bit signed value
U16	unsigned short	16-bit unsigned value
I32	signed long	32-bit signed value
U32	unsigned long	32-bit unsigned value
I16P	signed short	16-bit (or more) signed value
U16P	unsigned short	16-bit (or more) unsigned value

For most 16/32-bit controllers, the settings will work fine. However, if you have similar defines in other sections of your program, you might want to change or relocate them. A recommended place is in the file Global.h.

 © 2020 SEGGER Microcontroller GmbH

Chapter 2

Getting Started

The following chapter provides an overview of the basic procedures for setting up and configuring emWin on your target system. It also includes a simple program example.
If you find yourself unsure about certain areas, keep in mind that most topics are treated in greater detail in later chapters. You will most likely need to refer to other parts of the manual before you begin more complicated programming.

 © 2020 SEGGER Microcontroller GmbH

2.1 Recommended project structure

We recommend keeping emWin separate from your application files. It is good practice to keep all the program files (including the header files) together in the GUI subdirectories of your project's root directory. The directory structure should be similar to the one seen in the picture. This practice has the advantage of being very easy to update to newer versions of emWin by simply replacing the `GUI\` directories. Your application files can be stored anywhere.



Note

When updating to a newer emWin version:
Since files may have been added, moved or deleted, the project directories may need to be updated accordingly.

 © 2020 SEGGER Microcontroller GmbH

2.2 Subdirectories

The following table shows the contents of all GUI subdirectories:

Directory	Contents
`Config`	Configuration files
`GUI\AntiAlias`	Antialiasing support *
`GUI\ConvertMono`	Color conversion routines used for grayscale displays *
`GUI\ConvertColor`	Color conversion routines used for color displays *
`GUI\Core`	emWin core files
`GUI\Font`	Font files
`GUI\DisplayDriver`	Display driver
`GUI\MemDev`	Memory Device support *
`GUI\MT`	MultiTouch support
`GUI\VNC`	VNC support *
`GUI\Widget`	Widget library *
`GUI\WM`	Window Manager *

Legend

***** - optional

2.2.1 Include directories

You should make sure that the include path contains the following directories (the order of inclusion is of no importance):

- `Config`
- `GUI\Core`
- `GUI\DisplayDriver`
- `GUI\Widget` (if using the widget library)
- `GUI\WM` (if using Window Manager)

Note

Always make sure that you have only one version of each file!

It is frequently a major problem when updating to a new version of emWin if you have old files included and therefore mix different versions. If you keep emWin in the directories as suggested (and only in these), this type of problem cannot occur. When updating to a newer version, you should be able to keep your configuration files and leave them unchanged. For safety reasons, we recommend backing up (or at least renaming) the `GUI\` directories prior to updating.

 © 2020 SEGGER Microcontroller GmbH

2.3 Adding emWin to the target program

You basically have a choice between including only the source files that you are actually going to use in your project, which will then be compiled and linked, or creating a library and linking the library file. If your tool chain supports “smart” linking (linking in only the modules that are referenced and not those that are not referenced), there is no real need to create a library at all, since only the functions and data structures which are required will be linked. If your tool chain does not support “smart” linking, a library makes sense, because otherwise everything will be linked in and the program size will be excessively large. For some CPUs, we have example projects available to help you get started.

 © 2020 SEGGER Microcontroller GmbH

2.4 Creating a library

Building a library from the sources is a simple procedure. The first step is to copy the batch files (located under `Sample\Makelib`) into your project's root directory. That means the parent directory containing the `Config` and the `GUI` folder. Then, make any necessary changes. There are a total of four batch files which need to be copied, described in the table below. The main file, `Makelib.bat`, will be the same for all systems and requires no changes. To build a library for your target system, you will normally need to make slight modifications to the other three smaller files. Finally, start the file `Makelib.bat` to create the library. The batch files assume that your GUI and Config subdirectories are set up as recommended.
The procedure for creating a library is illustrated in the flow chart below. The `Makelib.bat` file first calls `Prep.bat` to prepare the environment for the tool chain. Then it calls `CC.bat` for every file to be included in the library. It does this as many times as necessary. `CC.bat` adds each object file to a list that will be used by `lib.bat`. When all files to be added to the library have been listed, `Makelib.bat` then calls `lib.bat`, which uses a librarian to put the listed object files into the actual library. Of course you are free to create libraries in another way.



It is not recommended to create an emWin library including a compile-time configurable display driver. Detailed information about the configurability of emWin display drivers can be found in the section *Available display drivers* on page 2609.

File	Description
`Makelib.bat`	Main batch file. No modification required.
`Prep.bat`	Called by Makelib.bat to prepare environment for the tool chain to be used.
`CC.bat`	Called by Makelib.bat for every file to be added to the library; creates a list of these object files which will then be used in the next step by the librarian in the lib.bat file.
`Lib.bat`	Called by Makelib.bat to put the object files listed by CC.bat into a library.

The files as shipped assume that a Microsoft compiler is installed in its default location. If all batch files are copied to the root directory (directly above GUI) and no changes are made at all, a simulation library will be generated for the emWin simulation. In order to create a target library, however, it will be necessary to modify `Prep.bat`, `CC.bat` and `lib.bat`.

 © 2020 SEGGER Microcontroller GmbH

2.4.1 Adapting the library batch files to a different system

The following will show how to adapt the files by an example adaptation for a Mitsubishi M32C CPU.

Adapting Prep.bat

Prep.bat is called at the beginning of Makelib.bat. As described above its job is to set the environment variables for the used tools and the environment variable PATH, so that the batch files can call the tools without specifying an absolute path. Assuming the compiler is installed in the folder `C:\MTOOL` the file `Prep.bat` could look as follows:

```
@ECHO OFF
SET TOOLPATH=C:
REM ********************************************************************
REM   Set the variable PATH to be able to call the tools
SET PATH=%TOOLPATH%;%TOOLPATH%;%PATH%
REM ********************************************************************
REM   Set the tool internal used variables
SET BIN308=%TOOLPATH%
SET INC308=%TOOLPATH%
SET LIB308=%TOOLPATH%
SET TMP308=%TOOLPATH%
```

Adapting CC.bat

The job of `CC.bat` is to compile the passed source file and adding the file name of the object file to a link list. When starting `MakeLib.bat` it creates the following subdirectories relative to its position:

Directory	Contents
`Lib`	This folder should contain the library file after the build process.
`Temp\Output`	Should contain all the compiler output and the link list file. Will be deleted after the build process.
`Temp\Source`	`MakeLib.bat` uses this folder to copy all source and header files used for the build process. Will be deleted after the build process.

The object file should be created (or moved) to `Temp\Output`. This makes sure all the output will be deleted after the build process. Also the link list should be located in the output folder. The following shows an example for the Mitsubishi compiler:

```
@ECHO OFF
GOTO START
REM ********************************************************************
REM   Explanation of the used compiler options:
-silent : Suppresses the copyright message display at startup
-M82    : Generates object code for M32C/80 Series (Remove this switch
          for M16C80 targets)
-c      : Creates a relocatable file (extension .r30) and ends processing
-I      : Specifies the directory containing the file(s) specified in #include
-dir    : Specifies the destination directory
-OS     : Maximum optimization of speed followed by ROM size
-fFRAM  : Changes the default attribute of RAM data to far
-fETI   : Performs operation after extending char-type data to the int type
          (Extended according to ANSI standards)
:START
REM ********************************************************************
REM   Compile the passed source file with the Mitsubishi NC308 compiler
NC308 -silent -M82 -c -IInc -dir Temp -OS -fFRAM -fETI Temp1.c
REM ********************************************************************
REM   Pause if any problem occurs
```

 © 2020 SEGGER Microcontroller GmbH

```
IF ERRORLEVEL 1 PAUSE
REM ************************************************************
REM   Add the file name of the object file to the link list
ECHO Temp1.R30>>Temp.dat
```

Adapting Lib.bat

After all source files have been compiled `Lib.bat` will be called from `MakeLib.bat`. The job is to create a library file using the link list created by `CC.bat`. The destination folder of the library file should be the Lib folder created by `MakeLib.bat`. The following shows an example for the Mitsubishi librarian:

```
@ECHO OFF
GOTO START
REM ************************************************************
REM   Explanation of the used options:
-C : Creates new library file
@  : Specifies command file
:START
REM ************************************************************
REM   Create the first part of the linker command file
ECHO -C Lib>Temp.DAT
REM ************************************************************
REM   Merge the first part with the link list to the linker command file
COPY Temp.DAT+Temp.dat Temp.DAT
REM ************************************************************
REM   Call the Mitsubishi librarian
LB308 @Temp.DAT
REM ************************************************************
REM   Pause if any problem occurs
IF ERRORLEVEL 1 PAUSE
```

 © 2020 SEGGER Microcontroller GmbH

2.5 C files to include in the project

Generally speaking, you need to include the core C files of emWin, the display driver, all font files you plan to use and any optional modules you have ordered with emWin:

- All C files of the folder `Config`
- All C files of the folder `GUI\Core`
- The fonts you plan to use (located in `GUI\Font`)
- Display driver: All C files of the folder `GUI\DisplayDriver`.

Additional software packages

If you plan to use additional, optional modules you must also include their C files:

- Gray scale converting functions: all C files located in `GUI\ConvertMono`
- Color conversion functions: all C files located in `GUI\ConvertColor`
- Antialiasing: all C files located in `GUI\AntiAlias`
- Memory Devices: all C files located in `GUI\MemDev`
- VNC support: all C files located in `GUI\VNC`
- Widget library: all C files located in `GUI\Widget`
- Window Manager: all C files located in `GUI\WM`

Target specifics

For displays with indirect interface hardware routines must be included. Examples for several kinds of indirect interface routines are available under `Sample\LCD_X_Port`.

RTOS specifics

- If emWin is intended to be used with an RTOS, some RTOS dependent functions need to be implemented. emWin comes with several sample files including implementations for common RTOS packages (called `GUI_X_<RTOS>.c`), as well as the file `GUI_X_Ex.c` which just contains place holders of the required functions and might be used to make emWin work with any RTOS.
- If multitasking is not required (access of the display by one task only) the file `GUI_X.c` may be used as a starting point for a custom implementation. The sample files can be found in the folder `Sample\GUI_X` which is contained in the emWin package.

Additional information

Be sure to include `GUI.h` in all emWin accessing source files.

 © 2020 SEGGER Microcontroller GmbH

2.6 Configuring emWin

The `Config` folder should contain all configuration files. The chapter *Configuration* on page 620 explains in detail how emWin should be configured.
The following types of configuration macros are available:

Binary switch "B"

Switches can have a value of either 0 or 1, where 0 means deactivated and 1 means activated (actually anything other than 0 would work, but using 1 makes it easier to read a config file). These switches can enable or disable a certain functionality or behavior. Switches are the simplest form of configuration macro.

Numerical value "N"

Numerical values are used somewhere in the code in place of a numerical constant. Typical examples are in the configuration of the resolution of a display.

Selection switch "S"

Selection switches are used to select one out of multiple options where only one of those options can be selected. A typical example might be the selection of the type of display controller used, where the number selected denotes which source code (in which display driver) is used to generate object code.

Alias "A"

A macro which operates like a simple text substitute. An example is U8, which is replaced by the preprocessor with `unsigned char`.

Function replacement "F"

Macros can basically be treated like regular functions although certain limitations apply, as a macro is still put into the code as simple text replacement. Function replacements are mainly used to add specific functionality to a module (such as the access to a display) which is highly hardware-dependent. This type of macro is always declared using brackets (and optional parameters).

Type replacement "T"

Type replacement macros allow changing the types of certain values.

 © 2020 SEGGER Microcontroller GmbH

2.7 Initializing emWin

The following functions should be used to initialize and 'de-initialize' emWin in order to start the configuration process (see chapter *Configuration* on page 620) or clear internal data from memory again.

Routine	Description
GUI_Init()	Initializes emWin internal data structures and variables.
GUI_IsInitialized()	Returns the initialization state of emWin.
GUI_Exit()	Clears emWin internal data from memory to make further calls of GUI_Init() possible.

 © 2020 SEGGER Microcontroller GmbH

2.7.1 GUI_Init()

Description

Initializes emWin internal data structures and variables.

Prototype

```
int GUI_Init(void);
```

Return value

= 0 if successful.
≠ 0 if the initialization of the display driver fails.

Additional information

Executing this function is mandatory before using any emWin functions. The only exception is setting create flags for windows (see `WM_SetCreateFlags()`). If the Window Manager is used, the background window is created from within `GUI_Init()`. So if create flags are set up before `GUI_Init()` is called, the background window is created according to them.

 © 2020 SEGGER Microcontroller GmbH

2.7.2 GUI_IsInitialized()

Description

Returns the initialization state of emWin.

Prototype

```
int GUI_IsInitialized(void);
```

Return value

1	if emWin is already initialized
0	if not.

 © 2020 SEGGER Microcontroller GmbH

2.7.3 GUI_Exit()

Description

Clears emWin internal data from memory to make further calls of `GUI_Init()` possible.

Prototype

```
void GUI_Exit(void);
```

Additional information

This function should be used if emWin represents a part of the application which is not used continuously and therefore has to be able to be turned on and off again. Please note that after `GUI_Exit()` was called emWin will not work properly until `GUI_Init()` is called again.

 © 2020 SEGGER Microcontroller GmbH

2.8 Using emWin with target hardware

The following is just a basic outline of the general steps that should be taken when starting to program with emWin. All steps are explained further in subsequent chapters.

Step 1: Configuring emWin

The first step is usually to customize emWin. For details about the configuration, refer to the chapter *Configuration* on page 620.

Step 2: Defining access addresses or access routines

For memory-mapped display controllers, the access addresses of the display simply need to be defined in the configuration file of the display controller. For port/buffer-accessed display controllers, interface routines must be defined. Examples of the required routines are available under `Sample\LCD_X_Port`.

Step 3: Compiling, linking and testing the example code

emWin comes with example code for both single- and multitask environments. Compile, link and test these little example programs until you feel comfortable doing so.

Step 4: Modifying the example program

Make simple modifications to the example programs. Add additional commands such as displaying text in different sizes on the display, showing lines and so on.

Step 5: In multitask applications: adapt to your OS (if necessary)

If multiple tasks should be able to access the display simultaneously, the macros `GUI_MAXTASK` and `GUI_OS` come into play, as well as the file `GUITask.c`. For details and example adaptations, refer to the chapter *Configuration* on page 620.

Step 6: Write your own application using emWin

By now you should have a clearer understanding of how to use emWin. Think about how to structure the program your application requires and use emWin by calling the appropriate routines. Consult the reference chapters later in this manual, as they discuss the specific emWin functions and configuration macros that are available.

 © 2020 SEGGER Microcontroller GmbH

2.9 The "Hello world" example program

In the following we will show the “Hello world” example program. If you like to see a wide range of emWin based sample applications as well as further simple tutorial applications, please have a look in the `Sample` folder of your emWin shipment or visit the “emWin Samples” section on www.segger.com.

A “Hello world” program has been used as a starting point for C programming since the early days, because it is essentially the smallest program that can be written. An emWin “Hello world” program is shown below and is available as `BASIC_HelloWorld.c` in the `Sample\Tutorial` folder shipped with emWin. The whole purpose of the program is to write “Hello world” in the upper left corner of the display. In order to be able to do this, the hardware of the application, the display controller and the GUI must be initialized first. emWin is initialized by a simple call of `GUI_Init()` in the beginning of the program. In this example, we assume that the hardware of your application is already initialized. The “Hello world” program looks as follows:

```
#include "GUI.h"
void MainTask(void) {
  GUI_Init();
  GUI_DispString("Hello world!");
  while(1);
}
```

Adding functionality to the "Hello world" program

Our little program has not been doing too much so far. We can now extend the functionality a bit: after displaying “Hello world”, we would like the program to start counting on the display in order to be able to estimate how fast outputs to the display can be made. We can simply add a bit of code to the loop at the end of the main program, which is essentially a call to the function that displays a value in decimal form.

The example is available as `BASIC_Hello1.c` in the `Sample` folder.

```
#include "GUI.h"
void MainTask(void) {
  int i = 0;
  GUI_Init();
  GUI_DispString("Hello world!");
  while(1) {
    GUI_DispDecAt( i++, 20,20,4);
    if (i > 9999) {
      i = 0;
    }
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

Chapter 3

Simulation

The PC simulation of emWin allows you to compile the same C source on your Windows PC using a native (typically Microsoft) compiler and create an executable for your own application. Doing so allows the following:

- Design of the user interface on your PC (no hardware required!).
- Debugging of the user interface program.
- Creation of demos of your application, which can be used to discuss the user interface.

The resulting executable can be sent easily via e-mail.



© 2020 SEGGER Microcontroller GmbH

3.1 Using the simulation

The emWin simulation requires Microsoft Visual C++ (version 6.00 or higher) and the integrated development environment (IDE) which comes with it. You will see a simulation of your LCD on your PC screen, which has the same resolution in X and Y and can display the exact same colors as your LCD once it has been properly configured. The entire graphic library API and Window Manager API of the simulation are identical to those on your target system; all functions will behave in the very same way as on the target hardware since the simulation uses the same C source code as the target system. The difference lies only in the lower level of the software: the display driver. Instead of using the actual display driver, the PC simulation uses a simulation driver which writes into a bitmap. The bitmap is then displayed on your screen using a second thread of the simulation. This second thread is invisible to the application; it behaves just as if the LCD routines were writing directly to the display.

3.1.1 Rotating and mirroring the screen

emWin supports rotating and/or mirroring of the screen. Please note that these features do not affect the simulation screen.

3.1.2 Using the simulation with the trial version of emWin

The trial version of emWin contains a full library which allows you to evaluate all available features of emWin. It also includes the emWin viewer (used for debugging applications), as well as demo versions of the Font Converter and the Bitmap Converter. Keep in mind that, being a trial version, you will not be able to view the source code of emWin or the simulation, but you will still be able to become familiar with what emWin can do.

3.1.2.1 Directory structure

The directory structure of the simulation in the trial version is shown below. The table below explains the contents of the folders:



Directory	Content
Application	Source of the demo program.

 © 2020 SEGGER Microcontroller GmbH

Directory	Content
Config	Configuration files used to build the library. Note that changes at the header files do not have any effect on the precompiled library!
Doc	Document folder, contains emWin manual.
Exe	Ready-to-use demo program.
GUI	Library files and include files need to use the library.
Sample	Simulation examples.
Simulation	Files needed for the simulation.
Tool	Contains all emWin tools, such as the emWin viewer, a demo version of the Bitmap and Font Converter and more.

3.1.2.2 Visual C++ workspace

The root directory shown above includes the Microsoft Visual C++ solution (Simulation-Trial.sln) and the rest of the project files. The workspace allows you to modify an application program and debug it before compiling it on your target system. Double-click the solution file to open the Microsoft Visual Studio IDE. The directory structure of the Visual C++ workspace will look like the one shown below.



3.1.2.3 Compiling the demo program

The source files for the demo program are located in the Application directory as a ready-to-go simulation, meaning that you only need to rebuild and start it. Note that to rebuild the executable, you will need to have Microsoft Visual C++ (version 6.00 or later) installed.

- **Step 1:** Open the Visual C++ workspace by double-clicking on SimulationTrial.sln.
- **Step 2:** Rebuild the project by choosing **Build ➔ Rebuild All** from the menu (or by pressing F7).
- **Step 3:** Start the simulation by choosing **Build ➔ Start Debug ➔ Go** from the menu (or by pressing F5). The demo project will begin to run and may be closed at any time by right-clicking on it and selecting **Exit**.

3.1.2.4 Compiling the samples

The Sample directory contains ready-to-go examples that demonstrate different features of emWin and provide examples of some of their typical uses. In order to build any of these executables, their C source must be 'activated' in the project. This is easily done with the following procedure:

- **Step 1:** Exclude the Application folder from the build process by right-clicking the Application folder of the workspace and selecting **Settings ➔ General ➔ Exclude from build**.

 © 2020 SEGGER Microcontroller GmbH

- **Step 2:** Open the Sample folder of the workspace by double-clicking on it. Include the example which should be used by right-clicking on it and deselecting **Settings ➔ General ➔ Exclude** from build.
- **Step 3:** If the example contains its own configuration files (`LCDConf.c` and/or `SIMConf.c`) the default configuration files located in the config folder need to be excluded from the build process.
- **Step 4:** Rebuild the example by choosing **Build ➔ Rebuild All** from the menu (or by pressing F7).
- **Step 5:** Start the simulation by choosing **Build ➔ Start Debug ➔ Go** from the menu (or by pressing F5). The result of the example selected above is pictured below:



3.1.3 Using the simulation with the emWin source

3.1.3.1 Directory structure

The root directory of the simulation can be anywhere on your PC, for example `C:\Work\emWinSim`. The directory structure will appear as shown below. This structure is very similar to that which we recommend for your target application (see *Getting Started* on page 94 for more information).



The following table shows the contents of the folders:

Directory	Content
`Doc`	Contains the emWin documentation.
`Sample`	Code examples, described later in this documentation.
`Start`	All you need to create a new project with emWin.
`Tool`	Tools shipped with emWin.

A new project can be started by making a copy of the Start-folder. It contains all required files for a new project. Subdirectories containing the emWin sources are in the `Start\GUI` folder and should contain the exact same files as the directories of the same names which

 © 2020 SEGGER Microcontroller GmbH

are used for your target (cross) compiler. The files of the GUI subdirectories should not be changed, as this would make updating to a newer version of emWin more difficult. The `Start\Config` directory contains configuration files which need to be modified in order to reflect your target hardware settings (mainly LCD-size and colors which can be displayed).



3.1.3.2 Visual C++ workspace

The root directory shown above includes the Microsoft Visual C++ workspace (`Simulation.dsw`) and project files (`Simulation.dsp`). The workspace allows you to modify an application program and debug it before compiling it on your target system. The directory structure of the Visual C++ workspace will appear similar to that shown to the right. Here, the `GUI` folder is open to display the emWin subdirectories. Note that your `GUI` directory may not look exactly like the one pictured, depending on which additional features of emWin you have. The folders `Core`, `Font` and `DisplayDriver` are part of the basic emWin package and will always appear in the workspace directory.



3.1.3.3 Compiling the application

The simulation contains one or more application C files (located in the `Application` directory), which can be modified or removed and additional files can be added to the project. You should then rebuild the program within the Visual C++ workspace in order to test/debug it. Once you have reached a point where you are satisfied with the result and want to use the program in your application, you should be able to compile these same files on your target system and get the same result on the target display. The general procedure for using the simulation would be as follows:

- **Step 1:** Open the Visual C++ workspace by double-clicking on `Simulation.dsw`.
- **Step 2:** Compile the project by choosing **Build ➔ Rebuild All** from the menu (or by pressing F7).

 © 2020 SEGGER Microcontroller GmbH

- **Step 3:** Run the simulation by choosing **Build ➔ Start Debug ➔ Go** from the menu (or by pressing F5).
- **Step 4:** Replace the bitmap with your own logo or image.
- **Step 5:** Make further modifications to the application program as you wish, by editing the source code or adding/deleting files.
- **Step 6:** Compile and run the application program within Visual C++ to test the results. Continue to modify and debug as needed.
- **Step 7:** Compile and run the application program on your target system.

3.1.4 Advanced features of the simulation

Clicking the right mouse button shows a context menu with several advanced functions:



3.1.4.1 Pause and Resume

These menu items allows to pause and to resume the application currently running in the simulation. The same can be done by pressing **<F4>** or **<F5>**. Trying to pause an already paused application or trying to resume an already running application causes an error message.

3.1.4.2 View system info

This menu item opens a further window with information of the memory currently used by the application. The window continuously shows the current status of memory consumption by showing the free and used bytes and the free and used number of memory blocks.



3.1.4.3 Copy to clipboard

This menu item copies the current contents of the display into the clipboard. This makes it easy to use it for documentation purpose with other applications.

 © 2020 SEGGER Microcontroller GmbH

3.2 Device simulation

The device simulation supports 3 views:

- Generated frame view
- Custom bitmap view
- Window view

The table below shows the different views:

Generated frame view	Custom bitmap view
	

Window view



The following will explain in detail how each option can be used.

3.2.1 Generated frame view

The simulation shows the display inside an automatically generated frame surrounding the display. The frame contains a small button which per default closes the application. This is the default behavior of the simulation for single layer systems. 'Single layer system' means that only the first layer is initialized.

 © 2020 SEGGER Microcontroller GmbH



3.2.2 Custom bitmap view

The simulation can show the simulated display in a bitmap of your choice, typically your target device. The bitmap can be used to simulate the behavior of the entire target device. In order to simulate the appearance of the device, bitmaps are required.

Device bitmap

The first bitmap is usually a photo (top view) of the device, and needs to be named Device.bmp. It may be a separate file (in the same directory as the executable), or it may be included as a resource in the application. How to do this is explained later in this chapter. The file should provide an area for the simulated display of the same size in pixels as the physical display resolution.
If there are any hardkeys to be simulated the bitmap should also show all of them in unpressed state.



Transparent areas need to be colored with exact the same color as defined with the function `SIM_GUI_SetTransColor()`, typically bright red (`0xFF0000`). These areas do not have to be rectangular; they can have an arbitrary shape (up to a certain complexity which is limited by your operating system, but is normally sufficient). Bright red is the default color for transparent areas, mainly because it is not usually contained in most bitmaps. To use a bitmap with bright red, the default transparency color may be changed with the function `SIM_GUI_SetTransColor()`.

Hardkey bitmap

The second bitmap file is required for defining the hardkeys and must be named `Device1.bmp`. It contains the buttons in pressed state. The non hardkey area has to be filled with the transparent color. This is only a short description. For more details about how to simulate hardkeys, see *Hardkey simulation* on page 141.

 © 2020 SEGGER Microcontroller GmbH



Using separate files

When starting the simulation, it checks if the directory of the executable contains the bitmap files `Device.bmp` and `Device1.bmp`. If these files are available, they are used automatically and the resource bitmaps are ignored. Note that this is only valid with single layer systems.

Adding the bitmap to the application resources

The resource file of the simulation can be found under `System\Simulation\Res\Simulation.rc`. It contains the following section:

```
/////////////////////////////////////////////////////////////////////////
//
// Customizable bitmaps
//
IDB_DEVICE              BITMAP  DISCARDABLE     "Device.bmp"
IDB_DEVICE1             BITMAP  DISCARDABLE     "Device1.bmp"
```

This section can be used to set custom device files. More information can be found in the Win32 documentation.

3.2.3 Window view

Default for simulating a multiple layer system is showing each layer in a separate window without using bitmaps or a generated frames.

 © 2020 SEGGER Microcontroller GmbH

3.3 Device simulation API

All of the device simulation API functions should be called in the setup phase. The calls should be done from within the routine `SIM_X_Config()`, which is located in the file `SIM-Conf.c` in the configuration folder. The example below calls `SIM_SetLCDPos()` in the setup:

```
#include "LCD_SIM.h"
void SIM_X_Config() {
  SIM_GUI_SetLCDPos(50, 20); // Define the position of the LCD in the bitmap}
}
```

Functions

Routine	Description
SIM_GUI_Delay()	Stops execution of simulation thread for the given period.
SIM_GUI_ExecIdle()	Called by the simulation on idle time.
SIM_GUI_GetCompositeTouch()	Returns the layer index to be passed to emWin if the composite view is touched by the PID.
SIM_GUI_GetTime()	Returns the period of time in ms elapsed since starting the simulation.
SIM_GUI_SaveBMP()	Saves a BMP file containing the current layer.
SIM_GUI_SaveBMPEx()	Saves a BMP file containing the given section of the current layer.
SIM_GUI_SaveCompositeBMP()	Saves a BMP file containing the current content of the composite view.
SIM_GUI_SetCallback()	Sets a callback function for receiving the handles of the simulation windows.
SIM_GUI_SetCompositeColor()	Sets the background color of the composite window. (Only used with MultiLayer support)
SIM_GUI_SetCompositeSize()	Enables composite window mode and sets the size of the composite window. (Only used with MultiLayer support)
SIM_GUI_SetCompositeTouch()	Sets the layer index to be used for touch events on the composite view.
SIM_GUI_SetLCDColorBlack()	Set the colors to be used as black on color monochrome displays.
SIM_GUI_SetLCDColorWhite()	Set the colors to be used as white on color monochrome displays.
SIM_GUI_SetLCDPos()	Sets the position for the simulated LCD within the target device bitmap.
SIM_GUI_SetMag()	Sets magnification factors for X and/or Y axis.
SIM_GUI_SetTransColor()	Sets the color to be used for transparent areas of device or hardkey bitmaps.
SIM_GUI_SetTransMode()	Sets the transparency mode for the given layer.
SIM_GUI_ShowDevice()	When using multiple layers, this function can be used to show the device bitmap.
SIM_GUI_UseCustomBitmaps()	Tells the simulation to use the custom bitmaps from the application resource file.

 © 2020 SEGGER Microcontroller GmbH

Data structures

Structure	Description
SIM_GUI_INFO	Contains the window handles of the simulation.

Defines

Group of defines	Description
Transparency modes	Available transparency modes for layers.

 © 2020 SEGGER Microcontroller GmbH

3.3.1 Functions

3.3.1.1 SIM_GUI_Delay()

Description

Stops execution of simulation thread for the given period.

Prototype

```
void SIM_GUI_Delay(int ms);
```

Parameters

Parameter	Description
ms	Period to be used.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.2 SIM_GUI_ExecIdle()

Description

Called by the simulation on idle time.

Prototype

```
void SIM_GUI_ExecIdle(void);
```

 © 2020 SEGGER Microcontroller GmbH

3.3.1.3 SIM_GUI_GetCompositeTouch()

Description

Returns the layer index to be passed to emWin if the composite view is touched by the PID.

Prototype

```
int SIM_GUI_GetCompositeTouch(void);
```

Return value

Layer index passed to emWin if the composite view is touched.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.4 SIM_GUI_GetTime()

Description

Returns the period of time in ms elapsed since starting the simulation.

Prototype

```
int SIM_GUI_GetTime(void);
```

Return value

Period of time in ms elapsed since starting the simulation.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.5 SIM_GUI_SaveBMP()

Description

Saves a BMP file containing the current layer.

Prototype

```
int SIM_GUI_SaveBMP(const char * sFileName);
```

Parameters

Parameter	Description
sFileName	Filename to be used.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.6 SIM_GUI_SaveBMPEx()

Description

Saves a BMP file containing the given section of the current layer.

Prototype

```
int SIM_GUI_SaveBMPEx(const char * sFileName,
                      int    x0,
                      int    y0,
                      int    xSize,
                      int    ySize);
```

Parameters

Parameter	Description
sFileName	Filename to be used.
x0	Left coordinate of the first pixels to be saved.
y0	Top coordinate of the first pixels to be saved.
xSize	X-size in pixels of the section to be saved.
ySize	Y-size in pixels of the section to be saved.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.7 SIM_GUI_SaveCompositeBMP()

Description

Saves a BMP file containing the current content of the composite view.

Prototype

```
int SIM_GUI_SaveCompositeBMP(const char * sFileName);
```

Parameters

Parameter	Description
sFileName	Filename to be used.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.8 SIM_GUI_SetCallback()

Description

If it is required to simulate more than the display window or hardkeys, you can set a callback function to receive the window handles of the simulation. This opens up the possibility e.g. to add additional controls outside of the display window like leds or sliders. Please note that the emWin functions can not be used there.

Prototype

```
void SIM_GUI_SetCallback(int ( *pfCallback)(SIM_GUI_INFO * pInfo ));
```

Parameters

Parameter	Description
pfInfoCallback	Pointer to the callback function. The function has to expect a pointer to a SIM_GUI_INFO structure as a parameter.

Elements of structure SIM_GUI_INFO

Data type	Element	Description
HWND	hWndMain	Handle to the main window.
HWND	ahWndLCD[16]	Array of handles to the display layers.
HWND	ahWndColor[16]	Array of handles to the palette layers.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.9 SIM_GUI_SetCompositeColor()

Description

When simulating a multiple layer system each layer can be shown in its own window. However, the physical display has only one area. It shows the result of the blended layers. The simulation shows the result in the composite window which can have its own size independent of the layers. Each layer can have its own position and its own size within the composite window. This means that not necessarily the complete area is covered by the layers. For this case (and also for transparency effects) this function sets the default background color of the composite window.

Prototype

```
void SIM_GUI_SetCompositeColor(U32 Color);
```

Parameters

Parameter	Description
Color	Background color to be used.

Additional information

This function does not have an effect when using SoftLayers.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.10 SIM_GUI_SetCompositeSize()

> **Note**
>
> This function also enables the composite window mode. It is used in `SIM_X_Config()`.

Description

As described above under `SIM_GUI_SetCompositeColor()` the size of the composite window is independent of the size of the layers. This function is used to set the size of the composite window, as well as enable the composite window mode.

Prototype

```
void SIM_GUI_SetCompositeSize(int xSize,
                              int ySize);
```

Parameters

Parameter	Description
`xSize`	Horizontal size in pixels.
`ySize`	Vertical size in pixels.

Example

This example screenshot shows the enabled composite window mode. The two layers are shown on the right and on the left is the composite window, which shows the two layers merged.



 © 2020 SEGGER Microcontroller GmbH

3.3.1.11 SIM_GUI_SetCompositeTouch()

Description

Sets the layer index to be passed to emWin if the composite view is touched by the PID.

Prototype

```
void SIM_GUI_SetCompositeTouch(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer index to be used for touch events on the composite view.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.12 SIM_GUI_SetLCDColorBlack()

3.3.1.13 SIM_GUI_SetLCDColorWhite()

Description

Set the colors to be used as black or white, respectively, on color monochrome displays.

Prototypes

```
int SIM_GUI_SetLCDColorBlack(int DisplayIndex,
                             int Color);

int SIM_GUI_SetLCDColorWhite(int DisplayIndex,
                             int Color);
```

Parameters

Parameter	Description
DisplayIndex	Reserved for future use; must be 0.
Color	RGB value of the color.

Additional information

These functions can be used to simulate the true background color of your display. The default color values are black and white, or 0x000000 and 0xFFFFFF. Refer to SIM_GUI_SetLCDColorBlack() for an example.

Example using default settings

```
void SIM_X_Config() {
  SIM_GUI_SetLCDPos(14,84);                 // Define the position of the LCD
                                            // in the bitmap
  SIM_GUI_SetLCDColorBlack (0, 0x000000);   // Define the color used as black
  SIM_GUI_SetLCDColorWhite (0, 0xFFFFFF);   // Define the color used as white
  (used for colored monochrome displays)
}
```



Example using yellow instead of white

```
void SIM_X_Config() {
  SIM_GUI_SetLCDPos(14,84);                 // Define the position of the LCD
                                            // in the bitmap
  SIM_GUI_SetLCDColorBlack (0, 0x000000);   // Define the color used as black
  SIM_GUI_SetLCDColorWhite (0, 0x00FFFF);   // Define the color used as white
  (used for colored monochrome displays)
}
```

 © 2020 SEGGER Microcontroller GmbH



 © 2020 SEGGER Microcontroller GmbH

3.3.1.14 SIM_GUI_SetLCDPos()

Description

Sets the position for the simulated LCD within the target device bitmap.

Prototype

```
void SIM_GUI_SetLCDPos(int xPos,
                       int yPos);
```

Parameters

Parameter	Description
xPos	X-position of the upper left corner for the simulated LCD (in pixels).
yPos	Y-position of the upper left corner for the simulated LCD (in pixels).

Additional information

The X- and Y-positions are relative to the target device bitmap, therefore position (0,0) refers to the upper left corner (origin) of the bitmap and not your actual LCD. Only the origin of the simulated screen needs to be specified; the resolution of your display should already be reflected in the configuration files in the Config directory. The use of this function enables the use of the bitmaps Device.bmp and Device1.bmp . Note that the values need to be ≥ 0 for enabling the use of the bitmaps. If the use of the device bitmaps should be disabled, omit the call of this function in `SIM_X_Init()`.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.15 SIM_GUI_SetMag()

Description

Sets magnification factors for X and/or Y axis.

Prototype

```
void SIM_GUI_SetMag(int MagX,
                    int MagY);
```

Parameters

Parameter	Description
MagX	Magnification factor for X axis.
MagY	Magnification factor for Y axis.

Additional information

Per default the simulation uses one pixel on the PC for each pixel of the simulated display. The use of this function makes sense for small displays. If using a device bit- map together with a magnification > 1 the device bitmap needs to be adapted to the magnification. The device bitmap is not magnified automatically.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.16 SIM_GUI_SetTransColor()

Description

Sets the color to be used for transparent areas of device or hardkey bitmaps.

Prototype

```
int SIM_GUI_SetTransColor(int Color);
```

Parameters

Parameter	Description
Color	RGB value of the color in the format 00000000RRRRRRRRGGGGGGGGBBBBBBBB.

Additional information

The default setting for transparency is bright red (0xFF0000). You would typically only need to change this setting if your bitmap contains the same shade of red.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.17 SIM_GUI_SetTransMode()

Description

Sets the transparency mode for the given layer.

Prototype

```
void SIM_GUI_SetTransMode(int LayerIndex,
                          int TransMode);
```

Parameters

Parameter	Description
LayerIndex	Index of the layer for which the transparency mode should be set.
TransMode	Permitted values are listed under *Transparency modes* on page 140.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.18 SIM_GUI_ShowDevice()

Before	After
	

Description

When using multiple layers, this function can be used to show the device bitmap. By default each layer and the composite view are displayed in separate windows.

Prototype

```
void SIM_GUI_ShowDevice(int OnOff);
```

Parameters

Parameter	Description
OnOff	1 for showing the bitmap, 0 for hiding it.

Return value

Period of time in ms elapsed since starting the simulation.

Additional information

This function has no impact in case only 1 layer is configured.

 © 2020 SEGGER Microcontroller GmbH

3.3.1.19 SIM_GUI_UseCustomBitmaps()

Description

As described earlier in this chapter it is possible to use device bitmaps from the application resources. This function tells the simulation to use the device- and hardkey bitmaps from the application resources and not to generate the default frame bitmap.

Prototype

```
void SIM_GUI_UseCustomBitmaps(void);
```

Parameters

Parameter	Description
LayerIndex	Index of the layer for which the transparency mode should be set.
TransMode	Permitted values are listed below.

Additional information

The emWin shipment contains per default 2 bitmaps, Device.bmp and Device1.bmp, located in Start which can be used as a starting point for your own bitmaps.

 © 2020 SEGGER Microcontroller GmbH

3.3.2 Data structures

3.3.2.1 SIM_GUI_INFO

Description

Contains the window handles of the simulation. This structure is required for `SIM_GUI_SetCallback()`.

Type definition

```
typedef struct {
  HWND  hWndMain;
  HWND  ahWndLCD[];
  HWND  ahWndColor[];
} SIM_GUI_INFO;
```

Structure members

Member	Description
hWndMain	Handle to the main window.
ahWndLCD	Array of handles to the display layers.
ahWndColor	Array of handles to the palette layers.

 © 2020 SEGGER Microcontroller GmbH

3.3.3 Defines

3.3.3.1 Transparency modes

Description

Available transparency modes for layers.

Definition

```
#define GUI_TRANSMODE_PIXELALPHA    0
#define GUI_TRANSMODE_ZERO          2
```

Symbols

Definition	Description
GUI_TRANSMODE_PIXELALPHA	The alpha value is taken from the pixel data in order to mix colors with the according background.
GUI_TRANSMODE_ZERO	In this mode pixels are fully transparent if the pixel data equals 0.

 © 2020 SEGGER Microcontroller GmbH

3.4 Hardkey simulation

The hardkey simulation can only be used in the custom bitmap view. Hardkeys may also be simulated as part of the device, and may be selected with the mouse pointer. The idea is to be able to distinguish whether a key or button on the simulated device is pressed or unpressed. A hardkey is considered "pressed" as long as the mouse button is held down; releasing the mouse button or moving the pointer off of the hardkey releases the key. A toggle behavior between pressed and unpressed may also be specified with the routine `SIM_HARDKEY_SetMode()`. In order to simulate hardkeys, you need a second bitmap of the device which is transparent except for the keys themselves (in their pressed state). As described earlier in this chapter, this bitmap can be in a separate file in the directory, or included as a resource in the executable. Hardkeys may be any shape, as long as they are exactly the same size in pixels in both `Device.bmp` and `Device1.bmp`. The following example illustrates this:

Device bitmap: unpressed hardkey state (Device.bmp)	Device hardkey bitmap: pressed hardkey state (Device1.bmp)
	

When a key is "pressed" with the mouse, the corresponding section of the hardkey bitmap (`Device1.bmp`) will overlay the device bitmap in order to display the key in its pressed state. The keys may be polled periodically to determine if their states (pressed/unpressed) have changed and whether they need to be updated. Alternatively, a callback routine may be set to trigger a particular action to be carried out when the state of a hardkey changes.

3.4.1 Hardkey simulation API

The hardkey simulation functions are part of the standard simulation program shipped with emWin. If using a user defined emWin simulation these functions may not be available. The table below lists the available hardkey-simulation-related routines in alphabetical order within their respective categories. Detailed descriptions of the routines follow:

Routine	Description
`SIM_HARDKEY_GetNum()`	Returns the number of available hardkeys.
`SIM_HARDKEY_GetState()`	Returns the state of a specified hardkey.
`SIM_HARDKEY_SetCallback()`	Sets a callback routine to be executed when the state of a specified hardkey changes.
`SIM_HARDKEY_SetMode()`	Sets the behavior for a specified hardkey.
`SIM_HARDKEY_SetState()`	Sets the behavior for a specified hardkey.

 © 2020 SEGGER Microcontroller GmbH

3.4.1.1 SIM_HARDKEY_GetNum()

Description

Returns the number of available hardkeys.

Prototype

```
int SIM_HARDKEY_GetNum(void);
```

Return value

The number of available hardkeys found in the bitmap.

Additional information

The numbering order for hardkeys is standard reading order (left to right, then top to bottom). The topmost pixel of a hardkey is therefore found first, regardless of its horizontal position. In the bitmap below, for example, the hardkeys are labeled as they would be referenced by the `KeyIndex` parameter in other functions:



It is recommended to call this function in order to verify that a bitmap is properly loaded.

 © 2020 SEGGER Microcontroller GmbH

3.4.1.2 SIM_HARDKEY_GetState()

Description

Returns the state of a specified hardkey.

Prototype

```
int SIM_HARDKEY_GetState(unsigned int i);
```

Parameters

Parameter	Description
KeyIndex	Index of hardkey (0 = index of first key).

Return value

State of the specified hardkey.

0	unpressed.
1	pressed.

 © 2020 SEGGER Microcontroller GmbH

3.4.1.3 SIM_HARDKEY_SetCallback()

Description

Sets a callback routine to be executed when the state of a specified hardkey changes.

Prototype

```
SIM_HARDKEY_CB *SIM_HARDKEY_SetCallback(unsigned int     KeyIndex,
                                        SIM_HARDKEY_CB * pfCallback);
```

Parameters

Parameter	Description
KeyIndex	Index of hardkey (0 = index of first key).
pfCallback	Pointer to callback routine.

Return value

Pointer to the previous callback routine.

Additional information

Note that multi tasking support has to be enabled if GUI functions need to be called within the callback functions. Without multi tasking support only the GUI functions which are allowed to be called within an interrupt routine should be used. The callback routine must have the following prototype:

Prototype of SIM_HARDKEY_CB

```
void SIM_HARDKEY_CB(int KeyIndex,
                    int State);
```

Parameter	Description
KeyIndex	Index of hardkey (0 = index of first key).
State	State of the specified hardkey. 0 for unpressed, 1 for pressed.

 © 2020 SEGGER Microcontroller GmbH

3.4.1.4 SIM_HARDKEY_SetMode()

Description

Sets the behavior for a specified hardkey.

Prototype

```
int SIM_HARDKEY_SetMode(unsigned int KeyIndex,
                        int          Mode);
```

Parameters

Parameter	Description
KeyIndex	Index of hardkey (0 = index of first key).
Mode	Behavior mode. 0 for normal behavior (default), 1 for toggle behavior.

Additional information

Normal (default) hardkey behavior means that a key is considered pressed only as long as the mouse button is held down on it. When the mouse is released or moved off of the hardkey, the key is considered unpressed.

With toggle behavior, each click of the mouse toggles the state of a hardkey to pressed or unpressed. That means if you click the mouse on a hardkey and it becomes pressed, it will remain pressed until you click the mouse on it again.

 © 2020 SEGGER Microcontroller GmbH

3.4.1.5 SIM_HARDKEY_SetState()

Description

Sets the behavior for a specified hardkey.

Prototype

```
int SIM_HARDKEY_SetState(unsigned int i,
                         int          State);
```

Parameters

Parameter	Description
KeyIndex	Index of hardkey (0 = index of first key).
State	State of the specified hardkey. See table below.

Return value

Previous state of the key updated.

Additional information

This function is only usable when SIM_HARDKEY_SetMode() is set to 1 (toggle mode).

 © 2020 SEGGER Microcontroller GmbH

3.5 Integrating the emWin simulation into an existing simulation

In order to integrate the emWin simulation into an existing simulation, the source code of the simulation is not required. Only in some rare cases it is required to use the source code of the simulation. If required the source code of the simulation can be purchased separately and it is not part of a normal emWin shipment.
As described earlier in this chapter the basic package and the trial version contains a simulation library. The API functions of this library can be used if for example the emWin simulation should be added to an existing hardware or real time kernel (RTOS) simulation.
To add the emWin simulation to an existing simulation (written in C or C++, using the Win32 API), only a few lines of code need to be added.

3.5.1 Directory structure

The subfolder Simulation of the System folder contains the emWin simulation. The directory structure is shown on the right. The table below explains the contents of the subfolders:



Directory	Content
`Simulation`	Simulation source and header files to be used with and without the simulation source code. The folder also contains a ready to use simulation library.
`Res`	Resource files.
`SIM_GUI`	GUI simulation source code (optional).
`WinMain`	Contains the WinMain routine.

3.5.2 Using the simulation library

The following steps will show how to use the simulation library to integrate the emWin simulation into an existing simulation:

- **Step 1:** Add the simulation library `GUISim.lib` to the project.
- **Step 2:** Add all GUI files to the project as described in the chapter *Subdirectories* on page 96.
- **Step 3:** Add the include directories to the project as described in the chapter *Include Directories*.
- **Step 4:** Modify `WinMain()` or `SIM_OS.c`.

3.5.2.1 Modifying WinMain

Every windows Win32 program starts with `WinMain()` (contrary to a normal C program from the command line, which starts with main(). All that needs to be done is to add a few lines of code to this routine.
The following function calls need to be added (normally in the order as it is shown in the following application code example):

- `SIM_GUI_Enable()`
- `SIM_GUI_Init()`
- `SIM_GUI_CreateLCDWindow()`
- `CreateThread()`
- `SIM_GUI_Exit()`

 © 2020 SEGGER Microcontroller GmbH

3.5.2.2 Example application

The following application is available under `Sample\WinMain\SampleApp.c` and shows how to integrate the emWin simulation into an existing application:

```
#include <windows.h>
#include "GUI_SIM_Win32.h"
void MainTask(void);
/*********************************************************************
*
*       _Thread
*/
static DWORD __stdcall _Thread(void * Parameter) {
  MainTask();
  return 0;
}
/*********************************************************************
*
*       _WndProcMain
*/
static LRESULT CALLBACK _WndProcMain(HWND   hWnd,   UINT   message,
                                     WPARAM wParam, LPARAM lParam) {
  SIM_GUI_HandleKeyEvents(message, wParam);
  switch (message) {
  case WM_DESTROY:
    PostQuitMessage(0);
    break;
  }
  return DefWindowProc(hWnd, message, wParam, lParam);
}
/*********************************************************************
*
*       _RegisterClass
*/
static void _RegisterClass(HINSTANCE hInstance) {
  WNDCLASSEX wcex;
  memset(&wcex, 0, sizeof(wcex));
  wcex.cbSize        = sizeof(WNDCLASSEX);
  wcex.hInstance     = hInstance;
  wcex.style         = CS_HREDRAW | CS_VREDRAW;
  wcex.lpfnWndProc   = (WNDPROC)_WndProcMain;
  wcex.hIcon         = 0;
  wcex.hCursor       = LoadCursor(NULL, IDC_ARROW);
  wcex.hbrBackground = (HBRUSH)(COLOR_APPWORKSPACE + 1);
  wcex.lpszMenuName  = 0;
  wcex.lpszClassName = "GUIApplication";
  RegisterClassEx(&wcex);
}
/*********************************************************************
*
*       WinMain
*/
int APIENTRY WinMain(HINSTANCE hInstance, HINSTANCE hPrevInstance,
                     LPSTR     lpCmdLine, int       nCmdShow) {
  DWORD ThreadID;
  MSG   Msg;
  HWND  hWndMain;
  //
  // Register window class
  //
  _RegisterClass(hInstance);
  //
  // Make sure the driver configuration is done
  //
  SIM_GUI_Enable();
  //
  // Create main window
```

 © 2020 SEGGER Microcontroller GmbH

```
  //
  hWndMain = CreateWindow("GUIApplication", "Application window",
                          WS_OVERLAPPEDWINDOW | WS_CLIPCHILDREN | WS_VISIBLE,
                          0, 0, 328, 267, NULL, NULL, hInstance, NULL);
  //
  // Initialize the emWin simulation and create an LCD window
  //
  SIM_GUI_Init(hInstance, hWndMain, lpCmdLine, "embOS - emWin Simulation");
  SIM_GUI_CreateLCDWindow(hWndMain, 0, 0, 320, 240, 0);
  //
  // Create a thread which executes the code to be simulated
  //
  CreateThread(NULL, 0, (LPTHREAD_START_ROUTINE)_Thread, NULL, 0, &ThreadID);
  //
  // Main message loop
  //
  while (GetMessage(&Msg, NULL, 0, 0)) {
    TranslateMessage(&Msg);
    DispatchMessage(&Msg);
  }
  SIM_GUI_Exit();
}
```

3.5.3 Integration into the embOS Simulation

3.5.3.1 SIM_OS.c

The following code example shows how to modify the existing SIM_OS.c of the embOS simulation in order to integrate the emWin simulation. Only four lines of coded have to be added to the function _WindowThread(). Add an include of GUI_SIM_Win32.h and the three function calls with prefix SIM_GUI_<FunctionName>() as shown below:

```
...
#include "GUI_SIM_Win32.h"
...
static DWORD WINAPI _WindowThread(LPVOID lpParameter) {
  BITMAP    BmpDevice;
  HINSTANCE hInstance;
  HACCEL    hAcceleratorTable;
  MSG       Msg;

  OS_USEPARA(lpParameter);
  //
  // Create a window. This window is used to simulate blinking LEDs.
  //
  _RegisterClass();
  hInstance         = GetModuleHandle(NULL);
  hAcceleratorTable = LoadAccelerators(hInstance,
                                       MAKEINTRESOURCE(SIM_OS_IDC_WINMAIN));
  _hBmpDevice
  = (HBITMAP)LoadImage(hInstance, MAKEINTRESOURCE(SIM_OS_IDB_DEVICE),
                                         IMAGE_BITMAP, 0, 0, 0);
  _hMenuPopup
  = LoadMenu(hInstance, MAKEINTRESOURCE(SIM_OS_IDC_CONTEXTMENU));
  _hMenuPopup       = GetSubMenu(_hMenuPopup, 0);
  //
  // Create main window
  //
  GetObject(_hBmpDevice, sizeof(BmpDevice), &BmpDevice);
  _hWnd = CreateWindowEx(0, _sWindowClass, "embOS Simulation",
                         WS_SYSMENU | WS_CLIPCHILDREN | WS_POPUP | WS_VISIBLE,
                         10, 20, BmpDevice.bmWidth, BmpDevice.bmHeight, NULL,
                         NULL, hInstance, NULL);
  if (_hWnd == NULL) {
    _ErrorWin32("Could not create window.");
```

 © 2020 SEGGER Microcontroller GmbH

```
    return -1;  // Error
  }
  //
  // Init emWin simulation and create window
  //
  SIM_GUI_Enable();
  SIM_GUI_Init(hInstance, _hWnd, "", "embOS - emWin Simulation");
  SIM_GUI_CreateLCDWindow(_hWnd, 0, 0, 320, 240, 0);
  //
  // Show main window
  //
  ShowWindow(_hWnd, SW_SHOWNORMAL);
#if defined(SIM_OS_TIMER_PERIOD) && (SIM_OS_TIMER_PERIOD != 0)
  //
  // Create a timer which is periodically invalidating the Win32 window in order
  // to redraw it
  //
  SetTimer(_hWnd, 0, SIM_OS_TIMER_PERIOD, _cbTimer);
#endif
  //
  // Handle message loop
  //
  while (GetMessage(&Msg, NULL, 0, 0)) {
    if (!TranslateAccelerator(_hWnd, hAcceleratorTable, &Msg)) {
      TranslateMessage(&Msg);
      DispatchMessage(&Msg);
    }
  }
  ExitProcess(0);
  return 0;
}
```

3.5.3.2 Target program (main)

The emWin API can be called from one or more target threads. Without RTOS, the WIN32 API function `CreateThread` is normally used to create a target thread which calls the emWin API; within an RTOS simulation, a target task/thread (Created by the simulated RTOS) is used to call the emWin API. In other words: Use `OS_CreateTask` to create a task for the user interface. Below a modified embOS start application:

```
#include <windows.h>
#include "RTOS.H"
#include "HW_LED.h"
#include "GUI.h"
OS_STACKPTR int Stack0[128], Stack1[128], Stack2[2000]; // Task stacks
OS_TASK        TCB0,        TCB1,        TCB2;         // Task-control-blocks
void Task0(void) {
  while (1) {
    HW_LED_Toggle0();
    OS_Delay(100);
  }
}
void Task1(void) {
  while (1) {
    HW_LED_Toggle1();
    OS_Delay(500);
  }
}
void MainTask(void) {
  int i;
  GUI_COLOR aColor[] = {GUI_RED, GUI_YELLOW};
  GUI_Init();
  while (1) {
    for (i = 0; i < 2; i++) {
      GUI_Clear();
      GUI_SetColor(aColor[i]);
```

 © 2020 SEGGER Microcontroller GmbH

```
      GUI_SetFont(&GUI_FontComic24B_ASCII);
      GUI_DispStringAt("Hello world!", 1, 1);
      OS_Delay(200);
    }
  }
}
/*************************************************************
*
*       main
*/
void main(void) {
  OS_IncDI();           // Initially disable interrupts
  OS_InitKern();        // Initialize OS
  OS_InitHW();          // Initialize Hardware for OS
  //
  // At least one task here needs to be created here
  //
  OS_CREATETASK(&TCB0, "HP Task",  Task0,    100, Stack0);
  OS_CREATETASK(&TCB1, "LP Task",  Task1,     50, Stack1);
  OS_CREATETASK(&TCB2, "GUI Task", MainTask,  80, Stack2);
  OS_Start();           // Start multitasking
}
```

The following table shows the simulation before and after integrating the emWin simulation:

Before	After
	

3.5.4 GUI simulation API

The table below lists the available routines for user defined simulation programs in alphabetical order within their respective categories. The functions are only available with the source code of the emWin simulation. Detailed descriptions of the routines follow:

Routine	Description
SIM_GUI_CreateLCDInfoWindow()	Creates a window which shows the available colors for the given layer.
SIM_GUI_CreateLCDWindow()	Creates a window which simulates a LCD display with the given size at the given position.
SIM_GUI_Enable()	Executes memory and driver configuration.
SIM_GUI_Exit()	Stops the GUI simulation.
SIM_GUI_Init()	Initializes the GUI simulation.
SIM_GUI_SetLCDWindowHook()	Sets a hook function to be called from the simulation if the LCD window receives a message.

 © 2020 SEGGER Microcontroller GmbH

3.5.4.1 SIM_GUI_CreateLCDInfoWindow()

Description

Creates a window which shows the available colors for the given layer.

Prototype

```
HWND SIM_GUI_CreateLCDInfoWindow(HWND hParent,
                                 int  x,
                                 int  y,
                                 int  xSize,
                                 int  ySize,
                                 int  LayerIndex);
```

Parameters

Parameter	Description
hParent	Handle of the parent window.
x	X position in parent coordinates.
y	Y position in parent coordinates.
xSize	X size in pixel of the new window. Should be 160 if using a color depth between 1 and 8 or 128 if working in high color mode.
ySize	Y size in pixel of the new window. Should be 160 if using a color depth between 1 and 8 or 128 if working in high color mode.
LayerIndex	Index of the layer to be shown.

Return value

Handle of the created window.

Additional information

The created color window has no frame, no title bar and no buttons.

Example

```
SIM_GUI_CreateLCDInfoWindow(hWnd, 0, 0, 160, 160, 0);
```

Screenshot



 © 2020 SEGGER Microcontroller GmbH

3.5.4.2 SIM_GUI_CreateLCDWindow()

Description

Creates a window which simulates a LCD display with the given size at the given position.

Prototype

```
HWND SIM_GUI_CreateLCDWindow(HWND hParent,
                             int  x,
                             int  y,
                             int  xSize,
                             int  ySize,
                             int  LayerIndex);
```

Parameters

Parameter	Description
hParent	Handle of the parent window.
x	X position in parent coordinates.
y	Y position in parent coordinates.
xSize	X size in pixel of the new window.
ySize	Y size in pixel of the new window.
LayerIndex	Index of the layer to be shown.

Return value

Handle of the created window.

Additional information

All display output to the given layer will be shown in this window. The size of the window should be the same as configured in LCDConf.c. The created simulation window has no frame, no title bar and no buttons.

 © 2020 SEGGER Microcontroller GmbH

3.5.4.3 SIM_GUI_Enable()

Description

The function needs to be called at the beginning of the application to make sure that memory and driver will be configured at first.

Prototype

```
void SIM_GUI_Enable(void);
```

 © 2020 SEGGER Microcontroller GmbH

3.5.4.4 SIM_GUI_Exit()

Description

The function should be called before the simulation returns to the calling process.

Prototype

```
void SIM_GUI_Exit(void);
```

 © 2020 SEGGER Microcontroller GmbH

3.5.4.5 SIM_GUI_Init()

Description

This function initializes the emWin simulation and should be called before any other SIM_GUI… function call.

Prototype

```
int SIM_GUI_Init(      HINSTANCE   hInst,
                       HWND        hWndMain,
                       char      * pCmdLine,
                 const char      * sAppName);
```

Parameters

Parameter	Description
hInst	Handle to current instance passed to WinMain.
hWndMain	Handle to current instance passed to WinMain.
pCmdLine	Pointer to command line passed to WinMain
sAppName	Pointer to a string that contains the application name.

Return value

0 on success
1 on error.

Additional information

The parameters hWndMain and sAppName are used in case a message box should be displayed.

 © 2020 SEGGER Microcontroller GmbH

3.5.4.6 SIM_GUI_SetLCDWindowHook()

Description

Sets a hook function to be called from the simulation if the LCD window receives a message.

Prototype

```
void SIM_GUI_SetLCDWindowHook(SIM_GUI_tfHook * pfHook);
```

Parameters

Parameter	Description
pfHook	Pointer to hook function.

Return value

The hook function should return 0 if the message has been processed. In this case the GUI simulation ignores the message.

 © 2020 SEGGER Microcontroller GmbH

Chapter 4

Viewer

If you use the simulation when debugging your application, you cannot see the display output when stepping through the source code. The primary purpose of the viewer is to solve this problem. It shows the contents of the simulated display(s) while debugging in the simulation.

The viewer gives you the following additional capabilities:

- Multiple windows for each layer
- Watching the whole virtual layer in one window
- Magnification of each layer window
- Composite view if using multiple layers

 © 2020 SEGGER Microcontroller GmbH

4.1 Using the viewer

The viewer allows you to:

- Open multiple windows for any layer/display
- Zoom in on any area of a layer/display
- See the contents of the individual layers/displays as well as the composite view in multilayer configurations
- See the contents of the virtual screen and the visible display when using the virtual screen support.



The screenshot shows the viewer displaying the output of a single layer configuration. The upper left corner shows the simulated display. In the upper right corner is a window, which shows the available colors of the display configuration. At the bottom of the viewer a second display window shows a magnified area of the simulated display. If you start to debug your application, the viewer shows one display window per layer and one color window per layer. In a MultiLayer configuration, a composite view window will also be visible.

4.1.1 Using the simulation and the viewer

If you use the simulation when debugging your application, you cannot see the display output when stepping through the source code. This is due to a limitation of Win32: If one thread (the one being debugged) is halted, all other threads of the process are also halted. This includes the thread which outputs the simulated display on the screen. The emWin viewer solves this problem by showing the display window and the color window of your simulation in a separate process. It is your choice if you want to start the viewer before debugging your application or while you are debugging. Our suggestion:

- **Step 1:** Start the viewer. No display- or color window is shown until the simulation has been started.
- **Step 2:** Open the Visual C++ workspace.
- **Step 3:** Compile and run the application program.
- **Step 4:** Debug the application as described previously.

The advantage is that you can now follow all drawing operations step by step in the LCD window.

 © 2020 SEGGER Microcontroller GmbH

4.1.2 Using the viewer with virtual pages

By default the viewer opens one window per layer which shows the visible part of the video RAM, normally the display. If the configured virtual video RAM is larger than the display, the command **View → Virtual Layer → Layer (0...4)** can be used to show the whole video RAM in one window. When using the function `GUI_SetOrg()`, the contents of the visible screen will change, but the virtual layer window remains unchanged:



For more information about virtual screens, refer to chapter *Virtual screens / Virtual pages* on page 2393.

4.1.3 Always on top

Per default the viewer window is always on top. You can change this behavior by selecting **Options → Always on top** from the menu.

4.1.4 Open further windows of the display output

If you want to show a magnified area of the LCD output or the composite view of a MultiLayer configuration it could be useful to open more than one output window. You can do this by

- **View → Visible Layer → Layer (1...4)**,
- **View → Virtual Layer → Layer(1...4)** or
- **View → Composite**.

 © 2020 SEGGER Microcontroller GmbH

4.1.5 Zooming

Zooming in or out is easy: Right-click on a layer or composite window opens the Zoom popup menu. Choose one of the zoom options:



Using the grid



If you magnify the LCD output ≥ 300%, you have the choice between showing the output with or without a grid. It is possible to change the color of the grid. This can be done choosing the Menu point **Options ➔ Grid color**.

Adapting the size of the window

If you want to adapt the size of the window to the magnification choose **Fit window to size** from the first popup menu.

4.1.6 Copy the output to the clipboard

Click onto a LCD window or a composite view with the right mouse key and choose **Copy to clipboard**. Now you can paste the contents of the clipboard for example into the MS Paint application.

4.1.7 Using the viewer with multiple displays

If you are working with multiple displays you should set the viewer into 'Multi display mode' by using the command **Options ➔ Multi layer ➔ display**.

 © 2020 SEGGER Microcontroller GmbH



When starting the debugger the viewer will open one display window and one color window for each display:

4.1.8 Using the viewer with multiple layers

If you are working with multiple layers you should set the viewer into 'Multi layer mode' by using the command **Options ➔ Multi layer ➔ display**.



When starting the debugger the viewer will open one LCD window and one color window for each layer and one composite window for the result.

Example

The example below shows a screenshot of the viewer with 2 layers. Layer 0 shows color bars with a high color configuration. Layer 1 shows a transparent circle on a white background with colored rectangles. The composite window shows the result which is actually visible on the display.

 © 2020 SEGGER Microcontroller GmbH



Transparency

The composite window of the viewer shows all layers; layers with higher index are on top of layers with lower index and can have transparent pixels:



 © 2020 SEGGER Microcontroller GmbH

Chapter 5

AppWizard

This chapter provides an overview about what the AppWizard is and some of its features.

To learn more about the AppWizard and how to use it, refer to the document **UM03003 AppWizard User Guide & Reference Manual**.



 © 2020 SEGGER Microcontroller GmbH

5.1 About the AppWizard

What is the AppWizard?

The AppWizard is a tool for creating complete and ready-to-use emWin applications. The tool makes it very easy to build an application, manage resources and even define the application’s behavior.

What You See Is What You Get

The AppWizard tool incorporates the idea of **WYSIWYG** (What You See Is What You Get). This means while the user is building their application with the tool, they simultaneously see the output of their build.

To go along with this motto, testing is made very easy, as it just requires a quick press of the F5 key to enter **Play mode**.

Define the application's behavior

Interactions are a key part of the AppWizard, they make it very easy to define what the application should do on certain events. For example, when clicking a button, the language of the application is changed or an animation is performed and so on.

Resource management

This tool manages application resources entirely by itself. This means the user does not have to fiddle around with any text, font or image files. When adding images to the AppWizard, all of the converting is done automatically.

Font creation and image conversion can be done comfortably within the tool. No external application is required.

The text manager lets the user easily save the application’s texts in different languages, which makes building a multilingual application incredibly easy.

In case of a small addressable ROM area, the tool can also outsource all kinds of resources to an SD card. This does not have to apply for all resource files, it can be done individually for each resource file.

Target system

The AppWizard’s output works with any system having at least 32 KBytes of RAM and 128 KBytes of ROM. The tool comes with a couple of predefined BSPs. Some of them already contain a ready-to-use emFile system properly configured for the according board which makes it possible to outsource resources to SD card without writing any additional line of code. Please note that for commercial use a license is required.

Output

The AppWizard generates an application as a bundle of C source and header files. If the user wants to debug their application and, perhaps, add custom defined code, the generated application comes with a simulation project.

 © 2020 SEGGER Microcontroller GmbH

5.2 AppWizard API

The following table provides an overview of the routines related to the AppWizard.

Routine	Description
APPW_GetFont()	Fills a font structure using the addressed setup structure.
APPW_GetVarData()	Returns the value of a variable.
APPW_SetVarData()	Sets the value of a variable.

 © 2020 SEGGER Microcontroller GmbH

5.2.1 APPW_GetFont()

Description

Fills a font structure using the addressed setup structure.

Prototype

```
int APPW_GetFont(U16            IdScreen,
                 U16            IdWidget,
                 GUI_FONT     * pFont,
                 GUI_XBF_DATA * pData);
```

Parameters

Parameter	Description
IdScreen	ID of the screen.
IdWidget	ID of the widget.
pFont	GUI_FONT structure to be filled.
pData	Pointer to a GUI_XBF_DATA structure

Return value

0 Function has succeeded.
1 Function has failed.

 © 2020 SEGGER Microcontroller GmbH

5.2.2 APPW_GetVarData()

Description

Returns the value of a variable.

Prototype

```
U32 APPW_GetVarData(U16   Id,
                    int * pError);
```

Parameters

Parameter	Description
Id	ID of the variable.
pError	Pointer to integer used to return error on demand.

Return value

Data value of the specified variable.

 © 2020 SEGGER Microcontroller GmbH

5.2.3 APPW_SetVarData()

Description

Sets the value of a variable.

Prototype

```
int APPW_SetVarData(U16 Id,
                    U32 Data);
```

Parameters

Parameter	Description
Id	ID of the variable.
Data	Data value to set.

Return value

0 Function has succeeded.
1 Function has failed.

 © 2020 SEGGER Microcontroller GmbH

Chapter 6

emWinSPY

emWinSPY is designed for showing runtime information of the embedded target on a PC. It shows information about the currently connected emWin application like memory status, a tree with detailed information about all currently existing windows and a list of user input, which optionally can be written into a log file. Further it is able to take screenshots of the current screen. Communication works via a socket connection (TCP/IP) or Segger's Real Time Transfer (RTT), a technology explained in detail on our website.



 © 2020 SEGGER Microcontroller GmbH

6.1 Introduction

The emWinSPY consists of two types of components: A server on application side, which is responsible for supplying data, and the emWinSPY viewer, which requests and shows that data. Server and viewer may be on different machines and on different architectures. The communication between server and viewer could be achieved via a socket connection (TCP/IP) or via Segger's Real Time Transfer (RTT). RTT is a technology for interactive user I/O in embedded applications.

6.1.1 Requirements

RTT

If a J-Link debug probe and RTT is available on the used system, the communication could be achieved over an RTT connection. To be able to use RTT the free available RTT-code needs to be added to the project, which is available on our website:

www.segger.com/jlink-rtt.html

TCP/IP stack

Alternatively the communication between server and viewer could be achieved by a socket connection. In that case a TCP/IP stack is required. In the Win32 simulation environment, TCP/IP (Winsock) is normally present. On the target hardware a TCP/IP stack needs to be present. The TCP/IP stack is NOT part of emWin. The flexible interface ensures that any TCP/IP stack can be used.

Multi tasking

The emWinSPY server needs to run as a separate thread. Therefore a multi tasking system is required.

Compile-time configuration

Support for emWinSPY needs to be enabled using the following definition in GUIConf.h:

```
#define GUI_SUPPORT_SPY 1
```

6.1.2 Availability

Currently emWinSPY (server and viewer) is part of the basic package. It is also available in the emWin simulation and trial version.

 © 2020 SEGGER Microcontroller GmbH

6.2 Starting the emWinSPY server...

6.2.1 ...in the simulation environment

The only thing to be done here is calling `GUI_SPY_StartServer()`. In the simulation environment that function automatically starts an emWinSPY server thread which waits on port 2468 for an incoming connection.

6.2.2 ...on the target hardware

Starting the server on the target hardware works exactly the same as in the simulation by calling `GUI_SPY_StartServer()`. But whereas the simulation already contains a routine for starting the server, that routine needs to be supplied by the application on hardware side. The routine to be added is `GUI_SPY_X_StartServer()`.

6.2.3 GUI_SPY_X_StartServer

The challenge of the routine is creating a task which executes the actual server `GUI_SPY_Process()`. The way how that could be achieved depends on the used communication method.

Example

emWin comes with a ready to use sample for that function. It could be found in the sample folder: `Sample\GUI_X\GUI_SPY_X_StartServer.c`.

That sample contains a ready to use implementation to be used with JLink RTT and/or embOS/IP. It is easily adaptable to any IP-stack and any RTOS.

Prototype

```
int GUI_SPY_X_StartServer(void);
```

 © 2020 SEGGER Microcontroller GmbH

6.3 The emWinSPY viewer

6.3.1 The screen

The screen of the viewer is divided into 4 areas:

Area	Description
Status	Major purpose is showing the current state of memory allocation.
History	History of memory allocation.
Windows	Shows a tree of all existing windows.
Input	List of user interface input: Keyboard, Touch and MTouch

6.3.1.1 Status area

The table below shows the information of the status area:

Item	Description
GUI-Version	Used GUI-Version of emWin application
Total bytes	Total bytes of memory available for emWin
Free bytes	Remaining free bytes
Dynamic bytes	Number of bytes currently allocated dynamically
Fixed bytes	Number of bytes used by fixed allocation
Peak	Maximum number of bytes used (fixed + dynamic)
Max layers	Maximum number of layers configured by `GUI_NUM_LAYERS`
Used layers	Number of layers used with current configuration.
Max tasks	Maximum number of GUI-tasks

Fixed bytes / Dynamic bytes

The memory management of emWin uses 2 kinds of memory allocation: dynamic allocated memory and fixed blocks. Dynamically allocated memory can be freed and reused for further dynamic allocation operations. A fixed memory block is no longer available for dynamic memory allocation. Once a fixed memory block is allocated, that block could not be used for dynamic allocation. Examples for fixed memory blocks are driver caches or conversion buffers.

 © 2020 SEGGER Microcontroller GmbH

6.3.1.2 History area



It shows the changes of used bytes, fixed bytes and memory peak in the curse of time. The history remains after disconnecting and reconnecting. A context menu available with a right click allows clearing the history.

6.3.1.3 Windows area



That screen contains a tree of all currently existing windows with some additional information about their current states. The following table shows the available information:

Column	Description
Window	Type of window.
Handle	The handle of the window.
x0/y0	Position of the window in screen coordinates.
Width/Height	Size of the window.
Visbl.	Shows if the window (and its children) is visible or not.
Trans	Transparency flag of the window.
MDev	Shows if automatic use of memory devices is enabled for that window.
Enbl.	Shows if the window is enabled or disabled.

 © 2020 SEGGER Microcontroller GmbH

6.3.1.4 Input area



That window shows the user interface input recognized by emWinSPY. The following table shows the available information:

Column	Description
Type	PID: Pointer interface input KEY: Keyboard input MTOUCH: MultiTouch input
Time	Timestamp created on target side
Content	PID: X- and Y-position, Layer, UP or DOWN KEY: Keycode and UP or DOWN MTOUCH: X- and Y-position, TP-Id and DOWN, MOVE or UP for each TP (TP: Touchpoint)

6.3.2 Connecting to target

The connection parameters to be entered depend on the choice of communication.

Connecting via TCP/IP



An URL or an IP-address could be used here. emWinSPY remembers the last used URL for the next connection.

 © 2020 SEGGER Microcontroller GmbH

Connecting via RTT



That dialog is required to enter the according parameters for an RTT connection. emWinSPY remembers the parameters for a further connection.

6.3.3 Configuration options



'Working directory'

That folder is used for LOG-files and screenshots. The default value is the home directory of the current user.

'Log input to file'

If logging is activated (default), all user interface input is written into a file. The filename is created automatically by using the current local time of the PC. The format is `YYYY_MM_DD_HH_MM_SS_MSEC.log`. For example `2014_12_16_15_04_44_0943.log` means the file was created at 12/2014 at 16:15 and 4 seconds. The last 4 digits contain the milliseconds. Each

 © 2020 SEGGER Microcontroller GmbH

time a connection is closed (or aborted) the file is be closed and a new one is created once the connection is established again.

'Expand window tree automatically'

If that option is active the nodes of the windows tree are automatically expanded.

Reconnect to target automatically

If activated emWinSPY automatically tries to reconnect to a target after the connection has been closed.

Select connection to be used

Select between RTT and socket connection.

6.3.4 Taking a screenshot from the target



With the command **Target ➔ Get screenshot** or by pressing **<CTRL> + <G>** a BMP-file containing the current content of the screen is created. The name of the file is created automatically by the same way as described under *Log input to file* above. Only the file extension is `.bmp` instead of `.log`. The screenshot can be found in the working directory.

 © 2020 SEGGER Microcontroller GmbH

6.4 emWinSPY API

The following table lists the emWinSPY related API functions.

Routine	Description
GUI_SPY_Process()	Actual emWinSPY-server to be called from the server thread.
GUI_SPY_SetMemHandler()	This function may be used to set a memory handler for the emWinSPY.
GUI_SPY_StartServer()	Starts the server thread by calling GUI_SPY_X_StartServer().
GUI_SPY_StartServerEx()	Starts the server thread by calling the given function pointer.
GUI_SPY_X_StartServer()	Responsible for creating the actual server thread, establishing connections and calling GUI_SPY_Process() from the server thread.

 © 2020 SEGGER Microcontroller GmbH

6.4.1 GUI_SPY_Process()

Description

That function is the actual server which supplies the emWinSPY with the requested information. Simply call that function from the server thread after establishing a connection.

Prototype

```
int GUI_SPY_Process(GUI_tSend   pfSend,
                    GUI_tRecv   pfRecv,
                    void      * pConnectInfo);
```

Parameters

Parameter	Description
pfSend	Pointer to the function to be used by the server to send data to the emWinSPY.
pfRecv	Pointer to the function to be used by the server to read data from the emWinSPY.
pConnectInfo	Pointer to be passed to the send and receive function.

Return value

0 after the connection has been closed properly.
1 on error.

Additional information

The sample folder Sample\GUI_X contains a sample implementation of a server thread. It is located in the file GUI_SPY_X_StartServer.c.

Example

```
static int _Send(const U8 * buf, int len, void * p) {
  ...
}
static int _Recv(U8 * buf, int len, void * p) {
  ...
}
static int _ServerTask(void * p) {
  int Sock;
  ...
  GUI_SPY_Process(_Send, _Recv, (void *)Sock);
}
```

 © 2020 SEGGER Microcontroller GmbH

6.4.2 GUI_SPY_SetMemHandler()

Description

This function may be used to set a memory handler for the emWinSPY. Some operations, especially collecting the windows information requires dynamic memory. That memory normally is allocated by using the emWin memory management system. With a separate memory manager (for example malloc and free) the server thread would not affect the dynamic memory manager.

Prototype

```
void GUI_SPY_SetMemHandler(void * ( *pMalloc)(unsigned int ),
                           void   ( *pFree)(void * ));
```

Parameters

Parameter	Description
pMalloc	Pointer to memory allocation routine.
pFree	Pointer to memory release function.

Additional information

Using a separate memory manager is optional and not required.

 © 2020 SEGGER Microcontroller GmbH

6.4.3 GUI_SPY_StartServer()

Description

That function starts the server by calling `GUI_SPY_X_StartServer()` explained later and sets the required hook functions for gathering information.

Prototype

```
int GUI_SPY_StartServer(void);
```

Return value

0	on success
1	on error.

 © 2020 SEGGER Microcontroller GmbH

6.4.4 GUI_SPY_StartServerEx()

Description

This function starts the server by calling the function pointer passed to this function. With this function emWinSPY can be used, although GUI_SUPPORT_SPY is set to zero.

Prototype

```
int GUI_SPY_StartServerEx(int ( *pGUI_SPY_X_StartServer)());
```

Parameters

Parameter	Description
pGUI_SPY_X_StartServer	Pointer to a function which starts the SPY server. Same as GUI_SPY_X_StartServer().

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

6.4.5 GUI_SPY_X_StartServer()

Description

That function actually is responsible for creating the server thread and establishing a connection. When running the simulation it already contains an implementation of that function. When running on hardware that function has to be supplied by the customer.

Prototype

```
int GUI_SPY_X_StartServer(void);
```

Return value

0	on success
1	on error.

Additional information

As already mentioned earlier the sample folder `Sample\GUI_X` contains a sample implementation of a server thread. It is located in the file `GUI_SPY_X_StartServer.c` and is written to be used with embOS/IP. In case of using different tools it should be an easy task to adapt that sample.

 © 2020 SEGGER Microcontroller GmbH

Chapter 7

Displaying Text

It is very easy to display text with emWin. Knowledge of only a few routines already allows you to write any text, in any available font, at any point on the display. We first provide a short introduction to displaying text, followed by more detailed descriptions of the individual routines that are available.

 © 2020 SEGGER Microcontroller GmbH

7.1 Basic routines

Text can be displayed just by calling `GUI_DispString()`. For example:

```
GUI_DispString("Hello world!");
```

The above code will display the text “Hello world” at the current text position. However, there are functions to display text using different fonts or at certain positions. Even when using byte-oriented displays the position can be specified pixel accurate. In addition to that, it is also possible to display decimal, hexadecimal and binary values. Details on how values can be displayed using emWin can be found in the chapter *Displaying Values* on page 223.

Control characters

Control characters are characters with a character code of less than 32. The control characters are defined as part of ASCII. emWin ignores all control characters except the following:

Char. Code	ASCII code	C	Description
10	LF	\n	Line feed. The current text position is changed to the beginning of the next line. Per default, this is: X = 0. Y += font-distance in pixels (as delivered by `GUI_GetFontDistY()`).
13	CR	\r	Carriage return. The current text position is changed to the beginning of the current line. Per default, this is: X = 0.

Usage of the line feeds can be very convenient in strings. They can be part of a string so that strings spanning multiple lines can be displayed with a single function call.

 © 2020 SEGGER Microcontroller GmbH

7.2 Drawing modes

Text is displayed using the foreground and background color which are set using the functions GUI_SetColor() and GUI_SetBkColor() described below. In order to set a certain drawing mode to display strings or single characters the function GUI_SetTextMode() can be called using the flags described below.

Normal text

Displaying normal text is the default behavior. The characters are displayed using the foreground color. The background color is used to clear the background according to its width of the text and height of the currently selected font. Text can be displayed normally by specifying just GUI_TM_NORMAL or 0.

Reverse text

Text can be displayed in reverse mode by specifying GUI_TM_REV. This causes characters to be displayed using the background color and the background to be cleared using the foreground color.

Transparent text

Text can be displayed in transparent mode by specifying GUI_TM_TRANS. This causes characters to be displayed without the background to be cleared. In this case whatever was drawn before the text was displayed can still be seen.

XOR text

Text can be displayed in XOR mode by specifying GUI_TM_XOR. This causes characters to be displayed using the inverted colors of the background. This is done pixel-wise. This is also a transparent drawing mode, so the background remains unchanged. This mode is often used to in 1bpp-configurations to ensure readability, since black is inverted to white and vice versa. In case colors are used a single pixel is inverted as follows:

```
New pixel color = number of colors - actual pixel color - 1
```

Transparent reversed text

Text can be displayed in reverse and transparent mode by specifying (GUI_TM_TRANS | GUI_TM_REV). According to the transparent mode, the background is not cleared. According to the reverse mode, the characters are displayed using the background color.

Example

Displays normal, reverse, transparent, XOR, and transparent reversed text:

```
GUI_SetFont(&GUI_Font8x16);
GUI_SetBkColor(GUI_BLUE);
GUI_Clear();
GUI_SetPenSize(10);
GUI_SetColor(GUI_RED);
GUI_DrawLine(80, 10, 240, 90);
GUI_DrawLine(80, 90, 240, 10);
GUI_SetBkColor(GUI_BLACK);
GUI_SetColor(GUI_WHITE);
GUI_SetTextMode(GUI_TM_NORMAL);
GUI_DispStringHCenterAt("GUI_TM_NORMAL"           , 160, 10);
GUI_SetTextMode(GUI_TM_REV);
GUI_DispStringHCenterAt("GUI_TM_REV"              , 160, 26);
GUI_SetTextMode(GUI_TM_TRANS);
GUI_DispStringHCenterAt("GUI_TM_TRANS"            , 160, 42);
GUI_SetTextMode(GUI_TM_XOR);
GUI_DispStringHCenterAt("GUI_TM_XOR"              , 160, 58);
GUI_SetTextMode(GUI_TM_TRANS | GUI_TM_REV);
```

 © 2020 SEGGER Microcontroller GmbH

```
GUI_DispStringHCenterAt("GUI_TM_TRANS | GUI_TM_REV", 160, 74);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

7.3 Position

Every task has a current text position. This is the position relative to the origin of the display. This position is used by text displaying functions to place the next characters. Initially this position is (0,0) which is the upper left corner of the display. When using the Window Manager the position is used according to the current window. In order to set the text position the function `GUI_GotoX()`, `GUI_GotoY()` and `GUI_GotoXY()` can be used.

 © 2020 SEGGER Microcontroller GmbH

7.4 Text API

The table below lists the available text-related functions in alphabetical order within their respective categories. Detailed function descriptions can be found in the following sections.

Functions

Routine	Description
Displaying text	
GUI_DispCEOL()	Clears the current line from the current position to the end.
GUI_DispChar()	Displays a single character.
GUI_DispCharAt()	Displays a single character at the specified position.
GUI_DispChars()	Displays a character a specified number of times.
GUI_DispString()	Displays a string.
GUI_DispStringAt()	Displays a string at the specified position.
GUI_DispStringAtCEOL()	Displays a string at the specified position and clears the current line to the end.
GUI_DispStringHCenterAt()	Displays a string centered horizontally at the given position.
GUI_DispStringInRect()	Displays a string in the specified rectangle.
GUI_DispStringInRectEx()	Displays a string rotated in the specified rectangle.
GUI_DispStringInRectWrap()	Displays a string wrapped in the specified rectangle.
GUI_DispStringInRectWrapEx()	Displays a string rotated and wrapped in the specified rectangle.
GUI_DispStringLen()	Displays a string at the current position with specified number of characters.
GUI_GetCharFromPos()	Returns a character from a string at a given X-position in the current font.
GUI_ShowMissingCharacters()	This function enables displaying of missing characters.
GUI_WrapGetNumLines()	Returns the number of lines required to display the given text with the given wrap mode at the given size using the current font.
Drawing modes	
GUI_GetTextMode()	Returns the currently selected text mode.
GUI_SetClearTextRectMode()	Enables or disables the clear text rect mode.
GUI_SetTextMode()	Sets the text mode to the parameter specified.
GUI_SetTextStyle()	Sets the text style to the parameter specified.
Alignment	
GUI_GetTextAlign()	Returns the current text alignment mode.
GUI_SetLBorder()	Sets the left border for line feeds in the current window.
GUI_SetTextAlign()	Sets the text alignment.
Position	

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_DispNextLine()	Moves the cursor to the beginning of the next line.
GUI_GotoX()	Sets the X-position.
GUI_GotoXY()	Sets the X- and Y-position.
GUI_GotoY()	Sets the Y-position.
GUI_GetDispPosX()	Returns the current X-position.
GUI_GetDispPosY()	Returns the current Y-position.

Defines

Group of defines	Description
Text alignment flags	Define the alignment of a text.
Text drawing modes	Define with which mode a text will be drawn.
Text rotation modes	Rotate the text.
Text style flags	Text style how a text will be displayed.

Enumerations

Enumeration type	Description
GUI_WRAPMODE	Configuration how text will be wrapped.

 © 2020 SEGGER Microcontroller GmbH

7.4.1 Displaying text

7.4.1.1 GUI_DispCEOL()

Description

Clears the current line in the current window (or the display) from the current text position to the end of the window using the height of the current font.

Prototype

```
void GUI_DispCEOL(void);
```

Example

Shows “Hello world” on the display, waits 1 second and then displays “Hi” in the same place, replacing the old string:

```
GUI_DispStringAt("Hello world", 0, 0);
GUI_Delay(1000);
GUI_DispStringAt("Hi", 0, 0);
GUI_DispCEOL();
```

 © 2020 SEGGER Microcontroller GmbH

7.4.1.2 GUI_DispChar()

Description

Displays a single character at the current text position in the current window using the current font.

Prototype

```
void GUI_DispChar(U16 c);
```

Parameters

Parameter	Description
c	Character to display

Additional information

This is the basic routine for displaying a single character. All other display routines (`GUI_DispCharAt()`, `GUI_DispString()`, etc.) call this routine to output the individual characters. Which characters are available depends on the selected font. If the character is not available in the current font, nothing is displayed.

Example

Shows a capital `A` on the display:

```
GUI_DispChar('A');
```

Related topics

- *GUI_DispChars* on page 194
- *GUI_DispCharAt* on page 193

 © 2020 SEGGER Microcontroller GmbH

7.4.1.3 GUI_DispCharAt()

Description

Displays a single character at the specified position in the current window using the current font.

Prototype

```
void GUI_DispCharAt(U16  c,
                    I16P x,
                    I16P y);
```

Parameters

Parameter	Description
c	Character to display
x	X-position to write to in pixels of the client window.
y	Y-position to write to in pixels of the client window.

Additional information

Displays the character with its upper left corner at the specified (X,Y) position. Writes the character using the routine `GUI_DispChar()`. If the character is not available in the current font, nothing is displayed.

Example

Shows a capital `A` on the display in the upper left corner:

```
GUI_DispCharAt('A',0,0);
```

Related topics

- *GUI_DispChar* on page 192
- *GUI_DispChars* on page 194

 © 2020 SEGGER Microcontroller GmbH

7.4.1.4 GUI_DispChars()

Description

Displays a character a specified number of times at the current text position in the current window using the current font.

Prototype

```
void GUI_DispChars(U16P c,
                   int  NumChars);
```

Parameters

Parameter	Description
c	Character to display
Cnt	Number of repetitions (0 ≤ Cnt ≤ 32767).

Additional information

Writes the character using the routine `GUI_DispChar()` . If the character is not available in the current font, nothing is displayed.

Example

Shows the line `******************************` on the display:

```
GUI_DispChars('*', 30);
```

Related topics

- *GUI_DispChar* on page 192
- *GUI_DispCharAt* on page 193

 © 2020 SEGGER Microcontroller GmbH

7.4.1.5 GUI_DispString()

Description

Displays the string passed as parameter at the current text position in the current window using the current font.

Prototype

```
void GUI_DispString(const char * s);
```

Parameters

Parameter	Description
s	String to display

Additional information

The string can contain the control character \n. This control character moves the current text position to the beginning of the next line.

Example

Shows “Hello world” on the display and “Next line” on the next line:

```
GUI_DispString("Hello world");  //Disp text
GUI_DispString("\nNext line");  //Disp text
```

Related topics

- *GUI_DispStringAt* on page 196
- *GUI_DispStringAtCEOL* on page 197
- *GUI_DispStringLen* on page 203

 © 2020 SEGGER Microcontroller GmbH

7.4.1.6 GUI_DispStringAt()

Description

Displays the string passed as parameter at a specified position in the current window using the current font.

Prototype

```
void GUI_DispStringAt(const char * s,
                      int    x,
                      int    y);
```

Parameters

Parameter	Description
s	String to display
x	X-position to write to in pixels of the client window.
y	Y-position to write to in pixels of the client window.

Example

Shows “Position 50,20” at position 50,20 on the display:

```
GUI_DispStringAt("Position 50,20", 50, 20);  // Disp text
```

Related topics

- *GUI_DispString* on page 195
- *GUI_DispStringAtCEOL* on page 197
- *GUI_DispStringLen* on page 203

 © 2020 SEGGER Microcontroller GmbH

7.4.1.7 GUI_DispStringAtCEOL()

Description

Displays a given string at a specified position and clearing the remaining part of the line to the end by calling the routine `GUI_DispCEOL()`. This routine can be handy if one string is to overwrite another, and the overwriting string is or may be shorter than the previous one.

Prototype

```
void GUI_DispStringAtCEOL(const char * s,
                          int    x,
                          int    y);
```

Parameters

Parameter	Description
s	String to display
x	X-position to write to in pixels of the client window.
y	Y-position to write to in pixels of the client window.

 © 2020 SEGGER Microcontroller GmbH

7.4.1.8 GUI_DispStringHCenterAt()

Description

Displays the string passed as parameter horizontally centered at a specified position in the current window using the current font.

Prototype

```
void GUI_DispStringHCenterAt(const char * s,
                             int    x,
                             int    y);
```

Parameters

Parameter	Description
s	String to display
x	X-position to write to in pixels of the client window.
y	Y-position to write to in pixels of the client window.

 © 2020 SEGGER Microcontroller GmbH

7.4.1.9 GUI_DispStringInRect()

Description

Displays the string passed as parameter at a specified position within a specified rectangle, in the current window using the current font.

Prototype

```
void GUI_DispStringInRect(const char     * pText,
                          GUI_RECT * pRect,
                          int        TextAlign);
```

Parameters

Parameter	Description
s	String to display
pRect	Rectangle to write to in pixels of the client window.
TextAlign	Text alignment mode to set. List of flags can be found under *Text alignment flags* on page 218.

Additional information

If the specified rectangle is too small, the text will be clipped.

Example

Shows the word “Text” centered horizontally and vertically in the current window:

```
GUI_RECT rClient;
GUI_GetClientRect(&rClient);
GUI_DispStringInRect("Text", &rClient, GUI_TA_HCENTER | GUI_TA_VCENTER);
```

Related topics

- *GUI_DispString* on page 195
- *GUI_DispStringAtCEOL* on page 197
- *GUI_DispStringLen* on page 203

 © 2020 SEGGER Microcontroller GmbH

7.4.1.10 GUI_DispStringInRectEx()

Description

Displays the string passed as parameter at a specified position within a specified rectangle, in the current window using the current font and (optionally) rotates it.

Prototype

```
void GUI_DispStringInRectEx(const char          * s,
                                  GUI_RECT      * pRect,
                                  int             TextAlign,
                                  int             MaxLen,
                            const GUI_ROTATION  * pLCD_Api);
```

Parameters

Parameter	Description
s	String to display
pRect	Rectangle to write to in pixels of the client window.
TextAlign	Text alignment mode. List of flags can be found under *Text alignment flags* on page 218.
MaxLen	Maximum number of characters to be shown.
pLCD_Api	Text rotation mode. See full list of available values under *Text rotation modes* on page 220.

Additional information

If the specified rectangle is too small, the text will be clipped. To make the function available the configuration switch GUI_SUPPORT_ROTATION must be activated (default).

Example

Shows the word “Text” centered horizontally and vertically in the given rectangle:

```
GUI_RECT Rect = {10, 10, 40, 80};
char acText[] = "Rotated\ntext";
GUI_SetTextMode(GUI_TM_XOR);
GUI_FillRectEx(&Rect);
GUI_DispStringInRectEx(acText, &Rect, GUI_TA_HCENTER | GUI_TA_VCENTER,
                       strlen(acText), GUI_ROTATE_CCW);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

7.4.1.11 GUI_DispStringInRectWrap()

Description

Displays a string at a specified position within a specified rectangle, in the current window using the current font and (optionally) wraps the text.

Prototype

```
void GUI_DispStringInRectWrap(const char          * s,
                              GUI_RECT      * pRect,
                              int             TextAlign,
                              GUI_WRAPMODE    WrapMode);
```

Parameters

Parameter	Description
s	String to display
pRect	Rectangle to write to in pixels of the client window.
TextAlign	Text alignment mode. List of flags can be found under *Text alignment flags* on page 218.
WrapMode	Text wrap mode. See full list of available values under *GUI_WRAPMODE* on page 222.

Example

Shows a text centered horizontally and vertically in the given rectangle with word wrapping:

```
GUI_WRAPMODE aWm[]
  = { GUI_WRAPMODE_NONE, GUI_WRAPMODE_CHAR, GUI_WRAPMODE_WORD};
GUI_RECT     Rect     = {10, 10, 59, 59};
char         acText[] = "This example demonstrates text wrapping";
int          i;
GUI_SetTextMode(GUI_TM_TRANS);
for (i = 0; i < 3; i++) {
  GUI_SetColor(GUI_BLUE);
  GUI_FillRectEx(&Rect);
  GUI_SetColor(GUI_WHITE);
  GUI_DispStringInRectWrap(acText, &Rect, GUI_TA_LEFT, aWm[i]);
  Rect.x0 += 60;
  Rect.x1 += 60;
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

7.4.1.12 GUI_DispStringInRectWrapEx()

Description

Displays a string rotated at a specified position within a specified rectangle, in the current window using the current font and (optionally) wraps the text.

Prototype

```
void GUI_DispStringInRectWrapEx(const char         * s,
                                      GUI_RECT     * pRect,
                                      int            TextAlign,
                                      GUI_WRAPMODE   WrapMode,
                                const GUI_ROTATION * pLCD_Api);
```

Parameters

Parameter	Description
s	String to display.
pRect	Rectangle to write to in pixels of the client window.
TextAlign	Text alignment mode. List of flags can be found under *Text alignment flags* on page 218.
WrapMode	Text wrap mode. See full list of available values under *GUI_WRAPMODE* on page 222.
pLCD_Api	Text rotation mode. See full list of available values under *Text rotation modes* on page 220.

 © 2020 SEGGER Microcontroller GmbH

7.4.1.13 GUI_DispStringLen()

Description

Displays the string passed as parameter with a specified number of characters at the current text position, in the current window using the current font.

Prototype

```
void GUI_DispStringLen(const char * s,
                       int    MaxNumChars);
```

Parameters

Parameter	Description
s	Should be a terminated array of 8-bit characters. Passing NULL as parameter is permitted.
MaxNumChars	Number of characters to display.

Additional information

If the string has less characters than specified (is shorter), it is padded with spaces. If the string has more characters than specified (is longer), then only the given number of characters is actually displayed. This function is especially useful if text messages can be displayed in different languages (and will naturally differ in length), but only a certain number of characters can be displayed.

Related topics

- *GUI_DispString* on page 195
- *GUI_DispStringAt* on page 196
- *GUI_DispStringAtCEOL* on page 197

 © 2020 SEGGER Microcontroller GmbH

7.4.1.14 GUI_GetCharFromPos()

Description

Returns a character from a string at a given X-position in the current font.

Prototype

```
U16 GUI_GetCharFromPos(const char * pText,
                       int    x,
                       int  * pIndex);
```

Parameters

Parameter	Description
pText	Pointer to a string.
x	X-position in pixels in the string.
pIndex	Pointer to int. Zero-based position of the character in the string. Can be NULL if not needed.

Return value

= 0 No character found.
≠ 0 Character at the given X-position in a string.

Additional information

The function assumes the text begins at x = 0. Notice also that a font has to have been set that contains the characters in the given string.

 © 2020 SEGGER Microcontroller GmbH

7.4.1.15 GUI_ShowMissingCharacters()

Description

This function enables displaying of missing characters.

Prototype

```
void GUI_ShowMissingCharacters(int OnOff);
```

Parameters

Parameter	Description
OnOff	Enables (1) or disables (0) displaying of missing characters.

Additional information

If a font does not contain a character to be displayed emWin skips this character. By calling this function a square gets displayed instead of the missing character.

 © 2020 SEGGER Microcontroller GmbH

7.4.1.16 GUI_WrapGetNumLines()

Description

Returns the number of lines required to display the given text with the given wrap mode at the given size using the current font.

Prototype

```
int GUI_WrapGetNumLines(const char         * pText,
                        int                  xSize,
                        GUI_WRAPMODE         WrapMode);
```

Parameters

Parameter	Description
pText	String to display. Should be a \0-terminated array of 8-bit characters.
xSize	X-size to be used to draw the text.
WrapMode	See table below.

Return value

The number of lines which is required to display the given text.

 © 2020 SEGGER Microcontroller GmbH

7.4.2 Drawing modes

7.4.2.1 GUI_GetTextMode()

Description

Returns the currently selected text mode.

Prototype

```
int GUI_GetTextMode(void);
```

Return value

The currently selected text mode.

 © 2020 SEGGER Microcontroller GmbH

7.4.2.2 GUI_SetClearTextRectMode()

Description

Enables or disables the clear text rect mode.

Prototype

```
U8 GUI_SetClearTextRectMode(unsigned OnOff);
```

Parameters

Parameter	Description
OnOff	Enables or disable the clear text rect mode.

Return value

The previous selected mode.

Additional information

If the clear text rect mode is enabled the rectangular area when using `GUI_DispStringInRect()` gets cleared with the given background color.

 © 2020 SEGGER Microcontroller GmbH

7.4.2.3 GUI_SetTextMode()

Description

Sets the text mode to the parameter specified.

Prototype

```
int GUI_SetTextMode(int Mode);
```

Parameters

Parameter	Description
Mode	Text mode. See full list of available values under *Text drawing modes* on page 219.

Return value

The previous selected text mode.

 © 2020 SEGGER Microcontroller GmbH

7.4.2.4 GUI_SetTextStyle()

Description

Sets the text style to the parameter specified.

Prototype

```
char GUI_SetTextStyle(char Style);
```

Parameters

Parameter	Description
Style	Text style to set. See full list of available values under *Text style flags* on page 221.

Return value

The previous selected text style.

 © 2020 SEGGER Microcontroller GmbH

7.4.3 Alignment

7.4.3.1 GUI_GetTextAlign()

Description

Returns the current text alignment mode.

Prototype

```
int GUI_GetTextAlign(void);
```

Return value

The current text alignment mode.

 © 2020 SEGGER Microcontroller GmbH

7.4.3.2 GUI_SetLBorder()

Description

Sets the left border for line feeds in the current window.

Prototype

```
int GUI_SetLBorder(int x);
```

Parameters

Parameter	Description
x	New left border (in pixels, 0 is left border).

 © 2020 SEGGER Microcontroller GmbH

7.4.3.3 GUI_SetTextAlign()

Description

Sets the text alignment for the next displayed string in the current window.

Prototype

```
int GUI_SetTextAlign(int Align);
```

Parameters

Parameter	Description
TextAlign	Text alignment mode to set. List of flags can be found under *Text alignment flags* on page 218.

Return value

The selected text alignment mode.

Additional information

Setting the text alignment does not affect GUI_DispChar…()-functions. Text alignment is valid only for the current window.

Example

Displays the value 1234 with the center of the text at x = 100, y = 100:

```
GUI_SetTextAlign(GUI_TA_HCENTER | GUI_TA_VCENTER);
GUI_DispDecAt(1234, 100, 100, 4);
```

 © 2020 SEGGER Microcontroller GmbH

7.4.4 Position

7.4.4.1 GUI_DispNextLine()

Description

Moves the cursor to the beginning of the next line which can be adjusted using the function `GUI_SetLBorder()`.

Prototype

```
void GUI_DispNextLine(void);
```

 © 2020 SEGGER Microcontroller GmbH

7.4.4.2 GUI_GotoXY()

7.4.4.3 GUI_GotoX()

7.4.4.4 GUI_GotoY()

Description

Set the current text write position.

Prototypes

```
char GUI_GotoXY(int x,
                int y);

char GUI_GotoX(int x);

char GUI_GotoY(int y);
```

Parameters

Parameter	Description
y	New Y-position (in pixels, 0 is top border).

Return value

= 0 on success.
≠ 0 if the set text position is right or below outside the window. Consequtive drawing operations can be omitted in this case.

Example

Shows a string at position (20, 20) on the display:

```
GUI_GotoXY(20,20);
GUI_DispString("The value is");
```

 © 2020 SEGGER Microcontroller GmbH

7.4.4.5 GUI_GetDispPosX()

Description

Returns the current X-position.

Prototype

```
int GUI_GetDispPosX(void);
```

Return value

The current X-position.

 © 2020 SEGGER Microcontroller GmbH

7.4.4.6 GUI_GetDispPosY()

Description

Returns the current Y-position.

Prototype

```
int GUI_GetDispPosY(void);
```

Return value

The current Y-position.

 © 2020 SEGGER Microcontroller GmbH

7.4.5 Defines

7.4.5.1 Text alignment flags

Description

Define the alignment of a text. Horizontal and vertical flags are OR-combinable.

Definition

```
#define GUI_TA_LEFT       (0)
#define GUI_TA_HCENTER    (2 << 0)
#define GUI_TA_RIGHT      (1 << 0)
#define GUI_TA_TOP        (0)
#define GUI_TA_VCENTER    (3 << 2)
#define GUI_TA_BOTTOM     (1 << 2)
```

Symbols

Definition	Description
Horizontal alignment	
GUI_TA_LEFT	Align X-position left (default).
GUI_TA_HCENTER	Center X-position.
GUI_TA_RIGHT	Align X-position right.
Vertical alignment	
GUI_TA_TOP	Align Y-position with top of characters (default).
GUI_TA_VCENTER	Center Y-position.
GUI_TA_BOTTOM	Align Y-position with bottom pixel line of font.

 © 2020 SEGGER Microcontroller GmbH

7.4.5.2 Text drawing modes

Description

These flags define with which mode a text will be drawn. These flags are OR-combinable.

Definition

```
#define GUI_TM_NORMAL    (0)
#define GUI_TM_XOR       (1 << 0)
#define GUI_TM_TRANS     (1 << 1)
#define GUI_TM_REV       (1 << 2)
```

Symbols

Definition	Description
GUI_TM_NORMAL	Default mode, characters are displayed using the foreground color, background color is used to clear the background according to width and height of the text.
GUI_TM_XOR	Characters are displayed using the inverted colors of the background (pixel-wise).
GUI_TM_TRANS	Characters are displayed without the background being cleared.
GUI_TM_REV	Characters are displayed using the background color, foreground color is used to clear the background according to width and height of the text.

Additional information

More information about text drawing modes can be found under Drawing modes.

 © 2020 SEGGER Microcontroller GmbH

7.4.5.3 Text rotation modes

Description

These macros are necessary for text rotation. They are used for example by the function `GUI_DispStringInRectEx()`.

Definition

```
#define GUI_ROTATE_0      0
#define GUI_ROTATE_180    &LCD_APIList180
#define GUI_ROTATE_CW     &LCD_APIListCW
#define GUI_ROTATE_CCW    &LCD_APIListCCW
```

Symbols

Definition	Description
GUI_ROTATE_0	Does not rotate the text. Shows it from left to right.
GUI_ROTATE_180	Rotates the text by 180 degrees.
GUI_ROTATE_CW	Rotates the text clockwise.
GUI_ROTATE_CCW	Rotates the text counter clockwise.

 © 2020 SEGGER Microcontroller GmbH

7.4.5.4 Text style flags

Description

Text style how a text will be displayed.

Definition

```
#define GUI_TS_NORMAL        (0)
#define GUI_TS_UNDERLINE     (1 << 0)
#define GUI_TS_STRIKETHRU    (1 << 1)
#define GUI_TS_OVERLINE      (1 << 2)
```

Symbols

Definition	Description
GUI_TS_NORMAL	Renders text normal (default).
GUI_TS_UNDERLINE	Renders text underlined.
GUI_TS_STRIKETHRU	Renders text in strike through type.
GUI_TS_OVERLINE	Renders text in overline type.

 © 2020 SEGGER Microcontroller GmbH

7.4.6 Enumerations

7.4.6.1 GUI_WRAPMODE

Description

Configuration how text will be wrapped.

Type definition

```
typedef enum {
  GUI_WRAPMODE_NONE,
  GUI_WRAPMODE_WORD,
  GUI_WRAPMODE_CHAR
} GUI_WRAPMODE;
```

Enumeration constants

Constant	Description
GUI_WRAPMODE_NONE	No wrapping will be performed.
GUI_WRAPMODE_WORD	Text is wrapped word wise.
GUI_WRAPMODE_CHAR	Text is wrapped char wise.

Additional information

If word wrapping should be performed and the given rectangle is too small for a word, char wrapping is executed at this word.

 © 2020 SEGGER Microcontroller GmbH

Chapter 8

Displaying Values

The preceding chapter explained how to show strings on the display. Of course you may use strings and the functions of the standard C library to display values. However, this can sometimes be a difficult task. It is usually much easier (and much more efficient) to call a routine that displays the value in the form that you want. emWin supports different decimal, hexadecimal and binary outputs. The individual routines are explained in this chapter.
All functions work without the usage of a floating-point library and are optimized for both speed and size. Of course `sprintf()` may also be used on any system. Using the routines in this chapter can sometimes simplify things and save both ROM space and execution time.

 © 2020 SEGGER Microcontroller GmbH

8.1 Value API

The table below lists the available value-related routines in alphabetical order within their respective categories. Detailed descriptions of the routines can be found in the sections that follow.

Routine	Description
Displaying decimal values	
GUI_DispDec()	Displays the given value in decimal form with the specified number of characters.
GUI_DispDecAt()	Displays the given value in decimal form at the specified position with specified number of characters.
GUI_DispDecMin()	Displays the given value in decimal form with minimum number of characters.
GUI_DispDecShift()	Displays long value in decimal form with decimal point at current position with specified number of characters.
GUI_DispDecSpace()	Display value in decimal form at current position with specified number of characters, replace leading zeros with spaces.
GUI_DispSDec()	Display value in decimal form at current position with specified number of characters and sign.
GUI_DispSDecShift()	Display long value in decimal form with decimal point at current position with specified number of characters and sign.
Displaying floating-point values	
GUI_DispFloat()	Display floating-point value with specified number of characters.
GUI_DispFloatFix()	Display floating-point value with fixed no. of digits to the right of decimal point.
GUI_DispFloatMin()	Display floating-point value with minimum number of characters.
GUI_DispSFloatFix()	Display floating-point value with fixed no. of digits to the right of decimal point and sign.
GUI_DispSFloatMin()	Display floating-point value with minimum number of characters and sign.
Displaying binary values	
GUI_DispBin()	Display value in binary form at current position.
GUI_DispBinAt()	Display value in binary form at specified position.
Displaying hexadecimal values	
GUI_DispHex()	Display value in hexadecimal form at current position.
GUI_DispHexAt()	Display value in hexadecimal form at specified position.
Version of emWin	
GUI_GetVersionString()	Returns a string containing the current version of emWin.

 © 2020 SEGGER Microcontroller GmbH

8.1.1 Displaying decimal values

8.1.1.1 GUI_DispDec()

Description

Displays a value in decimal form with a specified number of characters at the current text position, in the current window using the current font.

Prototype

```
void GUI_DispDec(I32 v,
                 U8  Len);
```

Parameters

Parameter	Description
v	Value to display. Minimum -2147483648 (= -2^31). Maximum 2147483647 (= 2^31 -1).
Len	Number of digits to display (max. 10).

Additional information

Leading zeros are not suppressed (are shown as 0). If the value is negative, a minus sign is shown.

Example

```
// Display time as minutes and seconds
GUI_DispString("Min:");
GUI_DispDec(Min, 2);
GUI_DispString(" Sec:");
GUI_DispDec(Sec, 2);
```

Related topics

- *GUI_DispSDec* on page 230
- *GUI_DispDecAt* on page 226
- *GUI_DispDecMin* on page 227
- *GUI_DispDecSpace* on page 229

 © 2020 SEGGER Microcontroller GmbH

8.1.1.2 GUI_DispDecAt()

Description

Displays a value in decimal form with a specified number of characters at a specified position, in the current window using the current font.

Prototype

```
void GUI_DispDecAt(I32  v,
                   I16P x,
                   I16P y,
                   U8   Len);
```

Parameters

Parameter	Description
v	Value to display. Minimum -2147483648 (= -2^31). Maximum 2147483647 (= 2^31 -1).
x	X-position to write to in pixels of the client window.
y	Y-position to write to in pixels of the client window.
Len	Number of digits to display (max. 10).

Additional information

Leading zeros are not suppressed (are shown as 0). If the value is negative, a minus sign is shown.

Example

```
// Update seconds in upper right corner
GUI_DispDecAT(Sec, 200, 0, 2);
```

Related topics

- *GUI_DispDec* on page 225
- *GUI_DispSDec* on page 230
- *GUI_DispDecMin* on page 227
- *GUI_DispDecSpace* on page 229

 © 2020 SEGGER Microcontroller GmbH

8.1.1.3 GUI_DispDecMin()

Description

Displays a value in decimal form at the current text position in the current window using the current font. The length of the value does not require to be specified. The minimum length will automatically be used.

Prototype

```
void GUI_DispDecMin(I32 v);
```

Parameters

Parameter	Description
v	Value to display. Minimum -2147483648 (= -2^31). Maximum 2147483647 (= 2^31 -1).

Additional information

The maximum number of displayed digits is 10. This function should not be used if values have to be aligned but differ in the number of digits. Try one of the functions which require specification of the number of digits to use in this case.

Example

```
// Show result
GUI_DispString("The result is :");
GUI_DispDecMin(Result);
```

Related topics

- *GUI_DispDec* on page 225
- *GUI_DispDecAt* on page 226
- *GUI_DispSDec* on page 230
- *GUI_DispDecSpace* on page 229

 © 2020 SEGGER Microcontroller GmbH

8.1.1.4 GUI_DispDecShift()

Description

Displays a long value in decimal form with a specified number of characters and with decimal point at the current text position, in the current window using the current font.

Prototype

```
void GUI_DispDecShift(I32 v,
                      U8  Len,
                      U8  Shift);
```

Parameters

Parameter	Description
v	Value to display. Minimum -2147483648 (= -2^31). Maximum 2147483647 (= 2^31 -1).
Len	Number of digits to display (max. 10).
Shift	Number of digits to show to right of decimal point.

Additional information

Watch the maximum number of 9 characters (including sign and decimal point).

 © 2020 SEGGER Microcontroller GmbH

8.1.1.5 GUI_DispDecSpace()

Description

Displays a long value in decimal form with a specified number of characters and with decimal point at the current text position, in the current window using the current font.

Prototype

```
void GUI_DispDecSpace(I32 v,
                      U8  MaxDigits);
```

Parameters

Parameter	Description
v	Value to display. Minimum -2147483648 (= -2^31). Maximum 2147483647 (= 2^31 -1).
MaxDigits	Number of digits to display, including leading spaces. Maximum number of digits displayed is 10 (excluding leading spaces).

Additional information

If values have to be aligned but differ in the number of digits, this function is a good choice.

Example

```
// Show result
GUI_DispString("The result is :");
GUI_DispDecSpace(Result, 200);
```

Related topics

- *GUI_DispDec* on page 225
- *GUI_DispDecAt* on page 226
- *GUI_DispSDec* on page 230
- *GUI_DispDecMin* on page 227

 © 2020 SEGGER Microcontroller GmbH

8.1.1.6 GUI_DispSDec()

Description

Displays a value in decimal form (with sign) with a specified number of characters at the current text position, in the current window using the current font.

Prototype

```
void GUI_DispSDec(I32 v,
                  U8  Len);
```

Parameters

Parameter	Description
v	Value to display. Minimum -2147483648 (= -2^31). Maximum 2147483647 (= 2^31 -1).
Len	Number of digits to display (max. 10).

Additional information

Leading zeros are not suppressed. This function is similar to `GUI_DispDec`, but a sign is always shown in front of the value, even if the value is positive.

Related topics

- *GUI_DispDec* on page 225
- *GUI_DispDecAt* on page 226
- *GUI_DispDecMin* on page 227
- *GUI_DispDecSpace* on page 229

 © 2020 SEGGER Microcontroller GmbH

8.1.1.7 GUI_DispSDecShift()

Description

Displays a long value in decimal form (with sign) with a specified number of characters and with decimal point at the current text position, in the current window using the current font.

Prototype

```
void GUI_DispSDecShift(I32 v,
                       U8  Len,
                       U8  Shift);
```

Parameters

Parameter	Description
v	Value to display. Minimum -2147483648 (= -2^31). Maximum 2147483647 (= 2^31 -1).
Len	Number of digits to display. (max. 8, if Shift is set; max. 9, if Shift is not set)
Shift	Number of digits to show to right of decimal point.

Additional information

A sign is always shown in front of the value. Watch the maximum number of 9 characters (including sign and decimal point).

Example

```
long Value = 12345;

GUI_Init();
GUI_Clear();
GUI_SetFont(&GUI_Font8x8);
GUI_DispStringAt("GUI_DispSDecShift:\n",0,0);
GUI_DispSDecShift(Value, 7, 3);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

8.1.2 Displaying floating point values

8.1.2.1 GUI_DispFloat()

Description

Displays a floating point value with a specified number of characters at the current text position in the current window using the current font.

Prototype

```
void GUI_DispFloat(     float f,
                   char Len);
```

Parameters

Parameter	Description
v	Value to display. Minimum 1.2 E-38; maximum 3.4 E38.
Len	Number of digits to display. (max. 10).

Additional information

Leading zeros are suppressed. The decimal point counts as one character. If the value is negative, a minus sign is shown.

Example

```
// Shows different possibilities to display floating point values.
float f = 123.45678;

GUI_Clear();
GUI_SetFont(&GUI_Font8x8);
GUI_DispStringAt("GUI_DispFloat:\n", 0, 0);
GUI_DispFloat(f, 9);
GUI_GotoX(100);
GUI_DispFloat(-f, 9);
GUI_DispStringAt("GUI_DispFloatFix:\n", 0, 20);
GUI_DispFloatFix(f, 9, 2);
GUI_GotoX(100);
GUI_DispFloatFix(-f, 9, 2);
GUI_DispStringAt("GUI_DispSFloatFix:\n", 0, 40);
GUI_DispSFloatFix(f, 9, 2);
GUI_GotoX(100);
GUI_DispSFloatFix(-f, 9, 2);
GUI_DispStringAt("GUI_DispFloatMin:\n", 0, 60);
GUI_DispFloatMin(f, 3);
GUI_GotoX(100);
GUI_DispFloatMin(-f, 3);
GUI_DispStringAt("GUI_DispSFloatMin:\n", 0, 80);
GUI_DispSFloatMin(f, 3);
GUI_GotoX(100);
GUI_DispSFloatMin(-f, 3);
```

 © 2020 SEGGER Microcontroller GmbH

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

8.1.2.2 GUI_DispFloatFix()

Description

Displays a floating-point value with specified number of total characters and a specified number of characters to the right of the decimal point, at the current text position in the current window using the current font.

Prototype

```
void GUI_DispFloatFix(     float f,
                      char Len,
                      char Decs);
```

Parameters

Parameter	Description
v	Value to display. Minimum 1.2 E-38; maximum 3.4 E38.
Len	Number of digits to display. (max. 10).
Decs	Number of digits to show to the right of the decimal point.

Additional information

Leading zeros are not suppressed. If the value is negative, a minus sign is shown.

 © 2020 SEGGER Microcontroller GmbH

8.1.2.3 GUI_DispFloatMin()

Description

Displays a floating-point value with a minimum number of decimals to the right of the decimal point, at the current text position in the current window using the current font.

Prototype

```
void GUI_DispFloatMin(     float f,
                      char Fract);
```

Parameters

Parameter	Description
v	Value to display. Minimum 1.2 E-38; maximum 3.4 E38.
Fract	Minimum number of characters to display.

Additional information

Leading zeros are suppressed. If the value is negative, a minus sign is shown. The length does not need to be specified. The minimum length will automatically be used. If values have to be aligned but differ in the number of digits, one of the "…Fix()"-functions should be used instead.

 © 2020 SEGGER Microcontroller GmbH

8.1.2.4 GUI_DispSFloatFix()

Description

Displays a floating-point value (with sign) with a specified number of total characters and a specified number of characters to the right of the decimal point, in the current window using the current font.

Prototype

```
void GUI_DispSFloatFix(     float f,
                       char Len,
                       char Fract);
```

Parameters

Parameter	Description
v	Value to display. Minimum 1.2 E-38; maximum 3.4 E38.
Len	Number of digits to display (max. 10).
Decs	Number of digits to show to the right of the decimal point.

Additional information

Leading zeros are not suppressed. A sign is always shown in front of the value.

 © 2020 SEGGER Microcontroller GmbH

8.1.2.5 GUI_DispSFloatMin()

Description

Displays a floating-point value (with sign) with a minimum number of decimals to the right of the decimal point, at the current text position in the current window using the current font.

Prototype

```
void GUI_DispSFloatMin(     float f,
                       char Fract);
```

Parameters

Parameter	Description
v	Value to display. Minimum 1.2 E-38; maximum 3.4 E38.
Fract	Minimum number of digits to display.

Additional information

Leading zeros are suppressed. A sign is always shown in front of the value. The length does not need to be specified. The minimum length will automatically be used. If values have to be aligned but differ in the number of digits, one of the "…Fix()"-functions should be used instead.

 © 2020 SEGGER Microcontroller GmbH

8.1.3 Displaying binary values

8.1.3.1 GUI_DispBin()

Description

Displays a value in binary form at the current text position in the current window using the current font.

Prototype

```
void GUI_DispBin(U32 v,
                 U8  Len);
```

Parameters

Parameter	Description
v	Value to display, 32-bit.
Len	Number of digits to display (including leading zeros).

Additional information

As with decimal and hexadecimal values, the least significant bit is rightmost.

Example

```
//
// Show binary value 7, result: 000111
//
U32 Input = 0x7;
GUI_DispBin(Input, 6);
```

Related topics

GUI_DispBinAt on page 239

 © 2020 SEGGER Microcontroller GmbH

8.1.3.2 GUI_DispBinAt()

Description

Displays a value in binary form at a specified position in the current window using the current font.

Prototype

```
void GUI_DispBinAt(U32  v,
                   I16P x,
                   I16P y,
                   U8   Len);
```

Parameters

Parameter	Description
v	Value to display, 32-bit.
x	X-position to write to in pixels of the client window.
y	Y-position to write to in pixels of the client window.
Len	Number of digits to display (including leading zeros).

Additional information

As with decimal and hexadecimal values, the least significant bit is rightmost.

Example

```
//
// Show binary input status
//
GUI_DispBinAt(Input, 0, 0, 8);
```

Related topics

- *GUI_DispBin* on page 238
- *GUI_DispHex* on page 240

 © 2020 SEGGER Microcontroller GmbH

8.1.4 Displaying hexadecimal values

8.1.4.1 GUI_DispHex()

Description

Displays a value in hexadecimal form at the current text position in the current window using the current font.

Prototype

```
void GUI_DispHex(U32 v,
                 U8  Len);
```

Parameters

Parameter	Description
v	Value to display, 16-bit.
Len	Number of digits to display.

Additional information

As with decimal and binary values, the least significant bit is rightmost.

Example

```
//
// Show value of AD-converter
//
GUI_DispHex(Input, 4);
```

Related topics

- *GUI_DispDec* on page 225
- *GUI_DispBin* on page 238
- *GUI_DispHexAt* on page 241

 © 2020 SEGGER Microcontroller GmbH

8.1.4.2 GUI_DispHexAt()

Description

Displays a value in hexadecimal form at a specified position in the current window using the current font.

Prototype

```
void GUI_DispHexAt(U32  v,
                   I16P x,
                   I16P y,
                   U8   Len);
```

Parameters

Parameter	Description
v	Value to display, 16-bit.
x	X-position to write to in pixels of the client window.
y	Y-position to write to in pixels of the client window.
Len	Number of digits to display.

Additional information

As with decimal and binary values, the least significant bit is rightmost.

Example

```
//
// Show value of AD-converter at specified position
//
GUI_DispHexAt(Input, 0, 0, 4);
```

Related topics

- *GUI_DispDec* on page 225
- *GUI_DispBin* on page 238
- *GUI_DispHexAt* on page 241

 © 2020 SEGGER Microcontroller GmbH

8.1.5 GUI_GetVersionString()

Description

Returns a string containing the current version of emWin.

Prototype

```
char *GUI_GetVersionString(void);
```

Return value

Returns a pointer to an array of chars containing the current emWin version.

Example

```
//
// Displays the current version at the current cursor position
//
GUI_DispString(GUI_GetVersionString());
```

 © 2020 SEGGER Microcontroller GmbH

Chapter 9

2-D Graphic Library

emWin contains a complete 2-D graphic library which should be sufficient for most applications. The routines supplied with emWin can be used with or without clipping (refer to the chapter *The Window Manager (WM)* on page 781) and are based on fast and efficient algorithms. Currently, only the `GUI_DrawArc()` function requires floating-point calculations.

 © 2020 SEGGER Microcontroller GmbH

9.1 Graphic API

The table below lists the available graphic-related routines in alphabetical order within their respective categories. Detailed descriptions can be found in the sections that follow.

Functions

Routine	Description
Drawing related functions	
GUI_AddRect()	This function resizes the given rectangle.
GUI_GetClientRect()	Returns the current available drawing area.
GUI_GetClipRect()	Returns the currently set clip rectangle.
GUI_GetDrawMode()	Returns the current drawing mode.
GUI_GetPenSize()	Returns the current pen size.
GUI_GetPixelIndex()	Returns the color index of a given position.
GUI_SetClipRect()	Sets the rectangle used for clipping.
GUI_SetDrawMode()	Selects the specified drawing mode.
GUI_SetPenSize()	Sets the pen size in pixels.
Basic drawing routines	
GUI_Clear()	Fills the display/the active window with the background color.
GUI_ClearRect()	Fills a rectangular area with the background color.
GUI_CopyRect()	Copies a rectangle area on the display.
GUI_DrawGradientH()	Draws a rectangle filled with a horizontal color gradient.
GUI_DrawGradientHEx()	Draws a horizontal color gradient from a GUI_RECT pointer.
GUI_DrawGradientV()	Draws a rectangle filled with a vertical color gradient.
GUI_DrawGradientVEx()	Draws a vertical color gradient from a GUI_RECT pointer.
GUI_DrawGradientRoundedH()	Draws a rectangle with rounded corners filled with a horizontal color gradient.
GUI_DrawGradientRoundedHEx()	Draws a rectangle with rounded corners filled with a horizontal color gradient.
GUI_DrawGradientRoundedV()	Draws a rectangle with rounded corners filled with a vertical color gradient.
GUI_DrawGradientRoundedVEx()	Draws a vertical color gradient with rounded corners from a GUI_RECT pointer.
GUI_DrawGradientMH()	Draws a rectangle filled with a horizontal multi color gradient.
GUI_DrawGradientMHEx()	Draws a rectangle filled with a horizontal multi color gradient.
GUI_DrawGradientMV()	Draws a rectangle filled with a vertical multi color gradient.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_DrawGradientMVEx()	Draws a vertical multi color gradient from a GUI_RECT pointer.
GUI_DrawPixel()	Draws a single pixel.
GUI_DrawPoint()	Draws a point.
GUI_DrawRect()	Draws a rectangle.
GUI_DrawRectEx()	Draws a rectangle from a GUI_RECT structure.
GUI_DrawRoundedFrame()	Draws a frame with rounded corners.
GUI_DrawRoundedFrameEx()	Draws a frame with rounded corners from a GUI_RECT structure.
GUI_DrawRoundedRect()	Draws a rectangle with rounded corners.
GUI_DrawRoundedRectEx()	Draws a rectangle with rounded corners from a GUI_RECT structure.
GUI_FillRect()	Draws a filled rectangle.
GUI_FillRectEx()	Draws a filled rectangle from a GUI_RECT structure.
GUI_FillRoundedRect()	Draws a filled rectangle with rounded corners.
GUI_FillRoundedRectEx()	Draws a filled rectangle with rounded corners from a GUI_RECT structure.
GUI_InvertRect()	Invert a rectangular area.
Alpha blending	
GUI_EnableAlpha()	Enables/disables automatic alpha blending.
GUI_PreserveTrans()	Makes sure that alpha channel remains after drawing operations.
GUI_RestoreUserAlpha()	Restores the previous state of user alpha blending
GUI_SetAlpha()	Sets the current alpha blending value. (Obsolete)
GUI_SetUserAlpha()	Sets an additional value which is used to calculate the actual alpha blending value to be used.
Drawing bitmaps	
GUI_DrawBitmap()	Draws a bitmap.
GUI_DrawBitmapEx()	Draws a scaled bitmap.
GUI_DrawBitmapMag()	Draws a magnified bitmap.
GUI_SetAlphaMask8888()	Can be used for setting an additional AND and OR mask to be used for drawing the pixels of 32bpp bitmaps.
Drawing streamed bitmaps	
GUI_CreateBitmapFromStream()	Creates a bitmap from a given stream of any type.
GUI_CreateBitmapFromStreamIDX()	Creates a bitmap from an index based bitmap stream.
GUI_CreateBitmapFromStreamRLE4()	Creates a bitmap from an RLE4 bitmap stream.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_CreateBitmapFromStreamRLE8()	Creates a bitmap from an RLE8 bitmap stream.
GUI_CreateBitmapFromStream444_12()	Creates a bitmap from a 12bpp (444_12) bitmap stream.
GUI_CreateBitmapFromStream444_12_1()	Creates a bitmap from a 12bpp (444_12_1) bitmap stream.
GUI_CreateBitmapFromStreamM444_12()	Creates a bitmap from a 12bpp (M444_12) bitmap stream.
GUI_CreateBitmapFromStreamM444_12_1()	Creates a bitmap from a 12bpp (M444_12_1 bitmap stream.
GUI_CreateBitmapFromStream444_16()	Creates a bitmap from a 12bpp (444_16) bitmap stream.
GUI_CreateBitmapFromStreamM444_16()	Creates a bitmap from a 12bpp (444_16_1) bitmap stream.
GUI_CreateBitmapFromStreamA555()	Creates a bitmap with an alpha channel from a 16bpp (A555) bitmap stream.
GUI_CreateBitmapFromStreamAM555()	Creates a bitmap with an alpha channel from a 16bpp (AM555) bitmap stream.
GUI_CreateBitmapFromStreamA565()	Creates a bitmap with an alpha channel from a 16bpp (A565) bitmap stream.
GUI_CreateBitmapFromStreamAM565()	Creates a bitmap with an alpha channel from a 16bpp (AM565) bitmap stream.
GUI_CreateBitmapFromStream565()	Creates a bitmap from a 16bpp (565) bitmap stream.
GUI_CreateBitmapFromStreamM565()	Creates a bitmap from a 16bpp (M565) bitmap stream with red and blue swapped.
GUI_CreateBitmapFromStream555()	Creates a bitmap from a 16bpp (555) bitmap stream.
GUI_CreateBitmapFromStreamM555()	Creates a bitmap from a 16bpp (M555) bitmap stream with red and blue swapped.
GUI_CreateBitmapFromStreamRLE16()	Creates a bitmap from an RLE16 (565) bitmap stream.
GUI_CreateBitmapFromStreamRLEM16()	Creates a bitmap from an RLEM16 (M565) bitmap stream with red and blue swapped.
GUI_CreateBitmapFromStream24()	Creates a bitmap from a 24 bit bitmap stream.
GUI_CreateBitmapFromStreamAlpha()	Creates a bitmap from a 32 bit bitmap stream.
GUI_CreateBitmapFromStreamRLEAlpha()	Creates a bitmap from an RLE compressed 8 bit alpha bitmap stream.
GUI_CreateBitmapFromStreamRLE32()	Creates a bitmap from an RLE32 bitmap stream.
GUI_DrawStreamedBitmap()	Draws a bitmap from an indexed based bitmap stream (1 - 8bpp).
GUI_DrawStreamedBitmapAuto()	Draws a bitmap from a bitmap stream of any supported format.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_DrawStreamedBitmapEx()	Draws a bitmap from an indexed based bitmap stream (1 - 8bpp) without loading the complete image.
GUI_DrawStreamedBitmapExAuto()	Draws a bitmap from a bitmap stream of any supported format without loading the complete image.
GUI_DrawStreamedBitmapA555Ex()	Draws a bitmap from a 16bpp (A555) bitmap stream with alpha channel without loading the complete image.
GUI_DrawStreamedBitmapAM555Ex()	Draws a bitmap from a 16bpp (AM555) bitmap stream with alpha channel without loading the complete image.
GUI_DrawStreamedBitmapA565Ex()	Draws a bitmap from a 16bpp (AM565) bitmap stream with alpha channel without loading the complete image.
GUI_DrawStreamedBitmapAM565Ex()	Draws a bitmap from a 16bpp (AM565) bitmap stream with alpha channel without loading the complete image.
GUI_DrawStreamedBitmap555Ex()	Draws a bitmap from a 16bpp (555) bitmap stream without loading the complete image.
GUI_DrawStreamedBitmapM555Ex()	Draws a bitmap from a 16bpp (M555) bitmap stream without loading the complete image.
GUI_DrawStreamedBitmap565Ex()	Draws a bitmap from a 16bpp (565) bitmap stream without loading the complete image.
GUI_DrawStreamedBitmapM565Ex()	Draws a bitmap from a 16bpp (M565) bitmap stream without loading the complete image.
GUI_DrawStreamedBitmap24Ex()	Draws a bitmap from a 24bpp bitmap stream without loading the complete image.
GUI_GetStreamedBitmapInfo()	Returns information about the given stream.
GUI_GetStreamedBitmapInfoEx()	Returns information about the given stream which can be located on any kind of media.
GUI_SetStreamedBitmapHook()	Sets a hook function for GUI_DrawStreamedBitmapEx().
Drawing lines	
GUI_DrawHLine()	Draws a horizontal line.
GUI_DrawLine()	Draws a line from a specified starting point to a specified endpoint in the current window (absolute coordinates).
GUI_DrawLineRel()	Draws a line from the current (x, y) position to an endpoint specified by X-distance and Y-distance in the current window (relative coordinates).
GUI_DrawLineTo()	Draws a line from the current position to a specified endpoint.
GUI_DrawPolyLine()	Draws a polyline.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_DrawVLine()	Draws a vertical line.
GUI_GetLineStyle()	Returns the current line style used by the function GUI_DrawLine.
GUI_MoveRel()	Moves the current line pointer relative to its current position.
GUI_MoveTo()	Moves the current line pointer to the given position.
GUI_SetLineStyle()	Sets the current line style used by the function GUI_DrawLine().
Drawing polygons	
GUI_DrawPolygon()	Draws the outline of a polygon.
GUI_EnlargePolygon()	Enlarges a polygon.
GUI_FillPolygon()	Draws a filled polygon.
GUI_MagnifyPolygon()	Magnifies a polygon by a specified factor.
GUI_RotatePolygon()	Rotates a polygon by a specified angle.
Drawing circles	
GUI_DrawCircle()	Draws the outline of a circle.
GUI_FillCircle()	Draws a filled circle.
Drawing ellipses	
GUI_DrawEllipse()	Draws the outline of an ellipse.
GUI_DrawEllipseXL()	Draws the outline of a large ellipse.
GUI_FillEllipse()	Draws a filled ellipse.
Drawing arcs	
GUI_DrawArc()	Draws an arc.
Drawing a graph	
GUI_DrawGraph()	Draws a graph.
Drawing barcodes	
GUI_BARCODE_Draw()	Draws a barcode.
GUI_BARCODE_GetXSize()	Returns the X-size of a given barcode without drawing it.
Drawing QR codes	
GUI_QR_Create()	Creates a QR-code bitmap.
GUI_QR_CreateFramed()	Creates a QR-code bitmap with a white frame around it.
GUI_QR_Delete()	Deletes a QR-code bitmap.
GUI_QR_Draw()	Draws a QR-code bitmap.
GUI_QR_GetInfo()	Fills an information structure.
Drawing a pie chart	
GUI_DrawPie()	Draws a circle sector.
Drawing a spline	
GUI_SPLINE_Create()	Creates a spline.
GUI_SPLINE_Delete()	Deletes a spline.
GUI_SPLINE_Draw()	Draws a spline.
GUI_SPLINE_DrawAA()	Draw an anti aliased spline.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_SPLINE_GetY()	Return the Y-value of a point.
GUI_SPLINE_GetXSize()	Returns the X-size of a spline.
Saving and restoring the GUI context	
GUI_RestoreContext()	The function restores the GUI-context.
GUI_SaveContext()	The function saves the current GUI-context.
Info about screen changes	
GUI_DIRTYDEVICE_Create()	Creates a DIRTYDEVICE object.
GUI_DIRTYDEVICE_CreateEx()	Creates a DIRTYDEVICE object in the given layer.
GUI_DIRTYDEVICE_Delete()	Deletes a DIRTYDEVICE object.
GUI_DIRTYDEVICE_DeleteEx()	Deletes a DIRTYDEVICE object from the given layer.
GUI_DIRTYDEVICE_Fetch()	Fetches information from a DIRTYDEVICE.
GUI_DIRTYDEVICE_FetchEx()	Fetches information from a DIRTYDEVICE of the given layer.
YUV device	
GUI_YUV_Create()	Creates a YUV device in the current layer.
GUI_YUV_CreateEx()	Creates a YUV device in the given layer with the given period.
GUI_YUV_Delete()	Deletes the YUV device of the current layer.
GUI_YUV_DeleteEx()	Deletes the YUV device of the given layer.
GUI_YUV_GetpData()	Returns a pointer to the YUV plane of the current layer and the size of the plane in bytes.
GUI_YUV_GetpDataEx()	Returns a pointer to the YUV plane of the given layer and the size of the plane in bytes.
GUI_YUV_InvalidateArea()	Invalidates the given area of the current layer.
GUI_YUV_SetPeriod()	Sets the recalculation period of the YUV device in the current layer.
GUI_YUV_SetPeriodEx()	Sets the period to be used for (re)calculation.
Cache with color reducer	
GUI_GCACHE_4_Create()	Activates a global display cache with color reducer.
GUI_GCACHE_4_CreateEx()	Activates a global display cache with color reducer in the given layer.
Hook functions	
GUI_SetAfterInitHook()	Sets an optional function to be called during the process of initialization.
GUI_SetControlHook()	Sets a function which is called immediately before a display driver cache operation should be executed.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_SetRefreshHook()	Sets a callback function which waits until the vertical non display period has been reached before updating the screen.

Data structures

Structure	Description
GUI_ALPHA_STATE	Used for storing the alpha value with GUI_SetUserAlpha().
GUI_BITMAPSTREAM_INFO	Information about a streamed bitmap.
GUI_BITMAPSTREAM_PARAM	Contains a command to be used by a set hook function for GUI_DrawStreamedBitmapEx().
GUI_DIRTYDEVICE_INFO	Information about the dirty device.
GUI_GRADIENT_INFO	Information used for drawing multi-color gradients.
GUI_POINT	Point on the screen.
GUI_QR_INFO	Information about a QR code.
GUI_RECT	Rectangle on the screen.

Defines

Group of defines	Description
Barcode types	Type of barcode to be drawn.
Drawing modes	Mode to be used for drawing operations.
ECC levels for QR codes	Error correction level to be used for a QR code.
Line styles	Style how a line is drawn.

 © 2020 SEGGER Microcontroller GmbH

9.1.1 Drawing related functions

9.1.1.1 GUI_AddRect()

Description

This function resizes the given rectangle.

Prototype

```
void GUI_AddRect(      GUI_RECT * pDest,
                 const GUI_RECT * pRect,
                       int        Dist);
```

Parameters

Parameter	Description
pDest	Pointer to a rectangle where the modified rectangle gets stored in.
pRect	Pointer to the original rectangle.
Dist	Value to be added to the rect. If negative it gets substracted.

 © 2020 SEGGER Microcontroller GmbH

9.1.1.2 GUI_GetClientRect()

Description

The current client rectangle depends on using the Window Manager or not. If using the Window Manager the function uses `WM_GetClientRect` to retrieve the client rectangle. If not using the Window Manager the client rectangle corresponds to the complete LCD display.

Prototype

```
void GUI_GetClientRect(GUI_RECT * pRect);
```

Parameters

Parameter	Description
`pRect`	Pointer to the `GUI_RECT`-structure which is filled with the co-ordinates of the client rectangle.

 © 2020 SEGGER Microcontroller GmbH

9.1.1.3 GUI_GetClipRect()

Description

Returns the currently set clip rectangle.

Prototype

```
GUI_RECT *GUI_GetClipRect(void);
```

Return value

Pointer to the currently set clip rectangle.

 © 2020 SEGGER Microcontroller GmbH

9.1.1.4 GUI_GetDrawMode()

Description

Returns the current drawing mode.

Prototype

```
GUI_DRAWMODE GUI_GetDrawMode(void);
```

Return value

The currently selected drawing mode.

 © 2020 SEGGER Microcontroller GmbH

9.1.1.5 GUI_GetPenSize()

Description

Returns the current pen size.

Prototype

```
U8 GUI_GetPenSize(void);
```

Return value

The current pen size.

 © 2020 SEGGER Microcontroller GmbH

9.1.1.6 GUI_GetPixelIndex()

Description

Returns the color index of a given position.

Prototype

```
unsigned GUI_GetPixelIndex(int x,
                           int y);
```

Parameters

Parameter	Description
x	Absolute x-position of the pixel
y	Absolute y-position of the pixel

Return value

The color index of the given position.

 © 2020 SEGGER Microcontroller GmbH

9.1.1.7 GUI_SetClipRect()

Description

Sets the clipping rectangle used for limiting the output.

Prototype

```
GUI_RECT *GUI_SetClipRect(const GUI_RECT * pRect);
```

Parameters

Parameter	Description
pRect	Pointer to the rectangle which should be used for clipping. A NULL pointer should be used to restore the default value.

Return value

Pointer to the old clipping rectangle.

Additional information

The clipping area is limited to the configured (virtual) display size per default. Under some circumstances it can be useful to use a smaller clipping rectangle, which can be set using this function. The rectangle referred to should remain unchanged until the function is called again with a NULL pointer.

Example

The following example shows how to use the function:

```
GUI_RECT Rect = {10, 10, 100, 100};
GUI_SetClipRect(&Rect);
.
. // Draw something...
.
GUI_SetClipRect(NULL);
```

 © 2020 SEGGER Microcontroller GmbH

9.1.1.8 GUI_SetDrawMode()

Description

Selects the specified drawing mode.

Prototype

```
GUI_DRAWMODE GUI_SetDrawMode(GUI_DRAWMODE dm);
```

Parameters

Parameter	Description
dm	Drawing mode to set. Full list of permitted values can be found under *Drawing modes* on page 207.

Return value

The previously set drawing mode.

Additional information

If using colors, an inverted pixel is calculated as follows:

Example

```
//
// Showing two circles, the second one XOR-combined with the first:
//
GUI_Clear();
GUI_SetDrawMode(GUI_DRAWMODE_NORMAL);
GUI_FillCircle(120, 64, 40);
GUI_SetDrawMode(GUI_DRAWMODE_XOR);
GUI_FillCircle(140, 84, 40);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.1.9 GUI_SetPenSize()

Description

Sets the pen size to be used for further drawing operations.

Prototype

```
U8 GUI_SetPenSize(U8 PenSize);
```

Parameters

Parameter	Description
PenSize	Pen size in pixels to be used.

Return value

Previous pen size.

Additional information

The pen size should be ≥ 1. It is not possible to combine line styles with a pen size > 1.

The following vector drawing operations are affected by the pen size:

- GUI_DrawPoint()
- GUI_DrawLine()
- GUI_DrawLineRel()
- GUI_DrawLineTo()
- GUI_DrawPolyLine()
- GUI_DrawPolygon()
- GUI_DrawEllipse()
- GUI_DrawArc()
- GUI_DrawRect()
- GUI_DrawRectEx()

 © 2020 SEGGER Microcontroller GmbH

9.1.2 Basic drawing routines

The basic drawing routines allow drawing of individual points, horizontal and vertical lines and shapes at any position on the display. Any available drawing mode can be used. Since these routines are called frequently in most applications, they are optimized for speed as much as possible. For example, the horizontal and vertical line functions do not require the use of single-dot routines.

9.1.2.1 GUI_Clear()

Description

Clears the current window.

Prototype

```
void GUI_Clear(void);
```

Additional information

If no window has been defined, the current window is the entire display. In this case, the entire display is cleared.

Example

```
GUI_DispStringAt("Hello world", 0, 0);  // Display text.
GUI_Delay(1000);                        // Wait 1 second.
GUI_Clear();                            // Clear screen.
```

 © 2020 SEGGER Microcontroller GmbH

9.1.2.2 GUI_ClearRect()

Description

Clears a rectangular area at a specified position in the current window by filling it with the background color.

Prototype

```
void GUI_ClearRect(int x0,
                   int y0,
                   int x1,
                   int y1);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.

Related topics

- *GUI_InvertRect* on page 285
- *GUI_FillRect* on page 281

 © 2020 SEGGER Microcontroller GmbH

9.1.2.3 GUI_CopyRect()

Description

Copies the content of the given rectangular area to the specified position.

Prototype

```
void GUI_CopyRect(int x0,
                  int y0,
                  int x1,
                  int y1,
                  int xSize,
                  int ySize);
```

Parameters

Parameter	Description
x0	Upper left X-position of the source rectangle.
y0	Upper left Y-position of the source rectangle.
x1	Upper left X-position of the destination rectangle.
y1	Upper left Y-position of the destination rectangle.
xSize	X-size of the rectangle.
ySize	Y-size of the rectangle.

Additional information

The source and destination rectangle may overlap each other.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.4 GUI_DrawGradientH()

Description

Draws a rectangle filled with a horizontal color gradient.

Prototype

```
void GUI_DrawGradientH(int       x0,
                       int       y0,
                       int       x1,
                       int       y1,
                       GUI_COLOR Color0,
                       GUI_COLOR Color1);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.
Color0	Color to be drawn on the leftmost side of the rectangle.
Color1	Color to be drawn on the rightmost side of the rectangle.

Example

```
GUI_DrawGradientH(0, 0, 99, 99, 0x0000FF, 0x00FFFF);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.2.5 GUI_DrawGradientHEx()

Description

Draws a horizontal color gradient from a GUI_RECT pointer.

Prototype

```
void GUI_DrawGradientHEx(const GUI_RECT  * pRect,
                         GUI_COLOR   Color0,
                         GUI_COLOR   Color1);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure.
Color0	Color to be drawn on the leftmost side of the rectangle.
Color1	Color to be drawn on the rightmost side of the rectangle.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.6 GUI_DrawGradientV()

Description

Draws a rectangle filled with a vertical color gradient.

Prototype

```
void GUI_DrawGradientV(int       x0,
                       int       y0,
                       int       x1,
                       int       y1,
                       GUI_COLOR Color0,
                       GUI_COLOR Color1);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.
Color0	Color to be drawn on the topmost side of the rectangle.
Color1	Color to be drawn on the bottommost side of the rectangle.

Example

```
GUI_DrawGradientV(0, 0, 99, 99, 0x0000FF, 0x00FFFF);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.2.7 GUI_DrawGradientVEx()

Description

Draws a vertical color gradient from a GUI_RECT pointer.

Prototype

```
void GUI_DrawGradientVEx(const GUI_RECT  * pRect,
                                GUI_COLOR   Color0,
                                GUI_COLOR   Color1);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure.
Color0	Color to be drawn on the topmost side of the rectangle.
Color1	Color to be drawn on the bottommost side of the rectangle.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.8 GUI_DrawGradientRoundedH()

Description

Draws a rectangle with rounded corners filled with a horizontal color gradient.

Prototype

```
void GUI_DrawGradientRoundedH(int       x0,
                              int       y0,
                              int       x1,
                              int       y1,
                              int       rd,
                              GUI_COLOR Color0,
                              GUI_COLOR Color1);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.
rd	Radius to be used for the rounded corners.
Color0	Color to be drawn on the leftmost side of the rectangle.
Color1	Color to be drawn on the rightmost side of the rectangle.

Example

```
GUI_DrawGradientRoundedH(0, 0,  99, 99, 25, 0x0000FF, 0x00FFFF);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.2.9 GUI_DrawGradientRoundedHEx()

Description

Draws a rectangle with rounded corners filled with a horizontal color gradient.

Prototype

```
void GUI_DrawGradientRoundedHEx(const GUI_RECT  * pRect,
                                int             rd,
                                GUI_COLOR       Color0,
                                GUI_COLOR       Color1);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure.
rd	Radius to be used for the rounded corners.
Color0	Color to be drawn on the leftmost side of the rectangle.
Color1	Color to be drawn on the rightmost side of the rectangle.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.10 GUI_DrawGradientRoundedV()

Description

Draws a rectangle with rounded corners filled with a vertical color gradient.

Prototype

```
void GUI_DrawGradientRoundedV(int       x0,
                              int       y0,
                              int       x1,
                              int       y1,
                              int       rd,
                              GUI_COLOR Color0,
                              GUI_COLOR Color1);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.
rd	Radius to be used for the rounded corners.
Color0	Color to be drawn on the leftmost side of the rectangle.
Color1	Color to be drawn on the rightmost side of the rectangle.

Example

```
GUI_DrawGradientRoundedV(0, 0, 99, 99, 25, 0x0000FF, 0x00FFFF);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.2.11 GUI_DrawGradientRoundedVEx()

Description

Draws a vertical color gradient with rounded corners from a GUI_RECT pointer.

Prototype

```
void GUI_DrawGradientRoundedVEx(const GUI_RECT  * pRect,
                                int             rd,
                                GUI_COLOR       Color0,
                                GUI_COLOR       Color1);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure.
rd	Radius to be used for the rounded corners.
Color0	Color to be drawn on the leftmost side of the rectangle.
Color1	Color to be drawn on the rightmost side of the rectangle.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.12 GUI_DrawGradientMH()

9.1.2.13 GUI_DrawGradientMV()

Description

These functions draw a multi color gradient either horizontal or vertical.

Prototype

```
void GUI_DrawGradientMH(int                 x0,
                        int                 y0,
                        int                 y1,
                        GUI_GRADIENT_INFO * pGradientInfo,
                        int                 NumColors);

void GUI_DrawGradientMV(int                 x0,
                        int                 y0,
                        int                 x1,
                        GUI_GRADIENT_INFO * pGradientInfo,
                        int                 NumColors);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.
pGradientInfo	Pointer to a GUI_GRADIENT_INFO structure.
NumColors	Number of colors in pGradientInfo.

Additional information

The member Pos of the GUI_GRADIENT_INFO structure is used to define the start and end position of the colors. It defines also the size of the gradient.

Example

```
#include "GUI.h"
/*********************************************************************
*
*       MainTask
*/
void MainTask(void) {
  GUI_GRADIENT_INFO aInfo[] = {
    {0,   GUI_RED},
    {60,  GUI_GREEN},
    {120, GUI_BLUE},  // Resulting in a gradient with a size of 120 Pixel
  };
  GUI_Init();
  GUI_DrawGradientMH(0, 0, 120, &aInfo[0], GUI_COUNTOF(aInfo));
  while (1) {
    GUI_Delay(100);
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

9.1.2.14 GUI_DrawGradientMHEx()

9.1.2.15 GUI_DrawGradientMVEx()

Description

These functions draw a multi color gradient either horizontal or vertical from a GUI_RECT pointer. See the functions GUI_DrawGradientMH() and GUI_DrawGradientMV() for more information.

Prototype

```
void GUI_DrawGradientMHEx(GUI_RECT          * pRect,
                          GUI_GRADIENT_INFO * pGradientInfo,
                          int                 NumColors);

void GUI_DrawGradientMVEx(GUI_RECT          * pRect,
                          GUI_GRADIENT_INFO * pGradientInfo,
                          int                 NumColors);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure.
pGradientInfo	Pointer to a GUI_GRADIENT_INFO structure.
NumColors	Number of colors in pGradientInfo.

Additional information

The member Pos of the GUI_GRADIENT_INFO structure is used to define the start and end position of the colors. It defines also the size of the gradient.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.16 GUI_DrawPixel()

Description

Draws a pixel at a specified position in the current window.

Prototype

```
void GUI_DrawPixel(int x,
                   int y);
```

Parameters

Parameter	Description
x	X-position of pixel.
y	Y-position of pixel.

Related topics

- *GUI_DrawPoint* on page 274

 © 2020 SEGGER Microcontroller GmbH

9.1.2.17 GUI_DrawPoint()

Description

Draws a point with the current pen size at a specified position in the current window.

Prototype

```
void GUI_DrawPoint(int x,
                   int y);
```

Parameters

Parameter	Description
x	X-position of point.
y	Y-position of point.

Related topics

- *GUI_DrawPixel* on page 273

 © 2020 SEGGER Microcontroller GmbH

9.1.2.18 GUI_DrawRect()

Description

Draws a rectangle at a specified position in the current window.

Prototype

```
void GUI_DrawRect(int x0,
                  int y0,
                  int x1,
                  int y1);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.19 GUI_DrawRectEx()

Description

Draws a rectangle in the current window at the position specified in the rectangle passed to the function.

Prototype

```
void GUI_DrawRectEx(const GUI_RECT * pRect);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT-structure containing the coordinates of the rectangle

 © 2020 SEGGER Microcontroller GmbH

9.1.2.20 GUI_DrawRoundedFrame()

Description

Draws a frame at a specified position in the current window with rounded corners an a specified width.

Prototype

```
void GUI_DrawRoundedFrame(int x0,
                          int y0,
                          int x1,
                          int y1,
                          int r,
                          int w);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.
r	Radius to be used for the rounded corners.
w	Width in which the frame is drawn.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.21 GUI_DrawRoundedFrameEx()

Description

Draws a frame at a specified position in the current window with rounded corners an a specified width.

Prototype

```
void GUI_DrawRoundedFrameEx(const GUI_RECT * pRect,
                            int        r,
                            int        w);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure.
r	Radius to be used for the rounded corners.
w	Width in which the frame is drawn.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.22 GUI_DrawRoundedRect()

Description

Draws a rectangle at a specified position in the current window with rounded corners.

Prototype

```
void GUI_DrawRoundedRect(int x0,
                         int y0,
                         int x1,
                         int y1,
                         int r);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.
r	Radius to be used for the rounded corners.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.23 GUI_DrawRoundedRectEx()

Description

Draws a rectangle at a specified position in the current window with rounded corners.

Prototype

```
void GUI_DrawRoundedRectEx(const GUI_RECT * pRect,
                           int        r);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure.
r	Radius to be used for the rounded corners.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.24 GUI_FillRect()

Description

Draws a filled rectangular area at a specified position in the current window.

Prototype

```
void GUI_FillRect(int x0,
                  int y0,
                  int x1,
                  int y1);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.

Additional information

Uses the current drawing mode, which normally means all pixels inside the rectangle are set.

Related topics

- *GUI_InvertRect* on page 285
- *GUI_ClearRect* on page 261

 © 2020 SEGGER Microcontroller GmbH

9.1.2.25 GUI_FillRectEx()

Description

Draws a filled rectangular area in the current window at the position specified in the rectangle passed to the function.

Prototype

```
void GUI_FillRectEx(const GUI_RECT * pRect);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT-structure containing the coordinates of the rectangle.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.26 GUI_FillRoundedRect()

Description

Draws a filled rectangle at a specified position in the current window with rounded corners.

Prototype

```
void GUI_FillRoundedRect(int x0,
                         int y0,
                         int x1,
                         int y1,
                         int r);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.
r	Radius to be used for the rounded corners.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.27 GUI_FillRoundedRectEx()

Description

Draws a filled rectangle at a specified position in the current window with rounded corners.

Prototype

```
void GUI_FillRoundedRectEx(const GUI_RECT * pRect,
                           int        r);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure containing the coordinates of the rectangle.
r	Radius to be used for the rounded corners.

 © 2020 SEGGER Microcontroller GmbH

9.1.2.28 GUI_InvertRect()

Description

Draws an inverted rectangular area at a specified position in the current window.

Prototype

```
void GUI_InvertRect(int x0,
                    int y0,
                    int x1,
                    int y1);
```

Parameters

Parameter	Description
x0	Upper left X-position.
y0	Upper left Y-position.
x1	Lower right X-position.
y1	Lower right Y-position.

Related topics

- *GUI_FillRect* on page 281
- *GUI_ClearRect* on page 261

 © 2020 SEGGER Microcontroller GmbH

9.1.3 Alpha blending

Alpha blending is a method of combining a foreground image with the background to create the appearance of semi transparency. An alpha value determines how much of a pixel should be visible and how much of the background should show through.

Color information

emWin internally works with 32 bits of color information. It is important to know that emWin is able to use 2 different color formats. For details please refer to *Logical colors* on page 619. That chapter explains the differences between both logical color modes. Important here is to know that when using the default logical color format (ABGR) an alpha value of 0 means opaque and a value of 255 means completely transparent. In case of using ARGB the meaning is vice versa: 0 means completely transparent and 255 means opaque. The documentation assumes using the default format (ABGR).

How it works

The alpha blending is done completely automatically once it is enabled by using the function `GUI_EnableAlpha()`. This makes emWin regard the upper 8 bits of the color information as alpha value. Enabling alpha blending is required only for functions which use the background or foreground color. Bitmaps which already contain alpha values (32bpp) are automatically displayed properly, so enabling alpha blending is not required in this case.

Example

The following small example shows how it works:

```
GUI_EnableAlpha(1);
GUI_SetBkColor(GUI_WHITE);
GUI_Clear();
GUI_SetColor(GUI_BLACK);
GUI_DispStringHCenterAt("Alphablending", 45, 41);
GUI_SetColor(GUI_MAKE_COLOR((0x40uL << 24) | 0x0000FF));
GUI_FillRect(0, 0, 49, 49);
GUI_SetColor(GUI_MAKE_COLOR((0x80uL << 24) | 0x00FF00));
GUI_FillRect(20, 20, 69, 69);
GUI_SetColor(GUI_MAKE_COLOR((0xC0uL << 24) | 0xFF0000));
GUI_FillRect(40, 40, 89, 89);
GUI_EnableAlpha(0);
```



Older versions

In older versions it was required to use the function `GUI_SetAlpha()` for blending the foreground with the current background color information. This also works but is no longer required.

 © 2020 SEGGER Microcontroller GmbH

9.1.3.1 GUI_EnableAlpha()

Description

Enables or disables automatic alpha blending.

Prototype

```
unsigned GUI_EnableAlpha(unsigned OnOff);
```

Parameters

Parameter	Description
OnOff	1 enables automatic alpha blending, 0 disables it.

Return value

Old state.

Additional information

After enabling automatic alpha blending the color information of each object automatically determines its transparency. It is recommended to disable the function after it has been used to avoid unwanted behavior.

> **Note**
>
> If alpha blending does not get disabled after using it, it might have a heavy impact on the overall performance.

 © 2020 SEGGER Microcontroller GmbH

9.1.3.2 GUI_PreserveTrans()

Description

Makes sure that alpha channel remains after drawing operations. Drawing items using an alpha value normally requires mixing the content of the framebuffer with the item color. Mixing is done by using the alpha channel of the item color as intensity information for mixing the colors. After the drawing operation the alpha value is normally lost. But there could be situations where mixing is not wanted, for example when working with a multi layer hardware. If the alpha values of a bitmap or set by `GUI_SetAlpha()` should remain as alpha channel in the frame buffer this function should be called immediately before the drawing operation. To avoid unwanted behavior and side effects on other drawing operations it is recommended to disable that function after use.

Prototype

```
unsigned GUI_PreserveTrans(unsigned OnOff);
```

Parameters

Parameter	Description
`OnOff`	1 enables transparency preserving, 0 disables it.

Return value

Old state.

 © 2020 SEGGER Microcontroller GmbH

9.1.3.3 GUI_RestoreUserAlpha()

Description

Restores the previous state of user alpha blending. Saved in the structure passed to the function.

Prototype

```
U32 GUI_RestoreUserAlpha(GUI_ALPHA_STATE * pAlphaState);
```

Parameters

Parameter	Description
pAlphaState	Pointer to a GUI_ALPHA_STATE structure containing information of the previous state to be restored.

Return value

Current user alpha value.

Example

```
GUI_ALPHA_STATE AlphaState;

GUI_EnableAlpha(1);
GUI_SetBkColor(GUI_WHITE);
GUI_Clear();
GUI_SetColor(GUI_BLACK);
GUI_DispStringHCenterAt("Alphablending", 45, 41);
GUI_SetUserAlpha(&AlphaState, 0xC0);
GUI_SetColor(GUI_RED);
GUI_FillRect(0, 0, 49, 49);
GUI_SetColor(GUI_GREEN);
GUI_FillRect(20, 20, 69, 69);
GUI_SetColor(GUI_BLUE);
GUI_FillRect(40, 40, 89, 89);
GUI_RestoreUserAlpha(&AlphaState);
```



 © 2020 SEGGER Microcontroller GmbH

9.1.3.4 GUI_SetAlpha()

Description

Enables software alpha blending for all subsequent drawing operations.

Parameters

Parameter	Description
Alpha	Alpha value to be used for all subsequent drawing operations. Default is 0 which means no alpha blending.

Return value

Previous value used for alpha blending.

Additional information

The function sets the alpha value to be used for all subsequent drawing operations. A value of 0 for parameter Alpha means opaque (alpha blending disabled) and a value of 255 means completely transparent (invisible).
Note that software alpha blending increases the CPU load. Further it is strongly recommended to set the alpha value back to the default value after finishing the drawing operations.

Example

```
extern const GUI_BITMAP _LogoBitmap;
GUI_SetColor(GUI_BLUE);
GUI_FillCircle(100, 50, 49);
GUI_SetColor(GUI_YELLOW);
for (i = 0; i < 100; i++) {
  U8 Alpha;
  Alpha = (i * 255 / 100);
  GUI_SetAlpha(Alpha);
  GUI_DrawHLine(i, 100 - i, 100 + i);
}
GUI_SetAlpha(0x80);
GUI_DrawBitmap(&_LogoBitmap, 30, 30);
GUI_SetColor(GUI_MAGENTA);
GUI_SetFont(&GUI_Font24B_ASCII);
GUI_SetTextMode(GUI_TM_TRANS);
GUI_DispStringHCenterAt("Alphablending", 100, 3);
GUI_SetAlpha(0);                          /* Set back to default (opaque) */
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.3.5 GUI_SetUserAlpha()

Description

Sets an additional value which is used to calculate the actual alpha value to be used.

Prototype

```
U32 GUI_SetUserAlpha(GUI_ALPHA_STATE * pAlphaState,
                     U32               UserAlpha);
```

Parameters

Parameter	Description
pAlphaState	Pointer to an GUI_ALPHA_STATE structure to be used to save the current state.
UserAlpha	Value to be used.

Return value

Previous value used for alpha blending.

Additional information

The actual alpha value is calculated as follows:

```
Alpha = AlphaFromObject + ((255 - AlphaFromObject) × UserAlpha) ÷ 255
```

The function GUI_RestoreUserAlpha() can be used to restore the previous state of the function.

 © 2020 SEGGER Microcontroller GmbH

9.1.4 Drawing bitmaps

Generally emWin is able to display any bitmap image at any display position. On 16 bit CPUs (`sizeof(int) = 2`), the size of one bitmap per default is limited to 64 KB. If larger bitmaps should be displayed with a 16 bit CPU, refer to the chapter *Configuration* on page 620.

9.1.4.1 GUI_DrawBitmap()

Description

Draws a bitmap image at a specified position in the current window.

Prototype

```
void GUI_DrawBitmap(const GUI_BITMAP * pBitmap,
                    int          x0,
                    int          y0);
```

Parameters

Parameter	Description
pBitmap	Pointer to the bitmap to display.
x	X-position of the upper left corner of the bitmap in the display.
y	Y-position of the upper left corner of the bitmap in the display.

Additional information

The picture data is interpreted as bit stream starting with the most significant bit (msb) of the first byte. A new line always starts at an even byte address, as the n th line of the bitmap starts at offset (n * BytesPerLine). The bitmap can be shown at any point in the client area. Usually, the Bitmap Converter is used to generate bitmaps. Detailed information can be found in the chapter *Bitmap Converter* on page 438.

Example

```
extern const GUI_BITMAP bmSeggerLogoBlue;  /* declare external Bitmap */

void main() {
  GUI_Init();
  GUI_DrawBitmap(&bmSeggerLogoBlue, 45, 20);
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.4.2 GUI_DrawBitmapEx()

Description

This routine makes it possible to scale and/or to mirror a bitmap on the display.

Prototype

```
void GUI_DrawBitmapEx(const GUI_BITMAP * pBitmap,
                      int          x0,
                      int          y0,
                      int          xCenter,
                      int          yCenter,
                      int          xMag,
                      int          yMag);
```

Parameters

Parameter	Description
pBitmap	Pointer to the bitmap to display.
x0	X-position of the anchor point in the display.
y0	Y-position of the anchor point in the display.
xCenter	X-position of the anchor point in the bitmap. Specifies the bitmap pixel of the bitmap which should be displayed at x0 on the screen independent of scaling or mirroring.
yCenter	Y-position of the anchor point in the bitmap. Specifies the bitmap pixel of the bitmap which should be displayed at y0 on the screen independent of scaling or mirroring.
xMag	Scale factor of X-direction in the unit 1/1000. A negative value mirrors the x-axis.
yMag	Scale factor of Y-direction in the unit 1/1000. A negative value mirrors the y-axis.

Additional information

This function can not be used to draw RLE-compressed bitmaps and bitmaps in the format A565.

 © 2020 SEGGER Microcontroller GmbH

9.1.4.3 GUI_DrawBitmapMag()

Description

This routine makes it possible to magnify a bitmap on the display.

Prototype

```
void GUI_DrawBitmapMag(const GUI_BITMAP * pBitmap,
                       int          x0,
                       int          y0,
                       int          xMul,
                       int          yMul);
```

Parameters

Parameter	Description
pBitmap	Pointer to the bitmap to display.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.
XMul	Magnification factor of X-direction.
YMul	Magnification factor of Y-direction.

 © 2020 SEGGER Microcontroller GmbH

9.1.4.4 GUI_SetAlphaMask8888()

Description

That routine takes only effect on drawing non compressed true color bitmaps (GUI_DRAW_BMP8888 and GUI_DRAW_BMPM8888I). It can be used to set additional masks used for drawing the pixels of a non compressed true color bitmap.

Prototype

```
void GUI_SetAlphaMask8888(U32 OrMask,
                          U32 AndMask);
```

Parameters

Parameter	Description
OrMask	Value to be OR combined with each pixel.
AndMask	Value to be AND combined with each pixel.

 © 2020 SEGGER Microcontroller GmbH

9.1.5 Drawing streamed bitmaps

Streamed bitmaps can be located in addressable area (RAM or ROM) as well as external memory (e.g. on removable devices).

Drawing from addressable memory

There are 2 possibilities to display streamed bitmaps which are located on addressable memory. The first one is to use the function `GUI_DrawStreamedBitmap()` or the function `GUI_DrawStreamedBitmapAuto()`. The second one is to create a `GUI_BITMAP` according to the streamed bitmap and use it for a regular call of e.g. `GUI_DrawBitmap()`.

Drawing from external memory

Streamed bitmaps which are located on external memory can be drawn using the *…Ex() functions*. *…Ex() functions* require a pointer to a user defined `GetData()` function (see *Getting data with the …Ex() functions* on page 436) in order to have emWin retrieve the stream self-dependently. If the format of the streamed bitmap is unknown at run-time, the function `GUI_DrawStreamedBitmapExAuto()` should be used.

Requirements

The *…Ex() functions* require to have enough free memory which is assigned to emWin to store at least one line of pixel data. If there is not enough free memory, the function will return immediately without having anything drawn. Using the *…Auto() function* causes the linker to add all functions referenced by the *…Auto() function*. If there is not enough memory the according function for the specific format should be used (e.g. `GUI_DrawStreamedBitmap565Ex()`).

Available bitmap formats

The following table shows the currently supported formats and the availability of according *…Ex() functions*:

Format	Description	…Ex() function available
IDX	Index based* bitmaps 1-8bpp.	Yes
444_12	12bpp Bitmaps, 4 bits blue, 4 bits green, 4 bits red.	Yes
444_12_1	12bpp Bitmaps, 4 bits blue, 4 bits green, 4 bits red.	Yes
444_16	12bpp Bitmaps, 4 bits blue, 4 bits green, 4 bits red.	Yes
M444_16	12bpp Bitmaps, 4 bits red, 4 bits green, 4 bits blue.	Yes
M444_12	12bpp Bitmaps, 4 bits red, 4 bits green, 4 bits blue.	Yes
M444_12_1	12bpp Bitmaps, 4 bits red, 4 bits green, 4 bits blue.	Yes
555	16bpp high color bitmaps, 5 bits blue, 5 bits green, 5 bits red.	Yes
M555	16bpp high color bitmaps, 5 bits red, 5 bits green, 5 bits blue.	Yes
565	16bpp high color bitmaps, 5 bits blue, 6 bits green, 5 bits red.	Yes
M565	16bpp high color bitmaps, 5 bits red, 6 bits green, 5 bits blue.	Yes
A555	16bpp high color bitmaps, 5 bits blue, 5 bits green, 5 bits red, 8 bit alpha channel	Yes
AM555	16bpp high color bitmaps, 5 bits red, 5 bits green, 5 bits blue, 8 bit alpha channel	Yes

 © 2020 SEGGER Microcontroller GmbH

Format	Description	...Ex() function available
A565	16bpp high color bitmaps, 5 bits blue, 6 bits green, 5 bits red, 8 bit alpha channel	Yes
AM565	16bpp high color bitmaps, 5 bits red, 6 bits green, 5 bits blue, 8 bit alpha channel	Yes
24	24bpp true color bitmaps, 8 bits blue, 8 bits green, 8 bits red.	Yes
Alpha	32bpp true color bitmaps, 8 bits alpha, 8 bits blue, 8 bits green, 8 bits red.	No
RLEAlpha	8bpp alpha channel bitmaps, compressed.	No
RLE4	4bpp index based bitmaps, RLE compressed.	Yes
RLE8	8bpp index based bitmaps, RLE compressed.	Yes
RLE16	16bpp (565) high color bitmaps, RLE compressed.	Yes
RLEM16	16bpp (M565) high color bitmaps, RLE compressed.	Yes
RLE32	32bpp (8888) true color bitmaps with alpha channel, RLE compressed.	Yes

Note

***** Index based bitmaps consist of a palette of colors stated as 32bit values. All other bitmaps do not have a palette and therefore have the bitmap data stored in the format specified in the table.

 © 2020 SEGGER Microcontroller GmbH

9.1.5.1 GUI_CreateBitmapFromStream()

Description

The function creates a bitmap structure by passing any type of bitmap stream.

Prototype

```
int GUI_CreateBitmapFromStream(      GUI_BITMAP     * pBMP,
                                     GUI_LOGPALETTE * pPAL,
                               const void           * p);
```

Parameters

Parameter	Description
pBMP	Pointer to a GUI_BITMAP structure to be initialized by the function.
pPAL	Pointer to a GUI_LOGPALETTE structure to be initialized by the function.
p	Pointer to the data stream.

Return value

0 on success
1 on error.

Additional information

This function should be used if the data stream can consist of several kinds of bitmap formats or unknown. Disadvantage of using this function is that it has a significant memory footprint. If memory usage (ROM) is a concern, it may be better to use the format specific functions below. All pointers passed to this function have to remain vaild as long as the bitmap should be used (e.g. take care if using stack variables).

Example

The following example shows how the GUI_CreateBitmapFromStream() functions can be used to create and draw a bitmap:

```
void DrawBitmap(const void * pData, int xPos, int yPos) {
  GUI_BITMAP     Bitmap;
  GUI_LOGPALETTE Palette;

  GUI_CreateBitmapFromStream(&Bitmap, &Palette, pData);
  GUI_DrawBitmap(&Bitmap, xPos, yPos);
}
```

 © 2020 SEGGER Microcontroller GmbH

9.1.5.2 GUI_CreateBitmapFromStreamIDX()

9.1.5.3 GUI_CreateBitmapFromStreamRLE4()

9.1.5.4 GUI_CreateBitmapFromStreamRLE8()

9.1.5.5 GUI_CreateBitmapFromStream444_12()

9.1.5.6 GUI_CreateBitmapFromStream444_12_1()

9.1.5.7 GUI_CreateBitmapFromStreamM444_12()

9.1.5.8 GUI_CreateBitmapFromStreamM444_12_1()

9.1.5.9 GUI_CreateBitmapFromStream444_16()

9.1.5.10 GUI_CreateBitmapFromStreamM444_16()

9.1.5.11 GUI_CreateBitmapFromStreamA555()

9.1.5.12 GUI_CreateBitmapFromStreamAM555()

9.1.5.13 GUI_CreateBitmapFromStreamA565()

9.1.5.14 GUI_CreateBitmapFromStreamAM565()

9.1.5.15 GUI_CreateBitmapFromStream565()

9.1.5.16 GUI_CreateBitmapFromStreamM565()

9.1.5.17 GUI_CreateBitmapFromStream555()

9.1.5.18 GUI_CreateBitmapFromStreamM555()

9.1.5.19 GUI_CreateBitmapFromStreamRLE16()

9.1.5.20 GUI_CreateBitmapFromStreamRLEM16()

9.1.5.21 GUI_CreateBitmapFromStream24()

9.1.5.22 GUI_CreateBitmapFromStreamAlpha()

9.1.5.23 GUI_CreateBitmapFromStreamRLEAlpha()

9.1.5.24 GUI_CreateBitmapFromStreamRLE32()

Description

These functions create bitmap structures by passing bitmap streams of a known format.

Prototype

```
int GUI_CreateBitmapFromStream<FORMAT>(      GUI_BITMAP     * pBMP,
```

 © 2020 SEGGER Microcontroller GmbH

```
                                    GUI_LOGPALETTE * pPAL,
                              const void           * p);
```

Parameters

Parameter	Description
pBMP	Pointer to a GUI_BITMAP structure to be initialized by the function.
pPAL	Pointer to a GUI_LOGPALETTE structure to be initialized by the function.
p	Pointer to the data stream.

Supported data stream formats

The following table shows the supported data stream formats for each function:

Function	Supported stream format
GUI_CreateBitmapFromStreamIDX()	Streams of index based bitmaps.
GUI_CreateBitmapFromStreamRLE4()	Streams of RLE4 compressed bitmaps.
GUI_CreateBitmapFromStreamRLE8()	Streams of RLE8 compressed bitmaps.
GUI_CreateBitmapFromStreamA555()	Streams of high color bitmaps with alpha channel (A555).
GUI_CreateBitmapFromStreamAM555()	Streams of high color bitmaps with alpha channel (AM555).
GUI_CreateBitmapFromStreamA565()	Streams of high color bitmaps with alpha channel (A565).
GUI_CreateBitmapFromStreamAM565()	Streams of high color bitmaps with alpha channel (AM565).
GUI_CreateBitmapFromStream444_12()	Streams 12bpp bitmaps (444_12).
GUI_CreateBitmapFromStream444_12_1()	Streams 12bpp bitmaps (444_12_1).
GUI_CreateBitmapFromStream444_16()	Streams 12bpp bitmaps (444_16).
GUI_CreateBitmapFromStreamM444_12()	Streams 12bpp bitmaps (M444_12).
GUI_CreateBitmapFromStreamM444_12_1()	Streams 12bpp bitmaps (M444_12_1).
GUI_CreateBitmapFromStreamM444_16()	Streams 12bpp bitmaps (M444_16).
GUI_CreateBitmapFromStream565()	Streams of high color bitmaps (565).
GUI_CreateBitmapFromStreamM565()	Streams of high color bitmaps (M565).
GUI_CreateBitmapFromStream555()	Streams of high color bitmaps (555).
GUI_CreateBitmapFromStreamM555()	Streams of high color bitmaps (M565).
GUI_CreateBitmapFromStreamRLE16()	Streams of RLE16 compressed bitmaps.
GUI_CreateBitmapFromStreamRLEM16()	Streams of RLE16 compressed bitmaps, red and blue swapped.
GUI_CreateBitmapFromStream24()	Streams of 24bpp bitmaps (true color).
GUI_CreateBitmapFromStreamAlpha()	Streams of 32bpp bitmaps (true color with alpha channel).
GUI_CreateBitmapFromStreamRLEAlpha()	Streams of RLE compressed 8bpp alpha bitmaps.
GUI_CreateBitmapFromStreamRLE32()	Streams of RLE32 compressed bitmaps (true color with alpha channel).

 © 2020 SEGGER Microcontroller GmbH

Return value

0	on success
1	on error

Additional information

These functions should be used if the data stream consists of a known format. This avoids linking of unused code and keeps the binary code small.

 © 2020 SEGGER Microcontroller GmbH

9.1.5.25 GUI_DrawStreamedBitmap()

Description

Draws a bitmap from an indexed based bitmap data stream.

Prototype

```
void GUI_DrawStreamedBitmap(const void * p,
                            int    x,
                            int    y);
```

Parameters

Parameter	Description
p	Pointer to the data stream.
x	X-position of the upper left corner of the bitmap in the display.
y	Y-position of the upper left corner of the bitmap in the display.

Additional information

The Bitmap Converter can be used to create bitmap data streams. The format of these streams does not equal the format of a bmp file. Details can be found in the chapter *Bitmap Converter* on page 438.

 © 2020 SEGGER Microcontroller GmbH

9.1.5.26 GUI_DrawStreamedBitmapAuto()

Description

Draws a bitmap from a bitmap data stream of any supported format.

Prototype

```
void GUI_DrawStreamedBitmapAuto(const void * p,
                                int    x,
                                int    y);
```

Parameters

Parameter	Description
p	Pointer to the data stream.
x	X-position of the upper left corner of the bitmap in the display.
y	Y-position of the upper left corner of the bitmap in the display.

Additional information

Additional information can be found under `GUI_DrawStreamedBitmap()`.

 © 2020 SEGGER Microcontroller GmbH

9.1.5.27 GUI_DrawStreamedBitmapEx()

Description

This function can be used for drawing index based bitmap data streams if not enough RAM or ROM is available to keep the whole file within the addressable memory (RAM or ROM). The GUI library calls the function pointed by the parameter pfGetData to read the data. This GetData function needs to return the number of read bytes.

Prototype

```
int GUI_DrawStreamedBitmapEx(      GUI_GET_DATA_FUNC * pfGetData,
                             const void              * p,
                                   int                 x,
                                   int                 y);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x	X-position of the upper left corner of the bitmap in the display.
y	Y-position of the upper left corner of the bitmap in the display.

Return value

0 on success
1 on error.

Additional information

The function requires at least memory for one line of bitmap data. For more details please also refer to the function GUI_SetStreamedBitmapHook().

 © 2020 SEGGER Microcontroller GmbH

9.1.5.28 GUI_DrawStreamedBitmapExAuto()

Description

This function can be used for drawing bitmap data streams of any supported format if not enough RAM or ROM is available to keep the whole file within the addressable memory (RAM or ROM). The GUI library calls the function pointed by the parameter pfGetData to read the data. This GetData function needs to return the number of read bytes.

Prototype

```
int GUI_DrawStreamedBitmapExAuto(      GUI_GET_DATA_FUNC * pfGetData,
                                 const void              * p,
                                       int                 x,
                                       int                 y);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x	X-position of the upper left corner of the bitmap in the display.
y	Y-position of the upper left corner of the bitmap in the display.

Return value

0 on success
1 on error.

Additional information

The function requires at least memory for one line of bitmap data.

 © 2020 SEGGER Microcontroller GmbH

9.1.5.29 GUI_DrawStreamedBitmapA555Ex()

9.1.5.30 GUI_DrawStreamedBitmapAM555Ex()

9.1.5.31 GUI_DrawStreamedBitmapA565Ex()

9.1.5.32 GUI_DrawStreamedBitmapAM565Ex()

9.1.5.33 GUI_DrawStreamedBitmap555Ex()

9.1.5.34 GUI_DrawStreamedBitmapM555Ex()

9.1.5.35 GUI_DrawStreamedBitmap565Ex()

9.1.5.36 GUI_DrawStreamedBitmapM565Ex()

9.1.5.37 GUI_DrawStreamedBitmap24Ex()

Description

This function can be used for drawing bitmap data streams of the respective format if not enough RAM or ROM is available to keep the whole file within the addressable memory (RAM or ROM). The GUI library calls the function pointed by the parameter `pfGetData` to read the data. This `GetData` function needs to return the number of read bytes.

Prototype

```
int GUI_DrawStreamedBitmap<XXX>Ex(      GUI_GET_DATA_FUNC * pfGetData,
                                  const void              * p,
                                        int                 x,
                                        int                 y);
```

Parameters

Parameter	Description
`pfGetData`	Pointer to a function which is called for getting data. For details about the `GetData` function, refer to *Getting data with the …Ex() functions* on page 436.
`p`	Void pointer passed to the function pointed by `pfGetData`.
`x`	X-position of the upper left corner of the bitmap in the display.
`y`	Y-position of the upper left corner of the bitmap in the display.

Return value

0	on success
1	on error

Additional information

The functions require at least memory for one line of bitmap data.

 © 2020 SEGGER Microcontroller GmbH

9.1.5.38 GUI_GetStreamedBitmapInfo()

Description

Returns a structure with information about the given data stream.

Prototype

```
void GUI_GetStreamedBitmapInfo(const void                  * p,
                               GUI_BITMAPSTREAM_INFO * pInfo);
```

Parameters

Parameter	Description
p	Pointer to the data stream.
pInfo	Pointer to a GUI_BITMAPSTREAM_INFO structure to be filled by the function.

 © 2020 SEGGER Microcontroller GmbH

9.1.5.39 GUI_GetStreamedBitmapInfoEx()

Description

Returns a structure with information about the given data stream which does not need to be located in the addressable ROM or RAM area of the CPU.

Prototype

```
int GUI_GetStreamedBitmapInfoEx(      GUI_GET_DATA_FUNC     * pfGetData,
                                const void                  * p,
                                      GUI_BITMAPSTREAM_INFO * pInfo);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
pInfo	Pointer to a GUI_BITMAPSTREAM_INFO structure to be filled by the function.

Return value

0 on success
1 on error.

Elements of structure GUI_BITMAPSTREAM_INFO

The elements of the structure GUI_BITMAPSTREAM_INFO are listed under *GUI_GetStreamedBitmapInfo* on page 307.

 © 2020 SEGGER Microcontroller GmbH

9.1.5.40 GUI_SetStreamedBitmapHook()

Description

Sets a hook function to be able to manipulate the palette of a streamed bitmap which is not located in the addressable area of the CPU. The hook function is called when executing `GUI_DrawStreamedBitmapEx()`.

Prototype

```
void GUI_SetStreamedBitmapHook(GUI_BITMAPSTREAM_CALLBACK pfStreamedBitmapHook);
```

Parameters

Parameter	Description
pfStreamedBitmapHook	Hook function to be called by `GUI_DrawStreamed-BitmapEx()`.

Prototype of hook function

```
void * Hook(GUI_BITMAPSTREAM_PARAM * pParam);
```

Parameters

Parameter	Description
pParam	Pointer to a `GUI_BITMAPSTREAM_PARAM` structure

Example

```
static void * _cbStreamedBitmapHook(GUI_BITMAPSTREAM_PARAM * pParam) {
  void * p = NULL;
  int    i, NumColors;
  U32    Color;
  U32  * pColor;
  switch (pParam->Cmd) {
  case GUI_BITMAPSTREAM_GET_BUFFER:
    //
    // Allocate buffer for palette data
    //
    p = malloc(pParam->v);
    break;
  case GUI_BITMAPSTREAM_RELEASE_BUFFER:
    //
    // Release buffer
    //
    free(pParam->p);
    break;
  case GUI_BITMAPSTREAM_MODIFY_PALETTE:
    //
    // Do something with the palette...
    //
    NumColors = pParam->v;
    pColor    = (U32 *)pParam->p;
    Color     = *(pColor + pParam->v - 1);
    for (i = NumColors - 2; i >= 0; i--) {
      *(pColor + i + 1) = *(pColor + i);
    }
    *pColor = Color;
    break;
  }
  return p;
}
```

 © 2020 SEGGER Microcontroller GmbH

9.1.6 Drawing lines

The most frequently used drawing routines are those that draw a line from one point to another.

 © 2020 SEGGER Microcontroller GmbH

9.1.6.1 GUI_DrawHLine()

Description

Draws a horizontal line one pixel thick from a specified starting point to a specified endpoint in the current window.

Prototype

```
void GUI_DrawHLine(int y0,
                   int x0,
                   int x1);
```

Parameters

Parameter	Description
y	Y-position.
x0	X-starting position.
x1	X-end position.

Additional information

If x1 < x0, nothing will be displayed.
With most LCD controllers, this routine is executed very quickly because multiple pixels can be set at once and no calculations are needed. If it is clear that horizontal lines are to be drawn, this routine executes faster than the GUI_DrawLine() routine.

 © 2020 SEGGER Microcontroller GmbH

9.1.6.2 GUI_DrawLine()

Description

Draws a line from a specified starting point to a specified endpoint in the current window (absolute coordinates).

Prototype

```
void GUI_DrawLine(int x0,
                  int y0,
                  int x1,
                  int y1);
```

Parameters

Parameter	Description
x0	X-starting position.
y0	Y-starting position.
x1	X-end position.
y1	Y-end position.

Additional information

If part of the line is not visible because it is not in the current window or because part of the current window is not visible, this is due to clipping.

 © 2020 SEGGER Microcontroller GmbH

9.1.6.3 GUI_DrawLineRel()

Description

Draws a line from the current (x, y) position to an endpoint specified by X-distance and Y-distance in the current window (relative coordinates).

Prototype

```
void GUI_DrawLineRel(int dx,
                     int dy);
```

Parameters

Parameter	Description
dx	Distance in X-direction to end of line to draw.
dy	Distance in Y-direction to end of line to draw.

 © 2020 SEGGER Microcontroller GmbH

9.1.6.4 GUI_DrawLineTo()

Description

Draws a line from the current (X,Y) position to an endpoint specified by X- and Y-coordinates in the current window.

Prototype

```
void GUI_DrawLineTo(int x,
                    int y);
```

Parameters

Parameter	Description
x	X-end position.
y	Y-end position.

 © 2020 SEGGER Microcontroller GmbH

9.1.6.5 GUI_DrawPolyLine()

Description

Connects a predefined list of points with lines in the current window.

Prototype

```
void GUI_DrawPolyLine(const GUI_POINT * pPoints,
                      int         NumPoints,
                      int         x0,
                      int         y0);
```

Parameters

Parameter	Description
pPoint	Pointer to the polyline to display.
NumPoints	Number of points specified in the list of points.
x	X-position of origin.
y	Y-position of origin.

Additional information

The starting point and endpoint of the polyline do not need to be identical.

 © 2020 SEGGER Microcontroller GmbH

9.1.6.6 GUI_DrawVLine()

Description

Draws a vertical line one pixel thick from a specified starting point to a specified endpoint in the current window.

Prototype

```
void GUI_DrawVLine(int x0,
                   int y0,
                   int y1);
```

Parameters

Parameter	Description
x0	X-position.
y0	Y-starting position.
y1	Y-end position.

Additional information

If y1 < y0, nothing will be displayed. With most LCD controllers, this routine is executed very quickly because multiple pixels can be set at once and no calculations are needed. If it is clear that vertical lines are to be drawn, this routine executes faster than the GUI_DrawLine() routine.

 © 2020 SEGGER Microcontroller GmbH

9.1.6.7 GUI_GetLineStyle()

Description

Returns the current line style used by the function `GUI_DrawLine`.

Prototype

```
U8 GUI_GetLineStyle(void);
```

Return value

Current line style used by the function `GUI_DrawLine`.

 © 2020 SEGGER Microcontroller GmbH

9.1.6.8 GUI_MoveRel()

Description

Moves the current line pointer relative to its current position.

Prototype

```
void GUI_MoveRel(int dx,
                 int dy);
```

Parameters

Parameter	Description
dx	Distance to move in X.
dy	Distance to move in Y.

Related topics

- *GUI_DrawLineTo* on page 314
- *GUI_MoveTo* on page 319

 © 2020 SEGGER Microcontroller GmbH

9.1.6.9 GUI_MoveTo()

Description

Moves the current line pointer to the given position.

Prototype

```
void GUI_MoveTo(int x,
                int y);
```

Parameters

Parameter	Description
x	New position in X.
y	New position in Y.

 © 2020 SEGGER Microcontroller GmbH

9.1.6.10 GUI_SetLineStyle()

Description

Sets the current line style used by the function `GUI_DrawLine()`.

Prototype

```
U8 GUI_SetLineStyle(U8 LineStyle);
```

Parameters

Parameter	Description
`LineStyle`	New line style to be used. A full list of available values can be found under *Line styles* on page 384.

Return value

Previous line style used by the function `GUI_DrawLine()`.

Additional information

This function sets only the line style used by `GUI_DrawLine()`. The style will be used only with a pen size of 1.

 © 2020 SEGGER Microcontroller GmbH

9.1.7 Drawing polygons

The polygon drawing routines can be helpful when drawing vectorized symbols.

9.1.7.1 GUI_DrawPolygon()

Description

Draws the outline of a polygon defined by a list of points in the current window.

Prototype

```
void GUI_DrawPolygon(const GUI_POINT * pPoints,
                     int               NumPoints,
                     int               x0,
                     int               y0);
```

Parameters

Parameter	Description
pPoint	Pointer to the polygon to display.
NumPoints	Number of points specified in the list of points.
x	X-position of origin.
y	Y-position of origin.

Additional information

The polyline drawn is automatically closed by connecting the endpoint to the starting point.

 © 2020 SEGGER Microcontroller GmbH

9.1.7.2 GUI_EnlargePolygon()

Description

Enlarges a polygon on all sides by a specified length in pixels.

Prototype

```
void GUI_EnlargePolygon(      GUI_POINT * pDest,
                        const GUI_POINT * pSrc,
                              int         NumPoints,
                              int         Len);
```

Parameters

Parameter	Description
pDest	Pointer to the destination polygon.
pSrc	Pointer to the source polygon.
NumPoints	Number of points specified in the list of points.
Len	Length (in pixels) by which to enlarge the polygon.

Additional information

Make sure the destination array of points is equal to or larger than the source array.

Example

```
const GUI_POINT aPoints[] = {
  { 40, 20},
  {  0, 20},
  { 20,  0}
};
GUI_POINT aEnlargedPoints[GUI_COUNTOF(aPoints)];
void Sample(void) {
  int i;
  GUI_Clear();
  GUI_SetDrawMode(GUI_DM_XOR);
  GUI_FillPolygon(aPoints, GUI_COUNTOF(aPoints), 140, 110);
  for (i = 1; i < 10; i++) {
    GUI_EnlargePolygon(aEnlargedPoints, aPoints, GUI_COUNTOF(aPoints), i * 5);
    GUI_FillPolygon(aEnlargedPoints, GUI_COUNTOF(aPoints), 140, 110);
  }
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.7.3 GUI_FillPolygon()

Description

Draws a filled polygon defined by a list of points in the current window.

Prototype

```
void GUI_FillPolygon(const GUI_POINT * pPoints,
                     int         NumPoints,
                     int         x0,
                     int         y0);
```

Parameters

Parameter	Description
pPoint	Pointer to the destination polygon.
NumPoints	Number of points specified in the list of points.
x	X-position of origin.
y	Y-position of origin.

Additional information

The polyline drawn is automatically closed by connecting the endpoint to the starting point. It is not required that the endpoint touches the outline of the polygon.
Rendering a polygon is done by drawing one or more horizontal lines for each y-position of the polygon. Per default the maximum number of points used to draw the horizontal lines for one y-position is 12 (which means 6 lines per y-position). If this value needs to be increased, the macro GUI_FP_MAXCOUNT can be used to set the maximum number of points.

Example

```
#define GUI_FP_MAXCOUNT 50
```

 © 2020 SEGGER Microcontroller GmbH

9.1.7.4 GUI_MagnifyPolygon()

Description

Magnifies a polygon by a specified factor.

Prototype

```
void GUI_MagnifyPolygon(      GUI_POINT * pDest,
                        const GUI_POINT * pSrc,
                              int         NumPoints,
                              int         Mag);
```

Parameters

Parameter	Description
pDest	Pointer to the destination polygon.
pSrc	Pointer to the source polygon.
NumPoints	Number of points specified in the list of points.
Mag	Factor used to magnify the polygon.

Additional information

Make sure the destination array of points is equal to or larger than the source array. Note the difference between enlarging and magnifying a polygon. Calling the function GUI_EnlargePolygon() with the parameter Len = 1 will enlarge the polygon by one pixel on all sides, whereas the call of GUI_MagnifyPolygon() with the parameter Mag = 1 will have no effect.

Example

```
const GUI_POINT aPoints[] = {
  {  0, 20},
  { 40, 20},
  { 20,  0}
};
GUI_POINT aMagnifiedPoints[GUI_COUNTOF(aPoints)];
void Sample(void) {
  int Mag, y = 0, Count = 4;
  GUI_Clear();
  GUI_SetColor(GUI_GREEN);
  for (Mag = 1; Mag <= 4; Mag *= 2, Count /= 2) {
    int i, x = 0;
    GUI_MagnifyPolygon(aMagnifiedPoints, aPoints, GUI_COUNTOF(aPoints), Mag);
    for (i = Count; i > 0; i--, x += 40 * Mag) {
      GUI_FillPolygon(aMagnifiedPoints, GUI_COUNTOF(aPoints), x, y);
    }
    y += 20 * Mag;
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.7.5 GUI_RotatePolygon()

Description

Rotates a polygon by a specified angle.

Prototype

```
void GUI_RotatePolygon(      GUI_POINT * pDest,
                       const GUI_POINT * pSrc,
                             int         NumPoints,
                             float       Angle);
```

Parameters

Parameter	Description
pDest	Pointer to the destination polygon.
pSrc	Pointer to the source polygon.
NumPoints	Number of points specified in the list of points.
Angle	Angle in radian used to rotate the polygon.

Additional information

Make sure the destination array of points is equal to or larger than the source array.

Example

The following example shows how to draw a polygon. It is available as 2DGL_DrawPolygon.c in the examples shipped with emWin.

```
#include "gui.h"
/*********************************************************************
*
*           The points of the arrow
*/
static const GUI_POINT aPointArrow[] = {
  {  0,  -5},
  {-40, -35},
  {-10, -25},
  {-10, -85},
  { 10, -85},
  { 10, -25},
  { 40, -35},
};
static GUI_POINT aPointRotate[GUI_COUNTOF(aPointArrow)];
/*********************************************************************
*
*               Draws a polygon
*/
static void DrawPolygon(void) {
  int r;
  int Cnt =0;
  GUI_SetBkColor(GUI_WHITE);
  GUI_Clear();
  GUI_SetFont(&GUI_Font8x16);
  GUI_SetColor(0x0);
  GUI_DispStringAt("Polygons of arbitrary shape ", 0, 0);
  GUI_DispStringAt("in any color", 120, 20);
  GUI_SetColor(GUI_BLUE);
  /* Rotate and draw polygon */
  r = 45.0 / (2.0 * 3.141592);
  GUI_RotatePolygon(&aPointRotate[0], &aPointArrow[0], GUI_COUNTOF(aPointArrow), r);
  GUI_FillPolygon (&aPointRotate[0],7,100,100);
}
```

 © 2020 SEGGER Microcontroller GmbH

```
/*********************************************************************
*
*                 main
*/
void main(void) {
  GUI_Init();
  DrawPolygon();
  while(1)
    GUI_Delay(100);
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.8 Drawing circles

9.1.8.1 GUI_DrawCircle()

Description

Draws the outline of a circle of specified dimensions, at a specified position in the current window.

Prototype

```
void GUI_DrawCircle(int x0,
                    int y0,
                    int r);
```

Parameters

Parameter	Description
x0	X-position of the center of the circle in pixels of the client window.
y0	Y-position of the center of the circle in pixels of the client window.
r	Radius of the circle (half the diameter). Must be a positive value.

Example

```
for (i = 10; i < 50; i += 3) {
  GUI_DrawCircle(120, 60, i);
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.8.2 GUI_FillCircle()

Description

Draws a filled circle of specified dimensions at a specified position in the current window.

Prototype

```
void GUI_FillCircle(int x0,
                    int y0,
                    int r);
```

Parameters

Parameter	Description
x0	X-position of the center of the circle in pixels of the client window.
y0	Y-position of the center of the circle in pixels of the client window.
r	Radius of the circle (half the diameter). Must be a positive value.

Example

```
GUI_FillCircle(120,60,50);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.9 Drawing ellipses

9.1.9.1 GUI_DrawEllipse()

Description

Draws the outline of an ellipse of specified dimensions, at a specified position in the current window.

Prototype

```
void GUI_DrawEllipse(int x0,
                     int y0,
                     int rx,
                     int ry);
```

Parameters

Parameter	Description
x0	X-position of the center of the circle in pixels of the client window.
y0	Y-position of the center of the circle in pixels of the client window.
rx	X-radius of the ellipse (half the diameter). Must be a positive value.
ry	Y-radius of the ellipse (half the diameter). Must be a positive value.

Additional information

This routine is based on integer calculation. Too large ellipses cause overflows which lead to unexpected results. In that case `GUI_DrawEllipseXL()` should be used instead.

Example

See the *GUI_FillEllipse* on page 332 example.

 © 2020 SEGGER Microcontroller GmbH

9.1.9.2 GUI_DrawEllipseXL()

Description

Draws the outline of a large ellipse.

Prototype

```
void GUI_DrawEllipseXL(int x0,
                       int y0,
                       int rx,
                       int ry);
```

Parameters

Parameter	Description
x0	X-position of the center of the circle in pixels of the client window.
y0	Y-position of the center of the circle in pixels of the client window.
rx	X-radius of the ellipse (half the diameter). Must be a positive value.
ry	Y-radius of the ellipse (half the diameter). Must be a positive value.

 © 2020 SEGGER Microcontroller GmbH

9.1.9.3 GUI_FillEllipse()

Description

Draws a filled ellipse of specified dimensions at a specified position in the current window.

Prototype

```
void GUI_FillEllipse(int x0,
                     int y0,
                     int rx,
                     int ry);
```

Parameters

Parameter	Description
x0	X-position of the center of the circle in pixels of the client window.
y0	Y-position of the center of the circle in pixels of the client window.
rx	X-radius of the ellipse (half the diameter). Must be a positive value.
ry	Y-radius of the ellipse (half the diameter). Must be a positive value.

Example

```
// Demo ellipses
GUI_SetColor(0xff);
GUI_FillEllipse(100, 180, 50, 70);
GUI_SetColor(0x0);
GUI_DrawEllipse(100, 180, 50, 70);
GUI_SetColor(0x000000);
GUI_FillEllipse(100, 180, 10, 50);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.10 Drawing arcs

9.1.10.1 GUI_DrawArc()

Description

Draws an arc of specified dimensions at a specified position in the current window. An arc is a section of the outline of a circle.

Prototype

```
void GUI_DrawArc(int x0,
                 int y0,
                 int rx,
                 int ry,
                 int a0,
                 int a1);
```

Parameters

Parameter	Description
xCenter	Horizontal position of the center in pixels of the client window.
yCenter	Vertical position of the center in pixels of the client window.
rx	X-radius (pixels).
ry	Y-radius (pixels).
a0	Starting angle (degrees).
a1	Ending angle (degrees).

Limitations

Currently the ry parameter is not used. The rx parameter is used instead.

Example

```
void DrawArcScale(void) {
  int x0 = 160;
  int y0 = 180;
  int i;
  char ac[4];
  GUI_SetBkColor(GUI_WHITE);
  GUI_Clear();
  GUI_SetPenSize( 5 );
  GUI_SetTextMode(GUI_TM_TRANS);
  GUI_SetFont(&GUI_FontComic18B_ASCII);
  GUI_SetColor( GUI_BLACK );
  GUI_DrawArc( x0,y0,150, 150,-30, 210 );
  GUI_Delay(1000);
  for (i=0; i<= 23; i++) {
    float a = (-30+i*10)*3.1415926/180;
    int x = -141*cos(a)+x0;
    int y = -141*sin(a)+y0;
    if (i%2 == 0)
      GUI_SetPenSize( 5 );
    else
      GUI_SetPenSize( 4 );
    GUI_DrawPoint(x,y);
    if (i%2 == 0) {
      x = -123*cos(a)+x0;
      y = -130*sin(a)+y0;
      sprintf(ac, "%d", 10*i);
      GUI_SetTextAlign(GUI_TA_VCENTER);
```

 © 2020 SEGGER Microcontroller GmbH

```
      GUI_DispStringHCenterAt(ac,x,y);
    }
  }
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.11 Drawing graphs

9.1.11.1 GUI_DrawGraph()

Description

Draws a graph at once.

Prototype

```
void GUI_DrawGraph(I16 * pay,
                   int   NumPoints,
                   int   x0,
                   int   y0);
```

Parameters

Parameter	Description
paY	Pointer to an array containing the Y-values of the graph.
NumPoints	Number of Y-values to be displayed.
x0	Starting point in x.
y0	Starting point in y.

Additional information

The function first sets the line-cursor to the position specified with x0, y0 and the first Y-value of the given array. Then it starts drawing lines to x0 + 1, y0 + *(paY + 1), x0 + 2, y0 + *(paY + 2) and so on.

Example

```
#include "GUI.h"
#include <stdlib.h>
I16 aY[100];
void MainTask(void) {
  int i;
  GUI_Init();
  for (i = 0; i < GUI_COUNTOF(aY); i++) {
    aY[i] = rand() % 50;
  }
  GUI_DrawGraph(aY, GUI_COUNTOF(aY), 0, 0);
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.12 Drawing barcodes

9.1.12.1 GUI_BARCODE_Draw()

Description

Draws a barcode of the given type at the specified position.

Prototype

```
int GUI_BARCODE_Draw(      int    xPos,
                           int    yPos,
                           int    ModuleSize,
                           int    ySize,
                           int    Type,
                     const char * sBarcode);
```

Parameters

Parameter	Description
xPos	X-position to be used.
yPos	Y-position to be used.
ModuleSize	Size of one module, that means width of the smallest bar in pixels
ySize	Y-size of the barcode. Cannot be lower than three times the module size.
Type	Type of the barcode to be drawn. See full list of available values under *Barcode types* on page 381.
sBarcode	String containing the data to be used for the barcode. The ITF barcode can only display numbers.

Return value

0 on success
-1 on error.

Additional information

The data string for ITF barcodes should contain an even amount of numbers. If it does not, a leading zero will be added to the code automatically due to technical limitations.

> **Note**
>
> Barcodes can be drawn in any color. But please note that the contrast between bars and spaces has to be high enough so the code can be read successfully by a scanner. We recommend using the 'standard' colors barcodes consist of, which are white for the background (spaces) and black for the foreground (bars).

Examples

```
GUI_SetColor(GUI_BLACK);
GUI_SetBkColor(GUI_WHITE);
GUI_BARCODE_Draw(0, 0, 3, 60, GUI_BARCODE_ITF, "131072");
GUI_BARCODE_Draw(0, 0, 2, 60, GUI_BARCODE_128, "SEGGER");
```

 © 2020 SEGGER Microcontroller GmbH

Screenshots of above examples

GUI_BARCODE_ITF	GUI_BARCODE_128
	

 © 2020 SEGGER Microcontroller GmbH

9.1.12.2 GUI_BARCODE_GetXSize()

Description

Returns the X-size of a given barcode without drawing it.

Prototype

```
int GUI_BARCODE_GetXSize(      int    Type,
                               int    ModuleSize,
                         const char * sBarcode);
```

Parameters

Parameter	Description
Type	Type of the barcode to be drawn. See list below.
ModuleSize	Size of one module, that means width of the smallest bar in pixels.
sBarcode	String containing the data to be used for the barcode. The ITF barcode can only display numbers.

Return value

X-size of the barcode on success, -1 on error.

 © 2020 SEGGER Microcontroller GmbH

9.1.13 Drawing QR codes



It should be made sure of that the QR code is surrounded by a bright colored frame of at least the pixel size of one 'module'. Alternatively, `GUI_QR_CreateFramed()` may be called to draw a QR code with the white frame around it.

9.1.13.1 GUI_QR_Create()

Description

Creates an QR-code bitmap which can be drawn with `GUI_QR_Draw()`.

Prototype

```
GUI_HMEM GUI_QR_Create(const char * pText,
                       int    PixelSize,
                       int    EccLevel,
                       int    Version);
```

Parameters

Parameter	Description
`pText`	UTF-8 text to be used for the QR-code.
`PixelSize`	Size in pixels of one 'Module'.
`EccLevel`	Error correction level to be used. See full list of available values under *ECC levels for QR codes* on page 383.
`Version`	Desired size in modules of the QR-code. Ff set to 0 (recommended) the size will be calculated automatically. Must be between 1 and 40. If it is less than required for the given text with the given `EccLevel`, the function fails.

Return value

Valid handle on success, 0 on error.

Additional information

After the QR code is no longer used, it should be deleted with `GUI_QR_Delete()`.

 © 2020 SEGGER Microcontroller GmbH

9.1.13.2 GUI_QR_CreateFramed()

Description

Creates an QR-code bitmap which can be drawn with `GUI_QR_Draw()`. A white frame by the size of one module will be added.

Prototype

```
GUI_HMEM GUI_QR_CreateFramed(const char * pText,
                             int    PixelSize,
                             int    EccLevel,
                             int    Version);
```

Parameters

Parameter	Description
`pText`	UTF-8 text to be used for the QR-code.
`PixelSize`	Size in pixels of one 'Module'.
`EccLevel`	Error correction level to be used. See full list of available values under *ECC levels for QR codes* on page 383.
`Version`	Desired size in modules of the QR-code. If set to 0 (recommended) the size will be calculated automatically. Must be between 1 and 40. If it is less than required for the given text with the given `EccLevel`, the function fails.

Return value

Valid handle on success, 0 on error.

Additional information

After the QR code is no longer used, it should be deleted with `GUI_QR_Delete()`.

 © 2020 SEGGER Microcontroller GmbH

9.1.13.3 GUI_QR_Delete()

Description

Frees the memory used for the QR-code.

Prototype

```
void GUI_QR_Delete(GUI_HMEM hQR);
```

Parameters

Parameter	Description
hQR	Handle of the QR-code to be deleted.

Additional information

A QR-code should be removed if it is no longer used.

 © 2020 SEGGER Microcontroller GmbH

9.1.13.4 GUI_QR_Draw()

Description

Draws the given QR-code at the given pixel position.

Prototype

```
void GUI_QR_Draw(GUI_HMEM hQR,
                 int      xPos,
                 int      yPos);
```

Parameters

Parameter	Description
hQR	Handle of the QR-code to be drawn.
xPos	X-position to be used.
yPos	Y-position to be used.

 © 2020 SEGGER Microcontroller GmbH

9.1.13.5 GUI_QR_GetInfo()

Description

Returns a structure containing information about the given QR-code.

Prototype

```
void GUI_QR_GetInfo(GUI_HMEM      hQR,
                    GUI_QR_INFO * pInfo);
```

Parameters

Parameter	Description
hQR	Handle of the QR-code to be deleted.
pInfo	Pointer to a structure of type GUI_QR_INFO

 © 2020 SEGGER Microcontroller GmbH

9.1.14 Drawing pie charts

9.1.14.1 GUI_DrawPie()

Description

Draws a circle sector.

Prototype

```
void GUI_DrawPie(int x0,
                 int y0,
                 int r,
                 int a0,
                 int a1,
                 int Type);
```

Parameters

Parameter	Description
x0	X-position of the center of the circle in pixels of the client window.
y0	Y-position of the center of the circle in pixels of the client window.
r	Radius of the circle (half the diameter).
a0	Starting angle (degrees).
a1	End angle (degrees).
Type	(reserved for future use, should be 0)

Example

```
int i, a0, a1;
const unsigned aValues[]  = { 100, 135, 190, 240, 340, 360};
const GUI_COLOR aColors[] = { GUI_BLUE, GUI_GREEN,   GUI_RED,
                              GUI_CYAN, GUI_MAGENTA, GUI_YELLOW };
for (i = 0; i < GUI_COUNTOF(aValues); i++) {
  a0 = (i == 0) ? 0 : aValues[i - 1];
  a1 = aValues[i];
  GUI_SetColor(aColors[i]);
  GUI_DrawPie(100, 100, 50, a0, a1, 0);
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

9.1.15 Drawing splines



9.1.15.1 GUI_SPLINE_Create()

Description

This function creates a spline handle with the given parameters.

Prototype

```
GUI_HMEM GUI_SPLINE_Create(const int      * px,
                           const int      * py,
                                 unsigned   NumPoints);
```

Parameters

Parameter	Description
px	Pointer to an array of values for x coordinates.
py	Pointer to an array of values for y coordinates.
NumPoints	Number of points to be used.

Return value

A handle of a spline. If zero, creation failed.

Additional information

The amount of points for x and y coordinates have to be the same. Please note that the values for the x coordinates have to be in a increasing order. It is not possible to create a spline where `px[0] > px[1]`.

 © 2020 SEGGER Microcontroller GmbH

9.1.15.2 GUI_SPLINE_Delete()

Description

This function deletes the memory allocated for a spline while it was created.

Prototype

```
void GUI_SPLINE_Delete(GUI_HMEM hSpline);
```

Parameters

Parameter	Description
hSpline	Handle of the spline to be deleted.

 © 2020 SEGGER Microcontroller GmbH

9.1.15.3 GUI_SPLINE_Draw()

Description

This function draws a spline created with `GUI_SPLINE_Create()` at the given position.

Prototype

```
void GUI_SPLINE_Draw(GUI_HMEM hSpline,
                     int      x,
                     int      y);
```

Parameters

Parameter	Description
hSpline	Handle of a spline.
x	Position in x.
y	Position in y.

 © 2020 SEGGER Microcontroller GmbH

9.1.15.4 GUI_SPLINE_DrawAA()

Description

This function draws a spline created with `GUI_SPLINE_Create()` at the given position using anti aliasing.

Prototype

```
void GUI_SPLINE_DrawAA(GUI_HMEM hSpline,
                       int      x,
                       int      y,
                       unsigned Width);
```

Parameters

Parameter	Description
`hSpline`	Handle of a spline.
`x`	Position in `x`.
`y`	Position in `y`.
`Width`	`Width` of the spline to be drawn.

Additional information

The color which is used to mix the anti aliased pixels with can be set using `GUI_SetBkColor()`. This only makes sense on a solid colored background. If the background consists of multiple colors the draw mode should be set to transparent by a call of `GUI_SetDrawMode(GUI_TM_TRANS)`.

 © 2020 SEGGER Microcontroller GmbH

9.1.15.5 GUI_SPLINE_GetY()

Description

This function returns the y coordinate corresponding to the given Index.

Prototype

```
I16 GUI_SPLINE_GetY(GUI_HMEM   hSpline,
                    unsigned   Index,
                    float    * py);
```

Parameters

Parameter	Description
hSpline	Handle of a spline.
Index	Position in x.
py	Outpointer to store the y value as floating value (can be NULL).

Return value

The y value corresponding to the given index value.

Additional information

IT is possible to use either the return value or if a higher precision is required the value stored in the third parameter. If the return value of this function is sufficient in regards of precision the last parameter can be NULL.

 © 2020 SEGGER Microcontroller GmbH

9.1.15.6 GUI_SPLINE_GetXSize()

Description

This function returns the X-size required for the spline to be drawn.

Prototype

```
unsigned GUI_SPLINE_GetXSize(GUI_HMEM hSpline);
```

Parameters

Parameter	Description
hSpline	Handle of a spline.

Return value

X-size in pixel required to draw the complete spline.

 © 2020 SEGGER Microcontroller GmbH

9.1.16 Saving and restoring the GUI context

9.1.16.1 GUI_RestoreContext()

Description

The function restores the GUI-context.

Prototype

```
void GUI_RestoreContext(const GUI_CONTEXT * pContext);
```

Parameters

Parameter	Description
pContext	Pointer to a GUI_CONTEXT structure containing the new context.

Additional information

The GUI-context contains the current state of the GUI like the text cursor position, a pointer to the current font and so on. Sometimes it can be useful to save the current state to restore it later. For this you can use these functions.

 © 2020 SEGGER Microcontroller GmbH

9.1.16.2 GUI_SaveContext()

Description

The function saves the current GUI-context.

Prototype

```
void GUI_SaveContext(GUI_CONTEXT * pContext);
```

Parameters

Parameter	Description
pContext	Pointer to a GUI_CONTEXT structure for saving the current context.

Additional information

See also the function GUI_RestoreContext().

 © 2020 SEGGER Microcontroller GmbH

9.1.17 Info about screen changes

9.1.17.1 GUI_DIRTYDEVICE_Create()

Description

A DITRTYDEVICE is an object which makes it possible to monitor the changed area of the screen. In combination with `GUI_DIRTYDEVICE_Fetch()` it makes it possible, to check if the content of the screen has been changed. If changes have been detected the function `GUI_DIRTYDEVICE_Fetch()` returns 1 and fills up an information structure with size and position of the changed area. If nothing has been changed `GUI_DIRTYDEVICE_Fetch()` returns 0.

In case of working with multiple layers the function does not monitor all layers simultaneously. For each layer a separate DIRTYDEVICE needs to be created (if monitoring is required).

Calling `GUI_DIRTYDEVICE_Create()` creates such an monitoring object in the currently selected layer which then automatically monitors all screen drawing operations. If no longer used it can be deleted with `GUI_DIRTYDEVICE_Delete()`.

Prototype

```
int GUI_DIRTYDEVICE_Create(void);
```

Return value

0	on success
1	on error.

Additional information

A DIRTYDEVICE is also able to return advanced information like a pointer to the first changed pixel, the number of bytes used per pixel and the stride value in pixels from one line of data to the next line. To be able to use those features, a linear addressable driver is required. Further, the DIRTYDEVICE needs to be created in `LCD_X_Config()` immediately after the driver of the layer was created.

 © 2020 SEGGER Microcontroller GmbH

9.1.17.2 GUI_DIRTYDEVICE_CreateEx()

Description

Creates a DIRTYDEVICE in the given layer. For details please refer to the function `GUI_DIRTYDEVICE_Create()`.

Prototype

```
int GUI_DIRTYDEVICE_CreateEx(int LayerIndex);
```

Parameters

Parameter	Description
`LayerIndex`	`LayerIndex` to be used.

Return value

0	on success
1	on error.

 © 2020 SEGGER Microcontroller GmbH

9.1.17.3 GUI_DIRTYDEVICE_Delete()

Description

Removes the DIRTYDEVICE of the currently selected layer. If not possible the function returns an error.

Prototype

```
int GUI_DIRTYDEVICE_Delete(void);
```

Return value

0	on success
1	on error.

 © 2020 SEGGER Microcontroller GmbH

9.1.17.4 GUI_DIRTYDEVICE_DeleteEx()

Description

Removes the DIRTYDEVICE of the given layer. If not possible the function returns an error.

Prototype

```
int GUI_DIRTYDEVICE_DeleteEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	LayerIndex to be used.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

9.1.17.5 GUI_DIRTYDEVICE_Fetch()

Description

The function fills the given structure with the coordinates and the size of the changed screenarea of the current layer. If no changes have been detected since the last call the function returns 0.

Prototype

```
int GUI_DIRTYDEVICE_Fetch(GUI_DIRTYDEVICE_INFO * pInfo);
```

Parameters

Parameter	Description
pInfo	Pointer to the GUI_DIRTYDEVICE_INFO-structure which is filled with size and coordinates of the changed area.

Return value

0 if no changes have been detected
1 if changes are detected.

 © 2020 SEGGER Microcontroller GmbH

9.1.17.6 GUI_DIRTYDEVICE_FetchEx()

Description

The function fills the given structure with the coordinates and the size of the changed screenarea of the given layer.

Prototype

```
int GUI_DIRTYDEVICE_FetchEx(GUI_DIRTYDEVICE_INFO * pInfo,
                            int                    LayerIndex);
```

Parameters

Parameter	Description
pInfo	Pointer to the GUI_DIRTYDEVICE_INFO-structure which is filled with size and coordinates of the changed area.
LayerIndex	Layer index to be used.

Elements of structure GUI_DIRTYDEVICE_INFO

Refer to *GUI_DIRTYDEVICE_Fetch* on page 357 for the elements of the structure GUI_DIRTYDEVICE_INFO.

Return value

0 if no changes have been detected
1 if changes are detected.

 © 2020 SEGGER Microcontroller GmbH

9.1.18 YUV device

9.1.18.1 GUI_YUV_Create()

Description

Creates a YUV device in the current layer. For details please refer to `GUI_YUV_CreateEx()`.

Prototype

```
int GUI_YUV_Create(void);
```

Return value

= 0	if successful.
≠ 0	if the creation fails.

 © 2020 SEGGER Microcontroller GmbH

9.1.18.2 GUI_YUV_CreateEx()

Description

Creates a YUV device in the given layer with the given period. It allocates an additional buffer for a YUV plane for the complete given layer. Memory requirement is 2 bytes per pixel. Please note that YUV devices are supported only for display drivers with direct interface like GUIDRV_Lin. In the given period it (re)calculates the 'dirty' framebuffer area from RGB data into YUV data.

Prototype

```
int GUI_YUV_CreateEx(int      LayerIndex,
                     unsigned Period);
```

Parameters

Parameter	Description
LayerIndex	The layer to be used.
Period	The period in ms to be used.

Return value

= 0 if successful.
≠ 0 if the creation fails.

Additional information

Please note that the calculation from RGB to YUV requires a lot of CPU load.

 © 2020 SEGGER Microcontroller GmbH

9.1.18.3 GUI_YUV_Delete()

Description

Deletes the YUV device of the current layer.

Prototype

```
int GUI_YUV_Delete(void);
```

Return value

= 0	if successful.
≠ 0	on error.

 © 2020 SEGGER Microcontroller GmbH

9.1.18.4 GUI_YUV_DeleteEx()

Description

Deletes the YUV device of the given layer.

Prototype

```
int GUI_YUV_DeleteEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	The layer to be used.

Return value

= 0 if successful.
≠ 0 on error.

 © 2020 SEGGER Microcontroller GmbH

9.1.18.5 GUI_YUV_GetpData()

Description

Returns a pointer to the YUV plane of the current layer and the size of the plane in bytes.

Prototype

```
U32 *GUI_YUV_GetpData(U32 * pSize);
```

Parameters

Parameter	Description
pSize	Pointer to a U32 value for returning the plane size.

Return value

Pointer to the YUV plane.

 © 2020 SEGGER Microcontroller GmbH

9.1.18.6 GUI_YUV_GetpDataEx()

Description

Returns a pointer to the YUV plane of the given layer and the size of the plane in bytes.

Prototype

```
U32 *GUI_YUV_GetpDataEx(int   LayerIndex,
                        U32 * pSize);
```

Parameters

Parameter	Description
LayerIndex	The layer to be used.
pSize	Pointer to a U32 value for returning the plane size.

Return value

Pointer to the YUV plane.

 © 2020 SEGGER Microcontroller GmbH

9.1.18.7 GUI_YUV_InvalidateArea()

Description

Invalidates the given area of the current layer. During the next interval that area will be (re)calculated.

Prototype

```
void GUI_YUV_InvalidateArea(int x,
                            int y,
                            int xSize,
                            int ySize);
```

Parameters

Parameter	Description
x	X-position in pixels.
y	Y-position in pixels.
xSize	Y-size in pixels.
xSize	Y-size in pixels.

 © 2020 SEGGER Microcontroller GmbH

9.1.18.8 GUI_YUV_SetPeriod()

Description

Sets the recalculation period of the YUV device in the current layer.

Prototype

```
int GUI_YUV_SetPeriod(unsigned Period);
```

Parameters

Parameter	Description
Period	The period in ms to be used

Return value

= 0 if successful.
≠ 0 on error.

 © 2020 SEGGER Microcontroller GmbH

9.1.18.9 GUI_YUV_SetPeriodEx()

Description

Sets the period to be used for (re)calculation.

Prototype

```
int GUI_YUV_SetPeriodEx(int      LayerIndex,
                        unsigned Period);
```

Parameters

Parameter	Description
LayerIndex	The layer to be used
Period	The period in ms to be used

Return value

= 0 if successful.
≠ 0 on error.

 © 2020 SEGGER Microcontroller GmbH

9.1.19 Cache with color reducer

Using a cache with color reducer could make sense if the display controller does not support reading frame buffer data and/or a display driver cache uses too much RAM. If enabled all drawing operations are executed once within the cache and the given color conversion and once with the native display driver configured in `LCD_X_Config()`. To be able to use such a cache nothing needs to be configured or changed. Simply enable it with one of the following functions. After enabled only the colors of the given color conversion could be used.

9.1.19.1 GUI_GCACHE_4_Create()

Description

Enables a global display cache which works with 4bpp color depth for the current layer.

Prototype

```
int GUI_GCACHE_4_Create(const LCD_API_COLOR_CONV * pColorConvAPI);
```

Parameters

Parameter	Description
`pColorConvAPI`	Color conversion to be used.

Return value

0 on success
1 on error.

Additional information

Once enabled only the colors of the given color conversion can be used. Reading operations or XOR-operations then use the content of the cache.

 © 2020 SEGGER Microcontroller GmbH

9.1.19.2 GUI_GCACHE_4_CreateEx()

Description

Enables a global display cache which works with 4bpp color depth.

Prototype

```
int GUI_GCACHE_4_CreateEx(      int                   LayerIndex,
                          const LCD_API_COLOR_CONV * pColorConvAPI);
```

Parameters

Parameter	Description
LayerIndex	Layer index to be used.
pColorConvAPI	Color conversion to be used.

Return value

0 on success
1 on error.

Additional information

Once enabled only the colors of the given color conversion can be used. Reading operations or XOR-operations then use the content of the cache.

 © 2020 SEGGER Microcontroller GmbH

9.1.20 Setting hook functions

9.1.20.1 GUI_SetAfterInitHook()

Description

Sets an optional function to be called during the process of initialization. It may be used for example for putting a PID into operation after the GUI has been initialized.

Prototype

```
void GUI_SetAfterInitHook(void ( *pFunc)());
```

Parameters

Parameter	Description
pFunc	Pointer to a function called immediately before GUI_Init() returns.

Additional information

This function should be called before GUI_Init() is called.

 © 2020 SEGGER Microcontroller GmbH

9.1.20.2 GUI_SetControlHook()

Description

Under certain circumstances it could make sense to have a function which is called immediately before a display driver cache operation should be executed. It could be used for example if GUIDRV_Lin is used for managing the content of a layer and a custom function should be used for transferring it to the display.

Prototype

```
void GUI_SetControlHook(void ( *pFunc)(int LayerIndex , int Cmd ));
```

Parameters

Parameter	Description
pFunc	Callback function to be called before a driver cache operation should be executed.

Additional information

That function is called independently of the existence of a cache in the driver.

 © 2020 SEGGER Microcontroller GmbH

9.1.20.3 GUI_SetRefreshHook()

Description

Sets a callback function which waits until the vertical non display period has been reached before updating the screen. Tearing effects could occur if the content of the frame buffer changes during the display controller is not in the vertical non display period and currently updating the screen. A detailed description of tearing effects can be found in the chapter *Multiple Buffering* on page 2372. If tearing effects should not occur and the following assumptions are fulfilled that function can be used to avoid those effects:

- Display uses an indirect interface
- Display provides a tearing signal (TE)
- Display communication is fast enough for updating the frame buffer within the vertical non display period. The function sets a callback function which is called immediately before sending any content to the display controller. That gives the application the chance to wait until the display controller is within the vertical non display period. That can be achieved by polling the TE-pin of the display (if available). The function should return immediately after reaching the non display period. After that the driver sends its (dirty) content to the display controller.

Prototype

```
void GUI_SetRefreshHook(void ( *pFunc)());
```

Parameters

Parameter	Description
pFunc	Callback function to be called before a driver cache operation should be executed.

Additional information

When using this function it is important to avoid writing to the display controller for each drawing operation. This can be achieved by the cache locking mechanism. Details can be found in the section *Cache group* on page 2817.

 © 2020 SEGGER Microcontroller GmbH

9.1.21 Data structures

9.1.21.1 GUI_ALPHA_STATE

Description

Used for storing the alpha value with `GUI_SetUserAlpha()`.

Type definition

```
typedef struct {
  U32  UserAlpha;
} GUI_ALPHA_STATE;
```

Structure members

Member	Description
`UserAlpha`	Alpha value to be used.

See also

- `GUI_SetUserAlpha()`

 © 2020 SEGGER Microcontroller GmbH

9.1.21.2 GUI_BITMAPSTREAM_INFO

Description

Information about a streamed bitmap.

Type definition

```
typedef struct {
  int  XSize;
  int  YSize;
  int  BitsPerPixel;
  int  NumColors;
  int  HasTrans;
} GUI_BITMAPSTREAM_INFO;
```

Structure members

Member	Description
XSize	Pixel size in X of the image.
YSize	Pixel size in Y of the image.
BitsPerPixel	Number of bits per pixel.
NumColors	Number of colors in case of an index based image.
HasTrans	In case of an index based image 1 if transparency exist, 0 if not.

See also

- GUI_GetStreamedBitmapInfo()
- GUI_GetStreamedBitmapInfoEx()

 © 2020 SEGGER Microcontroller GmbH

9.1.21.3 GUI_BITMAPSTREAM_PARAM

Description

Contains a command to be used by a set hook function for `GUI_DrawStreamedBitmapEx()`.

Type definition

```
typedef struct {
  int    Cmd;
  U32    v;
  void * p;
} GUI_BITMAPSTREAM_PARAM;
```

Structure members

Member	Description
Cmd	Command to be executed.
v	Depends on the command to be executed.
p	Depends on the command to be executed.

Supported values for member Cmd	
GUI_BITMAPSTREAM_GET_BUFFER	When receiving this command the application can spend a buffer for the palette of a bitmap stream. Parameters: p - Pointer to the buffer or NULL v - Requested buffer size
GUI_BITMAPSTREAM_RELEASE_BUFFER	If the application has spend a buffer for the palette here the buffer should be released. Parameters: p - Pointer to buffer to be released v - not used
GUI_BITMAPSTREAM_MODIFY_PALETTE	This command is sent after loading the palette and before drawing the image to be able to modify the palette of the streamed image. Parameters: p - Pointer to palette data v - Number of colors in palette

See also

- `GUI_SetStreamedBitmapHook()`

 © 2020 SEGGER Microcontroller GmbH

9.1.21.4 GUI_DIRTYDEVICE_INFO

Description

Information about the dirty device.

Type definition

```
typedef struct {
  void * pData;
  int    x0;
  int    y0;
  int    xSize;
  int    ySize;
  int    LineOff;
  int    BytesPerPixel;
  int    IsDirty;
} GUI_DIRTYDEVICE_INFO;
```

Structure members

Member	Description
pData	Pointer to the first changed pixel.*1
x0	Leftmost position of changed area.
y0	Topmost position of changed area.
xSize	Size in X of changed area.
ySize	Size in Y of changed area.
LineOff	Number of pixels (stride) from one line to the next line.*1
BytesPerPixel	Number of bytes required per pixel.
IsDirty	Indicates if dirty pixels exist.

See also

- GUI_DIRTYDEVICE_Fetch()

> **Note**
>
> *1 Only available if the DIRTYDEVICE is created before the driver has been created.

 © 2020 SEGGER Microcontroller GmbH

9.1.21.5 GUI_GRADIENT_INFO

Description

Information used for drawing multi-color gradients.

Type definition

```
typedef struct {
  U16        Pos;
  GUI_COLOR  Color;
} GUI_GRADIENT_INFO;
```

Structure members

Member	Description
Pos	Start position of color. The next entry is the end position. The last entry also defines the x1 / y1 position of the gradient, either if it's a horizontal or vertical gradient.
Color	Color to be used.

Additional information

The member Pos is used to define the start and end position of the colors. It defines also the size of the gradient.

See also

- GUI_DrawGradientMH()
- GUI_DrawGradientMV()
- GUI_DrawGradientMHEx()
- GUI_DrawGradientMVEx()

 © 2020 SEGGER Microcontroller GmbH

9.1.21.6 GUI_POINT

Description

Implementation of a point on the screen.

Type definition

```
typedef struct {
  I16P x;
  I16P y;
} GUI_POINT;
```

Structure members

Member	Description
x	X-position of the point.
y	Y-position of the point.

 © 2020 SEGGER Microcontroller GmbH

9.1.21.7 GUI_QR_INFO

Description

Information about a QR code.

Type definition

```
typedef struct {
  int  Version;
  int  Width;
  int  Size;
} GUI_QR_INFO;
```

Structure members

Member	Description
Version	Version according to QR code documentation.
Width	Number of 'Modules'.
Size	Size of bitmap in pixels.

See also

- GUI_QR_GetInfo()

 © 2020 SEGGER Microcontroller GmbH

9.1.21.8 GUI_RECT

Description

Implementation of a rectangle on the screen.

Type definition

```
typedef struct {
  I16 x0;
  I16 y0;
  I16 x1;
  I16 y1;
} GUI_RECT;
```

Structure members

Member	Description
x0	X-position of top left point of the rectangle.
y0	Y-position of top left point of the rectangle.
x1	X-position of bottom right point of the rectangle.
y1	Y-position of bottom right point of the rectangle.

 © 2020 SEGGER Microcontroller GmbH

9.1.22 Defines

9.1.22.1 Barcode types

Description

Type of barcode to be drawn.

Definition

```
#define GUI_BARCODE_ITF    0
#define GUI_BARCODE_128    1
```

Symbols

Definition	Description
GUI_BARCODE_ITF	**Interleaved 2 of 5 (ITF)** which can display an even amount of digits.
GUI_BARCODE_128	**Code128** which can display all 128 ASCII characters.

 © 2020 SEGGER Microcontroller GmbH

9.1.22.2 Drawing modes

Description

These flags define the mode to be used for drawing operations.

Definition

```
#define GUI_DM_NORMAL    (0)
#define GUI_DM_XOR       (1 << 0)
#define GUI_DM_TRANS     (1 << 1)
#define GUI_DM_REV       (1 << 2)
```

Symbols

Definition	Description
GUI_DM_NORMAL	Default: The content of the display is overdrawn by the graphic.
GUI_DM_XOR	The content of the display is inverted when it is over-drawn. Restrictions are listed below.
GUI_DM_TRANS	When drawing shapes with a background and fore-ground color the background color will be transparent.
GUI_DM_REV	Swaps background and foreground color.

Restrictions

- XOR mode is useful only when using two displayed colors inside the active window or screen.
- Functions which make use of the pen size might not work properly if the drawing mode is XOR and the pen size is unequal to 1. So before using one of those functions either the drawing mode should be set to NORMAL or the pen size should be set to 1. The functions which regard the pen size are listed in the description of *GUI_SetPenSize* on page 259.
- When drawing bitmaps with a color depth greater than 1 bit per pixel (bpp) this drawing mode takes no effect.
- When using drawing functions such as GUI_DrawPolyLine() or multiple calls of GUI_DrawLineTo(), the fulcrums are inverted twice. The result is that these pixels remain in the background color.

 © 2020 SEGGER Microcontroller GmbH

9.1.22.3 ECC levels for QR codes

Description

Error correction level to be used by the Reed-Solomon error correction for a QR code.

Definition

```
#define GUI_QR_ECLEVEL_L    0
#define GUI_QR_ECLEVEL_M    1
#define GUI_QR_ECLEVEL_Q    2
#define GUI_QR_ECLEVEL_H    3
```

Symbols

Definition	Description
GUI_QR_ECLEVEL_L	About 7% or less errors can be corrected.
GUI_QR_ECLEVEL_M	About 15% or less errors can be corrected.
GUI_QR_ECLEVEL_Q	About 25% or less errors can be corrected.
GUI_QR_ECLEVEL_H	About 30% or less errors can be corrected.

 © 2020 SEGGER Microcontroller GmbH

9.1.22.4 Line styles

Description

Style how a line is drawn.

Definition

```
#define GUI_LS_SOLID         (0)
#define GUI_LS_DASH          (1)
#define GUI_LS_DOT           (2)
#define GUI_LS_DASHDOT       (3)
#define GUI_LS_DASHDOTDOT    (4)
```

Symbols

Definition	Description
GUI_LS_SOLID	Lines are drawn solid (default).
GUI_LS_DASH	Lines are drawn dashed.
GUI_LS_DOT	Lines are drawn dotted.
GUI_LS_DASHDOT	Lines are drawn alternating with dashes and dots.
GUI_LS_DASHDOTDOT	Lines are drawn alternating with dashes and double dots.

 © 2020 SEGGER Microcontroller GmbH

Chapter 10

Displaying bitmap files

The recommended and most efficient way to display a bitmap known at compile time is to use the Bitmap Converter to convert it into a C file and add it to the project / make-file. Details about the Bitmap Converter can be found in the chapter *Bitmap Converter* on page 438.
If the application needs to display images not known at compile time, the image needs to be available in a graphic file format supported by emWin. In this case, the image file can reside in memory or on an other storage device; it can be displayed even if the amount of available memory is less than the size of the image file. emWin currently supports BMP-, JPEG- and GIF-files. PNG-file support can be achieved by adding the PNG-library available on our website which comes with its own BSD style license. More details about PNG support can be found under *PNG file support* on page 429.

 © 2020 SEGGER Microcontroller GmbH

10.1 BMP file support

Although bitmaps which can be used with emWin are normally compiled and linked as C files with the application, there may be situations when using these types of structures is not desirable. A typical example would be an application that continuously references new images, such as bitmaps downloaded by the user. The following functions support `bmp` files which have been loaded into memory.
For images that you plan to re-use (e.g. a company logo) it is much more efficient to compile and link it as C file which can be used directly by emWin. This may be easily done with the Bitmap Converter.

10.1.1 Supported formats

The BMP file format has been defined by Microsoft. emWin supports the BMP file format version 3. That contains a couple of different image formats shown in the table below:

Bits per pixel	Indexed	Compression	Supported
1	yes	no	yes
4	yes	no	yes
4	yes	yes	yes
8	yes	no	yes
8	yes	yes	yes
16	no	no	yes
24	no	no	yes
32	no	no	yes

10.1.2 BMP API

The table below lists the available BMP file related routines in alphabetical order. Detailed function descriptions follow:

Routine	Description
`GUI_BMP_Draw()`	Draws a BMP file which has been loaded into memory.
`GUI_BMP_DrawEx()`	Draws a BMP file which does not need to be loaded into memory.
`GUI_BMP_DrawScaled()`	Draws a BMP file with scaling which has been loaded into memory.
`GUI_BMP_DrawScaledEx()`	Draws a BMP file with scaling which does not need to be loaded into memory.
`GUI_BMP_EnableAlpha()`	Enables alpha channel for 32bpp V3 BMP files.
`GUI_BMP_GetXSize()`	Returns the X-size of a BMP file loaded into memory.
`GUI_BMP_GetXSizeEx()`	Returns the X-size of a BMP file which does not need to be loaded into memory.
`GUI_BMP_GetYSize()`	Returns the Y-size of a bitmap loaded into memory.
`GUI_BMP_GetYSizeEx()`	Returns the Y-size of a BMP file which does not need to be loaded into memory.
`GUI_BMP_Serialize()`	Creates a BMP file.
`GUI_BMP_SerializeEx()`	Creates a BMP file from the given rectangle.
`GUI_BMP_SerializeExBpp()`	Creates a BMP file from the given rectangle using the specified color depth.

 © 2020 SEGGER Microcontroller GmbH

10.1.2.1 GUI_BMP_Draw()

Description

Draws a Windows bmp file, which has been loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_BMP_Draw(const void * pBMP,
                 int    x0,
                 int    y0);
```

Parameters

Parameter	Description
pBMP	Pointer to the start of the memory area in which the bmp file resides.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.

Return value

= 0 on success.
≠ 0 if the function fails.

Additional information

The table at the beginning of the chapter shows the supported BMP file formats. The example 2DGL_DrawBMP.c shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

10.1.2.2 GUI_BMP_DrawEx()

Description

Draws a bmp file, which does not have to be loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_BMP_DrawEx(GUI_GET_DATA_FUNC * pfGetData,
                   void              * p,
                   int                 x0,
                   int                 y0);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.

Return value

= 0 on success.
≠ 0 if the function fails.

Additional information

This function is used for drawing bmp files if not enough RAM is available to load the whole file into memory. The GUI library then calls the function pointed by the parameter pfGetData to read the data. The GetData function needs to return the number of requested bytes. The maximum number of bytes requested by the GUI is the number of bytes needed for drawing one line of the image.

 © 2020 SEGGER Microcontroller GmbH

10.1.2.3 GUI_BMP_DrawScaled()

Description

Draws a bmp file, which has been loaded into memory, at a specified position in the current window using scaling.

Prototype

```
int GUI_BMP_DrawScaled(const void * pFileData,
                       int    x0,
                       int    y0,
                       int    Num,
                       int    Denom);
```

Parameters

Parameter	Description
pFileData	Pointer to the start of the memory area in which the bmp file resides.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.
Num	Numerator to be used for scaling.
Denom	Denominator used for scaling.

Return value

= 0 on success.
≠ 0 if the function fails.

Additional information

The function scales the image by building a fraction with the given numerator and denominator. If for example an image should be shrunk to 2/3 of size the parameter Num should be 2 and Denom should be 3.

 © 2020 SEGGER Microcontroller GmbH

10.1.2.4 GUI_BMP_DrawScaledEx()

Description

Draws a bmp file, which does not have to be loaded into memory, at a specified position in the current window using scaling.

Prototype

```
int GUI_BMP_DrawScaledEx(GUI_GET_DATA_FUNC * pfGetData,
                         void              * p,
                         int                 x0,
                         int                 y0,
                         int                 Num,
                         int                 Denom);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.
Num	Numerator to be used for scaling.
Denom	Denominator used for scaling.

Return value

= 0 on success.
≠ 0 if the function fails.

Additional information

The function scales the image by building a fraction with the given numerator and denominator. If for example an image should be shrunk to 2/3 of size the parameter Num should be 2 and Denom should be 3. For more details, refer to GUI_BMP_DrawEx().

 © 2020 SEGGER Microcontroller GmbH

10.1.2.5 GUI_BMP_EnableAlpha()

Description

Enables semi-transparency for BMP files with a color depth of 32bpp.

Prototype

```
void GUI_BMP_EnableAlpha(void);
```

Additional information

The BMP file format has been defined 1990 by Microsoft. The version of that format is V3. There do not exist earlier versions. In the further course Microsoft defined V4 (with Windows 95) and V5 (with Windows 98). But applications with support for those formats are very rarely. Unfortunately the defacto standard V3 does not support semi-transparency, whereas V4 and V5 offers that feature.
The bitmap converter of emWin is able to save images with alpha channel as 32bpp BMP-file. It simply preserves the alpha values in the upper 8 bits of each pixel. These bits are not used in the V3 standard for 32bpp BMP-files. To be able to draw this kind of images saved by the BitmapConverter `GUI_BMP_EnableAlpha()` needs to be called. It should be mentioned that this kind of alpha channel support is not the same as defined in the newer versions V4 and V5.
Using `GUI_BMP_EnableAlpha()` makes only sense, if the alpha channel of 32bpp BMP-files is definitively used, because observing the alpha channel decreases the drawing performance slightly.

 © 2020 SEGGER Microcontroller GmbH

10.1.2.6 GUI_BMP_GetXSize()

Description

Returns the X-size of a specified bitmap which has been loaded into memory.

Prototype

```
int GUI_BMP_GetXSize(const void * pBMP);
```

Parameters

Parameter	Description
pBMP	Pointer to the start of the memory area in which the bmp file resides.

Return value

X-size of the bitmap.

 © 2020 SEGGER Microcontroller GmbH

10.1.2.7 GUI_BMP_GetXSizeEx()

Description

Returns the X-size of a specified bmp file which does not have to be loaded into memory.

Prototype

```
int GUI_BMP_GetXSizeEx(GUI_GET_DATA_FUNC * pfGetData,
                       void              * p);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.

Return value

X-size of the bitmap.

 © 2020 SEGGER Microcontroller GmbH

10.1.2.8 GUI_BMP_GetYSize()

Description

Returns the Y-size of a specified bitmap which has been loaded into memory.

Prototype

```
int GUI_BMP_GetYSize(const void * pBMP);
```

Parameters

Parameter	Description
pBMP	Pointer to the start of the memory area in which the bmp file resides.

Return value

Y-size of the bitmap.

 © 2020 SEGGER Microcontroller GmbH

10.1.2.9 GUI_BMP_GetYSizeEx()

Description

Returns the Y-size of a specified bmp file which does not have to be loaded into memory.

Prototype

```
int GUI_BMP_GetYSizeEx(GUI_GET_DATA_FUNC * pfGetData,
                       void              * p);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.

Return value

Y-size of the bitmap.

 © 2020 SEGGER Microcontroller GmbH

10.1.2.10 GUI_BMP_Serialize()

Description

The function creates a BMP file containing the complete content of the LCD. The BMP file is created using the color depth which is used in emWin at a maximum of 24 bpp. In case of using a color depth of less than 8bpp the color depth of the BMP file will be 8bpp.
The currently selected device is used for reading the pixel data. If a Memory Device is selected its content is written to the file.
This function does not support storing compressed BMP data.

Prototype

```
void GUI_BMP_Serialize(GUI_CALLBACK_VOID_U8_P * pfSerialize,
                       void                   * p);
```

Parameters

Parameter	Description
pfSerialize	Pointer to serialization function
p	Pointer to user defined data passed to serialization function

Example

The following example shows how to create a BMP file under windows.

```
static void _DrawSomething(void) {
  /* Draw something */
  GUI_DrawLine(10, 10, 100, 100);
}
static void _WriteByte2File(U8 Data, void * p) {
  U32 nWritten;
  WriteFile(*((HANDLE *)p), &Data, 1, &nWritten, NULL);
}
static void _ExportToFile(void) {
  HANDLE hFile = CreateFile("C:\\GUI_BMP_Serialize.bmp", GENERIC_WRITE, 0, 0,
                            CREATE_ALWAYS, FILE_ATTRIBUTE_NORMAL, 0);
  GUI_BMP_Serialize(_WriteByte2File, &hFile);
  CloseHandle(hFile);
}
void MainTask(void) {
  GUI_Init();
  _DrawSomething();
  _ExportToFile();
}
```

 © 2020 SEGGER Microcontroller GmbH

10.1.2.11 GUI_BMP_SerializeEx()

Description

The function creates a BMP file containing the given area. The BMP file is created using the color depth which is used in emWin at a maximum of 24 bpp. In case of using a color depth of less than 8bpp the color depth of the BMP file will be 8bpp. The currently selected device is used for reading the pixel data. If a Memory Device is selected its content is written to the file.
This function does not support storing compressed BMP data.

Prototype

```
void GUI_BMP_SerializeEx(GUI_CALLBACK_VOID_U8_P * pfSerialize,
                         int                      x0,
                         int                      y0,
                         int                      xSize,
                         int                      ySize,
                         void                   * p);
```

Parameters

Parameter	Description
pfSerialize	Pointer to user defined serialization function. See prototype below.
x0	Start position in X to create the BMP file.
y0	Start position in Y to create the BMP file.
xSize	Size in X.
ySize	Size in Y.
p	Pointer to user defined data passed to serialization function.

Prototype of GUI_CALLBACK_VOID_U8_P

```
void GUI_CALLBACK_VOID_U8_P(U8 Data, void * p);
```

Additional information

An example can be found in the description of GUI_BMP_Serialize().

 © 2020 SEGGER Microcontroller GmbH

10.1.2.12 GUI_BMP_SerializeExBpp()

Description

The function creates a BMP file containing the given area using the specified color depth. In case of using a color depth of less than 8bpp the color depth of the BMP file will be 8bpp. The color depth should be a multiple of 8. In case of a system color depth of more than 8bpp the color depth needs to be 16bpp or more. The currently selected device is used for reading the pixel data. If a Memory Device is selected its content is written to the file. This function does not support storing compressed BMP data.

Prototype

```
void GUI_BMP_SerializeExBpp(GUI_CALLBACK_VOID_U8_P * pfSerialize,
                            int                      x0,
                            int                      y0,
                            int                      xSize,
                            int                      ySize,
                            void                   * p,
                            int                      BitsPerPixel);
```

Parameters

Parameter	Description
pfSerialize	Pointer to user defined serialization function. See prototype below.
x0	Start position in X to create the BMP file.
y0	Start position in Y to create the BMP file.
xSize	Size in X.
ySize	Size in Y.
p	Pointer to user defined data passed to serialization function.
BitsPerPixel	Color depth.

Prototype of GUI_CALLBACK_VOID_U8_P

```
void GUI_CALLBACK_VOID_U8_P(U8 Data, void * p);
```

Additional information

An example can be found in the description of GUI_BMP_Serialize() above.

 © 2020 SEGGER Microcontroller GmbH

10.2 JPEG file support

JPEG (pronounced "jay-peg") is a standardized compression method for full-color and gray-scale images. JPEG is intended for compressing "real-world" scenes; line drawings, cartoons and other non-realistic images are not its strong suit. JPEG is lossy, meaning that the output image is not exactly identical to the input image. Hence you must not use JPEG if you have to have identical output bits. However, on typical photographic images, very good compression levels can be obtained with no visible change, and remarkably high compression levels are possible if you can tolerate a low-quality image.

10.2.1 Supported JPEG compression methods

This software implements JPEG baseline, extended-sequential and progressive compression processes. Provision is made for supporting all variants of these processes, although some uncommon parameter settings are not implemented yet. For legal reasons, code for the arithmetic-coding variants of JPEG is not distributed. It appears that the arithmetic coding option of the JPEG spec is covered by patents owned by IBM, AT&T, and Mitsubishi. Hence arithmetic coding cannot legally be used without obtaining one or more licenses. For this reason, support for arithmetic coding has not been included. (Since arithmetic coding provides only a marginal gain over the unpatented Huffman mode, it is unlikely that very many implementations will support it.)
The JPEG file support does not contain provision for the hierarchical or lossless processes defined in the standard. Further it supports only JPEG files based on the yCbCr color space and gray scale JPEGs.

10.2.2 Converting a JPEG file to C source

Under some circumstances it can be useful to add a JPEG file as C file to the project. In this case the JPEG file first needs to be converted to a C file. This can be done using the tool `Bin2C.exe` shipped with emWin. It can be found in the `Tools` subfolder. It converts the given binary file (in this case the JPEG file) to a C file. The filename of the C file is the same as the binary file name with the file extension `.c`. The following steps will show how to embed a JPEG file using `Bin2C`:

- Start `Bin2C.exe` and select the JPEG file to be converted to a C file, for example 'Image.jpeg' and convert it to a C file.
- Add the C file to the project.

Example

The following example shows how to display the converted JPEG file:

```
#include "GUI.h"
#include "Image.c" /* Include the converted C file */
void MainTask(void) {
  GUI_Init();
  GUI_JPEG_Draw(acImage, sizeof(acImage), 0, 0);
  ...
}
```

10.2.3 Displaying JPEG files

The graphic library first decodes the graphic information. If the image has to be drawn the decoding process takes considerable time. If a JPEG file is used in a frequently called callback routine of the Window Manager, the decoding process can take a considerable amount of time. The calculation time can be reduced by the use of Memory Devices. The best way would be to draw the image first into a Memory Device. In this case the decompression would be executed only one time. For more information about Memory Devices, refer to chapter *Memory Devices* on page 666.

 © 2020 SEGGER Microcontroller GmbH

10.2.4 Hardware support for decoding JPEG files

It is possible to use a hardware JPEG decoder of a MCU. For further information, please refer to *Hardware JPEG decoding* on page 2915.

10.2.5 Memory usage

The JPEG decompression uses approximately 33 KB RAM for decompression independent of the image size and a size dependent amount of bytes. The RAM requirement can be calculated as follows:

```
Approx. RAM requirement = X-Size of image × 80 bytes + 33 KB
```

The X-size dependent amount depends on the compression type of the JPEG file. The following table shows some examples:

Compression	Size of image in pixels	RAM usage (KB)	RAM usage, size dependent (KB)
H1V1	160x120	45	12
H2V2	160x120	46	13
GRAY	160x120	38	4

The memory required for the decompression is allocated dynamically by the emWin memory management system. After drawing the JPEG image the complete RAM will be released.

10.2.6 Progressive JPEG files

Contrary to baseline and extended-sequential JPEG files progressive JPEGs consist of multiple scans. Each of these scans is based on the previous scan(s) and refines the appearance of the JPEG image. This requires scanning the whole file even if only one line needs to be decompressed.

10.2.7 JPEG API

The table below lists the available JPEG file related routines in alphabetical order. Detailed function descriptions follow:

Functions

Routine	Description
GUI_JPEG_Draw()	Draws a JPEG file which has been loaded into memory.
GUI_JPEG_DrawEx()	Draws a JPEG file which does not need to be loaded into memory.
GUI_JPEG_DrawScaled()	Draws a JPEG file with scaling which has been loaded into memory.
GUI_JPEG_DrawScaledEx()	Draws a JPEG file with scaling which does not need to be loaded into memory.
GUI_JPEG_GetInfo()	Fills a GUI_JPEG_INFO structure with information about a JPEG file, which has been loaded into memory.
GUI_JPEG_GetInfoEx()	Fills a GUI_JPEG_INFO structure with information about a JPEG file, which does not have to be loaded into memory.

 © 2020 SEGGER Microcontroller GmbH

Data structures

Structure	Description
GUI_JPEG_INFO	Information about a JPEG image.

 © 2020 SEGGER Microcontroller GmbH

10.2.7.1 Functions

10.2.7.1.1 GUI_JPEG_Draw()

Description

Draws a JPEG file, which has been loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_JPEG_Draw(const void * pFileData,
                  int    DataSize,
                  int    x0,
                  int    y0);
```

Parameters

Parameter	Description
pFileData	Pointer to the start of the memory area in which the JPEG file resides.
DataSize	Number of bytes of the JPEG file.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.

Return value

= 0 on success
≠ 0 if the function fails. (The current implementation always returns 0).

Additional information

The Sample folder contains the example 2DGL_DrawJPG.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

10.2.7.1.2 GUI_JPEG_DrawEx()

Description

Draws a JPEG file, which does not have to be loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_JPEG_DrawEx(GUI_GET_DATA_FUNC * pfGetData,
                    void              * p,
                    int                 x0,
                    int                 y0);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.

Return value

= 0 on success.
≠ 0 if the function fails. (The current implementation always returns 0.)

Additional information

This function is used for drawing jpegs if not enough RAM is available to load the whole file into memory. The JPEG library then calls the function pointed by the parameter pfGetData to read the data.
The GetData function should return the number of available bytes. This may be less or equal the number of requested bytes. The function needs at least to return 1 new byte. The Sample folder contains the example 2DGL_DrawJPGScaled.c which shows how to use a GetData function.

 © 2020 SEGGER Microcontroller GmbH

10.2.7.1.3 GUI_JPEG_DrawScaled()

Description

Draws a JPEG file, which has been loaded into memory, at a specified position in the current window using scaling.

Prototype

```
int GUI_JPEG_DrawScaled(const void * pFileData,
                        int    DataSize,
                        int    x0,
                        int    y0,
                        int    Num,
                        int    Denom);
```

Parameters

Parameter	Description
pFileData	Pointer to the start of the memory area in which the jpeg file resides.
DataSize	Number of bytes of the JPEG file.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.
Num	Numerator to be used for scaling.
Denom	Denominator used for scaling.

Return value

= 0 on success.
≠ 0 if the function fails. (The current implementation always returns 0).

Additional information

The function scales the image by building a fraction with the given numerator and denominator. If for example an image should be shrunk to 2/3 of size the parameter Num should be 2 and Denom should be 3.
The Sample folder contains the example 2DGL_DrawJPGScaled.c which shows how to draw scaled JPEGs.

 © 2020 SEGGER Microcontroller GmbH

10.2.7.1.4 GUI_JPEG_DrawScaledEx()

Description

Draws a JPEG file, which does not have to be loaded into memory, at a specified position in the current window using scaling.

Prototype

```
int GUI_JPEG_DrawScaledEx(GUI_GET_DATA_FUNC * pfGetData,
                          void              * p,
                          int                 x0,
                          int                 y0,
                          int                 Num,
                          int                 Denom);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.
Num	Numerator to be used for scaling.
Denom	Denominator used for scaling.

Return value

= 0 on success.
≠ 0 if the function fails. (The current implementation always returns 0).

Additional information

The function scales the image by building a fraction with the given numerator and denominator. If for example an image should be shrunk to 2/3 of size the parameter Num should be 2 and Denom should be 3.
For more details, refer to GUI_JPEG_DrawEx(). The Sample folder contains the example 2DGL_DrawJPGScaled.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

10.2.7.1.5 GUI_JPEG_GetInfo()

Description

Fills a GUI_JPEG_INFO structure with information about a JPEG file, which has been loaded into memory.

Prototype

```
int GUI_JPEG_GetInfo(const void          * pFileData,
                     int                   DataSize,
                     GUI_JPEG_INFO       * pInfo);
```

Parameters

Parameter	Description
pFileData	Pointer to the start of the memory area in which the JPEG file resides.
DataSize	Number of bytes of the JPEG file.
pInfo	Pointer to a GUI_JPEG_INFO structure to be filled by the function.

Return value

= 0 on success.
≠ 0 if the function fails.

Additional information

The Sample folder contains the example 2DGL_DrawJPG.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

10.2.7.1.6 GUI_JPEG_GetInfoEx()

Description

Fills a GUI_JPEG_INFO structure with information about a JPEG file, which does not have to be loaded into memory.

Prototype

```
int GUI_JPEG_GetInfoEx(GUI_GET_DATA_FUNC * pfGetData,
                       void              * p,
                       GUI_JPEG_INFO     * pInfo);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
pInfo	Pointer to a GUI_JPEG_INFO structure to be filled by the function.

Return value

= 0 on success.
≠ 0 if the function fails.

Additional information

For more details about the function and the parameters pfGetData and p, refer to GUI_JPEG_GetInfo() and GUI_JPEG_DrawEx(). The Sample folder contains the example 2DGL_DrawJPGScaled.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

10.2.7.2 Data structures

10.2.7.2.1 GUI_JPEG_INFO

Description

Information about a JPEG image.

Type definition

```
typedef struct {
  int  XSize;
  int  YSize;
} GUI_JPEG_INFO;
```

Structure members

Member	Description
XSize	X-size of the image.
YSize	Y-size of the image.

See also

- GUI_JPEG_GetInfo()
- GUI_JPEG_GetInfoEx()

 © 2020 SEGGER Microcontroller GmbH

10.3 GIF file support

The GIF file format (Graphic Interchange Format) has been developed by the CompuServe Information Service in the 1980s. It has been designed to transmit images across data networks.
The GIF standard supports interlacing, transparency, application defined data, animations and rendering of raw text. Unsupported data like raw text or application specific data will be ignored by emWin.
GIF files uses the LZW (Lempel-Zif-Welch) file compression method for compressing the image data. This compression method works without loosing data. The output image is exactly identical to the input image.

10.3.1 Converting a GIF file to C source

Under some circumstances it can be useful to add a GIF file as C file to the project. This can be done by exactly the same way as described before under *JPEG file support* on page 399.

10.3.2 Displaying GIF files

The graphic library first decodes the graphic information. If the image has to be drawn the decoding process takes considerable time. If a GIF file is used in a frequently called callback routine of the Window Manager, the decoding process can take a considerable amount of time. The calculation time can be reduced by the use of Memory Devices. The best way would be to draw the image first into a Memory Device. In this case the decompression would be executed only one time. For more information about Memory Devices, refer to the chapter *Memory Devices* on page 666.

10.3.3 Memory usage

The GIF decompression routine of emWin needs about 16Kbytes of dynamically allocated RAM for decompression. After drawing an image the RAM which was used for decompression will be released.

10.3.4 GIF API

The table below lists the available GIF file related routines in alphabetical order. Detailed function descriptions follow:

Functions

Routine	Description
GUI_GIF_Draw()	Draws the first image of a GIF file which has been loaded into memory.
GUI_GIF_DrawEx()	Draws the first image of a GIF file which does not need to be loaded into memory.
GUI_GIF_DrawSub()	Draws the given sub image of a GIF file which has been loaded into memory.
GUI_GIF_DrawSubEx()	Draws the given sub image of a GIF file which does not need to be loaded into memory.
GUI_GIF_DrawSubScaled()	Draws the given sub image of a GIF file with scaling which has been loaded into memory.
GUI_GIF_DrawSubScaledEx()	Draws the given sub image of a GIF file with scaling which does not need to be loaded into memory.
GUI_GIF_GetComment()	Returns the given comment of a GIF file which has been loaded into memory.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_GIF_GetCommentEx()	Returns the given comment of a GIF file which does not need to be loaded into memory.
GUI_GIF_GetImageInfo()	Returns information about the given sub image of a GIF file which has been loaded into memory.
GUI_GIF_GetImageInfoEx()	Returns information about the given sub image of a GIF file which does not need to be loaded into memory.
GUI_GIF_GetInfo()	Returns information about a GIF file which has been loaded into memory.
GUI_GIF_GetInfoEx()	Returns information about a GIF file which does not need to be loaded into memory.
GUI_GIF_GetXSize()	Returns the X-size of a bitmap loaded into memory.
GUI_GIF_GetXSizeEx()	Returns the X-size of a bitmap which does not need to be loaded into memory.
GUI_GIF_GetYSize()	Returns the Y-size of a bitmap loaded into memory.
GUI_GIF_GetYSizeEx()	Returns the Y-size of a bitmap which does not need to be loaded into memory.

Data structures

Structure	Description
GUI_GIF_IMAGE_INFO	Information about a sub-image in a GIF file.
GUI_GIF_INFO	Information about a sub-image in a GIF file.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1 Functions

10.3.4.1.1 GUI_GIF_Draw()

Description

Draws the first image of a gif file, which has been loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_GIF_Draw(const void * pGIF,
                 U32    NumBytes,
                 int    x0,
                 int    y0);
```

Parameters

Parameter	Description
pGIF	Pointer to the start of the memory area in which the gif file resides.
NumBytes	Number of bytes of the gif file.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.

Return value

= 0 on success
≠ 0 on error.

Additional information

If the file contains more than one image, the function shows only the first image of the file. Transparency and interlaced images are supported.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.2 GUI_GIF_DrawEx()

Description

Draws a gif file, which does not have to be loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_GIF_DrawEx(GUI_GET_DATA_FUNC * pfGetData,
                   void              * p,
                   int                 x0,
                   int                 y0);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.

Return value

= 0 on success
≠ 0 on error.

Additional information

This function is used for drawing gif files if not enough RAM is available to load the whole file into memory. The library calls the function pointed by the parameter pfGetData to read the data. The GetData function should return the number of available bytes. This could be less or equal the number of requested bytes. The function needs at least to return 1 new byte.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.3 GUI_GIF_DrawSub()

Description

Draws the given sub image of a gif file, which has been loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_GIF_DrawSub(const void * pGIF,
                    U32    NumBytes,
                    int    x0,
                    int    y0,
                    int    Index);
```

Parameters

Parameter	Description
pGIF	Pointer to the start of the memory area in which the gif file resides.
NumBytes	Number of bytes of the gif file.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.
Index	Zero-based index of sub image to be shown.

Return value

= 0 on success
≠ 0 on error.

Additional information

The function manages the background pixels between the current and the previous image. If for example sub image #3 should be drawn at offset x20/y20 with a size of w10/h10 and the previous sub image was shown at x15/y15 with a size of w20/h20 and the background needs to be redrawn, the function fills the pixels between the images with the background color. The file 2DGL_DrawGIF.c of the Sample folder shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.4 GUI_GIF_DrawSubEx()

Description

Draws the given sub image of a gif file, which does not have to be loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_GIF_DrawSubEx(GUI_GET_DATA_FUNC * pfGetData,
                      void              * p,
                      int                 x0,
                      int                 y0,
                      int                 Index);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.
Index	Zero-based index of sub image to be shown.

Return value

= 0 on success
≠ 0 on error.

Additional information

This function is used for drawing gif images if not enough RAM is available to load the whole file into memory. The GUI library then calls the function pointed by the parameter pfGetData to read the data.
For more details, refer to the GUI_GIF_DrawEx().

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.5 GUI_GIF_DrawSubScaled()

Description

Draws the given sub image of a gif file, which has been loaded into memory, at a specified position in the current window using scaling.

Prototype

```
int GUI_GIF_DrawSubScaled(const void * pGIF,
                          U32    NumBytes,
                          int    x0,
                          int    y0,
                          int    Index,
                          int    Num,
                          int    Denom);
```

Parameters

Parameter	Description
pGIF	Pointer to the start of the memory area in which the gif file resides.
NumBytes	Number of bytes of the gif file.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.
Index	Zero-based index of sub image to be shown.
Num	Numerator to be used for scaling.
Denom	Denominator used for scaling.

Return value

= 0 on success
≠ 0 on error.

Additional information

The function scales the image by building a fraction with the given numerator and denominator. If for example an image should be shrunk to 2/3 of size the parameter Num should be 2 and Denom should be 3.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.6 GUI_GIF_DrawSubScaledEx()

Description

Draws the given sub image of a gif file, which does not have to be loaded into memory, at a specified position in the current window using scaling.

Prototype

```
int GUI_GIF_DrawSubScaledEx(GUI_GET_DATA_FUNC * pfGetData,
                            void              * p,
                            int                 x0,
                            int                 y0,
                            int                 Index,
                            int                 Num,
                            int                 Denom);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.
Index	Zero-based index of sub image to be shown.
Num	Numerator to be used for scaling.
Denom	Denominator used for scaling.

Return value

= 0 on success
≠ 0 on error.

Additional information

The function scales the image by building a fraction with the given numerator and denominator. If for example an image should be shrunk to 2/3 of size the parameter Num should be 2 and Denom should be 3.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.7 GUI_GIF_GetComment()

Description

Returns the given comment from a GIF image, which has been loaded into memory.

Prototype

```
int GUI_GIF_GetComment(const void * pGIF,
                       U32    NumBytes,
                       U8   * pBuffer,
                       int    MaxSize,
                       int    Index);
```

Parameters

Parameter	Description
pGIF	Pointer to the start of the memory area in which the gif file resides.
NumBytes	Number of bytes of the gif file.
pBuffer	Pointer to a buffer to be filled with the comment.
MaxSize	Size of the buffer.
Index	Zero based index of comment to be returned.

Return value

= 0 on success
≠ 0 on error.

Additional information

A GIF file can contain 1 or more comments. The function copies the comment into the given buffer. If the comment is larger than the given buffer only the bytes which fit into the buffer will be copied. The file 2DGL_DrawGIF.c of the Sample folder shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.8 GUI_GIF_GetCommentEx()

Description

Returns the given comment from a GIF image, which does not have to be loaded into memory.

Prototype

```
int GUI_GIF_GetCommentEx(GUI_GET_DATA_FUNC * pfGetData,
                         void              * p,
                         U8                * pBuffer,
                         int                 MaxSize,
                         int                 Index);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
pBuffer	Pointer to a buffer to be filled with the comment.
MaxSize	Size of the buffer.
Index	Zero based index of comment to be returned.

Return value

= 0 on success
≠ 0 on error.

Additional information

For details, refer to GUI_GIF_GetComment().

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.9 GUI_GIF_GetImageInfo()

Description

Returns information about the given sub image of a GIF file, which has been loaded into memory.

Prototype

```
int GUI_GIF_GetImageInfo(const void               * pGIF,
                         U32                        NumBytes,
                         GUI_GIF_IMAGE_INFO * pInfo,
                         int                        Index);
```

Parameters

Parameter	Description
pGIF	Pointer to the start of the memory area in which the gif file resides.
NumBytes	Number of bytes of the gif file.
pInfo	Pointer to a GUI_GIF_IMAGE_INFO structure which will be filled by the function.
Index	Zero based index of sub image.

Return value

= 0 on success
≠ 0 on error.

Additional information

If an image needs be shown as a movie this function should be used to get the time the sub image should be visible and the next sub image should be shown. If the delay member is 0 the image should be visible for 1/10 second.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.10 GUI_GIF_GetImageInfoEx()

Description

Returns information about the given sub image of a GIF file, which does not need to be loaded into memory.

Prototype

```
int GUI_GIF_GetImageInfoEx(GUI_GET_DATA_FUNC  * pfGetData,
                           void               * p,
                           GUI_GIF_IMAGE_INFO * pInfo,
                           int                  Index);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
pInfo	Pointer to a GUI_GIF_IMAGE_INFO structure which will be filled by the function.
Index	Zero based index of sub image.

Return value

= 0 on success
≠ 0 on error.

Additional information

For more details, refer to GUI_GIF_GetImageInfo().

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.11 GUI_GIF_GetInfo()

Description

Returns an information structure with information about the size and the number of sub images within the given GIF file, which has been loaded into memory.

Prototype

```
int GUI_GIF_GetInfo(const void         * pGIF,
                    U32                  NumBytes,
                    GUI_GIF_INFO       * pInfo);
```

Parameters

Parameter	Description
pGIF	Pointer to the start of the memory area in which the gif file resides.
NumBytes	Number of bytes of the gif file.
pInfo	Pointer to a GUI_GIF_INFO structure which will be filled by this function.

Return value

= 0 on success
≠ 0 on error.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.12 GUI_GIF_GetInfoEx()

Description

Returns an information structure with information about the size and the number of sub images within the given GIF file, which does not need to be loaded into memory.

Prototype

```
int GUI_GIF_GetInfoEx(GUI_GET_DATA_FUNC * pfGetData,
                      void              * p,
                      GUI_GIF_INFO      * pInfo);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
pInfo	Pointer to a GUI_GIF_INFO structure which will be filled by this function.

Return value

= 0 on success
≠ 0 on error.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.13 GUI_GIF_GetXSize()

Description

Returns the X-size of a specified GIF image, which has been loaded into memory.

Prototype

```
int GUI_GIF_GetXSize(const void * pGIF);
```

Parameters

Parameter	Description
pGIF	Pointer to the start of the memory area in which the gif file resides.

Return value

X-size of the GIF image.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.14 GUI_GIF_GetXSizeEx()

Description

Returns the X-size of a specified GIF image, which does not need to be loaded into memory.

Prototype

```
int GUI_GIF_GetXSizeEx(GUI_GET_DATA_FUNC * pfGetData,
                       void              * p);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.

Return value

X-size of the GIF image.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.15 GUI_GIF_GetYSize()

Description

Returns the Y-size of a specified GIF image, which has been loaded into memory.

Prototype

```
int GUI_GIF_GetYSize(const void * pGIF);
```

Parameters

Parameter	Description
pGIF	Pointer to the start of the memory area in which the bmp file resides.

Return value

Y-size of the GIF image.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.1.16 GUI_GIF_GetYSizeEx()

Description

Returns the Y-size of a specified GIF image, which does not need to be loaded into memory.

Prototype

```
int GUI_GIF_GetYSizeEx(GUI_GET_DATA_FUNC * pfGetData,
                       void              * p);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. Detailed information about the Get-Data() function can be found unter to *Getting data with the …Ex() functions* on page 436
p	Void pointer passed to the function pointed by pfGetData.

Return value

Y-size of the GIF image.

 © 2020 SEGGER Microcontroller GmbH

10.3.4.2 Data structures

10.3.4.2.1 GUI_GIF_IMAGE_INFO

Description

Information about a sub-image in a GIF file.

Type definition

```
typedef struct {
  int  xPos;
  int  yPos;
  int  xSize;
  int  ySize;
  int  Delay;
} GUI_GIF_IMAGE_INFO;
```

Structure members

Member	Description
xPos	X-position of the last drawn image.
yPos	Y-position of the last drawn image.
xSize	X-size of the last drawn image.
ySize	Y-size of the last drawn image.
Delay	Time in 1/100 seconds the image should be shown in a movie.

See also

- GUI_GIF_GetImageInfo()
- GUI_GIF_GetImageInfoEx()

 © 2020 SEGGER Microcontroller GmbH

10.3.4.2.2 GUI_GIF_INFO

Description

Information about a sub-image in a GIF file.

Type definition

```
typedef struct {
  int  xSize;
  int  ySize;
  int  NumImages;
} GUI_GIF_INFO;
```

Structure members

Member	Description
xSize	Pixel size in X of the image.
ySize	Pixel size in Y of the image.
NumImages	Number of sub-images in the file.

See also

- GUI_GIF_GetInfo()
- GUI_GIF_GetInfoEx()

 © 2020 SEGGER Microcontroller GmbH

10.4 PNG file support

The PNG (Portable Network Graphics) format is an image format which offers lossless data compression and alpha blending by using a non-patented data compression method. Version 1.0 of the PNG specification has been released in 1996. Since the end of 2003 PNG is an international standard (ISO/IEC 15948). PNG support for emWin can be achieved by using the 'libpng' library from Glenn Randers-Pehrson, Guy Eric Schalnat and Andreas Dilger. An adapted version of this library ready to use with emWin is available on our website. That library can be added to emWin in order to to use the PNG API as explained later in this chapter.

Licensing

The use of 'libpng' library is subject to a BSD style license and copyright notice in the file `GUI\PNG\png.h` of the downloadable library. The original version of the library is available for free under www.libpng.org.

10.4.1 Converting a PNG file to C source

Under some circumstances it can be useful to add a PNG file as C file to the project. This can be done by exactly the same way as described before under *JPEG file support* on page 399. Further the Bitmap Converter is able to load PNG files and can convert them into C bitmap files.

10.4.2 Displaying PNG files

The graphic library first decodes the graphic information. If the image has to be drawn the decoding process takes considerable time. If a PNG file is used in a frequently called callback routine of the Window Manager, the decoding process can take a considerable amount of time. The calculation time can be reduced by the use of Memory Devices. The best way would be to draw the image first into a Memory Device. In this case the decompression would be executed only one time. For more information about Memory Devices, refer to the chapter *Memory Devices* on page 666.

10.4.3 Memory usage

The PNG decompression uses approximately 21 KB of RAM for decompression independent of the image size and a size dependent amount of bytes. The RAM requirement can be calculated as follows: `Approx. RAM requirement = (xSize + 1) × ySize × 4 + 54 KB`

10.4.4 PNG API

The table below lists the available PNG file related routines in alphabetical order. Detailed function descriptions follow:

Routine	Description
`GUI_PNG_Draw()`	Draws the PNG file which has been loaded into memory.
`GUI_PNG_DrawEx()`	Draws the PNG file which does not need to be loaded into memory.
`GUI_PNG_GetXSize()`	Returns the X-size of a bitmap loaded into memory.
`GUI_PNG_GetXSizeEx()`	Returns the X-size of a bitmap which does not need to be loaded into memory.
`GUI_PNG_GetYSize()`	Returns the Y-size of a bitmap loaded into memory.
`GUI_PNG_GetYSizeEx()`	Returns the Y-size of a bitmap which does not need to be loaded into memory.

 © 2020 SEGGER Microcontroller GmbH

10.4.4.1 GUI_PNG_Draw()

Description

Draws a png file, which has been loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_PNG_Draw(const void * pFileData,
                 int    FileSize,
                 int    x0,
                 int    y0);
```

Parameters

Parameter	Description
pFileData	Pointer to the start of the memory area in which the png file resides.
FileSize	Number of bytes of the png file.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.

Return value

= 0 on success.
≠ 0 if the function fails. (The current implementation always returns 0).

Additional information

The Sample folder contains the example 2DGL_DrawPNG.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

10.4.4.2 GUI_PNG_DrawEx()

Description

Draws a png file, which does not have to be loaded into memory, at a specified position in the current window.

Prototype

```
int GUI_PNG_DrawEx(GUI_GET_DATA_FUNC * pfGetData,
                   void              * p,
                   int                 x0,
                   int                 y0);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.
x0	X-position of the upper left corner of the bitmap in the display.
y0	Y-position of the upper left corner of the bitmap in the display.

Return value

= 0 on success.
≠ 0 if the function fails.

Additional information

This function is used for drawing png if not enough RAM is available to load the whole file into memory. The PNG library then calls the function pointed by the parameter pfGetData to read the data.
The GetData function should return the number of available bytes. This could be less or equal the number of requested bytes. The function needs at least to return 1 new byte. Note that the PNG library internally allocates a buffer for the complete image. This can not be avoided by using this function.

 © 2020 SEGGER Microcontroller GmbH

10.4.4.3 GUI_PNG_GetXSize()

Description

Returns the X-size of a specified PNG image, which has been loaded into memory.

Prototype

```
int GUI_PNG_GetXSize(const void * pFileData,
                           int    FileSize);
```

Parameters

Parameter	Description
pFileData	Pointer to the start of the memory area in which the png file resides.
FileSize	Size of the file in bytes.

Return value

X-size of the PNG image.

 © 2020 SEGGER Microcontroller GmbH

10.4.4.4 GUI_PNG_GetXSizeEx()

Description

Returns the X-size of a specified PNG image, which does not have to be loaded into memory.

Prototype

```
int GUI_PNG_GetXSizeEx(GUI_GET_DATA_FUNC * pfGetData,
                       void              * p);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.

Return value

X-size of the PNG image.

 © 2020 SEGGER Microcontroller GmbH

10.4.4.5 GUI_PNG_GetYSize()

Description

Returns the Y-size of a specified PNG image, which has been loaded into memory.

Prototype

```
int GUI_PNG_GetYSize(const void * pFileData,
                     int    FileSize);
```

Parameters

Parameter	Description
pFileData	Pointer to the start of the memory area in which the png file resides.
FileSize	Size of the file in bytes.

Return value

Y-size of the PNG image.

 © 2020 SEGGER Microcontroller GmbH

10.4.4.6 GUI_PNG_GetYSizeEx()

Description

Returns the Y-size of a specified PNG image, which does not have to be loaded into memory.

Prototype

```
int GUI_PNG_GetYSizeEx(GUI_GET_DATA_FUNC * pfGetData,
                       void              * p);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. For details about the GetData function, refer to *Getting data with the …Ex() functions* on page 436.
p	Void pointer passed to the function pointed by pfGetData.

Return value

Y-size of the PNG image.

 © 2020 SEGGER Microcontroller GmbH

10.5 Getting data with the ...Ex() functions

As well as streamed bitmaps, using BMP, GIF, JPEG and PNG files also works without loading the whole image into RAM. For this case the *...Ex() functions* can be used. Common for all of these functions is the use of a GetData function. Please note that the GetData function has to work slightly different depending on the actual task it is used for. See table of parameters and examples below.

Prototype of the 'GetData' function

```
int GUI_GET_DATA_FUNC(      void    * p,
                      const U8    * * ppData,
                            unsigned NumBytes,
                            U32      Off);
```

Parameters

Parameter	Description
p	Application defined void pointer.
ppData	BMP, GIF & JPEG: The GetData function has to set the pointer to the location the requested data resides in. Streamed bitmaps & PNG: The location the pointer points to has to be filled by the GetData function.
NumBytes	Number of requested bytes.
Off	Defines the offset to use for reading the source data.

Additional information

...Ex() functions require the GetData function to fetch at least one pixel line of data. It is recommended to make sure that the GetData function is able to fetch at least one pixel line of the biggest image used by the application.

Internal use of the function

In general the GetData function is called one time at the beginning to retrieve overhead information and, after this, several times to retrieve the actual image data.

Return value

The number of bytes which were actually read. If the number of read bytes does not match, the drawing function will return immediately.

Example

The following code excerpt shows how to implement a GetData function for usage with BMP, GIF and JPEG data:

```
int APP_GetData(void * p, const U8 ** ppData, unsigned NumBytes, U32 Off) {
  static char   _acBuffer[0x200];
  HANDLE      * phFile;
  DWORD         NumBytesRead;
  phFile = (HANDLE *)p;
  //
  // Check buffer size
  //
  if (NumBytes > sizeof(acBuffer)) {
    NumBytes = sizeof(acBuffer);
  }
  //
  // Set file pointer to the required position
  //
  SetFilePointer(*phFile, Off, 0, FILE_BEGIN);
  //
```

 © 2020 SEGGER Microcontroller GmbH

```
  // Read data into buffer
  //
  ReadFile(*phFile, acBuffer, NumBytes, &NumBytesRead, NULL);
  //
  // Set data pointer to the beginning of the buffer
  //
  *ppData = acBuffer;
  //
  // Return number of available bytes
  //
  return NumBytesRead;
}
```

Example (PNG and streamed bitmap)

The following code excerpt shows how to implement a `GetData` function for usage with PNG and streamed bitmap data:

```
int APP_GetData(void * p, const U8 ** ppData, unsigned NumBytes, U32 Off) {
  HANDLE * phFile;
  DWORD    NumBytesRead;
  U8     * pData;
  pData  = (U8 *)*ppData;
  phFile = (HANDLE *)p;
  //
  // Set file pointer to the required position
  //
  SetFilePointer(*phFile, Off, 0, FILE_BEGIN);
  //
  // Read data into buffer
  //
  ReadFile(*phFile, pData, NumBytes, &NumBytesRead, NULL);
  //
  // Return number of available bytes
  //
  return NumBytesRead;
}
```

 © 2020 SEGGER Microcontroller GmbH

Chapter 11

Bitmap Converter

The Bitmap Converter is designed for converting common image file formats like BMP, PNG, JPEG or GIF into the desired emWin bitmap format. That can be a C file which can directly be compiled and linked with the project or a binary format, which can be loaded at runtime. Simply load an image into the application. Convert the color format if you want or have to, and save it in the appropriate format.

Screenshot of the Bitmap Converter



 © 2020 SEGGER Microcontroller GmbH

11.1 What it does

The Bitmap Converter is primarily intended as a tool to convert bitmaps from a PC format to a C file. Bitmaps which can be used with emWin are normally defined as `GUI_BITMAP` structures in C. The structures — or rather the picture data which is referenced by these structures — can be quite large. It makes therefore sense to use the Bitmap Converter to generate C files from bitmaps.

Another useful feature is the ability to save images as C stream files. The advantage against a normal C file is, that these data streams can be located anywhere on any media whereas C files need to be located in the addressable ROM area.

The Bitmap Converter also features color conversion, so that the resulting C code is not unnecessarily large. Typically the number of bits per pixel are reduced to achieve less memory consumption. The tool displays the converted image as well.

A number of simple functions can be performed with the Bitmap Converter, including scaling the size, flipping the bitmap horizontally or vertically, rotating it, and inverting the bitmap indices or colors (these features can be found under the `Image` menu). Any further modifications to an image must be made in a bitmap manipulation program such as Adobe Photoshop or Corel Photopaint. It usually makes the most sense to perform any image modifications in such a program, using the Bitmap Converter for converting purposes only.

 © 2020 SEGGER Microcontroller GmbH

11.2 Loading a bitmap

11.2.1 Supported input file formats

The Bitmap Converter supports the following file types:

- Windows bitmap files (*.bmp)
- Graphic Interchange Format (*.gif)
- Portable Network Graphics (*.png)
- Joint Photographic Experts Group format (*.jpeg)

Windows Bitmap Files (BMP)

The Bitmap Converter supports the most common bitmap file formats. Bitmap files of the following formats can be opened by the Bitmap Converter:

- 1, 4 or 8 bits per pixel (bpp) with palette
- 16, 24 or 32 bpp without palette (full-color mode, in which each color is assigned an RGB value)
- RLE4 and RLE8

Trying to read bitmap files of other formats will cause an error message of the Bitmap Converter.

Graphic Interchange Format (GIF)

The Bitmap Converter supports reading GIF files. For general editing only the first image of the GIF file is used. GIF image consisting of several images may be converted to animated sprites and animated cursors.

Transparency and interlaced GIF images are supported by the converter.

Portable Network Graphic (PNG)

The PNG format is the most recommended format to create images with alpha blending. The Bitmap Converter supports reading PNG images with alpha channel.

Joint Photographic Experts Group (JPEG)

The JPEG format is the most common used format when dealing with photos. JPEG files using a lossy compression method. Because of that they are not the ideal format for diagrams or similar.

The Bitmap Converter supports reading JPEG images.

11.2.2 Loading from a file

An image file of one of the supported formats may be opened directly in the Bitmap Converter by selecting **File ➔ Open**.

11.2.3 Using the clipboard

Any other type of bitmap (that is, `.jpg`, `.jpeg`, `.tif`) may be opened with another program, copied to the clipboard, and pasted into the Bitmap Converter. This process will achieve the same effect as loading directly from a file.

 © 2020 SEGGER Microcontroller GmbH

11.3 Color conversion

The primary reason for converting the color format of a bitmap is to reduce memory consumption. The most common way of doing this is by using the option **Best palette** as in the above example, which customizes the palette of a particular bitmap to include only the colors which are used in the image. It is especially useful with full-color bitmaps in order to make the palette as small as possible while still fully supporting the image. Once a bitmap file has been opened in the Bitmap Converter, simply select **Image ➔ Convert Into ➔ Best palette** from the menu. If it is necessary to keep transparency select **Image ➔ Convert Into ➔ Best palette + transparency**.

For certain applications, it may be more efficient to use a fixed color palette, chosen from the menu under **Image ➔ Convert Into**. For example, suppose a bitmap in full-color mode is to be shown on a display which supports only four grayscales. It would be a waste of memory to keep the image in the original format, since it would only appear as four grayscales on the display. The full-color bitmap can be converted into a four-grayscale, 2bpp bitmap for maximum efficiency.

The procedure for conversion would be as follows:

Step	Result
Step 1: Load the image • The Bitmap Converter is opened and the same file is loaded as in steps 1 and 2 of the example shown in *Saving the file* on page 448. • The Bitmap Converter displays the loaded bitmap.	
Step 2: Convert the image • Choose **Image ➔ Convert Into ➔ Gray4**  • The Bitmap Converter displays the converted bitmap.	 • In this example, the image uses less memory since a palette of only 4 grayscales is used instead of the full-color mode. If the target display supports only 4 grayscales, there is no use in having a higher pixel depth as it would only waste memory.

 © 2020 SEGGER Microcontroller GmbH

11.4 Dithering

Dithering is a method for showing more details on systems with only a few available colors than with a simple color conversion. It gives the illusion of a better color depth by using noise to randomize quantization error. If for example a photo needs to be drawn on a b/w system normally not much details would be visible after a simple conversion. However, dithering is able to show much more details:

Original	black / white	black / white, dithered
		

The above table shows clearly the difference between dithering and a simple conversion. To dither a picture the command **Image ➔ Dither to ➔ ...** should be used:



 © 2020 SEGGER Microcontroller GmbH

11.5 Using a custom palette

Converting bitmaps to a custom palette and saving them without palette information can save memory and can increase the performance of bitmap drawing operations.

More efficient memory utilization

Per default each bitmap contains its own palette. Even the smallest bitmaps can contain a large palette with up to 256 colors. In many cases only a small fraction of the palette is used by the bitmap. If using many of these bitmaps the amount of memory used by the palettes can grow rapidly.
So it can save much ROM if converting the bitmaps used by emWin to the available hardware palette and saving them as (D)evice (D)ependent (B)itmaps without palette information.

Better bitmap drawing performance

Before emWin draws a bitmap, it needs to convert each device independent bitmap palette to the available hardware palette. This is required because the pixel indices of the bitmap file are indices into the device independent bitmap palette and not to the available hardware palette. Converting the bitmap to a DDB means that color conversion at run time is not required and speeds up the drawing.

11.5.1 Saving a palette file

The Bitmap Converter can save the palette of the currently loaded bitmap into a palette file which can be used for converting other bitmaps with the command **Image → Convert Into → Custom palette**. This requires that the current file is a palette based file and not a RGB file. To save the palette the command **File → Save palette...** can be used.

11.5.2 Palette file format

Custom palette files are simple files defining the available colors for conversion. They contain the following:

- Header (8 bytes)
- NumColors (U32, 4 bytes)
- 0 (4 bytes)
- U32 Colors[NumColors] (NumColors × 4 bytes, type `GUI_COLOR`)

Total file size is therefore: `16 + (NumColors × 4) bytes`. A custom palette file with 8 colors would be `16 + (8 × 4) = 48 bytes`. At this point, a binary editor must be used in order to create such a file.
The maximum number of colors supported is 256; the minimum is 2.

Example

This example file would define a palette containing 2 colors—red and white:

```
0000: 65 6d 57 69 6e 50 61 6c 02 00 00 00 00 00 00 00
0010: ff 00 00 00 ff ff ff 00
```

The 8 headers make up the first eight bytes of the first line. The U32 is stored lsb first (big endian) and represents the next four bytes, followed by the four 0 bytes. Colors are stored 1 byte per color, where the 4th byte is 0 as follows: RRGGBB00. The second line of code defines the two colors used in this example.

11.5.3 Palette files for fixed palette modes

Using the custom palette feature can even make sense with the most common used fixed palette modes, not only with custom hardware palettes. For the most palette based fixed palette modes a palette file can be found in the folder `Sample\Palette`.

 © 2020 SEGGER Microcontroller GmbH

11.5.4 Converting a bitmap

The command **Image → Convert Into → Custom palette** should be used for converting the currently loaded bitmap to a custom palette. The Bitmap Converter tries to find the nearest color of the palette file for each pixel of the currently loaded bitmap.

 © 2020 SEGGER Microcontroller GmbH

11.6 Generating C files from bitmaps

The main function of the Bitmap Converter is to convert PC-formatted bitmaps into C files which can be used by emWin. Before doing so, however, it is often desirable to modify the color palette of an image so that the generated C file is not excessively large.
The bitmap may be saved as a bmp, png or a gif file (which can be reloaded and used or loaded into other bitmap manipulation programs) or as a C file. A C file will serve as an input file for your C compiler. It may contain a palette (device-independent bitmap, or DIB) or be saved without (device-dependent bitmap, or DDB). DIBs are recommended, as they will display correctly on any display; a DDB will only display correctly on a display which uses the same palette as the bitmap.
C files may be generated as "C with palette", "C without palette", "C with palette, compressed" or "C without palette, compressed". For more information on compressed files, see the section "Compressed bitmaps" as well as the example at the end of the chapter.

11.6.1 Supported bitmap formats

The following table shows the currently available output formats for C and C stream files:

Format	Color depth [bpp]	Com-pression	Trans-parency	Palette
1 bit per pixel	1	no	yes	yes
2 bits per pixel	2	no	yes	yes
4 bits per pixel	4	no	yes	yes
8 bits per pixel	8	no	yes	yes
Compressed, RLE4	4	yes	yes	yes
Compressed, RLE8	8	yes	yes	yes
12 bits per pixel 444_12	12	no	no	no
12 bits per pixel M444_12, red and blue swapped	12	no	no	no
12 bits per pixel 444_12_1	12	no	no	no
12 bits per pixel M444_12_1, red and blue swapped	12	no	no	no
12 bits per pixel 444_16	12	no	no	no
12 bits per pixel M444_16, red and blue swapped	12	no	no	no
High color 555	15	no	no	no
High color 555, red and blue swapped	15	no	no	no
High color 565	16	no	no	no
High color 565, red and blue swapped	16	no	no	no
High color 565, compressed	16	yes	no	no
High color 565, red and blue swapped, compressed	16	yes	no	no
High color A555 with alpha channel	15	no	yes	no
High color AM555 with alpha channel, red and blue swapped	15	no	yes	no
High color A565 with alpha channel	16	no	yes	no
High color AM565 with alpha channel, red and blue swapped	16	no	yes	no
True color 888	24	no	no	no
True color 8888 with alpha channel	32	no	yes	no
True color 8888 with alpha channel, compressed	32	yes	yes	no

 © 2020 SEGGER Microcontroller GmbH

Format	Color depth [bpp]	Com-pression	Trans-parency	Palette
True color M8888I with alpha channel, red and blue swapped, alpha inverted	32	no	yes	no
Alpha channel, compressed	8	yes	yes	no

11.6.2 Palette information

A bitmap palette is an array of 24 bit RGB color entries. Bitmaps with a color depth from 1 - 8 bpp can be saved with (device independent bitmap, DIB) or without palette information (device dependent bitmap DDB).

Device independent bitmaps (DIB)

The color information is stored in the form of an index into the color array. Before emWin draws a DIB, it converts the 24 bit RGB colors of the bitmap palette into color indices of the hardware palette. The advantage of using DIBs is that they are hardware independent and can be drawn correctly on systems with different color configurations. The disadvantages are the additional ROM requirement for the palette and the slower performance because of the color conversion.

Device dependent bitmaps (DDB)

The pixel information of a DDB is the index of the displays hardware palette. No conversion needs to be done before drawing a DDB. The advantages are less ROM requirement and a better performance. The disadvantage is that these bitmaps can not be displayed correctly on systems with other color configurations.

11.6.3 Transparency

A palette based bitmap can be converted to a transparent bitmap. Transparency means each pixel with index 0 will not produce any output. The command **Image → Transparency** can be used to select the color which should be used for transparency. After selecting the transparent color, the pixel indices of the image will be recalculated, so that the selected color is on position 0 of the bitmap palette. When saving the bitmap file as C file, it will be saved with the transparency attribute.

11.6.4 Alpha blending

Alpha blending is a method of combining an image with the background to create the effect of semi transparency. The alpha value of a pixel determines its transparency. The color of a pixel after drawing the bitmap is a blend of the former color and the color value in the bitmap. In emWin, logical colors are handled as 32 bit values. The lower 24 bits are used for the color information and the upper 8 bits are used to manage the alpha value. An alpha value of 0 means the image is opaque and a value of `0xFF` means completely transparent. Whereas BMP and GIF files do not support alpha blending PNG files support alpha blending. So the easiest way to create bitmap files with alpha blending is to load a PNG file. When working with BMP and/or GIF files the Bitmap Converter initially has no information about the alpha values.

Loading a PNG file

This is the most recommended way for creating bitmaps with an alpha mask:

 © 2020 SEGGER Microcontroller GmbH



The PNG file contains all required information.

Loading the alpha values from an alpha mask bitmap

This method loads the alpha values from a separate file. Black pixels of the alpha mask file means opaque and white means transparent. The following table shows an example:

Starting point	Alpha mask	Result
		

The command **File ➔ Load Alpha Mask** can be used for loading an alpha mask.

Creating the alpha values from two bitmaps

This method uses the difference between the pixels of two pictures to calculate the alpha values. The first image should show the item on a black background. The second image should show the same on a white background. The following table shows an example of how to create the alpha values using the command **File ➔ Create Alpha**:

Starting point	Black background	White background	Result
			

The command **File ➔ Create Alpha** can be used tor creating the alpha values.

 © 2020 SEGGER Microcontroller GmbH

11.6.5 Selecting the best format

emWin supports various formats for the generated C file. It depends on several conditions which will be the 'best' format and there is no general rule to be used. Color depth, compression, palette and transparency affect the drawing performance and/or ROM requirement of the bitmap.

Color depth

In general the lower the color depth the smaller the ROM requirement of the bitmap. Each display driver has been optimized for drawing 1bpp bitmaps (text) and bitmaps with the same color depth as the display.

Compression

The supported RLE compression method has the best effect on bitmaps with many horizontal sequences of equal-colored pixels. Details later in this chapter. The performance is typically slightly slower than drawing uncompressed bitmaps.

Palette

The ROM requirement of a palette is 4 bytes for each color. So a palette of 256 colors uses 1 KB. Furthermore emWin needs to convert the colors of the palette before drawing the bitmap. Advantage: Bitmaps are device independent meaning they can be displayed on any display, independent of its color depth and format.

Transparency

The ROM requirement of transparent bitmaps is the same as without transparency. The performance is with transparency slightly slower than without.

High color and true color bitmaps

Special consideration is required for bitmaps in these formats. Generally the use of these formats only make sense on displays with a color depth of 15 bits and above. Further it is strongly recommended to save the C files in the exact same format used by the hardware. Note that using the right format will have a positive effect on the drawing performance. If a high color bitmap for example should be shown on a system with a color depth of 16bpp which has the red and blue components swapped, the best format is 'High color 565, red and blue swapped'. Already a slightly other format has the effect, that each pixel needs color conversion, whereas a bitmap in the right format can be rendered very fast without color conversion. The difference of drawing performance in this case can be factor 10 and more.

11.6.6 Saving the file

The basic procedure for using the Bitmap Converter is illustrated below:

Step	Result
Step 1: Start the application. • The Bitmap Converter is opened showing an empty window.	

 © 2020 SEGGER Microcontroller GmbH

Step	Result
Step 2: Load a bitmap into the Bitmap Converter. • Choose **File → Open** • Locate the document you want to open and click **Open**. The Bitmap Converter can open images of the bmp, gif, png and sbmp format.  • The Bitmap Converter displays the loaded bitmap.	
Step 3: Choose conversion  • Choose **Image → Convert Into** • Select the desired palette. In this example, the option Best palette is chosen. • The Bitmap Converter displays the converted bitmap.	 • The image is unchanged in terms of appearance, but uses less memory since a palette of only 15 colors is used instead of the full-color mode. These 15 colors are the only ones actually required to display this particular image.
Step 4: Save the bitmap as a C file. • Choose **File → Save As.** • Select a destination and a name for the C file. • Select the file type. In this example, the file is saved as C bitmap file. • Click **Save**.	

 © 2020 SEGGER Microcontroller GmbH

Step	Result
Step 5: Specify bitmap format. • If the bitmap should be saved as C file the format should now be specified. Use one of the available formats shown in the dialog. If the bitmap should be saved without palette, activate the check box **Without palette**. • The Bitmap Converter will create a separate file in the specified destination, containing the C source code for the bitmap.	

 © 2020 SEGGER Microcontroller GmbH

11.7 Generating C stream files

A C stream file consists of the same information as a C file. Contrary to a C file a data stream can be located anywhere and does not need to be compiled or linked with the project. All supported output formats described for C files are also available for C stream files. emWin supports creating bitmaps from data streams and drawing data streams directly. Detailed information about C stream file support can be found under *Drawing streamed bitmaps* on page 296.

```
(all values LSB):
Header (16 Bytes)
  2 Bytes Id (0x42, 0x4d, "BM")
  16 Bits Format (FORMAT_1BPP      - 1
                  FORMAT_2BPP      - 2
                  FORMAT_4BPP      - 4
                  FORMAT_8BPP      - 5
                  FORMAT_RLE4      - 6
                  FORMAT_RLE8      - 7
                  FORMAT_565       - 8
                  FORMAT_M565      - 9
                  FORMAT_555       - 10
                  FORMAT_M555      - 11
                  FORMAT_RLE16     - 12
                  FORMAT_RLEM16    - 13
                  FORMAT_8888      - 16
                  FORMAT_RLE32     - 15
                  FORMAT_24        - 17
                  FORMAT_RLEALPHA  - 18
                  FORMAT_444_12    - 19
                  FORMAT_M444_12   - 20
                  FORMAT_444_12_1  - 21
                  FORMAT_M444_12_1 - 22
                  FORMAT_444_16    - 23
                  FORMAT_M444_16   - 24
                  FORMAT_A555      - 25
                  FORMAT_AM555     - 26
                  FORMAT_A565      - 27
                  FORMAT_AM565     - 28
                  FORMAT_M8888I    - 29)
  16 Bits xSize
  16 Bits ySize
  16 Bits BytesPerLine
  16 Bits BitsPerPixel
  16 Bits NumEntries (Number of colors in palette based bitmaps)
  16 Bits HasTrans (1 if transparency exists, 0 if not)
Palette data (4 bytes per entry)
  for each entry:
    if ("Save colors in ARGB" == 0):
      8 Bits Red
      8 Bits Green
      8 Bits Blue
      8 Bits Alpha
    if ("Save colors in ARGB" == 1):
      8 Bits Blue
      8 Bits Red
      8 Bits Green
      8 Bits Alpha
// Pixel order is from left to right and from top to bottom
Pixel data (FORMAT_1BPP, FORMAT_2BPP, FORMAT_4BPP, FORMAT_8BPP):
  for each line:
    for each pixel:
      1-8 Bits per pixel index value
Pixel data (FORMAT_RLE4):
  8 Bit Counter
  if (Counter > 0):
    8 Bits index value into palette (Counter: number of pixels of same color)
```

 © 2020 SEGGER Microcontroller GmbH

```
    // Lower nibble used only
  if (Counter == 0):
    8 Bits number of pixels (1 or 2)
    8 Bits Index values into palette (Pixel 1: upper nibble, Pixel 2: lower
 nibble)
    // If (HasTrans == 1) and (Index == 0) pixel is transparent
Pixel data (FORMAT_RLE8):
  8 Bit Counter
  if (Counter > 0):
    8 Bits index value into palette (Counter: number of pixels of same color)
  if (Counter == 0):
    8 Bits number of pixels (1 or 2)
    for each pixel:
      8 Bits Index value into palette
      // If (HasTrans == 1) and (Index == 0) pixel is transparent
Pixel data (FORMAT_RLEALPHA):
  8 Bit Counter
  if (Counter > 0):
    8 Bits Intensity (Counter: number of pixels of same intensity)
  if (Counter == 0):
    8 Bits number of pixels (1 or 2)
    for each pixel:
      8 Bits Intensity (Counter: number of pixels of same intensity)
Pixel data (FORMAT_RLE16, FORMAT_RLEM16):
  8 Bit Counter
  if (Counter > 0):
    16 Bits color index value (Counter: number of pixels of same color)
  if (Counter == 0):
    8 Bits number of pixels (1 or 2)
    for each pixel:
      16 Bits color index value
Pixel data (FORMAT_RLE32):
  8 Bit Counter
  if (Counter > 0):
    32 Bits color value (Counter: number of pixels of same color)
  if (Counter == 0):
    8 Bits number of pixels (1 or 2)
    for each pixel:
      32 Bits color index value
Pixel data (FORMAT_565, FORMAT_M565, FORMAT_555, FORMAT_M555):
  for each line:
    for each pixel:
      16 Bits color index
Pixel data (FORMAT_8888, FORMAT_M8888I):
  for each line:
    for each pixel:
      32 Bits color value
Pixel data (FORMAT_24):
  for each line:
    for each pixel:
      8 Bits Red
      8 Bits Green
      8 Bits Blue
Pixel data (FORMAT_444_12,    FORMAT_M444_12, FORMAT_444_12_1
            FORMAT_M444_12_1, FORMAT_444_16,  FORMAT_M444_16):
  for each line:
    for each pixel:
      16 Bits color index (12 Bits used only, dependent on format)
Pixel data (FORMAT_A555, FORMAT_AM555, FORMAT_A565, FORMAT_AM565):
  for each line:
    for each pixel:
      16 Bits color index (15 Bits color, 1 bit alpha, dependent on format)
```

 © 2020 SEGGER Microcontroller GmbH

11.8 Compressed bitmaps

The Bitmap Converter and emWin support run-length encoding (RLE) compression of bitmaps in the resulting source code files. The RLE compression method works most efficiently if your bitmap contains many horizontal sequences of equal-colored pixels. An efficiently compressed bitmap will save a significant amount of space. However, compression is not recommended for photographic images since they do not normally have sequences of identical pixels. It should also be noted that a compressed image may take slightly longer to display.
Storing a bitmap using RLE compression can be done by selecting one of the according output formats when saving as a C file: "C with palette, compressed" or "C without palette, compressed". There are no special functions needed for displaying compressed bitmaps; they are displayed the same way uncompressed bitmaps are displayed.

Compression ratios

The ratio of compression achieved will vary depending on the bitmap used. The more horizontal uniformity in the image, the better the ratio will be. A higher number of bits per pixel will also result in a higher degree of compression.
In the bitmap used in the previous examples, the total number of pixels in the image is (200 × 94) = 18,800.
Since 2 pixels are stored in 1 byte, the total uncompressed size of the image is `18,800 ÷ 2 = 9,400 bytes`.
The total compressed size for this particular bitmap is 3,803 bytes for 18,800 pixels (see the example at the end of the chapter).
The ratio of compression can therefore be calculated as `9,400 ÷ 3,803 = 2.47`.

 © 2020 SEGGER Microcontroller GmbH

11.9 Creating animated sprites / cursors

The Bitmap Converter can be used to convert animated GIF files to animated sprites / cursors in C file format. This functionality is offered by the entries in the file menu which are shown below:



After clicking one of the according file menu entries, a file dialog appears and an animated GIF file can be chosen. Once this is done the name of the resulting C file needs to be specified. Converting animated GIF files to animated sprites / cursors does not require any further parameters. The process is performed automatically. Since the effort depends on the input GIF file, completing this task may take a moment. The Bitmap Converter can be used again as soon as the mouse cursor is changed to the simple arrow again.

11.9.1 Animated Sprite example

The following shows the structure of an animated sprite C file as it is generated by the Bitmap Converter. Although animations consist of several images, the palette and pixel data structures are shown only once here. Variable data is described using place holders.

File header

```
/*********************************************************************
*                SEGGER Microcontroller GmbH & Co. KG                *
*        Solutions for real time microcontroller applications        *
**********************************************************************
*                                                                    *
*        Internet: www.segger.com    Support:  support@segger.com    *
*                                                                    *
**********************************************************************
*                                                                    *
* Source file: %_FILENAME_%.gif (Animated Sprite)                    *
* Dimensions:  %_X_SIZE_% * %_Y_SIZE_%                               *
* NumImages:   %_NUMBER_OF_IMAGES_%                                  *
* Duration:    %_OVERALL_DURATION_%                                  *
*                                                                    *
**********************************************************************
*
* %_USAGE_EXAMPLE_%
*/
#include <stdlib.h>
#include "GUI.h"
```

 © 2020 SEGGER Microcontroller GmbH

```
#ifndef GUI_CONST_STORAGE
  #define GUI_CONST_STORAGE const
#endif
```

Palette and pixel data

```
static GUI_CONST_STORAGE GUI_COLOR%_FILENAME_%%_INDEX_%[] = {
  %_COLOR_DATA_%
};
static GUI_CONST_STORAGE GUI_LOGPALETTE _Pal%_FILENAME_%%_INDEX_% = {
  %_NUMBER_OF_COLORS_%,   // Number of entries
  &_Colors%_FILENAME_%%_INDEX_%[0]
};
static GUI_CONST_STORAGE unsigned char _ac%_FILENAME_%%_INDEX_%[] = {
  %_PIXEL_DATA_%
};
```

General data

```
static GUI_CONST_STORAGE GUI_BITMAP _abm%_FILENAME_%[] = {
  { %_X_SIZE_%,               %_Y_SIZE_%,
    %_BYTES_PER_LINE_%,       %_BITS_PER_PIXEL_%,
    _ac%_FILENAME_%%_INDEX_%,  &_Pal%_FILENAME_%%_INDEX_%
  },
  [...]
};
const GUI_BITMAP * apbm%_FILENAME_%[] = {
  &_abm%_FILENAME_%[0],
  [...]
};
const unsigned aDelay%_FILENAME_%[] = {
  %_DELAY_DATA_%
};
/************************** End of file ***************************/
```

11.9.2 Animated Cursor example

The file structure for animated cursors almost equals the structure for animated sprites. Therefor only the differences are mentioned here. The array of bitmap pointers is defined as static:

```
static const GUI_BITMAP * _apbm%_FILENAME_%[] = {
  [...]
 };
```

The array of delays is defined as static:

```
static const unsigned _aDelay%_FILENAME_%[] = {
  [...]
};
```

A non-static definition of a `GUI_CURSOR_ANIM` structure is placed at the end:

```
const GUI_CURSOR_ANIM Cursor%_FILENAME_% = {
  _apbm%_FILENAME_%,    // Pointer to an array of bitmaps
  0,                    // x coordinate of the hot spot
  0,                    // y coordinate of the hot spot
  0,                    // Period, should be 0 here
  _aDelay%_FILENAME_%,  // Pointer to an array of periods
  %_NUMBER_OF_IMAGES_%  // Number of images
};
```

 © 2020 SEGGER Microcontroller GmbH

11.9.3 Additional information

The hot spot coordinate define the position which is recognized by emWin when PID events occur. If the hot spot should not be represented by the topmost leftmost pixel, the according values in the `GUI_CURSOR_ANIM` structure may be modified.
The array of delays is always created. In case every image uses the same delay, the forth value in the `GUI_CURSOR_ANIM` structure may be set accordingly. In this case the array of delays may be deleted after the fifth value of the `GUI_CURSOR_ANIM` structure was set to `NULL`.

 © 2020 SEGGER Microcontroller GmbH

11.10 Command line usage

It is also possible to work with the Bitmap Converter using the command prompt. All conversion functions available in the Bitmap Converter menu are available as commands, and any number of functions may be performed on a bitmap in one command line.

11.10.1 Format for commands

Commands are entered using the following format:

```
BmpCvt <filename>.bmp <-command>
```

If more than one command is used, one space is typed between each. For example, a bitmap with the name logo.bmp is converted into Best palette format and saved as a C file named logo.bmp all at once by entering the following at the command prompt:

```
BmpCvt logo.bmp -convertintobestpalette -saveaslogo,1 -exit
```

Note that while the file to be loaded into the Bitmap Converter always includes its bmp extension, no file extension is written in the `-saveas` command. An integer is used instead to specify the desired file type. The number 1 in the `-saveas` command above designates "C with palette". The `-exit` command automatically closes the program upon completion. See the table below for more information.

11.10.2 Command line options

The following table lists all permitted Bitmap Converter commands. It can also be viewed at any time by entering `BmpCvt -?` at the command prompt.

Command	Description
`-convertintobw`	Convert to BW.
`-convertintogray4`	Convert to Gray4.
`-convertintogray16`	Convert to Gray16.
`-convertintogray64`	Convert to Gray64.
`-convertintogray256`	Convert to Gray256.
`-convertinto111`	Convert to 111.
`-convertinto222`	Convert to 222.
`-convertinto233`	Convert to 233.
`-convertinto323`	Convert to 323.
`-convertinto332`	Convert to 332.
`-convertinto8666`	Convert to 8666.
`-convertintorgb`	Convert to RGB.
`-convertintobestpalette`	Convert to best palette.
`-convertintotranspalette`	Convert to best palette with transparency.
`-convertintocustompalette<filename>`	Convert to a custom palette.
`<filename>`	User-specified filename of desired custom palette.
`-exit`	Terminate PC program automatically.
`-fliph`	Flip image horizontally.
`-flipv`	Flip image vertically.
`-help`	Displays the command line table.
`-hide`	Hides the application window.
`-invertindices`	Invert indices.

 © 2020 SEGGER Microcontroller GmbH

Command	Description
-invertpalette	Invert palette entries.
-reducecolors<numcolors>	Reduce number of used colors.
<numcolors>	Number of colors to be used.
-rotate90cw	Rotate image by 90 degrees clockwise.
-rotate90ccw	Rotate image by 90 degrees counterclockwise.
-rotate180	Rotate image by 180 degrees.
-saveas<filename>,<type>[,<fmt>[,<noplt>]]	Save file as filename.
<filename>	User-specified file name including the file extension.
<type>	Must be an integer from 1 to 4 as follows: 1: C with palette (.c file) 2: Windows Bitmap file (bmp file) 3: C stream (.dta file) 4: GIF format (gif file)
<fmt>	Specifies the bitmap format (only if type = 1): 1: 1 bit per pixel* 2: 2 bits per pixel* 4: 4 bits per pixel* 5: 8 bits per pixel* 6: RLE4 compression* 7: RLE8 compression* 8: High color 565 9: High color 565, red and blue swapped 10: High color 555 11: High color 555, red and blue swapped 12: RLE16 compression 13: RLE16 compression, red and blue swapped 15: True color 32bpp, compressed 16: True color 32bpp 17: True color 24bpp 18: Alpha channel 8bpp, compressed 19: 16bpp (444_12) 20: 16bpp (444_12), RB swapped 21: 16bpp (444_12_1) 22: 16bpp (444_12_1), RB swapped 23: 16bpp (444_16) 24: 16bpp (444_16), RB swapped 25: High color (A555) with alpha channel 26: High color (AM555) with alpha channel, red and blue swapped 27: High color (A565) with alpha channel 28: High color (AM565) with alpha channel, red and blue swapped 29: True color 32bpp, red and blue swapped, alpha inverted If this parameter is not given, the Bitmap Converter uses the following default formats in dependence of the number of colors of the bitmap: Number of colors ≤ 2: 1 bit per pixel Number of colors ≤ 4: 2 bits per pixel Number of colors ≤ 16: 4 bits per pixel Number of colors ≤ 256: 8 bits per pixel RGB: High color 565
<noplt>	Saves the bitmap with or without palette (only if type = 1) 0: Save bitmap with palette (default)

 © 2020 SEGGER Microcontroller GmbH

Command	Description
	1: Save bitmap without palette
-scale<WIDTH>,<HEIGHT>	Scale image
<WIDTH>	Width in percent.
<HEIGHT>	Height in percent.
-transparency<RGB-Color>	Sets the transparent color.
<RGB-Color>	RGB color which should be used as transparent color.
-?	Displays the command line table.

Note

* Images need to be converted to an according format before they can be stored in a format of 8 or less bpp.

 © 2020 SEGGER Microcontroller GmbH

11.11 Options

The Bitmap Converter offers you three more options when converting and saving a bitmap file. When clicking on the ’Options’ entry in the menu bar an options dialog will pop up. The following table will explain the available options:

Option	Description
Preserve transparency	If checked this option allows to convert an image, containing transparent pixels, in a palette based format and preserve the transparency. If not checked the transparency gets lost.
Big endian mode	This option is only useful if an image gets stored as a DTA file. With the C files the compiler takes care of the endianness but for binary files it is necessary to have them available with the proper byte order.
Save colors in ARGB	This option makes sure to save the colors of a palette as 32bit value where the alpha channel is inverted and the red and blue channels are swapped.

 © 2020 SEGGER Microcontroller GmbH

11.12 Example of a converted bitmap

A typical example for the use of the Bitmap Converter would be the conversion of your company logo into a C bitmap. Take another look at the example bitmap pictured below:



The bitmap is loaded into the Bitmap Converter, converted to `Best palette`, and saved as "C with palette". The resulting C source code is displayed below (some data is not shown to conserve space).

Resulting C code (generated by the Bitmap Converter)

```
/*********************************************************************
*                SEGGER Microcontroller GmbH & Co. KG                *
*        Solutions for real time microcontroller applications        *
**********************************************************************
*                                                                    *
*        Internet: www.segger.com    Support:  support@segger.com    *
*                                                                    *
**********************************************************************
*
* Source file: SeggerLogo200
* Dimensions:  200 * 100
* NumColors:   33
*
**********************************************************************
*/
#include <stdlib.h>
#include "GUI.h"
#ifndef GUI_CONST_STORAGE
  #define GUI_CONST_STORAGE const
#endif
static GUI_CONST_STORAGE GUI_COLOR ColorsSeggerLogo200[] = {
  0xFFFFFF,0x353537,0x9C4B37,0xCDCDCD,
  [...]
};
static GUI_CONST_STORAGE GUI_LOGPALETTE PalSeggerLogo200 = {
  33,  /* number of entries */
  0,   /* No transparency */
  &ColorsSeggerLogo200[0]
};
static GUI_CONST_STORAGE unsigned char acSeggerLogo200[] = {
  0x00, 0x00,       /* Not all data is shown in this example */
  0x00, 0x92,
  [...]
  0xC6, 0x22,
  0x0A, 0x22
};
extern GUI_CONST_STORAGE GUI_BITMAP bmSeggerLogo200;
GUI_CONST_STORAGE GUI_BITMAP bmSeggerLogo200 = {
  200, /* XSize */
  100, /* YSize */
  200, /* BytesPerLine */
  8, /* BitsPerPixel */
  acSeggerLogo200,  /* Pointer to picture data (indices) */
  &PalSeggerLogo200  /* Pointer to palette */
};
```

 © 2020 SEGGER Microcontroller GmbH

```
/*************************** End of file ****************************/
```

Compressing the file

We can use the same bitmap image to create a compressed C file, which is done simply by loading and converting the bitmap as before, and saving it as "C with palette, compressed". The source code is displayed below (some data is not shown to conserve space).
The compressed image size can be seen towards the end of the file as 3,730 bytes for 18,800 pixels.

Resulting compressed C code (generated by the Bitmap Converter)

```
/*********************************************************************
*                SEGGER Microcontroller GmbH & Co. KG                *
*        Solutions for real time microcontroller applications        *
**********************************************************************
*                                                                    *
*        Internet: www.segger.com    Support:  support@segger.com    *
*                                                                    *
**********************************************************************
*
* Source file: SeggerLogo200_comp
* Dimensions:  200 * 100
* NumColors:   33
*
**********************************************************************
*/
#include <stdlib.h>
#include "GUI.h"
#ifndef GUI_CONST_STORAGE
  #define GUI_CONST_STORAGE const
#endif
static GUI_CONST_STORAGE GUI_COLOR ColorsSeggerLogo200_comp[] = {
  0xFFFFFF, 0x353537, 0x9C4B37, 0xCDCDCD,
  [...]
};
static GUI_CONST_STORAGE GUI_LOGPALETTE PalSeggerLogo200_comp = {
  33,/* number of entries */
  0, /* No transparency */
  &ColorsSeggerLogo200_comp[0]
};
static GUI_CONST_STORAGE unsigned char acSeggerLogo200_comp[] = {
  /* RLE: 006 Pixels @ 000,000*/ 6, 0x00,
  /* RLE: 188 Pixels @ 006,000*/ 188, 0x01,
  [...]
  /* RLE: 188 Pixels @ 006,099*/ 188, 0x01,
  /* RLE: 006 Pixels @ 194,099*/ 6, 0x00,
  0
};  /* 3730 for 20000 pixels */
extern GUI_CONST_STORAGE GUI_BITMAP bmSeggerLogo200_comp;
GUI_CONST_STORAGE GUI_BITMAP bmSeggerLogo200_comp = {
  200, /* XSize */
  100, /* YSize */
  200, /* BytesPerLine */
  GUI_COMPRESS_RLE8, /* BitsPerPixel */
  acSeggerLogo200_comp,  /* Pointer to picture data (indices) */
  &PalSeggerLogo200_comp  /* Pointer to palette */
 ,GUI_DRAW_RLE8
};
/*************************** End of file ****************************/
```

 © 2020 SEGGER Microcontroller GmbH

Chapter 12

Fonts

This chapter describes the various methods of font support in emWin. The most common fonts are shipped with emWin as C font files. All of them contain the ASCII character set and most of them do also contain the characters included in the ISO 8859-1 character set. In fact, you will probably find that these fonts are fully sufficient for your application. For detailed information about the individual fonts, refer to *Standard fonts* on page 514.

emWin is compiled for 8-bit characters, allowing for a maximum of 256 different character codes out of which the first 32 are reserved as control characters. The availability of characters depends on the font. In order to display certain characters selecting an according font may be required. For accessing the complete 'Basic Multilingual Plane' (BMP, plane 0) of the Unicode codespace UTF8 decoding could be enabled. Details can be found in the chapter *Language Support* on page 2566.

TrueType font files (TTF) can also be used directly. Support for those kind of fonts can be achieved by adding the FreeType library which comes with its own BSD style license. More details about TTF support and a download link can be found under *TrueType Font (TTF) format* on page 470.

 © 2020 SEGGER Microcontroller GmbH

12.1 Introduction

The first way of font support was the possibility to use C files with font definitions containing bitmaps with 1bpp pixel information for each character. This kind of font support was limited to use only the fonts which are compiled with the application. Over time, the font support has been improved regarding font quality, ROM requirement, performance, scalability and the ability to add further fonts at run time. In the meantime emWin fonts cover anti-aliasing, drawing of compound characters like required in Thai language, fonts located on external non addressable media and TrueType support. Except the TrueType font format, which is a vector font, all other kinds of fonts are bitmap fonts.

 © 2020 SEGGER Microcontroller GmbH

12.2 Font types

emWin supports different internal types of fonts defined by emWin and the commonly used TrueType fonts.

Monospaced bitmap fonts

Each character of a monospaced bitmap font has the same size. In a proportional font each character has its own width, whereas in a monospaced font the width is defined only one time. The pixel information is saved with 1bpp and covers the whole character area.

Proportional bitmap fonts

Each character of a proportional bitmap font has the same height and its own width. The pixel information is saved with 1bpp and covers the whole character area.

Anti-aliased fonts with 2 bpp anti-aliasing information

Each character has the same height and its own width. The pixel information is saved with 2bpp anti-aliasing information and covers the whole character area.

Anti-aliased fonts with 4 bpp anti-aliasing information

Each character has the same height and its own width. The pixel information is saved with 4bpp anti-aliasing information and covers the whole character area.

Extended proportional bitmap fonts

Each character of an extended proportional bitmap font has its own height and its own width. The pixel information is saved with 1bpp and covers only the areas of the glyph bitmaps.

Extended proportional bitmap fonts with 2 bpp anti-aliasing information

Each character has the same height and its own width. The pixel information is saved with 2bpp anti-aliasing information and covers only the areas of the glyph bitmaps.

Extended proportional bitmap fonts with 4 bpp anti-aliasing information

Each character has the same height and its own width. The pixel information is saved with 4bpp anti-aliasing information and covers only the areas of the glyph bitmaps.

Extended proportional bitmap fonts, framed

In case the background color is unknown at compile time, it might be preferable to use a framed font. A framed font is always drawn in transparent mode regardless of the current settings. The character pixels are drawn in the currently selected foreground color and the frame is drawn in background color. A good contrast between foreground and background color makes sure, that the text can be read on any background. Framed fonts are not suitable for compound characters like in the Thai language. They are also not suitable for Arabic fonts.
The picture below shows some framed text in front of a photo:



Table of font types

The following table shows the difference between the font types. The pictures only show the pixel information saved in the font file:

 © 2020 SEGGER Microcontroller GmbH

Prop. bitmap font	Prop. bitmap font, AA2	Prop. bitmap font, AA4	Ext. prop. bitmap font	Ext. prop. bitmap font, framed
				

Ext. prop. bitmap font, AA2	Ext. prop. bitmap font, AA4
	

TrueType vector fonts

The TrueType font support of emWin means support for the TrueType font file format described later in this chapter.

 © 2020 SEGGER Microcontroller GmbH

12.3 Font formats

The following explains the differences between the supported font formats, when to use them and what is required to be able to use them.

12.3.1 C file format

This is the most common way of using fonts. When using fonts in form of C files, we recommend compiling all available fonts and linking them as library modules or putting all of the font object files in a library which you can link with your application. This way you can be sure that only the fonts which are needed by your application are actually linked. The Font Converter may be used to create additional fonts.

When to use

This format should be used if the fonts are known at compile time and if there is enough addressable memory available for the font data.

Requirements

In order to be able to use a font C file in your application, the following requirements must be met:

- The font file is in a form compatible with emWin as C file, object file or library.
- The font file is linked with your application.
- The font declaration is contained in the application.

Format description

A font C file contains at first the pixel information of all characters included by the font. It is followed by a character information table with size information about each character. This table is followed by range information structures for each contiguous area of characters contained in the font file, whereas each structure points to the next one. Note that this method can enlarge a font file a lot if using many separate characters. After the range information structures a `GUI_FONT` structure follows with the main information like type, pixel size and so on of the font.

12.3.2 System Independent Font (SIF) format

System independent fonts are binary data blocks containing the font information. The Font Converter can be used to create system independent fonts. This tool is not part of the basic package. A short description follows later in this chapter.

When to use

This format should be used if the fonts are not known at compile time and if there is enough addressable memory available for the font data.

Requirements

In order to be able to use a SIF font file in your application, it is required that the whole file reside in addressable memory (ROM or RAM).

Format description

The structure of a SIF file is nearly the same as of a C file. It contains the same information in binary format. The sequence of the file components is vice versa: General font information followed by range information structures, character information table and at least pixel information of all characters.

12.3.3 External Bitmap Font (XBF) format

As well as SIF fonts XBF fonts are binary data blocks containing the font information and the Font Converter can be used to create XBF files. The Font Converter is not part of the

 © 2020 SEGGER Microcontroller GmbH

emWin basic package. Details on how to create external bitmap fonts can be found in the chapter *Font Converter* on page 534.

Advantages

Contrary to other fonts, XBF fonts do not have to reside in memory when they are used, whereas all other kinds of emWin fonts need to reside completely in memory. The XBF font file can remain on any external media while it is used. Data access is done by a `GetData` callback function. The advantage of XBF fonts is that it is possible to use very large fonts on systems with little memory.

XBF fonts offer a performance advantage when using fonts including lots of characters which do not follow each other directly in sequence. This kind of character set would cause the Font Converter to create a C file font containing many `GUI_FONT_PROP` structures having a pointer to the according next one. The more `GUI_FONT_PROP` structures exist in a font the longer it might take to display a character. XBF fonts just use a memory offset so each character can be found in the same amount of time.

When to use

This format should be used if there is not enough addressable memory available for the font data and if there is any kind of external media available for storing the fonts.

Requirements

In order to be able to use a XBF font in your application, a `GetData` callback function is required which is responsible for getting font data.

Format description

This format differs in general from SIF and C file format. At first it contains a small block of general font information including the lowest character code and the highest character code. It is followed by an access table containing offset and data size information for each character between lowest and highest character code. If a character does not exist, this information is zero for the according character. The access table is followed by the character information of all characters containing pixel data and character size information.

File content

```
(all values LSB):
Header (18 Bytes)
  4 Bytes ID (0x47, 0x55, 0x49, 0x58, "GUIX")
  16 Bits ySize of font
  16 Bits yDist of font, to be used for cursor increment
  16 Bits Baseline position from top
  16 Bits Height in pixels of lowercase characters
  16 Bits Height in pixels of capital characters
  16 Bits First codepoint in access table
  16 Bits Last codepoint in access table
Character Access table (6 Bytes for each entry)
  32 Bits Position of bitmap information in file (0 means character is not
 available)
  16 Bits Size of bitmap information
Bitmap Information (Extended font format)
  12 Bytes header:
    16 Bits X-distance in pixels to be used for cursor increment
    16 Bits X-size of bitmap
    16 Bits Y-size of bitmap
    16 Bits X-position of bitmap
    16 Bits Y-position of bitmap
    16 Bits Bytes per line of bitmap
  Bitmap (Size - 12 bytes)
Bitmap Information (Standard font format)
  4 Bytes header:
    16 Bits X-size of bitmap
    16 Bits Y-size of bitmap
```

 © 2020 SEGGER Microcontroller GmbH

```
Bitmap (Size - 4 bytes)
```

12.3.4 iType and iTypeSpark font engine support

Since version V5.20 emWin supports using the iType® font engine, since V5.30 it also supports the iTypeSpark® engine. The iType® and iTypeSpark® font engines are font rendering subsystems developed by Monotype Imaging. They offer a host of advanced capabilities including font linking, font management and discovery, support for various industry standards and font formats in a small memory footprint. iType® and iTypeSpark® can be implemented into various platforms. Based on OpenType®, TrueType® and PostScript® font formats and packaged as ANSI C code for broad, flexible integration, iType® meets stringent size requirements for any applications, including those that support East Asian languages requiring thousands of characters. The glue code to be able to use the those font engines is freely available under the following links:

- www.segger.com/downloads/emwin/emWin_iType
- www.segger.com/downloads/emwin/emWin_iTypeSpark

Screenshot



Licensing

The emWin library by SEGGER does not provide the Monotype® font engines itself. It provides only the glue code required to be able to use the iType® or the iTypeSpark® library. Please contact Monotype Imaging under monotypeimaging.com for a license request if required.

When to use

This format could be used if high quality fonts need to be scalable at run-time and/or advanced font effects are required.

Requirements

In general the requirements are similar to the requirements of the true type font support described on the next page. For detailed information about requirements and performance please also contact Monotype Imaging under monotypeimaging.com.

 © 2020 SEGGER Microcontroller GmbH

12.3.5 TrueType Font (TTF) format

The functionality of emWin can be enhanced by making use of TrueType fonts. TrueType is an outline font standard developed by Apple Computer. It offers font developers a high degree of control over how their fonts are displayed at various font heights. Contrary to bitmap fonts which are based on bitmaps for each character, TrueType fonts are based on vector graphics. The advantage of the vector representation is the loss-free scalability.
This implies that each character first needs to be rasterized into a bitmap before it is drawn. To avoid rasterization each time a character is drawn the bitmap data normally is cached by the font engine. This requires a fast CPU and enough RAM. TTF support for emWin can be achieved by using the FreeType font library from David Turner, Robert Wilhelm and Werner Lemberg which is not part of emWin. An adapted version of this library ready to use with emWin is available on our website. That library can be added to emWin in order to use the TTF-API as explained later in this chapter.

Licensing

The use of FreeType font library is subject to a BSD style license with credit clause (freetype.org) also included in `GUI\TrueType\FTL.txt` of the zip file. The original version of the library is available for free under freetype.org.

When to use

This format should be used if fonts need to be scalable at run-time.

Requirements

- **CPU:** TTF support works only on 32 bit CPUs. Our definition of a 32bit CPU: `sizeof(int) = 4`.
- **ROM:** The ROM requirement of the TTF engine is approx. 250K. The exact size depends on the CPU, the compiler and the optimization level of the compiler.
- **RAM:** The RAM requirement of the library depends a lot on the used fonts. The basic RAM requirement of the TTF engine is approx. 50K. When creating a GUI font with `GUI_TTF_CreateFont()` the font engine loads all font tables defined in the TTF file required to generate the characters. The table sizes varies a lot between the fonts. The additional required amount of RAM for creating a font can be between a few KB up to more than 1MB. For typical fonts 80-300 KB are required. It depends on the used font file how much RAM is required. At least the TTF engine requires a bitmap cache. Per default the engine uses 200K for the cache. This should be enough for most applications. The TTF engine allocates its memory via the non-emWin functions `malloc()` and `free()`. It must be made sure that these functions work before using the TTF engine.

Format description

For details about the TTF format, refer to the information available under apple.com. It is also possible to display some fonts in the OTF format but this is not guaranteed. If a font is available in the TTF format it should be used instead of the OTF font.

 © 2020 SEGGER Microcontroller GmbH

12.4 Converting a TTF file to C source

Under some circumstances it can be useful to add a TTF file as C file to the project, for example if no file system is available. This can be done by using the tool `Bin2C.exe` shipped with emWin. It can be found in the `Tools` subfolder. It converts the given binary file (in this case the TTF file) to a C file.

 © 2020 SEGGER Microcontroller GmbH

12.5 Declaring custom fonts

The most recommended way of declaring the prototypes of custom fonts is to put them into an application defined header file. This should be included from each application source file which uses these fonts. It could look like the following example:

```
#include "GUI.h"
extern GUI_CONST_STORAGE GUI_FONT GUI_FontApp1;
extern GUI_CONST_STORAGE GUI_FONT GUI_FontApp2;
```

Note that this kind of declaring prototypes does not work if the fonts should be used with emWin configuration macros like `BUTTON_FONT_DEFAULT` or similar. In this case the fonts need to be declared in the configuration file `GUIConf.h`. The declaration in this case can look like the following example:

```
typedef struct GUI_FONT GUI_FONT;

extern const GUI_FONT GUI_FontApp1;

#define BUTTON_FONT_DEFAULT &GUI_FontApp1
#define EDIT_FONT_DEFAULT   &GUI_FontApp1
```

The `typedef` is required because the structure `GUI_FONT` has not been defined at the early point where `GUIConf.h` is included by emWin.

 © 2020 SEGGER Microcontroller GmbH

12.6 Selecting a font

emWin offers different fonts, one of which is always selected. This selection can be changed by calling the function `GUI_SetFont()` or one of the `GUI_XXX_CreateFont()` functions, which select the font to use for all text output to follow for the current task.
If no font has been selected by your application, the default font is used. This default is configured in `GUIConf.h` and can be changed. You should make sure that the default font is one that you are actually using in your application because the default font will be linked with your application and will therefore use up ROM memory.

 © 2020 SEGGER Microcontroller GmbH

12.7 Font API

The table below lists the available font-related routines in alphabetical order within their respective categories. Detailed descriptions can be found in the following sections.

Functions

Routine	Description
SIF file related font functions	
GUI_SIF_CreateFont()	Sets the font to be used by passing a pointer to system independent font data.
GUI_SIF_DeleteFont()	Deletes a font created by GUI_SIF_CreateFont().
TTF file related font functions	
GUI_TTF_CreateFont()	Creates and selects an emWin font by using a TTF font file.
GUI_TTF_CreateFontAA()	Creates and selects an antialised emWin font by using a TTF font file.
GUI_TTF_DestroyCache()	Destroys the cache of the TTF engine.
GUI_TTF_Done()	Frees all dynamically allocated memory of the TTF engine.
GUI_TTF_GetFamilyName()	Returns the family name of the font.
GUI_TTF_GetStyleName()	Returns the style name of the font.
GUI_TTF_SetCacheSize()	Can be used to set the default size of the TTF cache.
XBF file related font functions	
GUI_XBF_CreateFont()	Creates and selects a font by passing a pointer to a callback function, which is responsible for getting data from the XBF font file.
GUI_XBF_DeleteFont()	Deletes a font created by GUI_XBF_CreateFont().
Common font-related functions	
GUI_GetCharDistX()	Returns the width in pixels (X-size) used to display a specified character in the currently selected font.
GUI_GetDefaultFont()	Returns the default currently set default font.
GUI_GetFont()	Returns a pointer to the currently selected font.
GUI_GetFontDistY()	Returns the Y-spacing of the currently selected font.
GUI_GetFontInfo()	Calculates a pointer to a GUI_FONTINFO structure of a particular font.
GUI_GetFontSizeY()	Returns the height in pixels (Y-size) of the currently selected font.
GUI_GetLeadingBlankCols()	Returns the number of leading blank pixel columns in the currently selected font for the given character.
GUI_GetStringDistX()	Returns the X-size used to display a specified string in the currently selected font.
GUI_GetStringDistXEx()	Returns the X-size used to display a number of characters of a string in the currently selected font.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_GetTextExtend()	Calculates the pixel size in X required to draw the given string using the current font.
GUI_GetTrailingBlankCols()	Returns the number of trailing blank pixel columns in the currently selected font for the given character.
GUI_GetYDistOfFont()	Returns the Y-spacing of a particular font.
GUI_GetYSizeOfFont()	Returns the Y-size of a particular font.
GUI_IsInFont()	Evaluates whether a particular font contains a specified character or not.
GUI_SetDefaultFont()	Sets the font to be used by default for text output.
GUI_SetFont()	Sets the font to be used for text output.

Data structures

Structure	Description
GUI_FONTINFO	This structure is used when retrieving information about a font.
GUI_TTF_CS	
GUI_TTF_DATA	Contains the raw data of a TTF font file.

Defines

Group of defines	Description
Font info flags	Flags that define the type of a font.
SIF font types	SIF font types to be used by GUI_SIF_CreateFont().
XBF font types	XBF font types to be used by GUI_XBF_CreateFont().

 © 2020 SEGGER Microcontroller GmbH

12.7.1 SIF file related font functions

12.7.1.1 GUI_SIF_CreateFont()

Description

Sets the font to be used by passing a pointer to system independent font data.

Prototype

```
void GUI_SIF_CreateFont(const void          * pFontData,
                              GUI_FONT      * pFont,
                        const GUI_SIF_TYPE  * pFontType);
```

Parameters

Parameter	Description
pFontData	Pointer to the system independent font data.
pFont	Pointer to a GUI_FONT structure in RAM filled by the function.
pFontType	See a full list of available values under *SIF font types* on page 509.

Additional information

Contrary to the emWin standard fonts which must be compiled and linked with the application program, system independent fonts (SIF) are binary data blocks containing the font information. The Font Converter can be used to create system independent fonts. This tool is not part of the basic package. A short description follows later in this chapter. For details about how to create system independent fonts, refer to the chapter *Font Converter* on page 534.
When using this function emWin needs to fill a GUI_FONT structure with the font information. The user needs to pass a pointer to this structure in the parameter pFont. The contents of this structure must remain valid during the use of the font. The function does not know what kind of font should be created. To tell the function the type of the font to be created it must be passed in the parameter pFontType. This has been done to avoid linkage of code which is not required.

Example

```
static GUI_FONT _Font;  // Font structure in RAM

GUI_SIF_CreateFont(_DownloadedFont, &_Font, GUI_SIF_TYPE_PROP);
GUI_DispString("Hello World!");
```

 © 2020 SEGGER Microcontroller GmbH

12.7.1.2 GUI_SIF_DeleteFont()

Description

Deletes a font pointed by the parameter `pFont`.

Prototype

```
void GUI_SIF_DeleteFont(GUI_FONT * pFont);
```

Parameters

Parameter	Description
`pFont`	Pointer to the font to be deleted.

Additional information

After using a font created with `GUI_SIF_CreateFont()` the font should be deleted if not used anymore.

Example

```
static GUI_FONT _Font;  // Font structure in RAM

GUI_SIF_CreateFont(_DownloadedFont, &_Font, GUI_SIF_TYPE_PROP);
//
// Use the font
//
GUI_SIF_DeleteFont(&_Font);
```

 © 2020 SEGGER Microcontroller GmbH

12.7.2 TTF file related functions

The emWin implementation of TTF file support is based on the FreeType font library from David Turner, Robert Wilhelm and Werner Lemberg. For details, refer to *TrueType Font (TTF) format* on page 470.

12.7.2.1 GUI_TTF_CreateFont()

Description

Creates and selects an emWin font by using a TTF font file.

Prototype

```
int GUI_TTF_CreateFont(GUI_FONT   * pFont,
                       GUI_TTF_CS * pCS);
```

Parameters

Parameter	Description
pFont	Pointer to a GUI_FONT structure in RAM filled by the function.
pCS	Pointer to a GUI_TTF_CS structure containing the creation parameters.

Return value

0 on success
1 on error.

Additional information

When using the function the first time it initializes the TTF engine and the internal cache system. If the cache should use other values as defined per default it needs to be configured before the first call of this function. For details how to configure the cache, refer to GUI_TTF_SetCacheSize().
The internal data cache manages the complete mechanism of creating fonts and caching bitmap data. Font faces are uniquely identified from the cache by the address given in parameter pTTF and the parameter FaceIndex, which normally is 0. If the same font file for example should be used for creating fonts of different sizes the parameter pTTF should point to the same location of a GUI_TTF_DATA structure. The parameter PixelHeight specifies the height of the surrounding rectangle between the glyphs ’g’ and ’f’. The value PixelHeight does not represent the offset between lines.

Example

```
GUI_TTF_CS   Cs0, Cs1;
GUI_TTF_DATA Data;
GUI_FONT     Font0, Font1;
//
// Set parameters for accessing the font file
//
Data.pData      = aTTF;         // Address
Data.NumBytes   = sizeof(aTTF); // Size
//
// Set creation parameters of first font
//
Cs0.pTTF        = &Data;        // Use address of GUI_TTF_DATA
Cs0.PixelHeight = 24;           // Pixel height
Cs0.FaceIndex   = 0;            // Initialize to 0
//
// Set creation parameters of second font
//
Cs1.pTTF        = &Data;        // Use address of GUI_TTF_DATA
```

 © 2020 SEGGER Microcontroller GmbH

```
Cs1.PixelHeight = 48;           // Pixel height
Cs1.FaceIndex   = 0;            // Initialize to 0
//
// Create 2 fonts
//
GUI_TTF_CreateFont(&Font0, &Cs0);
GUI_TTF_CreateFont(&Font1, &Cs1);
//
// Draw something using the fonts
//
GUI_SetFont(&Font0);
GUI_DispString("Hello world\n");
GUI_SetFont(&Font1);
GUI_DispString("Hello world");
```

 © 2020 SEGGER Microcontroller GmbH

12.7.2.2 GUI_TTF_CreateFontAA()

Description

Creates and selects an antialised emWin font by using a TTF font file.

Prototype

```
int GUI_TTF_CreateFontAA(GUI_FONT   * pFont,
                         GUI_TTF_CS * pCS);
```

Parameters

Parameter	Description
pFont	Pointer to a GUI_FONT structure in RAM filled by the function.
pCS	Pointer to a GUI_TTF_CS structure containing the creation parameters.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

12.7.2.3 GUI_TTF_DestroyCache()

Description

This function frees all memory allocated by the TTF cache system and destroys the cache.

Prototype

```
void GUI_TTF_DestroyCache(void);
```

Additional information

The next time `GUI_TTF_CreateFont()` is used emWin automatically creates and initializes a new cache.

 © 2020 SEGGER Microcontroller GmbH

12.7.2.4 GUI_TTF_Done()

Description

This function frees all memory allocated by the TTF engine and its internal cache system.

Prototype

```
void GUI_TTF_Done(void);
```

Additional information

The next time `GUI_TTF_CreateFont()` is used emWin automatically initializes the TTF engine and creates and initializes a new cache.

 © 2020 SEGGER Microcontroller GmbH

12.7.2.5 GUI_TTF_GetFamilyName()

Description

The function returns the font family name defined in the font file.

Prototype

```
int GUI_TTF_GetFamilyName(GUI_FONT * pFont,
                          char     * pBuffer,
                          int        NumBytes);
```

Parameters

Parameter	Description
pFont	Pointer to a GUI_FONT structure which has been created using GUI_TTF_CreateFont().
pBuffer	Buffer to be filled with the family name.
NumBytes	Size of buffer in bytes.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

12.7.2.6 GUI_TTF_GetStyleName()

Description

The function returns the style name (bold, regular, …) defined in the font file.

Prototype

```
int GUI_TTF_GetStyleName(GUI_FONT * pFont,
                         char     * pBuffer,
                         int        NumBytes);
```

Parameters

Parameter	Description
pFont	Pointer to a GUI_FONT structure which has been created using GUI_TTF_CreateFont().
pBuffer	Buffer to be filled with the style name.
NumBytes	Size of buffer in bytes.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

12.7.2.7 GUI_TTF_SetCacheSize()

Description

Sets the size parameters used to create the cache on the first call of `GUI_TTF_CreateFont()`.

Prototype

```
void GUI_TTF_SetCacheSize(unsigned MaxFaces,
                          unsigned MaxSizes,
                          U32      MaxBytes);
```

Parameters

Parameter	Description
`MaxFaces`	Maximum number of font faces the cache should be able to handle simultaneously. 0 selects default value.
`MaxSizes`	Maximum number of size objects the cache should be able to handle simultaneously. 0 selects default value.
`MaxBytes`	Maximum number of bytes used for the bitmap cache. 0 selects default value.

Return value

0 on success
1 on error.

Additional information

If for example 3 font faces should be used, each with 2 sizes, the cache should be able to manage 6 size objects. The default values used by the TTF engine are: 2 faces, 4 size objects and 200K of bitmap data cache.

 © 2020 SEGGER Microcontroller GmbH

12.7.3 XBF file related font functions

12.7.3.1 GUI_XBF_CreateFont()

Description

Creates and selects a font by passing a pointer to a callback function, which is responsible for getting data from the XBF font file.

Prototype

```
int GUI_XBF_CreateFont(      GUI_FONT               * pFont,
                             GUI_XBF_DATA           * pXBF_Data,
                       const GUI_XBF_TYPE           * pFontType,
                             GUI_XBF_GET_DATA_FUNC  * pfGetData,
                             void                   * pVoid);
```

Parameters

Parameter	Description
pFont	Pointer to a GUI_FONT structure in RAM filled by the function.
pXBF_Data	Pointer to a GUI_XBF_DATA structure in RAM filled by the function.
pFontType	See a full list of available values under *XBF font types* on page 510.
pfGetData	Pointer to a callback function which is responsible for getting data from the font file. See prototype below.
pVoid	Application defined pointer passed to the 'GetData' callback function.

Prototype of GUI_XBF_GET_DATA_FUNC

```
int GUI_XBF_GET_DATA_FUNC(U32    Off,
                          U16    NumBytes,
                          void * pVoid,
                          void * pBuffer);
```

The function has to set pBuffer to point to the location the requested data resides in.

Return value

0	on success
1	if font creation fails.

Additional information

The parameter pfGetData should point to an application defined callback routine, which is responsible for getting data from the font. Parameter pVoid is passed to the callback function when requesting font data. It can be used for example to pass a file handle to the callback function.
The function requires pointers to a GUI_FONT structure and a GUI_XBF_DATA structure. The function will fill these structures with font information. It is required, that the contents of these structures remain valid during the usage of the font. The function does not know what kind of XBF font has to be created, so the parameter pFont-Type has to be used to tell the function the type of the font to be created. This has been done to avoid unnecessary linkage of code.
The maximum number of data bytes per character is limited to 200 per default. If the number of characters exceed this limit banding is used to display the remaining characters. This should cover the most requirements. If loading a character with more bytes a warning will be generated in the debug version. The default value can be increased by adding the following define to the file GUIConf.h:

 © 2020 SEGGER Microcontroller GmbH

```
#define GUI_MAX_XBF_BYTES 500 // Sets the maximum number of bytes/chars to 500
```

Example

```
static  GUI_FONT     Font;     // GUI_FONT structure in RAM
static  GUI_XBF_DATA XBF_Data; // GUI_XBF_DATA structure in RAM
static int _cbGetData(U32 Off, U16 NumBytes, void * pVoid, void * pBuffer) {
  //
  // The pVoid pointer may be used to get a file handle
  //
  ...// TBD
  //
  // Set file pointer to the given position
  //
  ...// TBD
  //
  // Read the required number of bytes into the given buffer
  //
  ...// TBD
  //
  // Return 0 on success. Return 1 if the function fails.
  //
}
GUI_XBF_CreateFont(&Font, &XBF_Data, GUI_XBF_TYPE_PROP, _cbGetData, pVoid);
```

 © 2020 SEGGER Microcontroller GmbH

12.7.3.2 GUI_XBF_DeleteFont()

Description

Deletes an XBF font pointed by the parameter `pFont`.

Prototype

```
void GUI_XBF_DeleteFont(GUI_FONT * pFont);
```

Parameters

Parameter	Description
`pFont`	Pointer to the font to be deleted.

Additional information

After using a font created with `GUI_XBF_CreateFont()` the font should be deleted if not used anymore.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.3 GUI_GetCharDistX()

Description

Returns the width in pixels (X-size) used to display a specified character in the currently selected font.

Prototype

```
int GUI_GetCharDistX(U16 c);
```

Parameters

Parameter	Description
c	Character to calculate width from.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.4 GUI_GetDefaultFont()

Description

Returns the default currently set default font.

Prototype

```
GUI_FONT *GUI_GetDefaultFont(void);
```

Return value

This function returns a pointer to the currently set default font.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.5 GUI_GetFont()

Description

Returns a pointer to the currently selected font.

Prototype

```
GUI_FONT *GUI_GetFont(void);
```

Return value

This function returns a pointer to the currently selected font.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.6 GUI_GetFontDistY()

Description

Returns the Y-spacing of the currently selected font.

Prototype

```
int GUI_GetFontDistY(void);
```

Return value

This function returns the Y-spacing of the currently selected font.

Additional information

The Y-spacing is the vertical distance in pixels between two adjacent lines of text. The returned value is the YDist value of the entry for the currently selected font. The returned value is valid for both proportional and monospaced fonts.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.7 GUI_GetFontInfo()

Description

Calculates a pointer to a GUI_FONTINFO structure of a particular font.

Prototype

```
void GUI_GetFontInfo(const GUI_FONT     * pFont,
                           GUI_FONTINFO * pFontInfo);
```

Parameters

Parameter	Description
pFont	Pointer to the font.
pfi	Pointer to a GUI_FONTINFO structure.

Example

Gets the info of GUI_Font6x8. After the calculation FontInfo.Flags contains the flag GUI_FONTINFO_FLAG_MONO.

```
GUI_FONTINFO FontInfo;
GUI_GetFontInfo(&GUI_Font6x8, &FontInfo);
```

 © 2020 SEGGER Microcontroller GmbH

12.7.3.8 GUI_GetFontSizeY()

Description

Returns the height in pixels (Y-size) of the currently selected font.

Prototype

```
int GUI_GetFontSizeY(void);
```

Return value

Size of the currently selected font in pixels.

Additional information

The returned value is the YSize value of the entry for the currently selected font. This value is less than or equal to the Y-spacing returned by the function `GUI_GetFontDistY()`. The returned value is valid for both proportional and monospaced fonts.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.9 GUI_GetLeadingBlankCols()

Description

Returns the number of leading blank pixel columns in the currently selected font for the given character.

Prototype

```
int GUI_GetLeadingBlankCols(U16 c);
```

Parameters

Parameter	Description
c	Character to be used.

Return value

Number of leading blank pixel columns in the currently selected font for the given character. -1 on error.

Example



The result for the character 'B' shown in the screenshot above should be 2.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.10 GUI_GetStringDistX()

Description

Returns the X-size used to display a specified string in the currently selected font.

Prototype

```
int GUI_GetStringDistX(const char * s);
```

Parameters

Parameter	Description
s	Pointer to the string.

Return value

≠ -1 X-size used to display a specified string in the currently selected font.
= -1 Error.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.11 GUI_GetStringDistXEx()

Description

Returns the X-size used to display a number of characters of a string in the currently selected font.

Prototype

```
int GUI_GetStringDistXEx(const char * s,
                         int    n);
```

Parameters

Parameter	Description
s	Pointer to the string.
n	Number of characters counted from the beginning.

Return value

≠ -1 X-size used to display a specified string in the currently selected font.
= -1 Error.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.12 GUI_GetTextExtend()

Description

Calculates the pixel size in X required to draw the given string using the current font.

Prototype

```
void GUI_GetTextExtend(      GUI_RECT * pRect,
                       const char     * s,
                             int        MaxNumChars);
```

Parameters

Parameter	Description
pRect	Pointer to GUI_RECT-structure to store result.
s	Pointer to the string.
Len	Number of characters of the string.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.13 GUI_GetTrailingBlankCols()

Description

Returns the number of trailing blank pixel columns in the currently selected font for the given character.

Prototype

```
int GUI_GetTrailingBlankCols(U16 c);
```

Parameters

Parameter	Description
c	Character to be used.

Return value

Number of trailing blank pixel columns in the currently selected font for the given character. -1 on error.

Example



The result for the character 'B' shown in the screenshot above should be 1.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.14 GUI_GetYDistOfFont()

Description

Returns the Y-spacing of a particular font.

Prototype

```
int GUI_GetYDistOfFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to the font.

Return value

Y-spacing of the font.

Additional information

Please refer to `GUI_GetFontDistY()`.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.15 GUI_GetYSizeOfFont()

Description

Returns the Y-size of a particular font.

Prototype

```
int GUI_GetYSizeOfFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to the font.

Return value

Y-size of the font.

Additional information

Additional information can be found in the description of `GUI_GetFontSizeY()`.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.16 GUI_IsInFont()

Description

Evaluates whether a particular font contains a specified character or not.

Prototype

```
char GUI_IsInFont(const GUI_FONT * pFont,
                        U16        c);
```

Parameters

Parameter	Description
pFont	Pointer to the font.
c	Character to be searched for.

Return value

1 if the character was found.
0 if the character was not found.

Additional information

If the pointer pFont is set to 0, the currently selected font is used.

Example

Evaluates whether the font GUI_FontD32 contains an “X”:

```
if (GUI_IsInFont(&GUI_FontD32, 'X') == 0) {
  GUI_DispString("GUI_FontD32 does not contain 'X'");
}
```

 © 2020 SEGGER Microcontroller GmbH

12.7.3.17 GUI_SetDefaultFont()

Description

Sets the font to be used by default for text output.

Prototype

```
void GUI_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to the font to be selected as default

Additional information

This function is intended to be used in GUI_X_Config(). Defining GUI_DEFAULT_FONT is not mandatory anymore. If there is neither defined GUI_DEFAULT_FONT nor GUI_SetDefault-Font is called, GUI_Font6x8 will be set as the default Font. If none of the emWin fonts shall be used, GUI_DEFAULT_FONT has to be defined by NULL and a custom font needs to be set as default with this function.

 © 2020 SEGGER Microcontroller GmbH

12.7.3.18 GUI_SetFont()

Description

Sets the font to be used for text output.

Prototype

```
GUI_FONT *GUI_SetFont(const GUI_FONT * pNewFont);
```

Parameters

Parameter	Description
pFont	Pointer to the font to be selected and used.

Return value

Returns a pointer to the previously selected font so that it may be buffered.

Example

Displays example text in 3 different sizes, restoring the former font afterwards:

```
const GUI_FONT GUI_FLASH * OldFont;
OldFont = GUI_SetFont(&GUI_Font8x16);                    // Buffer old font
GUI_DispStringAt("This text is 8 by 16 pixels", 0, 0);
GUI_SetFont(&GUI_Font6x8);
GUI_DispStringAt("This text is 6 by 8 pixels", 0, 20);
GUI_SetFont(&GUI_Font8);
GUI_DispStringAt("This text is proportional", 0, 40);
GUI_SetFont(OldFont);                                    // Restore old font
```

Screenshot of above example



Example

Displays text and value in different fonts:

```
GUI_SetFont(&GUI_Font6x8);
GUI_DispString("The result is: ");  // Disp text
GUI_SetFont(&GUI_Font8x8);
GUI_DispDec(42,2);                  // Disp value
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

12.7.4 Data structures

12.7.4.1 GUI_FONTINFO

Description

This structure is used when retrieving information about a font.

Type definition

```
typedef struct {
  U16  Flags;
  U8   Baseline;
  U8   LHeight;
  U8   CHeight;
} GUI_FONTINFO;
```

Structure members

Member	Description
Flags	Flags that define the type of the font. Permitted values are explained in *Font info flags* on page 508.
Baseline	Height of the baseline. The baseline is the line where most, but not all characters are 'placed on'. The lowest part of an 'A' is on the baseline.
LHeight	Height of a small lower case character such as 'a' or 'x'.
CHeight	Height of a small upper case character such as 'A' or 'X'.

See also

- GUI_GetFontInfo()

 © 2020 SEGGER Microcontroller GmbH

12.7.4.2 GUI_TTF_CS

Type definition

```
typedef struct {
  GUI_TTF_DATA * pTTF;
  U32            aImageTypeBuffer[];
  int            PixelHeight;
  int            FaceIndex;
} GUI_TTF_CS;
```

Structure members

Member	Description
pTTF	Pointer to GUI_TTF_DATA structure which contains location and size of font file.
aImageTypeBuffer	Internal use.
PixelHeight	Pixel height of new font. It means the height of the surrounding rectangle between the glyphs ’g’ anf ’f’. Please notice that it is not the distance between two lines of text. With other words the value returned by GUI_GetFontSizeY() is not identically with this value.
FaceIndex	Some font files can contain more than one font face. In case of more than one face this index specifies the zero based face index to be used to create the font. Usually 0.

See also

- GUI_TTF_CreateFont()
- GUI_TTF_CreateFontAA()

 © 2020 SEGGER Microcontroller GmbH

12.7.4.3 GUI_TTF_DATA

Description

Contains the raw data of a TTF font file.

Type definition

```
typedef struct {
  const void * pData;
  U32          NumBytes;
} GUI_TTF_DATA;
```

Structure members

Member	Description
pData	Pointer to TTF font file in addressable memory area.
NumBytes	Size of file in bytes.

See also

- GUI_TTF_CreateFont()

 © 2020 SEGGER Microcontroller GmbH

12.7.5 Defines

12.7.5.1 Font info flags

Description

These flags define of what type a font is. See the chapter *Font types* on page 465 for a detailed explanation of the font types.

Definition

```
#define GUI_FONTINFO_FLAG_PROP       (1 << 0)
#define GUI_FONTINFO_FLAG_MONO       (1 << 1)
#define GUI_FONTINFO_FLAG_AA         (1 << 2)
#define GUI_FONTINFO_FLAG_AA2        (1 << 3)
#define GUI_FONTINFO_FLAG_AA4        (1 << 4)
#define GUI_FONTINFO_FLAG_PROPFRM    (1 << 5)
```

Symbols

Definition	Description
GUI_FONTINFO_FLAG_PROP	Font is proportional.
GUI_FONTINFO_FLAG_MONO	Font is monospaced.
GUI_FONTINFO_FLAG_AA	Font is an antialiased font.
GUI_FONTINFO_FLAG_AA2	Font is an antialiased font with 2bpp anti-aliasing.
GUI_FONTINFO_FLAG_AA4	Font is an antialiased font with 4bpp anti-aliasing.
GUI_FONTINFO_FLAG_PROPFRM	Font is proportional and framed.

 © 2020 SEGGER Microcontroller GmbH

12.7.5.2 SIF font types

Description

Available font type defines to be used by the pFontType parameter in function GUI_SIF_CreateFont().

Definition

```
#define GUI_SIF_TYPE_PROP            &GUI_SIF_APIList_Prop
#define GUI_SIF_TYPE_PROP_EXT        &GUI_SIF_APIList_Prop_Ext
#define GUI_SIF_TYPE_PROP_FRM        &GUI_SIF_APIList_Prop_Frm
#define GUI_SIF_TYPE_PROP_AA2        &GUI_SIF_APIList_Prop_AA2
#define GUI_SIF_TYPE_PROP_AA4        &GUI_SIF_APIList_Prop_AA4
#define GUI_SIF_TYPE_PROP_AA2_EXT    &GUI_SIF_APIList_Prop_AA2_EXT
#define GUI_SIF_TYPE_PROP_AA4_EXT    &GUI_SIF_APIList_Prop_AA4_EXT
```

Symbols

Definition	Description
GUI_SIF_TYPE_PROP	Should be used if the parameter pFont points to a proportional font.
GUI_SIF_TYPE_PROP_EXT	Should be used if the parameter pFont points to an extended proportional font.
GUI_SIF_TYPE_PROP_FRM	Should be used if the parameter pFont points to an extended proportional framed font.
GUI_SIF_TYPE_PROP_AA2	Should be used if the parameter pFont points to a proportional font, which uses 2bpp anti-aliasing.
GUI_SIF_TYPE_PROP_AA4	Should be used if the parameter pFont points to a proportional font, which uses 4bpp anti-aliasing.
GUI_SIF_TYPE_PROP_AA2_EXT	Should be used if the parameter pFont points to an extended proportional font, which uses 2bpp anti-aliasing.
GUI_SIF_TYPE_PROP_AA4_EXT	Should be used if the parameter pFont points to an extended proportional font, which uses 4bpp anti-aliasing.

 © 2020 SEGGER Microcontroller GmbH

12.7.5.3 XBF font types

Description

Available font type defines to be used by the pFontType parameter in function GUI_XBF_CreateFont().

Definition

```
#define GUI_XBF_TYPE_PROP            &GUI_XBF_APIList_Prop
#define GUI_XBF_TYPE_PROP_EXT        &GUI_XBF_APIList_Prop_Ext
#define GUI_XBF_TYPE_PROP_FRM        &GUI_XBF_APIList_Prop_Frm
#define GUI_XBF_TYPE_PROP_AA2_EXT    &GUI_XBF_APIList_Prop_AA2_Ext
#define GUI_XBF_TYPE_PROP_AA4_EXT    &GUI_XBF_APIList_Prop_AA4_Ext
```

Symbols

Definition	Description
GUI_XBF_TYPE_PROP	Should be used if the parameter pFont points to a proportional font.
GUI_XBF_TYPE_PROP_EXT	Should be used if the parameter pFont points to an extended proportional font.
GUI_XBF_TYPE_PROP_FRM	Should be used if the parameter pFont points to an extended framed proportional font.
GUI_XBF_TYPE_PROP_AA2_EXT	Should be used if the parameter pFont points to an extended proportional font, which uses 2bpp anti-aliasing.
GUI_XBF_TYPE_PROP_AA4_EXT	Should be used if the parameter pFont points to an extended proportional font, which uses 4bpp anti-aliasing.

 © 2020 SEGGER Microcontroller GmbH

12.8 Character sets

12.8.1 ASCII

emWin supports the full set of ASCII characters. These are the following 96 characters from 32 to 127:

Hex	0	1	2	3	4	5	6	7	8	9	A	B	C	D	E	F
2x		!	"	#	$	%	&	'	(	)	*	+	,	-	.	/
3x	0	1	2	3	4	5	6	7	8	9	:	;	<	=	>	?
4x	@	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O
5x	P	Q	R	S	T	U	V	W	X	Y	Z	[	\	]	^	_
6x	`	a	b	c	d	e	f	g	h	i	j	k	l	m	n	o
7x	p	q	r	s	t	u	v	w	x	y	z	{	|	}	~	

Unfortunately, as ASCII stands for American Standard Code for Information Interchange, it is designed for American needs. It does not include any of the special characters used in European languages, such as Ä, Ö, Ü, á, à, and others. There is no single standard for these "European extensions" of the ASCII set of characters—several different ones exist. The one used on the Internet and by most Windows programs is ISO 8859-1, a superset of the ASCII set of characters.

12.8.2 ISO 8859-1 Western Latin character set

emWin supports the ISO 8859-1, which defines characters as listed below:

Code	Description	Char
160	Non-breaking space	
161	Inverted exclamation mark	¡
162	Cent sign	¢
163	Pound sign	£
164	Currency sign	¤
165	Yen sign	¥
166	Broken bar	¦
167	Section sign	§
168	Diaeresis (Umlaut)	¨
169	Copyright sign	©
170	Feminine Ordinal Indicator	ª
171	Left-pointing double angle quotation mark (Guillemet)	«
172	Not sign	¬
173	Soft hyphen	
174	Registered sign	®
175	Macron accent	¯
176	Degree symbol	°
177	Plus-minus sign	±
178	Superscript two	²
179	Superscript three	³
180	Acute accent	´
181	Micro sign	µ

 © 2020 SEGGER Microcontroller GmbH

Code	Description	Char
182	Pilcrow sign	¶
183	Middle dot	·
184	Cedilla	¸
185	Superscript one	¹
186	Masculine ordinal indicator	º
187	Right-pointing double angle quotation mark (Guillemet)	»
188	Vulgar fraction one quarter	¼
189	Vulgar fraction one half	½
190	Vulgar fraction three quarters	¾
191	Inverted Question Mark	¿
192	Latin Capital Letter A with grave	À
193	Latin Capital letter A with acute	Á
194	Latin Capital letter A with circumflex	Â
195	Latin Capital letter A with tilde	Ã
196	Latin Capital letter A with diaeresis	Ä
197	Latin Capital letter A with ring above	Å
198	Latin Capital letter Æ	Æ
199	Latin Capital letter C with cedilla	Ç
200	Latin Capital letter E with grave	È
201	Latin Capital letter E with acute	É
202	Latin Capital letter E with circumflex	Ê
203	Latin Capital letter E with diaeresis	Ë
204	Latin Capital letter I with grave	Ì
205	Latin Capital letter I with acute	Í
206	Latin Capital letter I with circumflex	Î
207	Latin Capital letter I with diaeresis	Ï
208	Latin Capital letter Eth	Ð
209	Latin Capital letter N with tilde	Ñ
210	Latin Capital letter O with grave	Ò
211	Latin Capital letter O with acute	Ó
212	Latin Capital letter O with circumflex	Ô
213	Latin Capital letter O with tilde	Õ
214	Latin Capital letter O with diaeresis	Ö
215	Multiplication sign	×
216	Latin Capital letter O with stroke	Ø
217	Latin Capital letter U with grave	Ù
218	Latin Capital letter U with acute	Ú
219	Latin Capital Letter U with circumflex	Û
220	Latin Capital Letter U with diaeresis	Ü
221	Latin Capital Letter Y with acute	Ý
222	Latin Capital Letter Thorn	Þ
223	Latin Small Letter sharp S	ß
224	Latin Small Letter A with grave	à

 © 2020 SEGGER Microcontroller GmbH

Code	Description	Char
225	Latin Small Letter A with acute	á
226	Latin Small Letter A with circumflex	â
227	Latin Small Letter A with tilde	ã
228	Latin Small Letter A with diaeresis	ä
229	Latin Small Letter A with ring above	å
230	Latin Small Letter Æ	æ
231	Latin Small Letter C with cedilla	ç
232	Latin Small Letter E with grave	è
233	Latin Small Letter E with acute	é
234	Latin Small Letter E with circumflex	ê
235	Latin Small Letter E with diaeresis	ë
236	Latin Small Letter I with grave	ì
237	Latin Small Letter I with acute	í
238	Latin Small Letter I with circumflex	î
239	Latin Small Letter I with diaeresis	ï
240	Latin Small Letter Eth	ð
241	Latin Small Letter N with tilde	ñ
242	Latin Small Letter O with grave	ò
243	Latin Small Letter O with acute	ó
244	Latin Small Letter O with circumflex	ô
245	Latin Small Letter O with tilde	õ
246	Latin Small Letter O with diaeresis	ö
247	Division sign	÷
248	Latin Small Letter O with stroke	ø
249	Latin Small Letter U with grave	ù
250	Latin Small Letter U with acute	ú
251	Latin Small Letter U with circumflex	û
252	Latin Small Letter U with diaeresis	ü
253	Latin Small Letter Y with acute	ý
254	Latin Small Letter Thorn	þ
255	Latin Small Letter Y with diaeresis	ÿ

12.8.3 Unicode

Unicode is the ultimate in character coding. It is an international standard based on ASCII and ISO 8859-1. Contrary to ASCII, UNICODE requires 16-bit characters because all characters have their own code. Currently, more than 30,000 different characters are defined. However, not all of the character images are defined in emWin. It is the responsibility of the user to define these additional characters.

 © 2020 SEGGER Microcontroller GmbH

12.9 Standard fonts

emWin is shipped with a selection of fonts which should cover most of your needs. The standard font package contains monospaced and proportional fonts in different sizes and styles. **Monospaced fonts** are fonts with a fixed character width, in which all characters have the same width in pixels. **Proportional fonts** are fonts in which each character has its own individual pixel-width. The following sections provide an overview of emWin standard fonts.

12.9.1 Font identifier naming convention

All standard fonts are named as follows. The components of the naming convention are explained in the table below:

```
GUI_Font[<style>][<width>x]<height>[x<MagX>x<MagY>][H][B][_<characterset>]
```

Element	Description
GUI_Font	Standard prefix for all fonts shipped with emWin.
<style>	Specifies a non-standard font style. Example: Comic style in GUI_FontComic18B_ASCII.
<width>	Width of characters, contained only in monospaced fonts.
<height>	Height of the font in pixels.
<MagX>	Factor of magnification in X, contained only in magnified fonts.
<MagY>	Factor of magnification in Y, contained only in magnified fonts.
H	Abbreviation for “high”. Only used if there is more than one font with the same height. It means that the font appears “higher” than other fonts.
B	Abbreviation for “bold”. Used in bold fonts.
<characterset>	Specifies the contents of characters: ASCII: Only ASCII characters 0x20-0x7E (0x7F). 1: ASCII characters and European extensions 0xA0 - 0xFF. HK: Hiragana and Katakana. 1HK: ASCII, European extensions, Hiragana and Katakana. D: Digit fonts, character set: +-.0123456789.

Example 1

`GUI_Font16_ASCII`

Element	Description
GUI_Font	Standard font prefix.
16	Height in pixels.
ASCII	Font contains ASCII characters only.

Example 2

`GUI_Font8x15B_ASCII`

Element	Description
GUI_Font	Standard font prefix.
8	Width of characters.
x15	Height in pixels.
B	Bold font.
ASCII	Font contains ASCII characters only.

 © 2020 SEGGER Microcontroller GmbH

Example 3

`GUI_Font8x16x1x2`

Element	Description
`GUI_Font`	Standard font prefix.
`8`	Width of characters.
`x16`	Height in pixels.
`x1`	Magnification factor in X.
`x2`	Magnification factor in Y.

12.9.2 Font file naming convention

The names for the font files are similar to the names of the fonts themselves. The files are named as follows:

```
F[<width>]<height>[H][B][<characterset>]
```

Element	Description
`F`	Standard prefix for all fonts files shipped with emWin.
`<width>`	Width of characters, contained only in monospaced fonts.
`<height>`	Height of the font in pixels.
`H`	Abbreviation for “high”. Only used if there is more than one font with the same height. It means that the font appears “higher” than other fonts.
`B`	Abbreviation for “bold”. Used in bold fonts.
`<characterset>`	Specifies the contents of characters: ASCII: Only ASCII characters `0x20-0x7E` (`0x7F`). 1: ASCII characters and European extensions `0xA0 - 0xFF`. HK: Hiragana and Katakana. 1HK: ASCII, European extensions, Hiragana and Katakana. D: Digit fonts.

12.9.3 Measurement, ROM-size and character set of fonts

The following sections describe the standard fonts shipped with emWin. For each font there is a measurement diagram, an overview of all characters included and a table containing the ROM size in bytes and the font files required for use.

The following parameters are used in the measurement diagrams:

Element	Description
`F`	Size of font in Y.
`B`	Distance of base line from the top of the font.
`C`	Height of capital characters.
`L`	Height of lowercase characters.
`U`	Size of underlength used by letters such as “g”, “j” or “y”.

12.9.4 Proportional fonts

12.9.4.1 Overview

The following screenshot gives an overview of all available proportional fonts:

 © 2020 SEGGER Microcontroller GmbH



12.9.4.2 Font details

The following table shows the measurement, ROM size and used files of the fonts:

 © 2020 SEGGER Microcontroller GmbH

Font name	Measurement	ROM size in bytes	Used files
GUI_Font8_ASCII	F: 8, B: 7, C: 7, L: 5, U: 1	1562	F08_ASCII.c
GUI_Font8_1	F: 8, B: 7, C: 7, L: 5, U: 1	1562 + 1586	F08_ASCII.c F08_1.c
GUI_Font10_ASCII	F: 10, B: 9, C: 8, L: 6, U: 1	1800	F10_ASCII.c
GUI_Font10_1	F: 10, B: 9, C: 8, L: 6, U: 1	1800 + 2456	F10_ASCII.c F10_1.c
GUI_Font10S_ASCII	F: 10, B: 8, C: 6, L: 4, U: 2	1760	F10S_ASCII.c
GUI_Font10S_1	F: 10, B: 8, C: 6, L: 4, U: 2	1760 + 1770	F10S_ASCII.c F10S_1.c
GUI_Font13_ASCII	F: 13, B: 11, C: 8, L: 6, U: 2	2076	F13_ASCII.c
GUI_Font13_1	F: 13, B: 11, C: 8, L: 6, U: 2	2076 + 2149	F13_ASCII.c F13_1.c
GUI_Font13B_ASCII	F: 13, B: 11, C: 8, L: 6, U: 2	2222	F13B_ASCII.c
GUI_Font13B_1	F: 13, B: 11, C: 8, L: 6, U: 2	2222 + 2216	F13B_ASCII.c F13B_1.c
GUI_Font13H_ASCII	F: 13, B: 11, C: 9, L: 7, U: 2	2232	F13H_ASCII.c
GUI_Font13H_1	F: 13, B: 11, C: 9, L: 7, U: 2	2232 + 2291	F13H_ASCII.c F13H_1.c
GUI_Font13HB_ASCII	F: 13, B: 11, C: 9, L: 7, U: 2	2690	F13HB_ASCII.c
GUI_Font13HB_1	F: 13, B: 11, C: 9, L: 7, U: 2	2690 + 2806	F13HB_ASCII.c F13HB_1.c
GUI_Font16_ASCII	F: 16, B: 13, C: 10, L: 7, U: 3	2714	F16_ASCII.c
GUI_Font16_1	F: 16, B: 13, C: 10, L: 7, U: 3	2714 + 3850	F16_ASCII.c F16_1.c
GUI_Font16_HK	F: 16, B: 13, C: 10, L: 7, U: 3	6950	F16_HK.c
GUI_Font16_1HK	F: 16, B: 13, C: 10, L: 7, U: 3	120 + 6950 + 2714 + 3850	F16_1HK.c F16_HK.c F16_ASCII.c F16_1.c
GUI_Font16B_ASCII	F: 16, B: 13, C: 10, L: 7, U: 3	2690	F16B_ASCII.c
GUI_Font16B_1	F: 16, B: 13, C: 10, L: 7, U: 3	2690 + 2790	F16B_ASCII.c F16B_1.c
GUI_FontComic18B_ASCII	F: 18, B: 15, C: 12, L: 9, U: 3	3572	FComic18B_ASCII.c
GUI_FontComic18B_1	F: 18, B: 15, C: 12, L: 9, U: 3	3572 + 4334	FComic18B_ASCII.c FComic18B_1.c
GUI_Font20_ASCII	F: 20, B: 16, C: 13, L: 10, U: 4	4044	F20_ASCII.c
GUI_Font20_1	F: 20, B: 16, C: 13, L: 10, U: 4	4044 + 4244	F20_ASCII.c F20_1.c
GUI_Font20B_ASCII	F: 20, B: 16, C: 13, L: 10, U: 4	4164	F20B_ASCII.c
GUI_Font20B_1	F: 20, B: 16, C: 13, L: 10, U: 4	4164 + 4244	F20B_ASCII.c F20B_1.c
GUI_Font24_ASCII	F: 24, B: 20, C: 17, L: 13, U: 4	4786	F24_ASCII.c
GUI_Font24_1	F: 24, B: 20, C: 17, L: 13, U: 4	4786 + 5022	F24_ASCII.c F24_1.c
GUI_Font24B_ASCII	F: 24, B: 19, C: 15, L: 11, U: 5	4858	F24B_ASCII.c
GUI_Font24B_1	F: 24, B: 19, C: 15, L: 11, U: 5	4858 + 5022	F24B_ASCII.c F24B_1.c

 © 2020 SEGGER Microcontroller GmbH

Font name	Measurement	ROM size in bytes	Used files
GUI_FontComic24B_ASCII	F: 24, B: 20, C: 17, L: 13, U: 4	6146	FComic24B_ASCII.c
GUI_FontComic24B_1	F: 24, B: 20, C: 17, L: 13, U: 4	6146 + 5598	FComic24B_ASCII.c FComic24B_1.c
GUI_Font32_ASCII	F: 32, B: 26, C: 20, L: 15, U: 6	7234	F32_ASCII.c
GUI_Font32_1	F: 32, B: 26, C: 20, L: 15, U: 6	7234 + 7734	F32_ASCII.c F32_1.c
GUI_Font32B_ASCII	F: 32, B: 25, C: 20, L: 15, U: 7	7842	F32B_ASCII.c
GUI_Font32B_1	F: 32, B: 25, C: 20, L: 15, U: 7	7842 + 8118	F32B_ASCII.c F32B_1.c

12.9.4.3 Characters

The following shows all characters of all proportional standard fonts:

GUI_Font8_ASCII



GUI_Font8_1



GUI_Font10_ASCII



GUI_Font10_1



GUI_Font10S_ASCII



GUI_Font10S_1



GUI_Font13_ASCII



GUI_Font13_1



 © 2020 SEGGER Microcontroller GmbH

GUI_Font13B_ASCII



GUI_Font13B_1



GUI_Font13H_ASCII



GUI_Font13H_1



GUI_Font13HB_ASCII



GUI_Font13HB_1



GUI_Font16_ASCII



GUI_Font16_1



 © 2020 SEGGER Microcontroller GmbH

GUI_Font16_HK



GUI_Font16_1HK



GUI_Font16B_ASCII



GUI_Font16B_1



GUI_FontComic18B_ASCII



GUI_FontComic18B_1



 © 2020 SEGGER Microcontroller GmbH

GUI_Font20_ASCII



GUI_Font20_1



GUI_Font20B_ASCII



GUI_Font20B_1



GUI_Font24_ASCII



GUI_Font24_1



 © 2020 SEGGER Microcontroller GmbH

GUI_Font24B_ASCII



GUI_Font24B_1



GUI_FontComic24B_ASCII



GUI_FontComic24B_1



GUI_Font32_ASCII



 © 2020 SEGGER Microcontroller GmbH

GUI_Font32_1



GUI_Font32B_ASCII



GUI_Font32B_1



 © 2020 SEGGER Microcontroller GmbH

12.9.5 Proportional fonts, framed

12.9.5.1 Overview

The following screenshot shows the currently available framed proportional fonts:



12.9.5.2 Font details

The following table shows the measurement, ROM size and used file of the font:

Font name	Measurement	ROM size in bytes	Used files
GUI_Font20F_ASCII	F: 20, B: 19, C: 19, L: 19, U: 1	5248	F20F_ASCII.c

12.9.5.3 Characters

The following shows all characters of the font:

GUI_Font20F_ASCII



12.9.6 Monospaced fonts

12.9.6.1 Overview

The following screenshot gives an overview of all available monospaced fonts:



 © 2020 SEGGER Microcontroller GmbH

12.9.6.2 Font details

The following table shows the measurement, ROM size and used files of the fonts:

Font name	Measurement	ROM size in bytes	Used files
GUI_Font4x6	F: 6, B: 5, C: 5, L: 4, U: 1	620	F4x6.c
GUI_Font6x8	F: 8, B: 7, C: 7, L: 5, U: 1	1840	F6x8.c
GUI_Font6x8_ASCII	F: 8, B: 7, C: 7, L: 5, U: 1	1568	F6x8_ASCII.c
GUI_Font6x8_1	F: 8, B: 7, C: 7, L: 5, U: 1	1568 + 1584	F6x8_ASCII.c F6x8_1.c
GUI_Font6x9	F: 9, B: 7, C: 7, L: 5, U: 2	1840 (same ROM location as GUI_Font8x16)	F6x8.c
GUI_Font8x8	F: 8, B: 7, C: 7, L: 5, U: 1	1840	F8x8.c
GUI_Font8x8_ASCII	F: 8, B: 7, C: 7, L: 5, U: 1	1568	F8x8_ASCII.c
GUI_Font8x8_1	F: 8, B: 7, C: 7, L: 5, U: 1	1568 + 1584	F8x8_ASCII.c F8x8_1.c
GUI_Font8x9	F: 9, B: 7, C: 7, L: 5, U: 2	1840 (same ROM location as GUI_Font8x16)	F8x8.c
GUI_Font8x10_ASCII	F: 10, B: 9, C: 9, L: 7, U: 1	1770	F8x10_ASCII.c
GUI_Font8x12_ASCII	F: 12, B: 10, C: 9, L: 6, U: 2	1962	F8x12_ASCII.c
GUI_Font8x13_ASCII	F: 13, B: 11, C: 9, L: 6, U: 2	2058	F8x13_ASCII.c
GUI_Font8x13_1	F: 13, B: 11, C: 9, L: 6, U: 2	2058 + 2070	F8x13_ASCII.c F8x13_1.c
GUI_Font8x15B_ASCII	F: 15, B: 12, C: 9, L: 7, U: 3	2250	F8x15_ASCII.c
GUI_Font8x15B_1	F: 15, B: 12, C: 9, L: 7, U: 3	2250 + 2262	F8x15B_ASCII.c F8x15B_1.c
GUI_Font8x16	F: 16, B: 12, C: 10, L: 7, U: 4	3304	F8x16.c
GUI_Font8x17	F: 17, B: 12, C: 10, L: 7, U: 5	3304 (same ROM location as GUI_Font8x16)	F8x16.c
GUI_Font8x18	F: 18, B: 12, C: 10, L: 7, U: 6	3304 (same ROM location as GUI_Font8x16)	F8x16.c
GUI_Font8x16x1x2	F: 32, B: 24, C: 20, L: 14, U: 8	3304 (same ROM location as GUI_Font8x16)	F8x16.c
GUI_Font8x16x2x2	F: 32, B: 24, C: 20, L: 14, U: 8	3304 (same ROM location as GUI_Font8x16)	F8x16.c
GUI_Font8x16x3x3	F: 48, B: 36, C: 30, L: 21, U: 12	3304 (same ROM location as GUI_Font8x16)	F8x16.c
GUI_Font8x16_ASCII	F: 16, B: 12, C: 10, L: 7, U: 4	3572 + 4334	F8x16_ASCII.c
GUI_Font8x16_1	F: 16, B: 12, C: 10, L: 7, U: 4	4044	F8x16_ASCII.c F8x16_1.c

12.9.6.3 Characters

The following shows all characters of all monospaced standard fonts:

 © 2020 SEGGER Microcontroller GmbH

GUI_Font4x6



GUI_Font6x8



GUI_Font6x8_ASCII



GUI_Font6x8_1



GUI_Font6x9



GUI_Font8x8



GUI_Font8x8_ASCII



GUI_Font8x8_1



GUI_Font8x9



GUI_Font8x10_ASCII



GUI_Font8x12_ASCII



 © 2020 SEGGER Microcontroller GmbH

GUI_Font8x13_ASCII



GUI_Font8x13_1



GUI_Font8x15B_ASCII



GUI_Font8x15B_1



GUI_Font8x16



GUI_Font8x17



GUI_Font8x18



 © 2020 SEGGER Microcontroller GmbH

GUI_Font8x16x1x2



GUI_Font8x16x2x2



 © 2020 SEGGER Microcontroller GmbH

GUI_Font8x16x3x3



GUI_Font8x16_ASCII



GUI_Font8x16_1



12.9.7 Digit fonts (proportional)

12.9.7.1 Overview

The following screenshot gives an overview of all available proportional digit fonts:

 © 2020 SEGGER Microcontroller GmbH



12.9.7.2 Font details

The following table shows the measurement, ROM size and used files of the fonts:

Font name	Measurement	ROM size in bytes	Used files
GUI_FontD32	F: 32, C: 31	1574	FD32.c
GUI_FontD48	F: 48, C: 47	3512	FD48.c
GUI_FontD64	F: 64, C: 63	5384	FD64.c
GUI_FontD80	F: 80, C: 79	8840	FD80.c

12.9.7.3 Characters

The following shows all characters of all proportional digit fonts:

GUI_FontD32



GUI_FontD48



 © 2020 SEGGER Microcontroller GmbH

GUI_FontD64



GUI_FontD80



12.9.8 Digit fonts (monospaced)

12.9.8.1 Overview

The following screenshot gives an overview of all available monospaced digit fonts:



 © 2020 SEGGER Microcontroller GmbH

12.9.8.2 Font details

The following table shows the measurement, ROM size and used files of the fonts:

Font name	Measurement	ROM size in bytes	Used files
GUI_FontD24x32	F: 32, C: 31	1606	FD24x32.c
GUI_FontD36x48	F: 48, C: 47	3800	FD36x48.c
GUI_FontD48x64	F: 64, C: 63	5960	FD48x60.c
GUI_FontD60x80	F: 80, C: 79	9800	FD60x80.c

12.9.8.3 Characters

The following shows all characters of all monospaced digit fonts:

GUI_FontD24x32



GUI_FontD36x48



GUI_FontD48x64



 © 2020 SEGGER Microcontroller GmbH

GUI_FontD60x80



 © 2020 SEGGER Microcontroller GmbH

Chapter 13

Font Converter

The Font Converter is a Windows program which allows convenient converting of any PC installed font into an emWin (bitmap) font which can be easily integrated into emWin based applications. PC installed fonts may be protected by copyright or any other intellectual property right of their legal owner. emWin fonts should be defined either as `GUI_FONT` structures in C files or should exist as binary files containing System Independent Fonts (SIF) or External Bitmap Font (XBF). Manual creation of those fonts is possible, but since this would be very time-consuming and inefficient, it is recommended to use the Font Converter instead.

The Font Converter is not part of the emWin Basic package. The full version has to be purchased separately. The emWin Basic package comes with the demo version of the Font Converter which provides full functionality but accurate storage of pixel data. Nevertheless the structure of C file fonts is stored well, so one might have a look at it in order to estimate the possibly saved effort by using the Font Converter.

The Font Converter does not come with any fonts or a permission or license to use any PC installed font for converting purposes. It is users sole responsibility to not infringe upon any third party intellectual property right by making use of the fonts in its application and obtain a license if required by the legal owner of the font.

 © 2020 SEGGER Microcontroller GmbH

13.1 Requirements

The Font Converter is a Windows program, so it can be used only within a windows environment. The source fonts need to meet the following requirements:

- The font is installed in Windows.
- The font is usable in Windows. (e.g. in MS Word)
- The 'Character To Glyph Index Mapping Table' (cmap) of a font file needs at least a legal subtable with a platform ID = 3 (Windows) and an encoding ID = 1 (Unicode).

Screenshot of the Font Converter with a loaded font



 © 2020 SEGGER Microcontroller GmbH

13.2 Creating an emWin font file from a Windows font

The basic procedure for using the Font Converter for creating an emWin font file from an installed Windows font is illustrated below. The steps are explained in detail in the following sections.

Step 1: Application start

As the Font Converter is started it immediately shows the "Font generation options" dialog box. The same dialog box appears if **File ➔ New** (CRTL+N) is chosen from the Font Converter menu bar.



Step 2: Specifying the type of font

In the above screenshot, a font is to be generated in extended mode using Unicode 16 Bit encoding. The anti-aliasing option can be modified only in case a font type is selected which supports anti-aliasing.

Step 3: Specifying the actual font

After confirming the "Font generation options", the "Font" dialog is opened which allows choosing a font, its style and size.
Please note that fonts with a size larger than 255 pixels in any direction can not be created and displayed.
The fonts shown in the selection list depend on MS Windows. In case an installed font is not shown, it might be required to change Windows font settings. Detailed information can be found in the section *Troubleshooting* on page 561.

In this example, a regular-style, 16 pixel Arial font is chosen.

 © 2020 SEGGER Microcontroller GmbH



Step 4: Modifying the font

Detail information on the possibilities to modify the currently loaded font can be found in the section *User Interface* on page 542. Please note that the letter 'a' has to be present in a font to calculate the baseline.

Step 5: Saving the font file

Choosing **File ➔ Save As...** from the menu bar opens the "Save font as" dialog which is shown below. In this dialog the desired format of the font file can be selected:

- C file (*.c)
- System independent font (*.sif)
- External binary font (*.xbf)



 © 2020 SEGGER Microcontroller GmbH

Clicking the **Save** button creates a font file of the selected format at the current location using the specified file name. Detailed information about the font types and how to use them can be found in the chapter *Fonts* on page 463.

 © 2020 SEGGER Microcontroller GmbH

13.3 Font generation options dialog

After starting the program or when choosing the menu point **File ➔ New**, the following dialog automatically occurs:



The selections made here will determine the output mode of the generated font, how it is to be encoded, and how it will be anti-aliased in case an anti-aliased output mode is selected.

13.3.1 Type of font to generate

Type	Description
`Standard`	Creates a 1 bit per pixel font without anti-aliasing.
`Anti-aliased 2bpp`	Creates an anti-aliased font using 2 bits per pixel.
`Anti-aliased 4bpp`	Creates an anti-aliased font using 4 bits per pixel.
`Extended`	Creates a non anti-aliased 1 bit per pixel font with extended character information. This type supports compound characters like they are used in the Thai language.
`Extended framed`	Creates a non anti-aliased 1 bit per pixel font with extended character information with a surrounding frame. A framed font is always drawn in transparent mode regardless of the current settings. The character pixels are drawn in the currently selected foreground color and the frame is drawn in background color.
`Extended anti-aliased 2bpp`	Creates an anti-aliased 2 bit per pixel font with extended character information. Each character has the same height and its own width. The pixel information is saved with 2bpp anti-aliasing information and covers only the areas of the glyph bitmaps.
`Extended anti-aliased 4bpp`	Creates an anti-aliased 4 bit per pixel font with extended character information. Each character has the same height and its own width. The pixel information is saved with 4bpp anti-aliasing information and covers only the areas of the glyph bitmaps.

13.3.2 Encoding

Encoding	Description
`Unicode 16 Bit`	With Unicode encoding, you have access to all characters of a font. Windows font files contain a maximum of 65536 characters. All character codes of the C file are the same as those in the Windows font file.

 © 2020 SEGGER Microcontroller GmbH

Encoding	Description
ASCII 8 Bit + ISO 8859	This encoding mode includes the ASCII codes (0x20 - 0x7F) and the ISO 8859 characters (0xA0 - 0xFF).
SHIFT JIS 8/16 Bit	Shift JIS (Japanese Industry Standard) enables mapping from Unicode to Shift JIS in accordance with the Unicode standard 2. For example, the Katakana letter "KU" is shifted from its Unicode value of 0x30AF to the Shift JIS value of 0x834E, the Kanji character 0x786F is shifted to 0x8CA5 and so on.

13.3.3 Antialiasing

You can choose between two ways of anti-aliasing. This choice only applies when an anti-aliased font type has been selected.

Antialiasing	Description
Using OS	The operating system is used to do the anti-aliasing. The resulting characters appear exactly the same as in any other windows application where anti-aliased characters are displayed.
Internal	The internal anti-aliasing routines of the Font Converter are used to do the anti-aliasing. The resulting characters are more exact with regard to proportions.

Showcase

Font Type	Black On White	White On Black
Standard (no anti-aliasing) 1 bpp 2 shades		
Low-quality (anti-aliased) 2 bpp 4 shades		
High-quality (anti-aliased) 4 bpp 16 shades		

 © 2020 SEGGER Microcontroller GmbH

13.4 Font Dialog

The Font Dialog appears after the font generation options have been confirmed:



This dialog allows selecting a font which has to be used in the target application. Confirming this dialog using the 'OK' button makes the Font Converter load the included characters and display it in the main user interface.

Note

Fonts which are legally owned by third parties may require a valid license in order to use them in a target system. emWin does not come with licenses for third party fonts.

All fonts included in emWin can be used according to the license under which emWin was provided. Detailed listings of those fonts and the included character sets can be found under *Standard fonts* on page 514.

13.4.1 Font, Font Style, and Size

These menus are used to select the particular font to be converted. The size of the font is specified in pixels.

13.4.2 Script

The Script box is used to select the character set which should be mapped down from Unicode into the first 256 characters in accordance with ISO 8859. It only applies when using the 8 Bit ASCII + ISO 8859 encoding mode.

13.4.3 Unit of Size

This option button can be used to set 'Points' or 'Pixels' as measuring unit. Please note that emWin does not know something about the unit 'Points' whereas most of other PC applications use the point size for specifying the font size. The Font Converter uses the operating system for getting the desired font resource. Please note that the font mapper of the operating system is not able to create each font in each desired pixel height. In these cases the font mapper of the operating system creates the nearest possible pixel height. This is not a bug of the Font Converter.

 © 2020 SEGGER Microcontroller GmbH

13.5 User Interface

After clicking OK in the Font dialog box, the main user interface of the Font Converter appears, loaded with the previously selected font. You may convert the font into a C file immediately if you wish or edit its appearance first.
The Font Converter is divided into two areas. In the upper area, all font characters appear scaled 1:1 as they will be displayed on your target device. Disabled characters are shown with a gray background. Per default all character codes which are not included in the chosen font are disabled. For example, many fonts do not include character codes from 0x00 to 0x1F and 0x7F to 0x9F, so these codes are grayed. The current character is displayed in a magnified scale on the left side of the lower area. Additional information about the font and the current character can be seen on the right side. If you want to modify the character data, you must first activate the lower area, either by pressing the <TAB> key or by simply clicking in the area.

13.5.1 Selecting the current character

Characters may be selected:

- by using the keys <UP>, <DOWN>, <LEFT>, <RIGHT>, <PGUP>, <PGDOWN>, <POS1> or <END>
- by using the scroll bars
- by clicking a character with the left mouse button

13.5.2 Toggling character status

Use the right mouse button to toggle the status of a specific character or to enable/disable an entire row of characters. The menu point **Edit ➔ Toggle activation** as well as the <SPACE> key will toggle the status of the current character.



If you need to change the status of a particular range of characters, choose **Edit ➔ Enable range of characters** or **Edit ➔ Disable range of characters** from the menu. The range to be enabled or disabled is then specified in a dialog box using hexadecimal character values. To disable all characters, select **Edit ➔ Disable all characters** from the menu.



13.5.3 Selecting pixels

When the lower area of the user interface is activated, you can move through the pixels with the cursor, either by using the <UP>, <DOWN>, <LEFT> and <RIGHT> keys or by clicking on the pixels with the left mouse button.

 © 2020 SEGGER Microcontroller GmbH

13.5.4 Modifying character bits

In the lower area you can use the <SPACE> key to invert the currently selected bit. In anti-aliased mode, you can increase and decrease the intensity of a pixel with the keys < +> and <->.



The status bar displays the intensity of the current pixel as follows:

Index of pixel [3, 3] = 4

13.5.5 Operations

The following size / shift / move operations are available:

Size operations

The size of a character (the font) may be modified by selecting **Edit → Insert → Right**, **Left**, **Top**, **Bottom** or **Edit → Delete → Right**, **Left**, **Top**, **Bottom** from the menu, or by using the toolbar:

Button	Operation
	Add one pixel to the right.
	Add one pixel to the left.
	Add one pixel at the top.
	Add one pixel at the bottom.
	Delete one pixel from the right.
	Delete one pixel to the left.
	Delete one pixel at the top.
	Delete one pixel at the bottom.

 © 2020 SEGGER Microcontroller GmbH

Shift operations

Choose **Edit ➔ Shift ➔ Right**, **Left**, **Up**, **Down** from the menu to shift the bits of the current character in the respective direction, or use the toolbar:

Button	Operation
	Shift all pixels right.
	Shift all pixels left.
	Shift all pixels up.
	Shift all pixels down.

Move operations (extended font format only)

Choose **Edit ➔ Move ➔ Right**, **Left**, **Up**, **Down** from the menu to move the character position in the respective direction, or use the toolbar:

Button	Operation
	Move image to the right.
	Move image to the left.
	Move image up.
	Move image down.

Change cursor distance (extended font format only)

Choose `Edit/Cursor distance/Increase`, `Decrease` from the menu to move the character position in the respective direction, or use the toolbar:

Button	Operation
	Increase cursor distance.
	Decrease cursor distance.

Change font height (extended font format only)

Choose **Edit ➔ Font height ➔ [Insert, Delete] [top, bottom]** from the menu to add or remove a row to or from the font, or use the toolbar:

Button	Operation
	Insert a row at the top of the font.
	Insert a row at the bottom of the font.
	Delete a row from the top of the font.
	Delete a row from the bottom of the font.

 © 2020 SEGGER Microcontroller GmbH

13.5.5.1 Modifying the viewing mode

The view mode may be changed by selecting the following options from the menu:

View/All Characters

If enabled (standard), all characters are shown. If disabled, only the rows with at least one enabled character are shown.

Button	Operation
	Toggles viewing mode.

 © 2020 SEGGER Microcontroller GmbH

13.6 Options

Compatibility options

The Font Converter is able to create font files for all versions of emWin. Because there have been a few small changes of the font format from the emWin version 3.50 to the version 3.52, the C font files for these versions should be slightly different to avoid compiler warnings or compiler errors.
Use the command **Options ➔ Compatibility** to get into the following dialog:



Magnification options

The Font Converter is able to save the font data in a magnified format. Use the command **Options ➔ Magnification** to get into the following dialog:



A magnification factor for the X and the Y axis can be specified here. If for example the magnification factor for the Y axis is 2 and the height of the current font data is 18, the font height in the font file will be 36. The magnification in X works similar. After saving the font in a magnified format a short message is shown to inform the user, that the saved font is magnified:



Logging

Logging of commands can be enabled or disabled using the command **Options ➔ Logging**:



 © 2020 SEGGER Microcontroller GmbH

When logging is enabled the C files contain a history of the commands which has been used to modify the font file.

Antialiasing

When using 'Internal anti-aliasing' it is recommended to enable `Suppress optimization`. This makes sure, that the horizontal and vertical alignment of the characters fit to each other:



The option `Enable gamma correction for AA2 and AA4` should be disabled. When the option is enabled the anti-aliased pixels of the characters will appear a little more darker.

 © 2020 SEGGER Microcontroller GmbH

13.7 Saving the font

The Font Converter can create C font files or system independent font data files. Details about the SIF format can be found under *System Independent Font (SIF) format* on page 467.

13.7.1 Creating a C file

When you are ready to generate a C file, simply select **File ➔ Save As** from the Font Converter menu, specify a destination and name for the file, choose the C file format and click **Save**. A C file will automatically be created.
The default setting for the filename is built by the name of the source font and the current height in pixels. For example, if the name of the source font is "Example" and the pixel height is 10, the default filename would be `Example10.c`. If you keep this default name when generating a C file, the resulting name of the font will be **`GUI_FontExample10.c`**.
Examples of C files generated from fonts can be found in the sub chapter *Font Examples* on page 556.

13.7.2 Creating a System Independent Font (SIF)

When you are ready to generate the file, simply select **File ➔ Save As** from the Font Converter menu, specify a destination and name for the file, choose the System independent font format and click **Save**. A system independent font file will automatically be created.
This file does not contain C structures which can be compiled with emWin but binary font data, which can be used as described in *System Independent Font (SIF) format* on page 467.

13.7.3 Creating an External Binary Font (XBF)

When you are ready to generate the file, simply select **File ➔ Save As** from the Font Converter menu, specify a destination and name for the file, choose the External binary font format and click **Save**. An external binary font file will automatically be created.
This file does not contain C structures which can be compiled with emWin but binary font data, which can be used as described in *External Bitmap Font (XBF) format* on page 467.

 © 2020 SEGGER Microcontroller GmbH

13.8 Loading and modifying a C font file

The Font Converter is able to open existing font files and to modify their font data. The tool can only open C font files generated by the Font Converter. If the C font files have been modified manually, it can not be guaranteed, that they can be opened by the Font Converter.

Step 1: Starting the application

The Font Converter is opened and automatically displays the Font generation options dialog box. In order to load an existing C font file, the "Font generation options" dialog should be closed.

Step 2: Loading an existing C file

The desired C font file can be opened by selecting **File ➔ Load 'C' file...** entry in the menu bar. The "Select 'C' file" dialog can be used to navigate through the file system in order to chose a 'C' font file which was previously created using the Font Converter. Not all of the font files which are shipped with emWin were created using the Font Converter. According to that not all of those can be reused.

 © 2020 SEGGER Microcontroller GmbH

13.9 Loading Glyph (B)itmap (D)istribution (F)ormat

That standard has been defined by Adobe 1993. Because there exist a large number of fonts that format, mainly in the Unix-world, the FontConverter has an option for loading BDF font files. That can be done by selecting **File ➔ Load 'BDF' file...**.

 © 2020 SEGGER Microcontroller GmbH

13.10 Merging fonts with existing C font files

The Font Converter is able to add the content of an existing C font file to the current font data. Once a font is loaded via **File ➔ Load 'C' file...** or created by **File ➔ New** a C font file can be merged to it using **File ➔ Merge 'C' file...**. The Font Converter requires the fonts to be of the same size, so the merging can be processed properly.

Step 1: Loading an existing font or creating a new one

This step was already described in previous sections. In this example the existing font contains the characters A-F (`0x41 - 0x46`).



Step 2: Merging a C file

The desired C font file can be merged by selecting **File ➔ Merge 'C' file...** entry in the menu bar. The *Select 'C' file* dialog can be used to navigate through the file system in order to chose a C font file to merge which was previously created using the Font Converter. Not all of the font files which are shipped with emWin were created using the Font Converter. According to that not all of those can be reused.

The characters included in the merged font will be shown and enabled. In this example the characters a-f (`0x61 - 0x66`) are merged to the existing font. The resulting font can be edited and saved as a new font file.

 © 2020 SEGGER Microcontroller GmbH



 © 2020 SEGGER Microcontroller GmbH

13.11 Pattern files

In order not having to enable every single required character manually, pattern files can be used. Pattern files are simple text files, including the text which has to be displayed in the application. They need to be saved in Unicode format (LE) including a BOM (**B**yte **O**rder **M**ark) at the beginning.

13.11.1 Creating pattern files using Notepad

One option for creating a pattern file is to use `Notepad`, which is part of the `Windows accessories`:

- Copy the text you want to display into the clipboard.
- Open `Notepad.exe`.
- Insert the contents of the clipboard into the Notepad document.
- Use **Format ➔ Font** to choose a font which contains all characters of the text. You can skip this step if you do not want to see the characters.
- Use **File ➔ Save As** to save the pattern file. It is very important that you save the file in text format:



13.11.2 Creating pattern files using the Font Converter

A pattern file may also be created directly in the Font Converter. Select **Edit ➔ Save pattern file** from the menu to create a text file which includes all currently enabled characters.

13.11.3 Enabling characters using a pattern file

It is usually helpful to begin by disabling all characters. Select **Edit ➔ Disable all characters** from the menu if you need to do so. Now choose **Edit ➔ Read pattern file**. After opening the appropriate pattern file, all characters included in the file are enabled. If the pattern file contains characters which are not included in the currently loaded font, a message box will appear.

 © 2020 SEGGER Microcontroller GmbH

13.12 Command line options

13.12.1 Table of commands

The following table shows the available command line options:

Command	Description
create<FONTNAME>,<STYLE>, <HEIGHT>,<TYPE>, <ENCODING>[,<METHOD>]	Create font: <FONTNAME> Name of the font to be used <STYLE> THIN - Creates a thin font THIN_ITALIC - Creates a thin italic font EXTRALIGHT - Creates an extra light font EXTRALIGHT_ITALIC - Creates an extra light italic font LIGHT - Creates a light font LIGHT_ITALIC - Creates a light italic font REGULAR - Creates a regular font REGULAR_ITALIC - Creates a regular italic font MEDIUM - Creates a medium font MEDIUM_ITALIC - Creates a medium italic font SEMIBOLD - Creates a semi bold font SEMIBOLD_ITALIC - Creates a semi bold italic font BOLD - Creates a bold font BOLD_ITALIC - Creates a bold italic font EXTRABOLD - Creates an extra bold font EXTRABOLD_ITALIC - Creates an extra bold italic font HEAVY - Creates a heavy font HEAVY_ITALIC - Creates a heavy italic font <HEIGHT> Height in pixels of the font to be created <TYPE> STD - Standard 1 bpp font AA2 - Anti-aliased font (2bpp) AA4 - Anti-aliased font (4bpp) EXT - Extended font EXT_FRM - Extended framed font EXT_AA2 - Extended font using 2bpp anti-aliasing EXT_AA4 - Extended font using 4bpp anti-aliasing <ENCODING> UC16 - 16 bit Unicode encoding ISO8859 - 8 bit ASCII + ISO8859 JIS - Shift JIS <METHOD> OS - Antialiasing of operating system (default) INTERNAL - Internal anti-aliasing method
edit<ACTION>, <DETAIL>[,<CNT>]	Equivalent to the 'Edit' menu: <ACTION> DEL - Deletes pixels INS - Inserts pixels <DETAIL> TOP - Delete/insert from top BOTTOM - Delete/insert from bottom <CNT> - Number of operations, default is 1
enable[FIRST-LAST>,<STATE>	Enables or disables the given range of characters: <FIRST-LAST> Hexadecimal values separated by a '-' defining the range of characters <STATE> 1 - Enables the given range 0 - Disables the given range

 © 2020 SEGGER Microcontroller GmbH

Command	Description
exit	Exits the application after the job was done.
merge<FILENAME>	Merges the given C file to the current content.
readpattern<FILENAME>	Reads a pattern file: <FILENAME> Name of the pattern file to be read
saveas<FILENAME>,<TYPE>	Saves the font data in a specific format: <FILENAME> File name including extension <TYPE> C - Saves as C file SIF - Saves as System independent font file XBF - Saves as external binary font file
?	Shows all available commands.

Note

- All commands are processed from left to right.
- If using -exit Font Converter will stop execution if an error occurs. The return code in this case is ≠ 0.

13.12.2 Load an existing font file

To load an already existing font, present as c- or xbf-file, call the FontConvert with the filename as first parameter.

```
FonCvt FontFile.xbf
```

13.12.3 Execution examples

```
FontCvt -create"Cordia New",BOLD,32,EXT,UC16
```

Creates an extended bold font of 32 pixels height with Unicode encoding using the font “Cordia New”.

```
FontCvt FontFile.c -enable0-ffff,0 -readpattern"data.txt"
```

Reads the C font file FontFile.c, disables all characters and reads a pattern file.

 © 2020 SEGGER Microcontroller GmbH

13.13 Font Examples

This section provides examples of C files generated by the Font Converter in standard, 2bpp anti-aliased and 4bpp anti-aliased mode, respectively.

13.13.1 Resulting C code, standard mode

The following is an example of a C file in standard mode:

```
/*
  C-file generated by Font Converter for emWin version 3.04
  Compiled:       Dec 13 2005 at 12:51:50
  C-file created: Dec 21 2005 at 12:42:57
  Copyright (C) 1998-2005
  Segger Microcontroller Systeme GmbH
  www.segger.com
  Solutions for real time microcontroller applications
  Source file: Sample10.c
  Font:        Arial
  Height:      10
*/
#include "GUI.H"
#ifndef GUI_CONST_STORAGE
  #define GUI_CONST_STORAGE const
#endif
/* The following line needs to be included in any file selecting the
   font. A good place would be GUIConf.H
*/
extern GUI_CONST_STORAGE GUI_FONT GUI_FontSample10;
/* Start of unicode area <Basic Latin> */
GUI_CONST_STORAGE unsigned char acFontSample10_0041[10] = { /* code 0041 */
  ________,
  ___X____,
  __X_X___,
  __X_X___,
  __X_X___,
  _X___X__,
  _XXXXX__,
  X_____X_,
  X_____X_,
  ________};
GUI_CONST_STORAGE unsigned char acFontSample10_0061[10] = { /* code 0061 */
  ________,
  ________,
  ________,
  _XXX____,
  X___X___,
  _XXXX___,
  X___X___,
  X__XX___,
  _XX_X___,
  ________};
GUI_CONST_STORAGE GUI_CHARINFO GUI_FontSample10_CharInfo[2] = {
   {   8,   8,  1, acFontSample10_0041 } /* code 0041 */
  ,{   6,   6,  1, acFontSample10_0061 } /* code 0061 */
};
GUI_CONST_STORAGE GUI_FONT_PROP GUI_FontSample10_Prop2 = {
   97                        /* first character               */
  ,97                        /* last character                */
  ,&GUI_FontSample10_CharInfo[1] /* address of first character    */
  ,(GUI_CONST_STORAGE GUI_FONT_PROP*)0  /* pointer to next GUI_FONT_PROP */
};
GUI_CONST_STORAGE GUI_FONT_PROP GUI_FontSample10_Prop1 = {
   65                        /* first character               */
  ,65                        /* last character                */
  ,&GUI_FontSample10_CharInfo[0] /* address of first character    */
```

 © 2020 SEGGER Microcontroller GmbH

```
  ,&GUI_FontSample10_Prop2      /* pointer to next GUI_FONT_PROP */
};
GUI_CONST_STORAGE GUI_FONT GUI_FontSample10 = {
   GUI_FONTTYPE_PROP /* type of font    */
  ,10                /* height of font  */
  ,10                /* space of font y */
  ,1                /* magnification x */
  ,1                /* magnification y */
  ,&GUI_FontSample10_Prop1
};
```

13.13.2 Resulting C code, 2 bpp anti-aliased mode

The following is an example of a C file in 2 bpp anti-aliased mode:

```
/*
  C-file generated by Font Converter for emWin version 3.04
  Compiled:       Dec 13 2005 at 12:51:50
  C-file created: Dec 21 2005 at 12:42:57
  Copyright (C) 1998-2005
  Segger Microcontroller Systeme GmbH
  www.segger.com
  Solutions for real time microcontroller applications
  Source file: Sample10.c
  Font:        Arial
  Height:      14
*/
#include "GUI.H"
#ifndef GUI_CONST_STORAGE
  #define GUI_CONST_STORAGE const
#endif
/* The following line needs to be included in any file selecting the
   font. A good place would be GUIConf.H
*/
extern GUI_CONST_STORAGE GUI_FONT GUI_FontSample10;
/* Start of unicode area <Basic Latin> */
GUI_CONST_STORAGE unsigned char acFontSample10_0041[ 28] = { /* code 0041 */
  0x00, 0x00,
  0x00, 0x00,
  0x00, 0x00,
  0x0B, 0xC0,
  0x1F, 0xD0,
  0x2E, 0xE0,
  0x3C, 0xF0,
  0x78, 0xB4,
  0xBF, 0xF8,
  0xE0, 0x78,
  0xE0, 0x3C,
  0x00, 0x00,
  0x00, 0x00,
  0x00, 0x00
};
GUI_CONST_STORAGE unsigned char acFontSample10_0061[ 28] = { /* code 0061 */
  0x00, 0x00,
  0x00, 0x00,
  0x00, 0x00,
  0x00, 0x00,
  0x00, 0x00,
  0x6F, 0x40,
  0x93, 0xC0,
  0x2B, 0xC0,
  0xB7, 0xC0,
  0xF7, 0xC0,
  0x7B, 0xC0,
  0x00, 0x00,
  0x00, 0x00,
```

 © 2020 SEGGER Microcontroller GmbH

```
  0x00, 0x00
};
GUI_CONST_STORAGE GUI_CHARINFO GUI_FontSample10_CharInfo[2] = {
   {   8,   8,  2, acFontSample10_0041 } /* code 0041 */
  ,{   6,   6,  2, acFontSample10_0061 } /* code 0061 */
};
GUI_CONST_STORAGE GUI_FONT_PROP GUI_FontSample10_Prop2 = {
   0x0061 /* first character */
  ,0x0061 /* last character  */
  ,&GUI_FontSample10_CharInfo[  1] /* address of first character */
  ,(GUI_CONST_STORAGE GUI_FONT_PROP*)0 /* pointer to next GUI_FONT_PROP */
};
GUI_CONST_STORAGE GUI_FONT_PROP GUI_FontSample10_Prop1 = {
   0x0041 /* first character */
  ,0x0041 /* last character  */
  ,&GUI_FontSample10_CharInfo[  0] /* address of first character */
  ,&GUI_FontSample10_Prop2 /* pointer to next GUI_FONT_PROP */
};
GUI_CONST_STORAGE GUI_FONT GUI_FontSample10 = {
   GUI_FONTTYPE_PROP_AA2 /* type of font    */
  ,14 /* height of font  */
  ,14 /* space of font y */
  ,1 /* magnification x */
  ,1 /* magnification y */
  ,&GUI_FontSample10_Prop1
};
```

13.13.3 Resulting C code, 4 bpp anti-aliased mode

The following is an example of a C file in 4 bpp anti-aliased mode:

```
/*
  C-file generated by Font Converter for emWin version 3.04
  Compiled:       Dec 13 2005 at 12:51:50
  C-file created: Dec 21 2005 at 12:42:57
  Copyright (C) 1998-2005
  Segger Microcontroller Systeme GmbH
  www.segger.com
  Solutions for real time microcontroller applications
  Source file: Sample10.c
  Font:        Arial
  Height:      10
*/
#include "GUI.H"
#ifndef GUI_CONST_STORAGE
  #define GUI_CONST_STORAGE const
#endif
/* The following line needs to be included in any file selecting the
   font. A good place would be GUIConf.H
*/
extern GUI_CONST_STORAGE GUI_FONT GUI_FontSample10;
/* Start of unicode area <Basic Latin> */
GUI_CONST_STORAGE unsigned char acFontSample10_0041[ 40] = { /* code 0041 */
  0x00, 0x00, 0x00, 0x00,
  0x00, 0xCF, 0xF2, 0x00,
  0x03, 0xFF, 0xF6, 0x00,
  0x09, 0xFB, 0xFB, 0x00,
  0x0E, 0xE2, 0xFE, 0x00,
  0x5F, 0x90, 0xCF, 0x40,
  0xBF, 0xFF, 0xFF, 0x90,
  0xFC, 0x00, 0x6F, 0xC0,
  0xF8, 0x00, 0x2F, 0xF2,
  0x00, 0x00, 0x00, 0x00
};
GUI_CONST_STORAGE unsigned char acFontSample10_0061[ 30] = { /* code 0061 */
  0x00, 0x00, 0x00,
```

 © 2020 SEGGER Microcontroller GmbH

```
  0x00, 0x00, 0x00,
  0x00, 0x00, 0x00,
  0x3D, 0xFE, 0x60,
  0xD3, 0x0F, 0xE0,
  0x29, 0xCF, 0xF0,
  0xDF, 0x4F, 0xF0,
  0xFF, 0x3F, 0xF0,
  0x6F, 0xAF, 0xF0,
  0x00, 0x00, 0x00
};
GUI_CONST_STORAGE GUI_CHARINFO GUI_FontSample10_CharInfo[2] = {
   {   8,   8,  4, acFontSample10_0041 } /* code 0041 */
  ,{   6,   6,  3, acFontSample10_0061 } /* code 0061 */
};
GUI_CONST_STORAGE GUI_FONT_PROP GUI_FontSample10_Prop2 = {
   0x0061 /* first character */
  ,0x0061 /* last character  */
  ,&GUI_FontSample10_CharInfo[  1] /* address of first character */
  ,(GUI_CONST_STORAGE GUI_FONT_PROP*)0 /* pointer to next GUI_FONT_PROP */
};
GUI_CONST_STORAGE GUI_FONT_PROP GUI_FontSample10_Prop1 = {
   0x0041 /* first character */
  ,0x0041 /* last character  */
  ,&GUI_FontSample10_CharInfo[  0] /* address of first character */
  ,&GUI_FontSample10_Prop2 /* pointer to next GUI_FONT_PROP */
};
GUI_CONST_STORAGE GUI_FONT GUI_FontSample10 = {
   GUI_FONTTYPE_PROP_AA4 /* type of font    */
  ,10 /* height of font  */
  ,10 /* space of font y */
  ,1 /* magnification x */
  ,1 /* magnification y */
  ,&GUI_FontSample10_Prop1
};
```

13.13.4 Resulting C code, extended mode

```
/*
  C-file generated by Font Converter for emWin version 3.04
  Compiled:       Dec 13 2005 at 12:51:50
  C-file created: Dec 21 2005 at 12:45:52
  Copyright (C) 1998-2005
  Segger Microcontroller Systeme GmbH
  www.segger.com
  Solutions for real time microcontroller applications
  Source file: Arial16.c
  Font:        Arial
  Height:      16
*/
#include "GUI.H"
#ifndef GUI_CONST_STORAGE
  #define GUI_CONST_STORAGE const
#endif
/* The following line needs to be included in any file selecting the
   font. A good place would be GUIConf.H
*/
extern GUI_CONST_STORAGE GUI_FONT GUI_Font16;
/* Start of unicode area <Basic Latin> */
GUI_CONST_STORAGE unsigned char acGUI_Font16_0041[ 20] = { /* code 0041 */
  ____X___,________,
  ___X_X__,________,
  ___X_X__,________,
  ___X_X__,________,
  __X___X_,________,
  __X___X_,________,
  _XXXXXXX,________,
```

 © 2020 SEGGER Microcontroller GmbH

```
  _X_____X,________,
  X_______,X_______,
  X_______,X_______};
GUI_CONST_STORAGE unsigned char acGUI_Font16_0061[  7] = { /* code 0061 */
  _XXX____,
  X___X___,
  ____X___,
  _XXXX___,
  X___X___,
  X__XX___,
  _XX_X___};
GUI_CONST_STORAGE GUI_CHARINFO_EXT GUI_Font16_CharInfo[2] = {
   {   9,  10,   0,   3,   9, acGUI_Font16_0041 } /* code 0041 */
  ,{   5,   7,   1,   6,   7, acGUI_Font16_0061 } /* code 0061 */
};
GUI_CONST_STORAGE GUI_FONT_PROP_EXT GUI_Font16_Prop2 = {
   0x0061 /* first character */
  ,0x0061 /* last character  */
  ,&GUI_Font16_CharInfo[  1] /* address of first character */
  ,(GUI_CONST_STORAGE GUI_FONT_PROP_EXT *)0
};
GUI_CONST_STORAGE GUI_FONT_PROP_EXT GUI_Font16_Prop1 = {
   0x0041 /* first character */
  ,0x0041 /* last character  */
  ,&GUI_Font16_CharInfo[  0] /* address of first character */
  ,&GUI_Font16_Prop2 /* pointer to next GUI_FONT_PROP_EXT */
};
GUI_CONST_STORAGE GUI_FONT GUI_Font16 = {
   GUI_FONTTYPE_PROP_EXT /* type of font    */
  ,16 /* height of font  */
  ,16 /* space of font y */
  ,1 /* magnification x */
  ,1 /* magnification y */
  ,{&GUI_Font16_Prop1}
  ,13 /* Baseline */
  ,7 /* Height of lowercase characters */
  ,10 /* Height of capital characters */
};
```

 © 2020 SEGGER Microcontroller GmbH

13.14 Troubleshooting

MS Windows 7 by default shows only fonts which match the computers language settings. If it is required to create a font for other languages, the required Windows fonts might not be shown in the 'Font' dialog. This is caused by the MS Windows font settings. In order to change those settings, the following 'Control Panel' path should be opened:

```
Control Panel\All Control Panel Items\Fonts\Font settings
```

Once the checkbox "`Hide fonts based on language settings`" is checked, all Windows fonts installed on the computer should be shown in the 'Font' dialog.

For calculating the baseline of a font it is required that the letter 'a' is present in the Font.

 © 2020 SEGGER Microcontroller GmbH

Chapter 14

Movies

With the movie file support of emWin it is possible to show movies. The movie file can be in two different formats. Besides our own movie format (EMF) it is also possible to display AVI files.



 © 2020 SEGGER Microcontroller GmbH

14.1 Introduction

EMF format

One way to play movies with the emWin API functions is to create files of the emWin specific (**E**)mWin (**M**)ovie (**F**)ile format. These EMF files are containers for single JPEG files. To be able to create such movie files each emWin-shipment contains the tool JPEG2Movie in the `\Tools` folder. This converter requires a folder containing JPEG images for each frame to be used.

Usually there are already existing movie files which should be shown with emWin. But the format of these files do not match the EMF file format. Because of that at first a tool is required which is able to create a folder with single JPEG files for each frame of the movie.

All that sounds quite complicated but can be done by a single drag-and-drop operation to one of our helper files. The following will explain in detail what needs to be done to be able to do that.

AVI format

Another way to show movies is to use the AVI format (Audio Video Interleave) which was introduced Microsoft. To be able to show AVI files these files must reside in a specific format. Please refer to *Requirements* on page 535.

The easiest way to create an AVI file which fits the requirements is to use the batch files which come with every emWin shipment. Please refer to *Creating an AVI file* on page 568 for more information.

 © 2020 SEGGER Microcontroller GmbH

14.2 Requirements

In opposite to movie file rendering using different frame methods the EMF file format contains complete JPEG files for each frame. The advantage of this format is that not more than one frame is required in memory.

RAM requirement

For the rendering process of an EMF file it is required to have enough dynamic RAM as required for rendering a single JPEG file plus the file size of a single JPEG file. The RAM requirement for rendering a JPEG file can be found in the chapter *JPEG file support* on page 399.

```
Requirement = JPEG requirement + File size of a single JPEG file
```

Please note that `File size` does not mean the whole movie file. It means the size of the biggest JPEG file of the movie only.

ROM requirement

Apart from the ROM requirement of the movie file itself approx. 22 KByte of additional ROM for the binary code for rendering JPEG based movie files are required.

Performance

To achieve a fluently rendering of the movie a frame rate of 25 frames/seconds is recommended.

AVI files

There are two requirements to be able to display AVI files with emWin.
The codec to be used in AVI file has to be MJPEG and the AVI file has to contain an index list called idx1 list.
The AVI files can also contain sound files, but these are not handled by emWin, yet.

 © 2020 SEGGER Microcontroller GmbH

14.3 Creating JPEG files with FFmpeg.exe

As mentioned above at first a tool is required which is able to convert files of any movie file format into a folder of single JPEG files for each frame. Currently a plenty of movie file formats exist. emWin does not support all these movie file formats directly.

We recommend the open source tool FFmpeg which is available under ffmpeg.org. It is free software licensed under the LGPL or GPL. It is able to convert files of nearly any movie file source format into any desired destination format, also into single JPEG files.

Because the tool is licensed under the LGPL we do not ship this tool directly. It can be loaded from ffmpeg.org. Version N-49757-g969039e or newer should be used.

 © 2020 SEGGER Microcontroller GmbH

14.4 Creating an EMF file

To make the conversion process as easy as possible there are batch files available in the folder Sample\MakeMovie\EMF. These files are:

File	Description
Prep.bat	Sets some defaults to be used. Needs to be adapted as explained in the following.
MakeMovie.bat	Main conversion file. Does not to be adapted normally.
<X_SIZE>x<Y_SIZE>.bat	Some helper files for different resolutions. Detailed description follows.

> **Note**
>
> Please note that all these files need to be located in the same folder. Otherwise they will not work correctly.

Prep.bat

The Prep.bat is required to prepare the environment for the actual process. Calling it directly will not have any effect. It is called by the MakeMovie.bat. To be able to use the batch files it is required to adapt this file at first. This file sets variables used by the file MakeMovie.bat. The following table shows these variables:

Variable	Description
%OUTPUT%	Destination folder for the JPEG files. Will be cleared automatically when starting the conversion with MakeMovie.bat.
%FFMPEG%	Access variable for the FFmpeg tool. Should contain the complete path required to call FFmpeg.exe.
%JPEG2MOVIE%	Access variable for the JPEG2MOVIE tool. Should contain the complete path required to call JPEG2Movie.exe.
%DEFAULT_SIZE%	Default movie resolution to be used. Can be ignored if one of the <X-SIZE>x<Y-SIZE>.bat files are used.
%DEFAULT_QUALITY%	Default quality to be used by FFmpeg.exe for creating the JPEG files. The less the number the better the quality. The value 1 indicates that a very good quality should be achieved. The value 31 indicates the worst quality. Details can be found in the FFmpeg documentation.
%DEFAULT_FRAMERATE%	Frame rate in frames/second to be used by FFmpeg. It defines the number of JPEG files to be generated by FFmpeg.exe for each second of the movie. Details can be found in the FFmpeg documentation.

MakeMovie.bat

This is the main batch file used for the conversion process. Normally it is not required to be change this file, but it is required to adapt Prep.bat first. It could be called with the following parameters:

Parameter	Description
%1	Movie file to be converted.
%2 (optional)	Size to be used. If not given %DEFAULT_SIZE% of Prep.bat is used.
%3 (optional)	Quality to be used. If not given %DEFAULT_QUALITY% of Prep.bat is used.
%4 (optional)	Frame rate to be used. If not given %DEFAULT_FRAMERATE% of Prep.bat is used.

 © 2020 SEGGER Microcontroller GmbH

Since the FFmpeg output can differ strongly from the output of previous actions, the Make-Movie.bat deletes all output files in the first place. The output folder is defined by in the environmental variable %OUTPUT% in Prep.bat. After that it uses FFmpeg.exe to create the required JPEG files for each frame. Afterwards it calls JPEG2Movie to create a single EMF file which can be used by emWin directly. After the conversion operation the result can be found in the conversion folder under FFmpeg.emf. It also creates a copy of that file into the source file folder. It will have the same name as the source file with a size-postfix and .emf extension.

If for example the source file is: C:\Temp\Movie.mp4 and the size to be used is 480x272 the folder C:\Temp\ will contain the file Movie_480x272.emf after the conversion.

<X_SIZE>x<Y_SIZE>.bat

These files are small but useful helpers if several movie resolutions are required. The file-names of the batch files itself are used as parameter -s for FFmpeg.exe. You can simply drag-and-drop the file to be converted to one of these helper files. After that an .emf file with the corresponding size-postfix can be found in the source file folder.

 © 2020 SEGGER Microcontroller GmbH

14.5 Creating an AVI file

Creating an AVI file which can be played with emWin is as simple as it is for EMF files. The folder `Sample\MakeMovie\AVI` contains almost the same batch files as the EMF folder except that it calls ffmpeg.exe with different parameters. Refer to *Creating an EMF file* on page 566 to get more information about the used parameters.

 © 2020 SEGGER Microcontroller GmbH

14.6 Modifying the conversion result

The process of conversion explained above describes how to convert a given movie automatically. But sometimes it could be required to remove or edit JPEGs after generating the images by FFmpeg and before creating the EMF file with JPEG2Movie. The most simple method for doing that is first creating a complete movie automatically as described above. After that the conversion folder defined by the `%FOLDER%` variable in `Prep.bat` contains all images. Now please feel free to remove, change or add images to the folder. After that JPEG2Movie can be used to convert the new compilation of files to an EMF file.

 © 2020 SEGGER Microcontroller GmbH

14.7 Using JPEG2Movie

If there is an already existing compilation of JPEG files to be used the tool JPEG2Movie can be used directly. It is available in the `\Tool` folder of each shipment:

1. Start `JPEG2Movie.exe`.
2. Select one of the existing JPEG files from the source folder with 'Select file'.
3. Define the frame duration to be used (default is 40ms).
4. Click the 'Convert' button for creating the EMF file.

After that the folder of the selected file should contain an EMF file. Please note that all JPEGs should have exactly the same resolution.

Screenshot of the tool



 © 2020 SEGGER Microcontroller GmbH

14.8 emWin Movie Player

Every emWin shipment comes with a tool named emWinPlayer. This tool makes it possible to show the previously created EMF on a Computer with a Windows operating system. This might come in handy since there is no need of a running application to watch the created EMF.

When using the emWinPlayer it provides the user with information about the currently running EMF. It shows the currently displayed frame and the time of this frame. This will make it easier to change the movie at a specific position.

To show an EMF either open a file vie the menu bar or 'drag and drop' the file to be played into the player. The EMF starts playing automatically. The control panel allows to jump at the beginning or the end of movie, step frame wise and to play/pause the movie file. With a click on the progress bar it is also possible to jump to a position in the movie.

Screenshot of the tool



 © 2020 SEGGER Microcontroller GmbH

14.9 Movies API

The table below lists the available movie-related routines in alphabetical order. Detailed descriptions follow:

Functions

Routine	Description
GUI_MOVIE_Create()	Creates a movie using a file which is completely available in addressable RAM or ROM.
GUI_MOVIE_CreateEx()	Creates a movie using a file which is not available in addressable RAM or ROM.
GUI_MOVIE_Delete()	Deletes the given movie from memory.
GUI_MOVIE_DrawFrame()	Draws a single frame of a movie.
GUI_MOVIE_GetFrameIndex()	Returns the current frame number of the given movie.
GUI_MOVIE_GetInfo()	Fills a GUI_MOVIE_INFO structure with information about the given movie.
GUI_MOVIE_GetInfoEx()	Fills a GUI_MOVIE_INFO structure with information about the given movie not being available in RAM or ROM.
GUI_MOVIE_GetInfoH()	Fills a GUI_MOVIE_INFO structure with information about the given movie using an existing movie handle.
GUI_MOVIE_GetNumFrames()	Returns the number of frames of a movie.
GUI_MOVIE_GetPos()	Returns the drawing position and resolution of the given movie.
GUI_MOVIE_GotoFrame()	Sets the frame index to be shown at next.
GUI_MOVIE_Pause()	Stops playing the given movie immediately.
GUI_MOVIE_Play()	Continues playing of the given movie.
GUI_MOVIE_SetPeriod()	Sets the period to be used for one single frame in ms.
GUI_MOVIE_SetpfNotify()	Set a notification callback function.
GUI_MOVIE_SetPos()	Sets the drawing position to be used for the given movie.
GUI_MOVIE_Show()	Starts playing the given movie at the given position.

Data structures

Structure	Description
GUI_MOVIE_INFO	Information about a movie.

Defines

Group of defines	Description
Movie notifications	Notifications sent to the movieâs callback function.

 © 2020 SEGGER Microcontroller GmbH

14.9.1 Functions

14.9.1.1 GUI_MOVIE_Create()

Description

Creates a movie using a file which is completely available in addressable RAM or ROM.

Prototype

```
GUI_MOVIE_HANDLE GUI_MOVIE_Create(const void           * pFileData,
                                  U32                  FileSize,
                                  GUI_MOVIE_FUNC * pfNotify);
```

Parameters

Parameter	Description
pFileData	Pointer to the memory location of the file.
FileSize	Size of file in bytes.
pfNotify	Optional pointer to a notification function of type GUI_MOVIE_FUNC. If set, this function would be called for each frame.

Prototype of GUI_MOVIE_FUNC

```
void GUI_MOVIE_FUNC(GUI_MOVIE_HANDLE hMovie,
                    int              Notification,
                    U32              CurrentFrame);
```

The permitted values for the Notification parameter are listed under *Movie notifications* on page 591.

Return value

Movie handle on success, 0 on error.

Additional information

The callback function can be used to achieve overlays for specific frames or for using multiple buffers for the drawing process. The sample folder contains the sample BASIC_ShowMovies.c which shows how to use that feature in detail.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.2 GUI_MOVIE_CreateEx()

Description

Creates a movie using a file which is not available in addressable RAM or ROM. A user defined GetData() function is used to fetch the file data.

Prototype

```
GUI_MOVIE_HANDLE GUI_MOVIE_CreateEx(GUI_GET_DATA_FUNC * pfGetData,
                                    void              * pParam,
                                    GUI_MOVIE_FUNC    * pfNotify);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. Details about the GetData() function can be found in the section *Getting data with the …Ex() functions* on page 436
pParam	Void pointer passed to the function pointed by pfGetData.
pfNotify	Optional pointer to a notification function as described under GUI_MOVIE_Create().

Return value

Movie handle on success, 0 on error.

Additional information

When playing a movie not from an addressable memory location, the movie function of emWin reads the file frame by frame. That means that only one file access is required for each frame. But that also means that enough RAM needs to be available for buffering a complete JPEG file. For more information please also refer to GUI_MOVIE_Create().

 © 2020 SEGGER Microcontroller GmbH

14.9.1.3 GUI_MOVIE_Delete()

Description

Deletes the given movie from memory.

Prototype

```
int GUI_MOVIE_Delete(GUI_MOVIE_HANDLE hMovie);
```

Parameters

Parameter	Description
hMovie	Handle to the movie to be deleted.

Return value

0 on success
1 on error.

Additional information

If the movie is currently playing, the function stops it. It is not required to call GUI_MOVIE_Stop() explicitly.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.4 GUI_MOVIE_DrawFrame()

Description

Draws the given frame of the movie at the given position.

Prototype

```
void GUI_MOVIE_DrawFrame(GUI_MOVIE_HANDLE hMovie,
                         int              Index,
                         int              x,
                         int              y);
```

Parameters

Parameter	Description
hMovie	Handle to the movie to be deleted.
Index	Index of the frame to be shows.
x	X-position in screen coordinates to be used.
y	Y-position in screen coordinates to be used.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.5 GUI_MOVIE_GetFrameIndex()

Description

If the movie is already playing the function returns the index of the next frame to be shown. If the movie is currently stopped/paused, it returns the frame index of the last shown image.

Prototype

```
U32 GUI_MOVIE_GetFrameIndex(GUI_MOVIE_HANDLE hMovie);
```

Parameters

Parameter	Description
hMovie	Handle to the movie to be deleted.

Return value

Frame index as described above.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.6 GUI_MOVIE_GetInfo()

Description

Fills a GUI_MOVIE_INFO structure with information about the given movie. The movie needs to be available in an addressable memory location.

Prototype

```
int GUI_MOVIE_GetInfo(const void           * pFileData,
                      U32                    FileSize,
                      GUI_MOVIE_INFO * pInfo);
```

Parameters

Parameter	Description
pFileData	Pointer to the memory location of the file.
FileSize	Size of file in bytes.
pInfo	Pointer to a structure of type GUI_MOVIE_INFO to be filled by the function.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.7 GUI_MOVIE_GetInfoEx()

Description

Fills a GUI_MOVIE_INFO structure with information about the given movie. The movie does not need to be available in an addressable memory location.

Prototype

```
int GUI_MOVIE_GetInfoEx(GUI_GET_DATA_FUNC * pfGetData,
                        void              * pParam,
                        GUI_MOVIE_INFO    * pInfo);
```

Parameters

Parameter	Description
pfGetData	Pointer to a function which is called for getting data. Details about the GetData() function can be found in the section *Getting data with the …Ex() functions* on page 436
pParam	Void pointer passed to the function pointed by pfGetData.
pInfo	Pointer to a structure of type GUI_MOVIE_INFO to be filled by the function.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.8 GUI_MOVIE_GetInfoH()

Description

Fills a GUI_MOVIE_INFO structure with information about the given movie using an existing movie handle.

Prototype

```
int GUI_MOVIE_GetInfoH(GUI_MOVIE_HANDLE   hMovie,
                       GUI_MOVIE_INFO   * pInfo);
```

Parameters

Parameter	Description
hMovie	Handle of the movie.
pInfo	Pointer to a structure of type GUI_MOVIE_INFO to be filled by the function.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.9 GUI_MOVIE_GetNumFrames()

Description

Returns the number of frames of a movie.

Prototype

```
int GUI_MOVIE_GetNumFrames(GUI_MOVIE_HANDLE hMovie);
```

Parameters

Parameter	Description
hMovie	Handle of the movie.

Return value

Number of frames present in the movie.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.10 GUI_MOVIE_GetPos()

Description

Returns the drawing position and resolution of the given movie.

Prototype

```
int GUI_MOVIE_GetPos(GUI_MOVIE_HANDLE   hMovie,
                     int              * pxPos,
                     int              * pyPos,
                     int              * pxSize,
                     int              * pySize);
```

Parameters

Parameter	Description
hMovie	Handle of the movie.
pxPos	Pointer to an integer to be filled with the drawing position in x. May be NULL.
pyPos	Pointer to an integer to be filled with the drawing position in y. May be NULL.
pxSize	Pointer to an integer to be filled with the horizontal resolution in x. May be NULL.
pySize	Pointer to an integer to be filled with the horizontal resolution in y. May be NULL.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.11 GUI_MOVIE_GotoFrame()

Description

Sets the frame index to be shown at next.

Prototype

```
int GUI_MOVIE_GotoFrame(GUI_MOVIE_HANDLE hMovie,
                        U32              Frame);
```

Parameters

Parameter	Description
hMovie	Handle of the movie.
Frame	Number of the desired frame.

Return value

0 on success
1 on error.

Additional information

If the given frame index is not in the range of the given file, the function stops the movie and returns with an error.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.12 GUI_MOVIE_Pause()

Description

Stops playing the given movie immediately. Can be continued later with `GUI_MOVIE_Play()`.

Prototype

```
int GUI_MOVIE_Pause(GUI_MOVIE_HANDLE hMovie);
```

Parameters

Parameter	Description
hMovie	Handle of the movie.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.13 GUI_MOVIE_Play()

Description

Continues playing of the given movie.

Prototype

```
int GUI_MOVIE_Play(GUI_MOVIE_HANDLE hMovie);
```

Parameters

Parameter	Description
hMovie	Handle of the movie.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.14 GUI_MOVIE_SetPeriod()

Description

Sets the period to be used for one single frame in ms.

Prototype

```
int GUI_MOVIE_SetPeriod(GUI_MOVIE_HANDLE hMovie,
                        unsigned         Period);
```

Parameters

Parameter	Description
hMovie	Handle of the movie.
Period	Period to be used in ms.

Return value

0 on success
1 on error.

Additional information

This function can be used to vary the speed of a movie. If the period is too short to be achieved by the hardware emWin skips the next image(s).

 © 2020 SEGGER Microcontroller GmbH

14.9.1.15 GUI_MOVIE_SetpfNotify()

Description

This function should be used when the JPEG decoding is performed by hardware. `GUI_MOVIE_SetpfNotify()` sets a callback function to signalize if a movie is running or not. An example on how to use this function can be found under `Sample\JPEG-Conf\ST-M32F769`. Further it is required to set up hardware decoding by hardware. Please refer to *Using hardware JPEG decoding* on page 2915.

Prototype

```
void GUI_MOVIE_SetpfNotify(GUI_MOVIE_FUNC * pfNotify);
```

Parameters

Parameter	Description
`hMovie`	Handle of the movie.
`Period`	`Period` to be used in ms.

Return value

0 on success
1 on error.

Additional information

The parameter `pfNotify` has the same prototype as described at *Prototype of `GUI_MOVIE_FUNC`*. Although it has the same prototype, it has not the functionality. The intention of this function pointer is to signal when a movie starts and ends.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.16 GUI_MOVIE_SetPos()

Description

Sets the drawing position to be used for the given movie.

Prototype

```
int GUI_MOVIE_SetPos(GUI_MOVIE_HANDLE hMovie,
                     int              xPos,
                     int              yPos);
```

Parameters

Parameter	Description
hMovie	Handle of the movie.
xPos	X-position in screen coordinates to be used.
yPos	Y-position in screen coordinates to be used.

Return value

0 on success
1 on error.

Additional information

It is not required that the given position makes the movie completely visible. It can be partly or completely outside of the visible screen.

 © 2020 SEGGER Microcontroller GmbH

14.9.1.17 GUI_MOVIE_Show()

Description

Starts playing the given movie at the given position.

Prototype

```
int GUI_MOVIE_Show(GUI_MOVIE_HANDLE hMovie,
                   int              xPos,
                   int              yPos,
                   int              DoLoop);
```

Parameters

Parameter	Description
hMovie	Handle of the movie.
xPos	X-position in screen coordinates to be used.
yPos	Y-position in screen coordinates to be used.
DoLoop	1 if the movie should be shown in an endless loop, 0 if not.

Return value

0 on success
1 on error.

Additional information

If the given movie is already playing the function returns an error. But the movie remains playing.

 © 2020 SEGGER Microcontroller GmbH

14.9.2 Data structures

14.9.2.1 GUI_MOVIE_INFO

Description

Information about a movie.

Type definition

```
typedef struct {
  int  xSize;
  int  ySize;
  int  msPerFrame;
  U32  NumFrames;
} GUI_MOVIE_INFO;
```

Structure members

Member	Description
xSize	Horizontal resolution of the movie in pixels.
ySize	Vertical resolution of the movie in pixels.
msPerFrame	Period of one frame in ms.
NumFrames	Number of frames of the movie file.

See also

- GUI_MOVIE_GetInfo()
- GUI_MOVIE_GetInfoEx()

 © 2020 SEGGER Microcontroller GmbH

14.9.3 Defines

14.9.3.1 Movie notifications

Description

Notifications sent to the movie's callback function. The callback function can be set with `GUI_MOVIE_SetpfNotify()`.

Definition

```
#define GUI_MOVIE_NOTIFICATION_PREDRAW     0
#define GUI_MOVIE_NOTIFICATION_POSTDRAW    1
#define GUI_MOVIE_NOTIFICATION_START       2
#define GUI_MOVIE_NOTIFICATION_STOP        3
#define GUI_MOVIE_NOTIFICATION_DELETE      4
```

Symbols

Definition	Description
GUI_MOVIE_NOTIFICATION_PREDRAW	Sent immediately before a frame is drawn.
GUI_MOVIE_NOTIFICATION_POSTDRAW	Sent immediately after a frame is drawn.
GUI_MOVIE_NOTIFICATION_START	Sent when starting to play a movie.
GUI_MOVIE_NOTIFICATION_STOP	Sent when the movie has stopped.
GUI_MOVIE_NOTIFICATION_DELETE	Sent when the movie has been deleted.

 © 2020 SEGGER Microcontroller GmbH

Chapter 15

Animations

Animations can be achieved by playing GIF animations, movies or showing animated graphic objects. Whereas GIF animations and movies can be used only for playing a fixed sequence of pictures, the animation object of emWin is able to draw runtime generated scenes of one or multiple independent animated objects, which could be used to reflect dynamic application data. The following chapter explains how the animation object could be used to achieve user defined animations.

 © 2020 SEGGER Microcontroller GmbH

15.1 Introduction

Bringing up motion into an application could be done by several ways. If a fixed sequence of pictures does not work and one or more objects should change their properties like position, color, shape, size or whatever within a given period of time, emWin offers an animation object for exactly that purpose. It is able to animate multiple animation items during the timeline of an animation. Animation item means a custom defined routine which receives a position value from the animation object. That value is calculated in dependence of the current point in time. The calculation could be done by predefined or custom defined methods.
Each item has its own start and end time which determine if it is called or not during the execution.

 © 2020 SEGGER Microcontroller GmbH

15.2 Creating an animation object

Creating an animation object is done by passing the duration and the minimum time per 'slice' to the creation routine. Optionally a custom defined void pointer and a pointer to a 'slice callback' routine could be passed. The term 'slice' will be explained later. After the handle of an animation object is available one or more animation items could be added to the animation.



The diagram shows an animation with several items within the animation period where each item has its own start and end time. emWin does not limit the number of items. Start time and end time of each item have to be within the timeline of the animation.

Example

```
//
// Creating an animation of 4 seconds and a min time/slice of 50ms
//
hAnim = GUI_ANIM_Create(4000, 50, NULL, NULL);
```

 © 2020 SEGGER Microcontroller GmbH

15.3 Adding items to an animation

An animation item is a routine which receives information from the animation object during the period of execution. When adding an item its start time, end time, 'method of position calculation' and animation routine to be called should be passed. Further an optional void pointer could be used which is passed to the animation routine during the animation is executed.

Example

```
static void _AnimDrawSomething(GUI_ANIM_INFO * pInfo, void * pVoid) {
  ...
}
void Application(void){
  ...
  GUI_ANIM_AddItem(hAnim,  500, 2500, ANIM_LINEAR, pVoid, _AnimDrawSomething);
  ...
}
```

 © 2020 SEGGER Microcontroller GmbH

15.4 Position calculation

Each item has its own start and end time within the timeline of the animation. If the current point of time is within the period of an item, the animation object calculates a position value. The following table shows the available methods for calculating the position value:

ANIM_LINEAR	ANIM_ACCEL
	
ANIM_DECEL	**ANIM_ACCELDECEL**
	

The value passed to the application is between 0 and `GUI_ANIM_RANGE`. If for example `ANIM_ACCEL` is used and the animation item is currently exactly in the middle the value passed to the application is `0.5 × 0.5 × GUI_ANIM_RANGE`.

GUI_ANIM_RANGE

That value is defined by emWin as follows:

Type	Macro	Default	Description
v	`GUI_ANIM_RANGE`	32767	Define the default range of an animation.

The value could be changed on demand.

 © 2020 SEGGER Microcontroller GmbH

15.4.1 Custom defined position calculation

If the above predefined methods do not meet the requirements a custom defined routine could be used. The below sample shows how that works. The routine is called by the animation object each time a single position value is required. The routine gets start time, end time and current time of the animation item. Its job is to calculate a value in dependence of the given parameters. The predefined methods of emWin generate values between 0 and `GUI_ANIM_RANGE`. If a custom defined routine is used the range could be different.

Example

```
I32 _CalcPosition(GUI_TIMER_TIME ts, GUI_TIMER_TIME te, GUI_TIMER_TIME tNow) {
  ...
}
void Application(void) {
  ...
  GUI_ANIM_AddItem(hAnim, ..., ..., _CalcPosition, ..., ...);
  ...
}
```

 © 2020 SEGGER Microcontroller GmbH

15.5 Executing an animation

Simply call GUI_ANIM_StartEx(). That function offers the possibility to run an animation a determined number of times or within an endless loop. GUI_ANIM_Stop() could be used to stop an animation which is running. Alternatively GUI_ANIM_Exec() could be called periodically to keep an animation alive, but most recommended is using automatic mode.
Each time emWin executes an animation (auto mode or with GUI_ANIM_Exec()) it checks which items of the given animation are within the current point of time. That collection of items represents one slice of animation items which are called at the given point of time. The animation diagram at the beginning for example shows the points of time t_0 and t_1. The t_0 slice consists of items 0, 1, 2 and n and the t_1 slice of item 2 and 3. The following example shows how an animation could be executed:

Example

```
void Application(void) {
  ...
  GUI_ANIM_StartEx(hAnim, -1, NULL);  // Start animation in endless loop
  ...
  while (1) {
    GUI_Delay(1);
  }
}
```

15.5.1 Using a slice callback function

Before calling the first item of an animation slice and after calling the last item an optional callback function could be called. A slice callback function could be used for example to avoid flickering. Before drawing the first item the application could switch to the back buffer or lock the cache and after drawing the last item the back buffer could be made visible or the cache could be unlocked. To use a slice callback function a pointer to that function should be passed to the creation routine.

Example

```
static void _cbSliceInfo(int State, void * pVoid) {
  switch (State) {
  case GUI_ANIM_START:
    GUI_MULTIBUF_Begin();
    break;
  case GUI_ANIM_END:
    GUI_MULTIBUF_End();
    break;
  }
}
void Application(void) {
  ...
  hAnim = GUI_ANIM_Create(..., ..., pVoid, _cbSliceInfo);
}
```

15.5.2 Animation item

An animation item is simply a routine which is executed by the animation object. It is called by passing a pointer to a GUI_ANIM_INFO structure and the application defined void pointer passed to GUI_ANIM_AddItem().

Prototype

```
static void _AnimDrawRect(GUI_ANIM_INFO * pInfo,
                          void          * pVoid);
```

 © 2020 SEGGER Microcontroller GmbH

15.5.3 Using a delete callback function

A delete callback is a routine that will be called when an animation has ended. This can be useful e.g. when a window handle should be deleted after an animation has finished. A delete callback is also called, when `GUI_ANIM_Delete()` is called for an animation.

Prototype

```
static void _OnDelete(void * pVoid);
```

Usage

A delete callback can be set for an animation by passing the function pointer to `GUI_ANIM_StartEx()`. The void pointer passed to `GUI_ANIM_Create()` as third parameter will also be passed to the delete callback of that animation.

Example

```
static void _OnDelete(void * pVoid) {
  ANIM_DATA * pData;
  pData = (ANIM_DATA *)pVoid;
  ...
}
...
ANIM_DATA Data;
...
hAnim = GUI_ANIM_Create(ANIM_PERIOD, 50, &Data, NULL);
...
GUI_ANIM_StartEx(hAnim, 1, _OnDelete);
```

 © 2020 SEGGER Microcontroller GmbH

15.6 Animations API

The following table lists the animation related API functions.

Functions

Routine	Description
GUI_ANIM_AddItem()	Adds an item to the given animation.
GUI_ANIM_Create()	Creates an animation object.
GUI_ANIM_Delete()	Deletes an animation object and all of its data.
GUI_ANIM_DeleteAll()	Deletes all animations.
GUI_ANIM_Exec()	Should be used to keep the given animation alive.
GUI_ANIM_GetData()	Returns the optional void pointer passed to the animation with GUI_ANIM_Create().
GUI_ANIM_GetFirst()	Returns the handle of the first animation to be executed automatically.
GUI_ANIM_GetItemData()	Returns the optional void pointer passed to an animation item with GUI_ANIM_AddItem().
GUI_ANIM_GetNext()	Returns the handle of the next animation to be executed after the given animation.
GUI_ANIM_GetNumItems()	Returns the number of items in an animation.
GUI_ANIM_IsRunning()	Returns if an animation is running.
GUI_ANIM_Start()	Sets the start time of the given animation.
GUI_ANIM_StartEx()	Starts the given animation automatically.
GUI_ANIM_Stop()	Stops the animation correspondig to the given handle.

Data structures

Structure	Description
GUI_ANIM_INFO	Contains information about the current state of an animation.

Defines

Group of defines	Description
Animation states	List of possible states for an animation.

 © 2020 SEGGER Microcontroller GmbH

15.6.1 Functions

15.6.1.1 GUI_ANIM_AddItem()

Description

Adds an item to the given animation.

Prototype

```
int GUI_ANIM_AddItem(GUI_ANIM_HANDLE        hAnim,
                     GUI_TIMER_TIME         ts,
                     GUI_TIMER_TIME         te,
                     GUI_ANIM_GETPOS_FUNC   pfGetPos,
                     void                 * pVoid,
                     GUI_ANIMATION_FUNC   * pfAnim);
```

Parameters

Parameter	Description
hAnim	Handle of animation object to be used.
ts	Relative start time in ms.
te	Relative end time in ms. Needs to be > ts.
pfGetPos	Pointer to a routine for calculating the position value.
pVoid	Optional void pointer passed to the animation function during the execution.
pfAnim	Pointer to the animation function (item) to be executed by the object.

Return value

0 on success
1 on error.

Additional information

Start and end time are relative to the time value set when calling GUI_ANIM_Start().

 © 2020 SEGGER Microcontroller GmbH

15.6.1.2 GUI_ANIM_Create()

Description

Creates an animation object.

Prototype

```
GUI_ANIM_HANDLE GUI_ANIM_Create(GUI_TIMER_TIME   Period,
                                unsigned         MinTimePerSlice,
                                void           * pVoid,
                                void             ( *pfSlice)(int , void * ));
```

Parameters

Parameter	Description
Period	Duration in ms of the whole animation. Maximum value is 0x20000.
MinTimePerSlice	Minimum time of one animation slice in ms.
pVoid	Optional void pointer passed to the slice callback function and/or the delete function.
pfSlice	Optional slice callback function.

Return value

Handle of the animation object or 0 if no memory is available.

Additional information

The value MinTimePerSlice determines the frame rate when executing the animation with GUI_ANIM_Exec(). The given time determines the minimum period between the execution of 2 slices of animation items.

 © 2020 SEGGER Microcontroller GmbH

15.6.1.3 GUI_ANIM_Delete()

Description

Deletes an animation object and all of its data.

Prototype

```
void GUI_ANIM_Delete(GUI_ANIM_HANDLE hAnim);
```

Parameters

Parameter	Description
hAnim	Animation object to be used.

 © 2020 SEGGER Microcontroller GmbH

15.6.1.4 GUI_ANIM_DeleteAll()

Description

Deletes all animations. Also calls the deletion function for each animation if it is set.

Prototype

```
void GUI_ANIM_DeleteAll(void);
```

 © 2020 SEGGER Microcontroller GmbH

15.6.1.5 GUI_ANIM_Exec()

Description

Should be used to keep the given animation alive. The function needs to be called periodically.

Prototype

```
int GUI_ANIM_Exec(GUI_ANIM_HANDLE hAnim);
```

Parameters

Parameter	Description
hAnim	Animation object to be used.

Return value

0 if the given animation is within its timeline.
1 if the animation period is expired.

Additional information

Within a typical execution loop the application should give other tasks a chance to do something. That can be done by simply calling `GUI_Delay()`.

Example

```
while (GUI_ANIM_Exec(hAnim) == 0) {
  GUI_X_Delay(5); // Idle time for other tasks
}
```

 © 2020 SEGGER Microcontroller GmbH

15.6.1.6 GUI_ANIM_GetData()

Description

Returns the optional void pointer passed to the animation with `GUI_ANIM_Create()`.

Prototype

```
void *GUI_ANIM_GetData(GUI_ANIM_HANDLE hAnim);
```

Parameters

Parameter	Description
hAnim	Animation handle.

Return value

Void pointer passed to the animation.

 © 2020 SEGGER Microcontroller GmbH

15.6.1.7 GUI_ANIM_GetFirst()

Description

Returns the handle of the first animation to be executed automatically.

Prototype

```
GUI_ANIM_HANDLE GUI_ANIM_GetFirst(void);
```

 © 2020 SEGGER Microcontroller GmbH

15.6.1.8 GUI_ANIM_GetItemData()

Description

Returns the optional void pointer passed to an animation item with `GUI_ANIM_AddItem()`.

Prototype

```
void *GUI_ANIM_GetItemData(GUI_ANIM_HANDLE hAnim,
                           unsigned        Index);
```

Parameters

Parameter	Description
`hAnim`	Animation handle.
`Index`	`Index` of animation item.

Return value

Void pointer passed to the animation item.

 © 2020 SEGGER Microcontroller GmbH

15.6.1.9 GUI_ANIM_GetNext()

Description

Returns the handle of the next animation to be executed after the given animation.

Prototype

```
GUI_ANIM_HANDLE GUI_ANIM_GetNext(GUI_ANIM_HANDLE hAnim);
```

Parameters

Parameter	Description
hAnim	Animation handle.

Return value

Handle of next animation to executed.

 © 2020 SEGGER Microcontroller GmbH

15.6.1.10 GUI_ANIM_GetNumItems()

Description

Returns the number of items in an animation.

Prototype

```
int GUI_ANIM_GetNumItems(GUI_ANIM_HANDLE hAnim);
```

Parameters

Parameter	Description
hAnim	Animation handle.

Return value

Number of items present in the given animation.

 © 2020 SEGGER Microcontroller GmbH

15.6.1.11 GUI_ANIM_IsRunning()

Description

Returns if an animation is running.

Prototype

```
int GUI_ANIM_IsRunning(GUI_ANIM_HANDLE hAnim);
```

Parameters

Parameter	Description
hAnim	Animation handle.

Return value

0 if the animation is not running.
1 if the animation is running.

 © 2020 SEGGER Microcontroller GmbH

15.6.1.12 GUI_ANIM_Start()

Description

Sets the start time of the given animation.

Prototype

```
void GUI_ANIM_Start(GUI_ANIM_HANDLE hAnim);
```

Parameters

Parameter	Description
hAnim	Animation object to be used.

Additional information

The function does nothing but setting the current time as start time. From that moment GUI_ANIM_Exec() should return 0 for the given animation period.

 © 2020 SEGGER Microcontroller GmbH

15.6.1.13 GUI_ANIM_StartEx()

Description

Sets the start time of the given animation and processes the animation automatically.

Prototype

```
void GUI_ANIM_StartEx(GUI_ANIM_HANDLE hAnim,
                      int             NumLoops,
                      void            ( *pfOnDelete)(void * pVoid ));
```

Parameters

Parameter	Description
hAnim	Animation object to be used.
NumLoops	Number of loops the animation should be executed.
pfOnDelete	Function pointer to a function which should be executed on deletion of the animation.

Additional information

This function should be used instead of GUI_ANIM_Start() since it is no longer necessary to call GUI_ANIM_Start() in combination GUI_ANIM_Exec() and handle the animation process on your own. GUI_ANIM_StartEx() handles the process automatically.

 © 2020 SEGGER Microcontroller GmbH

15.6.1.14 GUI_ANIM_Stop()

Description

Stops the animation correspondig to the given handle.

Prototype

```
void GUI_ANIM_Stop(GUI_ANIM_HANDLE hAnim);
```

Parameters

Parameter	Description
hAnim	Animation object to be used.

 © 2020 SEGGER Microcontroller GmbH

15.6.2 Data structures

15.6.2.1 GUI_ANIM_INFO

Description

Contains information about the current state of an animation.

Type definition

```
typedef struct {
  int              Pos;
  int              State;
  GUI_ANIM_HANDLE  hAnim;
  GUI_TIMER_TIME   Period;
} GUI_ANIM_INFO;
```

Structure members

Member	Description
Pos	Position value calculated by the selected position calculation routine.
State	State of the animation. See *Animation states* on page 616 for valid values.
hAnim	Handle of the animation object.
Period	Period of the animation object.

 © 2020 SEGGER Microcontroller GmbH

15.6.3 Defines

15.6.3.1 Animation states

Description

Describes the current state of an animation. Sent with the `State` member of the `GUI_ANIM_INFO` structure to an animation callback.

Definition

```
#define GUI_ANIM_START      0
#define GUI_ANIM_RUNNING    1
#define GUI_ANIM_END        2
```

Symbols

Definition	Description
GUI_ANIM_START	First execution.
GUI_ANIM_RUNNING	Passed to all items which are not the first and not the last.
GUI_ANIM_END	Last execution.

 © 2020 SEGGER Microcontroller GmbH

Chapter 16

Colors

emWin supports color displays, grayscale (monochrome with different intensities) and black/white displays. An existing emWin application can be used with different kinds of displays. If an existing application should be used with a new display only the display configuration (normally located in `LCDConf.c`) needs to be changed. To achieve this the application uses 'logical colors'. That logical color format is independent of the color (or better pixel-) format required for the display controller.



 © 2020 SEGGER Microcontroller GmbH

16.1 Color management

If an application uses a color for a drawing operation that color normally should be a 'logical color' containing 8 bits for each color channel and 8 bits for the alpha channel. The display controller normally requires a different format, called 'index value' in this document. 'Logical colors' are independent of the used hardware. The format of the 'index values' depend on the requirements of the display controller. Wherever emWin draws anything on the display it converts the 'logical color' used by the application into an 'index value' for the controller. That conversion is done automatically by the color conversion routines configured in the display configuration routine `LCD_X_Config()` which should set up the routines to be used. That could be done separately for each layer.

emWin supports different ways of color conversion:

Fixed palette mode

Using a fixed palette mode is the most recommended way of color conversion. It sets up conversion routines for converting a color into an index value and vice versa. emWin provides a large set of predefined fixed palette modes explained later in this chapter.

Application defined color conversion

If none of the predefined fixed palette modes match the requirements a custom color conversion could be used. That simply means custom defined routines for converting a color into an index value and vice versa. Details explained later in this chapter.

Custom palette mode

If a display controller with a palette based color management is used, either one of the fixed palette modes could be used or a custom palette could be defined.
In case of using a custom palette emWin converts the logical colors by using an optimized version of the "least-square deviation search". It compares the color to display (the logical color) with all the available palette colors and uses the one that the LCD-metric considers closest. Please note that using a custom palette mode could degrade the performance. Details about how to use a custom palette explained later in this chapter.

 © 2020 SEGGER Microcontroller GmbH

16.2 Logical colors

A logical color contains 8 bits for each color component and 8 bits for the alpha channel. Since V5.30 emWin supports 2 logical color formats:

Logical color format ABGR

Alpha	Blue	Green	Red
0x00 - opaque 0xFF - transparent			
DB31 - DB24	DB23 - DB16	DB15 - DB08	DB07 - DB00

For a long period of time the above format was the only supported logical color format. That implies that the used logical color format of all applications using emWin written within that period is also the same.

Logical color format ARGB (default)

Alpha	Red	Green	Blue
0x00 - transparent 0xFF - opaque			
DB31 - DB24	DB23 - DB16	DB15 - DB08	DB07 - DB00

Because of more and more hardware platforms using a slightly different pixel format we decided to add the option of using ARGB as logical color format to be able to improve performance significantly under certain circumstances. Please note that the alpha definition of the ARGB format is also different to the ABGR format.
This format is the default setting since version 5.48 of emWin. To use the ABGR format add the following to your GUIConf.h:

```
#define GUI_USE_ARGB  0
```

 © 2020 SEGGER Microcontroller GmbH

16.3 Switching to ARGB

Using that logical color format could make sense if a display controller is used which supports exactly that color format as index value. In that case the performance could be improved significantly, for example when using an on chip LCD controller with hardware acceleration.

16.3.1 Configuration

In previous versions of emWin it was required to configure emWin to use the ARGB format. Since version 5.48 this format is the default and no changes to the GUIConf.h are required any longer.

Under certain circumstances it might be necessary to switch back to the old configuration. If this is necessary just add the following to your `GUIConf.h`:

```
#define GUI_USE_ARGB 0
```

16.3.2 Required changes in existing applications

When switching from ABGR to ARGB or vice versa some things have to be considered.

Colors

Wherever colors are defined as hexadecimal values in the application the values have to be changed or even better a conversion macro has to be used. The following table shows the use of the same color with ARGB, ABGR and conversion macro:

File	Description
ARGB	`GUI_SetColor(0xA02010);`
ABGR	`GUI_SetColor(0xFF1020A0);`
Conversion macro	`GUI_SetColor(GUI_MAKE_COLOR(0xFF1020A0));`

Of course all predefined color values will be changed automatically.

32 bpp Memory devices

emWin contains a couple of functions to be used with 32 bpp memory devices only. Those functions expect a determined memory device format. When working in ABGR mode that format is `GUICC_8888`. When switching to ARGB that format is `GUICC_M8888I`.

DIB bitmaps

Palette based bitmaps created by the bitmap converter contains an array of palette colors. Example:

```
static GUI_CONST_STORAGE GUI_COLOR _Colors8x1[] = {
  0x000000, 0xC04040, 0x40C020, 0xC0A000,
  0x4020E0, 0xC040A0, 0x00FFFF, 0xFFFFFF
};
```

All existing bitmaps need to be changed:

```
static GUI_CONST_STORAGE GUI_COLOR _Colors8x1[] = {
  0xFF000000, 0xFF4040C0, 0xFF20C040, 0xFF00A0C0,
  0xFFE02040, 0xFFA040C0, 0xFFFFFF00, 0xFFFFFFFF
};
```

If an application contains a large number of bitmaps a better way would be to convert the bitmaps again with new settings for the bitmap converter.

 © 2020 SEGGER Microcontroller GmbH

16.3.3 Configuring the BitmapConverter

In order to configure the bitmap converter to save colors directly in ARGB instead of ABGR the option available under **Options ➔ Save colors in ARGB mode** should be activated:



 © 2020 SEGGER Microcontroller GmbH

16.4 Predefined colors

In addition to self-defined colors, some standard colors are predefined in emWin, as shown in the following table:

GUI_BLUE		0xFF0000
GUI_GREEN		0x00FF00
GUI_RED		0x0000FF
GUI_CYAN		0xFFFF00
GUI_MAGENTA		0xFF00FF
GUI_YELLOW		0x00FFFF
GUI_LIGHTBLUE		0xFF8080
GUI_LIGHTGREEN		0x80FF80
GUI_LIGHTRED		0x8080FF
GUI_LIGHTCYAN		0xFFFF80
GUI_LIGHTMAGENTA		0xFF80FF
GUI_LIGHTYELLOW		0x80FFFF
GUI_DARKBLUE		0x800000
GUI_DARKGREEN		0x008000
GUI_DARKRED		0x000080
GUI_DARKCYAN		0x808000
GUI_DARKMAGENTA		0x800080
GUI_DARKYELLOW		0x008080
GUI_WHITE		0xFFFFFF
GUI_LIGHTGRAY		0xD3D3D3
GUI_GRAY		0x808080
GUI_DARKGRAY		0x404040
GUI_BLACK		0x000000
GUI_BROWN		0x2A2AA5
GUI_ORANGE		0x00A5FF

Example

```
/* Set background color to magenta */
GUI_SetBkColor(GUI_MAGENTA);
GUI_Clear();
```

 © 2020 SEGGER Microcontroller GmbH

16.5 The color bar test routine

The color bar example program is used to show 13 color bars in the following order:

1. Black ➔ Red
2. White ➔ Red
3. Black ➔ Green
4. White ➔ Green
5. Black ➔ Blue
6. White ➔ Blue
7. Black ➔ White
8. Black ➔ Yellow
9. White ➔ Yellow
10. Black ➔ Cyan
11. White ➔ Cyan
12. Black ➔ Magenta
13. White ➔ Magenta

This simple routine may be used on all displays in any color format. Of course, the results vary depending on the colors that can be displayed; the routine requires a display size of 320 × 240 in order to show all colors. The routine is used to demonstrate the effect of the different color settings for displays. It may also be used by a test program to verify the functionality of the display, to check available colors and grayscales, as well as to correct color conversion. The screenshots are taken from the windows simulation and will look exactly like the actual output on your display if your settings and hardware are working properly. The routine is available as `COLOR_ShowColorBar.c` in the examples shipped with emWin.

 © 2020 SEGGER Microcontroller GmbH

16.6 Fixed palette modes

The following table lists the available fixed palette color modes and the necessary identifiers which need to be used when creating a driver- or a Memory Device. Detailed descriptions follow.

Identifier	No. available colors	Mask
GUICC_1	black and white	0x01 -> 00000001
GUICC_2	4 grayscales	0x03 -> 00000011
GUICC_4	16 grayscales	0x0F -> 00001111
GUICC_5	32 grayscales	0x1F -> 00011111
GUICC_16	16	0x0F -> 00001111
GUICC_1616I	16 + 4 bit alpha blending	0xFF -> 11111111
GUICC_111	8	0x07 -> 00000BGR
GUICC_M111	8	0x07 -> 00000RGB
GUICC_222	64	0x3F -> 00BBGGRR
GUICC_M222	64	0x3F -> 00RRGGBB
GUICC_8	256 grayscales	0xFF -> 11111111
GUICC_233	256	0xFF -> BBGGGRRR
GUICC_M233	256	0xFF -> RRGGGBBB
GUICC_323	256	0xFF -> BBBGGRRR
GUICC_M323	256	0xFF -> RRRGGBBB
GUICC_332	256	0xFF -> BBBGGGRR
GUICC_M332	256	0xFF -> RRRGGGBB
GUICC_444_12	4096	0x0FFF -> 0000BBBBGGGGRRRR
GUICC_M444_12	4096	0x0FFF -> 0000RRRRGGGGBBBB
GUICC_444_12_1	4096	0xFFF0 -> BBBBGGGGRRRR0000
GUICC_444_16	4096	0x7BDE -> 0BBBB0GGGG0RRRR0
GUICC_M444_16	4096	0x7BDE -> 0RRRR0GGGG0BBBB0
GUICC_M4444I	4096 + 4 bit alpha blending	0xFFFF -> AAAARRRRGGGGBBBB
GUICC_555	32768	0x7FFF -> 0BBBBBGGGGGRRRRR
GUICC_M555	32768	0x7FFF -> 0RRRRRGGGGGBBBBB
GUICC_M1555I	32768 + 1 bit transparency	0xFFFF -> TRRRRRGGGGGBBBBB
GUICC_565	65536	0xFFFF -> BBBBBGGGGGGRRRRR
GUICC_M565	65536	0xFFFF -> RRRRRGGGGGGBBBBB
GUICC_666	262144	0x0003FFFF -> BBBBBBGGGGGGRRRRRR
GUICC_M666	262144	0x0003FFFF -> RRRRRRGGGGGGBBBBBB
GUICC_666_9	262144	0x01FF01FF -> 0000000BBBBBBGGG0000000GGGRRRRRR
GUICC_M666_9	262144	0x01FF01FF -> 0000000RRRRRRGGG0000000GGGBBBBBB
GUICC_822216	256	0xFF - Bits are not explicitly assigned to a color.
GUICC_84444	240	0xFF - Bits are not explicitly assigned to a color.
GUICC_8666	232	0xFF - Bits are not explicitly assigned to a color.

 © 2020 SEGGER Microcontroller GmbH

Identifier	No. available colors	Mask
GUICC_8666_1	233 (232 + trans-parency)	0xFF - Bits are not explicitly assigned to a color.
GUICC_88666I	232 + 8 bits alpha blending	0xFFFF -> AAAAAAAACCCCCCCC
GUICC_888	16M	0x00FFFFFF -> BBBBBBBBGGGGGGGGRRRRRRRR
GUICC_M888	16M	0x00FFFFFF -> RRRRRRRRGGGGGGGGBBBBBBBB
GUICC_8888	16M + 8 bit alpha blending	0xFFFFFFFF -> AAAAAAAABBBBBBBBGGGGGGGGRRRRRRRR
GUICC_M8888	16M + 8 bit alpha blending	0xFFFFFFFF -> AAAAAAAARRRRRRRRGGGGGGGGBBBBBBBB
GUICC_M8888I	16M + 8 bit alpha blending	0xFFFFFFFF -> AAAAAAAARRRRRRRRGGGGGGGGBBBBBBBB
GUICC_0	-	CUSTOM DEFINED FIXED PALETTE MODE
GUICC_1_2 GUICC_1_4 GUICC_1_5 GUICC_1_8 GUICC_1_16 GUICC_1_24	2 (black and white)	0x00000001 0x00000003 0x0000001F 0x000000FF 0x0000FFFF 0x00FFFFFF

Legend

R - Red
G - Green
B - Blue
C - Color (in case of no explicit bit assignment to colors)
T - Transparency bit
A - Alpha mask

 © 2020 SEGGER Microcontroller GmbH

16.7 Detailed fixed palette mode description

The following gives a detailed description of the available colors in each predefined fixed palette mode.

16.7.1 GUICC_1: 1 bpp (black and white)

Use of this mode is necessary for monochrome displays with 1 bit per pixel.



Available colors: 2



16.7.2 GUICC_2: 2 bpp (4 grayscales)

Use of this mode is necessary for monochrome displays with 2 bits per pixel.



Available colors: 2 × 2 = 4



16.7.3 GUICC_4: 4 bpp (16 grayscales)

Use of this mode is necessary for monochrome displays with 4 bits per pixel.



Available colors: 2 × 2 × 2 × 2 = 16



16.7.4 GUICC_5: 5 bpp (32 grayscales)

Use of this mode is necessary for monochrome displays with 5 bits per pixel.



 © 2020 SEGGER Microcontroller GmbH

Available colors: 2 × 2 × 2 × 2 × 2 = 32



16.7.5 GUICC_111: 3 bpp (2 levels per color)

Use this mode if the basic 8 colors are enough, if your hardware supports only one bit per pixel and color or if you do not have sufficient video memory for a higher color depth.



Available colors: 2 × 2 × 2 = 8
Color mask: BGR



16.7.6 GUICC_M111: 3 bpp (2 levels per color), red and blue swapped

Use this mode if the basic 8 colors are enough, if your hardware supports only one bit per pixel and color or if you do not have sufficient video memory for a higher color depth. The available colors are the same as those in 111 mode.

Available colors: 2 × 2 × 2 = 8
Color mask: RGB



16.7.7 GUICC_16: 4 bpp (16 colors)

This mode can be used if the basic 16 colors are enough, if the hardware supports only 4 bits per pixel or if you do not have sufficient video memory for a higher color depth.



Available colors: 2 × 2 × 2 × 2 = 16



16.7.8 GUICC_1616I: 8 bpp (16 colors + 4 bits alpha mask)

Same colors as in GUICC_16. The lower 4 bits contain the color and the upper 4 bits are used for alpha blending.



Available colors: 2 × 2 × 2 × 2 = 16
Color mask: AAAACCCC



 © 2020 SEGGER Microcontroller GmbH

(AAAA = 0xF - opaque)
(AAAA = 0x0 - transparent)

16.7.9 GUICC_222: 6 bpp (4 levels per color)

This mode is a good choice if your hardware does not have a palette for every individual color. 2 bits per pixel and color are reserved; usually 1 byte is used to store one pixel.



Available colors: 4 × 4 × 4 = 64



Color mask: BBGGRR

16.7.10 GUICC_M222: 6 bpp (4 levels per color), red and blue swapped

This mode is a good choice if your hardware does not have a palette for every individual color. 2 bits per pixel and color are reserved; usually 1 byte is used to store one pixel. The available colors are the same as those in 222 mode.

Available colors: 4 × 4 × 4 = 64



Color mask: RRGGBB

16.7.11 GUICC_8: 8 bpp (256 grayscales)

This mode uses 8 bpp for grayscales only. This is the smoothes possible grayscale mode.



 © 2020 SEGGER Microcontroller GmbH

Available colors: 256 shades of gray.



16.7.12 GUICC_233: 8 bpp

This mode supports 256 colors. 3 bits are used for the red and green components of the color and 2 bits for the blue component. As shown in the picture, the result is 8 grades for green and red and 4 grades for blue. We discourage the use of this mode because it do not contain real shades of gray.



Available colors: 4 × 8 × 8 = 256



Color mask: BBGGGRRR

16.7.13 GUICC_M233: 8 bpp, red and blue swapped

This mode supports 256 colors. 3 bits are used for the red and green components of the color and 2 bits for the blue component. The result is 8 grades for green and blue and 4 grades for red. We discourage the use of this mode because it do not contain real shades of gray.



 © 2020 SEGGER Microcontroller GmbH

Available colors: 4 × 8 × 8 = 256



Color mask: RRGGGBBB

16.7.14 GUICC_323: 8 bpp

This mode supports 256 colors. 3 bits are used for the red and blue components of the color and 2 bits for the green component. As shown in the picture, the result is 8 grades for blue and red and 4 grades for green. We discourage the use of this mode because it do not contain real shades of gray.



Available colors: 8 × 4 × 8 = 256



Color mask: BBBGGRRR

16.7.15 GUICC_M323: 8 bpp, red and blue swapped

This mode supports 256 colors. 3 bits are used for the red and blue components of the color and 2 bits for the green component. The available colors are the same as those in 323 mode. The result is 8 grades for red and blue and 4 grades for green. We discourage the use of this mode because it do not contain real shades of gray.

 © 2020 SEGGER Microcontroller GmbH



Available colors: 8 × 4 × 8 = 256



Color mask: RRRGGBBB

16.7.16 GUICC_332: 8 bpp

This mode supports 256 colors. 3 bits are used for the blue and green components of the color and 2 bits for the red component. As shown in the picture, the result is 8 grades for green and blue and 4 grades for red. We discourage the use of this mode because it do not contain real shades of gray.



Available colors: 8 × 8 × 4 = 256



Color mask: BBBGGGRR

16.7.17 GUICC_M332: 8 bpp, red and blue swapped

This mode supports 256 colors. 3 bits are used for the red and green components of the color and 2 bits for the blue component. The result is 8 grades for red and green and only 4 grades for blue. We discourage the use of this mode because it do not contain real shades of gray.

 © 2020 SEGGER Microcontroller GmbH



Available colors: `8 × 8 × 4 = 256`

Color mask: `RRRGGGBB`

16.7.18 GUICC_444_12:

The red, green and blue components are each 4 bits.



Available colors: `16 × 16 × 16 = 4096`
Color mask: `0000BBBBGGGGRRRR`

16.7.19 GUICC_444_16:

The red, green and blue components are each 4 bits. One bit between the color components is not used. The available colors are the same as those in `444_12` mode.



Available colors: `16 × 16 × 16 = 4096`
Color mask: `0BBBB0GGGG0RRRR0`

16.7.20 GUICC_M444_12: red and blue swapped

The red, green and blue components are each 4 bits. The available colors are the same as those in `444_12` mode.

 © 2020 SEGGER Microcontroller GmbH



Available colors: 16 × 16 × 16 = 4096
Color mask: RRRRGGGGBBBB

16.7.21 GUICC_M444_16: red and blue swapped

The red, green and blue components are each 4 bits. One bit between the color components is not used. The available colors are the same as those in 444_12 mode.



Available colors: 16 × 16 × 16 = 4096
Color mask: 0RRRR0GGGG0BBBB0

16.7.22 GUICC_M444_12_1:

The red, green and blue components are each 4 bits. The lower 4 bits of the color mask are not used. The available colors are the same as those in 444_12 mode.



Available colors: 16 × 16 × 16 = 4096
Color mask: BBBBGGGGRRRR0000

16.7.23 GUICC_M4444I: 12 bits colors + 4 bits alpha mask

The red, green and blue components are each 4 bits, the upper 4 bits are used for alpha blending.



Available colors: 16 × 16 × 16 = 4096
Color mask: AAAARRRRGGGGBBBB
(AAAA = 0xF - opaque)

 © 2020 SEGGER Microcontroller GmbH

(AAAA = 0x0 - transparent)

16.7.24 GUICC_555: 15 bpp

Use of this mode is necessary for a display controller that supports RGB colors with a color-depth of 15 bpp. The red, green and blue components are each 5 bits.



Available colors: 32 × 32 × 32 = 32768
Color mask: BBBBBGGGGGRRRRR

16.7.25 GUICC_M555: 15 bpp, red and blue swapped

Use of this mode is necessary for a display controller that supports RGB colors with a color-depth of 15 bpp. The red, green and blue components are each 5 bits. The available colors are the same as those in 555 mode.



Available colors: 32 × 32 × 32 = 32768
Color mask: RRRRRGGGGGBBBBB

16.7.26 GUICC_M1555I: 15 bits colors + 1 bit transparency

The available colors are the same as those in 565 mode. The red, green and blue components are each 5 bits, the upper bit is used for transparency.



Available colors: 32 × 32 × 32 = 32768
Color mask: ARRRRRGGGGGBBBBB
(A = 1 - opaque)
(A = 0 - transparent)

16.7.27 GUICC_565: 16 bpp

Use of this mode is necessary for a display controller that supports RGB colors with a color-depth of 16 bpp. The red and the blue component is 5 bits and the green component is 6 bit.

 © 2020 SEGGER Microcontroller GmbH



Available colors: 32 × 64 × 32 = 65536
Color mask: BBBBBGGGGGGRRRRR

16.7.28 GUICC_M565: 16 bpp, red and blue swapped

Use of this mode is necessary for a display controller that supports RGB colors with a color-depth of 16 bpp. The available colors are the same as those in 565 mode.



Available colors: 32 × 64 × 32 = 65536
Color mask: RRRRRGGGGGGBBBBB

16.7.29 GUICC_666: 18 bpp

Use of this mode is necessary for a display controller that supports RGB colors with a color-depth of 18 bpp. The red, green and blue component is 6 bit.

Available colors: 64 × 64 × 64 = 262144 Color mask: BBBBBBGGGGGGRRRRRR

16.7.30 GUICC_M666: 18 bpp, red and blue swapped

Use of this mode is necessary for a display controller that supports RGB colors with a color-depth of 18 bpp. The red, green and the blue component is 6 bit.

Available colors: 64 × 64 × 64 = 262144 Color mask: RRRRRRGGGGGGBBBBBB

16.7.31 GUICC_666_9: 18 bpp

Use of this mode is necessary for a display controller that supports RGB colors with a color-depth of 18 bpp. The red, green and blue component is 6 bit.

Available colors: 64 × 64 × 64 = 262144
Color mask: 0000000BBBBB-
BGGG0000000GGGRRRRRR

16.7.32 GUICC_M666_9: 18 bpp, red and blue swapped

Use of this mode is necessary for a display controller that supports RGB colors with a color-depth of 18 bpp. The red, green and blue component is 6 bit.

Available colors: 64 × 64 × 64 = 262144 Color mask: RRRRRRGGGGGGBBBBBB

 © 2020 SEGGER Microcontroller GmbH

16.7.33 GUICC_822216: 8 bpp, 2 levels per color + 8 grayscales + 16 levels of alpha blending

This mode can be used with a programmable color lookup table (LUT), supporting a total of 256 possible colors and alpha blending support. It supports the 8 basic colors, 8 grayscales and 16 levels of alpha blending for each color / grayscale. With other words it can be used if only a few colors are required but more levels of alpha blending.



Available colors: `(2 × 2 × 2 + 8) × 16 = 256`



16.7.34 GUICC_84444: 8 bpp, 4 levels per color + 16 grayscales + 4(3) levels of alpha blending

This mode can be used with a programmable color lookup table (LUT), supporting a total of 240 possible colors and alpha blending support. 4 levels of intensity are available for each color, in addition to 16 grayscales and 4 levels of alpha blending for each color / grayscale. With other words it can be used if only a few levels of alpha blending are required and different shades of colors.



 © 2020 SEGGER Microcontroller GmbH

Available colors: `(4 × 4 × 4 + 16) × 3 = 240`



16.7.35 GUICC_8666: 8bpp, 6 levels per color + 16 grayscales

This mode is most frequently used with a programmable color lookup table (LUT), supporting a total of 256 possible colors using a palette. The screenshot gives an idea of the available colors; this mode contains the best choice for general purpose applications. Six levels of intensity are available for each color, in addition to 16 grayscales.



Available colors: `6 × 6 × 6 + 16 = 232`



16.7.36 GUICC_8666_1: 8bpp, 6 levels per color + 16 grayscales + transparency

This mode is most frequently used with MultiLayer configurations and a programmable color lookup table (LUT), supporting a total of 256 possible colors using a palette. The difference between 8666 and 86661 is, that the first color indices of the 86661 mode are not used. So the color conversion routine `GUI_Color2Index()` does never return 0 which is used for transparency.

 © 2020 SEGGER Microcontroller GmbH

Available colors: 6 × 6 × 6 + 16 = 232



16.7.37 GUICC_88666I: 16bpp - 8 bits color (6 levels per color + 16 grayscales) + 8 bits alpha blending

The available colors of this mode are exactly the same as described under GUICC_8666. The upper 8 bits are used for alpha blending.



Color mask: AAAAAAAACCCCCCCC
(AAAAAAAA = 0xFF - opaque)
(AAAAAAAA = 0x00 - transparent)

16.7.38 GUICC_888: 24 bpp

Use of this mode is necessary for a display controller that supports RGB colors with a color depth of 24 bpp. The red, green and blue components are each 8 bits.



Available colors: 256 × 256 × 256 = 16777216
Color mask: BBBBBBBBGGGGGGGGRRRRRRRR

16.7.39 GUICC_M888: 24 bpp, red and blue swapped

Use of this mode is necessary for a display controller that supports RGB colors with a color depth of 24 bpp. The red, green and blue components are each 8 bits.

 © 2020 SEGGER Microcontroller GmbH



Available colors: 256 × 256 × 256 = 16777216
Color mask: RRRRRRRRGGGGGGGGBBBBBBBB

16.7.40 GUICC_8888: 32 bpp

Use of this mode is necessary for a display controller that supports RGB colors with a color depth of 32 bpp, where the lower 3 bytes are used for the color components and the upper byte is used for alpha blending. The red, green, blue and alpha blending components are each 8 bits.



Available colors: 256 × 256 × 256 = 16777216
Color mask: AAAAAAAABBBBBBBBGGGGGGGGRRRRRRRR

16.7.41 GUICC_M8888: 32 bpp, red and blue swapped

Use of this mode is necessary for a display controller that supports RGB colors with a color depth of 32 bpp, where the lower 3 bytes are used for the color components and the upper byte is used for alpha blending. The red, green, blue and alpha blending components are each 8 bits.

Available colors: 256 × 256 × 256 = 16777216
Color mask: AAAAAAAARRRRRRRRGGGGGGGG-BBBBBBBB

16.7.42 GUICC_M8888I: 32 bpp, red and blue swapped

The color mode is exactly the same as described under GUICC_M8888 with the difference, that alpha blending is inverted.



Color mask: AAAAAAAARRRRRRRRGGGGGGGGBBBBBBBB
(AAAAAAAA = 0xFF - opaque)
(AAAAAAAA = 0x00 - transparent)

 © 2020 SEGGER Microcontroller GmbH

16.7.43 GUICC_0: Custom palette mode

How to use a custom palette mode is described under *Application defined color conversion* on page 641.

16.7.44 GUICC_1_2, GUICC_1_4, ... GUICC_1_24

These color conversion routines make it possible, to use display drivers which require a color depth of more than 1bpp, with emWin packages containing no support for colors or grayscales. The routines ensure that each color of the whole palette of possible colors will be converted into black or white.

Example

If the available emWin package does not contain color- or gray scale support and only a driver, which requires index values of 16 bits is available, `GUICC_1_16` can be used. This color conversion scheme ensures that each color of the whole 16 bit palette will be converted into `0xFFFF` (normally white) or `0x0000` (normally black).

 © 2020 SEGGER Microcontroller GmbH

16.8 Application defined color conversion

If none of the fixed palette modes matches the need of color conversion this mode makes it possible to use application defined color conversion routines. The purpose of these routines is converting an RGB value into an index value for the hardware and vice versa.

Example of defining custom color conversion routines

The following example should explain how it works:

```
static unsigned _Color2Index_User(LCD_COLOR Color) {
  unsigned Index;
  /* Add code for converting the RGB value to an index value for the hardware */
  return Index;
}
static LCD_COLOR _Index2Color_User(unsigned Index) {
  LCD_COLOR Color;
  /* Add code for converting the index value into an RGB value */
  return Color;
}
static unsigned _GetIndexMask_User(void) {
  return 0xffff; /* Example for using 16 bits */
}
const LCD_API_COLOR_CONV LCD_API_ColorConv_User = {
  _Color2Index_User,
  _Index2Color_User,
  _GetIndexMask_User
};
```

The function `LCD_Color2Index_User` is called by emWin if a RGB value should be converted into an index value for the display controller whereas the function `LCD_Index2Color_User()` is called if an index value should be converted into a RGB value.
`LCD_GetIndexMask_User` should return a bit mask value, which has each bit set to 1 which is used by the display controller and unused bits should be set to 0. For example the index mask of `GUICC_44416` mode is 0BBBB0GGGG0RRRR0, where 0 stands for unused bits. The bit mask for this mode is `0x7BDE`.

Example of using custom color conversion routines

As described in the chapter *Configuration* on page 620 a pointer to an API table is required for creating the display driver device. As shown in the example above the API table consists of function pointers to the color conversion routines.
A good location for the API table and the color conversion routines is the configuration file `LCDConf.c` located in the `Config` folder. The routines can be used as follow in the function `LCD_X_Config` which is responsible to create the display driver device:

```
void LCD_X_Config(void) {
  //
  // Set display driver and color conversion for 1st layer
  //
  GUI_DEVICE_CreateAndLink(GUIDRV_LIN_16, &LCD_API_ColorConv_User, 0, 0);
  .
  .
  .
}
```

 © 2020 SEGGER Microcontroller GmbH

16.9 Custom palette mode

If none of the fixed palette modes fulfills the requirements of the application emWin is able to use a custom palette. A custom palette simply lists all the available colors in the same order as they are used by the hardware. This means that no matter what colors the display controller/display combination is able to display, emWin will be able to simulate them in the PC simulation and handle these colors correctly in the target system. Working with a custom palette requires a color depth ≤ 8 bpp.
A custom palette is typically configured during the initialization in the function `LCD_X_Config()` which is responsible for creating and configuring the display driver device. This requires setting the look-up table entries using the function `LCD_SetLUTEntryEx()` which in turn is called by the functions `LCD_SetLUT()` and `LCD_SetLUTEx()`. These functions are implemented in the custom palette mode module `GUICC_0.c`, but might require modification according to the used hardware. Detailed information can be found in the according function descriptions in the section *Look-up table API* on page 642.

Example

The following example should show how a custom palette can be used. It passes the palette to the function:

```
static const LCD_COLOR _aColors_16[] = {
  0x000000,  0x0000FF,  0x00FF00,  0x00FFFF,
  0xFF0000,  0xFF00FF,  0xFFFF00,  0xFFFFFF,
  0x000000,  0x000080,  0x008000,  0x008080,
  0x800000,  0x800080,  0x808000,  0x808080,
};
static const LCD_PHYSPALETTE _aPalette_16 = {
  COUNTOF(_aColors_16), _aColors_16
};
void LCD_X_Config(void) {
  //
  // Set display driver and color conversion for 1st layer
  //
  .
  .
  .
  //
  // Set user palette data (only required if no fixed palette is used)
  //
  LCD_SetLUTEx(0, _aPalette_16);
}
```

Elements of structure LCD_PHYSPALETTE

Data type	Element	Description
`int`	`NumEntries`	Number of entries to be stored in the look-up table.
`const LCD_COLOR *`	`pPalEntries`	Pointer to an array of colors. The number of elements in this array has to match at least the value stored in NumEntries.

16.9.1 Look-up table API

Routine	Description
`LCD_SetLUT()`	Sets the look-up table for the currently selected layer.
`LCD_SetLUTEx()`	Sets the look-up table for the given layer.
`LCD_SetLUTEntryEx()`	Sets one entry in the look-up table.

 © 2020 SEGGER Microcontroller GmbH

16.9.1.1 LCD_SetLUT()

Description

Sets the look-up table for the currently selected layer. This function is defined in the module `GUICC_0.c`. It may require modification according to the used hardware.

Prototype

```
void LCD_SetLUT(const LCD_PHYSPALETTE * pPalette);
```

Parameters

Parameter	Description
`pPalette`	Pointer to a `LCD_PHYSPALETTE` structure.

 © 2020 SEGGER Microcontroller GmbH

16.9.1.2 LCD_SetLUTEx()

Description

Sets the look-up table for the given layer. This function is defined in the module `GUICC_0.c`. It may require modification according to the used hardware.

Prototype

```
void LCD_SetLUTEx(      int               LayerIndex,
                  const LCD_PHYSPALETTE * pPalette);
```

Parameters

Parameter	Description
`LayerIndex`	Index of the layer to set the look-up table for.
`pPalette`	Pointer to an `LCD_PHYSPALETTE` structure.

 © 2020 SEGGER Microcontroller GmbH

16.9.1.3 LCD_SetLUTEntryEx()

Description

Sets one entry in the look-up table.

Prototype

```
int LCD_SetLUTEntryEx(int       LayerIndex,
                      U8        Pos,
                      LCD_COLOR Color);
```

Parameters

Parameter	Description
LayerIndex	Index of the layer the look-up entry has to be set for.
Pos	Position in the look-up table to use for this color.
Color	32-bit color value.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

16.10 Gamma correction

Gamma correction can simply be achieved with custom color conversion routines. The trick is converting the colors twice. Please note that gamma correction does not work within the simulation.

Color2Index - conversion

It should first make the gamma correction of the color to be converted. The result of the gamma correction then should be passed to the Color2Index-function of the desired fixed palette mode, whose result then should be returned.

Index2Color - conversion

It should first convert the index to a color with the Color2Index-function of the desired fixed palette mode. The result then should be passed to the gamma correction routine whose result then should be returned.

Example

The sample folder `LCDConf\Common\` contains the sample file `LCDConf_GammaCorrection.c`. It shows in detail how gamma correction can be used.

 © 2020 SEGGER Microcontroller GmbH

16.11 Color API

The following table lists the available color-related functions in alphabetical order within their respective categories. Detailed description of the routines can be found in the sections that follow.

Basic functions	
GUI_GetBkColor()	Returns the current background color.
GUI_GetBkColorIndex()	Returns the index of the current background color.
GUI_GetColor()	Returns the current foreground color.
GUI_GetColorIndex()	Returns the index of the current foreground color.
GUI_GetDefaultColor()	Returns currently set default foreground color.
GUI_GetDefaultBkColor()	Returns currently set default background color.
GUI_SetBkColor()	Sets the default background color.
GUI_SetBkColorIndex()	Sets the index of the current background color.
GUI_SetColor()	Sets the current foreground color.
GUI_SetColorIndex()	Sets the index of the current foreground color.
GUI_SetDefaultColor()	Sets the default foreground color.
GUI_SetDefaultBkColor()	Sets the default background color.
Conversion functions	
GUI_CalcColorDist()	Calculates the distance between 2 colors.
GUI_CalcVisColorError()	Calculates the distance to the next available color.
GUI_Color2Index()	Returns the index of a specified RGB color value.
GUI_Color2VisColor()	Returns the next available color of the system as an RGB color value.
GUI_ColorIsAvailable()	Checks if the given color is available.
GUI_Index2Color()	Returns the RGB color value of a specified index.

 © 2020 SEGGER Microcontroller GmbH

16.11.1 Basic functions

16.11.1.1 GUI_GetBkColor()

Description

Returns the current background color.

Prototype

```
GUI_COLOR GUI_GetBkColor(void);
```

Return value

The current background color.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.2 GUI_GetBkColorIndex()

Description

Returns the index of the current background color.

Prototype

```
int GUI_GetBkColorIndex(void);
```

Return value

The current background color index.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.3 GUI_GetColor()

Description

Returns the current foreground color.

Prototype

```
GUI_COLOR GUI_GetColor(void);
```

Return value

The current foreground color.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.4 GUI_GetColorIndex()

Description

Returns the index of the current foreground color.

Prototype

```
int GUI_GetColorIndex(void);
```

Return value

The current foreground color index.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.5 GUI_GetDefaultColor()

Description

Returns currently set default foreground color.

Prototype

```
GUI_COLOR GUI_GetDefaultColor(void);
```

Return value

The default foreground color.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.6 GUI_GetDefaultBkColor()

Description

Returns currently set default background color.

Prototype

```
GUI_COLOR GUI_GetDefaultBkColor(void);
```

Return value

The current default background color.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.7 GUI_SetBkColor()

Description

Sets the default background color.

Prototype

```
void GUI_SetBkColor(GUI_COLOR color);
```

Parameters

Parameter	Description
Color	Color for background, 24-bit RGB value.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.8 GUI_SetBkColorIndex()

Description

Sets the index of the current background color.

Prototype

```
void GUI_SetBkColorIndex(LCD_PIXELINDEX Index);
```

Parameters

Parameter	Description
Index	Index of the color to be used.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.9 GUI_SetColor()

Description

Sets the current foreground color.

Prototype

```
void GUI_SetColor(GUI_COLOR color);
```

Parameters

Parameter	Description
Color	Color for foreground, 24-bit RGB value.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.10 GUI_SetColorIndex()

Description

Sets the index of the current foreground color.

Prototype

```
void GUI_SetColorIndex(LCD_PIXELINDEX Index);
```

Parameters

Parameter	Description
Index	Index of the color to be used.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.11 GUI_SetDefaultColor()

Description

Sets the default foreground color.

Prototype

```
void GUI_SetDefaultColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color for foreground, 24-bit RGB value.

 © 2020 SEGGER Microcontroller GmbH

16.11.1.12 GUI_SetDefaultBkColor()

Description

Sets the default background color.

Prototype

```
void GUI_SetDefaultBkColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color for foreground, 24-bit RGB value.

 © 2020 SEGGER Microcontroller GmbH

16.11.2 Conversion functions

16.11.2.1 GUI_CalcColorDist()

Description

Calculates the distance between 2 colors.

Prototype

```
U32 GUI_CalcColorDist(GUI_COLOR Color0,
                      GUI_COLOR Color1);
```

Parameters

Parameter	Description
Color0	RGB value of the first color.
Color1	RGB value of the second color.

Return value

The distance between the two colors as described.

Additional information

The distance will be calculated by the sum of the square value from the distances of the red, green and the blue component: Difference = (Red1 - Red0)² (Green1 - Green0)² (Blue1 - Blue0)²

 © 2020 SEGGER Microcontroller GmbH

16.11.2.2 GUI_CalcVisColorError()

Description

Calculates the distance to the next available color.

Prototype

```
U32 GUI_CalcVisColorError(GUI_COLOR color);
```

Parameters

Parameter	Description
Color	RGB value of the color to be calculated.

Return value

The distance to the next available color.

Additional information

For details about the calculation, refer to `GUI_CalcColorDist()`.

 © 2020 SEGGER Microcontroller GmbH

16.11.2.3 GUI_Color2Index()

Description

Returns the index of a specified RGB color value.

Prototype

```
int GUI_Color2Index(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	RGB value of the color to be calculated.

Return value

The color index.

 © 2020 SEGGER Microcontroller GmbH

16.11.2.4 GUI_Color2VisColor()

Description

Returns the next available color of the system as an RGB color value.

Prototype

```
GUI_COLOR GUI_Color2VisColor(GUI_COLOR color);
```

Parameters

Parameter	Description
Color	RGB value of the color.

Return value

The RGB color value of the nearest available color.

 © 2020 SEGGER Microcontroller GmbH

16.11.2.5 GUI_ColorIsAvailable()

Description

Checks if the given color is available.

Prototype

```
char GUI_ColorIsAvailable(GUI_COLOR color);
```

Parameters

Parameter	Description
Color	RGB value of the color.

Return value

1 if color is available
0 if not.

 © 2020 SEGGER Microcontroller GmbH

16.11.2.6 GUI_Index2Color()

Description

Returns the RGB color value of a specified index.

Prototype

```
GUI_COLOR GUI_Index2Color(int Index);
```

Parameters

Parameter	Description
Index	Index of the color to be converted.

Return value

The RGB color value.

 © 2020 SEGGER Microcontroller GmbH

Chapter 17

Memory Devices

Memory Devices can be used in a variety of situations, mainly to be used as a buffer for further drawing operations. For example, some images take some time to be displayed or loaded from memory. To reduce the overhead of loading or decoding images again and again, these images be drawn only once into a Memory Device. Later on only the Memory Device has to be displayed which is in most cases a simple `memcpy` operation. This will highly reduce the drawing time for frequently used images.

Memory Devices can also be used to modify a drawing before displaying it. This includes rotation, changing color and alpha values as well as blurring and blending. Further Memory Devices can be used as a last option to prevent flickering, but the first choice should be multi-buffering or a cache in case of an indirect display driver.

> **Note**
>
> Memory Devices are an additional (optional) software item and are not shipped with the emWin basic package. The software for Memory Devices is located in the subdirectory `GUI\Memdev`.

 © 2020 SEGGER Microcontroller GmbH

17.1 Using Memory Devices: Illustration

The following table shows screenshots of the same operations handled with and without a Memory Device. The objective in both cases is identical: a work piece is to be rotated and labeled with the respective angle of rotation (here, 10 degrees). In the first case (without a Memory Device) the screen must be cleared, then the polygon is redrawn in the new position and a string with the new label is written. In the second case (with a Memory Device) the same operations are performed in memory, but the screen is not updated during this time. The only update occurs when the routine `GUI_MEMDEV_CopyToLCD` is called, and this update reflects all the operations at once. Note that the initial states and final outputs of both procedures are identical.

API function	Without Memory Device	With Memory Device
Step 0: Initial state		
Step 1: `GUI_Clear()`		
Step 2: `GUI_DrawPolygon()`		
Step 3: `GUI_DispString()`		
Step 4: `GUI_MEMDEV_CopyToLCD()` (only when using Memory Device)		

 © 2020 SEGGER Microcontroller GmbH

17.2 Supported color depth (bpp)

Memory Devices are available in 4 different color depths:

- 1 bpp
- 8 bpp
- 16 bpp
- 32 bpp

Creating Memory Devices "compatible" to the display

There are two ways to create Memory Devices. If they are use to avoid flickering, a Memory Device compatible to the display is created. This “compatible” Memory Device needs to have the same or a higher color depth as the display. emWin automatically selects the “right” type of Memory Device for the display if the functions `GUI_MEMDEV_Create()`, `GUI_MEMDEV_CreateEx()` are used.
The Window Manager, which also has the ability to use Memory Devices for some or all windows in the system, also uses these functions.
This way, the Memory Device with the lowest color depth (using the least memory) is automatically used.

Creating Memory Devices for other purposes

Memory Devices of any type can be created using `GUI_MEMDEV_CreateFixed()`. A typical application would be the use of a Memory Device for printing as described later in this chapter.

 © 2020 SEGGER Microcontroller GmbH

17.3 Memory Devices and the Window Manager

The Window Manager works seamlessly with Memory Devices. Every window has a flag which tells the Window Manager if a Memory Device should be used for rendering. This flag can be specified when creating the window or set/reset at any time.
If the Memory Device flag is set for a particular window, the WM automatically uses a Memory Device when drawing the window. It creates a Memory Device before drawing a window and deletes it after the drawing operation. If enough memory is available, the whole window fits into the size of the Memory Device created by the WM. If not enough memory is available for the complete window in one Memory Device, the WM uses 'banding' for drawing the window. Details about 'banding' are described in the chapter *Banding Memory Device* on page 721. The memory used for the drawing operation is only allocated during the drawing operation. If there is not enough memory available when (re-)drawing the window, the window is redrawn without Memory Device.

 © 2020 SEGGER Microcontroller GmbH

17.4 Memory Devices and multiple layers

The Memory Device API does not offer any option to specify a layer. Memory Devices are associated with the current layer at creation. The color conversion settings of the current layer are automatically used by Memory Devices.

Example

```
//
// Create a Memory Device associated with layer 1
//
GUI_SelectLayer(1);
hMem = GUI_MEMDEV_Create(0, 0, 100, 100);
GUI_MEMDEV_Select(hMem);
GUI_DrawLine(0, 0, 99, 99);
GUI_MEMDEV_Select(0);
//
// Select layer 0
//
GUI_SelectLayer(0);
//
// The following line copies the Memory Device to layer 1 and not to layer 0
//
GUI_MEMDEV_CopyToLCD(hMem);
```

 © 2020 SEGGER Microcontroller GmbH

17.5 Memory requirements

If creating a Memory Device the required number of bytes depends on the color depth of the Memory Device and whether transparency support is needed or not.

Memory usage without transparency support

The following table shows the memory requirement in dependence of the system color depth for Memory Devices without transparency support.

Color depth of Memory Device	System color depth (LCD_BITSPERPIXEL)	Memory usage
1 bpp	1 bpp	1 byte / 8 pixels: `(XSIZE + 7) ÷ 8 × YSIZE`
8 bpp	2, 4 and 8 bpp	`XSIZE × YSIZE`
16 bpp	12 and 16 bpp	2 bytes / pixel: `XSIZE × YSIZE × 2`
32 bpp	18, 24 and 32 bpp	4 bytes / pixel: `XSIZE × YSIZE × 4`

Example

A Memory Device of 111 pixels in X and 33 pixels in Y should be created. It should be compatible to a display with a color depth of 12 bpp and should support transparency. The required number of bytes can be calculated as follows:

```
Number of required bytes = (111 × 2 + (111 + 7) ÷ 8) × 33 = 7788 bytes
```

Memory usage with transparency support

If a Memory Device should support transparency it needs one additional byte / 8 pixels for internal management.

Color depth of Memory Device	System color depth (LCD_BITSPERPIXEL)	Memory usage
1 bpp	1 bpp	2 byte / 8 pixels: `(XSIZE + 7) ÷ 8 × YSIZE × 2`
8 bpp	2, 4 and 8 bpp	1 bytes / pixel + 1 byte / 8 pixels: `(XSIZE + (XSIZE + 7) ÷ 8) × YSIZE`
16 bpp	12 and 16 bpp	2 bytes / pixel + 1 byte / 8 pixels: `(XSIZE × 2 + (XSIZE + 7) ÷ 8) × YSIZE`
32 bpp	18, 24 and 32 bpp	4 bytes / pixel: `XSIZE × 4 × YSIZE`

Example

A Memory Device of 200 pixels in X and 50 pixels in Y should be created. It should be compatible to a display with a color depth of 4bpp and should support transparency. The required number of bytes can be calculated as follows:

```
Number of required bytes = (200 + (200 + 7) ÷ 8) × 50 = 11250 bytes
```

Memory usage with window animation functions

One static Memory Device is created for each, the given window and all of its child window. The color depth is always 32bpp.

 © 2020 SEGGER Microcontroller GmbH

17.6 Performance

Using Memory Devices typically does not significantly affect performance. When Memory Devices are used, the work of the driver is easier: It simply transfers bitmaps to the display controller. On systems with slow drivers (for example displays connected via serial interface), the performance is better if Memory Devices are used; on systems with a fast driver (such as memory mapped display memory, `GUIDRV_Lin` and others) the use of Memory Devices costs some performance.
If 'banding' is needed, the used time to draw a window increases with the number of bands. The more memory available for Memory Devices, the better the performance.

 © 2020 SEGGER Microcontroller GmbH

17.7 Basic functions

The following routines are those that are normally called when using Memory Devices. Basic usage is rather simple:

1. Create the Memory Device (using `GUI_MEMDEV_Create()`).
2. Activate it (using `GUI_MEMDEV_Select()`).
3. Execute drawing operations.
4. Copy the result into the display (using `GUI_MEMDEV_CopyToLCD()`).
5. Delete the Memory Device if you no longer need it (using `GUI_MEMDEV_Delete()`).
6. De-select the Memory Device (using `GUI_MEMDEV_Select(0)` or with the return value of the previous call of `GUI_MEMDEV_Select()`).

 © 2020 SEGGER Microcontroller GmbH

17.8 In order to be able to use Memory Devices...

Memory Devices are enabled by default. In order to optimize performance of the software, support for Memory Devices can be switched off in the configuration file `GUIConf.h` by including the following line:

```
#define GUI_SUPPORT_MEMDEV        0
```

If this line is in the configuration file and you want to use Memory Devices, either delete the line or change the define to 1.

 © 2020 SEGGER Microcontroller GmbH

17.9 MultiLayer / MultiDisplay configuration

As explained earlier in this chapter Memory Devices “compatible” to the display needs to have the same or a higher color depth as the display. When creating a Memory Device compatible to the display emWin “knows” the color depth of the currently selected layer/display and automatically uses the lowest color depth.

 © 2020 SEGGER Microcontroller GmbH

17.10 Configuration options

Type	Macro	Default	Description
B	GUI_USE_MEMDEV_1BPP_FOR_SCREEN	1	Enables the use of 1bpp Memory Devices with displays of 1bpp color depth.

GUI_USE_MEMDEV_1BPP_FOR_SCREEN

On systems with a display color depth ≤ 8bpp the default color depth of Memory Devices compatible to the display is 8bpp. To enable the use of 1bpp Memory Devices with displays of 1bpp color depth the following line should be added to the configuration file `GUIConf.h`:

```
#define GUI_USE_MEMDEV_1BPP_FOR_SCREEN 0
```

 © 2020 SEGGER Microcontroller GmbH

17.11 Memory Device API

The table below lists the available routines of the emWin Memory Device API. All functions are listed in alphabetical order within their respective categories. Detailed descriptions of the routines can be found in the sections that follow.

Functions

Routine	Description
Basic functions	
GUI_MEMDEV_Clear()	Marks the entire contents of a Memory Device as "unchanged".
GUI_MEMDEV_ClearAlpha()	Clears all alpha values in the given memory device.
GUI_MEMDEV_CopyFromLCD()	Reads back the content of the display and stores it in the given Memory Device.
GUI_MEMDEV_CopyToLCD()	Copies the contents of a Memory Device from memory to the LCD.
GUI_MEMDEV_CopyToLCDAA()	Copies the contents of a Memory Device (antialiased) to the LCD.
GUI_MEMDEV_CopyToLCDAt()	Copies the contents of a Memory Device to the LCD at the given position.
GUI_MEMDEV_Create()	Creates the Memory Device (first step).
GUI_MEMDEV_CreateCopy()	This function creates a copy from a memory device.
GUI_MEMDEV_CreateEx()	Creates a Memory Device.
GUI_MEMDEV_CreateFixed()	Creates a Memory Device with dedicated color depth color conversion.
GUI_MEMDEV_CreateFixed32()	Creates a 32bpp Memory Device.
GUI_MEMDEV_Delete()	Deletes a Memory Device.
GUI_MEMDEV_DrawPerspectiveX()	Draws the given Memory Device perspectively distorted into the current selected device.
GUI_MEMDEV_GetDataPtr()	Returns a pointer to the data area (image area) of a Memory Device.
GUI_MEMDEV_GetXSize()	Returns the X-size (width) of a Memory Device.
GUI_MEMDEV_GetYSize()	Returns the Y-size (height) of a Memory Device in pixels.
GUI_MEMDEV_MarkDirty()	Marks a rectangle area as dirty.
GUI_MEMDEV_PunchOutDevice()	Punches out a shape of a Memory Device defined by a 8bpp mask Memory Device.
GUI_MEMDEV_ReduceYSize()	Reduces the Y-size of a Memory Device.
GUI_MEMDEV_Rotate()	Rotates and scales a Memory Device and writes the result into a Memory Device using the 'nearest neighbor' method.
GUI_MEMDEV_RotateAlpha()	Rotates and scales a Memory Device and blends in the result into a Memory Device using the 'nearest neighbor' method and the given alpha value.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_MEMDEV_RotateHQ()	Rotates and scales a Memory Device and writes the result into a Memory Device using the 'high quality' method.
GUI_MEMDEV_RotateHQAlpha()	Rotates and scales a Memory Device and blends in the result into a Memory Device using the 'high quality' method and the given alpha value.
GUI_MEMDEV_RotateHQHR()	Rotates and scales a Memory Device and writes the result into a Memory Device using the 'high quality' as well as the 'high resolution' method.
GUI_MEMDEV_RotateHQT()	Rotates and scales a Memory Device and writes the result into a Memory Device using the 'high quality' method. (Optimized for images with a large amount of transparent pixels)
GUI_MEMDEV_RotateHR()	Rotates and scales a Memory Device and writes the result into a Memory Device using the 'high resolution' method.
GUI_MEMDEV_Select()	Activates a Memory Device (or activates LCD if handle is 0).
GUI_MEMDEV_SerializeBMP()	Creates a BMP file from the given Memory Device.
GUI_MEMDEV_SetOrg()	Changes the origin of the Memory Device on the LCD.
GUI_MEMDEV_Write()	Writes the content of the given Memory Device into the currently selected device.
GUI_MEMDEV_WriteAlpha()	Writes the content of the given Memory Device into the currently selected device using alpha blending.
GUI_MEMDEV_WriteAlphaAt()	Writes the content of the given Memory Device into the currently selected device at the specified position using alpha blending.
GUI_MEMDEV_WriteAt()	Writes the content of the given Memory Device into the currently selected device at the specified position.
GUI_MEMDEV_WriteEx()	Writes the content of the given Memory Device into the currently selected device at position (0, 0) using alpha blending and scaling.
GUI_MEMDEV_WriteExAt()	Writes the content of the given Memory Device into the currently selected device at the specified position using alpha blending and scaling.
GUI_MEMDEV_WriteOpaque()	Writes the content of the given Memory Device into the currently selected device.
GUI_MEMDEV_WriteOpaqueAt()	Writes the content of the given Memory Device into the currently selected device at the specified position.
GUI_SelectLCD()	Selects the LCD as target for drawing operations.
Banding Memory Device	

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_MEMDEV_Draw()	Use a Memory Device for drawing.
Auto device object functions	
GUI_MEMDEV_CreateAuto()	Creates an auto device object.
GUI_MEMDEV_DeleteAuto()	Deletes an auto device object.
GUI_MEMDEV_DrawAuto()	Executes a specified drawing routine using a banding Memory Device.
Measurement device object functions	
GUI_MEASDEV_ClearRect()	Clears the measurement rectangle.
GUI_MEASDEV_Create()	Creates a measurement device.
GUI_MEASDEV_Delete()	Deletes a measurement device.
GUI_MEASDEV_GetRect()	Retrieves the measurement result.
GUI_MEASDEV_Select()	Selects a measurement device as target for drawing operations.
Animation functions	
GUI_MEMDEV_FadeInDevices()	Performs fading in one device over another Memory Device.
GUI_MEMDEV_FadeOutDevices()	Performs fading out one device overlaying another Memory Device.
GUI_MEMDEV_SetAnimationCallback()	Sets a user defined callback function to be called while animations are processed.
GUI_MEMDEV_SetTimePerFrame()	Sets the minimum time used for one animation frame.
Animation functions (Window Manager required)	
GUI_MEMDEV_FadeInWindow()	Fades in a window by decreasing the alpha value.
GUI_MEMDEV_FadeOutWindow()	Fades out a window by increasing the alpha value.
GUI_MEMDEV_MoveInWindow()	Moves a window into the screen.
GUI_MEMDEV_MoveOutWindow()	Moves a window out of the screen.
GUI_MEMDEV_ShiftInWindow()	Shifts a Window in a specified direction into the screen to its actual position.
GUI_MEMDEV_ShiftOutWindow()	Shifts a Window in a specified direction out of the screen from its actual position.
GUI_MEMDEV_SwapWindow()	Swaps a window with the old content of the target area.
Blending, Blurring and Dithering functions	
GUI_MEMDEV_BlendColor32()	Blends a window with the given color and blending intensity.
GUI_MEMDEV_CreateBlurredDevice32()	Creates a blurred copy of the given Memory Device using the currently set blurring function.
GUI_MEMDEV_CreateBlurredDevice32HQ()	Creates a blurred copy of the given Memory Device at high quality.
GUI_MEMDEV_CreateBlurredDevice32LQ()	Creates a blurred copy of the given Memory Device at low quality.
GUI_MEMDEV_Dither32()	The function dithers the given memory device using the given fixed palette mode.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_MEMDEV_SetBlurHQ()	Sets the blurring behavior of the function GUI_MEMDEV_CreateBlurredDevice32() to HQ.
GUI_MEMDEV_SetBlurLQ()	Sets the blurring behavior of the function GUI_MEMDEV_CreateBlurredDevice32() to LQ.
Blending and Blurring functions (Window Manager required)	
GUI_MEMDEV_BlendWinBk()	Blends the background of a window.
GUI_MEMDEV_BlurAndBlendWinBk()	Blurs and blends the background of a window.
GUI_MEMDEV_BlurWinBk()	Blurs the background of a window.
Setting up multiple buffering for animation functions	
GUI_MEMDEV_MULTIBUF_Enable()	Enable use of multiple buffers for memory device animation functions.

Defines

Group of defines	Description
Color conversion routines	Defines the desired color conversion routine for a memory device.
Direction symbols	Direction in which a window should be moved to using memory devices.
Memory device color depths	Available color depths for fixed memory devices.
Memory device flags	Flags to be used for the creation of a memory device.

 © 2020 SEGGER Microcontroller GmbH

17.11.1 Basic functions

17.11.1.1 GUI_MEMDEV_Clear()

Description

Marks the entire contents of a Memory Device as “unchanged”.

Prototype

```
void GUI_MEMDEV_Clear(GUI_MEMDEV_Handle hMem);
```

Parameters

Parameter	Description
hMem	Handle to a Memory Device.

Return value

The next drawing operation with `GUI_MEMDEV_CopyToLCD()` will then write only the bytes modified between `GUI_MEMDEV_Clear()` and `GUI_MEMDEV_CopyToLCD()`.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.2 GUI_MEMDEV_ClearAlpha()

Description

Clears all alpha values in the given Memory Device with the help of an 1bpp Memory Device mask.

Prototype

```
int GUI_MEMDEV_ClearAlpha(GUI_MEMDEV_Handle hMemData,
                          GUI_MEMDEV_Handle hMemMask);
```

Parameters

Parameter	Description
hMemData	Handle to a Memory Device. Must be a 32bpp Memory Device.
hMemMask	Optional handle to a Memory Device mask. Must be an 1bpp Memory Device with the same size as the hMemData handle.

Return value

0 on success
1 on error.

Additional information

The Memory Device mask must have the same dimensions as the given hMemData Memory Device. To use the Memory Device mask, an area has to be specified where the alpha values should be cleared. To do so basic drawing functions should be used. The function sets all pixels of the data memory device to opaque, which have the index value 1 in the mask memory device. If hMemMask is 0, the alpha values of the whole memory device will be set to opaque. No transparency remains then.

Example

```
#include "GUI.h"
/*********************************************************************
*
*       MainTask
*/
void MainTask(void) {
  GUI_MEMDEV_Handle hMemData;
  GUI_MEMDEV_Handle hMemMask;
  GUI_Init();
  //
  // Background
  //
  GUI_SetBkColor(GUI_DARKBLUE);
  GUI_Clear();
  GUI_DrawGradientV(0, 0, 320, 240, GUI_BLUE, GUI_RED);
  //
  // Mask device
  //
  hMemMask = GUI_MEMDEV_CreateFixed(0, 0, 320, 240, GUI_MEMDEV_NOTRANS,
                                    GUI_MEMDEV_APILIST_1,  GUICC_1);
  GUI_MEMDEV_Select(hMemMask);
  GUI_SetPenSize(8);
  GUI_DrawLine(0, 240, 320, 0);
  GUI_DrawLine(0, 0, 320, 240);
  GUI_MEMDEV_Select(0);
  //
  // Data Device
  //
```

 © 2020 SEGGER Microcontroller GmbH

```
  hMemData = GUI_MEMDEV_CreateFixed(0, 0, 320, 240, GUI_MEMDEV_NOTRANS,
                                    GUI_MEMDEV_APILIST_32, GUICC_8888);
  GUI_MEMDEV_Select(hMemData);
  GUI_Clear();
  GUI_DrawGradientH(0, 0, 320, 240, GUI_BLUE, GUI_TRANSPARENT);
  GUI_MEMDEV_Select(0);
  //
  // Calling GUI_MEMDEV_ClearAlpha()
  //
  GUI_MEMDEV_ClearAlpha(hMemData, hMemMask);
  //
  // Result
  //
  GUI_MEMDEV_Write(hMemData);
  while (1) {
    GUI_Delay(100);
  }
}
```

Screenshots

Background	Data	Mask	Result
			

 © 2020 SEGGER Microcontroller GmbH

17.11.1.3 GUI_MEMDEV_CopyFromLCD()

Description

Reads back the content of the display and stores it in the given Memory Device.

Prototype

```
void GUI_MEMDEV_CopyFromLCD(GUI_MEMDEV_Handle hMem);
```

Parameters

Parameter	Description
hMem	Handle to a Memory Device.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.4 GUI_MEMDEV_CopyToLCD()

Description

Copies the contents of a Memory Device from memory to the LCD.

Prototype

```
void GUI_MEMDEV_CopyToLCD(GUI_MEMDEV_Handle hMem);
```

Parameters

Parameter	Description
hMem	Handle to a Memory Device.

Additional information

This function ignores the clipping area of the Window Manager as well as the alpha channel. Therefor using this function from within a paint event is not recommended. In order to display a Memory Device regarding the clipping area as well as the alpha channel, the function `GUI_MEMDEV_WriteAt()` should be used instead.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.5 GUI_MEMDEV_CopyToLCDAA()

Description

Copies the contents of a Memory Device (antialiased) to the LCD.

Prototype

```
void GUI_MEMDEV_CopyToLCDAA(GUI_MEMDEV_Handle hMem);
```

Parameters

Parameter	Description
hMem	Handle to a Memory Device.

Additional information

The device data is handled as antialiased data. A matrix of 2x2 pixels is converted to 1 pixel. The intensity of the resulting pixel depends on how many pixels are set in the matrix.

Example

Creates a Memory Device and selects it for output. A large font is then set and a text is written to the Memory Device:

```
GUI_MEMDEV_Handle hMem = GUI_MEMDEV_Create(0,0,60,32);
GUI_MEMDEV_Select(hMem);
GUI_SetFont(&GUI_Font32B_ASCII);
GUI_DispString("Text");
GUI_MEMDEV_CopyToLCDAA(hMem);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

17.11.1.6 GUI_MEMDEV_CopyToLCDAt()

Description

Copies the contents of a Memory Device to the LCD at the given position.

Prototype

```
void GUI_MEMDEV_CopyToLCDAt(GUI_MEMDEV_Handle hMem,
                            int               x,
                            int               y);
```

Parameters

Parameter	Description
hMem	Handle to a Memory Device.
x	Position in X
y	Position in Y

 © 2020 SEGGER Microcontroller GmbH

17.11.1.7 GUI_MEMDEV_Create()

Description

Creates a Memory Device.

Prototype

```
GUI_MEMDEV_Handle GUI_MEMDEV_Create(int x0,
                                    int y0,
                                    int xSize,
                                    int ySize);
```

Parameters

Parameter	Description
x0	X-position of the Memory Device.
y0	Y-position of the Memory Device.
xSize	X-size of the Memory Device.
ySize	Y-size of the Memory Device.

Return value

Handle of the created Memory Device. If the routine fails the return value is 0.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.8 GUI_MEMDEV_CreateCopy()

Description

This function creates a copy from a memory device.

Prototype

```
GUI_MEMDEV_Handle GUI_MEMDEV_CreateCopy(GUI_MEMDEV_Handle hMemSrc);
```

Parameters

Parameter	Description
hMemSrc	Handle of the memory device to be copied.

Return value

The return value is a handle of a memory device containing the copy of hMemSrc. If there is not enough memory to create a memory device as copy, this function returns 0.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.9 GUI_MEMDEV_CreateEx()

Description

Creates a Memory Device.

Prototype

```
GUI_MEMDEV_Handle GUI_MEMDEV_CreateEx(int x0,
                                      int y0,
                                      int xSize,
                                      int ySize,
                                      int Flags);
```

Parameters

Parameter	Description
x0	x-position of the Memory Device.
y0	y-position of the Memory Device.
xSize	x-size of the Memory Device.
ySize	y-size of the Memory Device.
Flags	A list of permitted values can be found under *Memory device flags* on page 756.

Return value

Handle of the created Memory Device. If the routine fails the return value is 0.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.10 GUI_MEMDEV_CreateFixed()

Description

Creates a Memory Device with dedicated color depth color conversion.

Prototype

```
GUI_MEMDEV_Handle GUI_MEMDEV_CreateFixed(      int                  x0,
                                               int                  y0,
                                               int                  xSize,
                                               int                  ySize,
                                               int                  Flags,
                                         const GUI_DEVICE_API     * pDeviceAPI,
                                         const LCD_API_COLOR_CONV * pColorConvAPI);
```

Parameters

Parameter	Description
x0	x-position of the Memory Device.
y0	y-position of the Memory Device.
xSize	x-size of the Memory Device.
ySize	y-size of the Memory Device.
Flags	A list of permitted values can be found under *Memory device flags* on page 756.
pMemDevAPI	A list of permitted color depths can be found under *Memory device color depths* on page 755.
pColorConvAPI	A list of permitted color conversion routines can be found under *Color conversion routines* on page 753.

Return value

Handle of the created Memory Device. If the routine fails the return value is 0.

Additional information

This function can be used if a Memory Device with a specified color conversion should be created. This could make sense if for example some items should be printed on a printer device. The `Sample` folder contains the code example `MEMDEV_Printing.c` which shows how to use the function to print something in 1bpp color conversion mode.

Example

The following example shows how to create a Memory Device with 1bpp color depth:

```
GUI_MEMDEV_Handle hMem;
hMem = GUI_MEMDEV_CreateFixed(0, 0, 128, 128, 0,
                              GUI_MEMDEV_APILIST_1, // Used API list
                              GUI_COLOR_CONV_1);
  // Black/white color conversion
GUI_MEMDEV_Select(hMem);
```

 © 2020 SEGGER Microcontroller GmbH

17.11.1.11 GUI_MEMDEV_CreateFixed32()

Description

Creates a Memory Device with a color depth of 32bpp and GUICC_8888 color conversion.

Prototype

```
GUI_MEMDEV_Handle GUI_MEMDEV_CreateFixed32(int x0,
                                           int y0,
                                           int xSize,
                                           int ySize);
```

Parameters

Parameter	Description
x0	x-position of the Memory Device.
y0	y-position of the Memory Device.
xSize	x-size of the Memory Device.
ySize	y-size of the Memory Device.

Return value

Handle to the created Memory Device. If the routine fails the return value is 0.

Additional information

This function makes it more easy to create a 32 bpp memory device which is often required.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.12 GUI_MEMDEV_Delete()

Description

Deletes a Memory Device.

Prototype

```
void GUI_MEMDEV_Delete(GUI_MEMDEV_Handle hMemDev);
```

Parameters

Parameter	Description
hMem	Handle to the Memory Device which has to be deleted.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.13 GUI_MEMDEV_DrawPerspectiveX()

Description

Draws the given Memory Device perspectively distorted into the currently selected device.

Prototype

```
void GUI_MEMDEV_DrawPerspectiveX(GUI_MEMDEV_Handle hMem,
                                 int               x,
                                 int               y,
                                 int               h0,
                                 int               h1,
                                 int               dx,
                                 int               dy);
```

Parameters

Parameter	Description
hMem	Handle to source Memory Device with the image to be drawn.
x	Horizontal start position in pixels.
y	Vertical start position in pixels.
h0	Height of the leftmost edge of the image to be drawn.
h1	Height of the rightmost edge of the image to be drawn.
dx	Width of the image to be drawn.
dy	Position in y from the topmost pixel at the right relative to the topmost pixel at the left.

The picture below explains the parameters more detailed:



 © 2020 SEGGER Microcontroller GmbH

Additional information

The function draws the contents of the given Memory Device into the currently selected device. The origin of the source device should be (0, 0). Size and distortion of the new image is defined by the parameters dx, dy, h0 and h1. Note that the function currently only works with Memory Devices with 32-bpp color depth and a system color depth of 32 bpp.

Example

The following example shows how to use the function:

```
GUI_MEMDEV_Handle hMem0, hMem1, hMem2;
hMem0 = GUI_MEMDEV_CreateFixed(0, 0, 150, 150, GUI_MEMDEV_NOTRANS,
                               GUI_MEMDEV_APILIST_32,
                               GUI_COLOR_CONV_888);
hMem1 = GUI_MEMDEV_CreateFixed(0, 0,  75, 150, GUI_MEMDEV_HASTRANS,
                               GUI_MEMDEV_APILIST_32,
                               GUI_COLOR_CONV_888);
hMem2 = GUI_MEMDEV_CreateFixed(0, 0,  75, 150, GUI_MEMDEV_HASTRANS,
                               GUI_MEMDEV_APILIST_32,
                               GUI_COLOR_CONV_888);
GUI_MEMDEV_Select(hMem0);
GUI_JPEG_Draw(_aJPEG, sizeof(_aJPEG), 0, 0);
GUI_MEMDEV_Select(hMem1);
GUI_MEMDEV_DrawPerspectiveX(hMem0, 0,  0, 150, 110, 75,  20);
GUI_MEMDEV_Select(hMem2);
GUI_MEMDEV_DrawPerspectiveX(hMem0, 0, 20, 110, 150, 75, -20);
GUI_MEMDEV_CopyToLCDAt(hMem0,   0, 10);
GUI_MEMDEV_CopyToLCDAt(hMem1, 160, 10);
GUI_MEMDEV_CopyToLCDAt(hMem2, 245, 10);
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

17.11.1.14 GUI_MEMDEV_GetDataPtr()

Description

Returns a pointer to the data area (image area) of a Memory Device. This data area can then be manipulated without the use of GUI functions; it can for example be used as output buffer for a JPEG or video decompression routine.

Prototype

```
void *GUI_MEMDEV_GetDataPtr(GUI_MEMDEV_Handle hMem);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.

Return value

Data pointer to the Device's data area. NULL on error.

Additional information

The device data is stored from the returned address onwards. An application modifying this data has to take extreme caution that it does not overwrite memory outside of this data area.

> **Note**
>
> Allocating dynamic memory could cause invalid data pointers!

It should be kept sure, that no memory is allocated during the pointer is used. Allocating memory could cause invalid pointers because of memory cleaning operations.

Organization of the data area

The pixels are stored in the mode "native" to the display (or layer) for which they are intended. For layers with 8 bpp or less, 8 bits (1 byte) are used per pixel; for layers with more than 8 and less or equal 16 bpp, a 16 bit value (U16) is used for one pixel. The memory is organized in reading order which means: First byte (or U16), stored at the start address, represents the color index of the pixel in the upper left corner (y=0, x=0); the next pixel, stored right after the first one, is the one to the left at (y=0, x=1). (Unless the Memory Device area is only 1 pixel wide). The next line is stored right after the first line in memory, without any kind of padding. Endian mode is irrelevant, it is assumed that 16 bit units are accessed as 16 bit units and not as 2 separate bytes. The data area is comprised of (xSize × ySize) pixels, so xSize × ySize bytes for 8bpp or lower Memory Devices, 2 × xSize × ySize bytes (accessed as xSize × ySize units of 16 bits) for 16 bpp Memory Devices.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.15 GUI_MEMDEV_GetXSize()

Description

Returns the X-size (width) of a Memory Device.

Prototype

```
int GUI_MEMDEV_GetXSize(GUI_MEMDEV_Handle hMem);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.

Return value

X-size of Memory Device.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.16 GUI_MEMDEV_GetYSize()

Description

Returns the Y-size (height) of a Memory Device in pixels.

Prototype

```
int GUI_MEMDEV_GetYSize(GUI_MEMDEV_Handle hMem);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.

Return value

Y-size of Memory Device.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.17 GUI_MEMDEV_MarkDirty()

Description

Marks a rectangle area as dirty.

Prototype

```
void GUI_MEMDEV_MarkDirty(GUI_MEMDEV_Handle hMem,
                          int               x0,
                          int               y0,
                          int               x1,
                          int               y1);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.
x0	x-coordinate of the upper left corner.
y0	y-coordinate of the upper left corner.
x1	x-coordinate of the lower right corner.
y1	y-coordinate of the lower right corner.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.18 GUI_MEMDEV_PunchOutDevice()

Description

Punches out a shape of a Memory Device defined by a 8bpp mask Memory Device.

The mask device must consist of 8bpp index values which define the intensity of the pixels to be used:

- Intensity 0 means 100% transparent.
- Intensity 255 means 100% opaque.

Intensity values between 0 and 255 mean semi transparency. The behavior of the function depends on the draw mode:

- GUI_DM_TRANS - Pixel becomes semi transparent
- other value - Pixel is mixed with the current background color
  The punching operation will be done in the given device hMemData.

Prototype

```
int GUI_MEMDEV_PunchOutDevice(GUI_MEMDEV_Handle hMemData,
                              GUI_MEMDEV_Handle hMemMask);
```

Parameters

Parameter	Description
hMemData	Memory Device which should be punched out. Must be a 32 bit Memory Device.
hMemMask	Handle to the Memory Device mask, which contains the intensity values.

Return value

0 on success
1 on error.

Example

```
#include "GUI.h"
/*********************************************************************
*
*       MainTask
*/
void MainTask(void) {
  GUI_MEMDEV_Handle hMemData;
  GUI_MEMDEV_Handle hMemMask;
  GUI_RECT          Rect;
  GUI_Init();
  //
  // Background
  //
  GUI_SetBkColor(GUI_DARKBLUE);
  GUI_Clear();
  GUI_DrawGradientV(0, 0, 99, 49, GUI_DARKGRAY, GUI_DARKBLUE);
  GUI_SetColor(GUI_WHITE);
  //
  // Mask device
  //
  hMemMask = GUI_MEMDEV_CreateFixed(0, 0, 99, 49, GUI_MEMDEV_NOTRANS,
                                    GUI_MEMDEV_APILIST_8,  GUICC_8);
  GUI_SetDrawMode(GUI_DM_TRANS);
  GUI_MEMDEV_Select(hMemMask);
  GUI_SetBkColor(GUI_BLACK);
  GUI_Clear();
  GUI_AA_FillCircle(49, 24, 20);
```

 © 2020 SEGGER Microcontroller GmbH

```
  GUI_SetPenSize(8);
  GUI_DrawLine(0, 0, 99, 49);
  //
  // Data Device
  //
  hMemData = GUI_MEMDEV_CreateFixed(0, 0, 99, 49, GUI_MEMDEV_NOTRANS,
                                    GUI_MEMDEV_APILIST_32, GUICC_8888);
  GUI_MEMDEV_Select(hMemData);
  GUI_SetBkColor(GUI_LIGHTGRAY);
  GUI_Clear();
  Rect.x0 = 6;
  Rect.y0 = 0;
  Rect.x1 = 99;
  Rect.y1 = 49;
  GUI_SetColor(GUI_DARKGRAY);
  GUI_DispStringInRectEx("Punch\r\nme\r\nout!", &Rect,
                         GUI_TA_HCENTER | GUI_TA_VCENTER, 20, GUI_ROTATE_0);
  //
  // Result
  //
  GUI_MEMDEV_Select(0);
  GUI_MEMDEV_PunchOutDevice(hMemData, hMemMask);
  GUI_MEMDEV_Write(hMemData);
  while (1) {
    GUI_Delay(100);
  }
}
```

Screenshots

Background	Data	Mask	Result
			

 © 2020 SEGGER Microcontroller GmbH

17.11.1.19 GUI_MEMDEV_ReduceYSize()

Description

Reduces the Y-size of a Memory Device.

Prototype

```
void GUI_MEMDEV_ReduceYSize(GUI_MEMDEV_Handle hMem,
                            int               YSize);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.
YSize	New Y-size of the Memory Device.

Additional information

Changing the size of the Memory Device is more efficient than deleting and then recreating it.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.20 GUI_MEMDEV_Rotate()

17.11.1.21 GUI_MEMDEV_RotateAlpha()

17.11.1.22 GUI_MEMDEV_RotateHQ()

17.11.1.23 GUI_MEMDEV_RotateHQAlpha()

17.11.1.24 GUI_MEMDEV_RotateHQHR()

17.11.1.25 GUI_MEMDEV_RotateHQT()

17.11.1.26 GUI_MEMDEV_RotateHR()

General Description

The functions rotate and scale the given source Memory Device. The source device will be rotated and scaled around its center and then shifted by the given amount of pixels. The result is saved into the given destination Memory Device. All these functions have similar postfixes containing the sequences 'HQ', 'HQT', 'HR' and 'Alpha' which are explained in the following:

Description 'HQ'

HQ stands for "High Quality". The functions which are named HQ use a more complex algorithm for calculating the destination pixel data. The HQ-algorithm can be used to achieve accurate results. The functions without the HQ addition use the 'nearest neighbor' method which is fast, but less accurate.

Description 'HQT'

HQT stands for "High Quality Transparency". The HQT algorithm improves the performance when rotating Memory Devices containing completely transparent pixels. The more completely transparent pixels the Memory Device contains, the more significant the performance boost gets. This function is still a HQ function and therefore produces results of the same accuracy.

Description 'HR'

HR stands for "High Resolution". The functions named HR use a precision of 8 sub-pixels. This makes it possible to display a Memory Device much more precisely on the screen.

Description 'Alpha'

The 'Alpha' functions allow to use an alpha value for blending in the source device into the destination device. A value between 0 and 255 can be used, where 0 means completely visible and 255 completely transparent. Of course alpha values of the source device will be considered.

Prototypes

```
void GUI_MEMDEV_Rotate (GUI_MEMDEV_Handle hSrc,
                        GUI_MEMDEV_Handle hDst,
                        int               dx,
                        int               dy,
                        int               a,
                        int               Mag);

void GUI_MEMDEV_RotateHQT (GUI_MEMDEV_Handle hSrc,
                           GUI_MEMDEV_Handle hDst,
                           int               dx,
                           int               dy,
```

 © 2020 SEGGER Microcontroller GmbH

```
                            int               a,
                            int               Mag);

void GUI_MEMDEV_RotateHQ (GUI_MEMDEV_Handle hSrc,
                          GUI_MEMDEV_Handle hDst,
                          int               dx,
                          int               dy,
                          int               a,
                          int               Mag);
```

Parameters

Parameter	Description
hSrc	Handle of Memory Device to be rotated and scaled.
hDst	Handle of destination device.
dx	Distance in pixels for shifting the image in X.
dy	Distance in pixels for shifting the image in Y.
a	Angle to be used for rotation in degrees * 1000.
Mag	Magnification factor * 1000.

Prototypes Alpha

```
void GUI_MEMDEV_RotateAlpha (GUI_MEMDEV_Handle hSrc,
                             GUI_MEMDEV_Handle hDst,
                             int               dx,
                             int               dy,
                             int               a,
                             int               Mag,
                             U8                Alpha);

void GUI_MEMDEV_RotateHQAlpha(GUI_MEMDEV_Handle hSrc,
                              GUI_MEMDEV_Handle hDst,
                              int               dx,
                              int               dy,
                              int               a,
                              int               Mag,
                              U8                Alpha);
```

Parameters Alpha

Parameter	Description
hSrc	Handle of Memory Device to be rotated and scaled.
hDst	Handle of destination device.
dx	Distance in pixels for shifting the image in X.
dy	Distance in pixels for shifting the image in Y.
a	Angle to be used for rotation in degrees * 1000.
Mag	Magnification factor * 1000.
Alpha	Alpha value to be used for blending in the device.

Prototypes HR

```
void GUI_MEMDEV_RotateHQHR(GUI_MEMDEV_Handle hSrc,
                           GUI_MEMDEV_Handle hDst,
                           I32               dx,
                           I32               dy,
                           int               a,
                           int               Mag);

void GUI_MEMDEV_RotateHR (GUI_MEMDEV_Handle hSrc,
                          GUI_MEMDEV_Handle hDst,
                          I32               dx,
```

 © 2020 SEGGER Microcontroller GmbH

```
                I32             dy,
                int             a,
                int             Mag);
```

Parameters HR

Parameter	Description
hSrc	Handle of Memory Device to be rotated and scaled.
hDst	Handle of destination device.
dx	Distance in pixels for shifting the image in X.
dy	Distance in pixels for shifting the image in Y.
a	Angle to be used for rotation in degrees * 1000.
Mag	Magnification factor * 1000.

The following picture gives a more detailed impression of the parameters:



Additional information

Both Memory Devices, source and destination, need to be created using a color depth of 32bpp. Further GUI_MEMDEV_NOTRANS should be used as Flags parameter when creating the devices. If it is intended to preserve transparency, the according areas in both Memory Devices need to be filled with transparency before calling a rotate function. The Sample folder contains the MEMDEV_ZoomAndRotate.c application which shows in detail how the function can be used.

Performance advantage of GUI_MEMDEV_RotateHQT()

The following table shows an approximation of the performance in comparison to GUI_MEMDEV_RotateHQ() in dependence of the percentage of transparent pixels:

Percentage of transparent pixels	Performance advantage
0%	- 3%

 © 2020 SEGGER Microcontroller GmbH

Percentage of transparent pixels	Performance advantage
10%	0%
50%	+ 21%
90%	+ 74%

Example

```
GUI_MEMDEV_Handle hMemSource;
GUI_MEMDEV_Handle hMemDest;
GUI_RECT RectSource = {0, 0, 69, 39};
GUI_RECT RectDest   = {0, 0, 79, 79};
hMemSource = GUI_MEMDEV_CreateFixed(RectSource.x0, RectSource.y0,
                                    RectSource.x1 - RectSource.x0 + 1,
                                    RectSource.y1 - RectSource.y0 + 1,
                                    GUI_MEMDEV_NOTRANS,
                                    GUI_MEMDEV_APILIST_32, GUI_COLOR_CONV_888);
hMemDest   = GUI_MEMDEV_CreateFixed(RectDest.x0,   RectDest.y0,
                                    RectDest.x1   - RectDest.x0   + 1,
                                    RectDest.y1   - RectDest.y0   + 1,
                                    GUI_MEMDEV_NOTRANS,
                                    GUI_MEMDEV_APILIST_32, GUI_COLOR_CONV_888);
GUI_MEMDEV_Select(hMemSource);
GUI_DrawGradientV(RectSource.x0, RectSource.y0,
                  RectSource.x1, RectSource.y1,
                  GUI_WHITE, GUI_DARKGREEN);
GUI_SetColor(GUI_BLUE);
GUI_SetFont(&GUI_Font20B_ASCII);
GUI_SetTextMode(GUI_TM_TRANS);
GUI_DispStringInRect("emWin", &RectSource, GUI_TA_HCENTER | GUI_TA_VCENTER);
GUI_DrawRect(0, 0, RectSource.x1, RectSource.y1);
GUI_MEMDEV_Select(hMemDest);
GUI_Clear();
GUI_MEMDEV_Select(0);
GUI_MEMDEV_RotateHQ(hMemSource, hMemDest,
                    (RectDest.x1 - RectSource.x1) / 2,
                    (RectDest.y1 - RectSource.y1) / 2,
                    30 * 1000,
                    1000);
GUI_MEMDEV_CopyToLCDAt(hMemSource,  10, (RectDest.y1 - RectSource.y1) / 2);
GUI_MEMDEV_CopyToLCDAt(hMemDest,   100, 0);
```

Screenshot of the above example using GUI_MEMDEV_Rotate()



Screenshot of the above example using GUI_MEMDEV_RotateHQ()



 © 2020 SEGGER Microcontroller GmbH

Screenshot of the above example using GUI_MEMDEV_RotateHQHR()

This screenshot shows the 8 steps to move an anti-aliased corner one pixel to the right using sub-pixels.



 © 2020 SEGGER Microcontroller GmbH

17.11.1.27 GUI_MEMDEV_Select()

Description

Activates a Memory Device (or activates LCD if handle is 0).

Prototype

```
GUI_MEMDEV_Handle GUI_MEMDEV_Select(GUI_MEMDEV_Handle hMemDev);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.

Return value

Previously selected device. 0, if the display was selected.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.28 GUI_MEMDEV_SerializeBMP()

Description

Creates a BMP file from the given Memory Device.

Prototype

```
void GUI_MEMDEV_SerializeBMP(GUI_MEMDEV_Handle        hDev,
                             GUI_CALLBACK_VOID_U8_P * pfSerialize,
                             void                   * p);
```

Prototype of GUI_CALLBACK_VOID_U8_P

```
void GUI_CALLBACK_VOID_U8_P(U8     Data,
                            void * p);
```

Additional information

To create a BMP file the color depth of the given Memory Device is used. In case it is 32bpp the resulting BMP file will consist of valid alpha data which is recognized by the Bitmap Converter.
An example for serialization can be found in the description of `GUI_BMP_Serialize()`.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.29 GUI_MEMDEV_SetOrg()

Description

Changes the origin of the Memory Device on the LCD.

Prototype

```
void GUI_MEMDEV_SetOrg(GUI_MEMDEV_Handle hMem,
                       int               x0,
                       int               y0);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.
x0	Horizontal position (of the upper left pixel).
y0	Vertical position (of the upper left pixel).

Additional information

This routine can be helpful when the same device is used for different areas of the screen or when the contents of the Memory Device are to be copied into different areas. Changing the origin of the Memory Device is more efficient than deleting and then recreating it.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.30 GUI_MEMDEV_Write()

Description

Writes the content of the given Memory Device into the currently selected device.

Prototype

```
void GUI_MEMDEV_Write(GUI_MEMDEV_Handle hMem);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.

Additional information

In case of writing a 32 bpp memory device with alpha channel the alpha values will be considered for mixing the content of the given memory device with the content of the currently selected device.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.31 GUI_MEMDEV_WriteAlpha()

Description

Writes the content of the given Memory Device into the currently selected device using alpha blending.

Prototype

```
void GUI_MEMDEV_WriteAlpha(GUI_MEMDEV_Handle hMem,
                           int               Alpha);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.
Alpha	Alpha blending factor, 0 - 255

Additional information

Alpha blending means mixing 2 colors with a given intensity. This function makes it possible to write semi-transparent from one Memory Device into an other Memory Device. The Alpha -parameter specifies the intensity used when writing to the currently selected device. In case of writing a 32 bpp memory device with alpha channel the alpha values will also be considered.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.32 GUI_MEMDEV_WriteAlphaAt()

Description

Writes the content of the given Memory Device into the currently selected device at the specified position using alpha blending.

Prototype

```
void GUI_MEMDEV_WriteAlphaAt(GUI_MEMDEV_Handle hMem,
                             int               Alpha,
                             int               x,
                             int               y);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.
Alpha	Alpha blending factor, 0 - 255
x	Position in X
y	Position in Y

Additional information

See GUI_MEMDEV_WriteAlpha().

 © 2020 SEGGER Microcontroller GmbH

17.11.1.33 GUI_MEMDEV_WriteAt()

Description

Writes the content of the given Memory Device into the currently selected device at the specified position.

Prototype

```
void GUI_MEMDEV_WriteAt(GUI_MEMDEV_Handle hMem,
                        int               x,
                        int               y);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.
x	Position in X
y	Position in Y

Additional information

(See *GUI_MEMDEV_Write* on page 711)

 © 2020 SEGGER Microcontroller GmbH

17.11.1.34 GUI_MEMDEV_WriteEx()

Description

Writes the content of the given Memory Device into the currently selected device at position (0, 0) using alpha blending and scaling.

Prototype

```
void GUI_MEMDEV_WriteEx(GUI_MEMDEV_Handle hMem,
                        int               xMag,
                        int               yMag,
                        int               Alpha);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.
xMag	Scaling factor for X-axis * 1000.
yMag	Scaling factor for Y-axis * 1000.
Alpha	Alpha blending factor, 0 - 255.

Additional information

A negative scaling factor mirrors the output. Also refer to GUI_MEMDEV_WriteExAt() below.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.35 GUI_MEMDEV_WriteExAt()

Description

Writes the content of the given Memory Device into the currently selected device at the specified position using alpha blending and scaling.

Prototype

```
void GUI_MEMDEV_WriteExAt(GUI_MEMDEV_Handle hMem,
                          int               x,
                          int               y,
                          int               xMag,
                          int               yMag,
                          int               Alpha);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.
x	Position in X.
y	Position in Y.
xMag	Scaling factor for X-axis * 1000.
yMag	Scaling factor for Y-axis * 1000.
Alpha	Alpha blending factor, 0 - 255.

Additional information

A negative scaling factor mirrors the output.

Example

The following example creates 2 Memory Devices: hMem0 (40x10) and hMem1 (80x20). A small white text is drawn at the upper left position of hMem0 and hMem1. Then the function GUI_MEMDEV_WriteEx() writes the content of hMem0 to hMem1 using mirroring and magnifying:

```
GUI_MEMDEV_Handle hMem0, hMem1;
GUI_Init();
hMem0 = GUI_MEMDEV_Create(0, 0, 40, 10);
hMem1 = GUI_MEMDEV_Create(0, 0, 80, 20);
GUI_MEMDEV_Select(hMem0);
GUI_SetTextMode(GUI_TM_TRANS);
GUI_DispString("Text");
GUI_MEMDEV_Select(hMem1);
GUI_SetBkColor(GUI_RED);
GUI_Clear();
GUI_DispStringAt("Text", 0, 0);
GUI_MEMDEV_WriteExAt(hMem0, 0, 0, -2000, -2000, 160);
GUI_MEMDEV_CopyToLCD(hMem1);
```

Screenshot of the above example



 © 2020 SEGGER Microcontroller GmbH

17.11.1.36 GUI_MEMDEV_WriteOpaque()

Description

Writes the content of the given Memory Device into the currently selected device.

Prototype

```
void GUI_MEMDEV_WriteOpaque(GUI_MEMDEV_Handle hMem);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.

Additional information

In case of writing a 32 bpp memory device with alpha channel the alpha values will not be changed and copied as they are. Although, the name implies that the memory device becomes fully opaque the alpha values will remain. The alpha values will be copied without mixing with the background.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.37 GUI_MEMDEV_WriteOpaqueAt()

Description

Writes the content of the given Memory Device into the currently selected device at the specified position.

Prototype

```
void GUI_MEMDEV_WriteOpaqueAt(GUI_MEMDEV_Handle hMem,
                              int               x,
                              int               y);
```

Parameters

Parameter	Description
hMem	Handle to Memory Device.

Additional information

In case of writing a 32 bpp memory device with alpha channel the alpha values will not be changed and copied as they are. Although, the name implies that the memory device becomes fully opaque the alpha values will remain. The alpha values will be copied without mixing with the background.

 © 2020 SEGGER Microcontroller GmbH

17.11.1.38 GUI_SelectLCD()

Description

Selects the LCD as target for drawing operations.

Prototype

```
void GUI_SelectLCD(void);
```

 © 2020 SEGGER Microcontroller GmbH

17.11.2 Example for using a Memory Device

The Sample folder contains the following example which shows how Memory Devices can be used:

- MEMDEV_MemDev.c

This example demonstrates the use of a Memory Device. Some items are written to a Memory Device and then copied to the display. Note that several other examples also make use of Memory Devices and may also be helpful to get familiar with them.

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

17.11.3 Banding Memory Device

A Memory Device is first filled by executing the specified drawing functions. After filling the device, the contents are drawn to the LCD. There may be note enough memory available to store the complete output area at once, depending on your configuration. A banding Memory Device divides the drawing area into bands, in which each band covers as many lines as possible with the currently available memory.

17.11.3.1 GUI_MEMDEV_Draw()

Description

Drawing function to avoid flickering.

Prototype

```
int GUI_MEMDEV_Draw(GUI_RECT             * pRect,
                    GUI_CALLBACK_VOID_P * pfDraw,
                    void                * pData,
                    int                   NumLines,
                    int                   Flags);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure for the used LCD area.
pfDraw	Pointer to a callback function for executing the drawing.
pData	Pointer to a data structure used as parameter for the call-back function.
NumLines	0 (recommended) or number of lines for the Memory Device.
Flags	A list of permitted values can be found under *Memory device flags* on page 756. GUI_MEMDEV_NOTRANS is recommended.

Return value

0 if successful.
1 if the routine fails.

Additional information

If the parameter NumLines is 0, the number of lines in each band is calculated automatically by the function. The function then iterates over the output area band by band by moving the origin of the Memory Device.

 © 2020 SEGGER Microcontroller GmbH

17.11.3.2 Example for using a banding Memory Device

The `Sample` folder contains the following example which shows how the function can be used:

- `MEMDEV_Banding.c`

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

17.11.4 Auto device object functions

Memory Devices are useful when the display must be updated to reflect the movement or changing of items, since it is important in such applications to prevent the LCD from flickering. An auto device object is based on the banding Memory Device, and may be more efficient for applications such as moving indicators, in which only a small part of the display is updated at a time.
The device automatically distinguishes which areas of the display consist of fixed objects and which areas consist of moving or changing objects that must be updated. When the drawing function is called for the first time, all items are drawn. Each further call updates only the space used by the moving or changing objects. The actual drawing operation uses the banding Memory Device, but only within the necessary space. The main advantage of using an auto device object (versus direct usage of a banding Memory Device) is that it saves computation time, since it does not keep updating the entire display.

17.11.4.1 GUI_MEMDEV_CreateAuto()

Description

Creates an auto device object.

Prototype

```
int GUI_MEMDEV_CreateAuto(GUI_AUTODEV * pAutoDev);
```

Parameters

Parameter	Description
pAutoDev	Pointer to a GUI_AUTODEV object.

Return value

Currently 0, reserved for later use.

 © 2020 SEGGER Microcontroller GmbH

17.11.4.2 GUI_MEMDEV_DeleteAuto()

Description

Deletes an auto device object.

Prototype

```
void GUI_MEMDEV_DeleteAuto(GUI_AUTODEV * pAutoDev);
```

Parameters

Parameter	Description
pAutoDev	Pointer to a GUI_AUTODEV object.

 © 2020 SEGGER Microcontroller GmbH

17.11.4.3 GUI_MEMDEV_DrawAuto()

Description

Executes a specified drawing routine using a banding Memory Device.

Prototype

```
int GUI_MEMDEV_DrawAuto(GUI_AUTODEV         * pAutoDev,
                        GUI_AUTODEV_INFO    * pAutoDevInfo,
                        GUI_CALLBACK_VOID_P * pfDraw,
                        void                * pData);
```

Parameters

Parameter	Description
pAutoDev	Pointer to a GUI_AUTODEV object.
pAutoDevInfo	Pointer to a GUI_AUTODEV_INFO object.
pfDraw	Pointer to the user-defined drawing function which is to be executed.
pData	Pointer to a data structure passed to the drawing function.

Return value

0 if successful.
1 if the routine fails.

Additional information

The GUI_AUTODEV_INFO structure contains the information about what items must be drawn by the user function:

```
typedef struct {
  char DrawFixed;
} GUI_AUTODEV_INFO;
```

DrawFixed is set to 1 if all items have to be drawn. It is set to 0 when only the moving or changing objects have to be drawn. We recommend the following procedure when using this feature:

```
typedef struct {
  GUI_AUTODEV_INFO AutoDevInfo; /* Information about what has to be drawn */
  /* Additional data used by the user function */
  ...
} PARAM;
static void Draw(void * p) {
  PARAM * pParam = (PARAM *)p;
  if (pParam->AutoDevInfo.DrawFixed) {
    /* Draw fixed background */
    ...
  }
  /* Draw moving objects */
  ...
  if (pParam->AutoDevInfo.DrawFixed) {
    /* Draw fixed foreground (if needed) */
    ...
  }
}
void main(void) {
  PARAM Param;                    /* Parameters for drawing routine */
  GUI_AUTODEV AutoDev;            /* Object for banding Memory Device */
  /* Set/modify information for drawing routine */
  ...
```

 © 2020 SEGGER Microcontroller GmbH

```
  GUI_MEMDEV_CreateAuto(&AutoDev); /* Create GUI_AUTODEV-object */
  GUI_MEMDEV_DrawAuto(&AutoDev,    /* Use GUI_AUTODEV-object for drawing */
                      &Param.AutoDevInfo,
                      &Draw,
                      &Param);
  GUI_MEMDEV_DeleteAuto(&AutoDev); /* Delete GUI_AUTODEV-object */
}
```

17.11.4.4 Example for using an auto device object

The example `MEMDEV_AutoDev.c` demonstrates the use of an auto device object. It can be found as `MEMDEV_AutoDev.c`. A scale with a moving needle is drawn in the background and a small text is written in the foreground. The needle is drawn with the anti-aliasing feature of emWin. High-resolution anti-aliasing is used here to improve the appearance of the moving needle. For more information, see the chapter *Antialiasing* on page 540.

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

17.11.5 Measurement device object functions

Measurement devices are useful when you need to know the area used to draw something. Creating and selecting a measurement device as target for drawing operations makes it possible to retrieve the rectangle used for drawing operations.

17.11.5.1 GUI_MEASDEV_ClearRect()

Description

Call this function to clear the measurement rectangle of the given measurement device.

Prototype

```
void GUI_MEASDEV_ClearRect(GUI_MEASDEV_Handle hMemDev);
```

Parameters

Parameter	Description
hMem	Handle to measurement device.

 © 2020 SEGGER Microcontroller GmbH

17.11.5.2 GUI_MEASDEV_Create()

Description

Creates a measurement device.

Prototype

```
GUI_MEASDEV_Handle GUI_MEASDEV_Create(void);
```

Return value

The handle of the measurement device.

 © 2020 SEGGER Microcontroller GmbH

17.11.5.3 GUI_MEASDEV_Delete()

Description

Deletes a measurement device.

Prototype

```
void GUI_MEASDEV_Delete(GUI_MEASDEV_Handle hMemDev);
```

Parameters

Parameter	Description
hMem	Handle to measurement device.

 © 2020 SEGGER Microcontroller GmbH

17.11.5.4 GUI_MEASDEV_GetRect()

Description

Retrieves the result of the drawing operations.

Prototype

```
void GUI_MEASDEV_GetRect(GUI_MEASDEV_Handle   hMem,
                         GUI_RECT           * pRect);
```

Parameters

Parameter	Description
hMem	Handle to measurement device.
pRect	Pointer to GUI_RECT-structure to store result.

 © 2020 SEGGER Microcontroller GmbH

17.11.5.5 GUI_MEASDEV_Select()

Description

Selects a measurement device as target for drawing operations.

Prototype

```
void GUI_MEASDEV_Select(GUI_MEASDEV_Handle hMemDev);
```

Parameters

Parameter	Description
hMem	Handle to measurement device.

Example

The following example shows the use of a measurement device. It creates a measurement device, draws a line and displays the result of the measurement device:

```
void MainTask(void) {
  GUI_MEASDEV_Handle hMeasdev;
  GUI_RECT Rect;
  GUI_Init();
  hMeasdev = GUI_MEASDEV_Create();
  GUI_MEASDEV_Select(hMeasdev);
  GUI_DrawLine(10, 20, 30, 40);
  GUI_SelectLCD();
  GUI_MEASDEV_GetRect(hMeasdev, &Rect);
  GUI_MEASDEV_Delete(hMeasdev);
  GUI_DispString("X0:");
  GUI_DispDec(Rect.x0, 3);
  GUI_DispString(" Y0:");
  GUI_DispDec(Rect.y0, 3);
  GUI_DispString(" X1:");
  GUI_DispDec(Rect.x1, 3);
  GUI_DispString(" Y1:");
  GUI_DispDec(Rect.y1, 3);
}
```

Screenshot of the above example



 © 2020 SEGGER Microcontroller GmbH

17.11.6 Animation functions

Animations can be used to inject some life into the application. They will always help to let the user's eye smoothly capture what happens. All animation functions require 32-bit devices.

17.11.6.1 GUI_MEMDEV_FadeInDevices()

Description

Performs fading in one device over another Memory Device.

Prototype

```
int GUI_MEMDEV_FadeInDevices(GUI_MEMDEV_Handle hMem0,
                             GUI_MEMDEV_Handle hMem1,
                             int               Period);
```

Parameters

Parameter	Description
hMem0	Handle of background Memory Device.
hMem1	Handle of Memory Device to be faded in.
Period	Time period in which the fading is processed.

Return value

0 if successful.
1 if the function fails.

Additional information

This function requires hMem0 and hMem1 to be of the same size and to be located at the same position on the screen.

Example

An example application using fading functions can be found in the file MEMDEV_FadingPerformance.c which is located in the folder Sample\Tutorial.

Screenshots



 © 2020 SEGGER Microcontroller GmbH

17.11.6.2 GUI_MEMDEV_FadeOutDevices()

Description

Performs fading out one device overlaying another Memory Device.

Prototype

```
int GUI_MEMDEV_FadeOutDevices(GUI_MEMDEV_Handle hMem0,
                              GUI_MEMDEV_Handle hMem1,
                              int               Period);
```

Parameters

Parameter	Description
hMem0	Handle of background Memory Device.
hMem1	Handle of Memory Device to be faded out.
Period	Time period in which the fading is processed.

Return value

0 if successful.
1 if the function fails.

Additional information

This function requires hMem0 and hMem1 to be of the same size and to be located at the same position on the screen.

 © 2020 SEGGER Microcontroller GmbH

17.11.6.3 GUI_MEMDEV_SetAnimationCallback()

Description

Sets a user defined callback function to be called while animations are processed. The function should contain code to determine whether processing of the current animation shall go on or abort.

Prototype

```
void GUI_MEMDEV_SetAnimationCallback(GUI_ANIMATION_CALLBACK_FUNC * pCbAnimation,
                                     void                       * pVoid);
```

Parameters

Parameter	Description
pCbAnimation	Pointer to the user defined callback function.
pVoid	Data pointer.

Additional information

The callback function is called every time an animation function has just copied the actual step to the screen.

Example

The following example shows the use of a GUI_ANIMATION_CALLBACK_FUNC, which gives the possibility to react on PID events:

```
static int _cbAnimation(int TimeRem, void * pVoid) {
  int Pressed;
  if (TimeRem /* Insert Condition */) {
    /* ... React on remaining Time ... */
  }
  Pressed = _GetButtonState();
  if (Pressed) {
    return 1;   // Button was     pressed, stop     animation
  } else {
    return 0;   // Button was not pressed, continue animation
  }
}
void main(void) {
  GUI_Init();
  GUI_MEMDEV_SetAnimationCallback(_cbAnimation, (void *)&_Pressed);
  while (1) {
    /* Do animations... */
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

17.11.6.4 GUI_MEMDEV_SetTimePerFrame()

Description

Sets the minimum time used for one animation frame. If the process of drawing requires less time `GUI_X_Delay()` is called with the time difference.

Prototype

```
void GUI_MEMDEV_SetTimePerFrame(unsigned TimePerFrame);
```

Parameters

Parameter	Description
`TimePerFrame`	Minimum time used for one animation frame.

 © 2020 SEGGER Microcontroller GmbH

17.11.7 Animation functions (Window Manager required)

The following animation functions require usage of the Window Manager.

17.11.7.1 GUI_MEMDEV_FadeInWindow()

17.11.7.2 GUI_MEMDEV_FadeOutWindow()

Description

Fades in/out a window by decreasing/increasing the alpha value.

Prototypes

```
int GUI_MEMDEV_FadeInWindow (WM_HWIN hWin,
                             int     Period);

int GUI_MEMDEV_FadeOutWindow(WM_HWIN hWin,
                             int     Period);
```

Parameters

Parameter	Description
hWin	Handle to the window which has to be faded in/out.
Period	Time period in which the fading is processed.

Return value

0 if successful.
1 if the function fails.

Additional information

After the window has been faded the desktop and its child windows are validated.

Example

An example application using the fading functions for windows can be found in the file SKINNING_NestedModal.c which is located in the folder Sample\Tutorial.

Screenshots



 © 2020 SEGGER Microcontroller GmbH

17.11.7.3 GUI_MEMDEV_MoveInWindow()

17.11.7.4 GUI_MEMDEV_MoveOutWindow()

Description

Moves a window into/out of the screen. First the window is drawn minimized/maximized at the specified position/its actual position and then moved to its actual position/the specified position while magnifying to its actual size/demagnifying. The window can be spun clockwise as well as counterclockwise while it is moving.

Prototypes

```
int GUI_MEMDEV_MoveInWindow (WM_HWIN hWin,
                             int     x,
                             int     y,
                             int     a180,
                             int     Period);

int GUI_MEMDEV_MoveOutWindow(WM_HWIN hWin,
                             int     x,
                             int     y,
                             int     a180,
                             int     Period);
```

Parameters

Parameter	Description
hWin	Handle to the window which has to be moved
x	Position in x from/to where the window is moved
y	Position in y from/to where the window is moved
a180	Count of degrees the window will be spun for: a180 = 0 -> no spinning a180 > 0 -> clockwise a180 < 0 -> counter-clockwise
Period	Time period in which the moving is processed

Return value

0 if successful.
1 if the function fails.

Additional information

First the window is drawn maximized at its actual position and then moved to the specified position while demagnifying. The window can be spun clockwise as well as counterclockwise while it is moving. After the window has been moved the desktop and its child windows are validated. GUI_MEMDEV_MoveOutWindow() requires approximately 1 MB of dynamic memory to run properly in QVGA mode.

Example

An example application using the functions GUI_MEMDEV_MoveInWindow() and GUI_MEMDEV_MoveOutWindow() can be found in the file SKINNING_NestedModal.c which is located in the folder Sample\Tutorial folder.

 © 2020 SEGGER Microcontroller GmbH

Screenshots



 © 2020 SEGGER Microcontroller GmbH

17.11.7.5 GUI_MEMDEV_ShiftInWindow()

17.11.7.6 GUI_MEMDEV_ShiftOutWindow()

Description

Shifts a Window in a specified direction into/out of the screen to/from its actual position.

Prototypes

```
int GUI_MEMDEV_ShiftInWindow (WM_HWIN hWin,
                              int     Period,
                              int     Direction);

int GUI_MEMDEV_ShiftOutWindow(WM_HWIN hWin,
                              int     Period,
                              int     Direction);
```

Parameters

Parameter	Description
hWin	Handle to the window which has to be shifted.
Period	Time period in which the shifting is processed.
Edge	See permitted values under *Direction symbols* on page 754.

Return value

0 if successful.
1 if the function fails.

Additional information

After the window has been shifted the desktop and its child windows are validated. GUI_MEMDEV_ShiftOutWindow() requires approximately 1 MB of dynamic memory to run properly in QVGA mode.

Example

An example application using the functions GUI_MEMDEV_ShiftInWindow() and GUI_MEMDEV_ShiftOutWindow() can be found in the file SKINNING_Notepad.c which is located in the folder Sample\Tutorial folder.

Screenshots



 © 2020 SEGGER Microcontroller GmbH

17.11.7.7 GUI_MEMDEV_SwapWindow()

Description

Swaps a window with the old content of the target area.

Prototype

```
int GUI_MEMDEV_SwapWindow(WM_HWIN hWin,
                          int     Period,
                          int     Edge);
```

Parameters

Parameter	Description
hWin	Handle to the window which has to be swapped.
Period	Time period in which the shifting is processed.
Edge	See permitted values under *Direction symbols* on page 754.

Return value

0 if successful.
1 if the function fails.

Additional information

After the window has been swapped the desktop and its child windows are validated. GUI_MEMDEV_SwapWindow( ) requires approximately 1 MB of dynamic memory to run properly in QVGA mode.

Screenshots



 © 2020 SEGGER Microcontroller GmbH

17.11.8 Blending, Blurring and Dithering functions

17.11.8.1 GUI_MEMDEV_BlendColor32()

Description

Blends a window with the given color and blending intensity.

Prototype

```
int GUI_MEMDEV_BlendColor32(GUI_MEMDEV_Handle hMem,
                            U32               BlendColor,
                            U8                BlendIntens);
```

Parameters

Parameter	Description
hMem	Handle to the Memory Device which has to be blended.
BlendColor	Color which is used for the blending effect.
BlendIntens	Intensity of the blending effect. Should be 0 (no blending) - 255 (full blending).

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

17.11.8.2 GUI_MEMDEV_CreateBlurredDevice32()

Description

Creates a blurred copy of the given Memory Device using the currently set blurring function.

Prototype

```
GUI_MEMDEV_Handle GUI_MEMDEV_CreateBlurredDevice32(GUI_MEMDEV_Handle hMemSrc,
                                                   U8                Depth);
```

Parameters

Parameter	Description
hMem	Handle to the Memory Device which has to be blurred.
Depth	Depth of the blurring effect. Should be specified with 1-10.

Return value

Handle of the blurred Memory Device.

Additional information

The source Memory Device should consist of a color depth of 32 bpp. The resulting Memory Device will be of the same size at 32 bpp. Information about memory usage and performance can be found in the descriptions of the …HQ() and …LQ()-function. This function works according to the currently set blurring quality. In order to change the quality, the functions GUI_MEMDEV_SetBlurHQ() and GUI_MEMDEV_SetBlurLQ() can be used. The default quality is high.

Comparison

This screenshot shows the same elements without effect in the top row, blurred at high quality in the left column and blurred at low quality in the right column. The blurring depth was set as follows:



Row number	Blurring depth
1st row	0
2nd row	1
3rd row	3
4th row	5
5th row	7

 © 2020 SEGGER Microcontroller GmbH

Performance

The performance is given relative to the time it takes to create a blurred device at high quality using a blurring depth of 1.

Blurring depth	High Quality	Low Quality
1	1	1.32
3	3.54	2.01
5	8.65	2.65
7	16.16	3.26

According to the values creating a blurred device at high quality using a blurring depth of 5 takes approximately half the time it would take to create a blurred device at high quality using a blurring depth of 7.

 © 2020 SEGGER Microcontroller GmbH

17.11.8.3 GUI_MEMDEV_CreateBlurredDevice32HQ()

Description

Creates a blurred copy of the given Memory Device at high quality.

Prototype

```
GUI_MEMDEV_Handle GUI_MEMDEV_CreateBlurredDevice32HQ(GUI_MEMDEV_Handle hMemSrc,
                                                     U8                Depth);
```

Parameters

Parameter	Description
hMem	Handle to the Memory Device which has to be blurred.
Depth	Depth of the blurring effect. Should be specified with 1-10.

Return value

Handle of the blurred Memory Device. 0, if the function fails.

Additional information

The source Memory Device should consist of a color depth of 32 bpp. The resulting Memory Device will be of the same size at 32 bpp. This routine requires an addition of 16 bytes per pixel plus memory to allocate iterator arrays which are used to accelerate pixel addressing. The required memory for the iterator arrays depends on the blurring depth to perform. The number of bytes is calculated as follows:

```
Size = (1 + Depth * (Depth - 1) * 4) * (3 * sizeof(int) + 4)
```

A screenshot can be found under *GUI_MEMDEV_CreateBlurredDevice32* on page 742.

 © 2020 SEGGER Microcontroller GmbH

17.11.8.4 GUI_MEMDEV_CreateBlurredDevice32LQ()

Description

Creates a blurred copy of the given Memory Device at low quality.

Prototype

```
GUI_MEMDEV_Handle GUI_MEMDEV_CreateBlurredDevice32LQ(GUI_MEMDEV_Handle hMemSrc,
                                                     U8                Depth);
```

Parameters

Parameter	Description
hMem	Handle to the Memory Device which has to be blurred.
Depth	Depth of the blurring effect. Should be specified with 1-10.

Return value

Handle of the blurred Memory Device. 0, if the function fails.

Additional information

The source Memory Device should consist of a color depth of 32 bpp. This is a creating function. The created Memory Device will be of the same size at 32 bpp. Beyond that no additional memory is required. A screenshot can be found under GUI_MEMDEV_Create-BlurredDevice32().

 © 2020 SEGGER Microcontroller GmbH

17.11.8.5 GUI_MEMDEV_Dither32()

Before	After
	

Description

The function dithers the given memory device using the given fixed palette mode. Please note that the function does not reduce the color depth of the memory device. If dithered images with a reduced color depth (and less storage requirement) are desired, the bitmap converter should be used to dither the images.

Prototype

```
int GUI_MEMDEV_Dither32(      GUI_MEMDEV_Handle    hMem,
                        const LCD_API_COLOR_CONV * pColorConvAPI);
```

Parameters

Parameter	Description
hMem	Handle to the Memory Device which has to be dithered.
pColorConvAPI	Color conversion to be used.

Return value

0 on success
1 on error.

Additional information

The function works only with memory devices having a color depth of 32bpp.

 © 2020 SEGGER Microcontroller GmbH

17.11.8.6 GUI_MEMDEV_SetBlurHQ()

Description

Sets the blurring quality to high.

Prototype

```
void GUI_MEMDEV_SetBlurHQ(void);
```

Additional information

Setting the blurring quality affects the function `GUI_MEMDEV_CreateBlurredDevice32()` which in turn is called by other functions. (e.g. `GUI_MEMDEV_BlurWinBk()`).

 © 2020 SEGGER Microcontroller GmbH

17.11.8.7 GUI_MEMDEV_SetBlurLQ()

Description

Sets the blurring quality to low.

Prototype

```
void GUI_MEMDEV_SetBlurLQ(void);
```

Additional information

Additional information is stated under "`GUI_MEMDEV_SetBlurHQ()`".

 © 2020 SEGGER Microcontroller GmbH

17.11.9 Blending and Blurring functions (Window Manager required)

17.11.9.1 GUI_MEMDEV_BlendWinBk()

Description

Blends the background of a window within the given period from its initial state to the given blending intensity.

Prototype

```
int GUI_MEMDEV_BlendWinBk(WM_HWIN hWin,
                          int     Period,
                          U32     BlendColor,
                          U8      BlendIntens);
```

Parameters

Parameter	Description
hWin	Handle to the window which has to be blended.
Period	Effect Period.
BlendColor	Color which is used for the background to be blended with.
BlendIntens	Final intensity of the blending effect. Should be 0 (no blending) - 255 (full blending).

Return value

0 on success
1 on error.

Screenshots

The following screenshots show the background window being blended in 5 steps. The blending is performed using GUI_BLACK as BlendColor. BlendIntens is given with the highest possible value of 255.



 © 2020 SEGGER Microcontroller GmbH

17.11.9.2 GUI_MEMDEV_BlurAndBlendWinBk()

Description

Blurs and blends the background of a window within the given period from its initial state to the given blurring value and blending intensity.

Prototype

```
int GUI_MEMDEV_BlurAndBlendWinBk(WM_HWIN hWin,
                                 int     Period,
                                 U8      BlurDepth,
                                 U32     BlendColor,
                                 U8      BlendIntens);
```

Parameters

Parameter	Description
hWin	Handle to the window which has to be blurred.
Period	Effect Period.
BlurDepth	Final depth of the blurring effect. Should be specified with 1-10.
BlendColor	Color which is used for the background to be blended with.
BlendIntens	Final intensity of the blending effect. Should be 0 (no blending) - 255 (full blending).

Return value

0 on success
1 on error.

Additional information

The blurring quality can be changed using the functions GUI_MEMDEV_SetBlurHQ() or GUI_MEMDEV_SetBlurLQ().

Screenshots

The following screenshots show the background window being blurred and blended in 5 steps. The used values are 10 as blurring depth and 64 as blending intensity. The blending color is GUI_WHITE.



 © 2020 SEGGER Microcontroller GmbH

17.11.9.3 GUI_MEMDEV_BlurWinBk()

Description

Blurs the background of a window within the given period from its initial state to the given blurring value.

Prototype

```
int GUI_MEMDEV_BlurWinBk(WM_HWIN hWin,
                         int     Period,
                         U8      BlurDepth);
```

Parameters

Parameter	Description
hWin	Handle to the window which has to be blurred.
Period	Effect Period.
BlurDepth	Final depth of the blurring effect. Should be specified with 1-10.

Return value

0 on success
1 on error.

Additional information

The blurring quality can be changed using the functions GUI_MEMDEV_SetBlurHQ() or GUI_MEMDEV_SetBlurLQ().

Screenshots

The following screenshots show the background window being blurred in 5 steps. The used blurring depth is 10.



 © 2020 SEGGER Microcontroller GmbH

17.11.10 Setting up multiple buffering for animation functions

'Animation functions' refers to all functions listed in chapters

- *Animation functions* on page 732
- *Animation functions (Window Manager required)* on page 736
- *Blending, Blurring and Dithering functions* on page 741
- *Blending and Blurring functions (Window Manager required)* on page 749

17.11.10.1 GUI_MEMDEV_MULTIBUF_Enable()

Description

Normally memory device animation functions do not use multiple buffers. But under certain circumstances it could make sense to enable multiple buffers here. If enabled, the animation functions use `GUI_MULTIBUF_Begin()` and `GUI_MULTIBUF_End()` before/after drawing the memory device on the display.

Prototype

```
int GUI_MEMDEV_MULTIBUF_Enable(int OnOff);
```

Parameters

Parameter	Description
`OnOff`	Use 1 for enabling, 0 for disabling use of multiple buffers.

Return value

Previous state.

Additional information

Normally memory device animation functions do not use multiple buffers. But under certain circumstances it could make sense to enable multiple buffers here. If enabled, the animation functions use `GUI_MULTIBUF_Begin()` and `GUI_MULTIBUF_End()` before/after drawing the memory device on the display. That function makes sense in connection with '`GUI_DCACHE_SetClearCacheHook()`'.

 © 2020 SEGGER Microcontroller GmbH

17.11.11 Defines

17.11.11.1 Color conversion routines

Description

This parameter defines the desired color conversion. For more details about the used bits per pixel and the color conversion, refer to the chapter *Colors* on page 617.

Definition

```
#define GUICC_1       &LCD_API_ColorConv_1
#define GUICC_2       &LCD_API_ColorConv_2
#define GUICC_4       &LCD_API_ColorConv_4
#define GUICC_565     &LCD_API_ColorConv_565
#define GUICC_M565    &LCD_API_ColorConv_M565
#define GUICC_8666    &LCD_API_ColorConv_8666
#define GUICC_888     &LCD_API_ColorConv_888
#define GUICC_8888    &LCD_API_ColorConv_8888
```

Symbols

Definition	Description
GUICC_1	Fixed palette mode 1. (black/white)
GUICC_2	Fixed palette mode 2. (4 gray scales)
GUICC_4	Fixed palette mode 4. (16 gray scales)
GUICC_565	Fixed palette mode 565.
GUICC_M565	Fixed palette mode M565.
GUICC_8666	Fixed palette mode 8666.
GUICC_888	Fixed palette mode 888.
GUICC_8888	Fixed palette mode 8888.

 © 2020 SEGGER Microcontroller GmbH

17.11.11.2 Direction symbols

Description

Symbols used by memory device routines to determine in which direction a window should be moved.

Definition

```
#define GUI_MEMDEV_EDGE_LEFT      0
#define GUI_MEMDEV_EDGE_RIGHT     1
#define GUI_MEMDEV_EDGE_TOP       2
#define GUI_MEMDEV_EDGE_BOTTOM    3
```

Symbols

Definition	Description
GUI_MEMDEV_EDGE_LEFT	Shift window to the left.
GUI_MEMDEV_EDGE_RIGHT	Shift window to the right.
GUI_MEMDEV_EDGE_TOP	Shift window to the top.
GUI_MEMDEV_EDGE_BOTTOM	Shift window to the bottom.

See also

- GUI_MEMDEV_ShiftInWindow()
- GUI_MEMDEV_ShiftOutWindow()
- GUI_MEMDEV_SwapWindow()

 © 2020 SEGGER Microcontroller GmbH

17.11.11.3 Memory device color depths

Description

Defines the color depth of the Memory Device in bpp. The color depth of the Memory Device should be equal or greater than the required bits for the color conversion routines.

Definition

```
#define GUI_MEMDEV_APILIST_1     &GUI_MEMDEV_DEVICE_1
#define GUI_MEMDEV_APILIST_8     &GUI_MEMDEV_DEVICE_8
#define GUI_MEMDEV_APILIST_16    &GUI_MEMDEV_DEVICE_16
#define GUI_MEMDEV_APILIST_32    &GUI_MEMDEV_DEVICE_32
```

Symbols

Definition	Description
GUI_MEMDEV_APILIST_1	Create Memory Device with 1bpp color depth (1 byte per 8 pixels). Use if the specified color conversion requires 1bpp.
GUI_MEMDEV_APILIST_8	Create Memory Device with 8bpp color depth (1 byte per pixel). Use if the specified color conversion requires 8bpp or less.
GUI_MEMDEV_APILIST_16	Create Memory Device with 16bpp color depth (1 U16 per pixel). Use if the specified color conversion requires more than 8 bpp (high color modes).
GUI_MEMDEV_APILIST_32	Create Memory Device with 32bpp color depth (1 U32 per pixel). Use if the specified color conversion requires more than 16 bpp (true color modes).

Additional information

A Memory Device with a 1bpp color conversion (GUI_COLOR_CONV_1) for example requires at least a Memory Device with 1bpp color depth. The available Memory Devices are 1bpp, 8bpp, 16bpp and 32bpp Memory Devices. So an 1bpp Memory Device should be used.

If using a 4 bit per pixel color conversion (GUI_COLOR_CONV_4) at least 4bpp are needed for the Memory Device. In this case an 8bpp Memory Device should be used.

 © 2020 SEGGER Microcontroller GmbH

17.11.11.4 Memory device flags

Description

Flags to be used for the creation of a memory device.

Definition

```
#define GUI_MEMDEV_HASTRANS    0
#define GUI_MEMDEV_NOTRANS     (1 << 0)
```

Symbols

Definition	Description
GUI_MEMDEV_HASTRANS	Default: The Memory Device is created with a transparency flag which ensures that the background will be drawn correctly.
GUI_MEMDEV_NOTRANS	Creates a Memory Device without transparency. The user must make sure that the background is drawn correctly. This way the Memory Device can be used for non-rectangular areas. An other advantage is the higher speed: Using this flag accelerates the Memory Device approx. by 30 - 50%.

 © 2020 SEGGER Microcontroller GmbH

Chapter 18

Execution Model: Single Task / Multitask

emWin has been designed from the beginning to be compatible with different types of environments. It works in single task and in multitask applications, with a proprietary operating system or with any commercial RTOS such as embOS or uC/OS.

 © 2020 SEGGER Microcontroller GmbH

18.1 Supported execution models

We have to basically distinguish between 3 different execution models:

Single task system (super loop)

The entire program runs in one super loop. Normally, all software components are periodically called. Interrupts must be used for real time parts of the software since no real time kernel is used.

Multitask system: one task calling emWin

A real time kernel (RTOS) is used, but only one task calls emWin functions. From the graphic software's point of view, it is the same as being used in a single task system.

Multitask system: multiple tasks calling emWin

A real time kernel (RTOS) is used, and multiple tasks call emWin functions. This works without a problem as long as the software is made thread-safe, which is done by enabling multitask support in the configuration and adapting the kernel interface routines. For popular kernels, the kernel interface routines are readily available.

 © 2020 SEGGER Microcontroller GmbH

18.2 Single task system (super loop)

18.2.1 Description

The entire program runs in one super loop. Normally, all components of the software are periodically called. No real time kernel is used, so interrupts must be used for real time parts of the software. This type of system is primarily used in smaller systems or if real time behavior is not critical.

18.2.2 Superloop example (without emWin)

```
void main (void) {
  HARDWARE_Init();
  /* Init software components */
  XXX_Init();
  YYY_Init();
  /* Superloop: call all software components regularily */
  while (1) {
    /* Exec all compontents of the software */
    XXX_Exec();
    YYY_Exec();
  }
}
```

18.2.3 Advantages

No real time kernel is used (➔ smaller ROM size, just one stack ➔ less RAM for stacks), no preemption/synchronization problems.

18.2.4 Disadvantages

The super loop type of program can become hard to maintain if it exceeds a certain program size. Real time behavior is poor, since one software component cannot be interrupted by any other component (only by interrupts). This means that the reaction time of one software component depends on the execution time of all other components in the system.

18.2.5 Using emWin

There are no real restrictions regarding the use of emWin. As always, `GUI_Init()` has to be called before you can use the software. From there on, any API function can be used. If the Window Manager's callback mechanism is used, then an emWin update function has to be called regularly. This is typically done by calling the `GUI_Exec()` from within the super loop. Blocking functions such as `GUI_ExecDialog()` should not be used in the loop since they would block the other software modules. The default configuration, which does not support multitasking (`#define GUI_OS 0`) can be used; kernel interface routines are not required.

18.2.6 Superloop example (with emWin)

```
void main (void) {
  HARDWARE_Init();
  /* Init software components */
  XXX_Init();
  YYY_Init();
  GUI_Init();        /* Init emWin */
  /* Superloop: call all software components regularily */
  while (1) {
    /* Exec all compontents of the software */
    XXX_Exec();
    YYY_Exec();
    GUI_Exec();        /* Exec emWin for functionality like updating windows */
```

 © 2020 SEGGER Microcontroller GmbH

```
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

18.3 Multitask system: one task calling emWin

18.3.1 Description

A real time kernel (RTOS) is used. The user program is split into different parts, which execute in different tasks and typically have different priorities. Normally the real time critical tasks (which require a certain reaction time) will have the highest priorities. **One single task** is used for the user interface, which calls emWin functions. This task usually has the lowest priority in the system or at least one of the lowest (some statistical tasks or simple idle processing may have even lower priorities).
Interrupts can, but do not have to be used for real time parts of the software.

18.3.2 Advantages

The real time behavior of the system is excellent. The real time behavior of a task is affected only by tasks running at higher priority. This means that changes to a program component running in a low priority task do not affect the real time behavior at all. If the user interface is executed from a low priority task, this means that changes to the user interface do not affect the real time behavior. This kind of system makes it easy to assign different components of the software to different members of the development team, which can work to a high degree independently from each other.

18.3.3 Using emWin

If the Window Manager's callback mechanism is used, then an emWin update function (typically `GUI_Exec()`, `GUI_Delay()`) has to be called regularly from the task calling emWin. Since emWin is only called by one task, to emWin it is the same as being used in a single task system.
The default configuration, which does not support multitasking (`#define GUI_OS 0`) can be used; kernel interface routines are not required. You can use any real time kernel, commercial or proprietary.

 © 2020 SEGGER Microcontroller GmbH

18.4 Multitask system: multiple tasks calling emWin

18.4.1 Description

A real time kernel (RTOS) is used. The user program is split into different parts, which execute in different tasks with typically different priorities. Normally the real time critical tasks (which require a certain reaction time) will have the highest priorities. **Multiple tasks** are used for the user interface, calling emWin functions. These tasks typically have low priorities in the system, so they do not affect the real time behavior of the system.
Interrupts can, but do not have to be used for real time parts of the software.

18.4.2 Advantages

The real time behavior of the system is excellent. The real time behavior of a task is affected only by tasks running at higher priority. This means that changes of a program component running in a low priority task do not affect the real time behavior at all. If the user interface is executed from a low priority task, this means that changes on the user interface do not affect the real time behavior. This kind of system makes it easy to assign different components of the software to different members of the development team, which can work to a high degree independently from each other.

18.4.3 Using emWin

If the Window Manager's callback mechanism is used, then an emWin update function (typically `GUI_Exec()`, `GUI_Delay()`) has to be called regularly from one or more tasks calling emWin.
The default configuration, which does not support multitasking (`#define GUI_OS 0`) can **NOT** be used. The configuration needs to enable multitasking support and define a maximum number of tasks from which emWin is called (excerpt from `GUIConf.h`):

```
#define GUI_OS       1     // Enable multitasking support
#define GUI_MAXTASK  5     // Max. number of tasks that may call emWin
```

Kernel interface routines are required, and need to match the kernel being used. You can use any real time kernel, commercial or proprietary. Both the macros and the routines are discussed in the following chapter sections.

18.4.4 Recommendations

- Call the emWin update functions (that is, `GUI_Exec()`, `GUI_Delay()`) from just one task. It will help to keep the program structure clear. If you have sufficient RAM in your system, dedicate one task (with the lowest priority) to updating emWin. This task will continuously call `GUI_Exec()` as shown in the example below and will do nothing else.
- Keep your real time tasks (which determine the behavior of your system with respect to I/O, interface, network, etc.) separate from tasks that call emWin. This will help to assure best real time performance.
- If possible, use only one task for your user interface. This helps to keep the program structure simple and simplifies debugging. (However, this is not required and may not be suitable in some systems.)

18.4.5 Example

This excerpt shows the dedicated emWin update task. It is taken from the example `MT_Multitasking`, which is included in the examples shipped with emWin:

```
/*********************************************************************
*
*          GUI background processing
*
* This task does the background processing.
```

 © 2020 SEGGER Microcontroller GmbH

```
* The main job is to update invalid windows, but other things such as
* evaluating mouse or touch input may also be done.
*/
void GUI_Task(void) {
  while(1) {
    GUI_Exec();           /* Do the background work ... Update windows etc.) */
    GUI_X_ExecIdle();     /* Nothing left to do for the moment ... Idle
 processing */
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

18.5 Configuration functions for multitasking support

The following table shows the configuration functions available for a multitask system with multiple tasks calling emWin:

Routine	Description
GUI_SetSignalEventFunc()	Sets a function that signals an event.
GUI_SetWaitEventFunc()	Sets a function which waits for an event.
GUI_SetWaitEventTimedFunc()	Defines a function which waits for an event for a dedicated period of time.
GUI_WaitEvent()	Sets emWin into wait state.

 © 2020 SEGGER Microcontroller GmbH

18.5.1 GUI_SetSignalEventFunc()

Description

Sets a function that signals an event.

Prototype

```
void GUI_SetSignalEventFunc(GUI_SIGNAL_EVENT_FUNC pfSignalEvent);
```

Parameters

Parameter	Description
pfSignalEvent	Pointer to a function that signals an event.

Definition of GUI_SIGNAL_EVENT_FUNC

```
typedef void (* GUI_SIGNAL_EVENT_FUNC)(void);
```

Additional information

Per default the GUI needs to periodically check for events unless a function is defined which waits and one that triggers an event. This function sets the function which triggers an event. It makes only sense in combination with `GUI_SetWaitEventFunc()`. and `GUI_SetWaitEventTimedFunc()`. The advantage of using these functions instead of polling is the reduction of CPU load of the waiting task to 0% while it waits for input. If the function has been specified as recommended and the user gives the system any input (keyboard or pointer input device) the specified function should signal an event.
It is recommended to specify the function `GUI_X_SignalEvent()` for the job.

Example

```
GUI_SetSignalEventFunc(GUI_X_SignalEvent);
```

 © 2020 SEGGER Microcontroller GmbH

18.5.2 GUI_SetWaitEventFunc()

Description

Sets a function which waits for an event.

Prototype

```
void GUI_SetWaitEventFunc(GUI_WAIT_EVENT_FUNC pfWaitEvent);
```

Parameters

Parameter	Description
pfWaitEvent	Pointer to a function that waits for an event.

Definition of GUI_SIGNAL_EVENT_FUNC

```
typedef void (* GUI_WAIT_EVENT_FUNC)(void);
```

Additional information

Per default the GUI needs to periodically check for events unless a function is defined which waits and one that triggers an event. This function sets the function which waits for an event. Makes only sense in combination with `GUI_SetSignalEventFunc()` and `GUI_SetWaitEventTimedFunc()`. The advantage of using these functions instead of polling is the reduction of CPU load of the waiting task to 0% while it waits for input. If the function has been specified as recommended and the system waits for user input the defined function should wait for an event signaled from the function specified by `GUI_SetSignalEventFunc()`. It is recommended to specify the function `GUI_X_WaitEvent()` for the job.

Example

```
GUI_SetWaitEventFunc(GUI_X_WaitEvent);
```

 © 2020 SEGGER Microcontroller GmbH

18.5.3 GUI_SetWaitEventTimedFunc()

Description

Defines a function which waits for an event for a dedicated period of time.

Prototype

```
void GUI_SetWaitEventTimedFunc(GUI_WAIT_EVENT_TIMED_FUNC pfWaitEventTimed);
```

Parameters

Parameter	Description
pfWaitEventTimed	Pointer to a function that waits for an event.

Definition of GUI_WAIT_EVENT_TIMED_FUNC

```
typedef void (* GUI_WAIT_EVENT_TIMED_FUNC)(int Period);
```

Parameter	Description
Period	Period in ms to wait for an event.

Additional information

Per default the GUI needs to periodically check for events unless a function is defined which waits and one that triggers an event. This function sets the function which waits for an event if a timer is active. Makes only sense in combination with `GUI_SetSignalEventFunc()` and `GUI_SetWaitEventFunc()`. If the function has been specified as recommended and the system waits for user input during a timer is active the defined function should wait until the timer expires or an event signaled from the function set by `GUI_SetSignalEventFunc()`. It is recommended to specify the function `GUI_X_WaitEventTimed()` for the job.

Example

```
GUI_SetWaitEventTimedFunc(GUI_X_WaitEventTimed);
```

 © 2020 SEGGER Microcontroller GmbH

18.5.4 GUI_WaitEvent()

Description

Sets emWin into wait state. If an event gets signaled emWin will continue.

Prototype

```
void GUI_WaitEvent(void);
```

Additional information

This function is called to let emWin wait for an event which gets signaled by the function set by `GUI_SetWaitEventFunc()`.

Example

```
if (!GUI_Exec()) {
  GUI_WaitEvent();
}
```

 © 2020 SEGGER Microcontroller GmbH

18.6 Configuration macros for multitasking support

The following table shows the configuration macros used for a multitask system with multiple tasks calling emWin:

Type	Macro	Default	Description
N	GUI_MAXTASK	4	Defines the maximum number of tasks from which emWin is called when multi-tasking support is enabled.
B	GUI_OS	0	Activate to enable multitasking support.
F	GUI_X_SIGNAL_EVENT	-	Defines a function that signals an event. (Obsolete)
F	GUI_X_WAIT_EVENT	GUI_X_ExecIdle	Defines a function that waits for an event. (Obsolete)
F	GUI_X_WAIT_EVENT_TIMED	-	Defines a function that waits for an event for a dedicated period of time. (Obsolete)

18.6.1 GUI_MAXTASK

Description

Defines the maximum number of tasks from which emWin is called to access the display.

Type

Numerical value.

Additional information

This symbol is only relevant when GUI_OS is activated. If working with a pre-compiled library the function GUITASK_SetMaxTask() should be used instead. Further information can be found in the function description of *GUITASK_SetMaxTask* on page 2884.

18.6.2 GUI_OS

Description

Enables multitasking support by activating the module GUITask.

Type

Binary switch

- 0: inactive, multitask support disabled (default)
- 1: active, multitask support enabled

18.6.3 GUI_X_SIGNAL_EVENT

Description

Defines a function that signals an event.

Type

Function replacement

Additional information

Per default the GUI needs to periodically check for events unless a function is defined which waits and one that triggers an event. This macro defines the function which triggers an event. It makes only sense in combination with GUI_X_WAIT_EVENT. The advantage of using

 © 2020 SEGGER Microcontroller GmbH

the macros GUI_X_SIGNAL_EVENT and GUI_X_WAIT_EVENT instead of polling is the reduction of CPU load of the waiting task to 0% while it waits for input. If the macro has been defined as recommended and the user gives the system any input (keyboard or pointer input device) the defined function should signal an event.
It is recommended to specify the function GUI_X_SignalEvent() for the job.

Example

```
#define GUI_X_SIGNAL_EVENT GUI_X_SignalEvent
```

18.6.4 GUI_X_WAIT_EVENT

Description

Defines a function which waits for an event.

Type

Function replacement

Additional information

Per default the GUI needs to periodically check for events unless a function is defined which waits and one that triggers an event. This macro defines the function which waits for an event. Makes only sense in combination with GUI_X_SIGNAL_EVENT. The advantage of using the macros GUI_X_SIGNAL_EVENT and GUI_X_WAIT_EVENT instead of polling is the reduction of CPU load of the waiting task to 0% while it waits for input. If the macro has been defined as recommended and the system waits for user input the defined function should wait for an event signaled from the function defined by the macro GUI_X_SIGNAL_EVENT.
It is recommended to specify the function GUI_X_WaitEvent() for the job.

Example

```
#define GUI_X_WAIT_EVENT GUI_X_WaitEvent
```

18.6.5 GUI_X_WAIT_EVENT_TIMED

Description

Defines a function which waits for an event for a dedicated period of time.

Type

Function replacement

Additional information

Per default the GUI needs to periodically check for events unless a function is defined which waits and one that triggers an event. This macro defines the function which waits for an event if a timer is active. Makes only sense in combination with GUI_X_SIGNAL_EVENT. If the macro has been defined as recommended and the system waits for user input during a timer is active the defined function should wait until the timer expires or an event signaled from the function defined by the macro GUI_X_SIGNAL_EVENT.
It is recommended to specify the function GUI_X_WaitEventTimed() for the job.

Example

```
#define GUI_X_WAIT_EVENT_TIMED GUI_X_WaitEventTimed
```

 © 2020 SEGGER Microcontroller GmbH

18.7 Kernel interface API

An RTOS usually offers a mechanism called a resource semaphore, in which a task using a particular resource claims that resource before actually using it. The display is an example of a resource that needs to be protected with a resource semaphore. emWin uses the macro `GUI_USE` to call the function `GUI_Use()` before it accesses the display or before it uses a critical internal data structure. In a similar way, it calls `GUI_Unuse()` after accessing the display or using the data structure. This is done in the module `GUITask.c`.
`GUITask.c` in turn uses the GUI kernel interface routines shown in the table below. These routines are prefixed `GUI_X_` since they are high-level (hardware-dependent) functions. They must be adapted to the real time kernel used in order to make the emWin task (or thread) safe. Detailed descriptions of the routines follow, as well as examples of how they are adapted for different kernels.

Routine	Description
`GUI_X_GetTaskId()`	Returns a unique ID for the current task.
`GUI_X_InitOS()`	Creates the resource semaphore or mutex typically used by `GUI_X_Lock()` and `GUI_X_Unlock()`.
`GUI_X_Lock()`	Locks the GUI.
`GUI_X_SignalEvent()`	Signals an event.
`GUI_X_Unlock()`	Unlocks the GUI.
`GUI_X_WaitEvent()`	Waits for an event.
`GUI_X_WaitEventTimed()`	Waits for an event for the given period.

 © 2020 SEGGER Microcontroller GmbH

18.7.1 GUI_X_GetTaskId()

Description

Returns a unique ID for the current task.

Prototype

```
U32 GUI_X_GetTaskId(void);
```

Return value

ID of the current task as a 32-bit integer.

Additional information

Used with a real-time operating system. It does not matter which value is returned, as long as it is unique for each task/ thread using the emWin API and as long as the value is always the same for each particular thread.

 © 2020 SEGGER Microcontroller GmbH

18.7.2 GUI_X_InitOS()

Description

Creates the resource semaphore or mutex typically used by `GUI_X_Lock()` and `GUI_X_Unlock()`.

Prototype

```
void GUI_X_InitOS(void);
```

 © 2020 SEGGER Microcontroller GmbH

18.7.3 GUI_X_Lock()

Description

Locks the GUI.

Prototype

```
void GUI_X_Lock(void);
```

Additional information

This routine is called by the GUI before it accesses the display or before using a critical internal data structure. It blocks other threads from entering the same critical section using a resource semaphore/mutex until `GUI_X_Unlock()` has been called. When using a real time operating system, you normally have to increment a counting resource semaphore.

 © 2020 SEGGER Microcontroller GmbH

18.7.4 GUI_X_SignalEvent()

Description

Signals an event.

Prototype

```
void GUI_X_SignalEvent(void);
```

Additional information

This function is optional, it is used only via the macro `GUI_X_SIGNAL_EVENT` or the function `GUI_SetSignalEventFunc()`.

 © 2020 SEGGER Microcontroller GmbH

18.7.5 GUI_X_Unlock()

Description

Unlocks the GUI.

Prototype

```
void GUI_X_Unlock(void);
```

Additional information

This routine is called by the GUI after accessing the display or after using a critical internal data structure. When using a real time operating system, you normally have to decrement a counting resource semaphore.

 © 2020 SEGGER Microcontroller GmbH

18.7.6 GUI_X_WaitEvent()

Description

Waits for an event.

Prototype

```
void GUI_X_WaitEvent(void);
```

Additional information

This function is optional, it is used only via the macro `GUI_X_WAIT_EVENT` or the function `GUI_SetWaitEventFunc()`.

 © 2020 SEGGER Microcontroller GmbH

18.7.7 GUI_X_WaitEventTimed()

Description

Waits for an event for the given period.

Prototype

```
void GUI_X_WaitEventTimed(int Period);
```

Parameters

Parameter	Description
Period	Period in ms to be used.

Additional information

This function is optional, it is used only via the macro GUI_X_WAIT_EVENT_TIMED or the function GUI_SetWaitEventTimedFunc().

 © 2020 SEGGER Microcontroller GmbH

18.8 Examples

Kernel interface routines for embOS

The following example shows an adaption for embOS (excerpt from file `GUI_X_embOS.c` located in the folder `Sample\GUI_X`):

```
#include "RTOS.H"
static OS_TASK* _pGUITask;
static OS_RSEMA _RSema;
void GUI_X_InitOS(void)    { OS_CreateRSema(&_RSema);    }
void GUI_X_Unlock(void)    { OS_Unuse(&_RSema);          }
void GUI_X_Lock(void)      { OS_Use(&_RSema);            }
U32  GUI_X_GetTaskId(void) { return (U32)OS_GetTaskID(); }
void GUI_X_WaitEvent(void) {
  _pGUITask = OS_GetpCurrentTask();
  OS_WaitEvent(1);
}
void GUI_X_SignalEvent(void) {
  if (_pGUITask) {
    OS_SignalEvent(1, _pGUITask);
  }
}
void GUI_X_WaitEventTimed(int Period) {
  static OS_TIMER Timer;
  static int Initialized;

  if (Period > 0) {
    if (Initialized != 0) {
      OS_DeleteTimer(&Timer);
    }
    Initialized = 1;
    OS_CreateTimer(&Timer, GUI_X_SignalEvent, Period);
    OS_StartTimer(&Timer);
    GUI_X_WaitEvent();
  }
}
```

Kernel interface routines for uC/OS

The following example shows an adaption for uC/OS (excerpt from file `GUI_X_uCOS.c` located in the folder `Sample\GUI_X`):

```
#include "INCLUDES.H"
static OS_EVENT * pDispSem;
static OS_EVENT * pGUITask;
U32   GUI_X_GetTaskId(void) { return ((U32)(OSTCBCur->OSTCBPrio)); }
void  GUI_X_Unlock(void)    { OSSemPost(pDispSem);                 }
void  GUI_X_InitOS(void)    {
  pDispSem = OSSemCreate(1);
  pGUITask = OSSemCreate(0);
}
void  GUI_X_Lock(void)      {
  INT8U err;
  OSSemPend(pDispSem, 0, &err);
}
```

Kernel interface routines for Win32

The following is an excerpt from the Win32 simulation for emWin. When using the emWin simulation, there is no need to add these routines, as they are already in the library.

 © 2020 SEGGER Microcontroller GmbH

> **Note**
>
> Cleanup code has been omitted for clarity.

```
/*********************************************************************
*
*      emWin - Multitask interface for Win32
*
**********************************************************************
  The following section consisting of 4 routines is used to make
  emWin thread safe with WIN32
*/
static HANDLE hMutex;
void GUI_X_InitOS(void) {
  hMutex = CreateMutex(NULL, 0, "emWinSim - Mutex");
}
unsigned int GUI_X_GetTaskId(void) {
  return GetCurrentThreadId();
}
void GUI_X_Lock(void) {
  WaitForSingleObject(hMutex, INFINITE);
}
void GUI_X_Unlock(void) {
  ReleaseMutex(hMutex);
}
```

 © 2020 SEGGER Microcontroller GmbH

Chapter 19

The Window Manager (WM)

When using the emWin Window Manager (WM), everything which appears on the display is contained in a window—a rectangular area on the screen. A window can be of any size, and you can display multiple windows on the screen at once, even partially or entirely in front of other windows.

The Window Manager supplies a set of routines which allow you to easily create, move, resize, and otherwise manipulate any number of windows. It also provides lower-level support by managing the layering of windows on the display and by alerting your application to display changes that affect its windows.

The emWin Window Manager is a separate (optional) software item and is not included in the emWin basic package. The software for the Window Manager is located in the subdirectory `GUI\WM`.

 © 2020 SEGGER Microcontroller GmbH

19.1 Description of terms

Windows are rectangular in shape, defined by their origin (the X- and Y-coordinates of the upper left corner) as well as their X- and Y-sizes (width and height, respectively). A window in emWin:

- is rectangular.
- has a Z-position.
- may be hidden or shown.
- may have valid and/or invalid areas.
- may or may not have transparency.
- may or may not have a callback routine.

Active window

The window which is currently being used for drawing operations is referred to as the active window. It is not necessarily the same as the topmost window.

Callback routines

Callback routines are defined by the user program, instructing the graphic system to call a specific function when a specific event occurs. Normally they are used to automatically redraw a window when its content has changed.

Child windows

A child window is one that is defined relative to another window, called the parent. Whenever a parent window moves, its child or children move correspondingly. A child window is always completely contained within its parent, and will be clipped if necessary. Multiple child windows with the same parent are considered "siblings" to one another.

Client area

The client area of a window is simply its usable area. If a window contains a frame or title bar, then the client area is the rectangular inner area. If there is no such frame, then the coordinates of the client area are identical to those of the window itself.

Clipping, clip area

Clipping is the process of limiting output to a window or part of it. The clip area of a window is its visible area. This is the window area minus the area obstructed by siblings of higher Z-order, minus any part that does not fit into the visible area of the parent window.

Coordinates

Coordinates are usually 2 dimensional coordinates, expressed in units of pixels. A coordinate consists of 2 values. The first value specifies the horizontal component (also called the x-coordinate), the second value specifies the vertical component (also called the y-coordinate).

Current window

See active window.

Desktop coordinates

Desktop coordinates are coordinates of the desktop window. The upper left position (the origin) of the display is (0,0).

Desktop window

The desktop window is automatically created by the Window Manager, and always covers the entire display area. This is done for each layer, so each layer has its own desktop window. The desktop is always the bottommost window, and when no other window has been defined, it is the default (active) window. All windows are descendants (children,

 © 2020 SEGGER Microcontroller GmbH

grandchildren, etc.) of the desktop window of the currently selected layer. The desktop window has a buffer wich can hold data with the size of a void data type. This allows the user to add user data, e.g. a pointer to a structure.

Early clipping

This is the default clipping mode. In this mode clipping is performed before windows receive paint events. In case the current window needs to be clipped, it will receive more than one `WM_PAINT` message within a single drawing process.
In the late clipping mode, windows always receive only one single `WM_PAINT` message. In this mode clipping is performed within the drawing operations.

Handle

When a new window is created, the WM assigns it a unique identifier called a handle. The handle is used in any further operations performed on that particular window.

Hiding windows

A hidden window is not visible, although it still exists (has a handle). When a window is created, it is hidden by default if no create flag is specified. Showing a window makes it visible; hiding it makes it invisible.

Late clipping

See early clipping.

Parent coordinates

Parent coordinates are window coordinates relative to the parent window. The upper left position (the origin) of the window is (0,0).

Parent windows

See child windows.

Showing windows

See Hiding windows.

Siblings

See child windows.

Transparency

A window that has transparency contains areas that are not redrawn with the rest of the window. These areas operate as though the window behind "shows through" them. In this case, it is important that the window behind is redrawn before the window with transparency. The WM automatically handles redrawing in the correct order.

Validation/invalidation

A valid window is a fully updated window which does not need redrawing. An invalid window does not yet reflect all updates and therefore needs to be redrawn, either completely or partially. When changes are made that affect a particular window, the WM marks that window as invalid. The next time the window is redrawn (either manually or by a callback routine) it will be validated.

Window coordinates

Window coordinates are coordinates of a window. The upper left position (the origin) of the window is (0,0).

 © 2020 SEGGER Microcontroller GmbH

Z-position, bottom/top

Although a window is displayed on a two-dimensional screen in terms of X and Y, the WM also manages what is known as a Z-position, or depth coordinate—a position in a virtual third dimension which determines its placement from background to foreground. Windows can therefore appear on top of or beneath one another.
Setting a window to the bottom will place it "underneath" all of its sibling windows (if any); setting it to the top will place it "on top of" its siblings. When a window is created, it is set to the top by default if no create flag is specified.

 © 2020 SEGGER Microcontroller GmbH

19.2 Callback mechanism, invalidation, rendering and keyboard input

The idea behind the callback mechanism that emWin offers for windows and window objects (widgets) is that of an event-driven system. As in most windowing systems, the principle is that the flow of control is not just from the user program to the graphic system, but also from the user program to the graphic system and back up to the user program by means of the callback routines provided by the user program. This mechanism—often facetiously referred to as the Hollywood principle ("Don't call us, we'll call you!")—is needed by the Window Manager mainly in order to trigger the redrawing of windows. This contrasts with classical programming, but it makes it possible to exploit the invalidation logic of the Window Manager.

19.2.1 Rendering using callbacks

In order to create a window with a callback, you must have a callback routine. The routine is used as part of the `WM_CreateWindow()` function when creating the window (the `cb` parameter). All callback routines must have the following prototype:

Prototype

```
void Callback(WM_MESSAGE * pMsg);
```

Parameter	Description
`pMsg`	Pointer to a data structure of type `WM_MESSAGE`.

The action performed by the callback routine depends on the type of message it receives. The prototype above is usually followed by a switch statement, which defines different behaviors for different messages using one or more case statements (typically at least `WM_PAINT`).

Processing the WM_PAINT message

When a window receives a `WM_PAINT` message, it should repaint itself. Before sending this message to the window, the WM makes sure it is selected. **A non-transparent window (default!) has to repaint its entire invalid area.** The easiest way is to repaint the entire area of the window. The clipping mechanism of the WM makes sure that only the invalid area will be redrawn. In order to accelerate the drawing process, it can make sense to only repaint the invalid area. How to get the invalid area is described later in this chapter (Information is part of the message).
A transparent window on the other hand does not have to redraw the entire invalid area; it can leave the window area partially untouched. This untouched area will then be transparent.
Before the WM sends a `WM_PAINT` message to a transparent window, the area below has been redrawn (by sending a `WM_PAINT` message to the window(s) below).

> **Note**
>
> Certain things should not be done when processing `WM_PAINT`, `WM_PRE_PAINT` and `WM_POST_PAINT`.

When processing the `WM_PAINT` message, the callback routine should do nothing but redrawing the contents of the window. When processing the `WM_PAINT`, `WM_PRE_PAINT` or `WM_POST_PAINT` event, the following functions may not be called: `WM_SelectWindow()`, `WM_Paint()`, `WM_DeleteWindow()` and `WM_CreateWindow()`. Also any other functions which changes the properties of a window may not be called: `WM_Move()`, `WM_Resize()`, …

Example

Creates a callback routine to automatically redraw a window:

 © 2020 SEGGER Microcontroller GmbH

```
void WinHandler(WM_MESSAGE * pMsg) {
  switch (pMsg->MsgId) {
  case WM_PAINT:
    GUI_SetBkColor(0xFF00);
    GUI_Clear();
    GUI_DispStringAt("Hello world",0,0);
    break;
  default:
    WM_DefaultProc(pMsg);
  }
}
```

The messages WM_PRE_PAINT and WM_POST_PAINT are sent directly before and after the WM_PAINT messages are processed.

19.2.2 Overwriting callback functions

The default behavior of widgets and windows in emWin is defined in their callback functions. If the behavior of a widget has to be changed, or if the functionality of a window needs to be enhanced to meet custom needs, it is recommended to overwrite the internal callback function. This is done in a few simple steps:

Step 1: Creating a custom callback function

The first step is to implement a function using the following prototype:

```
void Callback(WM_MESSAGE * pMsg);
```

Step 2: Messages

The second step is to implement a reaction to certain messages.
Since custom callback functions do not need to handle all possible messages, it is recommended to make use of a switch / case condition. This makes it possible to easily add or remove one message specific code, without affecting another. The parameter pMsg contains the Id of the message (pMsg->MsgId). A complete list of messages handled by the Window Manager may be reviewed under *Message IDs* on page 951.

Step 3: Processing the default callback

The third step is to make sure all messages which are not handled by the custom callback function, are handled by the internal (default) callback function. The recommended way to do this is to use the default case of the switch / case condition to call the internal callback function.

Internal callback functions are different for each type of window. The internal callback functions for widgets are named <WIDGET>_Callback(). All other types of windows use the function WM_DefaultProc() for message handling.

```
switch (pMsg->MsgId) {
case WM_CREATE:
  .
  .
  .
  break;
case WM_PAINT:
  .
  .
  .
  break;
case WM_SIZE:
  .
  .
  .
  break;
default:
```

 © 2020 SEGGER Microcontroller GmbH

```
  <WIDGET>_Callback(pMsg);
}
```

Step 4: Setting the custom callback function to be used

The last step to do is setting the newly created callback function to be used by a window or widget. This is done with a simple call of `WM_SetCallback()`. Detailed information can be found under *`WM_SetCallback`* on page 882.

19.2.3 Background window redrawing and callback

During initialization of the Window Manager, a window containing the whole LCD area is created as a background window. The handle of this window is `WM_HBKWIN`. The WM does not redraw areas of the background window automatically, because there is no default background color. That means if you create a further window and then delete it, the deleted window will still be visible. The routine `WM_SetDesktopColor()` needs to be specified in order to set a color for redrawing the background window.
You can also set a callback function to take care of this problem. If a window is created and then deleted as before, the callback routine will trigger the WM to recognize that the background window is no longer valid and redraw it automatically. For more information on using a callback routine to redraw the background, see the example at the end of the chapter.

19.2.4 Invalidation

Invalidation of a window or a part of it tells the WM that the invalid area of the window should be redrawn the next time `GUI_Exec()` or `GUI_Delay()` is called. The invalidation routines of emWin do not redraw the invalid part of a window. They only manage the invalid areas of the windows.

The invalid area of a window

The WM uses just one rectangle per window to store the smallest rectangle containing the entire invalid area. If for example a small part in the upper left corner and a small part in the lower right corner becomes invalid, the complete window is invalidated.

Why using invalidation

The advantage of using window invalidation in opposite of drawing each window immediately is that the window will be drawn only one time even if it is invalidated more than one time. If for example several properties of a window need to be changed (for example the background color, the font and the size of the window) it takes more time to draw the window immediately after each property has been changed than drawing the window only one time after all properties have been changed.

Redrawing of invalid windows

The function `GUI_Exec()` redraws all invalid windows. This is done by sending one or more `WM_PAINT` messages to each invalid window.

19.2.5 Tiling mechanism

Until here it should be clear, that drawing of a window normally is done by sending a `WM_PAINT` message. But if a window is partly covered by a child window or any other window, it is very important to know that it receives more than one `WM_PAINT` message. The WM cuts the non covered area of the window to be drawn into a number of sub rectangles. During that process it sets the clipping area to each of the rectangular areas and sends a single `WM_PAINT` message for each of the rectangles to the window. The more fragmented the window area is, the more rectangles exist and the more messages are send. Because of that the `WM_PAINT` handler should not do time consuming calculations.

 © 2020 SEGGER Microcontroller GmbH

The sample below shows the tiling mechanism required for drawing the background window covered by a FRAMEWINDOW widget. The widget consists of 2 windows, the main window and the client area. The main window is a transparent window which is drawn on top of the background and has no effect on the tiling algorithm whereas the client area is opaque and causes tiling of the background. The WM generates tiles around the client area from the top to the bottom and from the left to the right. The tiling algorithm implies that the number of tiles increases with the number of covered areas.



The screenshot below shows the above sample with an additional small window at the bottom right edge. When starting the drawing process of a non transparent window the WM first sends a WM_PRE_PAINT message. After that the window receives a WM_PAINT message for each tile. And after drawing the last tile the WM sends a final WM_POST_PAINT message. The more areas covering a non transparent window the more tiles are required for drawing the window.



Drawing without tiling

Under some circumstances it may could make sense to suppress tiling. That could be achieved by using the flag WM_CF_LATE_CLIP explained later in this chapter.

 © 2020 SEGGER Microcontroller GmbH

19.2.6 Rendering of transparent windows

If a transparent window needs to be drawn, the WM automatically makes sure, that the background of the window is drawn before the transparent window receives a `WM_PAINT` message. This is done by redrawing all window areas below the invalid area of the transparent window first before sending a `WM_PAINT` message to the transparent window.
To make sure the Window Manager can handle the redrawing of transparent windows it is necessary to redraw the window in reaction to the `WM_PAINT` message. Otherwise it can not be guaranteed that the appearance of a transparent window will be correctly.
The use of transparent windows is more CPU-intensive than the use of non transparent windows. If performance is a problem, trying to avoid transparent windows may be an option.

19.2.7 Automatic use of Memory Devices

The default behavior of the Window Manager is sending a `WM_PAINT` message to each window which needs to be redrawn. This can cause flickering effects. To suppress these ?per window? flickering effects Memory Devices can be used automatically for the drawing operation. This can be achieved by setting the flag `WM_CF_MEMDEV` when creating the window, by setting the default creation flags with `WM_SetCreateFlags()` or by using the function `WM_EnableMemdev()`. The WM then redirects the output of the `WM_PAINT` message into a Memory Device which is copied to the display once the actual drawing was performed. If not enough memory for the whole window is available banding is used automatically. The according Memory Device is created internally just before the `WM_PAINT` message is sent and is removed immediately after the drawing is finished.
In case a transparent window should be drawn, the below area will also be drawn into the Memory Device.
Detailed information about Memory Devices can be found in the chapter *Memory Devices* on page 666.

19.2.8 Automatic use of multiple frame buffers

The WM is able to use automatically multiple frame buffers if they are available. This can be achieved by the function `WM_MULTIBUF_Enable()`. If enabled the Window Manager redirects the output of all drawing functions to the invisible back buffer before it draws the invalid windows. After the last invalid window has been drawn the WM makes the back buffer visible. This feature is available only if the display driver supports multiple buffers and if there is enough RAM to store at least 2 frame buffers. More information can be found in the chapter *Multiple Buffering* on page 2372.

19.2.9 Automatic use of display driver cache

The WM automatically uses the display driver cache if available. If available it locks the buffer before it starts to draw the invalid windows. After the last window has been drawn the WM unlocks the cache.

19.2.10 Keyboard input

The Window Manager handles keyboard input automatically. It polls the keyboard buffer and sends according keyboard messages to the currently focused window. The keyboard buffer can be filled using the function `GUI_StoreKeyMsg()`.

 © 2020 SEGGER Microcontroller GmbH

19.3 Motion support

Motion support enables the ability to move windows by gestures. It can be used with any pointer input device (PID) like a touch screen, a mouse or a joystick. If motion support is enabled the respective window can be put into movement simply with a gesture. After releasing the PID the movement is decelerated within a specified period. Movement operations can be also initiated by API functions instead of gestures.

19.3.1 Enabling motion support of the WM

First of all motion support needs to be enabled before it can be used. This can be done by calling the function `WM_MOTION_Enable()` once. Without calling this function once the motion support functions will not work.

19.3.2 Basic motion support for a window

To be able to use motion support for a window it needs to be enabled for each window which should be movable. In case of a movable parent window with several child windows motion support needs only be enabled for the parent window. There are 2 possibilities to achieve basic motion support for a window:

19.3.2.1 Using creation flags

To achieve movability for a window it can be created with one or more or-combined creation flags. The following table shows the available creation flags:

Flag	Description
`WM_CF_MOTION_R`	Enables circular movability for objects within the window.
`WM_CF_MOTION_X`	Enables movability for the X axis.
`WM_CF_MOTION_Y`	Enables movability for the Y axis.

Example

```
WM_HWIN hWin;
hWin = WM_CreateWindowAsChild(0, 0, 40, 40, hParent,

  WM_CF_SHOW | WM_CF_MOTION_X | WM_CF_MOTION_Y, cbWin, 0);
```

> **Note**
>
> Of course the motion flags can also be used with widget creation functions.

19.3.2.2 Using API function

To achieve movability for a window after it has been created without movability flags the function `WM_MOTION_SetMoveable()` explained later in this chapter can be used.

19.3.3 Motion processing by application

The easiest way to achieve movable windows is setting up basic motion support. The WM then automatically moves the window when dragging the PID. But in certain situations it could make sense to process the motion information by the application instead of moving the whole window. That makes it possible to move any kind of content within a window, achieving edge snapping, overlapping or circular moves. In order to make use of that kind of advanced motion features the callback function of the movable window has to be adapted. In case the WM recognizes PID movement it sends a `WM_MOTION` message to the window. In order to achieve advanced motion support an appropriate reaction to the `WM_MOTION` message needs to be implemented.

 © 2020 SEGGER Microcontroller GmbH

19.3.3.1 WM_MOTION message and WM_MOTION_INFO

As explained in the message description *WM_MOTION* on page 800 the Data.p element of the WM_MOTION message points to a WM_MOTION_INFO structure. The element Cmd of this structure contains information about the current operation. The following table shows the possible values of the element Cmd:

Flag	Description
WM_MOTION_INIT	Sent to a window to initiate a motion operation.
WM_MOTION_MOVE	Sent to a window to achieve custom moving operations.
WM_MOTION_GETPOS	Sent to get the current position of custom moving operations.

WM_MOTION_INIT

If a PID move has been detected by the WM it first checks if there is any visible window available under the PID position which is already movable. This makes it possible to achieve moving operations for windows which are partially or totally covered by child windows. If the WM does not find an already movable window it sends the command to the 'top window' of the PID position.
If the window is not already movable when receiving this command the element Flags of the WM_MOTION_INFO structure can be used to enable motion support. The creation flags explained earlier can be used here to achieve automatic motion support. The Flags element simply needs to be OR-combined with the desired flag(s).

WM_MOTION_INIT and custom motion support

Custom motion support means that the moving operation is not done automatically by the WM but by the callback routine of the window. This can be useful if for example radial motions are required or if the content of a window should be moved instead of the window itself. To achieve custom motion support the Flags element needs to be OR-combined with the flag WM_MOTION_MANAGE_BY_WINDOW.

WM_MOTION_MOVE

Sent to a window with custom motion support enabled. The elements dx and dy of the WM_MOTION_INFO structure can be used to achieve the custom moving operation.

WM_MOTION_GETPOS

Sent to a window with custom motion support enabled. The task of the callback routine here is returning the current position. This needs to be done with the elements xPos and yPos of the WM_MOTION_INFO structure.

Snapping

The elements SnapX and SnapY of the WM_MOTION_INFO structure can be used to achieve snapping. These values determine a kind of grid for snapping. This means that the deceleration of the movement operation will stop exactly on a grid position. Also if there currently is no movement and the window is only released it will snap into the next grid position.

Overlapping

Overlapping means a short distance a window/object could be moved beyond its boundary. When releasing the PID it will move to its boundary automatically. The element Overlap of the WM_MOTION_INFO structure can be used to achieve overlapping. It is recommended to use at maximum the half of the snapping distance.

Examples

Several samples in the tutorial folder show how to achieve overlapping, snapping, circular moves and how to use advanced motion support.

 © 2020 SEGGER Microcontroller GmbH

19.3.4 Motion support for circular moves

That kind of motion support can be used to turn items around the center of a window. Windows can not be rotated. To enable support for circular moves the flag WM_CF_MOTION_R should be used which should be set within the WM_MOTION_INIT message. Moving the items need to be managed by the application. Because of that also the flag WM_MOTION_MANAGE_BY_WINDOW explained earlier must be set. The values in 1/10 degrees to be used are passed to the application in the element da of the WM_MOTION_INFO structure available within the message WM_MOTION_MOVE. The KNOB widget for example is completely based on motion support for circular moves.

Example

```
static void _OnMotion(WM_HWIN hWin, WM_MOTION_INFO * pInfo) {
  ...
  switch (pInfo->Cmd) {
  case WM_MOTION_INIT:
    pInfo->Flags  = WM_CF_MOTION_R | WM_MOTION_MANAGE_BY_WINDOW;
    break;
  case WM_MOTION_MOVE:
    _DoMotion(hObj, pInfo->da);
    break;
  ...
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

19.4 Window manager and multiple layers

A hardware with multiple layers offers a range of new possibilities. This subchapter should give some guidelines and explain the most important pitfalls. We highly recommend to consider the following rules.

19.4.1 Drawing operations

One of the most important recommendations is using the invalidation mechanism of the window manager for drawing operations. If something should be drawn in a further layer a window with callback function should be used and the drawing operation should be done within `WM_PAINT`.

> **Note**
>
> Do not draw outside of `WM_PAINT`!

On the first glance it often looks easy to use `GUI_SelectLayer()` and draw something outside of the current window in a different layer. But please note that this most often leads in unexpected behavior of the GUI. Multiple buffering, clipping and calculation of invalid state could fail in that case, even if it seems to work on the first glance.

19.4.2 Window relationship

A child window must be created in the same layer as its parent window. The WM won't work as expected if that rule is not observed. `WM_CreateWindow()` currently does not fail in that case, but the WM does not work correctly if the parent window is in a different layer than its child window.

19.4.3 Semi-Transparency

Most LCD controllers with multiple layers support an alpha channel for semi transparency effects. That requires an alpha value in the alpha channel of the frame buffer after executing a drawing operation. Please note that the default behavior of emWin is using the given alpha values (for example of an PNG image) for mixing up the current background with the foreground and not leaving any alpha values. The function `GUI_PreserveTrans()` should be used before/after those drawing operations. The same applies for drawing anti-aliased text.

19.4.4 Touch input

Within a multiple layer application it could make sense to have touch sensitive widgets in more than one layer. But the touch pad does not 'know' something about different layers. The normal behavior is setting the element `Layer` of the `GUI_PID_STATE` structure within the touch ISR. The used value should be the layer index containing the touch sensitive widgets. If it is required to manage touch input in different layers a callback function could be set with `GUI_PID_SetHook()`. That callback function is called immediately before a `GUI_PID_STATE` element is added to the input buffer. Dependent on the coordinates the application could change the `Layer` element. Please note that is is not required to change the coordinates. This is done by the WM automatically.

19.4.5 Memory devices

Currently a memory device which should be drawn in a `WM_PAINT` event, needs to be created in the same layer as the window which should draw the memory device.

 © 2020 SEGGER Microcontroller GmbH

19.5 ToolTips

A ToolTip in emWin is a small window with one line of text, which appears in conjunction with a pointer input device (PID), usually a mouse. The user hovers the PID over a 'tool', without clicking it, and a small ToolTip window with information about the item being hovered over may appear. After a short time the window disappears automatically. ToolTips make sense for active elements like any kind of button or similar widgets/windows, which can be used as tool for changing something. But they can be used with any kind of window.

19.5.1 How they work

A ToolTip belongs to a particular parent (or grandparent) window. When the PID hovers over a tool window without any motion, after a specified time (PERIOD_FIRST) the ToolTip window occurs. If the PID remains over the tool without motion, the ToolTip automatically disappears after a specified period of no motion (PERIOD_SHOW). It remains until the PID does not move for this period. If the PID is clicked or hovers out of the tool window the ToolTip disappears. If the PID remains in the parent area and the PID then hovers again over a tool of the same parent, the ToolTip occurs immediately after a very short period (PERIOD_NEXT) of no motion. If the PID moves out of the parent area, the next time a ToolTip occurs is again after PERIOD_FIRST. Appearance and timing can be configured at runtime.

19.5.2 Creating ToolTips

> **Note**
>
> The functions and structures mentioned in the following are described in detail later in this chapter under *ToolTip related functions* on page 918.

The function WM_TOOLTIP_Create() should be used for creating a ToolTip object. It requires a handle to the parent (or grand parent) window. Optional a pointer to an array of TOOLTIP_INFO structures can be passed which is used for adding the desired tools to the ToolTip object. These structures should contain the IDs of the tools and the text to be shown. Alternatively the function WM_TOOTIP_AddTool() can be used to add the tools. This makes sense if the tool window does not have an Id.

19.5.2.1 Creating ToolTips for dialog items

As mentioned above the TOOLTIP_INFO structure is used to address the desired tools by its IDs. Because the items of a dialog normally have an Id this is quite easy.

Example

The following example shows how it works:

```
#include "DIALOG.h"
#define ID_BUTTON_0 (GUI_ID_USER + 0x01)
#define ID_BUTTON_1 (GUI_ID_USER + 0x02)
static const GUI_WIDGET_CREATE_INFO _aDialogCreate[] = {
  { FRAMEWIN_CreateIndirect, "Framewin",         0, 0,  0, 320, 240, 0, 0, 0 },
  { BUTTON_CreateIndirect, "Button 0", ID_BUTTON_0, 5,  5,  80,  20, 0, 0, 0 },
  { BUTTON_CreateIndirect, "Button 1", ID_BUTTON_1, 5, 30,  80,  20, 0, 0, 0 },
};
static const TOOLTIP_INFO _aInfo[] = {
  { ID_BUTTON_0, "I am Button 0" },
  { ID_BUTTON_1, "I am Button 1" },
};
static void _ShowDialog(void) {
  WM_HWIN hWin;
  WM_TOOLTIP_HANDLE hInfo;
  hWin = GUI_CreateDialogBox(_aDialogCreate, GUI_COUNTOF(_aDialogCreate), 0,
                             WM_HBKWIN, 0, 0);
```

 © 2020 SEGGER Microcontroller GmbH

```
  hInfo = WM_TOOLTIP_Create(hWin, _aInfo, GUI_COUNTOF(_aInfo));
  while (1) {
    GUI_Delay(100);
  }
}
```

19.5.2.2 Creating ToolTips for simple windows

Because simple windows normally do not have an Id, there exists a function for adding tools without using IDs. The function `WM_TOOLTIP_AddTool()` can be used to do this by passing the tool window handle and the required text to be shown.

Example

The following example shows how it works:

```
#include <stddef.h>
#include "WM.h"
static void _cbParent(WM_MESSAGE * pMsg) {
  switch (pMsg->MsgId) {
  case WM_PAINT:
    GUI_SetBkColor(GUI_BLUE);
    GUI_Clear();
    GUI_DispString("Parent window");
    break;
  }
}
static void _cbTool(WM_MESSAGE * pMsg) {
  switch (pMsg->MsgId) {
  case WM_PAINT:
    GUI_SetBkColor(GUI_RED);
    GUI_Clear();
    GUI_DispString("Tool window");
    break;
  }
}
void MainTask(void) {
  WM_HWIN hTool, hParent;
  WM_TOOLTIP_HANDLE hToolTip;

  GUI_Init();
  WM_SetDesktopColor(GUI_BLACK);
  hParent = WM_CreateWindow(0, 0, 200, 100, WM_CF_SHOW, _cbParent, 0);
  hTool
  = WM_CreateWindowAsChild(20, 20, 100, 50, hParent, WM_CF_SHOW, _cbTool, 0);
  hToolTip = WM_TOOLTIP_Create(hParent, NULL, 0);
  WM_TOOLTIP_AddTool(hToolTip, hTool, "I am a ToolTip");
  while (1) {
    GUI_Delay(100);
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

19.6 Messages

The following section shows which system messages are used by emWin, how to use the message data and how to use application defined messages.

19.6.1 Message structure

When a callback routine is called, it receives the message specified as its `pMsg` parameter. This message is actually a `WM_MESSAGE` data structure, a full description of the structure can be read under *WM_MESSAGE* on page 946.

19.6.2 List of messages

> **Note**
>
> A full list of messages sent by emWin can be found under *Message IDs* on page 951.

19.6.3 System-defined messages

These kind of messages are sent by the GUI library. Do not send system defined messages from the user application to a window or a widget.

19.6.3.1 WM_CREATE

Description

This message is sent immediately after a window has been created, giving the window the chance to initialize and create any child windows.

Data

This message contains no data.

19.6.3.2 WM_DELETE

Description

This message is sent just before a window is deleted, telling the window to free its data structures (if any).

Data

This message contains no data.

19.6.3.3 WM_GET_ID

Description

This message is sent to a window to request its Id. All emWin widgets handle this message. Application defined windows should handle this message in their callback routine. Otherwise this message will be ignored.

Data

The callback routine of the window should store the Id in the `Data.v` value.

 © 2020 SEGGER Microcontroller GmbH

19.6.3.4 WM_GET_INSIDE_RECT

Description

This message is sent to a window to receive the client rectangle without the effect size. The effect size which is typically 0-3 pixels (2 pixels with the standard 3D effect).

Data

The `Data.p` pointer of the messages points to a `GUI_RECT` structure which has to be filled with the proper coordinates of the client rectangle.

19.6.3.5 WM_INIT_DIALOG

Description

This message is sent to a window immediately after the creation of the dialog and before the dialog is displayed. Dialog procedures typically use this message to initialize widgets and carry out any other initialization tasks that affect the appearance of the dialog box.

Data

This message contains no data.

19.6.3.6 WM_KEY

Description

Sent to the window currently containing the focus if a key has been pressed.

Data

The `Data.p` pointer of the message points to a `WM_KEY_INFO` structure.

19.6.3.7 WM_MOVE

Description

This message is sent to a window immediately after it has been moved. If the window has any child windows, they will be moved first. Also each child window will receive this message after it has been moved. The message is sent regardless if the window is visible or not.

Data

The `Data.p` pointer of the message points to a `WM_MOVE_INFO` structure.

19.6.3.8 WM_NOTIFY_PARENT

Description

Informs a parent window that something has occurred in one of its child window. These messages are typically sent by widgets to their parent windows to give them a chance to react on the event.

Data

The `Data.v` value of the message contains the notification code of the message. For more information about the notification codes, refer to the appropriate widget.

 © 2020 SEGGER Microcontroller GmbH

19.6.3.9 WM_NOTIFY_VIS_CHANGED

Description

This message is sent to a window if its visibility is changed and the configuration switch WM_SUPPORT_NOTIFY_VIS_CHANGED is set to 1. The visibility of a window changes if

- obstruction changes: The window is partially or totally covered or uncovered by a higher level window (a window which is displayed on top of the window),
- the window is deleted or
- the window changes from not hidden to hidden or reverse.

Typical application

Applications which show a video in a window using a hardware decoder. The hardware decoder can write directly into the display, bypassing emWin, if the window containing the video is completely visible. If the visibility changes, the hardware decoder needs to be reprogrammed.

Example

The following shows a typical reaction on this message:

```
case WM_NOTIFY_VIS_CHANGED:
  if (WM_IsCompletelyVisible(WM_GetClientWindow(pMsg->hWin))) {
    ...
  }
```

The Sample folder of emWin contains the example WM_Video.c which shows how to use the message.

Data

This message contains no data.

19.6.3.10 WM_PAINT

Description

The WM sends this message to a window if it has become invalid (partially or complete) and needs to be drawn. When a window receives a WM_PAINT message, it should repaint itself. Before sending this message to the window, the WM makes sure it is selected. More details about how to react on the WM_PAINT message is described earlier in this chapter under *Callback mechanism, invalidation, rendering and keyboard input* on page 785.

Data

The Data.p pointer of the message points to a GUI_RECT structure containing the invalid rectangle of the window in screen coordinates. This information could be used to optimize the paint function.

19.6.3.11 WM_POST_PAINT

Description

The WM sends this message to a window right after the last WM_PAINT message was processed.

Data

This message contains no data.

 © 2020 SEGGER Microcontroller GmbH

19.6.3.12 WM_PRE_PAINT

Description

The WM sends this message to a window before the first `WM_PAINT` is sent.

Data

This message contains no data.

19.6.3.13 WM_SET_CALLBACK

Description

The WM sends this message to a window after a callback function has been set.

Data

This message contains no data.

19.6.3.14 WM_SET_FOCUS

Description

Sent to a window if it gains or loses the input focus.

Data

If the window gains the input focus, the `Data.v` value is set to 1. If the window 'accepts' the input focus, it should set the `Data.v` value to 0 in reaction on this message.
If the window loses the input focus, the `Data.v` value is set to 0.

19.6.3.15 WM_SET_ID

Description

Sent to a window to change the Id. All emWin widgets handle this message. Application defined windows should handle this message in their callback routine. Otherwise this message will be ignored.

Data

The Data.v value contains the new Id of the window.

19.6.3.16 WM_SIZE

Description

Sent to a window after its size has changed. Gives the window the chance to reposition its child windows (if any).

Data

This message contains no data.

19.6.3.17 WM_TIMER

Description

This message will be sent to a window when a timer created by `WM_CreateTimer()` has expired.

 © 2020 SEGGER Microcontroller GmbH

Data

The Data.v value contains the handle of the expired timer.

19.6.3.18 WM_USER_DATA

Description

Sent to a window immediately after `WM_SetUserData()` has been called.

19.6.4 Pointer input device (PID) messages

These kind of messages are sent by the GUI library in reaction of PID input. Do not send this messages from the user application to a window or a widget.

19.6.4.1 WM_MOTION

Description

A `WM_MOTION` message is sent to a window to achieve advanced motion support. It is sent if a pointer input device is moved over a movable window and to initiate a moving operation. Detailed information about Motion Support can be found in the section *Motion support* on page 910.

Data

The `Data.p` pointer of the message points to a `WM_MOTION_INFO` structure.

19.6.4.2 WM_MOUSEOVER

Description

A `WM_MOUSEOVER` message is sent to a window if a pointer input device touches the outline of a window. It is sent only if mouse support is enabled. This message is not sent to disabled windows.
To enable mouse support, add the following line to the file `GUIConf.h`:

```
#define GUI_SUPPORT_MOUSE 1
```

Data

The `Data.p` pointer of the message points to a `GUI_PID_STATE` structure. The structure member `Pressed` is always set to 0 when receiving a `WM_MOUSEOVER` message.

19.6.4.3 WM_MOUSEOVER_END

Description

A `WM_MOUSEOVER_END` message is sent to a window if the mouse pointer has been moved out of the window. It is sent only if mouse support is enabled. This message is not sent to disabled windows.

Data

The `Data.p` pointer of the message points to a `GUI_PID_STATE` structure. For details about this structure, refer to the message `WM_MOUSEOVER`.

 © 2020 SEGGER Microcontroller GmbH

19.6.4.4 WM_PID_STATE_CHANGED

Description

Sent to the window affected by the pointer input device when the pressed state has changed. The affected window is the visible window at the input position. With other words: If the user releases for example the touch screen over a window, the pressed state changes from 1 (pressed) to 0 (unpressed). In this case a WM_PID_STATE_CHANGED message is sent to the window. This message is sent before the touch message is sent. An invisible window does not receive this message. Transparent windows are handled the same way as visible windows. This message is not sent to disabled windows.

Data

The Data.p pointer of the message points to a WM_PID_STATE_CHANGED_INFO structure.

19.6.4.5 WM_TOUCH

Description

A WM_TOUCH message is sent to a window once the PID

- is pressed.
- is moved in pressed state.
- is released.

Windows receive this message, if one of the actions above happens over the visible area and if they are not disabled.

If a window should not receive touch messages the create flag WM_CF_UNTOUCHABLE can be used. This causes the touch input to be routed to its parent window.

Data

The Data.p pointer of the message points to a GUI_PID_STATE structure. Data.p = NULL means that the PID was moved out of bounds in pressed state.

19.6.4.6 WM_TOUCH_CHILD

Description

This message is sent to the parent window if the outline of a child window has been touched with a pointer input device in pressed or unpressed state. This message is not sent to disabled windows.

Data

The Data.p pointer of the message points to the WM_MESSAGE sent to the child window. Details about the message data can be found under *WM_TOUCH* on page 801. The message has to be dereferenced twice to get access to the GUI_PID_STATE attached to this message.

Example

```
//                        -> WM_TOUCH message          -> GUI_PID_STATE
pState = (GUI_PID_STATE *)((WM_MESSAGE *)pMsg->Data.p)->Data.p;
```

19.6.4.7 Example

The following example explains what happens if a pointer input device is dragged over a dialog with a button:

 © 2020 SEGGER Microcontroller GmbH



Position	Description
1	The pointer input device (PID) is pressed at this position. This causes the WM to send the following WM_PID_STATE_CHANGED message to the window at this position: x = Horizontal position in desktop coordinates. y = Vertical position in desktop coordinates. State = 1 StatePrev = 0 The WM also sends a WM_TOUCH message with the same x and y coordinates to the window: x = Horizontal position in desktop coordinates. y = Vertical position in desktop coordinates. Pressed = 1
2	The PID is dragged to this position. The window below (the button) will receive no WM_PID_STATE_CHANGED message, because the PID remains in pressed state. The WM only sends a WM_TOUCH message to the window: x = Horizontal position in desktop coordinates. y = Vertical position in desktop coordinates. Pressed = 1
3	The PID is released at this position. This causes the WM to send the following WM_PID_STATE_CHANGED message to the window at this position: x = Horizontal position in desktop coordinates. y = Vertical position in desktop coordinates. State = 0 StatePrev = 1 The WM also sends a WM_TOUCH message with the same x and y coordinates to the window: x = Horizontal position in desktop coordinates. y = Vertical position in desktop coordinates. Pressed = 0

19.6.5 System-defined notification codes

A message of this type is sent from a window to its parent window to notify it of a change in the child window. This gives the parent window the chance to react on this event. The message contains a hWinSrc element which is a handle to the widget which caused the message. Detailed information about which notification messages are utilized by a widget can be found in the according Widget description in the chapter *Widgets (window objects)* on page 963.

> **Note**
>
> Do not send system defined notification codes from the user application to a window.

A full list of notification codes can be found under *Notification codes* on page 955.

19.6.6 Application-defined messages

The application program can define additional messages for its own usage. In order to ensure that they custom message Ids do not equal the Ids which are predefined in emWin, user-defined messages start numbering at WM_USER. Defining custom messages is recommended as follows:

```
#define MY_MESSAGE_AAA (WM_USER + 0)
```

 © 2020 SEGGER Microcontroller GmbH

```
#define MY_MESSAGE_BBB (WM_USER + 1)
```

 © 2020 SEGGER Microcontroller GmbH

19.7 Configuration options

Type	Macro	Default	Description
B	WM_SUPPORT_NOTIFY_VIS_CHANGED	0	Enables the WM to send a WM_NOTIFY_VIS_CHANGED message to a window if its visibility is changed.
B	WM_SUPPORT_TRANSPARENCY	1	Enable support for transparent windows. If set to 0 the additional code for transparency support is not included.

19.7.1 WM_SUPPORT_NOTIFY_VIS_CHANGED

Per default emWin does not inform windows if their visibility has changed. If enabled, the WM sends WM_NOTIFY_VIS_CHANGED messages.

19.7.2 WM_SUPPORT_TRANSPARENCY

Per default emWin supports transparent windows. This means per default the additional code used to handle transparent windows is linked if the WM is used. If the application does not use transparent windows the memory requirement of the application can be reduced if WM_SUPPORT_TRANSPARENCY is set to 0.

 © 2020 SEGGER Microcontroller GmbH

19.8 WM API

The following table lists the available routines of the emWin Window Manager API. All functions are listed in alphabetical order within their respective categories. Detailed descriptions of the routines can be found later in the chapter.

Functions

Routine	Description
Basic functions	
WM_Activate()	Activates the Window Manager.
WM_AttachWindow()	Attaches a window to a new parent window.
WM_AttachWindowAt()	Attaches a window to a new parent window at the given position.
WM_BroadcastMessage()	Sends the given message to all existing windows.
WM_BringToBottom()	Places a specified window underneath its siblings.
WM_BringToTop()	Places a specified window on top of its siblings.
WM_ClrHasTrans()	Clears the has transparency flag (sets it to 0).
WM_CreateWindow()	Creates a window.
WM_CreateWindowAsChild()	Creates a window as a child window.
WM_Deactivate()	Deactivates the Window Manager.
WM_DefaultProc()	Default message handler.
WM_DeleteWindow()	Deletes a specified window.
WM_DetachWindow()	Detaches a window from its parent window.
WM_DisableWindow()	Disables the specified window.
WM_EnableWindow()	Sets the specified window to enabled state.
WM_Exec()	Redraws invalid windows by executing callbacks (all jobs).
WM_Exec1()	Redraws one invalid window by executing one callback (one job only).
WM_ForEachDesc()	Iterates over all descendants of the given window.
WM_GetActiveWindow()	Returns handle of the active window.
WM_GetCallback()	Returns a pointer to the callback function of the given window.
WM_GetClientRect()	Returns the coordinates of the client area in the active window in window coordinates.
WM_GetClientRectEx()	Returns the coordinates of the client area of a window in window coordinates.
WM_GetDesktopWindow()	Returns the handle of the desktop window.
WM_GetDesktopWindowEx()	Returns the window handle of the specified desktop window.
WM_GetDialogItem()	Returns the window handle of a dialog box item (widget).
WM_GetFirstChild()	Returns the handle of a specified window’s first child window.
WM_GetFocusedWindow()	Returns the handle of the window with the input focus.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
WM_GetHasTrans()	Returns the current value of the has transparency flag.
WM_GetInvalidRect()	Returns the invalid rectangle of a window in desktop coordinates.
WM_GetModalLayer()	Returns the current modal layer.
WM_GetModalWindow()	Returns the modal window.
WM_GetNextSibling()	Returns the handle of a specified window's next sibling.
WM_GetNumInvalidWindows()	Returns the number of currently invalid windows.
WM_GetOrgX()	Returns the origin in X of the active window.
WM_GetOrgY()	Returns the origin in Y of the active window.
WM_GetParent()	Returns the handle of a specified window's parent window.
WM_GetPrevSibling()	Returns the handle of a specified window's previous sibling.
WM_GetStayOnTop()	Returns the current value of the stay on top flag.
WM_GetUserData()	Retrieves the data set with WM_SetUserData().
WM_GetWindowOrgX()	Returns the origin in X of a window.
WM_GetWindowOrgY()	Returns the origin in Y of a window.
WM_GetWindowRect()	Returns the coordinates of the active window in desktop coordinates.
WM_GetWindowRectEx()	Returns the coordinates of a window in desktop coordinates.
WM_GetWindowSizeX()	Return the X-size of a specified window.
WM_GetWindowSizeY()	Return the Y-size of a specified window.
WM_HasCaptured()	Checks if the given window has captured PID input.
WM_HasFocus()	Checks if the given window has the input focus.
WM_HideWindow()	Makes a specified window invisible.
WM_InvalidateArea()	Invalidates a certain section of the display.
WM_InvalidateRect()	Invalidates a part of a window.
WM_InvalidateWindow()	Invalidates a window.
WM_IsCompletelyCovered()	Checks if the given window is completely covered or not.
WM_IsCompletelyVisible()	Checks if the given window is completely visible or not.
WM_IsEnabled()	This function returns if a window is enabled or not.
WM_IsVisible()	Determines whether or not a specified window is visible.
WM_IsWindow()	Determines whether or not a specified handle is a valid window handle.
WM_MakeModal()	This function makes the window work in 'modal' mode.
WM_MoveChildTo()	Sets the position of a window in window coordinates.
WM_MoveTo()	Sets the position of a window in desktop coordinates.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
WM_MoveWindow()	Moves a window to another position.
WM_NotifyParent()	Sends a WM_NOTIFY_PARENT message to the given window.
WM_Paint()	Draws or redraws a specified window immediately.
WM_PaintWindowAndDescs()	Draws a given window and all descendant windows immediately.
WM_ReleaseCapture()	Releases capturing of mouse- and touch-screen-input.
WM_ResizeWindow()	Changes the size of a specified window by adding (or subtracting) the given differences.
WM_Rect2Screen()	Converts the given rectangle holding coordinates relative to the given window into screen positions.
WM_Rect2Client()	Converts the given rectangle holding coordinates relative to the screen into coordinates relative to the window.
WM_Screen2hWin()	Returns the window which lies at the specified position.
WM_Screen2hWinEx()	Returns the window which lies at the specified position.
WM_SelectWindow()	Selects a window to be used for drawing operations.
WM_SendMessage()	Sends a message to a specified window.
WM_SendMessageNoPara()	Sends a message without parameters to a specified window.
WM_SendToParent()	Sends the given message to the parent window of the given window.
WM_SetCallback()	Sets a callback routine to be executed by the Window Manager.
WM_SetCapture()	Routes all PID-messages to the given window.
WM_SetCaptureMove()	Moves a window according to the given PID state.
WM_SetCreateFlags()	Sets the flags to be used as default when creating a new window.
WM_SetDesktopColor()	Sets the color for the desktop window.
WM_SetDesktopColorEx()	Sets the color for the desktop window in a multi layer environment.
WM_SetEnableState()	Sets the window to an enabled or disabled state.
WM_SetFocus()	Sets the input focus to a specified window.
WM_SetHasTrans()	Enables transparency for the given window.
WM_SetId()	This function sends a WM_SET_ID message to the given window.
WM_SetModalLayer()	Sets the layer to be used as modal layer.
WM_SetpfPollPID()	Sets a function to be called by the WM for polling the PID.
WM_SetSize()	Sets the new size of a window.
WM_SetUntouchable()	This function makes a window 'untouchable'.
WM_SetWindowPos()	Sets the size and the position of a window.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
WM_SetXSize()	Sets the new X-size of a window.
WM_SetYSize()	Sets the new Y-size of a window.
WM_SetStayOnTop()	Sets the stay on top flag.
WM_SetTransState()	This function sets or clears the flags WM_CF_HASTRANS and WM_CF_CONST_OUTLINE of the given window.
WM_SetUserClipRect()	Reduces the clipping area temporarily.
WM_SetUserData()	Sets the extra data of a window.
WM_ShowWindow()	Makes a specified window visible.
WM_Update()	Draws the invalid part of the specified window immediately.
WM_UpdateWindowAndDescs()	Draws the invalid part of a given window and the invalid part of all descendant windows.
WM_ValidateRect()	Validates parts of a window.
WM_ValidateWindow()	Validates a window.
WM_XY2Screen()	Converts window coordinate into screen coordinates.
WM_XY2Client()	Converts screen coordinates into window coordinates.
Motion support	
WM_MOTION_Enable()	Enables motion support for the WM.
WM_MOTION_SetDeceleration()	Sets the deceleration for the current movement.
WM_MOTION_SetDefaultPeriod()	Sets the default period for movements.
WM_MOTION_SetMotion()	Sets speed and deceleration for the desired movement.
WM_MOTION_SetMoveable()	Sets movability flags for the given window.
WM_MOTION_SetMovement()	Sets speed and distance for the desired movement.
WM_MOTION_SetSpeed()	Sets the speed for the desired movement.
WM_MOTION_SetThreshold()	Sets the minimum distance required for starting a move.
ToolTip related functions	
WM_TOOLTIP_AddTool()	Adds a tool to an existing ToolTip object.
WM_TOOLTIP_Create()	Creates a ToolTip object for the given dialog.
WM_TOOLTIP_Delete()	Deletes the given ToolTip object.
WM_TOOLTIP_SetDefaultColor()	Sets the default colors to be used for drawing ToolTips.
WM_TOOLTIP_SetDefaultFont()	Sets the font to be used for displaying the text of ToolTips.
WM_TOOLTIP_SetDefaultPeriod()	Sets the default periods to be used for showing ToolTips.
Multiple Buffering support	
WM_MULTIBUF_Enable()	This functions enables or disables the automatic use of Multiple Buffering by the Window Manager.
Memory Device support (optional)	

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
WM_DisableMemdev()	Disables the use of Memory Devices for redrawing a window.
WM_EnableMemdev()	Enables the use of Memory Devices for redrawing a window.
Timer related	
WM_CreateTimer()	Creates a timer which sends a WM_TIMER message to a window.
WM_DeleteTimer()	Deletes the given timer.
WM_GetTimerId()	Gets the Id of the given timer.
WM_RestartTimer()	Restarts the given timer with the given period.
Widget related functions	
WM_GetClientWindow()	Returns the handle of the client window.
WM_GetId()	Returns the ID of a widget.
WM_GetInsideRect()	Returns the size of the active window less the border.
WM_GetInsideRectEx()	Returns the size of a window less the border.
WM_GetScrollbarH()	Returns the handle of an attached horizontal scroll bar.
WM_GetScrollbarV()	Returns the handle of an attached vertical scroll bar.
WM_GetScrollPosH()	Returns the horizontal scroll position of a window.
WM_GetScrollPosV()	Returns the vertical scroll position of a window.
WM_GetScrollState()	Gets the state of a SCROLLBAR widget.
WM_SetScrollPosH()	Sets the horizontal scrolling position of a window.
WM_SetScrollPosV()	Sets the vertical scrolling position of a window.
WM_SetScrollState()	Sets the state of a specified SCROLLBAR widget.

Data structures

Structure	Description
GUI_PID_STATE	Stores the position of the pointer input device.
TOOLTIP_INFO	Contains the information about a ToolTip.
WM_KEY_INFO	Contains information about a pressed key.
WM_MESSAGE	Contains the data for a message sent by a window.
WM_MOTION_INFO	Contains information about a move with motion support.
WM_MOVE_INFO	Stores the distance of a window move operation.
WM_PID_STATE_CHANGED_INFO	Information about the changed PID state.
WM_SCROLL_STATE	Saves the scrollstate of a scrollbar.

Defines

Group of defines	Description
Message IDs	List of all messages sent by the Window Manager.
Motion flags	Flags for motion support.
Motion messages	Commands sent with a WM_MOTION message.

 © 2020 SEGGER Microcontroller GmbH

Group of defines	Description
Notification codes	List of all notification codes sent with WM_NOTIFY_PARENT.
ToolTip color indexes	Color indexes for ToolTip related routines.
ToolTip period indexes	Period indexes for ToolTip related routines.
Window create flags	Flags that define a window upon creation.

19.8.1 Using the WM API functions

Many of the WM functions have window handles as parameters. Observe the following rules when using handles:

- Window handles can be 0. In this case functions usually return immediately. Functions which do not follow this rule are described accordingly.
- If a window handle is ≠ 0, it should be a valid handle. The WM does not check if the given handle is valid. If an invalid handle is given to a function it fails or may even cause the application to crash.

 © 2020 SEGGER Microcontroller GmbH

19.8.2 Basic functions

19.8.2.1 WM_Activate()

Description

Activates the Window Manager.

Prototype

```
void WM_Activate(void);
```

Additional information

The WM is activated by default after initialization. This function only needs to be called if there has been a previous call of `WM_Deactivate()`.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.2 WM_AttachWindow()

Description

The given window will be detached from its parent window and attached to the new parent window. The new origin in window coordinates of the new parent window will be the same as the old origin in window coordinates of the old parent window.

Prototype

```
void WM_AttachWindow(WM_HWIN hWin,
                     WM_HWIN hParent);
```

Parameters

Parameter	Description
hWin	Window handle.
hWinParent	Window handle of the new parent.

Additional information

If the given window handle is 0 or both handles are the same the function returns immediately.
If only the given parent window handle is 0 the function detaches the given window and returns; the window remains unattached.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.3 WM_AttachWindowAt()

Description

The given window will be detached from its parent window and attached to the new parent window. The given position will be used to set the origin of the window in window coordinates of the parent window.

Prototype

```
void WM_AttachWindowAt(WM_HWIN hWin,
                       WM_HWIN hParent,
                       int     x,
                       int     y);
```

Parameters

Parameter	Description
hWin	Window handle.
hWinParent	Window handle of the new parent.
x	X position of the window in window coordinates of the parent window.
y	Y position of the window in window coordinates of the parent window.

Additional information

If the given window handle is 0 or both handles are the same the function returns immediately.
If only the given parent window handle is 0 the function detaches the given window, moves it to the new position and returns; the window remains unattached.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.4 WM_BringToBottom()

Description

Places a specified window underneath its siblings.

Prototype

```
void WM_BringToBottom(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

The window will be placed underneath all other sibling windows, but will remain in front of its parent.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.5 WM_BringToTop()

Description

Places a specified window on top of its siblings.

Prototype

```
void WM_BringToTop(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

The window will be placed on top of all other sibling windows and its parent.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.6 WM_BroadcastMessage()

Description

Sends the given message to all existing windows.

Prototype

```
int WM_BroadcastMessage(WM_MESSAGE * pMsg);
```

Parameters

Parameter	Description
pMsg	Pointer to the message structure to be sent.

Return value

Returns 0.

Additional information

A window should not delete itself or a parent window in reaction of a broadcasted message.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.7 WM_ClrHasTrans()

Description

Clears the `has transparency` flag (sets it to 0).

Prototype

```
void WM_ClrHasTrans(WM_HWIN hWin);
```

Parameters

Parameter	Description
`hWin`	Window handle.

Additional information

When set, this flag tells the Window Manager that a window contains sections which are not redrawn and will therefore be transparent. The WM then knows that the back- ground needs to be redrawn prior to redrawing the window in order to make sure the transparent sections are restored correctly.
When the flag is cleared with `WM_ClrHasTrans()`, the WM will not automatically redraw the background before redrawing the window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.8 WM_CreateWindow()

Description

Creates a window of a specified size at a specified location.

Prototype

```
WM_HWIN WM_CreateWindow(int           x0,
                        int           y0,
                        int           width,
                        int           height,
                        U32           Style,
                        WM_CALLBACK * cb,
                        int           NumExtraBytes);
```

Parameters

Parameter	Description
x0	Upper left X-position in desktop coordinates.
y0	Upper left Y-position in desktop coordinates.
width	X-size of window.
height	Y-size of window.
Style	Window create flags which are OR-combinable. See a full list under *Window create flags* on page 958.
cb	Pointer to callback routine, or NULL if no callback used.
NumExtraBytes	Number of extra bytes to be allocated, normally 0.

Return value

Handle to the created window.

Additional information

Several create flags can be combined by using the OR operator. Negative-position coordinates may be used.

Examples

Creates a window with callback:

```
hWin2 = WM_CreateWindow(100, 10, 180, 100, WM_CF_SHOW, &_cbWin, 0);
```

Creates a window without callback:

```
hWin2 = WM_CreateWindow(100, 10, 180, 100,WM_CF_SHOW, NULL, 0);
```

 © 2020 SEGGER Microcontroller GmbH

19.8.2.9 WM_CreateWindowAsChild()

Description

Creates a window as a child window.

Prototype

```
WM_HWIN WM_CreateWindowAsChild(int           x0,
                               int           y0,
                               int           width,
                               int           height,
                               WM_HWIN       hParent,
                               U32           Style,
                               WM_CALLBACK * cb,
                               int           NumExtraBytes);
```

Parameters

Parameter	Description
x0	Upper left X-position in window coordinates of the parent window.
y0	Upper left Y-position in window coordinates of the parent window.
width	X-size of window. If 0, X-size of client area of parent window.
height	Y-size of window. If 0, Y-size of client area of parent window.
hWinParent	Handle of parent window.
Style	Window create flags (see *Window create flags* on page 958).
cb	Pointer to callback routine, or NULL if no callback used.
NumExtraBytes	Number of extra bytes to be allocated, normally 0.

Return value

Handle to the created window.

Additional information

If the hWinParent parameter is set to 0, the background window is used as parent. A child window is placed on top of its parent and any previous siblings by default, so that if their Z-positions are not changed, the “youngest” window will always be topmost.
The Z-positions of siblings may be changed, although they will always remain on top of their parent regardless of their order.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.10 WM_Deactivate()

Description

Deactivates the Window Manager.

Prototype

```
void WM_Deactivate(void);
```

Additional information

After calling this function, the clip area is set to the complete LCD area and the WM will not execute window callback functions.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.11 WM_DefaultProc()

Description

Default message handler.

Prototype

```
void WM_DefaultProc(WM_MESSAGE * pMsg);
```

Parameters

Parameter	Description
pMsg	Pointer to message.

Additional information

Use this function to handle unprocessed messages as in the following example:

```
static WM_RESULT cbBackgroundWin(WM_MESSAGE * pMsg) {
  switch (pMsg->MsgId) {
  case WM_PAINT:
    GUI_Clear();
    break;
  default:
    WM_DefaultProc(pMsg);
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

19.8.2.12 WM_DeleteWindow()

Description

Deletes a specified window.

Prototype

```
void WM_DeleteWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

Before the window is deleted, it receives a WM_DELETE message. This message is typically used to delete any objects (widgets) it uses and to free memory dynamically allocated by the window.
If the specified window has any existing child windows, these are automatically deleted before the window itself is deleted. Child windows therefore do not need to be separately deleted.
Before the window will be deleted it sends a WM_NOTIFICATION_CHILD_DELETED message to its parent window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.13 WM_DetachWindow()

Description

Detaches a window from its parent window. Detached windows will not be redrawn by the Window Manager.

Prototype

```
void WM_DetachWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.14 WM_DisableWindow()

Description

Disables the specified window. The WM does not pass user input messages (touch, mouse, joystick, …) to a disabled window.

Prototype

```
void WM_DisableWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

A widget that is disabled will typically appear gray, and will not accept input from the user. However, the actual appearance may vary (depends on widget/configuration settings, etc.). A disabled window will not receive the following messages: WM_TOUCH, WM_TOUCH_CHILD, WM_PID_STATE_CHANGED and WM_MOUSEOVER.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.15 WM_EnableWindow()

Description

Sets the specified window to enabled state. An enabled window receives pointer input device (PID) messages (touch, mouse, joystick, …) from the WM.

Prototype

```
void WM_EnableWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hObj	Handle of window.

Additional information

This is the default setting for any widget.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.16 WM_Exec()

Description

This function takes care of handling window related input and redrawing of invalid windows.

Prototype

```
int WM_Exec(void);
```

Return value

0	if there were no jobs performed (or only one window has been drawn).
1	if a job was performed.

Additional information

This function keeps the WindowManager 'alive'. `WM_Exec()` gets also called by `GUI_Exec()`. A return value of 0 does not necessarily mean that nothing has been done by the Window Manager. If only one window is invalid and no input has to be processed, `WM_Exec()` will return 0 as well.
To check if something has been done, albeit `WM_Exec()` returns zero, the function `WM_GetNumInvalidWindows()` can be used.

```
r = WM_GetNumInvalidWindows();
r |= WM_Exec();
if (r) {
  // Something has been done
}
```

In general this function does not need to be called by the user application and it is recommended to call `GUI_Exec()` instead. Therefore, it is also called by `GUI_Delay()`, which is recommended in a multitasking environment.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.17 WM_Exec1()

Description

This function handles one job. This means, handling either one touch input or one paint event.

Prototype

```
int WM_Exec1(void);
```

Return value

0	if there were no jobs performed.
1	if a job was performed.

Additional information

This routine may be called repeatedly until 0 is returned, which means all jobs have been completed.
It is recommended to call the function `GUI_Exec1()` instead.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.18 WM_ForEachDesc()

Description

Iterates over all descendants of the given window. A descendant of a window is a child window or a grand child window or a child of a grand child and so on.

Prototype

```
void WM_ForEachDesc(WM_HWIN        hWin,
                    WM_tfForEach * pcb,
                    void         * pData);
```

Parameters

Parameter	Description
hWin	Window handle.
pcb	Pointer to callback function to be called by WM_ForEachDesc.
pData	User data to be passed to the callback function.

Additional information

This function calls the callback function given by the pointer pcb for each descendant of the given window. The parameter pData will be passed to the user function and can be used to point to user defined data.

Prototype of callback function

```
void CallbackFunction(WM_HWIN hWin,
                      void  * pData);
```

Example

The following example shows how the function can be used. It creates 3 windows, the first as a child window of the desktop, the second as a child window of the first window and the third as a child window of the second window. After creating the window it uses WM_ForEachDesc() to move each window within its parent window:

```
static void _cbWin(WM_MESSAGE * pMsg) {
  GUI_COLOR Color;
  switch (pMsg->MsgId) {
  case WM_PAINT:
    WM_GetUserData(pMsg->hWin, &Color, 4);
    GUI_SetBkColor(Color);
    GUI_Clear();
    break;
  default:
    WM_DefaultProc(pMsg);
  }
}
static void _cbDoSomething(WM_HWIN hWin, void * p) {
  int Value = *(int *)p;
  WM_MoveWindow(hWin, Value, Value);
}
void MainTask(void) {
  WM_HWIN hWin_1, hWin_2, hWin_3;
  int Value = 10;
  GUI_COLOR aColor[] = {GUI_RED, GUI_GREEN, GUI_BLUE};
  GUI_Init();
  WM_SetDesktopColor(GUI_BLACK);
  hWin_1 = WM_CreateWindow( 10, 10, 100, 100, WM_CF_SHOW, _cbWin, 4);
  hWin_2 = WM_CreateWindowAsChild(10, 10, 80, 80, hWin_1, WM_CF_SHOW, _cbWin, 4);
  hWin_3 = WM_CreateWindowAsChild(10, 10, 60, 60, hWin_2, WM_CF_SHOW, _cbWin, 4);
  WM_SetUserData(hWin_1, &aColor[0], 4);
```

 © 2020 SEGGER Microcontroller GmbH

```
  WM_SetUserData(hWin_2, &aColor[1], 4);
  WM_SetUserData(hWin_3, &aColor[2], 4);
  while(1) {
    WM_ForEachDesc(WM_HBKWIN, _cbDoSomething, (void *)&Value);
    Value *= -1;
    GUI_Delay(500);
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

19.8.2.19 WM_GetActiveWindow()

Description

Returns the handle of the active window used for drawing operations.

Prototype

```
WM_HWIN WM_GetActiveWindow(void);
```

Return value

The handle of the active window.

Additional information

This function should be used only when the message WM_PAINT is processed in a window callback function.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.20 WM_GetCallback()

Description

Returns a pointer to the callback function of the given window.

Prototype

```
WM_CALLBACK *WM_GetCallback(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

Pointer of type WM_CALLBACK which points to the callback function of the given window. If the window has no callback function, NULL is returned.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.21 WM_GetClientRect()

Description

Returns the coordinates of the client area in the active window in window coordinates. That means x0 and y0 of the GUI_RECT structure will be 0, x1 and y1 corresponds to the size - 1.

Prototype

```
void WM_GetClientRect(GUI_RECT * pRect);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.22 WM_GetClientRectEx()

Description

Returns the coordinates of the client area of a window in window coordinates. That means x0 and y0 of the GUI_RECT structure will be 0, x1 and y1 corresponds to the size - 1.

Prototype

```
void WM_GetClientRectEx(WM_HWIN    hWin,
                        GUI_RECT * pRect);
```

Parameters

Parameter	Description
hWin	Window handle.
pRect	Pointer to a GUI_RECT structure.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.23 WM_GetDesktopWindow()

Description

Returns the handle of the desktop window.

Prototype

```
WM_HWIN WM_GetDesktopWindow(void);
```

Return value

The handle of the desktop window.

Additional information

The desktop window is always the bottommost window and any further created windows are its descendants.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.24 WM_GetDesktopWindowEx()

Description

Returns the handle of the specified desktop window when working in a multi layer environment.

Prototype

```
WM_HWIN WM_GetDesktopWindowEx(unsigned int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Index of layer.

Return value

The handle of the specified desktop window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.25 WM_GetDialogItem()

Description

Returns the window handle of a dialog box item (widget).

Prototype

```
WM_HWIN WM_GetDialogItem(WM_HWIN hWin,
                         int     Id);
```

Parameters

Parameter	Description
hDialog	Handle of dialog box.
Id	Window Id of the widget.

Return value

The window handle of the widget.

Additional information

This function is always used when creating dialog boxes, since the window Id of a widget used in a dialog must be converted to its handle before it can be used.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.26 WM_GetFirstChild()

Description

Returns the handle of a specified window’s first child window.

Prototype

```
WM_HWIN WM_GetFirstChild(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

Handle of the window’s first child window; 0 if no child window exists.

Additional information

A window’s first child window is the first child created to that particular parent. If the Z-positions of the windows have not been changed, it will be the window directly on top of the specified parent.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.27 WM_GetFocusedWindow()

Description

Returns the handle of the window with the input focus.

Prototype

```
WM_HWIN WM_GetFocusedWindow(void);
```

Return value

Handle of the window with the input focus or 0 if no window has the input focus.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.28 WM_GetHasTrans()

Description

Returns the current value of the has transparency flag.

Prototype

```
int WM_GetHasTrans(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

0 no transparency
1 window has transparency

Additional information

When set, this flag tells the Window Manager that a window contains sections which are not redrawn and will therefore be transparent. The WM then knows that the background needs to be redrawn prior to redrawing the window in order to make sure the transparent sections are restored correctly.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.29 WM_GetInvalidRect()

Description

Returns the invalid rectangle of a window in desktop coordinates.

Prototype

```
int WM_GetInvalidRect(WM_HWIN    hWin,
                      GUI_RECT * pRect);
```

Parameters

Parameter	Description
hWin	Window handle.
pRect	Pointer to a GUI_RECT-structure for storing the invalid rectangle.

Return value

0 if nothing is invalid.
1 otherwise.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.30 WM_GetModalLayer()

Description

Returns the current modal layer. Per default there does not exist a modal layer. In that case the function returns -1.

Prototype

```
int WM_GetModalLayer(void);
```

Return value

≥ 0	Index of current modal layer.
= -1	No modal layer is used.

Additional information

Additional information can be found in the description of `WM_SetModalLayer()`.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.31 WM_GetModalWindow()

Description

Returns the modal window.

Prototype

```
WM_HWIN WM_GetModalWindow(void);
```

Return value

= 0	If there is no modal window.
≠ 0	Handle of the modal window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.32 WM_GetNextSibling()

Description

Returns the handle of a specified window’s next sibling.

Prototype

```
WM_HWIN WM_GetNextSibling(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

Handle of the window’s next sibling.
0 if none exists.

Additional information

A window’s next sibling is the next child window that was created relative to the same parent. If the Z-positions of the windows have not been changed, it will be the window directly on top of the one specified.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.33 WM_GetNumInvalidWindows()

Description

Returns the number of currently invalid windows.

Prototype

```
int WM_GetNumInvalidWindows(void);
```

Return value

Number of invalid windows.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.34 WM_GetOrgX()

19.8.2.35 WM_GetOrgY()

Description

Returns the X- or Y-position (respectively) of the origin of the active window in desktop coordinates.

Prototypes

```
int WM_GetOrgX(void);

int WM_GetOrgY(void);
```

Return value

X- or Y-position of the origin of the active window in desktop coordinates.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.36 WM_GetParent()

Description

Returns the handle of a specified window’s parent window.

Prototype

```
WM_HWIN WM_GetParent(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

Handle of the window’s parent window.
0 if none exists.

Additional information

The only case in which no parent window exists is if the handle of the desktop window is used as parameter.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.37 WM_GetPrevSibling()

Description

Returns the handle of a specified window’s previous sibling.

Prototype

```
WM_HWIN WM_GetPrevSibling(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

Handle of the window’s previous sibling.
0 if none exists.

Additional information

A window’s previous sibling is the previous child window that was created relative to the same parent. If the Z-positions of the windows have not been changed, it will be the window directly below of the one specified.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.38 WM_GetStayOnTop()

Description

Returns the current value of the stay on top flag.

Prototype

```
int WM_GetStayOnTop(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

0 stay on top flag not set
1 stay on top flag set

 © 2020 SEGGER Microcontroller GmbH

19.8.2.39 WM_GetUserData()

Description

Retrieves the data set with `WM_SetUserData()`.

Prototype

```
int WM_GetUserData(WM_HWIN   hWin,
                   void    * pDest,
                   int       NumBytes);
```

Parameters

Parameter	Description
`hWin`	Window handle.
`pDest`	Pointer to buffer.
`SizeOfBuffer`	Size of buffer.

Return value

Number of bytes retrieved.

Additional information

The maximum number of bytes returned by this function is the number of ExtraBytes specified when creating the window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.40 WM_GetWindowOrgX()

19.8.2.41 WM_GetWindowOrgY()

Description

Returns the X- or Y-position (respectively) of the origin of the specified window in desktop coordinates.

Prototypes

```
int WM_GetWindowOrgX(WM_HWIN hWin);

int WM_GetWindowOrgY(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

X- or Y-position of the client area in pixels.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.42 WM_GetWindowRect()

Description

Returns the coordinates of the active window in desktop coordinates.

Prototype

```
void WM_GetWindowRect(GUI_RECT * pRect);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.43 WM_GetWindowRectEx()

Description

Returns the coordinates of a window in desktop coordinates.

Prototype

```
void WM_GetWindowRectEx(WM_HWIN    hWin,
                        GUI_RECT * pRect);
```

Parameters

Parameter	Description
hWin	Window handle.
pRect	Pointer to a GUI_RECT structure.

Additional information

If the given window handle is 0 or the given pointer to the GUI_RECT structure is NULL the function returns immediately.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.44 WM_GetWindowSizeX()

19.8.2.45 WM_GetWindowSizeY()

Description

Return the X- or Y-size (respectively) of a specified window.

Prototypes

```
int WM_GetWindowSizeX(WM_HWIN hWin);

int WM_GetWindowSizeY(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

X- or Y-size of the window in pixels.
Defined as x1-x0+1 in horizontal direction, y1-y0+1 in vertical direction, where x0, x1, y0, y1 are the leftmost/rightmost/topmost/bottommost positions of the window. If the given window handle is 0 the function returns the size of the desktop window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.46 WM_HasCaptured()

Description

Checks if the given window has captured PID input.

Prototype

```
int WM_HasCaptured(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

1 if the given window has captured mouse- and touchscreen-input.
0 if not.

Additional information

If the given window handle is invalid or 0 the function returns a wrong result.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.47 WM_HasFocus()

Description

Checks if the given window has the input focus.

Prototype

```
int WM_HasFocus(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

1 if the given window has the input focus.
0 if not.

Additional information

If the given window handle is invalid or 0 the function returns a wrong result.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.48 WM_HideWindow()

Description

Makes a specified window invisible.

Prototype

```
void WM_HideWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

The window will not immediately appear "invisible" after calling this function. The invalid areas of other windows (areas which appear to lie "behind" the window which should be hidden) will be redrawn when executing `WM_Exec()`. If you need to hide (draw over) a window immediately, you should call `WM_Paint()` to redraw the other windows.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.49 WM_InvalidateArea()

Description

Invalidates a specified, rectangular area of the display.

Prototype

```
void WM_InvalidateArea(const GUI_RECT * pRect);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure with desktop coordinates.

Additional information

Calling this function will tell the WM that the specified area is not updated.
This function can be used to invalidate any windows or parts of windows that overlap or intersect the area. The coordinates of the GUI_RECT structure have to be in desktop coordinates.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.50 WM_InvalidateRect()

Description

Invalidates a specified, rectangular area of a window.

Prototype

```
void WM_InvalidateRect(      WM_HWIN    hWin,
                       const GUI_RECT * pRect);
```

Parameters

Parameter	Description
hWin	Window handle.
pRect	Pointer to a GUI_RECT structure with window coordinates of the parent window.

Additional information

Calling this function will tell the WM that the specified area is not updated.
The next time the Window Manager is executed so the window is redrawn, the area will be redrawn as well. The GUI_RECT structure has to be filled with window coordinates.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.51 WM_InvalidateWindow()

Description

Invalidates a specified window.

Prototype

```
void WM_InvalidateWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

Calling this function tells the WM that the specified window is not updated.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.52 WM_IsCompletelyCovered()

Description

Checks if the given window is completely covered or not.

Prototype

```
char WM_IsCompletelyCovered(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

1 if the given window is completely covered.
0 if not.

Additional information

If the given window handle is invalid or 0 the function returns a wrong result.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.53 WM_IsCompletelyVisible()

Description

Checks if the given window is completely visible or not.

Prototype

```
char WM_IsCompletelyVisible(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

1 if the given window is completely visible.
0 if not.

Additional information

If the given window handle is invalid or 0 the function returns a wrong result.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.54 WM_IsEnabled()

Description

This function returns if a window is enabled or not.

Prototype

```
int WM_IsEnabled(WM_HWIN hObj);
```

Parameters

Parameter	Description
hObj	Window handle.

Return value

1 if the window is enabled.
0 if not.

Additional information

A widget that is disabled will typically appear gray, and will not accept input from the user. However, the actual appearance may vary (depends on widget/configuration settings, etc.)

 © 2020 SEGGER Microcontroller GmbH

19.8.2.55 WM_IsVisible()

Description

Determines whether or not a specified window is visible.

Prototype

```
int WM_IsVisible(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

0 if the window is not visible.
1 if the window is visible.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.56 WM_IsWindow()

Description

Determines whether or not a specified handle is a valid window handle.

Prototype

```
int WM_IsWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

0 handle is not a valid window handle.
1 handle is a valid window handle.

Additional information

This function should be used only if absolutely necessary. The more windows exist the more time will be used to evaluate, if the given handle is a window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.57 WM_MakeModal()

Description

This function makes the window work in ’modal’ mode. This means pointer device input will only be sent to the ’modal’ window or a child window of it if the input position is within the rectangle of the modal window.

Prototype

```
void WM_MakeModal(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle. 0 removes the modal state from the current modal window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.58 WM_MoveChildTo()

Description

Moves a specified window to a certain position.

Prototype

```
void WM_MoveChildTo(WM_HWIN hWin,
                    int     x,
                    int     y);
```

Parameters

Parameter	Description
hWin	Window handle.
x	New X-position in window coordinates of the parent window.
y	New Y-position in window coordinates of the parent window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.59 WM_MoveTo()

Description

Moves a specified window to a certain position.

Prototype

```
void WM_MoveTo(WM_HWIN hWin,
               int     x,
               int     y);
```

Parameters

Parameter	Description
hWin	Window handle.
x	New X-position in desktop coordinates.
y	New Y-position in desktop coordinates.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.60 WM_MoveWindow()

Description

Moves a specified window by a certain distance.

Prototype

```
void WM_MoveWindow(WM_HWIN hWin,
                   int     dx,
                   int     dy);
```

Parameters

Parameter	Description
hWin	Window handle.
dx	Horizontal distance to move.
dy	Vertical distance to move.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.61 WM_NotifyParent()

Description

Sends a WM_NOTIFY_PARENT message to the given window.

Prototype

```
void WM_NotifyParent(WM_HWIN hWin,
                     int     Notification);
```

Parameters

Parameter	Description
hWin	Window handle.
Notification	Value to send to the parent window.

Additional information

The Notification parameter will be sent in the Data.v element of the message. The macro WM_NOTIFICATION_USER can be used for defining application defined messages:

```
#define NOTIFICATION_1 (WM_NOTIFICATION_USER + 0)
#define NOTIFICATION_2 (WM_NOTIFICATION_USER + 1)
```

 © 2020 SEGGER Microcontroller GmbH

19.8.2.62 WM_Paint()

Description

Draws or redraws a specified window immediately.

Prototype

```
void WM_Paint(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

The window is redrawn reflecting all updates made since the last time it was drawn.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.63 WM_PaintWindowAndDescs()

Description

Paints the given window and all its descendants.

Prototype

```
void WM_PaintWindowAndDescs(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

The function draws the complete window regions by invalidating them before drawing.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.64 WM_Rect2Client()

Description

Converts the given rectangle holding coordinates relative to the screen into coordinates relative to the window.

Prototype

```
void WM_Rect2Client(WM_HWIN    hWin,
                    GUI_RECT * pRect);
```

Parameters

Parameter	Description
hWin	Window handle.
pRect	Pointer to a rectangle with coordinates relative to the screen.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.65 WM_Rect2Screen()

Description

Converts the given rectangle holding coordinates relative to the given window into screen positions.

Prototype

```
void WM_Rect2Screen(WM_HWIN    hWin,
                    GUI_RECT * pRect);
```

Parameters

Parameter	Description
hWin	Window handle.
pRect	Pointer to a rectangle with coordinates relative to the window.

Additional information

This function is useful when using Memory Devices in combination with windows/widgets, because Memory Device use coordinates relative to the screen.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.66 WM_ReleaseCapture()

Description

Releases capturing of mouse- and touchscreen-input.

Prototype

```
void WM_ReleaseCapture(void);
```

Additional information

Use `WM_SetCapture()` to send all mouse- and touchscreen-input to a specific window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.67 WM_ResizeWindow()

Description

Changes the size of a specified window by adding (or subtracting) the given differences.

Prototype

```
void WM_ResizeWindow(WM_HWIN hWin,
                     int     dx,
                     int     dy);
```

Parameters

Parameter	Description
hWin	Window handle.
dx	Difference in X.
dy	Difference in Y.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.68 WM_Screen2hWin()

Description

Returns the window which lies at the specified position.

Prototype

```
WM_HWIN WM_Screen2hWin(int x,
                       int y);
```

Parameters

Parameter	Description
x	X-coordinate
y	Y-coordinate

Return value

Handle to the found window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.69 WM_Screen2hWinEx()

Description

Returns the window which lies at the specified position.

Prototype

```
WM_HWIN WM_Screen2hWinEx(WM_HWIN hStop,
                         int     x,
                         int     y);
```

Parameters

Parameter	Description
hStop	Handle of a descendant (low-level window) to stop at.
x	X-coordinate
y	Y-coordinate

Return value

Handle to the found window. If hStop was found the handle to its parent window is returned.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.70 WM_SelectWindow()

Description

Selects a window to be used for drawing operations. The selected window is also called the active window.

Prototype

```
WM_HWIN WM_SelectWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

The previously selected window.

Additional information

If using this function it is possible to paint into a window from outside of the Window Manager, in general this is not recommended. Further you will not benefit from the automatic multi buffering and memory device feature of the Window Manager. Use this function very rarely and only as a last choice.
This function should not be called within a paint function called by the Window Manager. If the Window Manager sends a WM_PAINT message the target window already has been selected.
When working with a multi layer configuration the function switches also to the layer of the top level parent window of the given window.
If the given window handle is 0 the function selects the first created window, normally the first desktop window.

Example

Sets a window with handle hWin2 to the active window, sets the background color, and then clears the window:

```
WM_SelectWindow(hWin2);
GUI_SetBkColor(0xFF00);
GUI_Clear();
```

 © 2020 SEGGER Microcontroller GmbH

19.8.2.71 WM_SendMessage()

Description

Sends a message to a specified window.

Prototype

```
void WM_SendMessage(WM_HWIN      hWin,
                    WM_MESSAGE * pMsg);
```

Parameters

Parameter	Description
hWin	Window handle.
pMsg	Pointer to a WM_MESSAGE structure. See *Elements of structure WM_MESSAGE*.

Additional information

This function can be also used to send custom messages as described in the section *Application-defined messages* on page 802.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.72 WM_SendMessageNoPara()

Description

Sends a message without parameters to a specified window.

Prototype

```
void WM_SendMessageNoPara(WM_HWIN hWin,
                          int     MsgId);
```

Parameters

Parameter	Description
hWin	Window handle.
MsgId	Id of message to be sent.

Additional information

If only a message Id should be sent to a window this should be done with this function, because it does not need a pointer to a WM_MESSAGE structure. Note that the receiving window gets no further information except the message Id.
This function can be used to send application-defined messages. Refer to the chapter *Application-defined messages* on page 802.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.73 WM_SendToParent()

Description

Sends the given message to the parent window of the given window.

Prototype

```
void WM_SendToParent(WM_HWIN      hChild,
                     WM_MESSAGE * pMsg);
```

Parameters

Parameter	Description
hWin	Window handle.
pMsg	Pointer to WM_MESSAGE-structure.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.74 WM_SetCallback()

Description

Sets a callback routine to be executed by the Window Manager.

Prototype

```
WM_CALLBACK *WM_SetCallback(WM_HWIN       hWin,
                            WM_CALLBACK * cb);
```

Parameters

Parameter	Description
hWin	Window handle.
cb	Pointer to callback routine.

Return value

Pointer to the previous callback routine.

Additional information

The given window will be invalidated. This makes sure the window will be redrawn.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.75 WM_SetCapture()

Description

Routes all PID-messages to the given window.

Prototype

```
void WM_SetCapture(WM_HWIN hObj,
                   int     AutoRelease);
```

Parameters

Parameter	Description
hWin	Window handle.
AutoRelease	1 if capturing should end when the user releases the touch.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.76 WM_SetCaptureMove()

Description

Moves a window according to the given PID state. This function is intended to be used in a window callback function. It should react to the message WM_TOUCH if the PID is in pressed state.

Prototype

```
void WM_SetCaptureMove(      WM_HWIN         hWin,
                       const GUI_PID_STATE * pState,
                             int             MinVisibility,
                             int             LimitTop);
```

Parameters

Parameter	Description
hWin	Handle of the window which should be moved.
pState	Pointer to the PID state.
MinVisibility	Defines the minimum visibility of the parent window in pixels. The window will not be moved farther than the parent window reduced by the minimum visibility.
LimitTop	Defines a number of top pixel lines which can not be moved outside the parent rectangle. The bottom pixel lines which are excluded are allowed to be moved outside the parent rectangle.

Example

The following example application shows a callback function of a window which is moved using WM_SetCaptureMove():

```
static void _cbWin(WM_MESSAGE * pMsg) {
  const GUI_PID_STATE * pState;
  WM_HWIN hWin;
  hWin = pMsg->hWin;
  switch (pMsg->MsgId) {
  case WM_TOUCH:
    pState = (const GUI_PID_STATE *)pMsg->Data.p;
    if (pState) {
      if (pState->Pressed) {
        WM_SetCaptureMove(hWin, pState, 0, 0);
      }
    }
    break;
  case WM_PAINT:
    GUI_SetBkColor(GUI_DARKBLUE);
    GUI_Clear();
    break;
  default:
    WM_DefaultProc(pMsg);
  }
}
void MainTask(void) {
  WM_HWIN hWin;

  GUI_Init();
  WM_SetDesktopColor(GUI_DARKGREEN);
  hWin = WM_CreateWindow(10, 10, 200, 100, WM_CF_SHOW, _cbWin, 0);
  while (1) { GUI_Delay(1); }
}
```

 © 2020 SEGGER Microcontroller GmbH

19.8.2.77 WM_SetCreateFlags()

Description

Sets the flags to be used as default when creating a new window.

Prototype

```
U32 WM_SetCreateFlags(U32 Flags);
```

Parameters

Parameter	Description
Flags	Window create flags (see *Window create flags* on page 958).

Return value

Former value of this parameter.

Additional information

The flags specified here are binary ORed with the flags specified in the `WM_CreateWindow()` and `WM_CreateWindowAsChild()` routines.
The flag `WM_CF_MEMDEV` is frequently used to enable Memory Devices on all windows. Setting create flags is permitted before `GUI_Init()` is called. This causes the background window to be also affected by the create flags.

Example

```
WM_SetCreateFlags(WM_CF_MEMDEV);  // Auto. use Memory Devices on all windows
```

 © 2020 SEGGER Microcontroller GmbH

19.8.2.78 WM_SetDesktopColor()

Description

Sets the color for the desktop window.

Prototype

```
GUI_COLOR WM_SetDesktopColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color for desktop window, 24-bit RGB value.

Return value

The previously selected desktop window color.

Additional information

The default setting for the desktop window is not to repaint itself. If this function is not called, the desktop window will not be redrawn at all; therefore other windows will remain visible even after they are deleted.
Once a color is specified with this function, the desktop window will repaint itself. In order to restore the default, call this function and specify GUI_INVALID_COLOR.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.79 WM_SetDesktopColorEx()

Description

Sets the color for the desktop window in a multi layer environment.

Prototype

```
GUI_COLOR WM_SetDesktopColorEx(GUI_COLOR    Color,
                               unsigned int LayerIndex);
```

Parameters

Parameter	Description
Color	Color for desktop window, 24-bit RGB value.
LayerIndex	Index of the layer.

Return value

The previously selected desktop window color.

Additional information

See WM_SetDesktopColor().

 © 2020 SEGGER Microcontroller GmbH

19.8.2.80 WM_SetEnableState()

Description

Sets the window to an enabled or disabled state.

Prototype

```
void WM_SetEnableState(WM_HWIN hWin,
                       int     State);
```

Parameters

Parameter	Description
hWin	Window handle.
State	1 to enable window, 0 to disable window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.81 WM_SetFocus()

Description

Sets the input focus to a specified window.

Prototype

```
int WM_SetFocus(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

= 0 if window accepted focus.
≠ 0 if it could not.

Additional information

The window receives a WM_SET_FOCUS message which gives it the input focus. If for some reason the window could not accept the focus, nothing happens.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.82 WM_SetHasTrans()

Description

Enables transparency for the given window.

Prototype

```
void WM_SetHasTrans(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

Using this function causes the Window Manager to redraw the background of the given window in order to have the transparent parts updated before the actual window is drawn.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.83 WM_SetId()

Description

This function sends a WM_SET_ID message to the given window.

Prototype

```
void WM_SetId(WM_HWIN hObj,
              int     Id);
```

Parameters

Parameter	Description
hObj	Window handle.
Id	Id to be sent to the window.

Additional information

This function can be used to change the Id of a widget. It works with every widget. When using this function with an application defined window, the callback function of the window should handle the message. Otherwise it will be ignored.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.84 WM_SetModalLayer()

Description

emWin supports one modal window on each layer per default. But sometimes it could make sense to have only one modal window. To be able to achieve that function could be used. Once a modal layer has been set only windows of that layer will receive input.

Prototype

```
int WM_SetModalLayer(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer to be set as modal layer, -1 means no modal layer

Return value

≥ 0	Index of previous modal layer.
= -1	No modal layer was used previously.
= -2	Error.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.85 WM_SetpfPollPID()

Description

Sets a function which will be called by the Window Manager in order to poll the pointer input device (touch-screen or mouse).

Prototype

```
WM_tfPollPID *WM_SetpfPollPID(WM_tfPollPID * pf);
```

Parameters

Parameter	Description
pf	Pointer to a function of type WM_tfPollPID.

Return value

≥ 0	Index of previous modal layer.
= -1	No modal layer was used previously.
= -2	Error.

Additional information

The function type is defined as follows:

```
typedef void WM_tfPollPID(void);
```

Example

Example of a touch-screen handled as a device:

```
void ReadTouch(void) {
  // ...read touchscreen
}
WM_SetpfPollPID(ReadTouch);
```

 © 2020 SEGGER Microcontroller GmbH

19.8.2.86 WM_SetSize()

Description

Sets the new size of a window.

Prototype

```
void WM_SetSize(WM_HWIN hWin,
                int     xSize,
                int     ySize);
```

Parameters

Parameter	Description
hWin	Window handle.
XSize	New size in X.
YSize	New size in Y.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.87 WM_SetUntouchable()

Description

This function makes a window 'untouchable'. It has the same effect than the create flag WM_CF_UNTOUCHABLE.

Prototype

```
int WM_SetUntouchable(WM_HWIN hWin,
                      int     OnOff);
```

Parameters

Parameter	Description
hWin	Window handle.
OnOff	Enables (1) or disables (0) touch for a specific window.

Additional information

Calling this function will cause a window to route touch input to its parent. This way it is possible to place window over another window, but the lower window will still receive touch input.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.88 WM_SetWindowPos()

Description

Sets the size and the position of a window.

Prototype

```
void WM_SetWindowPos(WM_HWIN hWin,
                     int     xPos,
                     int     yPos,
                     int     xSize,
                     int     ySize);
```

Parameters

Parameter	Description
hWin	Window handle.
xPos	New position in X in desktop coordinates.
yPos	New position in Y in desktop coordinates.
xSize	New size in X.
ySize	New size in Y.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.89 WM_SetXSize()

Description

Sets the new X-size of a window.

Prototype

```
int WM_SetXSize(WM_HWIN hWin,
                int     XSize);
```

Parameters

Parameter	Description
hWin	Window handle.
XSize	New size in X.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.90 WM_SetYSize()

Description

Sets the new Y-size of a window.

Prototype

```
int WM_SetYSize(WM_HWIN hWin,
                int     YSize);
```

Parameters

Parameter	Description
hWin	Window handle.
YSize	New size in Y.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.91 WM_SetStayOnTop()

Description

Sets the stay on top flag.

Prototype

```
void WM_SetStayOnTop(WM_HWIN hWin,
                     int     OnOff);
```

Parameters

Parameter	Description
hWin	Window handle.
OnOff	See table below.

Permitted values for parameter OnOff	
0	Stay on top flag would be cleared.
1	Stay on top flag would be set.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.92 WM_SetTransState()

Description

This function sets or clears the flags WM_CF_HASTRANS and WM_CF_CONST_OUTLINE of the given window.

Prototype

```
void WM_SetTransState(WM_HWIN  hWin,
                      unsigned State);
```

Parameters

Parameter	Description
hWin	Window handle.
State	Combination of the flags WM_CF_HASTRANS and WM_CF_CONST_OUTLINE.

Additional information

Details about the flags WM_CF_CONST_OUTLINE and WM_CF_HASTRANS can be found in the function description of WM_CreateWindow().

 © 2020 SEGGER Microcontroller GmbH

19.8.2.93 WM_SetUserClipRect()

Description

Temporarily reduces the clip area of the current window to a specified rectangle.

Prototype

```
GUI_RECT *WM_SetUserClipRect(const GUI_RECT * pRect);
```

Parameters

Parameter	Description
pRect	Pointer to a GUI_RECT structure defining the clipping region in desktop coordinates.

Return value

Pointer to the previous clip rectangle.

Additional information

A NULL pointer can be passed in order to restore the default settings. The clip rectangle will automatically be reset by the WM when callbacks are used.
The specified rectangle must be relative to the current window. You cannot enlarge the clip rectangle beyond the current window rectangle.
Your application must ensure that the specified rectangle retains its value until it is no longer needed; that is, until a different clip rectangle is specified or until a NULL pointer is passed. This means that the rectangle structure passed as parameter should not be an auto variable (usually located on the stack) if the clip rectangle remains active until after the return. In this case, a static variable should be used.

Example

This example is taken from the drawing routine of a progress indicator. The progress indicator must write text on top of the progress bar, where the text color has to be different on the left and right parts of the bar. This means that half of a digit could be in one color, while the other half could be in a different color. The best way to do this is to temporarily reduce the clip area when drawing each part of the bar as shown below:

```
/* Draw left part of the bar */
    r.x0=0; r.x1=x1-1; r.y0=0; r.y1 = GUI_YMAX;
    WM_SetUserClipRect(&r);
    GUI_SetBkColor(pThis->ColorBar[0]);
    GUI_SetColor(pThis->ColorText[0]);
    GUI_Clear();
    GUI_GotoXY(xText,yText); GUI_DispDecMin(pThis->v); GUI_DispChar('%');
/* Draw right part of the bar */
    r.x0=r.x1; r.x1=GUI_XMAX;
    WM_SetUserClipRect(&r);
    GUI_SetBkColor(pThis->ColorBar[1]);
    GUI_SetColor(pThis->ColorText[1]);
    GUI_Clear();
    GUI_GotoXY(xText,yText); GUI_DispDecMin(pThis->v); GUI_DispChar('%');
```

Screenshot of progress bar



 © 2020 SEGGER Microcontroller GmbH

19.8.2.94 WM_SetUserData()

Description

Sets the extra data of a window. Memory for extra data is reserved with the parameter NumExtraBytes when creating a window.

Prototype

```
int WM_SetUserData(      WM_HWIN   hWin,
                   const void    * pSrc,
                         int       NumBytes);
```

Parameters

Parameter	Description
hWin	Window handle.
pSrc	Pointer to buffer.
NumBytes	Size of buffer.

Return value

Number of bytes written.

Additional information

The maximum number of bytes used to store user data is the number of ExtraBytes specified when creating a window.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.95 WM_ShowWindow()

Description

Makes a specified window visible.

Prototype

```
void WM_ShowWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Return value

Number of bytes written.

Additional information

The window will not immediately be visible after calling this function. It will be redrawn when executing `WM_Exec()`. If you need to show (draw) the window immediately, you should call `WM_Paint()`.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.96 WM_Update()

Description

Draws the invalid part of the specified window immediately.

Prototype

```
void WM_Update(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

After updating a window its complete region is marked as valid.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.97 WM_UpdateWindowAndDescs()

Description

Paints the invalid part of the given window and the invalid part of all its descendants.

Prototype

```
void WM_UpdateWindowAndDescs(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

Additional information

The function only draws the invalid window regions.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.98 WM_ValidateRect()

Description

Validates a specified, rectangular area of a window.

Prototype

```
void WM_ValidateRect(      WM_HWIN    hWin,
                     const GUI_RECT * pRect);
```

Parameters

Parameter	Description
hWin	Window handle.
pRect	Pointer to a GUI_RECT structure with window coordinates of the parent window.

Additional information

Calling this function will tell the WM that the specified area is updated.
Normally this function is called internally and does not need to be called by the user application. The coordinates of the GUI_RECT structure have to be in desktop coordinates.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.99 WM_ValidateWindow()

Description

Validates a specified window.

Prototype

```
void WM_ValidateWindow(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.
pRect	Pointer to a GUI_RECT structure with window coordinates of the parent window.

Additional information

Calling this function will tell the WM that the specified window is updated.
Normally this function is called internally and does not need to be called by the user application.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.100 WM_XY2Screen()

Description

Converts the given coordinates (relative to the given window) into screen coordinates.

Prototype

```
void WM_XY2Screen(WM_HWIN   hWin,
                  int     * px,
                  int     * py);
```

Parameters

Parameter	Description
hWin	Window handle.
px	Pointer to a x position to be converted.
py	Pointer to a y position to be converted.

Additional information

This function is very useful when using Memory Devices in combination with windows/widgets, because Memory Device use coordinates relative to the screen.

 © 2020 SEGGER Microcontroller GmbH

19.8.2.101 WM_XY2Client()

Description

Converts the given coordinates (relative to the screen) into coordinates relative to the given window.

Prototype

```
void WM_XY2Client(WM_HWIN   hWin,
                  int     * px,
                  int     * py);
```

Parameters

Parameter	Description
hWin	Window handle.
px	Pointer to a x position to be converted.
py	Pointer to a y position to be converted.

 © 2020 SEGGER Microcontroller GmbH

19.8.3 Motion support

19.8.3.1 WM_MOTION_Enable()

Description

Enables motion support for the WM. Needs to be called once at the beginning of the program.

Prototype

```
void WM_MOTION_Enable(int OnOff);
```

Parameters

Parameter	Description
OnOff	1 for enabling motion support, 0 for disabling it.

 © 2020 SEGGER Microcontroller GmbH

19.8.3.2 WM_MOTION_SetDeceleration()

Description

Can be used to set the deceleration of the current moving operation.

Prototype

```
void WM_MOTION_SetDeceleration(WM_HWIN hWin,
                               int     Axis,
                               I32     Deceleration);
```

Parameters

Parameter	Description
hWin	Window handle.
Axis	See table below.
Deceleration	Deceleration in pixel / (s * s)

Permitted values for parameter Axis	
GUI_COORD_X	X axis should be used.
GUI_COORD_Y	Y axis should be used.

Additional information

Makes only sense if the given window is already moving.

 © 2020 SEGGER Microcontroller GmbH

19.8.3.3 WM_MOTION_SetDefaultPeriod()

Description

Sets the default value to be used for the duration of the deceleration phase after the PID has been released. If the window is already moving the window decelerates its motion until it stops. If the window is not moving but snapping is used the window moves within that period to the next raster position. If the window is already moving and snapping is used the window decelerates its motion until it stops to the nearest raster position given by the current speed.

Prototype

```
unsigned WM_MOTION_SetDefaultPeriod(unsigned Period);
```

Parameters

Parameter	Description
Period	Period to be used.

Return value

Previous default value of the period.

 © 2020 SEGGER Microcontroller GmbH

19.8.3.4 WM_MOTION_SetMotion()

Description

Starts a moving operation with the given speed and deceleration.

Prototype

```
void WM_MOTION_SetMotion(WM_HWIN hWin,
                         int     Axis,
                         I32     Speed,
                         I32     Deceleration);
```

Parameters

Parameter	Description
hWin	Window handle.
Axis	See table below.
Speed	Speed to be used.
Deceleration	Deceleration to be used.

Permitted values for parameter Axis	
GUI_COORD_X	X axis should be used.
GUI_COORD_Y	Y axis should be used.

Additional information

The moving operation then can be affected by further motion functions.

 © 2020 SEGGER Microcontroller GmbH

19.8.3.5 WM_MOTION_SetMoveable()

Description

Enables movability of the given window.

Prototype

```
void WM_MOTION_SetMoveable(WM_HWIN hWin,
                           U32     Flags,
                           int     OnOff);
```

Parameters

Parameter	Description
hWin	Window handle.
Flags	Permitted values are listed under *Motion flags* on page 953.
OnOff	1 for enabling, 0 for disabling.

Permitted values for parameter Flags	
WM_CF_MOTION_R	Enables circular movability for objects within the window.
WM_CF_MOTION_X	Enables / disables movability for the X axis.
WM_CF_MOTION_Y	Enables / disables movability for the Y axis.

Additional information

Motion support of a window can also be set with creation flags when creating the window or within the callback routine of the window. Details can be found in the section *Motion support*.

 © 2020 SEGGER Microcontroller GmbH

19.8.3.6 WM_MOTION_SetMovement()

Description

Starts a moving operation with the given speed for the given distance.

Prototype

```
void WM_MOTION_SetMovement(WM_HWIN hWin,
                           int     Axis,
                           I32     Speed,
                           I32     Dist);
```

Parameters

Parameter	Description
hWin	Window handle.
Axis	See table below.
Speed	Speed in pixels / s to be used. Positive and negative values are supported.
Dist	Distance to be used. Needs to be a positive value.

Permitted values for parameter Axis	
GUI_COORD_X	X axis should be used.
GUI_COORD_Y	Y axis should be used.

Additional information

The moving operation stops automatically if the given distance is reached.

 © 2020 SEGGER Microcontroller GmbH

19.8.3.7 WM_MOTION_SetSpeed()

Description

Starts moving the given window with the given speed.

Prototype

```
void WM_MOTION_SetSpeed(WM_HWIN hWin,
                        int     Axis,
                        I32     Speed);
```

Parameters

Parameter	Description
hWin	Window handle.
Axis	See table below.
Speed	Speed in pixels / s to be used.

Permitted values for parameter Axis	
GUI_COORD_X	X axis should be used.
GUI_COORD_Y	Y axis should be used.

 © 2020 SEGGER Microcontroller GmbH

19.8.3.8 WM_MOTION_SetThreshold()

Description

Sets the number of pixels required for starting a move operation. When holding down a finger on a touchscreen the touch controller normally generates a lot of input containing different coordinates. The threshold value can be used to avoid moving in that case.

Prototype

```
void WM_MOTION_SetThreshold(unsigned Threshold);
```

Parameters

Parameter	Description
hWin	Window handle.
Axis	See table below.
Speed	Speed in pixels / s to be used.

Permitted values for parameter Axis	
GUI_COORD_X	X axis should be used.
GUI_COORD_Y	Y axis should be used.

 © 2020 SEGGER Microcontroller GmbH

19.8.4 ToolTip related functions

In addition to the introduction at the beginning of the chapter the following contains the detailed descriptions of the ToolTip related functions.

19.8.4.1 WM_TOOLTIP_AddTool()

Description

Adds a tool to an existing ToolTip object.

Prototype

```
int WM_TOOLTIP_AddTool(      WM_TOOLTIP_HANDLE   hToolTip,
                             WM_HWIN             hTool,
                       const char              * pText);
```

Parameters

Parameter	Description
hToolTip	Handle of ToolTip object.
hTool	Handle of tool window.
pText	Pointer to a string.

Return value

= 0 on success
≠ 0 on error.

Additional information

This function can be used for adding tools by passing the window Id and a string pointer. The given string is copied into the dynamic memory of emWin and does not need to remain valid.

 © 2020 SEGGER Microcontroller GmbH

19.8.4.2 WM_TOOLTIP_Create()

Description

Creates a ToolTip object for the given dialog.

Prototype

```
WM_TOOLTIP_HANDLE WM_TOOLTIP_Create(      WM_HWIN        hDlg,
                                    const TOOLTIP_INFO * pInfo,
                                          unsigned       NumItems);
```

Parameters

Parameter	Description
hDlg	Handle of the dialog containing the tools as child- or grand child windows.
pInfo	Pointer to an array of TOOLTIP_INFO structures. Can be NULL.
NumItems	Number of tools to be added.

Return value

Handle to the ToolTip object on success, 0 on failure.

Additional information

If one of the parameters pInfo or NumItems is 0 the function only creates the ToolTip object. It is the responsibility of the application to delete the object if it is no longer used.

 © 2020 SEGGER Microcontroller GmbH

19.8.4.3 WM_TOOLTIP_Delete()

Description

Deletes the given ToolTip object.

Prototype

```
void WM_TOOLTIP_Delete(WM_TOOLTIP_HANDLE hToolTip);
```

Parameters

Parameter	Description
hToolTip	Handle of ToolTip object to be deleted.

 © 2020 SEGGER Microcontroller GmbH

19.8.4.4 WM_TOOLTIP_SetDefaultColor()

Description

Sets the default colors to be used for drawing ToolTips.

Prototype

```
GUI_COLOR WM_TOOLTIP_SetDefaultColor(unsigned  Index,
                                     GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *ToolTip color indexes* on page 956 for a list of possible values.
Color	Default color to be used.

Return value

Previous used color.

 © 2020 SEGGER Microcontroller GmbH

19.8.4.5 WM_TOOLTIP_SetDefaultFont()

Description

Sets the font to be used for displaying the text of ToolTips.

Prototype

```
GUI_FONT *WM_TOOLTIP_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Font to be used.

Return value

Previous default font used for ToolTips.

 © 2020 SEGGER Microcontroller GmbH

19.8.4.6 WM_TOOLTIP_SetDefaultPeriod()

Description

Sets the default periods to be used for showing ToolTips.

Prototype

```
unsigned WM_TOOLTIP_SetDefaultPeriod(unsigned Index,
                                     unsigned Period);
```

Parameters

Parameter	Description
Index	See *ToolTip period indexes* on page 957 for a list of possible values.
Period	Period to be used.

Return value

Previously used value.

 © 2020 SEGGER Microcontroller GmbH

19.8.5 Multiple Buffering support

19.8.5.1 WM_MULTIBUF_Enable()

Description

This functions enables or disables the automatic use of Multiple Buffering by the Window Manager.

Prototype

```
int WM_MULTIBUF_Enable(int OnOff);
```

Parameters

Parameter	Description
OnOff	1 to enable the automatic use of multiple buffers. 0 to disable the automatic use of multiple buffers.

Return value

Previous state.

Additional information

Detailed information on how to use Multiple Buffering can be found in the chapter *Multiple Buffering* on page 2372.

 © 2020 SEGGER Microcontroller GmbH

19.8.6 Memory Device support (optional)

When a Memory Device is used for redrawing a window, all drawing operations are automatically routed to a Memory Device context and are executed in memory. Only after all drawing operations have been carried out is the window redrawn on the LCD, reflecting all updates at once. The advantage of using Memory Devices is that any flickering effects (which normally occur when the screen is continuously updated as drawing operations are executed) are eliminated.
For more information on how Memory Devices operate, see the chapter *Memory Devices* on page 666.

19.8.6.1 WM_DisableMemdev()

Description

Disables the use of Memory Devices for redrawing a window.

Prototype

```
void WM_DisableMemdev(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

 © 2020 SEGGER Microcontroller GmbH

19.8.6.2 WM_EnableMemdev()

Description

Enables the use of Memory Devices for redrawing a window.

Prototype

```
void WM_EnableMemdev(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Window handle.

 © 2020 SEGGER Microcontroller GmbH

19.8.7 Timer related

19.8.7.1 WM_CreateTimer()

Description

Creates a timer which sends a message to the given window after the given time period has expired. The timer is associated to the given window.

Prototype

```
WM_HTIMER WM_CreateTimer(WM_HWIN hWin,
                         int     UserId,
                         int     Period,
                         int     Mode);
```

Parameters

Parameter	Description
hWin	Handle of window to be informed.
UserId	User defined Id. Can be set to 0 if not using multiple timers for the same window.
Period	Time period after which the given window should receive a message.
Mode	(reserved for future use, should be 0)

Return value

Handle of the timer.

Additional information

The function creates a 'one shot timer' which sends a WM_TIMER message to the given window. After the timer period has expired the timer object remains valid and can be restarted using the function WM_RestartTimer() or deleted with WM_DeleteTimer(). Once a window is deleted the Window Manager automatically deletes all timers associated to the window.

Example

```
static void _cbWin(WM_MESSAGE * pMsg) {
  switch (pMsg->MsgId) {
  case WM_TIMER:
    /*
      ... do something ...
    */
    WM_RestartTimer(pMsg->Data.v, 1000);
    break;
  default:
    WM_DefaultProc(pMsg);
  }
}
static void _DemoTimer(void) {
  WM_HWIN hWin;
  WM_HTIMER hTimer;
  hWin   = WM_CreateWindow(10, 10, 100, 100, WM_CF_SHOW, _cbWin, 0);
  hTimer = WM_CreateTimer(hWin, 0, 1000, 0);
  while (1) {
    GUI_Exec();
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

19.8.7.2 WM_DeleteTimer()

Description

Deletes the given timer.

Prototype

```
void WM_DeleteTimer(WM_HTIMER hTimer);
```

Parameters

Parameter	Description
hTimer	Handle of the timer to be deleted.

Additional information

After a timer has expired the timer object remains valid and will not be deleted automatically. If it is not used anymore it should be deleted using this function. Once a window is deleted the Window Manager automatically deletes all timers associated to the window.

 © 2020 SEGGER Microcontroller GmbH

19.8.7.3 WM_GetTimerId()

Description

Gets the Id of the given timer.

Prototype

```
int WM_GetTimerId(WM_HTIMER hTimer);
```

Parameters

Parameter	Description
hTimer	Handle of the timer.

Return value

The Id of the timer which was previously set within the function WM_CreateTimer().

 © 2020 SEGGER Microcontroller GmbH

19.8.7.4 WM_RestartTimer()

Description

Restarts the given timer with the given period.

Prototype

```
void WM_RestartTimer(WM_HTIMER hTimer,
                     int       Period);
```

Parameters

Parameter	Description
hTimer	Handle of the timer to be restarted.
Period	New period to be used.

Additional information

If this function gets called with Period set to zero the timer gets restarted with the period set on creation. After the period has expired a WM_TIMER message will be sent to the window assigned to the timer. For details, refer to WM_CreateTimer().

 © 2020 SEGGER Microcontroller GmbH

19.8.8 Widget related functions

19.8.8.1 WM_GetClientWindow()

Description

Returns the handle of the client window. The function sends a message to the active window to retrieve the handle of the client window. If the window does not handle the message the handle of the current window will be returned.

Prototype

```
WM_HWIN WM_GetClientWindow(WM_HWIN hObj);
```

Parameters

Parameter	Description
hWin	Handle of widget.

Return value

Handle of the client window.

Additional information

Use this function to retrieve the client window handle of a FRAMEWIN widget.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.2 WM_GetId()

Description

Returns the ID of a specified widget window.

Prototype

```
int WM_GetId(WM_HWIN hObj);
```

Parameters

Parameter	Description
hObj	Handle of widget.

Return value

> 0 ID of the widget which was specified at creation or set using WM_SetId().
= 0 will be returned if the specified window is not a widget.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.3 WM_GetInsideRect()

Description

Returns the coordinates of the client area of the active widget less the border size. The function sends a message to the active window to retrieve the inside rectangle. If the widget does not handle the message (that means the widget has no border) `WM_GetClientRect` will be used to calculate the rectangle. The result is given in window coordinates. That means x0 and y0 of the `GUI_RECT` structure corresponds to the border size in x and y, x1 and y1 corresponds to the size of the window less the border size - 1.
This function sends the `WM_GET_INSIDE_RECT` message to the given window which should be filled by the user. This message is quite helpful when creating an own widget.

Prototype

```
void WM_GetInsideRect(GUI_RECT * pRect);
```

Parameters

Parameter	Description
pRect	Pointer to a `GUI_RECT` structure.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.4 WM_GetInsideRectEx()

Description

Returns the coordinates of a window less the border size.

Prototype

```
void WM_GetInsideRectEx(WM_HWIN    hWin,
                        GUI_RECT * pRect);
```

Parameters

Parameter	Description
hObj	Handle of widget.
pRect	Pointer to a GUI_RECT structure.

Additional information

For details, refer to WM_GetInsideRect().

 © 2020 SEGGER Microcontroller GmbH

19.8.8.5 WM_GetScrollbarH()

Description

If the given window has a horizontal scroll bar attached the function returns the handle of that scrollbar.

Prototype

```
WM_HWIN WM_GetScrollbarH(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Handle of a window which has a horizontal SCROLLBAR attached.

Return value

Handle of the horizontal SCROLLBAR widget
0, if no horizontal SCROLLBAR widget is attached.

Additional information

Additional information can be found in *SCROLLBAR: Scroll bar widget* on page 1911.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.6 WM_GetScrollbarV()

Description

If the given window has a vertical scroll bar attached the function returns the handle of that scrollbar.

Prototype

```
WM_HWIN WM_GetScrollbarV(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Handle of a window which has a vertical SCROLLBAR attached.

Return value

Handle of the vertical SCROLLBAR widget
0, if no vertical SCROLLBAR widget is attached.

Additional information

Additional information can be found in *SCROLLBAR: Scroll bar widget* on page 1911.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.7 WM_GetScrollPosH()

Description

Returns the horizontal scrolling position of a window.

Prototype

```
int WM_GetScrollPosH(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Handle of a window which has a horizontal SCROLLBAR attached.

Return value

Position of the horizontal SCROLLBAR widget (0 < n)
0, if no horizontal SCROLLBAR widget is attached.

Additional information

Additional information can be found in *SCROLLBAR: Scroll bar widget* on page 1911.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.8 WM_GetScrollPosV()

Description

Returns the vertical scrolling position of a window.

Prototype

```
int WM_GetScrollPosV(WM_HWIN hWin);
```

Parameters

Parameter	Description
hWin	Handle of a window which has a horizontal SCROLLBAR attached.

Return value

Position of the horizontal SCROLLBAR widget (0 < n)
0, if no horizontal SCROLLBAR widget is attached.

Additional information

Additional information can be found in *SCROLLBAR: Scroll bar widget* on page 1911.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.9 WM_GetScrollState()

Description

Fills a data structure with information of the current state of a specified SCROLLBAR widget.

Prototype

```
void WM_GetScrollState(WM_HWIN           hObj,
                       WM_SCROLL_STATE * pScrollState);
```

Parameters

Parameter	Description
hObj	Handle of scroll bar widget.
pScrollState	Pointer to a data structure of type WM_SCROLL_STATE.

Additional information

This function does not return since the state of a scroll bar is defined by more than one value.
It has no effect on other types of widgets or windows. Additional information can be found in *SCROLLBAR: Scroll bar widget* on page 1911.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.10 WM_SetScrollPosH()

Description

Sets the horizontal scrolling position of a window.

Prototype

```
void WM_SetScrollPosH(WM_HWIN  hWin,
                      unsigned ScrollPos);
```

Parameters

Parameter	Description
hWin	Handle of a window which has a horizontal SCROLLBAR attached.
ScrollPos	New scroll position of the scroll bar.

Additional information

Additional information can be found in *SCROLLBAR: Scroll bar widget* on page 1911.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.11 WM_SetScrollPosV()

Description

Sets the vertical scrolling position of a window.

Prototype

```
void WM_SetScrollPosV(WM_HWIN  hWin,
                      unsigned ScrollPos);
```

Parameters

Parameter	Description
hWin	Handle of a window which has a vertical SCROLLBAR attached.
ScrollPos	New scroll position of the scroll bar.

Additional information

Additional information can be found in *SCROLLBAR: Scroll bar widget* on page 1911.

 © 2020 SEGGER Microcontroller GmbH

19.8.8.12 WM_SetScrollState()

Description

Sets the state of a specified SCROLLBAR widget.

Prototype

```
void WM_SetScrollState(      WM_HWIN           hWin,
                       const WM_SCROLL_STATE * pState);
```

Parameters

Parameter	Description
hObj	Handle of scroll bar widget.

 © 2020 SEGGER Microcontroller GmbH

19.8.9 Data structures

19.8.9.1 GUI_PID_STATE

Description

Stores the position of the pointer input device.

Type definition

```
typedef struct {
  int  x;
  int  y;
  U8   Pressed;
  U8   Layer;
} GUI_PID_STATE;
```

Structure members

Member	Description
x	Horizontal position of the PID in window coordinates.
y	Vertical position of the PID in window coordinates.
Pressed	If the message is originated by a touch screen this value can be 0 (unpressed) or 1 (pressed). If the message is originated by a mouse each bit represents a mouse button (0 for unpressed and 1 for pressed state): • Bit 0 represents the first button (normally the left button) • Bit 1 represents the second button (normally the right button) • Bit 2 represents the third button (normally the middle button) The remaining bits can be used for further buttons.
Layer	ID of layer.

 © 2020 SEGGER Microcontroller GmbH

19.8.9.2 TOOLTIP_INFO

Description

Contains the information about a ToolTip.

Type definition

```
typedef struct {
  int          Id;
  const char * pText;
} TOOLTIP_INFO;
```

Structure members

Member	Description
Id	Id of the ToolTip.
pText	String containing the text of the ToolTip.

 © 2020 SEGGER Microcontroller GmbH

19.8.9.3 WM_KEY_INFO

Description

Contains information about a pressed key.

Type definition

```
typedef struct {
  int  Key;
  int  PressedCnt;
} WM_KEY_INFO;
```

Structure members

Member	Description
Key	The key which has been pressed.
PressedCnt	>0 if the key has been pressed, 0 if the key has been released.

 © 2020 SEGGER Microcontroller GmbH

19.8.9.4 WM_MESSAGE

Description

Contains the data for a message sent by a window.

Type definition

```
typedef struct {
  int            MsgId;
  WM_HWIN        hWin;
  WM_HWIN        hWinSrc;
  union {
    const void * p;
    int          v;
    GUI_COLOR    Color;
    void       (* pFunc)(void);
  } Data;
} WM_MESSAGE;
```

Structure members

Member	Description
MsgId	Type of message.
hWin	Destination window.
hWinSrc	Source window.
Data	Data union. See elements below.
Elements of Data	
p	Message-specific data pointer.
v	Message-specific data value.
Color	Message-specific color.
pFunc	Message-specific function pointer.

 © 2020 SEGGER Microcontroller GmbH

19.8.9.5 WM_MOTION_INFO

Description

Contains information about a move with motion support.

Type definition

```
typedef struct {
  U8              Cmd;
  U8              FinalMove;
  U8              StopMotion;
  U8              IsDragging;
  int             dx;
  int             dy;
  int             da;
  int             xPos;
  int             yPos;
  int             Period;
  int             SnapX;
  int             SnapY;
  U8              IsOutside;
  unsigned        Overlap;
  U32             Flags;
  GUI_PID_STATE * pState;
  GUI_HMEM        hContext;
} WM_MOTION_INFO;
```

Structure members

Member	Description
Cmd	Command. See *Motion messages* on page 954.
FinalMove	Set to 1 on the final moving operation.
StopMotion	Can be set to 1 to stop motion immediately.
IsDragging	Is set to 1 if the PID is pressed, 0 if released.
dx	Distance in X to be used to move the window.
dy	Distance in Y to be used to move the window.
da	Distance in 1/10 degrees to be used to move an item.
xPos	Used to return the current position in X for custom moving operations.
yPos	Used to return the current position in Y for custom moving operations.
Period	Duration of the moving operation after the PID has been released.
SnapX	Raster size in X for snapping operations, 0 if no snapping is required.
SnapY	Raster size in Y for snapping operations, 0 if no snapping is required.
IsOutside	If motion is managed by window.
Overlap	Overlapping distance allowed for dragging operations.
Flags	To be used to enable motion support.
pState	Internal use.
hContext	Internal use.

 © 2020 SEGGER Microcontroller GmbH

19.8.9.6 WM_MOVE_INFO

Description

Stores the distance of a window move operation.

Type definition

```
typedef struct {
  int  dx;
  int  dy;
} WM_MOVE_INFO;
```

Structure members

Member	Description
dx	Difference between old and new position on the X-axis.
dy	Difference between old and new position on the Y-axis.

 © 2020 SEGGER Microcontroller GmbH

19.8.9.7 WM_PID_STATE_CHANGED_INFO

Description

Information about the changed PID state. Sent to a window with the WM_PID_STATE_CHANGED message.

Type definition

```
typedef struct {
  int  x;
  int  y;
  U8   State;
  U8   StatePrev;
} WM_PID_STATE_CHANGED_INFO;
```

Structure members

Member	Description
x	Horizontal position of the PID in window coordinates.
y	Vertical position of the PID in window coordinates.
State	Pressed state (> 0 if PID is pressed).
StatePrev	Previous pressed state.

 © 2020 SEGGER Microcontroller GmbH

19.8.9.8 WM_SCROLL_STATE

Description

Saves the scrollstate of a scrollbar.

Type definition

```
typedef struct {
  int  NumItems;
  int  v;
  int  PageSize;
} WM_SCROLL_STATE;
```

Structure members

Member	Description
NumItems	Number of items.
v	Current value.
PageSize	Number of items visible on one page.

 © 2020 SEGGER Microcontroller GmbH

19.8.10 Defines

19.8.10.1 Message IDs

Description

List of all messages sent by the Window Manager. The member `MsgId` of the `WM_MESSAGE` structure contains one of these values to identify a message.

Definition

```
#define WM_CREATE               0x0001
#define WM_MOVE                 0x0003
#define WM_SIZE                 0x0005
#define WM_DELETE               11
#define WM_TOUCH                0x0240
#define WM_TOUCH_CHILD          13
#define WM_KEY                  14
#define WM_PAINT                0x000F
#define WM_MOUSEOVER            16
#define WM_MOUSEOVER_END        18
#define WM_PID_STATE_CHANGED    17
#define WM_GET_INSIDE_RECT      20
#define WM_GET_ID               21
#define WM_SET_ID               22
#define WM_INIT_DIALOG          29
#define WM_SET_FOCUS            30
#define WM_GET_ACCEPT_FOCUS     31
#define WM_NOTIFY_PARENT        38
#define WM_NOTIFY_VIS_CHANGED   41
#define WM_PRE_PAINT            46
#define WM_POST_PAINT           47
#define WM_MOTION               48
#define WM_USER_DATA            52
#define WM_SET_CALLBACK         53
#define WM_TIMER                0x0113
#define WM_USER                 0x0400
```

Symbols

Definition	Description
WM_CREATE	Sent immediately after a window has been created, giving the window the chance to initialize and create any child windows.
WM_MOVE	Sent to a window immediately after it has been moved.
WM_SIZE	Sent to a window after its size has changed.
WM_DELETE	Sent just before a window is deleted, telling the window to free its data structures (if any).
WM_TOUCH	Sent to a window once a pointer input device is pressed, pressed and moved or released over its area.
WM_TOUCH_CHILD	Sent to a parent window if a child window has been touched by the pointer input device.
WM_KEY	Sent to the window currently containing the focus if a key has been pressed.
WM_PAINT	Sent to a window after it has become invalid and it should be redrawn.
WM_MOUSEOVER	Sent to a window if a pointer input device touches the outline of a window. Only sent if mouse support is enabled.

 © 2020 SEGGER Microcontroller GmbH

Definition	Description
WM_MOUSEOVER_END	Sent to a window if a pointer input device has been moved out of the outline of a window. Only sent if mouse support is enabled.
WM_PID_STATE_CHANGED	Sent to the window pointed by the pointer input device when the pressed state has been changed.
WM_GET_INSIDE_RECT	Send to a window to get the client rectangle without the effect size.
WM_GET_ID	Sent to a window to request the Id of the window.
WM_SET_ID	Sent to a window to change the window Id.
WM_INIT_DIALOG	Sent to a dialog window immediately after the creation of the dialog.
WM_SET_FOCUS	Sent to a window if it gains or loses the input focus.
WM_GET_ACCEPT_FOCUS	Sent to a window to determine if the window is able to receive the input focus.
WM_NOTIFY_PARENT	Informs a parent window that something has occurred in one of its child windows. The information is detailed as a notification code.
WM_NOTIFY_VIS_CHANGED	Sent to a window if its visibility has been changed.
WM_PRE_PAINT	Sent to a window before the first WM_PAINT message is sent.
WM_POST_PAINT	Sent to a window after the last WM_PAINT message was processed.
WM_MOTION	Sent to a window to achieve advanced motion support.
WM_USER_DATA	Sent to a window after user data has been set.
WM_SET_CALLBACK	Sent to a window after a callback has been set.
WM_TIMER	Sent to a window after a timer has expired.
WM_USER	The WM_USER constant can be used by applications to define private messages, usually of the form (WM_USER + X), where X is an integer value.

Additional information

WM_MOTION, WM_MOUSEOVER, WM_MOUSEOVER_END, WM_PID_STATE_CHANGED, WM_TOUCH and WM_TOUCH_CHILD are “Pointer input device (PID) messages”.

 © 2020 SEGGER Microcontroller GmbH

19.8.10.2 Motion flags

Description

Flags for motion support. The flags are supposed to be OR-combined with the member `Flags` of the `WM_MOTION_INFO` structure.

Definition

```
#define WM_MOTION_MANAGE_BY_WINDOW    (1 << 0)
```

Symbols

Definition	Description
WM_MOTION_MANAGE_BY_WINDOW	Window movement is managed by window itself.

 © 2020 SEGGER Microcontroller GmbH

19.8.10.3 Motion messages

Description

Commands sent with a WM_MOTION message. The command can be found in the member Cmd of the WM_MOTION_INFO structure.

Definition

```
#define WM_MOTION_INIT          0
#define WM_MOTION_MOVE          1
#define WM_MOTION_GETPOS        2
#define WM_MOTION_GETCONTEXT    3
```

Symbols

Definition	Description
WM_MOTION_INIT	Sent to a window to initiate a motion operation.
WM_MOTION_MOVE	Sent to a window to achieve custom moving operations.
WM_MOTION_GETPOS	Sent to get the current position of custom moving operations.
WM_MOTION_GETCONTEXT	Internal use.

Additional information

More information about these commands can be read under *WM_MOTION message and WM_MOTION_INFO* on page 791.

 © 2020 SEGGER Microcontroller GmbH

19.8.10.4 Notification codes

Description

List of all notifications sent by the Window Manager. A notification code is sent with a WM_NOTIFY_PARENT message and can be read with pMsg->Data.v.

Definition

```
#define WM_NOTIFICATION_CLICKED           1
#define WM_NOTIFICATION_RELEASED          2
#define WM_NOTIFICATION_MOVED_OUT         3
#define WM_NOTIFICATION_SEL_CHANGED       4
#define WM_NOTIFICATION_VALUE_CHANGED     5
#define WM_NOTIFICATION_SCROLLBAR_ADDED   6
#define WM_NOTIFICATION_CHILD_DELETED     7
#define WM_NOTIFICATION_GOT_FOCUS         8
#define WM_NOTIFICATION_LOST_FOCUS        9
#define WM_NOTIFICATION_SCROLL_CHANGED    10
```

Symbols

Definition	Description
WM_NOTIFICATION_CLICKED	This notification message will be sent when the window has been clicked.
WM_NOTIFICATION_RELEASED	This notification message will be sent when a clicked widget has been released.
WM_NOTIFICATION_MOVED_OUT	This notification message will be sent when the pointer was moved out of the window while it is clicked.
WM_NOTIFICATION_SEL_CHANGED	This notification message will be sent when the selection of a widget has changed.
WM_NOTIFICATION_VALUE_CHANGED	This notification message will be sent when a widget specific value has changed.
WM_NOTIFICATION_SCROLLBAR_ADDED	This notification message will be sent when a SCROLLBAR widget has been added to the window.
WM_NOTIFICATION_CHILD_DELETED	This notification message will be sent from a window to its parent before it is deleted.
WM_NOTIFICATION_GOT_FOCUS	This notification message will be sent once a window receives and accepts the focus.
WM_NOTIFICATION_LOST_FOCUS	This notification message will be sent when the window has lost the focus.
WM_NOTIFICATION_SCROLL_CHANGED	This notification message will be sent when the scroll position of an attached SCROLLBAR widget has changed.

 © 2020 SEGGER Microcontroller GmbH

19.8.10.5 ToolTip color indexes

Description

Color indexes for ToolTip related routines.

Definition

```
#define WM_TOOLTIP_CI_BK       0
#define WM_TOOLTIP_CI_FRAME    1
#define WM_TOOLTIP_CI_TEXT     2
```

Symbols

Definition	Description
WM_TOOLTIP_CI_BK	Color to be used for the background.
WM_TOOLTIP_CI_FRAME	Color to be used for the thin frame.
WM_TOOLTIP_CI_TEXT	Color to be used for the text.

 © 2020 SEGGER Microcontroller GmbH

19.8.10.6 ToolTip period indexes

Description

Period indexes for ToolTip related routines.

Definition

```
#define WM_TOOLTIP_PI_FIRST    0
#define WM_TOOLTIP_PI_SHOW     1
#define WM_TOOLTIP_PI_NEXT     2
```

Symbols

Definition	Description
WM_TOOLTIP_PI_FIRST	Period to be used the first time the PID is hovered over a tool. The ToolTip appears after the PID has not moved for at least this period. Default is 1000 ms.
WM_TOOLTIP_PI_SHOW	Period to be used for showing the ToolTip. The ToolTip disappears after the PID remains for at least this period without moving. Default is 5000 ms.
WM_TOOLTIP_PI_NEXT	Period to be used if the PID hovers over a tool of the same parent as before. The ToolTip appears after the PID is not moved for at least this period. Default is 50 ms.

 © 2020 SEGGER Microcontroller GmbH

19.8.10.7 Window create flags

Description

Flags that define a window upon creation. These flags can be passed to the create window function as flag-parameter. The flags are combinable using the binary OR-operator.

Definition

```
#define WM_CF_HASTRANS            (1UL << 0)
#define WM_CF_HIDE                (0UL << 1)
#define WM_CF_SHOW                (1UL << 1)
#define WM_CF_MEMDEV              (1UL << 2)
#define WM_CF_STAYONTOP           (1UL << 3)
#define WM_CF_DISABLED            (1UL << 4)
#define WM_CF_ACTIVATE            (1UL << 5)
#define WM_CF_FGND                (0UL << 6)
#define WM_CF_BGND                (1UL << 6)
#define WM_CF_ANCHOR_RIGHT        (1UL << 7)
#define WM_CF_ANCHOR_BOTTOM       (1UL << 8)
#define WM_CF_ANCHOR_LEFT         (1UL << 9)
#define WM_CF_ANCHOR_TOP          (1UL << 10)
#define WM_CF_CONST_OUTLINE       (1UL << 11)
#define WM_CF_LATE_CLIP           (1UL << 12)
#define WM_CF_MEMDEV_ON_REDRAW    (1UL << 13)
#define WM_SF_INVALID_DRAW        (1UL << 14)
#define WM_SF_DELETE              (1UL << 15)
#define WM_CF_STATIC              (1UL << 16)
#define WM_CF_MOTION_X            (1UL << 17)
#define WM_CF_MOTION_Y            (1UL << 18)
#define WM_CF_GESTURE             (1UL << 19)
#define WM_CF_ZOOM                (1UL << 20)
#define WM_CF_MOTION_R            (1UL << 21)
#define WM_CF_UNTOUCHABLE         (1UL << 22)
#define WM_CF_APPWIZARD           (1UL << 23)
```

Symbols

Definition	Description
WM_CF_HASTRANS	Has transparency flag. Must be defined for windows whose client area is not entirely filled. To set this flag after the window has been created the function WM_SetTransState() should be used.
WM_CF_HIDE	Hide window after creation (default).
WM_CF_SHOW	Show window after creation.
WM_CF_MEMDEV	Automatically use a Memory Device for drawing. This will avoid flickering and also improve the output speed in most cases, as clipping is simplified. The Window Manager creates a Memory Device for the current window according to the configured color depth and window size. The Memory Device is deleted immediately after the drawing process was finished. In order to draw images into a remaining Memory Device the IMAGE widget can be used with the creation flag IMAGE_CF_MEMDEV. Details can be found in the section *IMAGE: Image widget* on page 1440. Note that the Memory Device package is required (and needs to be enabled in the configuration) in order to be able to use this flag. If Memory Devices are not enabled, this flag is ignored.
WM_CF_STAYONTOP	Make sure window stays on top of all siblings created without this flag.

 © 2020 SEGGER Microcontroller GmbH

Definition	Description
WM_CF_DISABLED	Window is disabled after creation. This means it receives no PID (mouse and touch) input.
WM_CF_ACTIVATE	Internal use.
WM_CF_FGND	Put window in foreground after creation (default).
WM_CF_BGND	Put window in background after creation.
WM_CF_ANCHOR_RIGHT	Anchors the right edge of the new window relative to the right edge of the parent window. If the position of the parent windows right edge will be adjusted due to a size change, the position of new window will also be adjusted.
WM_CF_ANCHOR_BOTTOM	Anchors the bottom edge of the new window relative to the bottom edge of the parent window. If the position of the parent windows bottom edge will be adjusted due to a size change, the position of new window will also be adjusted.
WM_CF_ANCHOR_LEFT	Anchors the left edge of the new window relative to the left edge of the parent window (default). If the position of the parent windows left edge will be adjusted due to a size change, the position of new window will also be adjusted.
WM_CF_ANCHOR_TOP	Anchors the top edge of the new window relative to the top edge of the parent window (default). If the position of the parent windows top edge will be adjusted due to a size change, the position of new window will also be adjusted.
WM_CF_CONST_OUTLINE	This flag is an optimization for transparent windows. It gives the Window Manager a chance to optimize redrawing and invalidation of transparent windows. A transparent window is normally redrawn as part of the background, which is less efficient than redrawing the window separately. However, this flag may NOT be used if the window has semi transparency (alpha blending / anti-aliasing with background) or the outline (the shape) changes with the window's states. To set this flag after the window has been created the function WM_SetTransState() should be used.
WM_CF_LATE_CLIP	This flag can be used to tell the WM that the clipping should be done in the drawing routines (late clipping). The default behavior of the WM is early clipping. That means that the clipping rectangle will be calculated before a WM_PAINT message will be sent to a window. In dependence of other existing windows it might be necessary to send more than one WM_PAINT message to a window. If using WM_CF_LATE_CLIP the WM makes sure only one message will be sent to an invalid window and the clipping will be done by the drawing routines. The Sample folder of emWin contains the example WM_LateClipping.c to show the effect.
WM_CF_MEMDEV_ON_REDRAW	Equals WM_CF_MEMDEV with the difference that the according window is drawn the first time without using a Memory Device. The WM will automatically use a Memory Device for redrawing. This flag can be used as a replacement of WM_CF_MEMDEV. It typically accelerates the initial rendering of the window, but maintains the advantage of flicker free updates.
WM_SF_INVALID_DRAW	Internal use.
WM_SF_DELETE	Internal use.
WM_CF_STATIC	Window uses a static memory device for redrawing.
WM_CF_MOTION_X	Window can be moved automatically in X axis.
WM_CF_MOTION_Y	Window can be moved automatically in Y axis.

 © 2020 SEGGER Microcontroller GmbH

Definition	Description
WM_CF_GESTURE	Marks the window to be able to receive gesture messages. This requires gesture support.
WM_CF_ZOOM	Window can be scaled automatically by multi-touch gesture input.
WM_CF_MOTION_R	This enables the window to be rotated.
WM_CF_UNTOUCHABLE	A window created with this flag routes its touch input to its parent. This makes a window 'untouchable'.
WM_CF_APPWIZARD	Internal use.

 © 2020 SEGGER Microcontroller GmbH

19.9 Example

The following example illustrates the difference between using a callback routine for redrawing the background and not having one. It also shows how to set your own callback function. The example is available as `WM_Redraw.c` in the examples shipped with emWin:

```
/*********************************************************************
*                SEGGER MICROCONTROLLER SYSTEME GmbH                 *
*        Solutions for real time microcontroller applications        *
*                                                                    *
*                     emWin example code                             *
*                                                                    *
**********************************************************************
----------------------------------------------------------------------
File        : WM_Redraw.c
Purpose     : Demonstrates the redrawing mechanism of the Window Manager
----------------------------------------------------------------------
*/
#include "GUI.H"
/*********************************************************************
*
*            Callback routine for background window
*
**********************************************************************
*/
static void cbBackgroundWin(WM_MESSAGE * pMsg) {
  switch (pMsg->MsgId) {
  case WM_PAINT:
    GUI_Clear();
    break;
  default:
    WM_DefaultProc(pMsg);
  }
}
/*********************************************************************
*
*            Callback routine for foreground window
*
**********************************************************************
*/
static void cbForegroundWin(WM_MESSAGE * pMsg) {
  switch (pMsg->MsgId) {
  case WM_PAINT:
    GUI_SetBkColor(GUI_GREEN);
    GUI_Clear();
    GUI_DispString("Foreground window");
    break;
  default:
    WM_DefaultProc(pMsg);
  }
}
/*********************************************************************
*
*         Demonstrates the redraw mechanism of emWin
*
**********************************************************************
*/
static void DemoRedraw(void) {
  GUI_HWIN hWnd;
  while(1) {
    /* Create foreground window */
    hWnd = WM_CreateWindow(10, 10, 100, 100, WM_CF_SHOW, cbForegroundWin, 0);
    /* Show foreground window */
    GUI_Delay(1000);
    /* Delete foreground window */
    WM_DeleteWindow(hWnd);
    GUI_DispStringAt("Background of window has not been redrawn", 10, 10);
```

 © 2020 SEGGER Microcontroller GmbH

```
    /* Wait a while, background will not be redrawn */
    GUI_Delay(1000);
    GUI_Clear();
    /* Set callback for Background window */
    WM_SetCallback(WM_HBKWIN, cbBackgroundWin);
    /* Create foreground window */
    hWnd = WM_CreateWindow(10, 10, 100, 100,WM_CF_SHOW, cbForegroundWin, 0);
    /* Show foreground window */
    GUI_Delay(1000);
    /* Delete foreground window */
    WM_DeleteWindow(hWnd);
    /* Wait a while, background will be redrawn */
    GUI_Delay(1000);
    /* Delete callback for Background window */
    WM_SetCallback(WM_HBKWIN, 0);
 }}
/*************************************************************************
*
*                 main
*
*************************************************************************
*/
void main(void) {
  GUI_Init();
  DemoRedraw();
}
```

 © 2020 SEGGER Microcontroller GmbH

Chapter 20

Widgets (window objects)

Widgets are windows with object-type properties. They are called controls in the Windows environments and make up the elements of the user interface. They can react automatically to certain events. For example, a button can appear in a different state if it is pressed. Widgets have properties which may be changed at any time during their existence. They are typically deleted as soon as they are not used any longer. Similar to windows, widgets are referenced by handles which are returned by the respective create function.

Widgets require the Window Manager. Once a widget is created, it is treated just like any other window. The WM ensures that it is properly displayed (and redrawn) whenever necessary. The use of widgets is not mandatory for applications or user interfaces, but they decrease development time.

Since widgets are essentially windows it is possible to use most of the Window Manager API functions as well.

 © 2020 SEGGER Microcontroller GmbH

20.1 Some basics

20.1.1 Available widgets

The following table shows the appearance of the currently available widgets. Some of the widgets support skinning. This method of changing the appearance is explained in detail in chapter *Skinning* on page 2288. The second screenshot shows the appearance when skinning is enabled for the widget:

Name	Screenshot (classic)	Screenshot (skinned)	Description
BUTTON			Button which can be pressed. Text or bitmaps may be displayed on a button.
CHECKBOX			Check box which may be checked or unchecked.
DROPDOWN			Dropdown listbox, opens a listbox when pressed.
EDIT			Single-line edit field which prompts the user to type a number or text.
FRAMEWIN			Frame window. Creates the typical GUI look.
GAUGE			Gauge widget, basically a radial progress bar.
GRAPH			Graph widget, used to show curves or measured values.
HEADER			Header control, used to manage columns.
ICONVIEW			Icon view widget. Useful for icon based platforms as found in common hand held devices.
IMAGE			Image widget. Displays several image formats automatically.
KNOB *(obsolete)*			Knob widget which can be used to adjust uncountable values.

 © 2020 SEGGER Microcontroller GmbH

Name	Screenshot (classic)	Screenshot (skinned)	Description
LISTBOX			Listbox which highlights items as they are selected by the user.
LISTVIEW			Listview widgets are used to creates tables.
LISTWHEEL			Listwheel widget. The data can be moved and accelerated via pointer input device.
MENU			Menu widgets are used to create horizontal and vertical menus.
MULTIEDIT			Multiedit widgets are used to edit multiple lines of text.
MULTIPAGE			Multipage widgets are used to create dialogs with multiple pages.
PROGBAR			Progress bar used for visualization.
QRCODE			QR code.
RADIO			Radio button which may be selected. Only one button may be selected at a time.
ROTARY			Rotary widget which can be rotated to return uncountable values.
SCROLLBAR			Scrollbar which may be horizontal or vertical.
SLIDER			Slider bar used for changing values.
SPINBOX			Spinning box to display and adjust a specific value.

 © 2020 SEGGER Microcontroller GmbH

Name	Screenshot (classic)	Screenshot (skinned)	Description
SWIPELIST			Swipelist widgets are used for creating swipeable lists which could be moved by swiping the finger (or any other PID) over the touch screen.
SWITCH			Switch which can be toggled.
TEXT			Static text controls typically used in dialogs.
TREEVIEW			Treeview widget for managing hierarchical lists.

20.1.2 Custom widget types

emWin users have the possibility to create custom types of widgets. This can be done using a custom callback function for an existing widget in order to preserve certain functionality. In case it is required to implement a new type of widget it is recommended to use a simple window as starting point and follow the instructions in `AN03002_Custom_Widget_Type.pdf` which can also be found in the Doc-folder.

20.1.3 Understanding the redrawing mechanism

A widget draws itself according to its properties. This is done when `WM_Exec()`, `GUI_Exec()` or `GUI_Delay()` is called. In a multitasking environment, a background task is normally used to call `WM_Exec()` and update the widgets (and all other windows with callback functions).
When a property of a widget is changed, the window of the widget (or part of it) is marked as invalid, but it is not immediately redrawn. Therefore, the section of code executes very fast. The redrawing is done by the WM at a later time or it can be forced by calling `WM_Paint()` for the widget (or `WM_Exec()` until all windows are redrawn).

20.1.4 How to use widgets

Suppose we would like to display a progress bar. All that is needed is the following code:

```
PROGBAR_Handle hProgBar;
GUI_DispStringAt("Progress bar", 100, 20);
hProgBar = PROGBAR_Create(100, 40, 100, 20, WM_CF_SHOW);
```



 © 2020 SEGGER Microcontroller GmbH

The first line reserves memory for the handle of the widget. The last line actually creates the widget. The widget will then automatically be drawn by the Window Manager once WM_Exec() is called the next time, what may happen in a separate task.
Member functions are available for each type of widget which allow modifications to their appearance. Once the widget has been created, its properties can be changed by calling its member functions. These functions take the handle of the widget as their first argument. In order to make the progress bar created above show 45% and to change the bar colors from their defaults (dark gray/light gray) to green/red, the following section of code may be used:

```
PROGBAR_SetBarColor(hProgBar, 0, GUI_GREEN);
PROGBAR_SetBarColor(hProgBar, 1, GUI_RED);
PROGBAR_SetValue(hProgBar, 45);
```



Default configuration

All widgets also have one or more configuration macros which define various default settings such as fonts and colors used. The available configuration options are listed for each widget in their respective sections later in the chapter. The default configurations have to be set prior using the widget. Otherwise, the set properties will not be taken into account.

How widgets communicate

Widgets are often created as child windows. The parent window may be any type of window, even another widget. A parent window usually needs to be informed whenever something occurs with one of its children in order to ensure synchronization. Child window widgets communicate with their parent window by sending a WM_NOTIFY_PARENT message whenever an event occurs. The notification code sent as part of the message depends on the event. Most widgets have one or more notification codes defining different types of events. The available notification codes for each widget (if any) are listed under their respective sections.

Skinning

The appearance of a widget can be modified by using the member functions of the respective widget. Some of the widgets support skinning. If skinning is used for a widget the 'skin' determines the appearance of the widget and some of the member functions have no effect. Details can be found in the chapter *Skinning* on page 2288.



Dynamic memory usage for widgets

In embedded applications it is usually not very desirable to use dynamic memory at all because of fragmentation effects. There are a number of different strategies that can be used to avoid this, but they all work in a limited way whenever memory areas are referenced by a pointer in the application program. For this reason, emWin uses a different approach: all objects (and all data stored at run-time) are stored in memory areas referenced by a handle. This makes it possible to relocate the allocated memory areas at run-time, thus avoiding the long-term allocation problems which occur when using pointers. All widgets are thus referenced by handles.

 © 2020 SEGGER Microcontroller GmbH

Determine the type of a widget

The type of a widget can be determined by comparing the callback function of a specific widget with the public callback functions of the widget API. The following shows a short example how to determine the type of a widget. In case of overwritten callback functions the method should be adapted:

```
WM_CALLBACK * pCb;
pCb = WM_GetCallback(hWidget);
if        (pCb == BUTTON_Callback) {
  // Widget is a button
} else if (pCb == DROPDOWN_Callback) {
  // Widget is a dropdown
} else if (pCb == LISTBOX_Callback) {
  // Widget is a listbox
} else if (...) {
  ...
}
```

This code works only if callback function have not been overwritten. As custom callback functions are used, the code above needs to be adapted.

 © 2020 SEGGER Microcontroller GmbH

20.2 Configuration options

Type	Macro	Default	Description
B	WIDGET_USE_PARENT_EFFECT	0	If set to 1, each 'child widget' of a widget, has the same effect as the parent widget. If for example a listbox needs to create a scroll bar, the new scroll bar has the same effect as the listbox.
B	WIDGET_USE_SCHEME_LARGE	0	If set to 1, the default appearance of the widgets is large sized. That means that all widgets which show text are configured to use large sized default fonts.
B	WIDGET_USE_SCHEME_MEDIUM	0	If set to 1, the default appearance of the widgets is medium sized. That means that all widgets which show text are configured to use medium sized default fonts.
B	WIDGET_USE_SCHEME_SMALL	1	If set to 1, the default appearance of the widgets is small sized. That means that all widgets which show text are configured to use small sized default fonts.
B	WIDGET_USE_FLEX_SKIN	0	If set to 1, widgets are drawn using the Flex Skin by default. Detailed information about skinning can be found in the chapter *Skinning* on page 2288.

WIDGET_USE_SCHEME...

The table below shows the default appearance of the widget schemes:

WIDGET_USE_SCHEME_LARGE	WIDGET_USE_SCHEME_MEDIUM
	

 © 2020 SEGGER Microcontroller GmbH

WIDGET_USE_SCHEME_SMALL



 © 2020 SEGGER Microcontroller GmbH

20.3 Widget IDs

In order to be able to separate all widgets from each other IDs can be assigned. This is usually done by using the according parameter of the <WIDGET>_Create…() functions. To make sure that every widget has its unique Id, predefined symbols may be used. The predefined symbols are listed in the subsections of the according widgets. If the predefined symbols do not match ones requirements, custom unique IDs may be defined as follows:

```
#define MY_WIDGET_ID_0 (GUI_ID_USER + 0)
#define MY_WIDGET_ID_1 (GUI_ID_USER + 1)
#define MY_WIDGET_ID_2 (GUI_ID_USER + 2)
#define MY_WIDGET_ID_3 (GUI_ID_USER + 3)
 .
 .
 .
```

 © 2020 SEGGER Microcontroller GmbH

20.4 General widget API

20.4.1 WM routines used for widgets

Since widgets are essentially windows, they are compatible with any of the Window Manager API routines. The handle of the widget is used as the hWin parameter and the widget is treated like any other window. The WM functions most commonly used with widgets are listed as follows:

Routine	Description
WM_DeleteWindow()	Deletes a specified window.
WM_DisableWindow()	Disables the specified window.
WM_EnableMemdev()	Enables the use of Memory Devices for redrawing a window.
WM_InvalidateWindow()	Invalidates a specified window.
WM_Paint()	Draws or redraws a specified window immediately.

The complete list of WM-related functions can be found in the chapter *The Window Manager (WM)* on page 781.

20.4.2 Common routines

The table below lists available widget-related routines in alphabetical order. These functions are common to all widgets, and are listed here in order to avoid repetition. Detailed descriptions of the routines follow. The additional member functions available for each widget may be found in later sections.

Routine	Description
<WIDGET>_Callback()	Default callback function.
<WIDGET>_CreateIndirect()	Used for automatic creation in dialog boxes.
<WIDGET>_CreateUser()	Creates a widget using extra bytes as user data.
<WIDGET>_GetUserData()	Retrieves the data set with <WIDGET>_SetUserData.
<WIDGET>_SetUserData()	Sets the extra data of a widget.
WIDGET_EnableStreamAuto()	Enables support for all streamed bitmap formats.
WIDGET_GetDefaultEffect()	Returns the default effect used for widgets.
WIDGET_SetDefaultEffect()	Sets the default effect used for widgets.
WIDGET_SetEffect()	Sets the effect for the given widget.
WIDGET_SetFocusable()	Sets the ability to receive the input focus.

 © 2020 SEGGER Microcontroller GmbH

20.4.2.1 <WIDGET>_Callback()

Description

Default callback function of the widgets to be used from within overwritten callback function.

Prototype

```
void <WIDGET>_Callback(WM_MESSAGE * pMsg);
```

Parameter	Description
pMsg	Pointer to a data structure of type WM_MESSAGE.

Additional information

A default callback function of a widget should not be called directly. It is only to be used from within an overwritten callback function.
This function replaces the default callback of a standard window when overwriting a WIDGET callback function (WM_DefaultProc()).
For details about the WM_MESSAGE data structure, refer to *Messages* on page 796.

 © 2020 SEGGER Microcontroller GmbH

20.4.2.2 <WIDGET>_CreateIndirect()

Description

Creates a widget to be used in dialog boxes.

Prototype

```
<WIDGET>_Handle <WIDGET>_CreateIndirect(const GUI_WIDGET_CREATE_INFO * pCreateInfo,
                                        WM_HWIN                      hParent,
                                        int                          x0,
                                        int                          y0,
                                        WM_CALLBACK                * cb);
```

Parameter	Description
pCreateInfo	Pointer to a GUI_WIDGET_CREATE_INFO structure (see below).
hParent	Handle of parent window.
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
cb	Pointer to a callback function.

Additional information

Any widget may be created indirectly by using the appropriate prefix. For example: BUTTON_CreateIndirect() to indirectly create a button widget, CHECKBOX_CreateIndirect() to indirectly create a check box widget, and so on.

A widget only needs to be created indirectly if it is to be included in a dialog box. Otherwise, it may be created directly by using the <WIDGET>_Create() functions. See the chapter *Dialogs* on page 2229 for more information about dialog boxes.

Resource table

The GUI_WIDGET_CREATE_INFO data structure is defined in the dialog resource table as follows:

```
typedef struct {
  GUI_WIDGET_CREATE_FUNC * pfCreateIndirect; // Create function
  const char * pName;                   // Text (not used for all widgets)
  I16 Id;                               // Window ID of the widget
  I16 x0, y0, xSize, ySize;             // Size and position of the widget
  I16 Flags;                            // Widget-specific flags (or 0)
  I32 Para;                             // Widget-specific parameter (or 0)
  U32 NumExtraBytes;                    // Number of extra bytes usable
                                        // with <WIDGET>_SetUserData &
                                        //      <WIDGET>_GetUserData
} GUI_WIDGET_CREATE_INFO;
```

Widget flags and parameters are optional, and vary depending on the type of widget. The available flags and parameters for each widget (if any) will be listed under the appropriate section later in this chapter.

 © 2020 SEGGER Microcontroller GmbH

20.4.2.3 <WIDGET>_CreateUser()

Description

Creates a widget using extra bytes as user data. This function is similar to the <WIDGET>_CreateEx() function of the appropriate widget in every case except the additional parameter NumExtraBytes.

Prototype

```
<WIDGET>_Handle <WIDGET>_CreateUser(int x0,
                                    int y0,
                                    ... ...,
                                    int Id,
                                    int NumExtraBytes);
```

Parameter	Description
NumBytes	Number of extra bytes to be allocated

Return value

Handle of the created widget.
0 if the function fails.

Additional information

For more information about the other parameters the appropriate <WIDGET>_CreateEx() functions can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.4.2.4 <WIDGET>_GetUserData()

Description

Retrieves the data set with <WIDGET>_SetUserData.

Prototype

```
int <WIDGET>_GetUserData(<WIDGET>_Handle hObj,
                         void          * pDest,
                         int             NumBytes);
```

Parameter	Description
hObj	Handle of the widget
pDest	Pointer to buffer
NumBytes	Number of bytes to read

Return value

Number of bytes read.

Additional information

The maximum number of bytes returned by this function is the number of extra bytes specified when creating the widget using <WIDGET>_CreateUser() or <WIDGET>_CreateIndirect().

 © 2020 SEGGER Microcontroller GmbH

20.4.2.5 <WIDGET>_SetUserData()

Description

Sets the extra data of a widget.

Prototype

```
int <WIDGET>_GetUser(<WIDGET>_Handle hObj,
                     void          * pDest,
                     int             NumBytes);
```

Parameter	Description
hObj	Handle of the widget
pDest	Pointer to buffer
NumBytes	Number of bytes to write

Return value

Number of bytes written.

Additional information

The maximum number of bytes used to store user data is the number of extra bytes specified when creating the widget using <WIDGET>_CreateUser() or <WIDGET>_CreateIndirect().

 © 2020 SEGGER Microcontroller GmbH

20.4.2.6 WIDGET_EnableStreamAuto()

Description

Enables drawing of all supported streamed bitmap formats for widgets like ICONVIEW and IMAGE widget.

Prototype

```
void WIDGET_EnableStreamAuto(void);
```

Additional information

Per default support for drawing all streamed bitmap formats is enabled. To be able to spare ROM that support could be disabled by adding the following line to `GUIConf.h`:

```
#define GUI_USE_STREAMED_BITMAP_AUTO 0
```

 © 2020 SEGGER Microcontroller GmbH

20.4.2.7 WIDGET_GetDefaultEffect()

Description

Returns the default effect used for widgets.

Prototype

```
const WIDGET_EFFECT * WIDGET_GetDefaultEffect(void);
```

Return value

The result of the function is a pointer to a `WIDGET_EFFECT` structure.

Additional information

For more information, refer to *`WIDGET_SetDefaultEffect`* on page 980.

 © 2020 SEGGER Microcontroller GmbH

20.4.2.8 WIDGET_SetDefaultEffect()

Description

Sets the default effect used for widgets.

Prototype

```
const WIDGET_EFFECT * WIDGET_SetDefaultEffect(const WIDGET_EFFECT * pEffect);
```

Parameters

Parameter	Description
pEffect	Pointer to a WIDGET_EFFECT structure. See table below.

Permitted values for parameter pEffect	
&WIDGET_Effect_3D	Sets the default effect to *3D*.
&WIDGET_Effect_None	Sets the default effect to *None*.
&WIDGET_Effect_Simple	Sets the default effect to *Simple*.

Return value

Previous used default effect.

Additional information

The following table shows the appearance of some widgets in dependence of the used effect:

3D	None	Simple
		
		
		

 © 2020 SEGGER Microcontroller GmbH

20.4.2.9 WIDGET_SetEffect()

Description

Sets the effect for the given widget.

Prototype

```
void WIDGET_SetEffect(      WM_HWIN         hObj,
                      const WIDGET_EFFECT * pEffect);
```

Parameters

Parameter	Description
hObj	Handle of widget.
pEffect	Pointer to a WIDGET_EFFECT structure. For details, refer to *WIDGET_SetDefaultEffect* on page 980.

 © 2020 SEGGER Microcontroller GmbH

20.4.2.10 WIDGET_SetFocusable()

Description

Sets the ability to receive the input focus.

Prototype

```
void WIDGET_SetFocusable(WM_HWIN hObj,
                         int     State);
```

Parameters

Parameter	Description
hObj	Handle of widget.
State	(see table below)

Permitted values for parameter State	
1	Widget can receive the input focus.
0	Widget can’t receive the input focus.

 © 2020 SEGGER Microcontroller GmbH

20.4.3 User drawn widgets

Some widgets supports owner drawing, for example the LISTBOX widget. If the user draw mode of a widget has been activated a application-defined function of type WIDGET_DRAW_ITEM_FUNC will be called to draw the widget (item). The prototype of an application-defined owner draw function should be defined as follows:

Prototype

```
int WIDGET_DRAW_ITEM_FUNC(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo);
```

Parameter	Description
pDrawItemInfo	Pointer to a WIDGET_ITEM_DRAW_INFO structure.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	Cmd	See table below.
int	ItemIndex	Zero based index of item to be drawn.
int	Col	Zero based column index of item to be drawn.
int	x0	x0 window coordinate which is used to draw the item.
int	y0	y0 window coordinate which is used to draw the item.
int	x1	x1 window coordinate which is used to draw the item.
int	y1	y1 window coordinate which is used to draw the item.

Permitted values for parameter Cmd	
WIDGET_ITEM_GET_XSIZE	The function returns the x-size (width) in pixels of the given item.
WIDGET_ITEM_GET_YSIZE	The function returns the y-size (height) in pixels of the given item.
WIDGET_ITEM_DRAW	The function draws the given item at the given position.
WIDGET_DRAW_BACKGROUND	The background of the widget should be drawn.
WIDGET_DRAW_OVERLAY	This command is sent after all other drawing operations have been finished and enables the possibility to draw some overlaying items above the widget.

Return value

Depends on the given command.

Reaction to commands

The function has to react to the command given in the WIDGET_ITEM_DRAW_INFO structure. This can be done in one of 2 ways:

- By calling the appropriate default function supplied by the particular widget (for example, LISTBOX_OwnerDraw())
- By supplying code that reacts accordingly.

 © 2020 SEGGER Microcontroller GmbH

Commands

The commands listed below are supported and should be reacted to by the function. As explained above, the default owner draw function should be called for all not handled functions. This can save code size (for example if the height is the same as the default height) and makes sure that your code stays compatible if additional commands are introduced in future versions of the software.

WIDGET_ITEM_GET_XSIZE

The X-size in pixels of the given item has to be returned.

WIDGET_ITEM_GET_YSIZE

The Y-size (height) in pixels of the given item has to be returned.

WIDGET_ITEM_DRAW

The given item has to be drawn. x0 and y0 of the `WIDGET_ITEM_DRAW_INFO` structure specify the position of the item in window coordinates. The item has to fill its entire rectangle; the rectangle is defined by the starting position x0, y0 supplied to the function and the sizes returned by the function as reaction to the commands `WIDGET_ITEM_GET_YSIZE`, `WIDGET_ITEM_GET_XSIZE`. It may NOT leave a part of this rectangular area unpainted. It can not paint outside of this rectangular area because the clip rectangle has been set before the function call.

 © 2020 SEGGER Microcontroller GmbH

20.5 BUTTON: Button widget

BUTTON widgets are commonly used as the primary user interface element for touch-screens. If the button has the input focus, it also reacts on the keys GUI_KEY_SPACE and GUI_KEY_ENTER. Buttons may be displayed with text, as shown below, or with a bitmap.



Note

All BUTTON-related routines are located in the file(s) BUTTON*.c, BUTTON.h.
All identifiers are prefixed BUTTON.

Skinning...



…is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.5.1 Configuration options

Type	Macro	Default	Description
N	BUTTON_3D_MOVE_X	1	Number of pixels that text/ bitmap moves in horizontal direction in pressed state.
N	BUTTON_3D_MOVE_Y	1	Number of pixels that text/ bitmap moves in vertical direction in pressed state.
N	BUTTON_ALIGN_DEFAULT	GUI_TA_HCENTER | GUI_TA_VCENTER	Alignment used to display the button text.
N	BUTTON_BKCOLOR0_DEFAULT	0xAAAAAA	Background color, unpressed state.
N	BUTTON_BKCOLOR1_DEFAULT	GUI_WHITE	Background color, pressed state.
N	BUTTON_FOCUSCOLOR_DEFAULT	GUI_BLACK	Default color for rendering the focus rectangle.
S	BUTTON_FONT_DEFAULT	&GUI_Font13_1	Font used for button text.
B	BUTTON_REACT_ON_LEVEL	0	See description below.
N	BUTTON_TEXTCOLOR0_DEFAULT	GUI_BLACK	Text color, unpressed state.
N	BUTTON_TEXTCOLOR1_DEFAULT	GUI_BLACK	Text color, pressed state.

20.5.1.1 BUTTON_REACT_ON_LEVEL

There are 2 ways for a BUTTON widget to handle PID events.
The default way is recognizing and processing all PID events which happen on the BUTTON area. This includes PIDs moved in the BUTTON area in pressed state. The BUTTON widget would "accept" the pressed state and change its state accordingly. This behavior can be useful in combination with a touch panel, but the disadvantage is that BUTTONs may be mistakenly clicked.
The other way of handling PID events for the BUTTON widget would be reacting on level changes, only. This would make BUTTON widgets react, only if the PID state changes on the BUTTON. This logic can be enabled either by defining BUTTON_REACT_ON_LEVEL with 1 or by calling the function BUTTON_SetReactOnLevel().

 © 2020 SEGGER Microcontroller GmbH

Example for an unwanted BUTTON click

This example shows how a BUTTON widget may be mistakenly clicked without the BUTTON being configured to react on level.





20.5.1.2 BUTTON_BKCOLOR0_DEFAULT, BUTTON_BKCOLOR1_DEFAULT

The default for the BUTTON widget is to use a white background in the pressed state. This has been done purposely because it makes it very obvious that the button is pressed, on any kind of display. If you want the background color of the BUTTON widget to be the same in both its pressed and unpressed states, change `BUTTON_BKCOLOR1_DEFAULT` to `BUTTON_BKCOLOR0_DEFAULT`.

20.5.2 Predefined IDs

The following symbols define IDs which may be used to make BUTTON widgets distinguishable from creation.

```
#define GUI_ID_BUTTON0    0x170
#define GUI_ID_BUTTON1    0x171
#define GUI_ID_BUTTON2    0x172
#define GUI_ID_BUTTON3    0x173
#define GUI_ID_BUTTON4    0x174
#define GUI_ID_BUTTON5    0x175
#define GUI_ID_BUTTON6    0x176
#define GUI_ID_BUTTON7    0x177
#define GUI_ID_BUTTON8    0x178
#define GUI_ID_BUTTON9    0x179
```

20.5.3 Notification codes

The following events are sent from a BUTTON widget to its parent window as part of a `WM_NOTIFY_PARENT` message:

Message	Description
`WM_NOTIFICATION_CLICKED`	BUTTON has been clicked.
`WM_NOTIFICATION_RELEASED`	BUTTON has been released.
`WM_NOTIFICATION_MOVED_OUT`	BUTTON has been clicked and pointer has been moved out of the BUTTON widget without releasing.

20.5.4 Keyboard reaction

The BUTTON widget reacts to the following keys if it has the input focus:

 © 2020 SEGGER Microcontroller GmbH

Key	Reaction
GUI_KEY_ENTER	If the key is pressed, the BUTTON reacts as it has been pressed and immediately released.
GUI_KEY_SPACE	If the key is pressed, the BUTTON state changes to pressed. If the keys is released, the BUTTON state changes to unpressed.

20.5.5 BUTTON API

The table below lists the available emWin BUTTON-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
BUTTON_Create()	Creates a BUTTON widget. (Obsolete)
BUTTON_CreateAsChild()	Creates a BUTTON widget as a child window. (Obsolete)
BUTTON_CreateEx()	Creates a BUTTON widget.
BUTTON_CreateIndirect()	Creates a BUTTON widget from a resource table entry.
BUTTON_CreateUser()	Creates a BUTTON widget using extra bytes as user data.
BUTTON_GetBitmap()	Returns a pointer to the optional BUTTON bitmap.
BUTTON_GetBkColor()	Returns the background color of the given BUTTON widget.
BUTTON_GetDefaultBkColor()	Returns the default background color for BUTTON widgets.
BUTTON_GetDefaultFont()	Returns the pointer to the font used to display the text of BUTTON widgets.
BUTTON_GetDefaultTextAlign()	Returns the default text alignment used to display the text of BUTTON widgets.
BUTTON_GetDefaultTextColor()	Returns the default text color used to display the text of BUTTON widgets.
BUTTON_GetFont()	Returns a pointer to the font used to display the text of the given BUTTON widget.
BUTTON_GetText()	Retrieves the text of the specified BUTTON widget.
BUTTON_GetTextAlign()	Returns the alignment of the BUTTON text.
BUTTON_GetTextColor()	Returns the text color of the given BUTTON widget.
BUTTON_GetUserData()	Retrieves the data set with BUTTON_SetUserData().
BUTTON_IsPressed()	Returns if the BUTTON is pressed or not.
BUTTON_SetBitmap()	Sets the bitmap used when displaying the BUTTON.
BUTTON_SetBitmapEx()	Sets the bitmap used when displaying the BUTTON.
BUTTON_SetBkColor()	Sets the background color of a BUTTON widget.
BUTTON_SetBMP()	Sets the bitmap to be displayed on the specified BUTTON widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
BUTTON_SetBMPEx()	Sets the bitmap to be displayed at the specified position on the given BUTTON widget.
BUTTON_SetDefaultBkColor()	Sets the default background color used for BUTTON widgets.
BUTTON_SetDefaultFocusColor()	Sets the default focus rectangle color for BUTTON widgets. (Obsolete)
BUTTON_SetDefaultFont()	Sets a pointer to a GUI_FONT structure used to display the text of BUTTON widgets.
BUTTON_SetDefaultTextAlign()	Sets the default text alignment used to display the text of BUTTON widgets.
BUTTON_SetDefaultTextColor()	Sets the default text color used to display the text of BUTTON widgets.
BUTTON_SetFocusColor()	Sets the color used to render the focus rectangle of the BUTTON widget. (Obsolete)
BUTTON_SetFocusable()	Sets the ability to receive the input focus.
BUTTON_SetFont()	Sets the font of the BUTTON widget.
BUTTON_SetFrameColor()	Sets the color of BUTTON frame. (Obsolete)
BUTTON_SetPressed()	Sets the state of the button to pressed or unpressed.
BUTTON_SetReactOnLevel()	Sets all BUTTON widgets to react on level changes of the PID.
BUTTON_SetReactOnTouch()	Sets all BUTTON widgets to react on touch events.
BUTTON_SetStreamedBitmap()	Sets the streamed bitmap used when displaying the BUTTON widget.
BUTTON_SetStreamedBitmapEx()	Sets the streamed bitmap used when displaying the BUTTON widget.
BUTTON_SetText()	Sets the text.
BUTTON_SetTextAlign()	Sets the text alignment of the BUTTON widget.
BUTTON_SetTextColor()	Set the color(s) for the text.
BUTTON_SetTextOffset()	Adjusts the position of the BUTTON text considering the current text alignment setting.
BUTTON_SetUserData()	Sets the extra data of a BUTTON widget.

Defines

Group of defines	Description
BUTTON bitmap indexes	Bitmap indexes for BUTTON widget.
BUTTON color indexes	Color indexes for BUTTON widget.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1 Functions

20.5.5.1.1 BUTTON_Create()

> **Note**
>
> This function is **deprecated**, `BUTTON_CreateEx()` should be used instead.

Description

Creates a BUTTON widget of a specified size at a specified location.

Prototype

```
BUTTON_Handle BUTTON_Create(int x0,
                            int y0,
                            int xSize,
                            int ySize,
                            int Id,
                            int Flags);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the button (in parent coordinates).
`y0`	Topmost pixel of the button (in parent coordinates).
`xSize`	Horizontal size of the button (in pixels).
`ySize`	Vertical size of the button (in pixels).
`Id`	ID to be returned when button is pressed.
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).

Return value

Handle of the created BUTTON widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.2 BUTTON_CreateAsChild()

> **Note**
>
> This function is **deprecated**, `BUTTON_CreateEx()` should be used instead.

Description

Creates a BUTTON widget as a child window.

Prototype

```
BUTTON_Handle BUTTON_CreateAsChild(int     x0,
                                   int     y0,
                                   int     xSize,
                                   int     ySize,
                                   WM_HWIN hParent,
                                   int     Id,
                                   int     Flags);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the button (in parent coordinates).
`y0`	Topmost pixel of the button (in parent coordinates).
`xSize`	Horizontal size of the button (in pixels).
`ySize`	Vertical size of the button (in pixels).
`hParent`	Handle of parent window. If 0, the BUTTON widget will be a child of the desktop (top-level window).
`Id`	ID to be returned when button is pressed.
`Flags`	Window create flags (see *Window create flags* on page 958).

Return value

Handle of the created `BUTTON` widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.3 BUTTON_CreateEx()

Description

Creates a BUTTON widget of a specified size at a specified location.

Prototype

```
BUTTON_Handle BUTTON_CreateEx(int     x0,
                              int     y0,
                              int     xSize,
                              int     ySize,
                              WM_HWIN hParent,
                              int     WinFlags,
                              int     ExFlags,
                              int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the button (in parent coordinates).
y0	Topmost pixel of the button (in parent coordinates).
xSize	Horizontal size of the button (in pixels).
ySize	Vertical size of the button (in pixels).
hParent	Handle of parent window. If 0, the BUTTON widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used yet, reserved for future use.
Id	Window ID of the widget.

Return value

Handle of the created BUTTON widget; 0 if the function fails.

Additional information

If the possibility of storing user data is a matter the function BUTTON_CreateUser() should be used instead.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.4 BUTTON_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The elements `Flags` and `Para` of the according `GUI_WIDGET_CREATE_INFO` structure are not used.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.5 BUTTON_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `BUTTON_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.6 BUTTON_GetBitmap()

Description

Returns a pointer to the optional BUTTON bitmap.

Prototype

```
GUI_BITMAP *BUTTON_GetBitmap(BUTTON_Handle hObj,
                             unsigned int  Index);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *BUTTON bitmap indexes* on page 1030 for a full list of permitted values.

Return value

Pointer to the bitmap, 0 if no bitmap exists.

Additional information

For details about how to set a button bitmap, refer to `BUTTON_SetBitmap()` and `BUTTON_SetBitmapEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.7 BUTTON_GetBkColor()

Description

Returns the background color of the given BUTTON widget.

Prototype

```
GUI_COLOR BUTTON_GetBkColor(BUTTON_Handle hObj,
                            unsigned int  Index);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *Button color indexes* on page for a full list of permitted values.

Return value

Background color of the given BUTTON widget.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.8 BUTTON_GetDefaultBkColor()

Description

Returns the default background color for BUTTON widgets.

Prototype

```
GUI_COLOR BUTTON_GetDefaultBkColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *Button color indexes* on page for a full list of permitted values.

Return value

Default background color for BUTTON widgets.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.9 BUTTON_GetDefaultFont()

Description

Returns the pointer to the font used to display the text of BUTTON widgets.

Prototype

```
GUI_FONT *BUTTON_GetDefaultFont(void);
```

Return value

Pointer to the font used to display the text of BUTTON widgets.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.10 BUTTON_GetDefaultTextAlign()

Description

Returns the default text alignment used to display the text of BUTTON widgets.

Prototype

```
int BUTTON_GetDefaultTextAlign(void);
```

Return value

Default text alignment used to display the text of BUTTON widgets.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.11 BUTTON_GetDefaultTextColor()

Description

Returns the default text color used to display the text of BUTTON widgets.

Prototype

```
GUI_COLOR BUTTON_GetDefaultTextColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *Button color indexes* on page for a full list of permitted values.

Return value

Default text alignment used to display the text of BUTTON widgets.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.12 BUTTON_GetFont()

Description

Returns a pointer to the font used to display the text of the given BUTTON widget.

Prototype

```
GUI_FONT *BUTTON_GetFont(BUTTON_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.

Return value

Pointer to the font used to display the text of the given BUTTON widget.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.13 BUTTON_GetText()

Description

Retrieves the text of the specified BUTTON widget.

Prototype

```
void BUTTON_GetText(BUTTON_Handle   hObj,
                    char          * pBuffer,
                    int             MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
pBuffer	Pointer to buffer.
MaxLen	Size of buffer.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.14 BUTTON_GetTextAlign()

Description

Returns the alignment of the BUTTON text.

Prototype

```
int BUTTON_GetTextAlign(BUTTON_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.

Return value

Alignment of the BUTTON text.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.15 BUTTON_GetTextColor()

Description

Returns the text color of the given BUTTON widget.

Prototype

```
GUI_COLOR BUTTON_GetTextColor(BUTTON_Handle hObj,
                              unsigned int  Index);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *Button color indexes* on page for a full list of permitted values.

Return value

Text color of the given BUTTON widget.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.16 BUTTON_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.17 BUTTON_IsPressed()

Description

Returns if the BUTTON is pressed or not.

Prototype

```
unsigned BUTTON_IsPressed(BUTTON_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.

Return value

1 if the button is pressed.
0 if the button is not pressed.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.18 BUTTON_SetBitmap()

Description

Sets the bitmap(s) to be used when displaying a specified BUTTON widget.

Prototype

```
void BUTTON_SetBitmap(      BUTTON_Handle   hObj,
                            unsigned int    Index,
                      const GUI_BITMAP    * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *BUTTON bitmap indexes* on page 1030 for a full list of permitted values.
pBitmap	Pointer to the bitmap structure.

Return value

If only a bitmap for the unpressed state is set the button will show it also when it is pressed or disabled. To deactivate a previously set bitmap, NULL has to be passed as pBitmap.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.19 BUTTON_SetBitmapEx()

Description

Sets the bitmap(s) to be used when displaying a specified BUTTON widget.

Prototype

```
void BUTTON_SetBitmapEx(      BUTTON_Handle   hObj,
                              unsigned int    Index,
                        const GUI_BITMAP    * pBitmap,
                              int             x,
                              int             y);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *BUTTON bitmap indexes* on page 1030 for a full list of permitted values.
pBitmap	Pointer to the bitmap structure.
x	X-position for the bitmap relative to the button.
y	Y-position for the bitmap relative to the button.

Return value

If only a bitmap for the unpressed state is set the BUTTON widget will show it also when it is pressed or disabled.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.20 BUTTON_SetBkColor()

Description

Sets the background color of a BUTTON widget.

Prototype

```
void BUTTON_SetBkColor(BUTTON_Handle hObj,
                       unsigned int  Index,
                       GUI_COLOR     Color);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *Button color indexes* on page for a full list of permitted values.
Color	Background color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.21 BUTTON_SetBMP()

Description

Sets the bitmap to be displayed on the specified BUTTON widget.

Prototype

```
void BUTTON_SetBMP(      BUTTON_Handle   hObj,
                         unsigned int    Index,
                   const void          * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *BUTTON bitmap indexes* on page 1030 for a full list of permitted values.
pBitmap	Pointer to bitmap file data.

Additional information

If a bitmap was set only for the unpressed state, it will be also displayed in pressed or disabled state. For additional information regarding bitmap files, refer to *BMP file support* on page 386.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.22 BUTTON_SetBMPEx()

Description

Sets the bitmap to be displayed at the specified position on the given BUTTON widget.

Prototype

```
void BUTTON_SetBMPEx(      BUTTON_Handle   hObj,
                           unsigned int    Index,
                     const void          * pBitmap,
                           int             x,
                           int             y);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *BUTTON bitmap indexes* on page 1030 for a full list of permitted values.
pBitmap	Pointer to bitmap file data
x	X-position for the bitmap relative to the button.
y	Y-position for the bitmap relative to the button.

Additional information

If only a bitmap for the unpressed state is set the BUTTON widget will show it also when it is pressed or disabled. For additional information regarding bitmap files, refer to *BMP file support* on page 386.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.23 BUTTON_SetDefaultBkColor()

Description

Sets the default background color used for BUTTON widgets.

Prototype

```
void BUTTON_SetDefaultBkColor(GUI_COLOR Color,
                              unsigned  Index);
```

Parameters

Parameter	Description
Color	Color to be used.
Index	See *Button color indexes* on page for a full list of permitted values.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.24 BUTTON_SetDefaultFocusColor()

> **Note**
>
> This function is **deprecated** and only works in conjunction with the classic skin (`BUTTON_SetSkinClassic()`). Skinning props should be used instead which can be set via `BUTTON_SetSkinFlexProps()`.

Description

Sets the default focus rectangle color for BUTTON widgets.

Prototype

```
GUI_COLOR BUTTON_SetDefaultFocusColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
`Color`	Default color to be used for BUTTON widgets.

Return value

Previous default focus rectangle color.

Additional information

For more information, refer to `BUTTON_SetFocusColor()`.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.25 BUTTON_SetDefaultFont()

Description

Sets a pointer to a GUI_FONT structure used to display the text of BUTTON widgets.

Prototype

```
void BUTTON_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to GUI_FONT structure to be used.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.26 BUTTON_SetDefaultTextAlign()

Description

Sets the default text alignment used to display the text of BUTTON widgets.

Prototype

```
void BUTTON_SetDefaultTextAlign(int Align);
```

Parameters

Parameter	Description
Align	Text alignment mode. List of flags can be found under *Text alignment flags* on page 218.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.27 BUTTON_SetDefaultTextColor()

Description

Sets the default text color used to display the text of BUTTON widgets.

Prototype

```
void BUTTON_SetDefaultTextColor(GUI_COLOR Color,
                                unsigned  Index);
```

Parameters

Parameter	Description
Color	Default text color to be used.
Index	See *Button color indexes* on page for a full list of permitted values.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.28 BUTTON_SetFocusColor()

> **Note**
>
> This function is **deprecated** and only works in conjunction with the classic skin (`BUTTON_SetSkinClassic()`). Skinning props should be used instead which can be set via `BUTTON_SetSkinFlexProps()`.

Before	After
	

Description

Sets the color used to render the focus rectangle of the BUTTON widget.

Prototype

```
GUI_COLOR BUTTON_SetFocusColor(BUTTON_Handle hObj,
                               GUI_COLOR     Color);
```

Parameters

Parameter	Description
`hObj`	Handle of BUTTON widget.
`Color`	`Color` to be used for the focus rectangle.

Return value

Previous color of the focus rectangle.

Additional information

The focus rectangle is only visible if the widget has the input focus.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.29 BUTTON_SetFocusable()

Description

Sets the ability to receive the input focus.

Prototype

```
void BUTTON_SetFocusable(BUTTON_Handle hObj,
                         int           State);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
State	See table below.

Permitted values for parameter Index	
1	Button can receive the input focus
0	Button can’t receive the input focus

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.30 BUTTON_SetFont()

Description

Sets the font of the BUTTON widget.

Prototype

```
void BUTTON_SetFont(      BUTTON_Handle   hObj,
                    const GUI_FONT      * pfont);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
pFont	Pointer to the font.

Additional information

If no font is selected, BUTTON_FONT_DEF will be used.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.31 BUTTON_SetFrameColor()

> **Note**
>
> This function is **deprecated** and only works in conjunction with the classic skin (`BUTTON_SetSkinClassic()`). Skinning props should be used instead which can be set via `BUTTON_SetSkinFlexProps()`.

Description

Sets the color of BUTTON frame.

Prototype

```
void BUTTON_SetFrameColor(BUTTON_Handle hObj,
                          GUI_COLOR     Color);
```

Parameters

Parameter	Description
`hObj`	Handle of BUTTON widget.
`Color`	`Color` of the frame.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.32 BUTTON_SetPressed()

Description

Sets the state of the button to pressed or unpressed.

Prototype

```
void BUTTON_SetPressed(BUTTON_Handle hObj,
                       int           State);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
State	State, 1 for pressed, 0 for unpressed

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.33 BUTTON_SetReactOnLevel()

Description

Sets all BUTTON widgets to react on level changes of the PID.

Prototype

```
void BUTTON_SetReactOnLevel(void);
```

Additional information

Alternatively to this function the configuration option `BUTTON_REACT_ON_LEVEL` can be used.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.34 BUTTON_SetReactOnTouch()

Description

Sets all BUTTON widgets to react on touch events.

Prototype

```
void BUTTON_SetReactOnTouch(void);
```

Additional information

The default behavior of BUTTON widgets is reacting on touch events.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.35 BUTTON_SetStreamedBitmap()

Description

Sets the streamed bitmap(s) to be used when displaying a specified BUTTON widget.

Prototype

```
void BUTTON_SetStreamedBitmap(      BUTTON_Handle       hObj,
                                    unsigned int        Index,
                              const GUI_BITMAP_STREAM * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *BUTTON bitmap indexes* on page 1030 for a full list of permitted values.
pBitmap	Pointer to a bitmap stream.

Additional information

For details about streamed bitmaps, refer to *Drawing streamed bitmaps* on page 296.

Example

```
BUTTON_SetStreamedBitmap(hButton, BUTTON_CI_UNPRESSED, (const GUI_BITMAP_STREAM*)acImage);
```

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.36 BUTTON_SetStreamedBitmapEx()

Description

Sets the streamed bitmap(s) to be used when displaying the specified BUTTON widget.

Prototype

```
void BUTTON_SetStreamedBitmapEx(      BUTTON_Handle       hObj,
                                      unsigned int        Index,
                                const GUI_BITMAP_STREAM * pBitmap,
                                      int                 x,
                                      int                 y);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *BUTTON bitmap indexes* on page 1030 for a full list of permitted values.
pBitmap	Pointer to a bitmap stream.
x	X-position for the bitmap relative to the button.
y	Y-position for the bitmap relative to the button.

Additional information

For details about streamed bitmaps, refer to *Drawing streamed bitmaps* on page 296.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.37 BUTTON_SetText()

Description

Sets the text to be displayed on the BUTTON widget.

Prototype

```
int BUTTON_SetText(      BUTTON_Handle   hObj,
                   const char          * s);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
s	Text to display.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.38 BUTTON_SetTextAlign()

Description

Sets the text alignment of the BUTTON widget.

Prototype

```
void BUTTON_SetTextAlign(BUTTON_Handle hObj,
                         int           Align);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Align	Text alignment mode. List of flags can be found under *Text alignment flags* on page 218.

Additional information

The default value of the text alignment is GUI_TA_HCENTER | GUI_TA_VCENTER.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.39 BUTTON_SetTextColor()

Description

Sets the text color of the BUTTON widget.

Prototype

```
void BUTTON_SetTextColor(BUTTON_Handle hObj,
                         unsigned int  Index,
                         GUI_COLOR     Color);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
Index	See *Button color indexes* on page for a full list of permitted values.
Color	Text color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.40 BUTTON_SetTextOffset()

Description

Adjusts the position of the BUTTON text considering the current text alignment setting.

Prototype

```
void BUTTON_SetTextOffset(BUTTON_Handle hObj,
                          int           xPos,
                          int           yPos);
```

Parameters

Parameter	Description
hObj	Handle of BUTTON widget.
xPos	Offset to be used for the x-axis. Default is 0.
yPos	Offset to be used for the y-axis. Default is 0.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.1.41 BUTTON_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.2 Defines

20.5.5.2.1 BUTTON bitmap indexes

Description

Bitmap indexes for BUTTON widget.

Definition

```
#define BUTTON_BI_UNPRESSED    0
#define BUTTON_BI_PRESSED      1
#define BUTTON_BI_DISABLED     2
```

Symbols

Definition	Description
BUTTON_BI_UNPRESSED	Bitmap for disabled state.
BUTTON_BI_PRESSED	Bitmap for pressed state.
BUTTON_BI_DISABLED	Bitmap for unpressed state.

 © 2020 SEGGER Microcontroller GmbH

20.5.5.2.2 BUTTON color indexes

Description

Color indexes for BUTTON widget.

Definition

```
#define BUTTON_CI_UNPRESSED    0
#define BUTTON_CI_PRESSED      1
#define BUTTON_CI_DISABLED     2
```

Symbols

Definition	Description
BUTTON_CI_UNPRESSED	Color for disabled state.
BUTTON_CI_PRESSED	Color for pressed state.
BUTTON_CI_DISABLED	Color for unpressed state.

 © 2020 SEGGER Microcontroller GmbH

20.5.6 Examples

The `Sample` folder contains the following examples which show how the widget can be used:

- `WIDGET_ButtonSimple.c`
- `WIDGET_ButtonPhone.c`
- `WIDGET_ButtonRound.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_ButtonSimple.c:



Screenshot of WIDGET_ButtonPhone.c:



Screenshot of WIDGET_ButtonRound.c:



 © 2020 SEGGER Microcontroller GmbH

20.6 CHECKBOX: Checkbox widget

One of the most familiar widgets for selecting various choices is the check box. A check box may be checked or unchecked by the user, and any number of boxes may be checked at one time. If using a keyboard interface the state of a focused check box can be toggled by the <SPACE> key. A box will appear gray if it is disabled, as seen in the table below where each of the possible check box appearances are illustrated:

	Unchecked	Checked	Third state
Enabled			
Disabled			

> **Note**
>
> All CHECKBOX-related routines are located in the file(s) `CHECKBOX*.c`, `CHECKBOX.h`. All identifiers are prefixed CHECKBOX.

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.6.1 Configuration options

Type	Macro	Default	Description
N	`CHECKBOX_BKCOLOR_DEFAULT`	`0xC0C0C0`	Default background color.
N	`CHECKBOX_BKCOLOR0_DEFAULT`	`0x808080`	Background color of the default image, disabled state.
N	`CHECKBOX_BKCOLOR1_DEFAULT`	`GUI_WHITE`	Background color of the default image, enabled state.
N	`CHECKBOX_FGCOLOR0_DEFAULT`	`0x101010`	Foreground color of the default image, disabled state.
N	`CHECKBOX_FGCOLOR1_DEFAULT`	`GUI_BLACK`	Foreground color of the default image, enabled state.
N	`CHECKBOX_FOCUSCOLOR_DEFAULT`	`GUI_BLACK`	Color used to render the focus rectangle.
S	`CHECKBOX_FONT_DEFAULT`	`&GUI_Font13_1`	Default font used to display the optional CHECKBOX text.
S	`CHECKBOX_IMAGE0_DEFAULT`	(see table above)	Pointer to bitmap used to draw the widget if checked, disabled state.
S	`CHECKBOX_IMAGE1_DEFAULT`	(see table above)	Pointer to bitmap used to draw the widget if checked, enabled state.
N	`CHECKBOX_SPACING_DEFAULT`	4	Spacing used to display the optional CHECKBOX text beside the box.
N	`CHECKBOX_TEXTALIGN_DEFAULT`	`GUI_TA_LEFT | GUI_TA_VCENTER`	Default alignment of the optional CHECKBOX text.

 © 2020 SEGGER Microcontroller GmbH

Type	Macro	Default	Description
N	CHECKBOX_TEXTCOLOR_DEFAULT	GUI_BLACK	Default color used to display the optional CHECKBOX text.

20.6.2 Predefined IDs

The following symbols define IDs which may be used to make CHECKBOX widgets distinguishable from creation.

```
#define GUI_ID_CHECK0    0x120
#define GUI_ID_CHECK1    0x121
#define GUI_ID_CHECK2    0x122
#define GUI_ID_CHECK3    0x123
#define GUI_ID_CHECK4    0x124
#define GUI_ID_CHECK5    0x125
#define GUI_ID_CHECK6    0x126
#define GUI_ID_CHECK7    0x127
#define GUI_ID_CHECK8    0x128
#define GUI_ID_CHECK9    0x129
```

20.6.3 Notification codes

The following events are sent from a check box widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	CHECKBOX has been clicked.
WM_NOTIFICATION_RELEASED	CHECKBOX has been released.
WM_NOTIFICATION_MOVED_OUT	CHECKBOX has been clicked and pointer has been moved out of the box without releasing.
WM_NOTIFICATION_VALUE_CHANGED	Status of CHECKBOX has been changed.

20.6.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Message	Description
GUI_KEY_SPACE	Toggles the checked state of the CHECKBOX widget.

20.6.5 CHECKBOX API

The table below lists the available emWin CHECKBOX-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
CHECKBOX_Check()	Set the state of CHECKBOX to checked. (Obsolete)
CHECKBOX_Create()	Creates a CHECKBOX widget. (Obsolete)
CHECKBOX_CreateEx()	Creates a CHECKBOX widget.
CHECKBOX_CreateIndirect()	Creates a CHECKBOX widget from resource table entry.
CHECKBOX_CreateUser()	Creates a CHECKBOX widget using extra bytes as user data.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
CHECKBOX_GetBkColor()	Returns the currently set background color of the CHECKBOX widget.
CHECKBOX_GetBoxBkColor()	Returns the currently set background color used in the box of the CHECKBOX widget.
CHECKBOX_GetDefaultAlign()	Returns the default text alignment used for CHECKBOX widgets.
CHECKBOX_GetDefaultBkColor()	Returns the default background color of new CHECKBOX widgets.
CHECKBOX_GetDefaultFont()	Returns a pointer to a GUI_FONT structure used to display the text of new CHECKBOX widgets.
CHECKBOX_GetDefaultSpacing()	Returns the default spacing between box and text used to display the text of new CHECKBOX widgets.
CHECKBOX_GetDefaultTextAlign()	Returns the default alignment used to display the text of CHECKBOX widgets.
CHECKBOX_GetDefaultTextColor()	Returns the default text color used to display the text of new CHECKBOX widgets.
CHECKBOX_GetFocusColor()	This function returns the color currently used as focus color.
CHECKBOX_GetFont()	Returns the currently set font.
CHECKBOX_GetImage()	Returns the image set for the given index.
CHECKBOX_GetState()	Returns the current state of the given CHECKBOX widget.
CHECKBOX_GetText()	Returns the optional text of the given CHECKBOX widget.
CHECKBOX_GetTextAlign()	This function returns the text alignment of the given TEXT widget.
CHECKBOX_GetTextColor()	This function returns the color currently used the text.
CHECKBOX_GetUserData()	Retrieves the data set with CHECKBOX_SetUserData().
CHECKBOX_IsChecked()	Returns the current state (checked or not checked) of a specified CHECKBOX widget.
CHECKBOX_SetBkColor()	Sets the background color used to display the background of the CHECKBOX widget.
CHECKBOX_SetBoxBkColor()	Sets the background color of the box area. (Obsolete)
CHECKBOX_SetDefaultAlign()	Sets the default text alignment used for new CHECKBOX widgets.
CHECKBOX_SetDefaultBkColor()	Sets the default background color used for new CHECKBOX widgets.
CHECKBOX_SetDefaultFocusColor()	Sets the color used to render the focus rectangle of new CHECKBOX widgets.
CHECKBOX_SetDefaultFont()	Sets a pointer to a GUI_FONT structure used to display the text of new CHECKBOX widgets.
CHECKBOX_SetDefaultImage()	Sets the default image to be shown when a box has been checked.
CHECKBOX_SetDefaultSpacing()	Sets the default spacing between box and text used to display the text of new CHECKBOX widgets.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
CHECKBOX_SetDefaultTextAlign()	Sets the default alignment used to display the text of CHECKBOX widgets.
CHECKBOX_SetDefaultTextColor()	Sets the default text color used to display the text of new CHECKBOX widgets.
CHECKBOX_SetFocusColor()	Sets the color of the focus rectangle.
CHECKBOX_SetFont()	Sets the font of the CHECKBOX widget.
CHECKBOX_SetImage()	Sets the image to be shown when CHECKBOX widget been checked.
CHECKBOX_SetNumStates()	Sets the number of possible states of the CHECKBOX widget (2 or 3).
CHECKBOX_SetSpacing()	Sets the spacing between the box and the check box text.
CHECKBOX_SetState()	Sets the state of the CHECKBOX widget.
CHECKBOX_SetText()	Sets the text of the CHECKBOX widget.
CHECKBOX_SetTextAlign()	Sets the alignment used to display the text of the CHECKBOX widget.
CHECKBOX_SetTextColor()	Sets the color used to display the text of the CHECKBOX widget.
CHECKBOX_SetUserData()	Sets the extra data of a CHECKBOX widget.
CHECKBOX_Uncheck()	Set the state of CHECKBOX to unchecked. (Obsolete)

Defines

Group of defines	Description
CHECKBOX bitmap indexes	Bitmap indexes for CHECKBOX widget.
CHECKBOX color indexes	Color indexes for CHECKBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1 Functions

20.6.5.1.1 CHECKBOX_Check()

> **Note**
>
> This function is **deprecated**, `CHECKBOX_SetState()` should be used instead.

Before	After
	

Description

Sets the state of a specified CHECKBOX widget to checked.

Prototype

```
void CHECKBOX_Check(CHECKBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.2 CHECKBOX_Create()

> **Note**
>
> This function is **deprecated**, `CHECKBOX_CreateEx()` should be used instead.

Description

Creates a CHECKBOX widget of a specified size at a specified location.

Prototype

```
CHECKBOX_Handle CHECKBOX_Create(int     x0,
                                int     y0,
                                int     xSize,
                                int     ySize,
                                WM_HWIN hParent,
                                int     Id,
                                int     Flags);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the check box (in parent coordinates).
`y0`	Topmost pixel of the check box (in parent coordinates).
`xSize`	Horizontal size of the check box (in pixels).
`ySize`	Vertical size of the check box (in pixels).
`hParent`	Handle of parent window.
`Id`	ID to be returned.
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).

Return value

Handle of the created CHECKBOX widget; 0 if the function fails.

Additional information

If the parameters `xSize` or `ySize` are 0 the size of the bitmap will be used as default size of the check box.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.3 CHECKBOX_CreateEx()

Description

Creates a CHECKBOX widget of a specified size at a specified location.

Prototype

```
CHECKBOX_Handle CHECKBOX_CreateEx(int     x0,
                                  int     y0,
                                  int     xSize,
                                  int     ySize,
                                  WM_HWIN hParent,
                                  int     WinFlags,
                                  int     ExFlags,
                                  int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the check box (in parent coordinates).
y0	Topmost pixel of the check box (in parent coordinates).
xSize	Horizontal size of the check box (in pixels).
ySize	Vertical size of the check box (in pixels).
hParent	Handle of parent window.
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used yet, reserved for future use.
Id	ID to be returned.

Return value

Handle of the created CHECKBOX widget; 0 if the function fails.

Additional information

If the parameters xSize or ySize are 0 the size of the default check mark bitmap (11 × 11 pixels) plus the effect size will be used as default size of the check box. If the desired size of the check box is different to the default size it can be useful to set a user defined check mark image using the function CHECKBOX_SetImage().

If check box text should be shown with the widget the size should be large enough to show the box + text + spacing between box and text.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.4 CHECKBOX_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The elements `Flags` and `Para` of the according `GUI_WIDGET_CREATE_INFO` structure are not used.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.5 CHECKBOX_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function CHECKBOX_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.6 CHECKBOX_GetBkColor()

Description

Returns the currently set background color of the CHECKBOX widget.

Prototype

```
GUI_COLOR CHECKBOX_GetBkColor(CHECKBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.

Return value

The color currently used as background color.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.7 CHECKBOX_GetBoxBkColor()

Description

Returns the currently set background color used in the box of the CHECKBOX widget.

Prototype

```
GUI_COLOR CHECKBOX_GetBoxBkColor(CHECKBOX_Handle hObj,
                                 int             Index);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
Index	See *Checkbox color indexes* on page for a full list of permitted values.

Return value

Background color used for the corresponding state.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.8 CHECKBOX_GetDefaultAlign()

Description

Returns the default text alignment used for CHECKBOX widgets.

Prototype

```
int CHECKBOX_GetDefaultAlign(void);
```

Return value

Default text alignment. Refer to *Text alignment flags* on page 218 a list of permitted values.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.9 CHECKBOX_GetDefaultBkColor()

Description

Returns the default background color of new CHECKBOX widgets.

Prototype

```
GUI_COLOR CHECKBOX_GetDefaultBkColor(void);
```

Return value

Default background color of new CHECKBOX widgets.

Additional information

The background color returned by this function is not the background color shown in the box, but the background color of the rest of the widget.

For more information, refer to `CHECKBOX_SetBoxBkColor()`.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.10 CHECKBOX_GetDefaultFont()

Description

Returns a pointer to a GUI_FONT structure used to display the text of new CHECKBOX widgets.

Prototype

```
GUI_FONT *CHECKBOX_GetDefaultFont(void);
```

Return value

Pointer to a GUI_FONT structure used to display the text of new CHECKBOX widgets.

Additional information

For more information, refer to CHECKBOX_SetFont().

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.11 CHECKBOX_GetDefaultSpacing()

Description

Returns the default spacing between box and text used to display the text of new CHECKBOX widgets.

Prototype

```
int CHECKBOX_GetDefaultSpacing(void);
```

Return value

Default spacing between box and text used to display the text of new CHECKBOX widgets.

Additional information

For more information, refer to `CHECKBOX_SetSpacing()`.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.12 CHECKBOX_GetDefaultTextAlign()

Description

Returns the default alignment used to display the text of new CHECKBOX widgets.

Prototype

```
int CHECKBOX_GetDefaultAlign(void);
```

Return value

Default alignment used to display the text of new CHECKBOX widgets.

Additional information

For more information, refer to *CHECKBOX_SetTextAlign()* on page .

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.13 CHECKBOX_GetDefaultTextColor()

Description

Returns the default text color used to display the text of new CHECKBOX widgets.

Prototype

```
GUI_COLOR CHECKBOX_GetDefaultTextColor(void);
```

Return value

Default text color used to display the text of new check box widgets.

Additional information

For more information, refer to `CHECKBOX_SetTextColor()`.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.14 CHECKBOX_GetFocusColor()

Description

This function returns the color currently used as focus color.

Prototype

```
GUI_COLOR CHECKBOX_GetFocusColor(CHECKBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.

Return value

The color currently used to draw the focus.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.15 CHECKBOX_GetFont()

Description

Returns the currently set font.

Prototype

```
GUI_FONT *CHECKBOX_GetFont(CHECKBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.

Return value

A pointer the font which is used for the CHECKBOX.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.16 CHECKBOX_GetImage()

Description

Returns the image set for the given index.

Prototype

```
GUI_BITMAP *CHECKBOX_GetImage(CHECKBOX_Handle hObj,
                              unsigned int    Index);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
Index	See *Checkbox bitmap indexes* on page for a full list of permitted values.

Return value

A pointer the image used with the given index.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.17 CHECKBOX_GetState()

Description

Returns the current state of the given CHECKBOX widget.

Prototype

```
int CHECKBOX_GetState(CHECKBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.

Return value

Current state of the given CHECKBOX widget.

Additional information

Per default a check box can have 2 states, checked (1) and unchecked (0). With the function CHECKBOX_SetNumStates() the number of possible states can be increased to 3. If the check box is in the third state the function returns 2.
For more information, refer to CHECKBOX_SetNumStates().

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.18 CHECKBOX_GetText()

Description

Returns the optional text of the given CHECKBOX widget.

Prototype

```
int CHECKBOX_GetText(CHECKBOX_Handle   hObj,
                     char            * pBuffer,
                     int               MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
pBuffer	Pointer to buffer to which the text will be copied.
MaxLen	Buffer size in bytes.

Return value

Length of the text copied into the buffer.

Additional information

If the CHECKBOX widget contains no text the function returns 0 and the buffer remains unchanged.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.19 CHECKBOX_GetTextAlign()

Description

This function returns the text alignment of the given TEXT widget.

Prototype

```
int CHECKBOX_GetTextAlign(CHECKBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.

Return value

Returns the currently used text alignment.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.20 CHECKBOX_GetTextColor()

Description

This function returns the color currently used the text.

Prototype

```
GUI_COLOR CHECKBOX_GetTextColor(CHECKBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.

Return value

The color currently used displaying the text.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.21 CHECKBOX_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.22 CHECKBOX_IsChecked()

Description

Returns the current state (checked or not checked) of a specified CHECKBOX widget.

Prototype

```
int CHECKBOX_IsChecked(CHECKBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.

Return value

0 not checked
1 checked

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.23 CHECKBOX_SetBkColor()

Before	After
	

Description

Sets the background color used to display the background of the CHECKBOX widget.

Prototype

```
void CHECKBOX_SetBkColor(CHECKBOX_Handle hObj,
                         GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
Color	Color to be used to draw the background or GUI_INVALID_COLOR to work in transparent mode.

Additional information

If the check box should work in transparent mode GUI_INVALID_COLOR should be used.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.24 CHECKBOX_SetBoxBkColor()

> **Note**
>
> This function is **deprecated** and only works in conjunction with the classic skin (`CHECKBOX_SetSkinClassic()`). Skinning props should be used instead which can be set via `CHECKBOX_SetSkinFlexProps()`.

Before	After
	

Description

Sets the background color of the box area.

Prototype

```
GUI_COLOR CHECKBOX_SetBoxBkColor(CHECKBOX_Handle hObj,
                                 GUI_COLOR       Color,
                                 int             Index);
```

Parameters

Parameter	Description
`hObj`	Handle of CHECKBOX widget.
`Color`	`Color` to be used.
`Index`	See *Checkbox color indexes* on page for a full list of permitted values.

Return value

Previous background color.

Additional information

The color set by this function will only be visible, if the images used by the widget are transparent or no image is used. The default images of this widget are transparent.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.25 CHECKBOX_SetDefaultAlign()

Description

Sets the default text alignment used for new CHECKBOX widgets.

Prototype

```
void CHECKBOX_SetDefaultAlign(int Align);
```

Parameters

Parameter	Description
Align	Text alignment flags. See *Text alignment flags* on page 218 for a full list of permitted values.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.26 CHECKBOX_SetDefaultBkColor()

Description

Sets the default background color used for new CHECKBOX widgets.

Prototype

```
void CHECKBOX_SetDefaultBkColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color to be used, GUI_INVALID_COLOR for transparency.

Additional information

For more information, refer to CHECKBOX_SetBkColor.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.27 CHECKBOX_SetDefaultFocusColor()

Description

Sets the color used to render the focus rectangle of new CHECKBOX widgets.

Prototype

```
GUI_COLOR CHECKBOX_SetDefaultFocusColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color to be used.

Return value

Previous color used to render the focus rectangle.

Additional information

For mode information, refer to CHECKBOX_SetFocusColor().

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.28 CHECKBOX_SetDefaultFont()

Description

Sets a pointer to a GUI_FONT structure used to display the text of new CHECKBOX widgets.

Prototype

```
void CHECKBOX_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to GUI_FONT structure to be used.

Additional information

For mode information, refer to CHECKBOX_SetFont().

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.29 CHECKBOX_SetDefaultImage()

Description

Sets the images used for new CHECKBOX widgets to be shown if they has been checked.

Prototype

```
void CHECKBOX_SetDefaultImage(const GUI_BITMAP   * pBitmap,
                              unsigned int   Index);
```

Parameters

Parameter	Description
pBitmap	Pointer to bitmap.
Index	See *Checkbox bitmap indexes* on page for a full list of permitted values.

Additional information

The image has to fill the complete inner area of the CHECKBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.30 CHECKBOX_SetDefaultSpacing()

Description

Sets the default spacing between box and text used to display the text of new CHECKBOX widgets.

Prototype

```
void CHECKBOX_SetDefaultSpacing(int Spacing);
```

Parameters

Parameter	Description
Spacing	Number of pixels between box and text used for new CHECKBOX widgets.

Additional information

For more information, refer to CHECKBOX_SetSpacing().

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.31 CHECKBOX_SetDefaultTextAlign()

Description

Sets the default alignment used to display the text of new CHECKBOX widgets.

Prototype

```
void CHECKBOX_SetDefaultTextAlign(int Align);
```

Parameter	Description
Align	Text alignment mode. List of flags can be found under *Text alignment flags* on page 218.

Additional information

For more information, refer to *CHECKBOX_SetTextAlign()* on page .

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.32 CHECKBOX_SetDefaultTextColor()

Description

Sets the default text color used to display the text of new CHECKBOX widgets.

Prototype

```
void CHECKBOX_SetDefaultTextColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color to be used.

Additional information

For more information, refer to CHECKBOX_SetTextColor().

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.33 CHECKBOX_SetFocusColor()

Before	After
	

Description

Sets the color used to render the focus rectangle.

Prototype

```
GUI_COLOR CHECKBOX_SetFocusColor(CHECKBOX_Handle hObj,
                                 GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
Color	Color to be used.

Return value

Previous color of the focus rectangle.

Additional information

The focus rectangle is only visible if the widget has the input focus.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.34 CHECKBOX_SetFont()

Description

Sets the font of the CHECKBOX widget.

Prototype

```
void CHECKBOX_SetFont(      CHECKBOX_Handle   hObj,
                      const GUI_FONT        * pFont);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
pFont	Pointer to the font.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.35 CHECKBOX_SetImage()

Before	After
	
	

Description

Sets the images to be shown if the CHECKBOX widget has been checked.

Prototype

```
void CHECKBOX_SetImage(      CHECKBOX_Handle   hObj,
                       const GUI_BITMAP      * pBitmap,
                             unsigned int      Index);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
pBitmap	Pointer to bitmap.
Index	See *Checkbox bitmap indexes* on page for a full list of permitted values.

Additional information

The image has to fill the complete inner area of the check box. If using this function make sure, the size of the check box used to create the widget is large enough to show the bitmap and (optional) the text.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.36 CHECKBOX_SetNumStates()

Description

This function sets the number of possible states of the given CHECKBOX widget.

Prototype

```
void CHECKBOX_SetNumStates(CHECKBOX_Handle hObj,
                           unsigned        NumStates);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
NumStates	Number of possible states of the given check box. Currently supported are 2 or 3 states.

Additional information

Per default a check box supports 2 states: checked (1) and unchecked (0). If the check box should support a third state the number of possible states can be increased to 3.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.37 CHECKBOX_SetSpacing()

Before	After
	

Description

Sets the number of pixels between box and text of a given CHECKBOX widget.

Prototype

```
void CHECKBOX_SetSpacing(CHECKBOX_Handle hObj,
                         unsigned        Spacing);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
Spacing	Number of pixels between box and text to be used.

Additional information

The default spacing is 4 pixels. The function `CHECKBOX_SetDefaultSpacing()` or the configuration macro `CHECKBOX_SPACING_DEFAULT` can be used to set the default value.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.38 CHECKBOX_SetState()

Before	After
	

Description

Sets the new state of the given CHECKBOX widget.

Prototype

```
void CHECKBOX_SetState(CHECKBOX_Handle hObj,
                       unsigned        State);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
State	Zero-based number of new state.

Permitted values for parameter State	
0	Unchecked
1	Checked
2	Third state

Additional information

The passed state should not be greater than the number of possible states set with CHECKBOX_SetNumStates() minus 1.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.39 CHECKBOX_SetText()

Before	After
	

Description

Sets the optional text shown beside the box.

Prototype

```
void CHECKBOX_SetText(      CHECKBOX_Handle   hObj,
                      const char            * s);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
s	Pointer to text to be shown beside the box.

Additional information

Clicking on the text beside the box has the same effect as clicking into the box.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.40 CHECKBOX_SetTextAlign()

Before	After
	

Description

Sets the alignment used to display the text beside the box.

Prototype

```
void CHECKBOX_SetTextAlign(CHECKBOX_Handle hObj,
                           int             Align);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
Align	Text alignment mode. List of flags can be found under *Text alignment flags* on page 218.

Additional information

Per default the text alignment is GUI_TA_LEFT | GUI_TA_VCENTER. The function CHECKBOX_SetDefaultTextAlign() and the configuration macro CHECKBOX_TEXTALIGN_DEFAULT can be used to set a user defined default value.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.41 CHECKBOX_SetTextColor()

Before	After
	

Description

Sets the color used to display the text of the CHECKBOX widget.

Prototype

```
void CHECKBOX_SetTextColor(CHECKBOX_Handle hObj,
                           GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of CHECKBOX widget.
Color	Desired color of check box text.

Additional information

Per default the text color of a check box text is GUI_BLACK. The function CHECKBOX_SetDefaultTextColor() and the configuration macro CHECKBOX_TEXTCOLOR_DEFAULT can be used to set a user defined default color.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.42 CHECKBOX_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.1.43 CHECKBOX_Uncheck()

> **Note**
>
> This function is **deprecated**, `CHECKBOX_SetState()` should be used instead.

Before	After
	

Description

Sets the state of a specified CHECKBOX widget to unchecked.

Prototype

```
void CHECKBOX_Uncheck(CHECKBOX_Handle hObj);
```

Parameter	Description
hObj	Handle of CHECKBOX widget.

Additional information

This is the default setting for CHECKBOX widgets.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.2 Defines

20.6.5.2.1 CHECKBOX bitmap indexes

Description

Bitmap indexes for CHECKBOX widget.

Definition

```
#define CHECKBOX_BI_INACTIV_UNCHECKED    0
#define CHECKBOX_BI_ACTIV_UNCHECKED      1
#define CHECKBOX_BI_INACTIV_CHECKED      2
#define CHECKBOX_BI_ACTIV_CHECKED        3
#define CHECKBOX_BI_INACTIV_3STATE       4
#define CHECKBOX_BI_ACTIV_3STATE         5
```

Symbols

Definition	Description
CHECKBOX_BI_INACTIV_UNCHECKED	Bitmap displayed when the CHECKBOX is unchecked and disabled.
CHECKBOX_BI_ACTIV_UNCHECKED	Bitmap displayed when the CHECKBOX is unchecked and enabled.
CHECKBOX_BI_INACTIV_CHECKED	Bitmap displayed when the CHECKBOX is checked and disabled.
CHECKBOX_BI_ACTIV_CHECKED	Bitmap displayed when the CHECKBOX is checked and enabled.
CHECKBOX_BI_INACTIV_3STATE	Bitmap displayed when the CHECKBOX is in the third state and disabled.
CHECKBOX_BI_ACTIV_3STATE	Bitmap displayed when the CHECKBOX is in the third state and enabled.

 © 2020 SEGGER Microcontroller GmbH

20.6.5.2.2 CHECKBOX color indexes

Description

Color indexes for CHECKBOX widget.

Definition

```
#define CHECKBOX_CI_DISABLED    0
#define CHECKBOX_CI_ENABLED     1
```

Symbols

Definition	Description
CHECKBOX_CI_DISABLED	Color used for disabled state.
CHECKBOX_CI_ENABLED	Color used for enabled state.

 © 2020 SEGGER Microcontroller GmbH

20.6.6 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_Checkbox.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_Checkbox.c:



 © 2020 SEGGER Microcontroller GmbH

20.7 DROPDOWN: Dropdown widget

DROPDOWN widgets are used to select one element of a list with several columns. It shows the currently selected item in non open state. If the user opens a DROPDOWN widget a LISTBOX appears to select a new item.

DROPDOWN closed	DROPDOWN opened
	

Note

All DROPDOWN-related routines are located in the file(s) `DROPDOWN*.c`, `DROPDOWN.h`. All identifiers are prefixed DROPDOWN.

If mouse support is enabled, the open list reacts on moving the mouse over it.

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.7.1 Configuration options

Type	Macro	Default	Description
N	DROPDOWN_ALIGN_DEFAULT	GUI_TA_LEFT	Text alignment used to display the dropdown text in closed state.
S	DROPDOWN_FONT_DEFAULT	&GUI_Font13_1	Default font.
N	DROPDOWN_BKCOLOR0_DEFAULT	GUI_WHITE	Background color, unselected state.
N	DROPDOWN_BKCOLOR1_DEFAULT	GUI_GRAY	Background color, selected state without focus.
N	DROPDOWN_BKCOLOR2_DEFAULT	GUI_BLUE	Background color, selected state with focus.
N	DROPDOWN_KEY_EXPAND	GUI_KEY_SPACE	Key which can be used to expand the DROPDOWN list.
N	DROPDOWN_KEY_SELECT	GUI_KEY_ENTER	Key which can be used to select an item from the open dropdown list.
N	DROPDOWN_TEXTCOLOR0_DEFAULT	GUI_BLACK	Text color, unselected state.
N	DROPDOWN_TEXTCOLOR1_DEFAULT	GUI_BLACK	Text color, selected state without focus.
N	DROPDOWN_TEXTCOLOR2_DEFAULT	GUI_WHITE	Enable 3D support.

 © 2020 SEGGER Microcontroller GmbH

20.7.2 Predefined IDs

The following symbols define IDs which may be used to make DROPDOWN widgets distinguishable from creation.

```
#define GUI_ID_DROPDOWN0    0x180
#define GUI_ID_DROPDOWN1    0x181
#define GUI_ID_DROPDOWN2    0x182
#define GUI_ID_DROPDOWN3    0x183
#define GUI_ID_DROPDOWN4    0x184
#define GUI_ID_DROPDOWN5    0x185
#define GUI_ID_DROPDOWN6    0x186
#define GUI_ID_DROPDOWN7    0x187
#define GUI_ID_DROPDOWN8    0x188
#define GUI_ID_DROPDOWN9    0x189
```

20.7.3 Notification codes

The following events are sent from the widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	DROPDOWN has been clicked.
WM_NOTIFICATION_RELEASED	DROPDOWN has been released.
WM_NOTIFICATION_MOVED_OUT	DROPDOWN has been clicked and pointer has been moved out of the widget without releasing.
WM_NOTIFICATION_SCROLL_CHANGED	The scroll position of the optional scroll bar of the opened DROPDOWN widget has been changed.
WM_NOTIFICATION_SEL_CHANGED	The selection of the DROPDOWN list has been changed.

20.7.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_ENTER	Selects an item from the open DROPDOWN list and closes the list.
GUI_KEY_SPACE	Opens the DROPDOWN list.

20.7.5 DROPDOWN API

The table below lists the available emWin DROPDOWN-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
DROPDOWN_AddString()	Adds a new element to the DROPDOWN widget.
DROPDOWN_Collapse()	Closes the DROPDOWN list.
DROPDOWN_Create()	Creates a DROPDOWN widget. (Obsolete)
DROPDOWN_CreateEx()	Creates a DROPDOWN widget.
DROPDOWN_CreateIndirect()	Creates a DROPDOWN widget from a resource table entry.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
DROPDOWN_CreateUser()	Creates a DROPDOWN widget using extra bytes as user data.
DROPDOWN_DecSel()	Decrements selection.
DROPDOWN_DecSelExp()	Decrements selection in expanded state.
DROPDOWN_DeleteItem()	Deletes the given item of the DROPDOWN widget.
DROPDOWN_Expand()	Opens the list of the DROPDOWN widget.
DROPDOWN_GetBkColor()	Returns the background color of the given DROPDOWN widget.
DROPDOWN_GetColor()	Returns the color used for either the button or the arrow.
DROPDOWN_GetDefaultFont()	Returns the default font of DROPDOWN widgets.
DROPDOWN_GetFont()	Returns the font currently used by the widget.
DROPDOWN_GetItemDisabled()	Returns the state of the given item.
DROPDOWN_GetItemText()	Returns the text of a specific item of the given DROPDOWN widget.
DROPDOWN_GetListbox()	Returns the handle of the attached LISTBOX widget in expanded state.
DROPDOWN_GetNumItems()	Returns the number of items in the given DROPDOWN widget.
DROPDOWN_GetSel()	Returns the number of the currently selected item in a specified DROPDOWN widget.
DROPDOWN_GetSelExp()	Returns the index of the currently selected item of the attached LISTBOX in expanded state.
DROPDWON_GetTextColor()	Returns the color of the text.
DROPDOWN_GetUserData()	Retrieves the data set with DROPDOWN_SetUserData().
DROPDOWN_IncSel()	Increments selection.
DROPDOWN_IncSelExp()	Increments selection in expanded state.
DROPDOWN_InsertString()	Inserts a string to the DROPDOWN widget at the given position.
DROPDOWN_SetAutoScroll()	Enables the automatic use of a vertical scroll bar in the DROPDOWN widget.
DROPDOWN_SetBkColor()	Sets the background color of the given DROPDOWN widget.
DROPDOWN_SetColor()	Sets the color of the button or the arrow of the given DROPDOWN widget.
DROPDOWN_SetDefaultColor()	Sets the default colors for the arrow and the button of new DROPDOWN widgets.
DROPDOWN_SetDefaultFont()	Sets the default font used for new DROPDOWN widgets.
DROPDOWN_SetDefaultScrollbarColor()	Sets the default colors used for the optional scroll bar in the DROPDOWN widget.
DROPDOWN_SetFont()	Sets the font used to display the given DROPDOWN widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
DROPDOWN_SetItemDisabled()	Sets the enabled state of the given item.
DROPDOWN_SetItemSpacing()	Sets an additional spacing below the items of the DROPDOWN widget.
DROPDOWN_SetListHeight()	Sets the height in pixels to be used for the expanded list of the DROPDOWN widget.
DROPDOWN_SetScrollbarColor()	Sets the colors of the optional scroll bar in the DROPDOWN widget.
DROPDOWN_SetScrollbarWidth()	Sets the width of the scroll bars used by the list of the given DROPDOWN widget.
DROPDOWN_SetSel()	Sets the current selection.
DROPDOWN_SetSelExp()	Sets the selected item of the attached LISTBOX in expanded state.
DROPDOWN_SetTextAlign()	Sets the alignment used to display the text of the DROPDOWN widget in closed state.
DROPDOWN_SetTextColor()	Sets the text color of the given DROP-DOWN widget.
DROPDOWN_SetTextHeight()	Sets the height of the rectangle used to display the dropdown text in closed state.
DROPDOWN_SetUpMode()	Enables opening of the list to the upper side of the DROPDOWN widget.
DROPDOWN_SetUserData()	Sets the extra data of a DROPDOWN wid-get.

Defines

Group of defines	Description
CHECKBOX bitmap indexes	Bitmap indexes for CHECKBOX widget.
CHECKBOX color indexes	Color indexes for CHECKBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1 Functions

20.7.5.1.1 DROPDOWN_AddString()

Description

Adds a new element to the DROPDOWN widget.

Prototype

```
void DROPDOWN_AddString(      DROPDOWN_Handle   hObj,
                        const char            * s);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
s	Pointer to string to be added

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.2 DROPDOWN_Collapse()

Description

Closes the dropdown list of the DROPDOWN widget.

Prototype

```
void DROPDOWN_Collapse(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.3 DROPDOWN_Create()

> **Note**
>
> This function is **deprecated**, `DROPDOWN_CreateEx()` should be used instead.

Description

Creates a DROPDOWN widget of a specified size at a specified location.

Prototype

```
DROPDOWN_Handle DROPDOWN_Create(WM_HWIN hWinParent,
                                int     x0,
                                int     y0,
                                int     xSize,
                                int     ySize,
                                int     Flags);
```

Parameters

Parameter	Description
`hWinParent`	Handle of parent window
`x0`	Leftmost pixel of the DROPDOWN widget (in parent coordinates).
`y0`	Topmost pixel of the DROPDOWN widget (in parent coordinates).
`xSize`	Horizontal size of the DROPDOWN widget (in pixels).
`ySize`	Vertical size of the DROPDOWN widget in open state (in pixels).
`Flags`	Window create flags. Typically, `WM_CF_SHOW` to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).

Return value

Handle of the created DROPDOWN widget; 0 if the function fails.

Additional information

The `ySize` of the widget in closed state depends on the font used to create the widget. You can not set the `ySize` of a closed DROPDOWN widget.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.4 DROPDOWN_CreateEx()

Description

Creates a DROPDOWN widget of a specified size at a specified location.

Prototype

```
DROPDOWN_Handle DROPDOWN_CreateEx(int     x0,
                                  int     y0,
                                  int     xSize,
                                  int     ySize,
                                  WM_HWIN hParent,
                                  int     WinFlags,
                                  int     ExFlags,
                                  int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the DROPDOWN widget (in parent coordinates).
y0	Topmost pixel of the DROPDOWN widget (in parent coordinates).
xSize	Horizontal size of the DROPDOWN widget (in pixels).
ySize	Vertical size of the DROPDOWN widget in open state (in pixels).
hParent	Handle of parent window. If 0, the new DROPDOWN widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *DROPDOWN create flags* on page 1132.
Id	Window ID of the widget.

Return value

Handle of the created DROPDOWN widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.5 DROPDOWN_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Para` of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element `Flags` is used according to the parameter `ExFlags` of the function `DROPDOWN_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.6 DROPDOWN_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function DROPDOWN_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.7 DROPDOWN_DecSel()

Description

Decrement the selection, moves the selection of a specified DROPDOWN widget up by one item.

Prototype

```
void DROPDOWN_DecSel(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.8 DROPDOWN_DecSelExp()

Description

Decrements the selection of the attached LISTBOX in expanded state.

Prototype

```
void DROPDOWN_DecSelExp(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.9 DROPDOWN_DeleteItem()

Description

Deletes the given item of the DROPDOWN widget.

Prototype

```
void DROPDOWN_DeleteItem(DROPDOWN_Handle hObj,
                         unsigned int    Index);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
Index	Zero based index of the item to be deleted.

Additional information

If the index is greater than the number of items < 1 the function returns immediately.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.10 DROPDOWN_Expand()

Description

Opens the list of the DROPDOWN widget.

Prototype

```
void DROPDOWN_Expand(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.

Additional information

The DROPDOWN list remains open until an element has been selected or the focus has been lost.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.11 DROPDOWN_GetBkColor()

Description

Returns the background color of the given DROPDOWN widget.

Prototype

```
GUI_COLOR DROPDOWN_GetBkColor(DROPDOWN_Handle hObj,
                              unsigned int    Index);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
Index	Index for background color. See *DROPDOWN color indexes* on page 1131 for a full list of permitted values.

Return value

The background color used with the corresponding index value.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.12 DROPDOWN_GetColor()

Description

Returns the color used for either the button or the arrow.

Prototype

```
GUI_COLOR DROPDOWN_GetColor(DROPDOWN_Handle hObj,
                            unsigned int    Index);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
Index	Index for background color. See table below.

Permitted values for parameter Index	
DROPDOWN_CI_ARROW	Color of small arrow within the button.
DROPDOWN_CI_BUTTON	Button color.

Return value

The color of the button or the arrow.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.13 DROPDOWN_GetDefaultFont()

Description

Returns the default font of DROPDOWN widgets.

Prototype

```
GUI_FONT *DROPDOWN_GetDefaultFont(void);
```

Return value

Returns a pointer to the default font used by DROPDOWN widgets.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.14 DROPDOWN_GetFont()

Description

Returns the font currently used by the widget.

Prototype

```
GUI_FONT *DROPDOWN_GetFont(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget

Return value

A pointer to the currently set font.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.15 DROPDOWN_GetItemDisabled()

Description

Returns the state of the given item.

Prototype

```
unsigned DROPDOWN_GetItemDisabled(DROPDOWN_Handle hObj,
                                  unsigned        Index);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Index	Zero-based index of the item.

Return value

1 if the given item is disabled
0 if not.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.16 DROPDOWN_GetItemText()

Description

Returns the text of a specific item of the given DROPDOWN widget.

Prototype

```
int DROPDOWN_GetItemText(DROPDOWN_Handle   hObj,
                         unsigned          Index,
                         char            * pBuffer,
                         int               MaxSize);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Index	Zero-based index of the item.
pBuffer	Pointer to a char buffer which is filled with the text.
MaxSize	Maximum number of chars which can be stored by pBuffer.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.17 DROPDOWN_GetListbox()

Description

Returns the handle of the attached LISTBOX widget in expanded state.

Prototype

```
LISTBOX_Handle DROPDOWN_GetListbox(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.

Return value

Handle of the attached LISTBOX widget in expanded state, 0 if DROPDOWN is in collapsed state.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.18 DROPDOWN_GetNumItems()

Description

Returns the number of items in the given DROPDOWN widget.

Prototype

```
int DROPDOWN_GetNumItems(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.

Return value

Number of items in the given DROPDOWN widget.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.19 DROPDOWN_GetSel()

Description

Returns the number of the currently selected item in a specified DROPDOWN widget.

Prototype

```
int DROPDOWN_GetSel(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.

Return value

Number of the currently selected item.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.20 DROPDOWN_GetSelExp()

Description

Returns the index of the currently selected item of the attached LISTBOX in expanded state.

Prototype

```
int DROPDOWN_GetSelExp(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.

Return value

Index of the currently selected item.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.21 DROPDOWN_GetTextColor()

Description

Returns the color used for text to be displayed.

Prototype

```
GUI_COLOR DROPDOWN_GetTextColor(DROPDOWN_Handle hObj,
                                unsigned int    Index);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
Index	Index for background color. See *DROPDOWN color indexes* on page 1131 for a full list of permitted values.

Return value

The color of the text corresponding to the given index.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.22 DROPDOWN_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.23 DROPDOWN_IncSel()

Description

Increment the selection, moves the selection of a specified DROPDOWN widget down by one item.

Prototype

```
void DROPDOWN_IncSel(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.24 DROPDOWN_IncSelExp()

Description

Increments the selection of the attached LISTBOX in expanded state.

Prototype

```
void DROPDOWN_IncSelExp(DROPDOWN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.25 DROPDOWN_InsertString()

Description

Inserts a string to the DROPDOWN widget at the given position.

Prototype

```
void DROPDOWN_InsertString(      DROPDOWN_Handle   hObj,
                           const char            * s,
                                 unsigned int      Index);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
s	Pointer to the string to be inserted.
Index	Zero based index of the position.

Additional information

If the given index is greater than the number of items the string will be appended to the end of the dropdown list.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.26 DROPDOWN_SetAutoScroll()

Description

Enables the automatic use of a vertical scroll bar in the DROPDOWN widget.

Prototype

```
void DROPDOWN_SetAutoScroll(DROPDOWN_Handle hObj,
                            int             OnOff);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
OnOff	See table below.

Permitted values for parameter OnOff	
0	Disable automatic use of a scroll bar.
1	Enable automatic use of a scroll bar.

Additional information

If enabled the DROPDOWN widget checks if all elements fits into the listbox. If not a vertical scroll bar will be added.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.27 DROPDOWN_SetBkColor()

Before	After
	

Description

Sets the background color of the given DROPDOWN widget.

Prototype

```
void DROPDOWN_SetBkColor(DROPDOWN_Handle hObj,
                         unsigned int    Index,
                         GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
Index	Index for background color. See *DROPDOWN color indexes* on page 1131 for a full list of permitted values.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.28 DROPDOWN_SetColor()

Before	After
	

Description

Sets the color of the button or the arrow of the given DROPDOWN widget.

Prototype

```
void DROPDOWN_SetColor(DROPDOWN_Handle hObj,
                       unsigned int    Index,
                       GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
Index	Index of desired item. See table below.
Color	Color to be used.

Permitted values for parameter Index	
DROPDOWN_CI_ARROW	Color of small arrow within the button.
DROPDOWN_CI_BUTTON	Button color.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.29 DROPDOWN_SetDefaultColor()

Description

Sets the default colors for the arrow and the button of new DROPDOWN widgets.

Prototype

```
GUI_COLOR DROPDOWN_SetDefaultColor(int       Index,
                                   GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	Refer to DROPDOWN_SetColor().
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.30 DROPDOWN_SetDefaultFont()

Description

Sets the default font used for new DROPDOWN widgets.

Prototype

```
void DROPDOWN_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to GUI_FONT structure.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.31 DROPDOWN_SetDefaultScrollbarColor()

Description

Sets the default colors used for the optional scroll bar in the DROPDOWN widget.

Prototype

```
GUI_COLOR DROPDOWN_SetDefaultScrollbarColor(int       Index,
                                            GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	Refer to DROPDOWN_SetScrollbarColor().
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.32 DROPDOWN_SetFont()

Description

Sets the font used to display the given DROPDOWN widget.

Prototype

```
void DROPDOWN_SetFont(      DROPDOWN_Handle   hObj,
                      const GUI_FONT        * pFont);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
pFont	Pointer to the font.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.33 DROPDOWN_SetItemDisabled()

Before	After
	

Description

Sets the enabled state of the given item.

Prototype

```
void DROPDOWN_SetItemDisabled(DROPDOWN_Handle hObj,
                              unsigned        Index,
                              int             OnOff);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Index	Zero-based index of the item.
OnOff	1 for enabled, 0 for disabled.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.34 DROPDOWN_SetItemSpacing()

Before	After
	

Description

Sets an additional spacing below the items of the DROPDOWN widget.

Prototype

```
void DROPDOWN_SetItemSpacing(DROPDOWN_Handle hObj,
                             unsigned        Value);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Value	Number of pixels used as additional space between the items of the DROPDOWN widget.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.35 DROPDOWN_SetListHeight()

Description

Sets the height in pixels to be used for the expanded list of the DROPDOWN widget.

Prototype

```
int DROPDOWN_SetListHeight(DROPDOWN_Handle hObj,
                           unsigned        Height);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Height	Height to be used.

Return value

Previously used height for the DROPDOWN list in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.36 DROPDOWN_SetScrollbarColor()

Before	After
	

Description

Sets the colors of the optional scroll bar in the DROPDOWN widget.

Prototype

```
void DROPDOWN_SetScrollbarColor(DROPDOWN_Handle hObj,
                                unsigned        Index,
                                GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Index	Index of desired item. See *SCROLLBAR color indexes* on page 1939 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.37 DROPDOWN_SetScrollbarWidth()

Description

Sets the width of the scroll bars used by the list of the given DROPDOWN widget.

Prototype

```
void DROPDOWN_SetScrollbarWidth(DROPDOWN_Handle hObj,
                                unsigned        Width);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Width	Width of the scroll bar(s) used by the dropdown list of the given DROPDOWN widget.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.38 DROPDOWN_SetSel()

Description

Sets the selected item of a specified DROPDOWN widget.

Prototype

```
void DROPDOWN_SetSel(DROPDOWN_Handle hObj,
                     int             Sel);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Sel	Element to be selected.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.39 DROPDOWN_SetSelExp()

Description

Sets the selected item of the attached LISTBOX in expanded state.

Prototype

```
void DROPDOWN_SetSelExp(DROPDOWN_Handle hObj,
                        int             Sel);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Sel	Element to be selected.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.40 DROPDOWN_SetTextAlign()

Before	After
	

Description

Sets the alignment used to display the text of the DROPDOWN widget in closed state.

Prototype

```
void DROPDOWN_SetTextAlign(DROPDOWN_Handle hObj,
                           int             Align);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Align	Alignment used to display the dropdown text in closed state.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.41 DROPDOWN_SetTextColor()

Description

Sets the background color of the given DROPDOWN widget.

Prototype

```
void DROPDOWN_SetTextColor(DROPDOWN_Handle hObj,
                           unsigned int    Index,
                           GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
Index	Index for background color. See *DROPDOWN color indexes* on page 1131 for a full list of permitted values.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.42 DROPDOWN_SetTextHeight()

Before	After
	

Description

Sets the height of the rectangle used to display the text of DROPDOWN widget in closed state.

Prototype

```
void DROPDOWN_SetTextHeight(DROPDOWN_Handle hObj,
                            unsigned        TextHeight);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget.
TextHeight	Height of the rectangle used to display the text in closed state.

Additional information

Per default the height of the DROPDOWN widget depends on the used font. Using this function with `TextHeight > 0` means the given value should be used. `TextHeight = 0` means the default behavior should be used.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.43 DROPDOWN_SetUpMode()

Before	After
	

Description

Enables opening of the list to the upper side of the DROPDOWN widget.

Prototype

```
int DROPDOWN_SetUpMode(DROPDOWN_Handle hObj,
                       int             OnOff);
```

Parameters

Parameter	Description
hObj	Handle of DROPDOWN widget
OnOff	1 for enabling, 0 for disabling ’up mode’.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.1.44 DROPDOWN_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.2 Defines

20.7.5.2.1 DROPDOWN color indexes

Description

Color indexes for DROPDOWN widget.

Definition

```
#define DROPDOWN_CI_UNSEL       0
#define DROPDOWN_CI_SEL         1
#define DROPDOWN_CI_SELFOCUS    2
```

Symbols

Definition	Description
DROPDOWN_CI_UNSEL	Unselected element.
DROPDOWN_CI_SEL	Selected element, without focus.
DROPDOWN_CI_SELFOCUS	Selected element, with focus.

 © 2020 SEGGER Microcontroller GmbH

20.7.5.2.2 DROPDOWN create flags

Description

These flags can be used when creating a DROPDOWN widget via `DROPDOWN_CreateEx()`. 0 can be specified for the `ExFlags` parameter, if no flags should be used.

Definition

```
#define DROPDOWN_CF_AUTOSCROLLBAR    (1 << 0)
#define DROPDOWN_CF_UP               (1 << 1)
```

Symbols

Definition	Description
DROPDOWN_CF_AUTOSCROLLBAR	Enable automatic use of a scroll bar. For details, refer to `DROPDOWN_SetAutoScroll()`.
DROPDOWN_CF_UP	Creates a DROPDOWN widget which opens the dropdown list above the widget. This flag is useful if the space below the widget is not sufficient for the dropdown list.

 © 2020 SEGGER Microcontroller GmbH

20.7.6 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_Dropdown.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_Dropdown.c:



 © 2020 SEGGER Microcontroller GmbH

20.8 EDIT: Edit widget

EDIT widgets are commonly used as the primary user interface for text input:

Blank EDIT widget	EDIT widget with user input
	

You can also use EDIT widgets for entering values in binary, decimal, or hexadecimal modes. A decimal-mode edit field might appear similar to those in the following table. The background color of EDIT widgets by default turns gray if disabled:

EDIT widget with user input (decimal)	Disabled EDIT widget
	

Note

All EDIT-related routines are located in the file(s) `EDIT*.c`, `EDIT.h`.
All identifiers are prefixed EDIT.

20.8.1 Configuration options

Type	Macro	Default	Description
S	EDIT_ALIGN_DEFAULT	GUI_TA_RIGHT | GUI_TA_VCENTER	Text alignment for EDIT widget.
N	EDIT_BKCOLOR0_DEFAULT	0xc0c0c0	Background color, disabled state.
N	EDIT_BKCOLOR1_DEFAULT	GUI_WHITE	Background color, enabled state.
N	EDIT_BORDER_DEFAULT	1	Width of border, in pixels.
S	EDIT_FONT_DEFAULT	&GUI_Font13_1	Font used for edit field text.
N	EDIT_TEXTCOLOR0_DEFAULT	GUI_BLACK	Text color, disabled state.
N	EDIT_TEXTCOLOR1_DEFAULT	GUI_BLACK	Text color, enabled state.
N	EDIT_XOFF	2	Distance in X to offset text from left border of EDIT widget.

Available alignment flags are:

- `GUI_TA_LEFT`, `GUI_TA_RIGHT`, `GUI_TA_HCENTER` for **horizontal** alignment.
- `GUI_TA_TOP`, `GUI_TA_BOTTOM`, `GUI_TA_VCENTER` for **vertical** alignment.

20.8.2 Predefined IDs

The following symbols define IDs which may be used to make EDIT widgets distinguishable from creation.

```
#define GUI_ID_EDIT0    0x100
#define GUI_ID_EDIT1    0x101
#define GUI_ID_EDIT2    0x102
#define GUI_ID_EDIT3    0x103
#define GUI_ID_EDIT4    0x104
#define GUI_ID_EDIT5    0x105
#define GUI_ID_EDIT6    0x106
#define GUI_ID_EDIT7    0x107
#define GUI_ID_EDIT8    0x108
#define GUI_ID_EDIT9    0x109
```

 © 2020 SEGGER Microcontroller GmbH

20.8.3 Notification codes

The following events are sent from an EDIT widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	Widget has been clicked.
WM_NOTIFICATION_RELEASED	Widget has been released.
WM_NOTIFICATION_MOVED_OUT	Widget has been clicked and pointer has been moved out of the widget without releasing.
WM_NOTIFICATION_VALUE_CHANGED	Value (content) of the EDIT widget has changed.

20.8.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_UP	Increases the current character. If for example the current character (the character below the cursor) is a 'A' it changes to 'B'.
GUI_KEY_DOWN	Decreases the current character. If for example the current character is a 'B' it changes to 'A'.
GUI_KEY_RIGHT	Moves the cursor one character to the right.
GUI_KEY_LEFT	Moves the cursor one character to the left.
GUI_KEY_BACKSPACE	If the widget works in text mode, the character before the cursor is deleted.
GUI_KEY_DELETE	If the widget works in text mode, the current is deleted.
GUI_KEY_INSERT	If the widget works in text mode, this key toggles the edit mode between GUI_EDIT_MODE_OVERWRITE and GUI_EDIT_MODE_INSERT. For details, refer to EDIT_SetInsertMode().
GUI_KEY_HOME	Moves the cursor to its first position.
GUI_KEY_END	Moves the cursor to its last position.

20.8.5 EDIT API

The table below lists the available emWin EDIT-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
EDIT_AddKey()	Adds user input to a specified EDIT widget.
EDIT_Create()	Creates an EDIT widget. (Obsolete)
EDIT_CreateAsChild()	Creates an EDIT widget as a child window. (Obsolete)
EDIT_CreateEx()	Creates an EDIT widget.
EDIT_CreateIndirect()	Creates an EDIT widget from resource table entry.
EDIT_CreateUser()	Creates an EDIT widget using extra bytes as user data.
EDIT_EnableBlink()	Enables/disables a blinking cursor

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
EDIT_EnableInversion()	Enables/disables an inverted cursor (default is inverting)
EDIT_GetBkColor()	Returns the background color of the EDIT widget.
EDIT_GetBorderSize()	Returns the border size of an EDIT widget.
EDIT_GetCharAtPixel()	Returns the character at the given pixel position.
EDIT_GetCursorCharPos()	Returns the character related position of the cursor.
EDIT_GetCursorPixelPos()	Returns the pixel related position of the cursor in window coordinates.
EDIT_GetDefaultBkColor()	Returns the default background color used for EDIT widgets.
EDIT_GetDefaultFont()	Returns the default font used for EDIT widgets.
EDIT_GetDefaultTextAlign()	Returns the default text alignment used for EDIT widgets.
EDIT_GetDefaultTextColor()	Returns the default text color used for EDIT widgets.
EDIT_GetFloatValue()	Returns the current value of the EDIT widget as floating point value.
EDIT_GetFont()	Returns a pointer to the used font.
EDIT_GetNumChars()	Returns the number of characters of the specified EDIT widget.
EDIT_GetSel()	Returns the current selection.
EDIT_GetSelText()	Copies the selected text into a buffer.
EDIT_GetText()	Retrieves the user input of a specified EDIT widget.
EDIT_GetTextAlign()	This function returns the currently set alignment of the EDIT widget.
EDIT_GetTextColor()	Returns the text color.
EDIT_GetUserData()	Retrieves the data set with EDIT_SetUserData().
EDIT_GetValue()	Returns the current value of the EDIT widget.
EDIT_SetBinMode()	Enables the binary edit mode of the EDIT widget.
EDIT_SetBkColor()	Sets the background color of the EDIT widget.
EDIT_SetBorderSize()	Sets the border size of an EDIT widget.
EDIT_SetCursorAtChar()	Sets the EDIT widget cursor to a specified character position.
EDIT_SetCursorAtPixel()	Sets the EDIT widget cursor to a specified pixel position.
EDIT_SetDecMode()	Enables the decimal edit mode of the EDIT widget.
EDIT_SetDefaultBkColor()	Sets the default background color used for EDIT widgets.
EDIT_SetDefaultFont()	Sets the default font used for EDIT widgets.
EDIT_SetDefaultTextAlign()	Sets the default text alignment for EDIT widgets.
EDIT_SetDefaultTextColor()	Sets the default text color used for EDIT widgets.
EDIT_SetFloatMode()	Enables the floating point edit mode of the EDIT widget.
EDIT_SetFloatValue()	The function can be used to set the floating point value of the EDIT widget if working in floating point mode.
EDIT_SetFocusable()	Sets focusability of the EDIT widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
EDIT_SetFont()	Sets the used font of the EDIT widget.
EDIT_SetHexMode()	Enables the hexadecimal edit mode of the EDIT widget.
EDIT_SetInsertMode()	Enables or disables the insert mode of the EDIT widget.
EDIT_SetMaxLen()	Sets the maximum number of characters to be edited by the given EDIT widget.
EDIT_SetpfAddKeyEx()	Sets a function which is called to add a character.
EDIT_SetSel()	Sets the current selection.
EDIT_SetText()	Sets the text.
EDIT_SetTextAlign()	Sets the text alignment of the EDIT widget.
EDIT_SetTextColor()	Sets the text color of the EDIT widget.
EDIT_SetTextMode()	Sets the edit mode of the EDIT widget back to text mode.
EDIT_SetValue()	Sets the current value of the EDIT widget.
EDIT_SetUlongMode()	Enables the unsigned long decimal edit mode of the EDIT widget.
EDIT_SetUserData()	Sets the extra data of an EDIT widget.
GUI_EditBin()	Edits a binary value at the current cursor position.
GUI_EditDec()	Edits a decimal value at the current cursor position.
GUI_EditFloat()	Edits a floating point value at the current cursor position.
GUI_EditHex()	Edits a hexadecimal value at the current cursor position.
GUI_EditString()	Edits a string at the current cursor position.

Defines

Group of defines	Description
EDIT color indexes	Color indexes for EDIT widget.
EDIT flags	Flags used for EDIT widgets.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1 Functions

20.8.5.1.1 EDIT_AddKey()

Description

Adds user input to a specified EDIT widget.

Prototype

```
void EDIT_AddKey(EDIT_Handle hObj,
                 int         Key);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget
Key	Character to be added.

Additional information

The specified character is added to the user input of the EDIT widget. If the last character should be erased, the key GUI_KEY_BACKSPACE can be used. If the maximum count of characters has been reached, another character will not be added.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.2 EDIT_Create()

> **Note**
>
> This function is **deprecated**, `EDIT_CreateEx()` should be used instead.

Description

Creates an EDIT widget of a specified size at a specified location.

Prototype

```
EDIT_Handle EDIT_Create(int x0,
                        int y0,
                        int xSize,
                        int ySize,
                        int Id,
                        int MaxLen,
                        int Flags);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the edit field (in parent coordinates).
`y0`	Topmost pixel of the edit field (in parent coordinates).
`xSize`	Horizontal size of the edit field (in pixels).
`ySize`	Vertical size of the edit field (in pixels.
`Id`	ID to be returned.
`MaxLen`	Maximum count of characters.
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).

Return value

Handle of the created EDIT widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.3 EDIT_CreateAsChild()

> **Note**
>
> This function is **deprecated**, `EDIT_CreateEx()` should be used instead.

Description

Creates an EDIT widget as a child window.

Prototype

```
EDIT_Handle EDIT_CreateAsChild(int     x0,
                               int     y0,
                               int     xSize,
                               int     ySize,
                               WM_HWIN hParent,
                               int     Id,
                               int     Flags,
                               int     MaxLen);
```

Parameters

Parameter	Description
`x0`	X-position of the edit field relative to the parent window.
`y0`	Y-position of the edit field relative to the parent window.
`xSize`	Horizontal size of the edit field (in pixels).
`ySize`	Vertical size of the edit field (in pixels).
`hParent`	Handle of parent window.
`Id`	ID to be assigned to the EDIT widget.
`Flags`	Window create flags (see *Window create flags* on page 958).
`MaxLen`	Maximum count of characters.

Return value

Handle of the created EDIT widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.4 EDIT_CreateEx()

Description

Creates an EDIT widget of a specified size at a specified location.

Prototype

```
EDIT_Handle EDIT_CreateEx(int     x0,
                          int     y0,
                          int     xSize,
                          int     ySize,
                          WM_HWIN hParent,
                          int     WinFlags,
                          int     ExFlags,
                          int     Id,
                          int     MaxLen);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new EDIT widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used, reserved for future use.
Id	Window ID of the widget.
MaxLen	Maximum count of characters.

Return value

Handle of the created EDIT widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.5 EDIT_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Flags` is used according to the parameter `Align` of the function `EDIT_SetTextAlign()`. The element `Para` is used according to the parameter `MaxLen` of the function `EDIT_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.6 EDIT_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `EDIT_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.7 EDIT_EnableBlink()

Description

Enables/disables a blinking cursor.

Prototype

```
void EDIT_EnableBlink(EDIT_Handle hObj,
                      int         Period,
                      int         OnOff);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Period	Blinking period
OnOff	1 enables blinking, 0 disables blinking

Additional information

This function calls GUI_X_GetTime().

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.8 EDIT_EnableInversion()

Description

Toggles between inversion mode.

Prototype

```
int EDIT_EnableInversion(EDIT_Handle hObj,
                         int         OnOff);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
OnOff	1 enables inverting, 0 disables inverting

Return value

Previous used mode.

Additional information

The text cursor per default is drawn by inverting the character which is currently edited. If a cursor with a dedicated text- and background color is required, inversion can be deactivated and the functions EDIT_SetTextColor() and EDIT_SetBkColor() may be used for setting the cursor color.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.9 EDIT_GetBkColor()

Description

Returns the background color of the EDIT widget.

Prototype

```
GUI_COLOR EDIT_GetBkColor(EDIT_Handle  hObj,
                          unsigned int Index);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Index	Color index. See *EDIT color indexes* on page 1195 for a full list of permitted values.

Return value

Background color of the EDIT widget.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.10 EDIT_GetBorderSize()

Description

Returns the border size of an EDIT widget.

Prototype

```
int EDIT_GetBorderSize(EDIT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.

Return value

= -1 Error.
≠ -1 Border size of the EDIT widget.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.11 EDIT_GetCharAtPixel()

Description

Returns the character at the given pixel position.

Prototype

```
U16 EDIT_GetCharAtPixel(EDIT_Handle   hObj,
                        int           x,
                        int           y,
                        int         * pIndex);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
x	X-position.
y	Y-position.
pIndex	Pointer to int. Zero-based position of the character in the string. Can be NULL if not needed.

Return value

= 0 No character found.
≠ 0 The character at the given pixel position.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.12 EDIT_GetCursorCharPos()

Description

Returns the character related position of the cursor.

Prototype

```
int EDIT_GetCursorCharPos(EDIT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.

Return value

Character related position of the cursor.

Additional information

The widget returns the character position if it has the focus or not. This means the cursor position is also returned, if the cursor is currently not visible in the widget.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.13 EDIT_GetCursorPixelPos()

Description

Returns the pixel related position of the cursor in window coordinates.

Prototype

```
void EDIT_GetCursorPixelPos(EDIT_Handle   hObj,
                            int         * pxPos,
                            int         * pyPos);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
pxPos	Pointer to integer variable for the X-position in window coordinates.
pyPos	Pointer to integer variable for the Y-position in window coordinates.

Additional information

The widget returns the pixel position if it has the focus or not. This means the cursor position is also returned, if the cursor is currently not visible in the widget.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.14 EDIT_GetDefaultBkColor()

Description

Returns the default background color used for EDIT widgets.

Prototype

```
GUI_COLOR EDIT_GetDefaultBkColor(unsigned int Index);
```

Parameters

Parameter	Description
Index	Color index. See table below.

Return value

Default background color used for EDIT widgets.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.15 EDIT_GetDefaultFont()

Description

Returns the default font used for EDIT widgets.

Prototype

```
GUI_FONT *EDIT_GetDefaultFont(void);
```

Return value

Default font used for EDIT widgets.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.16 EDIT_GetDefaultTextAlign()

Description

Returns the default text alignment used for EDIT widgets.

Prototype

```
int EDIT_GetDefaultTextAlign(void);
```

Return value

Default text alignment used for EDIT widgets.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.17 EDIT_GetDefaultTextColor()

Description

Returns the default text color used for EDIT widgets.

Prototype

```
GUI_COLOR EDIT_GetDefaultTextColor(unsigned int Index);
```

Parameters

Parameter	Description
Index	Has to be 0, reserved for future use.

Return value

Default text color used for EDIT widgets.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.18 EDIT_GetFloatValue()

Description

Returns the current value of the EDIT widget as floating point value.

Prototype

```
float EDIT_GetFloatValue(EDIT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.

Return value

The current value.

Additional information

The use of this function makes only sense if the edit field is in floating point edit mode.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.19 EDIT_GetFont()

Description

Returns a pointer to the used font.

Prototype

```
GUI_FONT *EDIT_GetFont(EDIT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.

Return value

Pointer to the used font.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.20 EDIT_GetNumChars()

Description

Returns the number of characters of the specified EDIT widget.

Prototype

```
int EDIT_GetNumChars(EDIT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.

Return value

Number of characters of the specified EDIT widget.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.21 EDIT_GetSel()

Description

Returns the current selection.

Prototype

```
void EDIT_GetSel(EDIT_Handle   hObj,
                 int         * pFirstChar,
                 int         * pLastChar);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
pFirstChar	Pointer to an int where the number of the first selected char will be stored in.
pLastChar	Pointer to an int where the number of the last selected char will be stored in.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.22 EDIT_GetSelText()

Description

Copies the selected text into a buffer.

Prototype

```
void EDIT_GetSelText(EDIT_Handle   hObj,
                     char        * sDest,
                     int           MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
sDest	Pointer to buffer.
MaxLen	Size of buffer.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.23 EDIT_GetText()

Description

Retrieves the user input of a specified EDIT widget.

Prototype

```
void EDIT_GetText(EDIT_Handle   hObj,
                  char        * sDest,
                  int           MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
sDest	Pointer to buffer.
MaxLen	Size of buffer.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.24 EDIT_GetTextAlign()

Description

This function returns the currently set alignment of the EDIT widget.

Prototype

```
int EDIT_GetTextAlign(EDIT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.

Return value

The currently set text alignment for the given EDIT widget.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.25 EDIT_GetTextColor()

Description

Returns the text color.

Prototype

```
GUI_COLOR EDIT_GetTextColor(EDIT_Handle  hObj,
                            unsigned int Index);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Index	Color index. See *EDIT color indexes* on page 1195 for a full list of permitted values.

Return value

The currently set text color.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.26 EDIT_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.27 EDIT_GetValue()

Description

Returns the current value of the EDIT widget. The current value is only useful if the EDIT widget is in binary, decimal or hexadecimal mode.

Prototype

```
I32 EDIT_GetValue(EDIT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.

Return value

The current value.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.28 EDIT_SetBinMode()

Description

Enables the binary edit mode of the EDIT widget. The given value can be modified in the given range.

Prototype

```
void EDIT_SetBinMode(EDIT_Handle hEdit,
                     U32         Value,
                     U32         Min,
                     U32         Max);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Value	Value to be modified.
Min	Minimum value.
Max	Maximum value.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.29 EDIT_SetBkColor()

Description

Sets the background color of the EDIT widget.

Prototype

```
void EDIT_SetBkColor(EDIT_Handle  hObj,
                     unsigned int Index,
                     GUI_COLOR    Color);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Index	Color index. See *EDIT color indexes* on page 1195 for a full list of permitted values.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.30 EDIT_SetCursorAtChar()

Description

Sets the EDIT widget cursor to a specified character position.

Prototype

```
void EDIT_SetCursorAtChar(EDIT_Handle hObj,
                          int         Pos);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Pos	Character position to set cursor to.

Additional information

The character position works as follows:
0: left of the first (leftmost) character,
1: between the first and second characters,
2: between the second and third characters, and so on.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.31 EDIT_SetCursorAtPixel()

Description

Sets the EDIT widget cursor to a specified pixel position.

Prototype

```
void EDIT_SetCursorAtPixel(EDIT_Handle hObj,
                           int         xPos);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
xPos	Pixel position to set cursor to.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.32 EDIT_SetDecMode()

Description

Enables the decimal edit mode of the EDIT widget. The given value can be modified in the given range.

Prototype

```
void EDIT_SetDecMode(EDIT_Handle hEdit,
                     I32         Value,
                     I32         Min,
                     I32         Max,
                     int         Shift,
                     U8          Flags);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Value	Value to be set.
Min	Minimum value.
Max	Maximum value.
Shift	If > 0 it specifies the position of the decimal point.
Flags	See *EDIT flags* on page 1196 for a full list of permitted values.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.33 EDIT_SetDefaultBkColor()

Description

Sets the default background color used for EDIT widgets.

Prototype

```
void EDIT_SetDefaultBkColor(unsigned int Index,
                            GUI_COLOR    Color);
```

Parameters

Parameter	Description
Index	Color index. See table below.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.34 EDIT_SetDefaultFont()

Description

Sets the default font used for EDIT widgets.

Prototype

```
void EDIT_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to the font to be set as default.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.35 EDIT_SetDefaultTextAlign()

Description

Sets the default text alignment for EDIT widgets.

Prototype

```
void EDIT_SetDefaultTextAlign(int Align);
```

Parameters

Parameter	Description
Align	Default text alignment. For details, refer to EDIT_SetTextAlign().

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.36 EDIT_SetDefaultTextColor()

Description

Sets the default text color used for EDIT widgets.

Prototype

```
void EDIT_SetDefaultTextColor(unsigned int Index,
                              GUI_COLOR    Color);
```

Parameters

Parameter	Description
Index	Has to be 0, reserved for future use.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.37 EDIT_SetFloatMode()

Description

Enables the floating point edit mode of the EDIT widget. The given value can be modified in the given range.

Prototype

```
void EDIT_SetFloatMode(EDIT_Handle hEdit,
                       float       Value,
                       float       Min,
                       float       Max,
                       int         Shift,
                       U8          Flags);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Value	Value to be modified.
Min	Minimum value.
Max	Maximum value.
Shift	Number of post decimal positions.
Flags	See *EDIT flags* on page 1196 for a full list of permitted values.

Additional information

The float calculation of the EDIT widget is based on 32 bit signed integer calculation. If using 4 decimal places, the values have to be internally multiplied with 10^4. That exceeds the range of 2^{31}. Editing values with 9 digits (before and after decimal point) will work.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.38 EDIT_SetFloatValue()

Description

The function can be used to set the floating point value of the EDIT widget if working in floating point mode.

Prototype

```
void EDIT_SetFloatValue(EDIT_Handle hObj,
                        float       Value);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Value	New floating point value of the EDIT widget.

Additional information

The use of this function makes only sense if the EDIT widget works in floating point mode. If working in text mode the function has no effect. If working in binary, decimal or hexadecimal mode the behavior of the EDIT widget is undefined.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.39 EDIT_SetFocusable()

Description

Sets the focusability of the EDIT widget.

Prototype

```
void EDIT_SetFocusable(EDIT_Handle hObj,
                       int         State);
```

Parameter	Description
hObj	Handle of EDIT widget.
State	If State is set to 0, the EDIT widget is set not to be focusable. Otherwise it is set to be focusable.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.40 EDIT_SetFont()

Description

Sets the used font of the EDIT widget.

Prototype

```
void EDIT_SetFont(      EDIT_Handle   hObj,
                  const GUI_FONT    * pFont);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
pFont	Pointer to the font.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.41 EDIT_SetHexMode()

Description

Enables the hexadecimal edit mode of the EDIT widget. The given value can be modified in the given range.

Prototype

```
void EDIT_SetHexMode(EDIT_Handle hEdit,
                     U32         Value,
                     U32         Min,
                     U32         Max);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Value	Value to be modified.
Min	Minimum value.
Max	Maximum value.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.42 EDIT_SetInsertMode()

Description

Enables or disables the insert mode of the EDIT widget.

Prototype

```
int EDIT_SetInsertMode(EDIT_Handle hObj,
                       int         OnOff);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
OnOff	0 for disabling insert mode, 1 for enabling insert mode.

Return value

Returns the previous insert mode state.

Additional information

The use of this function makes only sense if the EDIT widget operates in text mode or in any user defined mode. If working in hexadecimal, binary, floating point or decimal mode the use of this function has no effect except that it changes the appearance of the cursor.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.43 EDIT_SetMaxLen()

Description

Sets the maximum number of characters to be edited by the given EDIT widget.

Prototype

```
void EDIT_SetMaxLen(EDIT_Handle hObj,
                    int         MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
MaxLen	Number of characters.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.44 EDIT_SetpfAddKeyEx()

Description

Sets the function pointer which is used by the EDIT widget to call the function which is responsible for adding characters.

Prototype

```
void EDIT_SetpfAddKeyEx(EDIT_Handle      hObj,
                        tEDIT_AddKeyEx * pfAddKeyEx);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
pfAddKeyEx	Function pointer to the function to be used to add a character.

Additional information

If working in text mode (default) or one of the modes for editing values, the EDIT widget uses its own routines to add a character. The use of this function only makes sense if the default behavior of the EDIT widget needs to be changed. If a function pointer has been set with this function the application program is responsible for the content of the text buffer.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.45 EDIT_SetSel()

Before	After
	

Description

Used to set the current selection of the EDIT widget.

Prototype

```
void EDIT_SetSel(EDIT_Handle hObj,
                 int         FirstChar,
                 int         LastChar);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
FirstChar	Zero based index of the first character to be selected. -1 if no character should be selected.
LastChar	Zero based index of the last character to be selected. -1 if all characters from the first character until the last character should be selected.

Additional information

Selected characters are usually displayed in reverse. Setting the cursor position deselects all characters.

Example

```
EDIT_SetSel(hEdit,  0, -1);  // Selects all characters of the widget
EDIT_SetSel(hEdit, -1,  0);  // Deselects all characters
EDIT_SetSel(hEdit,  0,  2);  // Selects the first 3 characters
```

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.46 EDIT_SetText()

Description

Sets the text to be displayed in the EDIT widget.

Prototype

```
void EDIT_SetText(      EDIT_Handle   hObj,
                  const char        * s);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
s	Text to display.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.47 EDIT_SetTextAlign()

Description

Sets the text alignment of the EDIT widget.

Prototype

```
void EDIT_SetTextAlign(EDIT_Handle hObj,
                       int         Align);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Align	Or-combination of text alignment flags. List of flags can be found under *Text alignment flags* on page 218.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.48 EDIT_SetTextColor()

Description

Sets the text color of the EDIT widget.

Prototype

```
void EDIT_SetTextColor(EDIT_Handle  hObj,
                       unsigned int Index,
                       GUI_COLOR    Color);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Index	Index for text color. See *EDIT color indexes* on page 1195 for a full list of permitted values.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.49 EDIT_SetTextMode()

Description

Sets the edit mode of the EDIT widget back to text mode.

Prototype

```
void EDIT_SetTextMode(EDIT_Handle hEdit);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.

Additional information

If one of the functions EDIT_SetBinMode(), EDIT_SetDecMode(), EDIT_SetFloatMode() or EDIT_SetHexMode() has been used to set the EDIT widget to one of the numeric edit modes, this function sets the edit mode back to text mode. It also clears the content of the EDIT widget.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.50 EDIT_SetValue()

Description

Sets the current value of the EDIT widget. Only useful if binary, decimal or hexadecimal edit mode is set.

Prototype

```
void EDIT_SetValue(EDIT_Handle hObj,
                   I32         Value);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Value	New value.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.51 EDIT_SetUlongMode()

Description

Enables the unsigned long decimal edit mode of the EDIT widget. The given value can be modified in the given range.

Prototype

```
void EDIT_SetUlongMode(EDIT_Handle hEdit,
                       U32         Value,
                       U32         Min,
                       U32         Max);
```

Parameters

Parameter	Description
hObj	Handle of EDIT widget.
Value	Value to be modified.
Min	Minimum value.
Max	Maximum value.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.52 EDIT_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.53 GUI_EditBin()

Description

Edits a binary value at the current cursor position.

Prototype

```
U32 GUI_EditBin(U32 Value,
                U32 Min,
                U32 Max,
                int Len,
                int xSize);
```

Parameters

Parameter	Description
Value	Value to be modified.
Min	Minimum value.
Max	Maximum value.
Len	Number of digits to edit.
xSize	Pixel-size in X of the edit field.

Return value

The new value will be returned if <ENTER> is pressed. If <ESC> is pressed, the old value is returned.

Additional information

The routine returns after pressing <ENTER> or <ESC>. The content of the given text will be modified only if <ENTER> is pressed.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.54 GUI_EditDec()

Description

Edits a decimal value at the current cursor position.

Prototype

```
I32 GUI_EditDec(I32 Value,
                I32 Min,
                I32 Max,
                int Len,
                int xSize,
                int Shift,
                U8  Flags);
```

Parameters

Parameter	Description
Value	Value to be modified.
Min	Minimum value.
Max	Maximum value.
Len	Number of digits to edit.
xSize	Pixel-size in X of edit field.
Shift	If > 0 it specifies the position of the decimal point.
Flags	See EDIT_SetDecMode().

Return value

The new value will be returned if <ENTER> is pressed. If <ESC> is pressed, the old value is returned.

Additional information

The routine returns after pressing <ENTER> or <ESC>. The content of the given text will be modified only if <ENTER> is pressed.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.55 GUI_EditFloat()

Description

Edits a floating point value at the current cursor position.

Prototype

```
float GUI_EditFloat(float Value,
                    float Min,
                    float Max,
                    int   Len,
                    int   xSize,
                    int   Shift,
                    U8    Flags);
```

Parameters

Parameter	Description
Value	Value to be modified.
Min	Minimum value.
Max	Maximum value.
Len	Number of digits to edit.
xSize	Pixel-size in X of the EDIT widget.
Shift	Specifies the position of the decimal point, if > 0.
Flags	See EDIT_SetFloatMode().

Return value

The new value will be returned if <ENTER> is pressed. If <ESC> is pressed, the old value is returned.

Additional information

The routine returns after pressing <ENTER> or <ESC>. The content of the given text will be modified only if <ENTER> is pressed.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.56 GUI_EditHex()

Description

Edits a hexadecimal value at the current cursor position.

Prototype

```
U32 GUI_EditHex(U32 Value,
                U32 Min,
                U32 Max,
                int Len,
                int xSize);
```

Parameters

Parameter	Description
Value	Value to be modified.
Min	Minimum value.
Max	Maximum value.
Len	Number of digits to edit.
xSize	Pixel-size in X of the edit field.

Return value

The new value will be returned if <ENTER> is pressed. If <ESC> is pressed, the old value is returned.

Additional information

The routine returns after pressing <ENTER> or <ESC>. The content of the given text will be modified only if <ENTER> is pressed.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.1.57 GUI_EditString()

Description

Edits a string at the current cursor position.

Prototype

```
void GUI_EditString(char * pString,
                    int    Len,
                    int    xSize);
```

Parameters

Parameter	Description
pString	Pointer to the string to be edited.
Len	Maximum number of characters.
xSize	Pixel-size in X of the edit field.

Additional information

The routine returns after pressing <ENTER> or <ESC>. The content of the given text will be modified only if <ENTER> is pressed.

 © 2020 SEGGER Microcontroller GmbH

20.8.5.2 Defines

20.8.5.2.1 EDIT color indexes

Description

Color indexes for EDIT widget.

Definition

```
#define EDIT_CI_DISABLED    0
#define EDIT_CI_ENABLED     1
#define EDIT_CI_CURSOR      2
```

Symbols

Definition	Description
EDIT_CI_DISABLED	Color index for the disabled state.
EDIT_CI_ENABLED	Color index for the enabled state.
EDIT_CI_CURSOR	Color to be used for the cursor. This is only taken into account if the cursor is not in inversion mode (EDIT_EnableInversion(0)).

 © 2020 SEGGER Microcontroller GmbH

20.8.5.2.2 EDIT flags

Description

These flags are used if the EDIT widget is in decimal or float mode. This can be activated by calling `EDIT_SetDecMode()` or `EDIT_SetFloatMode()`. These flags are OR-combinable.

Definition

```
#define GUI_EDIT_NORMAL                   (0 << 0)
#define GUI_EDIT_SIGNED                   (1 << 0)
#define GUI_EDIT_SUPPRESS_LEADING_ZEROES  (1 << 1)
```

Symbols

Definition	Description
GUI_EDIT_NORMAL	Edit in normal mode. A sign is displayed only if the value is negative.
GUI_EDIT_SIGNED	"+" and "-" sign is displayed.
GUI_EDIT_SUPPRESS_LEADING_ZEROES	Does not show leading zeroes.

 © 2020 SEGGER Microcontroller GmbH

20.8.6 Examples

The Sample folder contains the following examples which show how the widget can be used:

- WIDGET_Edit.c
- WIDGET_EditWinmode.c

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_Edit.c:



Screenshot of WIDGET_EditWinmode.c:



 © 2020 SEGGER Microcontroller GmbH

20.9 FRAMEWIN: Frame window widget

FRAMEWIN widgets give your application a PC application-window appearance. They consist of a surrounding frame, a title bar and a user area. The color of the title bar changes to show whether the window is active or inactive, as seen below:

Active frame window	Inactive frame window
	

Note

All FRAMEWIN-related routines are located in the file(s) `FRAMEWIN*.c`, `FRAMEWIN.h`. All identifiers are prefixed FRAMEWIN.

You can attach predefined buttons to the title bar as seen below or you can attach your own buttons to a title bar:

Description	Frame window
Frame window with minimize-, maximize- and close button.	
Frame window with minimize-, maximize- and close button in maximized state.	
Frame window with minimize-, maximize- and close button in minimized state	

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

 © 2020 SEGGER Microcontroller GmbH

20.9.1 Structure of the frame window

The following diagram shows the detailed structure and looks of a frame window:



The frame window actually consists of 2 windows; the main window and a child window. The child window is called `Client window`. It is important to be aware of this when dealing with callback functions: There are 2 windows with 2 different callback functions. When creating child windows, these child windows are typically created as children of the client window; their parent is therefor the client window.

Detail	Description
`B`	Border size of the frame window. The default size of the border is 3 pixels.
`H`	Height of the title bar. Depends on the size of the used font for the title.
`D`	Spacing between title bar and client window. (1 pixel)
`Title bar`	The title bar is part of the frame window and not a separate window.
`Client window`	The client window is a separate window created as a child window of the frame window.

 © 2020 SEGGER Microcontroller GmbH

20.9.2 Configuration options

Type	Macro	Default	Description
B	FRAMEWIN_ALLOW_DRAG_ON_FRAME	1	Allows dragging the widget on the surrounding frame.
N	FRAMEWIN_BARCOLOR_ACTIVE_DEFAULT	0xff0000	Title bar background color, active state.
N	FRAMEWIN_BARCOLOR_INACTIVE_DEFAULT	0x404040	Title bar background color, inactive state.
N	FRAMEWIN_BORDER_DEFAULT	3	Outer border width, in pixels.
N	FRAMEWIN_CLIENTCOLOR_DEFAULT (with WIDGET_USE_FLEX_SKIN = 0) (with WIDGET_USE_FLEX_SKIN = 1)	0xc0c0c0 GUI_WHITE	Color of client window area.
S	FRAMEWIN_DEFAULT_FONT (with WIDGET_USE_FLEX_SKIN = 0) (with WIDGET_USE_FLEX_SKIN = 1)	&GUI_Font8_1 &GUI_Font13_1	Font used for title bar text.
N	FRAMEWIN_FRAMECOLOR_DEFAULT	0xaaaaaa	Frame color.
N	FRAMEWIN_IBORDER_DEFAULT	1	Inner border width, in pixels.
N	FRAMEWIN_TEXTCOLOR_ACTIVE_DEFAULT (with WIDGET_USE_FLEX_SKIN = 0) (with WIDGET_USE_FLEX_SKIN = 1)	GUI_WHITE GUI_BLACK	Title bar text color, active state.
N	FRAMEWIN_TEXTCOLOR_INACTIVE_DEFAULT (with WIDGET_USE_FLEX_SKIN = 0) (with WIDGET_USE_FLEX_SKIN = 1)	GUI_WHITE GUI_BLACK	Title bar text color, inactive state.
N	FRAMEWIN_TITLEHEIGHT_DEFAULT	0	Default height of title bar.

20.9.3 Keyboard reaction

The widget can not gain the input focus and does not react on keyboard input.

20.9.4 FRAMEWIN API

The table below lists the available emWin FRAMEWIN-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
FRAMEWIN_AddButton()	Adds a button to the title bar of the FRAMEWIN widget.
FRAMEWIN_AddCloseButton()	Adds a close button to the title bar of the FRAMEWIN widget.
FRAMEWIN_AddMaxButton()	Adds a maximize button to the title bar of the FRAMEWIN widget.
FRAMEWIN_AddMenu()	Adds the given menu to a FRAMEWIN widget.
FRAMEWIN_AddMinButton()	Adds a minimize button to the title bar of the FRAMEWIN widget.
FRAMEWIN_Create()	Creates a FRAMEWIN widget. (Obsolete)
FRAMEWIN_CreateAsChild()	Creates a FRAMEWIN widget as a child window. (Obsolete)

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
FRAMEWIN_CreateEx()	Creates a FRAMEWIN widget.
FRAMEWIN_CreateIndirect()	Creates a FRAMEWIN widget from a resource table entry.
FRAMEWIN_CreateUser()	Creates a FRAMEWIN widget using extra bytes as user data.
FRAMEWIN_GetActive()	Returns if the given FRAMEWIN widget is in active state or not.
FRAMEWIN_GetBarColor()	Returns the color of the title bar of the given FRAMEWIN widget.
FRAMEWIN_GetBorderSize()	Returns the border size of the given FRAMEWIN widget.
FRAMEWIN_GetDefaultBarColor()	Returns the default color for title bars in FRAMEWIN widgets.
FRAMEWIN_GetDefaultBorderSize()	Returns the default border size of FRAMEWIN widgets.
FRAMEWIN_GetDefaultClientColor()	Returns the default color of client areas in FRAMEWIN widgets.
FRAMEWIN_GetDefaultFont()	Returns the default font used for captions of FRAMEWIN widgets.
FRAMEWIN_GetDefaultTextColor()	Returns the default text color of the title.
FRAMEWIN_GetDefaultTitleHeight()	Returns the default height of title bars in FRAMEWIN widget.
FRAMEWIN_GetFont()	Returns a pointer to the font used to draw the title text.
FRAMEWIN_GetText()	Returns the title text.
FRAMEWIN_GetTextAlign()	Returns the text alignment of the title text.
FRAMEWIN_GetTitleHeight()	Returns the height of title bar of the given FRAMEWIN widget.
FRAMEWIN_GetUserData()	Retrieves the data set with FRAMEWIN_SetUserData().
FRAMEWIN_IsMinimized()	Returns if the FRAMEWIN widget is minimized or not.
FRAMEWIN_IsMaximized()	Returns if the FRAMEWIN widget is maximized or not.
FRAMEWIN_Maximize()	Enlarges a FRAMEWIN widget to the size of its parent window.
FRAMEWIN_Minimize()	Hides the client area of the given FRAMEWIN widget.
FRAMEWIN_OwnerDraw()	Default function for drawing the title bar of a FRAMEWIN widget.
FRAMEWIN_Restore()	Restores a minimized or maximized FRAMEWIN widget to its old size and position.
FRAMEWIN_SetActive()	Sets the state of a specified FRAMEWIN widget.
FRAMEWIN_SetBarColor()	Sets the color of the title bar of a specified FRAMEWIN widget.
FRAMEWIN_SetBorderSize()	Sets the border size of a specified FRAMEWIN widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
FRAMEWIN_SetClientColor()	Sets the color of the client window area of a specified FRAMEWIN widget.
FRAMEWIN_SetDefaultBarColor()	Sets the default color for title bars in FRAMEWIN widgets.
FRAMEWIN_SetDefaultBorderSize()	Sets the default border size of FRAMEWIN widgets.
FRAMEWIN_SetDefaultClientColor()	Sets the default color for client areas in FRAMEWIN widgets.
FRAMEWIN_SetDefaultFont()	Sets the default font used to display the title in FRAMEWIN widgets.
FRAMEWIN_SetDefaultTextColor()	Sets the default text color of the title.
FRAMEWIN_SetDefaultTitleHeight()	Sets the size in Y for the title bar.
FRAMEWIN_SetFont()	Sets the title font of the FRAMEWIN widget.
FRAMEWIN_SetMoveable()	Sets a FRAMEWIN widget to a moveable or fixed state.
FRAMEWIN_SetOwnerDraw()	Enables the FRAMEWIN widget to be owner drawn.
FRAMEWIN_SetResizeable()	Sets the resizable state of the given FRAMEWIN widget.
FRAMEWIN_SetText()	Sets the title text.
FRAMEWIN_SetTextAlign()	Sets the text alignment of the title bar.
FRAMEWIN_SetTextColor()	Sets the color of the title text for both states, active and inactive.
FRAMEWIN_SetTextColorEx()	Sets the text color for the given state.
FRAMEWIN_SetTitleHeight()	Sets the height of the title bar.
FRAMEWIN_SetTitleVis()	Sets the visibility flag of the title bar.
FRAMEWIN_SetUserData()	Sets the extra data of a FRAMEWIN widget.

Defines

Group of defines	Description
FRAMEWIN button flags	Determine on which side of the FRAMEWIN a button should be added.
FRAMEWIN create flags	Create flags that define the behavior of the FRAMEWIN widget.
FRAMEWIN states	State of the FRAMEWIN used for various functions.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1 Functions

20.9.4.1.1 FRAMEWIN_AddButton()

Before	After
	

Description

Adds a button to the title bar of the FRAMEWIN widget.

Prototype

```
WM_HWIN FRAMEWIN_AddButton(FRAMEWIN_Handle hObj,
                           int             Flags,
                           int             Off,
                           int             Id);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Flags	See *FRAMEWIN button flags* on page 1255 for a full list of permitted values.
Off	X-offset used to create the BUTTON widget
Id	ID of the BUTTON widget

Return value

Handle of the BUTTON widget.

Additional information

The button will be created as a child window from the FRAMEWIN widget. So the Window Manager keeps sure it will be deleted when the FRAMEWIN widget will be deleted.

The button can be created at the left side or at the right side of the title bar depending on the parameter Flags. The parameter Offset specifies the space between the button and the border of the FRAMEWIN widget or the space between the previous created button.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.2 FRAMEWIN_AddCloseButton()

Before	After
	

Description

Adds a close button to the title bar of the FRAMEWIN widget.

Prototype

```
WM_HWIN FRAMEWIN_AddCloseButton(FRAMEWIN_Handle hObj,
                                int             Flags,
                                int             Off);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Flags	See *FRAMEWIN button flags* on page 1255 for a full list of permitted values.
Off	X-offset used to create the BUTTON widget

Return value

Handle of the close button.

Additional information

When the user presses the close button the frame window and all its children will be deleted.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.3 FRAMEWIN_AddMaxButton()

Before	After	Maximized
		

Description

Adds a maximize button to the title bar of the FRAMEWIN widget.

Prototype

```
WM_HWIN FRAMEWIN_AddMaxButton(FRAMEWIN_Handle hObj,
                              int             Flags,
                              int             Off);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Flags	See *FRAMEWIN button flags* on page 1255 for a full list of permitted values.
Off	X-offset used to create the BUTTON widget

Return value

Handle of the maximize button.

Additional information

When the user presses the maximize button the first time the FRAMEWIN widget will be enlarged to the size of its parent window. The second use of the button will reduce the frame window to its old size and restores the old position.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.4 FRAMEWIN_AddMenu()

Before	After
	

Description

Adds the given menu to a FRAMEWIN widget. The menu is shown below the title bar.

Prototype

```
void FRAMEWIN_AddMenu(FRAMEWIN_Handle hObj,
                      WM_HWIN         hMenu);
```

Parameters

Parameter	Description
hObj	Handle of frame window.
hMenu	Handle of MENU widget to be added.

Return value

Handle of the maximize button.

Additional information

The added MENU is attached as a child of the FRAMEWIN widget. If the FRAMEWIN widget has been created with a callback routine, the function makes sure, that the WM_MENU messages are passed to the client window of the FRAMEWIN widget.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.5 FRAMEWIN_AddMinButton()

Before	After	Maximized
		

Description

Adds a minimize button to the title bar of the FRAMEWIN widget.

Prototype

```
WM_HWIN FRAMEWIN_AddMinButton(FRAMEWIN_Handle hObj,
                              int             Flags,
                              int             Off);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Flags	See *FRAMEWIN button flags* on page 1255 for a full list of permitted values.
Off	X-offset used to create the BUTTON widget

Return value

Handle of the minimize button.

Additional information

When the user presses the minimize button the first time the client area of the FRAMEWIN widget will be hidden and only the title bar remains visible. The second use of the button will restore the FRAMEWIN widget to its old size.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.6 FRAMEWIN_Create()

> **Note**
>
> This function is **deprecated**, `FRAMEWIN_CreateEx()` should be used instead.

Description

Creates a FRAMEWIN widget of a specified size at a specified location.

Prototype

```
FRAMEWIN_Handle FRAMEWIN_Create(const char        * pText,
                                WM_CALLBACK * cb,
                                int           Flags,
                                int           x0,
                                int           y0,
                                int           xSize,
                                int           ySize);
```

Parameters

Parameter	Description
pTitle	Title displayed in the title bar.
cb	Pointer to callback routine of client area.
Flags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
x0	Leftmost pixel of the frame window (in parent coordinates).
y0	Topmost pixel of the frame window (in parent coordinates).
xSize	Horizontal size of the frame window (in pixels).
ySize	Vertical size of the frame window (in pixels).

Return value

Handle of the created FRAMEWIN widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.7 FRAMEWIN_CreateAsChild()

> **Note**
>
> This function is **deprecated**, `FRAMEWIN_CreateEx()` should be used instead.

Description

Creates a FRAMEWIN widget as a child window.

Prototype

```
FRAMEWIN_Handle FRAMEWIN_CreateAsChild(      int           x0,
                                             int           y0,
                                             int           xSize,
                                             int           ySize,
                                             WM_HWIN       hParent,
                                       const char        * pText,
                                             WM_CALLBACK * cb,
                                             int           Flags);
```

Parameters

Parameter	Description
x0	X-position of the FRAMEWIN widget relative to the parent window.
y0	Y-position of the FRAMEWIN widget relative to the parent window.
xSize	Horizontal size of the FRAMEWIN widget (in pixels).
ySize	Vertical size of the FRAMEWIN widget (in pixels).
hParent	Handle of parent window.
pText	Text to be displayed in the title bar.
cb	Optional pointer to a custom callback function for the client window.
Flags	Window create flags (see *Window create flags* on page 958).

Return value

Handle of the created FRAMEWIN widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.8 FRAMEWIN_CreateEx()

Description

Creates a FRAMEWIN widget of a specified size at a specified location.

Prototype

```
FRAMEWIN_Handle FRAMEWIN_CreateEx(      int           x0,
                                        int           y0,
                                        int           xSize,
                                        int           ySize,
                                        WM_HWIN       hParent,
                                        int           WinFlags,
                                        int           ExFlags,
                                        int           Id,
                                  const char        * pTitle,
                                        WM_CALLBACK * cb);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the FRAMEWIN widget (in parent coordinates).
y0	Topmost pixel of the FRAMEWIN widget (in parent coordinates).
xSize	Horizontal size of the FRAMEWIN widget (in pixels).
ySize	Vertical size of the FRAMEWIN widget (in pixels).
hParent	Handle of parent window. If 0, the new FRAMEWIN widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *FRAMEWIN create flags* on page 1256.
Id	Window ID of the FRAMEWIN widget.
pTitle	Title displayed in the title bar.
cb	Optional pointer to a custom callback function for the client window.

Return value

Handle of the created FRAMEWIN widget; 0 if the function fails.

Additional information

The user callback routine is typically used for 2 purposes:

- to paint the client window (if filling with a color is not desired)
- to react to messages of child windows, typically dialog elements The normal behaviour of the client window is to paint itself, filling the entire window with the client color.
  If the user callback also fills the client window (or a part of it), it can be desirable to set the client color to GUI_INVALID_COLOR, causing the window callback not to fill the client window.
  The user callback of the client window does not receive all messages sent to the client window; some system messages are completely handled by the window callback routine and are not passed to the user callback. All notification messages as well as WM_PAINT and all user messages are sent to the user callback routine. The handle received by the user callback is the handle of the frame window (the parent window of the client window), except for the WM_PAINT message, which receives the handle of the client window.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.9 FRAMEWIN_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Para` of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element `Flags` is used according to the parameter `ExFlags` of the function `FRAMEWIN_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.10 FRAMEWIN_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function FRAMEWIN_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.11 FRAMEWIN_GetActive()

Description

Returns if the given FRAMEWIN widget is in active state or not.

Prototype

```
int FRAMEWIN_GetActive(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.

Return value

1 if FRAMEWIN widget is in active state
0 if not.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.12 FRAMEWIN_GetBarColor()

Description

Returns the color of the title bar of the given FRAMEWIN widget.

Prototype

```
GUI_COLOR FRAMEWIN_GetBarColor(FRAMEWIN_Handle hObj,
                               unsigned        Index);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Index	See *FRAMEWIN states* on page 1257 for a full list of permitted values.

Return value

Color of the title bar as RGB value.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.13 FRAMEWIN_GetBorderSize()

Description

Returns the border size of the given FRAMEWIN widget.

Prototype

```
int FRAMEWIN_GetBorderSize(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.

Return value

The border size of the given FRAMEWIN widget.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.14 FRAMEWIN_GetDefaultBarColor()

Description

Returns the default color for title bars in FRAMEWIN widgets.

Prototype

```
GUI_COLOR FRAMEWIN_GetDefaultBarColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *FRAMEWIN states* on page 1257 for a full list of permitted values.

Return value

Pointer to the default title bar color used for FRAMEWIN widgets in the specified state.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.15 FRAMEWIN_GetDefaultBorderSize()

Description

Returns the default border size of FRAMEWIN widgets.

Prototype

```
int FRAMEWIN_GetDefaultBorderSize(void);
```

Return value

Default border size of FRAMEWIN widgets.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.16 FRAMEWIN_GetDefaultClientColor()

Description

Returns the default color of client areas in FRAMEWIN widgets.

Prototype

```
GUI_COLOR FRAMEWIN_GetDefaultClientColor(void);
```

Return value

Pointer to the default client area color.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.17 FRAMEWIN_GetDefaultFont()

Description

Returns the default font used for captions of FRAMEWIN widgets.

Prototype

```
GUI_FONT *FRAMEWIN_GetDefaultFont(void);
```

Return value

Pointer to the default font used for captions of captions widgets.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.18 FRAMEWIN_GetDefaultTextColor()

Description

Returns the default text color of the title.

Prototype

```
GUI_COLOR FRAMEWIN_GetDefaultTextColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *FRAMEWIN states* on page 1257 for a full list of permitted values.

Return value

Default text color of the title.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.19 FRAMEWIN_GetDefaultTitleHeight()

Description

Returns the default height of title bars in FRAMEWIN widget.

Prototype

```
int FRAMEWIN_GetDefaultTitleHeight(void);
```

Return value

Default title bar height. For more information about the title height, refer to `FRAMEWIN_SetDefaultTitleHeight()`.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.20 FRAMEWIN_GetFont()

Description

Returns a pointer to the font used to draw the title text.

Prototype

```
GUI_FONT *FRAMEWIN_GetFont(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.

Return value

Pointer to the font used to draw the title text.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.21 FRAMEWIN_GetText()

Description

Returns the title text.

Prototype

```
void FRAMEWIN_GetText(FRAMEWIN_Handle   hObj,
                      char            * pBuffer,
                      int               MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
pBuffer	Pointer to buffer to be filled with the title text.
MaxLen	Buffer size in bytes.

Additional information

If the buffer size is smaller than the title text the function copies MaxLen .

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.22 FRAMEWIN_GetTextAlign()

Description

Returns the text alignment of the title text.

Prototype

```
int FRAMEWIN_GetTextAlign(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.

Return value

The currently used text alignment. For details about text alignment, refer to GUI_SetTextAlign().

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.23 FRAMEWIN_GetTitleHeight()

Description

Returns the height of title bar of the given FRAMEWIN widget.

Prototype

```
int FRAMEWIN_GetTitleHeight(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget

Return value

The height of title bar of the given FRAMEWIN widget. For more information about the title height, refer to *FRAMEWIN_SetDefaultTitleHeight* on page 1242.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.24 FRAMEWIN_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.25 FRAMEWIN_IsMinimized()

Description

Returns if the FRAMEWIN widget is minimized or not.

Prototype

```
int FRAMEWIN_IsMinimized(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget

Return value

1 if the FRAMEWIN widget is minimized
0 if not.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.26 FRAMEWIN_IsMaximized()

Description

Returns if the FRAMEWIN widget is maximized or not.

Prototype

```
int FRAMEWIN_IsMaximized(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget

Return value

1 if the FRAMEWIN widget is maximized
0 if not.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.27 FRAMEWIN_Maximize()

Before	After
	

Description

Enlarges a FRAMEWIN widget to the size of its parent window.

Prototype

```
void FRAMEWIN_Maximize(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget

Additional information

When calling this function the FRAMEWIN widget will show the same behavior as when the user presses the maximize button. The FRAMEWIN widget will be enlarged to the size of its parent window.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.28 FRAMEWIN_Minimize()

Before	After
	

Description

Hides the client area of the given FRAMEWIN widget.

Prototype

```
void FRAMEWIN_Minimize(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget

Additional information

When calling this function the FRAMEWIN widget will show the same behavior as when the user presses the minimize button. The FRAMEWIN widget will be enlarged and only the title bar remains visible.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.29 FRAMEWIN_OwnerDraw()

> **Note**
>
> OwnerDraw routines for FRAMEWIN widgets are deprecated and only work in conjunction the classic skin.

Description

Default function for drawing the title bar of a FRAMEWIN widget.

Prototype

```
int FRAMEWIN_OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo);
```

Parameters

Parameter	Description
pDrawItemInfo	Pointer to a WIDGET_ITEM_DRAW_INFO structure.

Return value

Returns 0.

Additional information

This function is useful if FRAMEWIN_SetOwnerDraw() is used. It should be called for all unhandled commands passed to the owner draw function. For more information, refer to the section explaining user drawn widgets and FRAMEWIN_SetOwnerDraw().

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.30 FRAMEWIN_Restore()

Before	After
	

Description

Restores a minimized or maximized FRAMEWIN widget to its old size and position.

Prototype

```
void FRAMEWIN_Restore(FRAMEWIN_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.

Return value

Returns 0.

Additional information

If the given FRAMEWIN widget is neither maximized nor minimized the function takes no effect.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.31 FRAMEWIN_SetActive()

Before	After
	

Description

Sets the state of a specified FRAMEWIN widget. Depending on the state, the color of the title bar will change.

Prototype

```
void FRAMEWIN_SetActive(FRAMEWIN_Handle hObj,
                        int             State);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
State	See *FRAMEWIN states* on page 1257 for a full list of permitted values.

Return value

Returns 0.

Additional information

This function is obsolete. If pointing with a input device to a child of a FRAMEWIN widget the FRAMEWIN widget will become active automatically. It is not recommended to use this function. If using this function to set a FRAMEWIN widget to active state, it is not warranted that the state becomes inactive if an other FRAMEWIN widget becomes active.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.32 FRAMEWIN_SetBarColor()

Before	After
	

Description

Sets the color of the title bar of a specified FRAMEWIN widget.

Prototype

```
void FRAMEWIN_SetBarColor(FRAMEWIN_Handle hObj,
                          unsigned        Index,
                          GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Index	See *FRAMEWIN states* on page 1257 for a full list of permitted values.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.33 FRAMEWIN_SetBorderSize()

Before	After
	

Description

Sets the border size of a specified FRAMEWIN widget.

Prototype

```
void FRAMEWIN_SetBorderSize(FRAMEWIN_Handle hObj,
                            unsigned        Size);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Size	New border size of the FRAMEWIN widget.

Additional information

This function has no effect when using Flex Skin (default).

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.34 FRAMEWIN_SetClientColor()

Before	After
	

Description

Sets the color of the client window area of a specified FRAMEWIN widget.

Prototype

```
void FRAMEWIN_SetClientColor(FRAMEWIN_Handle hObj,
                             GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.35 FRAMEWIN_SetDefaultBarColor()

Description

Sets the default color for title bars in FRAMEWIN widgets.

Prototype

```
void FRAMEWIN_SetDefaultBarColor(unsigned  Index,
                                 GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *FRAMEWIN states* on page 1257 for a full list of permitted values.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.36 FRAMEWIN_SetDefaultBorderSize()

Description

Sets the default border size of FRAMEWIN widgets.

Prototype

```
void FRAMEWIN_SetDefaultBorderSize(int DefaultBorderSize);
```

Parameters

Parameter	Description
BorderSize	Size to be set.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.37 FRAMEWIN_SetDefaultClientColor()

Description

Sets the default color for client areas in FRAMEWIN widgets.

Prototype

```
void FRAMEWIN_SetDefaultClientColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.38 FRAMEWIN_SetDefaultFont()

Description

Sets the default font used to display the title in FRAMEWIN widgets.

Prototype

```
void FRAMEWIN_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to font to be used as default.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.39 FRAMEWIN_SetDefaultTextColor()

Description

Sets the default text color of the title.

Prototype

```
void FRAMEWIN_SetDefaultTextColor(unsigned  Index,
                                  GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *FRAMEWIN states* on page 1257 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.40 FRAMEWIN_SetDefaultTitleHeight()

Description

Sets the size in Y for the title bar.

Prototype

```
void FRAMEWIN_SetDefaultTitleHeight(int Height);
```

Parameters

Parameter	Description
Height	Size to be set

Additional information

The default value of the title height is 0. That means the height of the title depends on the font used to display the title text. If the default value is set to a value > 0 each new FRAMEWIN widget will use this height for the title height and not the height of the font of the title.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.41 FRAMEWIN_SetFont()

Before	After
	

Description

Sets the title font of the FRAMEWIN widget.

Prototype

```
void FRAMEWIN_SetFont(      FRAMEWIN_Handle   hObj,
                      const GUI_FONT        * pFont);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
pFont	Pointer to the font.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.42 FRAMEWIN_SetMoveable()

Description

Sets a FRAMEWIN widget to a moveable or fixed state.

Prototype

```
void FRAMEWIN_SetMoveable(FRAMEWIN_Handle hObj,
                          int             State);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
State	State of frame window. See table below.

Permitted values for parameter State	
0	Frame window is fixed (non-moveable).
1	Frame window is moveable.

Additional information

The default state of a FRAMEWIN widget after creation is fixed. Moveable state means, the FRAMEWIN widget can be dragged with a pointer input device (PID). To move the FRAMEWIN widget, it first needs to be touched with a PID in pressed state in the title area. Moving the pressed PID now moves also the widget. If the config macro FRAMEWIN_ALLOW_DRAG_ON_FRAME is 1 (default), the FRAMEWIN widget can also be dragged on the surrounding frame. This works only if the FRAMEWIN widget is not in resizable state.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.43 FRAMEWIN_SetOwnerDraw()

> **Note**
>
> OwnerDraw routines for FRAMEWIN widgets are deprecated and only work in conjunction the classic skin.

Description

Enables the FRAMEWIN widget to be owner drawn.

Prototype

```
void FRAMEWIN_SetOwnerDraw(FRAMEWIN_Handle         hObj,
                           WIDGET_DRAW_ITEM_FUNC * pfDrawItem);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
pfDrawItem	Pointer to owner draw function.

Supported commands

- WIDGET_ITEM_DRAW

Additional information

This function sets a function pointer to a function which will be called by the widget if a FRAMEWIN widget has to be drawn. It gives you the possibility to draw a complete customized title bar, not just plain text. pfDrawItem is a pointer to an application-defined function of type WIDGET_DRAW_ITEM_FUNC which is explained at the beginning of the chapter.

Example

The following shows a typical owner draw function:

```
int _OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo) {
  GUI_RECT Rect;
  char acBuffer[20];
  switch (pDrawItemInfo->Cmd) {
  case WIDGET_ITEM_DRAW:
    Rect.x0 = pDrawItemInfo->x0 + 1;
    Rect.x1 = pDrawItemInfo->x1 - 1;
    Rect.y0 = pDrawItemInfo->y0 + 1;
    Rect.y1 = pDrawItemInfo->y1;
    FRAMEWIN_GetText(pDrawItemInfo->hWin, acBuffer, sizeof(acBuffer));
    GUI_DrawGradientH(pDrawItemInfo->x0, pDrawItemInfo->y0,
                      pDrawItemInfo->x1, pDrawItemInfo->y1,
                      GUI_RED, GUI_GREEN);
    GUI_SetFont(FRAMEWIN_GetFont(pDrawItemInfo->hWin));
    GUI_SetTextMode(GUI_TM_TRANS);
    GUI_SetColor(GUI_YELLOW);
    GUI_DispStringInRect(acBuffer, &Rect,
                         FRAMEWIN_GetTextAlign(pDrawItemInfo->hWin));
    return 0;
  }
  return FRAMEWIN_OwnerDraw(pDrawItemInfo);
}
void CreateFrameWindow(void) {
  ...
  FRAMEWIN_SetOwnerDraw(hWin, _OwnerDraw);
  ...
```

 © 2020 SEGGER Microcontroller GmbH

```
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.44 FRAMEWIN_SetResizeable()

Before	After
	

Description

Sets the resizable state of the given FRAMEWIN widget.

Prototype

```
void FRAMEWIN_SetResizeable(FRAMEWIN_Handle hObj,
                            int             State);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
State	1 if the frame window should be resizable, 0 if not.

Additional information

If the FRAMEWIN widget is in resizable state its size can be changed by dragging the borders. If a pointer input device points over the border, the cursor will change to a resize cursor (if cursor is on and if optional mouse support is enabled). If pointing to the edge of the border, the X and Y size of the window can be changed simultaneously.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.45 FRAMEWIN_SetText()

Before	After
	

Description

Sets the title text.

Prototype

```
void FRAMEWIN_SetText(      FRAMEWIN_Handle   hObj,
                      const char            * s);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
s	Text to display as the title.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.46 FRAMEWIN_SetTextAlign()

Before	After
	

Description

Sets the text alignment of the title bar.

Prototype

```
void FRAMEWIN_SetTextAlign(FRAMEWIN_Handle hObj,
                           int             Align);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Align	Alignment attribute for the title. List of flags can be found under *Text alignment flags* on page 218.

Additional information

If this function is not called, the default behavior is to display the text centered.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.47 FRAMEWIN_SetTextColor()

Before	After
	

Description

Sets the color of the title text for both states, active and inactive.

Prototype

```
void FRAMEWIN_SetTextColor(FRAMEWIN_Handle hObj,
                           GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.48 FRAMEWIN_SetTextColorEx()

Before	After
	

Description

Sets the text color for the given state.

Prototype

```
void FRAMEWIN_SetTextColorEx(FRAMEWIN_Handle hObj,
                             unsigned        Index,
                             GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Index	See *FRAMEWIN states* on page 1257 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.49 FRAMEWIN_SetTitleHeight()

Before	After
	

Description

Sets the height of the title bar.

Prototype

```
int FRAMEWIN_SetTitleHeight(FRAMEWIN_Handle hObj,
                            int             Height);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Height	Height of the title bar.

Additional information

Per default the height of the title bar depends on the size on the font used to display the title text. When using FRAMEWIN_SetTitleHeight() the height will be fixed to the given value. Changes of the font takes no effect concerning the height of the title bar. A value of 0 will restore the default behavior.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.50 FRAMEWIN_SetTitleVis()

Before	After
	

Description

Sets the visibility flag of the title bar.

Prototype

```
void FRAMEWIN_SetTitleVis(FRAMEWIN_Handle hObj,
                          int             Show);
```

Parameters

Parameter	Description
hObj	Handle of FRAMEWIN widget.
Show	1 for visible (default), 0 for hidden

 © 2020 SEGGER Microcontroller GmbH

20.9.4.1.51 FRAMEWIN_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.2 Defines

20.9.4.2.1 FRAMEWIN button flags

Description

These flags determine on which side of the FRAMEWIN widget a button should be added.

Definition

```
#define FRAMEWIN_BUTTON_RIGHT    (1 << 0)
#define FRAMEWIN_BUTTON_LEFT     (1 << 1)
```

Symbols

Definition	Description
FRAMEWIN_BUTTON_RIGHT	The BUTTON will be created at the right side.
FRAMEWIN_BUTTON_LEFT	The BUTTON will be created at the left side.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.2.2 FRAMEWIN create flags

Description

Create flags that define the behavior of the FRAMEWIN widget. These flags are OR-combinable and can be specified upon creation of the widget via the ExFlags parameter of FRAMEWIN_CreateEx().

Definition

```
#define FRAMEWIN_CF_ACTIVE       (1 << 3)
#define FRAMEWIN_CF_MOVEABLE     (1 << 4)
#define FRAMEWIN_CF_TITLEVIS     (1 << 5)
#define FRAMEWIN_CF_MINIMIZED    (1 << 6)
#define FRAMEWIN_CF_MAXIMIZED    (1 << 7)
#define FRAMEWIN_CF_DRAGGING     (1 << 8)
```

Symbols

Definition	Description
FRAMEWIN_CF_ACTIVE	Active-state of the frame window. See FRAMEWIN_SetActive().
FRAMEWIN_CF_MOVEABLE	Sets the frame window to a moveable state. See FRAMEWIN_SetMoveable().
FRAMEWIN_CF_TITLEVIS	Visibility of the frame window's title. See FRAMEWIN_SetTitleVis().
FRAMEWIN_CF_MINIMIZED	Minimized-state of the frame window. See FRAMEWIN_Minimize().
FRAMEWIN_CF_MAXIMIZED	Maximized-state of the frame window. See FRAMEWIN_Maximize().
FRAMEWIN_CF_DRAGGING	Internal use.

 © 2020 SEGGER Microcontroller GmbH

20.9.4.2.3 FRAMEWIN states

Description

State of the FRAMEWIN used for various functions.

Definition

```
#define FRAMEWIN_CI_INACTIVE    0
#define FRAMEWIN_CI_ACTIVE      1
```

Symbols

Definition	Description
FRAMEWIN_CI_INACTIVE	When the FRAMEWIN is inactive.
FRAMEWIN_CI_ACTIVE	When the FRAMEWIN is active.

 © 2020 SEGGER Microcontroller GmbH

20.9.5 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_FrameWin.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_FrameWin.c:



 © 2020 SEGGER Microcontroller GmbH

20.10 GAUGE: Gauge widget

The GAUGE widget displays a value in a certain range like a progress bar, but instead the progress is displayed in a radial manner. A GAUGE is consists of two arcs that are drawn, a background line and a foreground line. The foreground line's length shows the set value of the GAUGE widget. Depending on the given angle, the widget can obviously also show two circles instead of two arcs.

> **Note**
>
> All GAUGE-related routines are in the file(s) `GAUGE.c` and `GAUGE.h`.
> All identifiers are prefixed with GAUGE.

The GAUGE shown below has a gray background line and and green foreground line.



20.10.1 Configuration options

Type	Macro	Default	Description
N	GAUGE_ALIGN_DEFAULT	GUI_TA_HCENTER | GUI_TA_VCENTER	Alignment of the arc.
N	GAUGE_BKCOLOR_DEFAULT	GUI_BLACK	Background color.
N	GAUGE_COLOR0_DEFAULT	GUI_WHITE	Color of the background line.
N	GAUGE_COLOR1_DEFAULT	GUI_DARKGRAY	Color of the foreground line.

20.10.2 Predefined IDs

The following symbols define IDs which may be used to make GAUGE widgets distinguishable from creation.

```
#define GUI_ID_GAUGE0    0x340
#define GUI_ID_GAUGE1    0x341
#define GUI_ID_GAUGE2    0x342
#define GUI_ID_GAUGE3    0x343
#define GUI_ID_GAUGE4    0x344
#define GUI_ID_GAUGE5    0x345
#define GUI_ID_GAUGE6    0x346
#define GUI_ID_GAUGE7    0x347
#define GUI_ID_GAUGE8    0x348
#define GUI_ID_GAUGE9    0x349
```

20.10.3 Notification codes

The following events are sent from a GAUGE widget to its parent window as part of a `WM_NOTIFY_PARENT` message:

 © 2020 SEGGER Microcontroller GmbH

Message	Description
WM_NOTIFICATION_VALUE_CHANGED	The value of the GAUGE widget has been changed.

20.10.4 Keyboard reaction

The widget can not receive input focus and does therefore not react on any keys.

20.10.5 GAUGE API

The table below lists the available emWin GAUGE-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
GAUGE_CreateIndirect()	Creates a GAUGE widget from a resource table entry.
GAUGE_CreateUser()	Creates a GAUGE widget.
GAUGE_GetValue()	Returns the current value of a GAUGE.
GAUGE_SetAlign()	Sets the alignment of the arc drawn in the GAUGE widget.
GAUGE_SetBkColor()	Sets the background color of the GAUGE widget.
GAUGE_SetColor()	Sets the color of the line drawn in the GAUGE widget.
GAUGE_SetOffset()	Sets an X and Y offset to the arc drawn in the GAUGE widget.
GAUGE_SetRadius()	Sets the radius of the GAUGE.
GAUGE_SetRange()	Sets the range in angles where the GAUGE will be drawn.
GAUGE_SetRoundedEnd()	When enabled, the background line will be drawn with a rounded edge on the ends.
GAUGE_SetRoundedValue()	When enabled, the foreground line will be drawn with a rounded edge on the ends.
GAUGE_SetValue()	Sets a new value for the GAUGE widget.
GAUGE_SetValueRange()	Defines the range of the values shown by the GAUGE widget.
GAUGE_SetWidth()	Sets the width of the line drawn in the GAUGE widget.

Defines

Group of defines	Description
GAUGE curved flags	Define if the GAUGE’s arcs should have rounded edges.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1 Functions

20.10.5.1.1 GAUGE_CreateIndirect()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateIndirect()* on page 974. The elements `Flags` and `Para` of the resource passed as parameter are not used.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.2 GAUGE_CreateUser()

Description

Creates a GAUGE widget.

Prototype

```
GAUGE_Handle GAUGE_CreateUser(int     x0,
                              int     y0,
                              int     xSize,
                              int     ySize,
                              WM_HWIN hParent,
                              int     WinFlags,
                              int     ExFlags,
                              int     Id,
                              int     NumExtraBytes);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the GAUGE widget (in parent coordinates).
y0	Topmost pixel of the GAUGE widget (in parent coordinates).
xSize	Horizontal size of the GAUGE widget (in pixels).
ySize	Vertical size of the GAUGE widget (in pixels).
hParent	Parent window of the GAUGE widget.
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *GAUGE curved flags* on page 1275.
Id	ID of the GAUGE widget.
NumExtraBytes	Number of extra bytes to be allocated.

Return value

Handle of the GAUGE widget.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.3 GAUGE_GetValue()

Description

Returns the current value of a GAUGE.

Prototype

```
I32 GAUGE_GetValue(GAUGE_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.

Return value

Value of the GAUGE widget.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.4 GAUGE_SetAlign()

Description

Sets the alignment of the arc drawn in the GAUGE widget.

Prototype

```
void GAUGE_SetAlign(GAUGE_Handle hObj,
                    int          Align);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
Align	Alignment of the arc in the widget area. *Text alignment flags* on page 218 can be used.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.5 GAUGE_SetBkColor()

Before	After
	

Description

Sets the background color of the GAUGE widget.

Prototype

```
void GAUGE_SetBkColor(GAUGE_Handle hObj,
                      GUI_COLOR    BkColor);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
BkColor	New background color.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.6 GAUGE_SetColor()

Before	After
	

Description

Sets the color of the line drawn in the GAUGE widget.

Prototype

```
void GAUGE_SetColor(GAUGE_Handle hObj,
                    unsigned     Index,
                    GUI_COLOR    Color);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
Index	Line index, 0 for the background line, 1 for the foreground line.
Color	Color of the specified line.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.7 GAUGE_SetOffset()

Description

Sets an X and Y offset to the arc drawn in the GAUGE widget.

Prototype

```
void GAUGE_SetOffset(GAUGE_Handle hObj,
                     int          xOff,
                     int          yOff);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
xOff	X-offset in pixels.
yOff	Y-offset in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.8 GAUGE_SetRadius()

Description

Sets the radius of the GAUGE.

Prototype

```
void GAUGE_SetRadius(GAUGE_Handle hObj,
                     int          Radius);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
Radius	Radius to be used.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.9 GAUGE_SetRange()

Description

Sets the range in angles where the GAUGE will be drawn.

Prototype

```
void GAUGE_SetRange(GAUGE_Handle hObj,
                    I32          Ang0,
                    I32          Ang1);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
Ang0	Angle of starting point.
Ang1	Angle of ending point.

Additional information

The angles have to be specified in 1000th of degrees. For example, 90° equals to 90000.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.10 GAUGE_SetRoundedEnd()

Before	After
	

Description

When enabled, the background line will be drawn with a rounded edge on the ends.

Prototype

```
void GAUGE_SetRoundedEnd(GAUGE_Handle hObj,
                         int          OnOff);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
OnOff	1 for enabling, 0 for disabling.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.11 GAUGE_SetRoundedValue()

Before	After
	

Description

When enabled, the foreground line will be drawn with a rounded edge on the ends. The foreground line is the line that displays the GAUGE's value.

Prototype

```
void GAUGE_SetRoundedValue(GAUGE_Handle hObj,
                           int          OnOff);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
OnOff	1 for enabling, 0 for disabling.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.12 GAUGE_SetValue()

Before	After
	

Description

Sets a new value for the GAUGE widget.

Prototype

```
void GAUGE_SetValue(GAUGE_Handle hObj,
                    I32          Value);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
Value	New value to be set.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.13 GAUGE_SetValueRange()

Description

Defines the range of the values shown by the GAUGE widget.

Prototype

```
void GAUGE_SetValueRange(GAUGE_Handle hObj,
                         I32          Min,
                         I32          Max);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
Min	Minimum value to be set.
Max	Maximum value to be set.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.1.14 GAUGE_SetWidth()

Before	After
	

Description

Sets the width of the line drawn in the GAUGE widget.

Prototype

```
void GAUGE_SetWidth(GAUGE_Handle hObj,
                    unsigned     Index,
                    int          Width);
```

Parameters

Parameter	Description
hObj	Handle of GAUGE widget.
Index	Line index, 0 for the background line, 1 for the foreground line.
Width	Width of the specified line.

 © 2020 SEGGER Microcontroller GmbH

20.10.5.2 Defines

20.10.5.2.1 GAUGE curved flags

Description

With these flags the drawing of the widget's arc lines can be set to have round edges. The flags can be used upon creation of the GAUGE widget.

Definition

```
#define GAUGE_CURVED_VALUE     (1 << 0)
#define GAUGE_CURVED_END       (1 << 1)
```

Symbols

Definition	Description
GAUGE_CURVED_VALUE	The arc that is drawn for the GAUGE's value will have a curved edge on the beginning and end of the line.
GAUGE_CURVED_END	The background arc will be drawn with a curved edge on the beginning and end of the line.

 © 2020 SEGGER Microcontroller GmbH

20.11 GRAPH: Graph widget

GRAPH widgets can be used to visualize data. Typical applications for GRAPH widgets are showing measurement values or the curve of a function graph. Multiple curves can be shown simultaneously. Horizontal and vertical scales can be used to label the curves. A grid with different horizontal and vertical spacing can be shown on the background. If the data array does not fit into the visible area of the graph, the widget can automatically show scroll bars which allow scrolling through large data arrays.

20.11.1 Structure of the graph widget

A GRAPH widget consists of different kinds objects:

- The GRAPH widget itself to which data objects and scale objects can be attached.
- Optionally one or more data objects.
- Optionally one or more scale objects.

The following diagram shows the detailed structure of a graph widget:



The following table explains the details of the diagram above:

Detail	Description
Border	The optional border is part of the graph widget.
Frame	A thin line around the data area, part of the graph widget.
Grid	Shown in the background of the data area, part of the graph widget.
Data area	Area, in which grid and data objects are shown.
Data object(s)	For each curve one data object should be added to the graph widget.
Application defined graphic	An application defined callback function can be used to draw any application defined text and/or graphics.
Scrollbar(s)	If the range of the data object is bigger than the data area of the graph widget, the graph widget can automatically show a horizontal and/or a vertical scroll bar.

 © 2020 SEGGER Microcontroller GmbH

Detail	Description
Scale object(s)	Horizontal and vertical scales can be attached to the graph widget.
X-Size	X-Size of the data area.
Y-Size	Y-Size of the data area.

20.11.2 Creating and deleting a graph widget

The process of creating a GRAPH widget should be the following:

1. Create the GRAPH widget and set the desired attributes.
2. Create the data object(s).
3. Attach the data object(s) to the GRAPH widget.
4. Create the optional scale object(s).
5. Attach the scale object(s) to the GRAPH widget.

Once attached to the graph widget the data and scale objects need not to be deleted by the application. This is done by the graph widget.

Example

The following shows a small example how to create and delete a GRAPH widget:

```
GRAPH_DATA_Handle  hData;
GRAPH_SCALE_Handle hScale;
WM_HWIN hGraph;
hGraph = GRAPH_CreateEx(10, 10, 216, 106, WM_HBKWIN, WM_CF_SHOW, 0, GUI_ID_GRAPH0);
hData
  = GRAPH_DATA_YT_Create(GUI_DARKGREEN, NumDataItems, aData0, MaxNumDataItems);
GRAPH_AttachData(hGraph, hData);
hScale = GRAPH_SCALE_Create(28, GUI_TA_RIGHT, GRAPH_SCALE_CF_VERTICAL, 20);
GRAPH_AttachScale(hGraph, hScale);
/*
  Do something with the widget...
*/
WM_DeleteWindow(hGraph);
```

20.11.3 Drawing process

As explained above a GRAPH widget consists of different parts and ’sub’ objects. The following will explain, in which sequence the widget is drawn:

1. Filling the background with the background color.
2. Calling an optional callback routine. This makes it possible to draw for example a user defined grid.
3. Drawing the grid (if enabled).
4. Drawing the data objects and the border area.
5. Drawing the scale objects.
6. Calling an optional callback routine. This makes it possible to draw for example a user defined scale or some additional text and/or graphics.

20.11.4 Supported types of curves

The requirements for showing a curve with continuously updated measurement values can be different to the requirements when showing a function graph with X/Y coordinates. For that reason the widget currently supports 2 kinds of data objects, which are shown in the table below:

 © 2020 SEGGER Microcontroller GmbH

GRAPH_DATA_XY	GRAPH_DATA_YT
	

20.11.4.1 GRAPH_DATA_XY

This data object is used to show curves which consist of an array of points. The object data is drawn as a polyline. A typical application for using this data object is drawing a function graph.

20.11.4.2 GRAPH_DATA_YT

This data object is used to show curves with one Y-value for each X-position on the graph. A typical application for using this data object is showing a curve with continuously updated measurement values.

20.11.5 Configuration options

20.11.5.1 Graph widget

Type	Macro	Default	Description
N	GRAPH_BKCOLOR_DEFAULT	GUI_BLACK	Default background color of the data area.
N	GRAPH_BORDERCOLOR_DEFAULT	0xC0C0C0	Default background color of the border.
N	GRAPH_FRAMECOLOR_DEFAULT	GUI_WHITE	Default color of the thin frame line.
N	GRAPH_GRIDCOLOR_DEFAULT	GUI_DARKGRAY	Default color used to draw the grid.
N	GRAPH_GRIDSPACING_X_DEFAULT	50	Default horizontal spacing of the grid.
N	GRAPH_GRIDSPACING_Y_DEFAULT	50	Default vertical spacing of the grid.
N	GRAPH_BORDER_L_DEFAULT	0	Default size of the left border.
N	GRAPH_BORDER_T_DEFAULT	0	Default size of the top border.
N	GRAPH_BORDER_R_DEFAULT	0	Default size of the right border.
N	GRAPH_BORDER_B_DEFAULT	0	Default size of the bottom border.

20.11.5.2 Scale object

Type	Macro	Default	Description
N	GRAPH_SCALE_TEXTCOLOR_DEFAULT	GUI_WHITE	Default text color.
S	GRAPH_SCALE_FONT_DEFAULT	&GUI_Font6x8	Default font used to draw the values.

 © 2020 SEGGER Microcontroller GmbH

20.11.6 Predefined IDs

The following symbols define IDs which may be used to make GRAPH widgets distinguishable from creation.

```
#define GUI_ID_GRAPH0    0x220
#define GUI_ID_GRAPH1    0x221
#define GUI_ID_GRAPH2    0x222
#define GUI_ID_GRAPH3    0x223
#define GUI_ID_GRAPH4    0x224
#define GUI_ID_GRAPH5    0x225
#define GUI_ID_GRAPH6    0x226
#define GUI_ID_GRAPH7    0x227
#define GUI_ID_GRAPH8    0x228
#define GUI_ID_GRAPH9    0x229
```

20.11.7 Keyboard reaction

The widget can not gain the input focus and does not react on keyboard input.

20.11.8 GRAPH API

The table below lists the available emWin GRAPH-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
Common routines	
GRAPH_AttachData()	Attaches a data object to an existing GRAPH widget.
GRAPH_AttachScale()	Attaches a scale object to an existing GRAPH widget.
GRAPH_CreateEx()	Creates a GRAPH widget.
GRAPH_CreateIndirect()	Creates a GRAPH widget from a resource table entry.
GRAPH_CreateUser()	Creates a GRAPH widget using extra bytes as user data.
GRAPH_DetachData()	Detaches a data object from a GRAPH widget.
GRAPH_DetachScale()	Detaches a scale object from a GRAPH widget.
GRAPH_GetColor()	This function returns one of the colors set for the GRAPH widget.
GRAPH_GetScrollValue()	Returns the current scroll value for the given scroll bar.
GRAPH_GetUserData()	Retrieves the data set with GRAPH_SetUserData().
GRAPH_InvertScrollbar()	Inverts the direction of the attached scrollbars.
GRAPH_SetAutoScrollbar()	Sets the automatic use of scroll bars.
GRAPH_SetBorder()	Sets the left, top, right and bottom border of the given GRAPH widget.
GRAPH_SetColor()	Sets the desired color of the given GRAPH widget.
GRAPH_SetGridDistX()	Sets the horizontal grid spacing.
GRAPH_SetGridDistY()	Sets the vertical grid spacing.
GRAPH_SetGridFixedX()	Fixes the grid in X-axis.
GRAPH_SetGridOffX()	Adds an offset used to show the vertical grid lines.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GRAPH_SetGridOffY()	Adds an offset used to show the horizontal grid lines.
GRAPH_SetGridVis()	Sets the visibility of the grid lines.
GRAPH_SetLineStyleH()	Sets the line style used to draw the horizontal grid lines.
GRAPH_SetLineStyleV()	Sets the line style used to draw the vertical grid lines.
GRAPH_SetScrollValue()	Sets the scroll value for the given scroll bar.
GRAPH_SetUserData()	Sets the extra data of a GRAPH widget.
GRAPH_SetUserDraw()	Sets the user draw function.
GRAPH_SetVSizeX()	Sets the virtual size in X-axis.
GRAPH_SetVSizeY()	Sets the virtual size in Y-axis.
GRAPH_DATA_YT related routines	
GRAPH_DATA_YT_AddValue()	Adds a new data item to a GRAPH_DATA_YT object.
GRAPH_DATA_YT_Clear()	Clears all data items of the data object.
GRAPH_DATA_YT_Create()	Creates a GRAPH_DATA_YT object.
GRAPH_DATA_YT_Delete()	Deletes the given data object.
GRAPH_DATA_YT_GetValue()	Returns value for the given index.
GRAPH_DATA_YT_MirrorX()	Mirrors the x-axis of the widget.
GRAPH_DATA_YT_SetAlign()	Sets the alignment of the data.
GRAPH_DATA_YT_SetColor()	This function sets a color for the given data object.
GRAPH_DATA_YT_SetOffY()	Sets a vertical offset used to draw the object data.
GRAPH_DATA_XY related routines	
GRAPH_DATA_XY_AddPoint()	Adds a new data item to a GRAPH_DATA_XY object.
GRAPH_DATA_XY_Clear()	Clears all data items of the data object.
GRAPH_DATA_XY_Create()	Creates a GRAPH_DATA_XY object.
GRAPH_DATA_XY_Delete()	Deletes the given data object.
GRAPH_DATA_XY_GetLineVis()	Returns if the line of the data object is visible.
GRAPH_DATA_XY_GetPoint()	Returns a point for the given index.
GRAPH_DATA_XY_GetPointVis()	Returns if the points of a data object have been made visible.
GRAPH_DATA_XY_SetColor()	This function sets a color for the given data object.
GRAPH_DATA_XY_SetLineStyle()	Sets the line style used to draw the polyline.
GRAPH_DATA_XY_SetLineVis()	Sets the visibility of the data object's line.
GRAPH_DATA_XY_SetOffX()	Sets a horizontal offset used to draw the polyline.
GRAPH_DATA_XY_SetOffY()	Sets a vertical offset used to draw the polyline.
GRAPH_DATA_XY_SetOwnerDraw()	Sets the owner callback function.
GRAPH_DATA_XY_SetPenSize()	Sets the pen size used to draw the polyline.
GRAPH_DATA_XY_SetPointVis()	Makes all points of a data object visible.
Scale related routines	
GRAPH_SCALE_Create()	Creates a GRAPH_SCALE object.
GRAPH_SCALE_Delete()	Deletes the given scale object.
GRAPH_SCALE_SetFactor()	Sets a factor used to calculate the numbers to be drawn.
GRAPH_SCALE_SetFont()	Sets the font used to draw the scale numbers.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GRAPH_SCALE_SetNumDecs()	Sets the number of post decimal positions to be shown.
GRAPH_SCALE_SetOff()	Sets an offset used to 'shift' the scale object in positive or negative direction.
GRAPH_SCALE_SetPos()	Sets the position for showing the scale object within the GRAPH widget.
GRAPH_SCALE_SetTextColor()	Sets the text color used to draw the numbers.
GRAPH_SCALE_SetTickDist()	Sets the distance from one number to the next.

Defines

Group of defines	Description
GRAPH alignment flags	Determine the alignment of the date of a graph.
GRAPH color indexes	Color indexes used by the GRAPH widget.
GRAPH create flags	Create flags used for GRAPH widgets.
GRAPH user draw stages	Color indexes used by the GRAPH widget.
SCALE create flags	Create flags used for scale objects.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1 Common routines

20.11.8.1.1 GRAPH_AttachData()

Before	After
	

Description

Attaches a data object to an existing GRAPH widget.

Prototype

```
void GRAPH_AttachData(GRAPH_Handle      hObj,
                      GRAPH_DATA_Handle hData);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget
hData	Handle of the data object to be added to the widget. The data object should be created with GRAPH_DATA_YT_Create() or GRAPH_DATA_XY_Create().

Additional information

Once attached to a GRAPH widget the application does not need to destroy the data object. The GRAPH widget deletes all attached data objects when it is deleted. For details about how to create data objects, refer to GRAPH_DATA_YT_Create() and GRAPH_DATA_XY_Create().

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.2 GRAPH_AttachScale()

Description

Attaches a scale object to an existing GRAPH widget.

Prototype

```
void GRAPH_AttachScale(GRAPH_Handle       hObj,
                       GRAPH_SCALE_Handle hScale);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget
hScale	Handle of the scale to be added.

Additional information

Once attached to a GRAPH widget the application does not need to destroy the scale object. The GRAPH widget deletes all attached scale objects when it is deleted. For details about how to create scale objects, refer to *GRAPH_SCALE_Create* on page 1331.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.3 GRAPH_CreateEx()

Description

Creates a new GRAPH widget of a specified size at a specified location.

Prototype

```
GRAPH_Handle GRAPH_CreateEx(int     x0,
                            int     y0,
                            int     xSize,
                            int     ySize,
                            WM_HWIN hParent,
                            int     WinFlags,
                            int     ExFlags,
                            int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new button window will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *GRAPH create flags* on page 1342.
Id	Window Id of the widget.

Return value

Handle of the created GRAPH widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.4 GRAPH_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Para` of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element `Flags` is used according to the parameter `ExFlags` of the function `GRAPH_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.5 GRAPH_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `GRAPH_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.6 GRAPH_DetachData()

Description

Detaches a data object from a GRAPH widget.

Prototype

```
void GRAPH_DetachData(GRAPH_Handle      hObj,
                      GRAPH_DATA_Handle hData);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget
hData	Handle of the data object to be detached from the widget.

Additional information

Once detached from a GRAPH widget the application needs to destroy the data object. Detaching a data object does not delete it. For more details about deleting data objects, refer to GRAPH_DATA_YT_Delete() and GRAPH_DATA_XY_Delete().

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.7 GRAPH_DetachScale()

Description

Detaches a scale object from a GRAPH widget.

Prototype

```
void GRAPH_DetachScale(GRAPH_Handle       hObj,
                       GRAPH_SCALE_Handle hScale);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget
hScale	Handle of the scale object to be detached from the widget.

Additional information

Once detached from a GRAPH widget the application needs to destroy the scale object. Detaching a scale object does not delete it. For more details about deleting scale objects, refer to GRAPH_SCALE_Delete().

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.8 GRAPH_GetColor()

Description

This function returns one of the colors set for the GRAPH widget.

Prototype

```
GUI_COLOR GRAPH_GetColor(GRAPH_Handle hObj,
                         unsigned     Index);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget
Index	See *GRAPH color indexes* on page 1341 for a full list of permitted values.

Return value

The color which corresponds to the given index.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.9 GRAPH_GetScrollValue()

Description

Returns the current scroll value for the given scroll bar.

Prototype

```
I32 GRAPH_GetScrollValue(GRAPH_Handle hObj,
                         U8           Coord);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget
Coord	See table below.

Permitted values for parameter Coord	
GUI_COORD_X	Get the horizontal scroll value.
GUI_COORD_Y	Get the vertical scroll value.

Return value

Current scroll value. -1, if scroll value could not be determined.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.10 GRAPH_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.11 GRAPH_InvertScrollbar()

Description

This function inverts the direction of the attached scrollbars.

Prototype

```
void GRAPH_InvertScrollbar(GRAPH_Handle hObj,
                           U8           Coord);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget
Coord	See table below.

Permitted values for parameter Coord	
GUI_COORD_X	Inverts the horizontal scrollbar.
GUI_COORD_Y	Inverts the vertical scrollbar.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.12 GRAPH_SetAutoScrollbar()

Description

Sets the automatic use of scroll bars.

Prototype

```
void GRAPH_SetAutoScrollbar(GRAPH_Handle hObj,
                            U8           Coord,
                            U8           OnOff);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget
Coord	See table below.
OnOff	1 the scroll bar should be used automatically. 0, if the scroll bar should not be created automatically.

Permitted values for parameter Coord	
GUI_COORD_X	Toggle automatic creation of the horizontal scroll-bar.
GUI_COORD_Y	Toggle automatic creation of the vertical scrollbar.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.13 GRAPH_SetBorder()

Before	After
	

Description

Sets the left, top, right and bottom border of the given GRAPH widget.

Prototype

```
void GRAPH_SetBorder(GRAPH_Handle hObj,
                     unsigned     BorderL,
                     unsigned     BorderT,
                     unsigned     BorderR,
                     unsigned     BorderB);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget.
BorderL	Size in pixels from the left border.
BorderT	Size in pixels from the top border.
BorderR	Size in pixels from the right border.
BorderB	Size in pixels from the bottom border.

Additional information

The border size is the number of pixels between the widget effect frame and the data area of the GRAPH widget. The frame, the thin line around the data area, is only visible if the border size is at least one pixel. For details about how to set the color of the border and the thin frame, refer to GRAPH_SetColor().

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.14 GRAPH_SetColor()

Before	After
	

Description

Sets the desired color of the given GRAPH widget.

Prototype

```
GUI_COLOR GRAPH_SetColor(GRAPH_Handle hObj,
                         GUI_COLOR    Color,
                         unsigned     Index);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget.
Color	Color to be used for the desired item.
Index	See *GRAPH color indexes* on page 1341 for a full list of permitted values.

Return value

Previous color used for the desired item.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.15 GRAPH_SetGridDistX()

20.11.8.1.16 GRAPH_SetGridDistY()

Before	After
	

Description

These functions set the distance from one grid line to the next.

Prototypes

```
unsigned GRAPH_SetGridDistX(GRAPH_Handle hObj,
                            unsigned     Value);

unsigned GRAPH_SetGridDistY(GRAPH_Handle hObj,
                            unsigned     Value);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget.
Value	Distance in pixels from one grid line to the next, default is 50 pixel.

Return value

Previous grid line distance.

Additional information

The first vertical grid line is drawn at the leftmost position of the data area and the first horizontal grid line is drawn at the bottom position of the data area, except an offset is used.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.17 GRAPH_SetGridFixedX()

Description

Fixes the grid in X-axis.

Prototype

```
unsigned GRAPH_SetGridFixedX(GRAPH_Handle hObj,
                             unsigned     OnOff);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget.
OnOff	1 if grid should be fixed in X-axis, 0 if not (default).

Return value

Previous value used.

Additional information

In some situations it can be useful to fix the grid in X-axis. A typical application would be a YT-graph, to which continuously new values are added and horizontal scrolling is possible. In this case it could be desirable to fix the grid in the background. For details about how to activate scrolling for a GRAPH widget, refer to `GRAPH_SetVSizeX()`.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.18 GRAPH_SetGridOffX()

Description

Adds an offset used to show the vertical grid lines. Similar to `GRAPH_SetGridOffY()`.

Prototype

```
unsigned GRAPH_SetGridOffX(GRAPH_Handle hObj,
                           unsigned     Value);
```

Parameters

Parameter	Description
`hObj`	Handle of GRAPH widget.
`Value`	Offset to be used.

Return value

Previous offset used to draw the vertical grid lines.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.19 GRAPH_SetGridOffY()

Before	After
	

Description

Adds an offset used to show the horizontal grid lines.

Prototype

```
unsigned GRAPH_SetGridOffY(GRAPH_Handle hObj,
                           unsigned     Value);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget.
Value	Offset to be used.

Return value

Previous offset used to draw the horizontal grid lines.

Additional information

When rendering the grid the widget starts drawing the horizontal grid lines from the bottom of the data area and uses the current spacing. In case of a zero point in the middle of the Y-axis it could happen, that there is no grid line in the middle. In this case the grid can be shifted in Y-axis by adding an offset with this function. A positive value shifts the grid down and negative values shifts it up.

For details about how to set the grid spacing, refer to the functions GRAPH_SetGridDistX() and GRAPH_SetGridDistY().

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.20 GRAPH_SetGridVis()

Before	After
	

Description

Sets the visibility of the grid lines.

Prototype

```
unsigned GRAPH_SetGridVis(GRAPH_Handle hObj,
                          unsigned     OnOff);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget.
OnOff	1 if the grid should be visible, 0 if not (default).

Return value

Previous value of the grid visibility.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.21 GRAPH_SetLineStyleH()

20.11.8.1.22 GRAPH_SetLineStyleV()

Before	After
	

Description

These functions are used to set the line style used to draw the horizontal and vertical grid lines.

Prototypes

```
U8 GRAPH_SetLineStyleH(GRAPH_Handle hObj,
                       U8           LineStyle);

U8 GRAPH_SetLineStyleV(GRAPH_Handle hObj,
                       U8           LineStyle);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget.
LineStyle	Line style to be used. For details about the supported line styles, refer to GUI_SetLineStyle().
Default	is GUI_LS_SOLID.

Return value

Previous line style used to draw the horizontal/vertical grid lines.

Additional information

Note that using other styles than GUI_LS_SOLID will need more time to show the grid.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.23 GRAPH_SetScrollValue()

Before	After
	

Description

Sets the scroll value for the given scroll bar.

Prototype

```
void GRAPH_SetScrollValue(GRAPH_Handle hObj,
                          U8           Coord,
                          U32          Value);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget.
Coord	See table below.
Value	Scroll value to set.

Permitted values for parameter Coord	
GUI_COORD_X	Set the horizontal scroll value.
GUI_COORD_Y	Set the vertical scroll value.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.24 GRAPH_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.25 GRAPH_SetUserDraw()

Before	After
	

Description

Sets the user draw function. This function is called by the widget during the drawing process to give the application the possibility to draw user defined data.

Prototype

```
void GRAPH_SetUserDraw(GRAPH_Handle hObj,
                       void         ( *pUserDraw)(WM_HWIN , int ));
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget
pUserDraw	Pointer to application function to be called by the widget during the drawing process.

Additional information

The user draw function is called at the beginning after filling the background of the data area and after drawing all GRAPH items like described at the beginning of the chapter. On the first call the clipping region is limited to the data area. On the last call it is limited to the complete GRAPH widget area except the effect frame.

> **Note**
>
> The user draw routine is called with a parameter State, available values for this parameter are listed under *GRAPH user draw stages* on page 1343.

Example

```
static void _UserDraw(WM_HWIN hWin, int Stage) {
  switch (Stage) {
  case GRAPH_DRAW_FIRST:
    //
    // Draw for example a user defined grid...
    //
    break;
  case GRAPH_DRAW_LAST:
    //
    // Draw for example a user defined scale or additional text...
    //
    break;
  }
}
static void _CreateGraph(void) {
  WM_HWIN hGraph;
  hGraph = GRAPH_CreateEx(10, 10, 216, 106, WM_HBKWIN, WM_CF_SHOW, 0, GUI_ID_GRAPH0);
```

 © 2020 SEGGER Microcontroller GmbH

```
  GRAPH_SetUserDraw(hGraph, _UserDraw);  // Enable user draw
  ...
}
```

 © 2020 SEGGER Microcontroller GmbH

20.11.8.1.26 GRAPH_SetVSizeX()

20.11.8.1.27 GRAPH_SetVSizeY()

Before	After
	

Description

The functions set the virtual size in X and Y-axis.

Prototypes

```
unsigned GRAPH_SetVSizeX(GRAPH_Handle hObj,
                         unsigned     Value);

unsigned GRAPH_SetVSizeY(GRAPH_Handle hObj,
                         unsigned     Value);
```

Parameters

Parameter	Description
hObj	Handle of GRAPH widget.
Value	Virtual size in pixels in X or Y axis.

Return value

Previous virtual size of the widgets data area in X or Y-axis.

Additional information

If the widgets virtual size is bigger than the visible size of the data area, the widget automatically shows a scroll bar. If for example a data object, created by the function GRAPH_DATA_YT_Create(), contains more data than can be shown in the data area, the function GRAPH_SetVSizeX() can be used to enable scrolling. A function call like

 © 2020 SEGGER Microcontroller GmbH

`GRAPH_SetVSizeX(NumDataItems)` enables the horizontal scroll bar, provided that the number of data items is bigger than the X-size of the visible data area.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.2 GRAPH_DATA_YT related routines



20.11.8.2.1 GRAPH_DATA_YT_AddValue()

Before	After
	

Description

Adds a new data item to a GRAPH_DATA_YT object.

Prototype

```
void GRAPH_DATA_YT_AddValue(GRAPH_DATA_Handle hDataObj,
                            I16               Value);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
Value	Value to be added to the data object.

Additional information

The given data value is added to the data object. If the data object is 'full', that means it contains as many data items as specified in parameter MaxNumItems during the creation, it first shifts the data items by one before adding the new value. So the first data item is shifted out when adding a data item to a 'full' object. The value 0x7FFF can be used to handle invalid data values. These values are excluded when drawing the GRAPH. The following screenshot shows a graph with 2 gaps of invalid data:



 © 2020 SEGGER Microcontroller GmbH

20.11.8.2.2 GRAPH_DATA_YT_Clear()

Before	After
	

Description

Clears all data items of the data object.

Prototype

```
void GRAPH_DATA_YT_Clear(GRAPH_DATA_Handle hDataObj);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.2.3 GRAPH_DATA_YT_Create()

Description

Creates a GRAPH_DATA_YT object. This kind of object requires for each point on the x-axis a value on the y-axis. Typically used for time related graphs.

Prototype

```
GRAPH_DATA_Handle GRAPH_DATA_YT_Create(      GUI_COLOR   Color,
                                             unsigned    MaxNumItems,
                                       const I16       * pItems,
                                             unsigned    NumItems);
```

Parameters

Parameter	Description
Color	Color to be used to draw the data.
MaxNumItems	Maximum number of data items.
pItems	Pointer to data to be added to the object. The pointer should point to an array of I16 values.
NumItems	Number of data items to be added.

Return value

Handle of data object if creation was successful, otherwise 0.

Additional information

The last data item is shown at the rightmost column of the data area. If a data object contains more data as can be shown in the data area of the GRAPH widget, the function GRAPH_SetVSizeX() can be used to show a scroll bar which makes it possible to scroll through large data objects.
Once attached to a GRAPH widget a data object does not need to be deleted by the application. This is automatically done during the deletion of the GRAPH widget.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.2.4 GRAPH_DATA_YT_Delete()

Description

Deletes the given data object.

Prototype

```
void GRAPH_DATA_YT_Delete(GRAPH_DATA_Handle hDataObj);
```

Parameters

Parameter	Description
hDataObj	Handle of data object to be deleted.

Additional information

When a GRAPH widget is deleted it deletes all currently attached data objects. So the application needs only to delete unattached data objects.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.2.5 GRAPH_DATA_YT_GetValue()

Description

Returns value for the given index.

Prototype

```
int GRAPH_DATA_YT_GetValue(GRAPH_DATA_Handle   hDataObj,
                           I16               * pValue,
                           U32                 Index);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
pValue	Pointer to a I16 variable.
Index	Index of data to be received.

Return value

0 on success.
1 on error.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.2.6 GRAPH_DATA_YT_MirrorX()

Before	After
	

Description

Mirrors the x-axis of the widget.

Prototype

```
void GRAPH_DATA_YT_MirrorX(GRAPH_DATA_Handle hDataObj,
                           int               OnOff);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
OnOff	1 for mirroring the x-axis, 0 for default view.

Additional information

Per default the data is drawn from the right to the left. After calling this function the data is drawn from the left to the right.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.2.7 GRAPH_DATA_YT_SetAlign()

Before	After
	

Description

Sets the alignment of the data.

Prototype

```
void GRAPH_DATA_YT_SetAlign(GRAPH_DATA_Handle hDataObj,
                            int               Align);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
Align	Alignment of the data. See *GRAPH alignment flags* on page 1340.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.2.8 GRAPH_DATA_YT_SetColor()

Description

This function sets a color for the given data object.

Prototype

```
GUI_COLOR GRAPH_DATA_YT_SetColor(GRAPH_DATA_Handle hDataObj,
                                 GUI_COLOR         Color);
```

Parameters

Parameter	Description
hDataObj	Handle to data object.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.2.9 GRAPH_DATA_YT_SetOffY()

Before	After
	

Description

Sets a vertical offset used to draw the object data.

Prototype

```
void GRAPH_DATA_YT_SetOffY(GRAPH_DATA_Handle hDataObj,
                           int               Off);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
Off	Vertical offset which should be used to draw the data.

Additional information

The vertical range of data, which is shown by the data object, is the range (0) - (Y-size of data area - 1). In case of using a scroll bar the current scroll position is added to the range.

Example

If for example the visible data range should be -200 to -100 the data needs to be shifted in positive direction by 200 pixels:

```
GRAPH_DATA_YT_SetOffY(hDataObj, 200);
```

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3 GRAPH_DATA_XY related routines



20.11.8.3.1 GRAPH_DATA_XY_AddPoint()

Before	After
	

Description

Adds a new data item to a GRAPH_DATA_XY object.

Prototype

```
void GRAPH_DATA_XY_AddPoint(GRAPH_DATA_Handle   hDataObj,
                            GUI_POINT         * pPoint);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
pPoint	Pointer to a GUI_POINT structure to be added to the data object.

Additional information

The given point is added to the data object. If the data object is 'full', that means it contains as many points as specified in parameter MaxNumItems during the creation, it first shifts the data items by one before adding the new point. So the first point is shifted out when adding a new point to a 'full' object.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.2 GRAPH_DATA_XY_Clear()

Description

Clears all data items of the data object.

Prototype

```
void GRAPH_DATA_XY_Clear(GRAPH_DATA_Handle hDataObj);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.3 GRAPH_DATA_XY_Create()

Description

Creates a GRAPH_DATA_XY object. This kind of object is able to store any pairs of values which will be connected by adding order.

Prototype

```
GRAPH_DATA_Handle GRAPH_DATA_XY_Create(      GUI_COLOR   Color,
                                             unsigned    MaxNumItems,
                                       const GUI_POINT * pItems,
                                             unsigned    NumItems);
```

Parameters

Parameter	Description
Color	Color to be used to draw the data.
MaxNumItems	Maximum number of points.
pData	Pointer to data to be added to the object. The pointer should point to a GUI_POINT array.
NumItems	Number of points to be added.

Return value

Handle of data object if creation was successful, otherwise 0.

Additional information

Once attached to a GRAPH widget a data object does not need to be deleted by the application. This is automatically done during the deletion of the GRAPH widget.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.4 GRAPH_DATA_XY_Delete()

Description

Deletes the given data object.

Prototype

```
void GRAPH_DATA_XY_Delete(GRAPH_DATA_Handle hDataObj);
```

Parameters

Parameter	Description
hDataObj	Data object to be deleted.

Additional information

When a GRAPH widget is deleted it deletes all currently attached data objects. So the application needs only to delete unattached data objects.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.5 GRAPH_DATA_XY_GetLineVis()

Description

Returns if the line of the data object is visible.

Prototype

```
unsigned GRAPH_DATA_XY_GetLineVis(GRAPH_DATA_Handle hDataObj);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.

Return value

0 Line is not visible.
1 Line is visible.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.6 GRAPH_DATA_XY_GetPoint()

Description

Returns a point for the given index.

Prototype

```
int GRAPH_DATA_XY_GetPoint(GRAPH_DATA_Handle   hDataObj,
                           GUI_POINT         * pPoint,
                           U32                 Index);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
pPoint	Pointer to a GUI_POINT structure.
Index	Index of data to be received.

Return value

0 on success.
1 on error.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.7 GRAPH_DATA_XY_GetPointVis()

Description

Returns if the points of a data object have been made visible.

Prototype

```
unsigned GRAPH_DATA_XY_GetPointVis(GRAPH_DATA_Handle hDataObj);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.

Return value

0 Points are not made visible.
1 Points are made visible.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.8 GRAPH_DATA_XY_SetColor()

Description

This function sets a color for the given data object.

Prototype

```
GUI_COLOR GRAPH_DATA_XY_SetColor(GRAPH_DATA_Handle hDataObj,
                                 GUI_COLOR         Color);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.9 GRAPH_DATA_XY_SetLineStyle()

Before	After
	

Description

Sets the line style used to draw the polyline.

Prototype

```
void GRAPH_DATA_XY_SetLineStyle(GRAPH_DATA_Handle hDataObj,
                                U8                LineStyle);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
LineStyle	New line style to be used. For details about the supported line styles refer to GUI_SetLineStyle().

Limitations

Note that only curves with line style GUI_LS_SOLID (default) can be drawn with a pen size > 1.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.10 GRAPH_DATA_XY_SetLineVis()

Description

Sets the visibility of the data object's line.

Prototype

```
unsigned GRAPH_DATA_XY_SetLineVis(GRAPH_DATA_Handle hDataObj,
                                  unsigned          OnOff);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
OnOff	1 to make the line visible, 0 to clear visibility flag.

Return value

0 If line was not previously visible.
1 If line was previously visible.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.11 GRAPH_DATA_XY_SetOffX()

20.11.8.3.12 GRAPH_DATA_XY_SetOffY()

Before	After
	

Description

Sets a vertical or horizontal offset used to draw the polyline.

Prototypes

```
void GRAPH_DATA_XY_SetOffX(GRAPH_DATA_Handle hDataObj,
                           int               Off);

void GRAPH_DATA_XY_SetOffY(GRAPH_DATA_Handle hDataObj,
                           int               Off);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
Off	Horizontal/vertical offset which should be used to draw the polyline.

Additional information

The range of data shown by the data object is (0, 0) - (X-size of data area - 1, Y-size of data area - 1). In case of using scroll bars the current scroll position is added to the respective range. To make other ranges of data visible this functions should be used to set an offset, so that the data is in the visible area.

Example

If for example the visible data range should be (100, -1200) - (200, -1100) the following offsets need to be used:

```
GRAPH_DATA_XY_SetOffX(hDataObj, -100);
GRAPH_DATA_XY_SetOffY(hDataObj, 1200);
```

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.13 GRAPH_DATA_XY_SetOwnerDraw()

Description

Sets the owner callback function. This function is called by the widget during the drawing process to give the application the possibility to draw additional items on top of the widget.

Prototype

```
void GRAPH_DATA_XY_SetOwnerDraw(GRAPH_DATA_Handle       hDataObj,
                                WIDGET_DRAW_ITEM_FUNC * pfOwnerDraw);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
Color	Color to be set.

Supported commands

- WIDGET_ITEM_DRAW

Additional information

The owner draw function is called after background, scales and grid lines are drawn.

Example

The following code snippet shows an example of an user draw function:

```
static int _cbData(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo) {
  switch (pDrawItemInfo->Cmd) {
  case WIDGET_ITEM_DRAW:
    GUI_DrawRect(pDrawItemInfo->x0 - 3, pDrawItemInfo->y0 - 3,
                 pDrawItemInfo->x0 + 3, pDrawItemInfo->y0 + 3);
    break;
  }
  return 0;
}
void MainTask(void) {
  WM_HWIN            hGraph;
  GRAPH_DATA_Handle  hData;
  GUI_Init();
  hGraph = GRAPH_CreateEx (140, 100, 171, 131, 0, WM_CF_SHOW, 0, GUI_ID_GRAPH0);
  hData  = GRAPH_DATA_XY_Create(USER_DEFINED_COLOR, 126, 0, 0);
  GRAPH_DATA_XY_SetOwnerDraw(hData, _cbData);
}
```

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.14 GRAPH_DATA_XY_SetPenSize()

Before	After
	

Description

Sets the pen size used to draw the polyline.

Prototype

```
void GRAPH_DATA_XY_SetPenSize(GRAPH_DATA_Handle hDataObj,
                              U8                PenSize);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
PenSize	Pen size which should be used to draw the polyline.

Limitations

Note that only curves with line style GUI_LS_SOLID (default) can be drawn with a pen size > 1.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.3.15 GRAPH_DATA_XY_SetPointVis()

Before	After
	

Description

Makes all points of a data object visible. Each point has a small marking.

Prototype

```
unsigned GRAPH_DATA_XY_SetPointVis(GRAPH_DATA_Handle hDataObj,
                                   unsigned          OnOff);
```

Parameters

Parameter	Description
hDataObj	Handle of data object.
OnOff	1 to make all points visible, 0 to just show the line.

Return value

0 If points were not previously visible.
1 If points were previously visible.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.4 Scale related routines

The GRAPH widget supports horizontal and vertical scales for labeling purpose. The following describes the available functions for using scales.

20.11.8.4.1 GRAPH_SCALE_Create()

Description

Creates a GRAPH_SCALE object.

Prototype

```
GRAPH_SCALE_Handle GRAPH_SCALE_Create(int      Pos,
                                      int      TextAlign,
                                      unsigned Flags,
                                      unsigned TickDist);
```

Parameters

Parameter	Description
Pos	Position relative to the left/top edge of the GRAPH widget.
TextAlign	Text alignment used to draw the numbers. See *Text alignment flags* on page 218.
Flags	See *SCALE create flags* on page 1344.
TickDist	Distance from one tick mark to the next.

Return value

Handle of the scale object if creation was successful, otherwise 0.

Additional information

A horizontal scale object starts labeling from the bottom edge of the data area to the top and a vertical scale object from the left edge (horizontal scale) to the right, where the first position is the zero point. The parameter TickDist specifies the distance between the numbers.

The parameter Pos specifies in case of a horizontal scale the vertical distance in pixels from the top edge of the GRAPH widget to the scale text. In case of a vertical scale the parameter specifies the horizontal distance from the left edge of the GRAPH widget to the horizontal text position. Note that the actual text position also depends on the text alignment specified with parameter TextAlign.

The scale object draws a number for each position which is within the data area. In case of a horizontal scale there is one exception: If the first position is 0 no number is drawn at this position.

Once attached to a GRAPH widget a scale object does not need to be deleted by the application. This is automatically done during the deletion of the GRAPH widget.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.4.2 GRAPH_SCALE_Delete()

Description

Deletes the given scale object.

Prototype

```
void GRAPH_SCALE_Delete(GRAPH_SCALE_Handle hScaleObj);
```

Parameters

Parameter	Description
hScaleObj	Handle of scale object to be deleted.

Additional information

When a GRAPH widget is deleted it deletes all currently attached scale objects. So the application needs only to delete unattached scale objects.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.4.3 GRAPH_SCALE_SetFactor()

Before	After
	

Description

Sets a factor used to calculate the numbers to be drawn.

Prototype

```
float GRAPH_SCALE_SetFactor(GRAPH_SCALE_Handle hScaleObj,
                            float              Factor);
```

Parameters

Parameter	Description
hScaleObj	Handle of scale object.
Factor	Factor to be used to calculate the number.

Return value

Old factor used to calculate the numbers.

Additional information

Without using a factor the unit of the scale object is ’pixel’. So the given factor should convert the pixel value to the desired unit.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.4.4 GRAPH_SCALE_SetFont()

Before	After
	

Description

Sets the font used to draw the scale numbers.

Prototype

```
GUI_FONT *GRAPH_SCALE_SetFont(      GRAPH_SCALE_Handle   hScaleObj,
                              const GUI_FONT           * pFont);
```

Parameters

Parameter	Description
hScaleObj	Handle of scale object.
pFont	Font to be used.

Return value

Previous used font used to draw the numbers.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.4.5 GRAPH_SCALE_SetNumDecs()

Before	After
	

Description

Sets the number of post decimal positions to be shown.

Prototype

```
int GRAPH_SCALE_SetNumDecs(GRAPH_SCALE_Handle hScaleObj,
                           int                NumDecs);
```

Parameters

Parameter	Description
hScaleObj	Handle of scale object.
NumDecs	Number of post decimal positions.

Return value

Previous number of post decimal positions.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.4.6 GRAPH_SCALE_SetOff()

Before	After
	

Description

Sets an offset used to ’shift’ the scale object in positive or negative direction.

Prototype

```
int GRAPH_SCALE_SetOff(GRAPH_SCALE_Handle hScaleObj,
                       int                Off);
```

Parameters

Parameter	Description
hScaleObj	Handle of scale object.
Off	Offset used for drawing the scale.

Return value

Previous used offset.

Additional information

As described under the function GRAPH_SCALE_Create() a horizontal scale object starts labeling from the bottom edge of the data area to the top and a vertical scale object from the left edge (horizontal scale) to the right, where the first position is the zero point. In many situations it is not desirable, that the first position is the zero point. If the scale should be ’shifted’ in positive direction, a positive offset should be added, for negative direction a negative value.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.4.7 GRAPH_SCALE_SetPos()

Before	After
	

Description

Sets the position for showing the scale object within the GRAPH widget.

Prototype

```
int GRAPH_SCALE_SetPos(GRAPH_SCALE_Handle hScaleObj,
                       int                Pos);
```

Parameters

Parameter	Description
hScaleObj	Handle of scale object.
Pos	Position, at which the scale should be shown.

Return value

Previous position of the scale object.

Additional information

The parameter Pos specifies in case of a horizontal scale the vertical distance in pixels from the top edge of the GRAPH widget to the scale text. In case of a vertical scale the parameter specifies the horizontal distance from the left edge of the GRAPH widget to the horizontal text position. Note that the actual text position also depends on the text alignment of the scale object.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.4.8 GRAPH_SCALE_SetTextColor()

Before	After
	

Description

Sets the text color used to draw the numbers.

Prototype

```
GUI_COLOR GRAPH_SCALE_SetTextColor(GRAPH_SCALE_Handle hScaleObj,
                                   GUI_COLOR          Color);
```

Parameters

Parameter	Description
hScaleObj	Handle of scale object.
Color	Color to be used to show the numbers.

Return value

Previous color used to show the numbers.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.4.9 GRAPH_SCALE_SetTickDist()

Before	After
	

Description

Sets the distance from one number to the next.

Prototype

```
unsigned GRAPH_SCALE_SetTickDist(GRAPH_SCALE_Handle hScaleObj,
                                 unsigned           Value);
```

Parameters

Parameter	Description
hScaleObj	Handle of scale object.
Dist	Distance in pixels between the numbers.

Return value

Previous distance between the numbers.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.5 Defines

20.11.8.5.1 GRAPH alignment flags

Description

Flags that define the alignment of the date of a graph.

Definition

```
#define GRAPH_ALIGN_RIGHT    (0 << 0)
#define GRAPH_ALIGN_LEFT     (1 << 0)
```

Symbols

Definition	Description
GRAPH_ALIGN_RIGHT	The data is aligned at the right edge (default).
GRAPH_ALIGN_LEFT	The data is aligned at the left edge.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.5.2 GRAPH color indexes

Description

Color indexes used by the GRAPH widget.

Definition

```
#define GRAPH_CI_BK        0
#define GRAPH_CI_BORDER    1
#define GRAPH_CI_FRAME     2
#define GRAPH_CI_GRID      3
```

Symbols

Definition	Description
GRAPH_CI_BK	Background color.
GRAPH_CI_BORDER	Color of the border area.
GRAPH_CI_FRAME	Color of the thin frame line.
GRAPH_CI_GRID	Color of the grid.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.5.3 GRAPH create flags

Description

Create flags used for GRAPH objects.

Definition

```
#define GRAPH_CF_GRID_FIXED_X         (1 << 0)
#define GRAPH_CF_AVOID_SCROLLBAR_H    (1 << 1)
#define GRAPH_CF_AVOID_SCROLLBAR_V    (1 << 2)
```

Symbols

Definition	Description
GRAPH_CF_GRID_FIXED_X	This flag 'fixes' the grid in X-axis. That means if horizontal scrolling is used, the grid remains in its position.
GRAPH_CF_AVOID_SCROLL-BAR_H	Automatic use of a horizontal scrollbar is disabled. (Default).
GRAPH_CF_AVOID_SCROLL-BAR_V	Automatic use of a vertical scrollbar is disabled. (Default).

 © 2020 SEGGER Microcontroller GmbH

20.11.8.5.4 GRAPH user draw stages

Description

Stages sent to a user draw routine with the `Stage` parameter. For more information, refer to `GRAPH_SetUserDraw()`.

Definition

```
#define GRAPH_DRAW_FIRST           0
#define GRAPH_DRAW_AFTER_BORDER    1
#define GRAPH_DRAW_LAST            2
```

Symbols

Definition	Description
GRAPH_DRAW_FIRST	Gives the application the possibility to perform drawing operations at the beginning of the drawing process.
GRAPH_DRAW_AFTER_BORDER	Gives the application the possibility to perform drawing operations after the border was drawn.
GRAPH_DRAW_LAST	Performs final drawing operations.

 © 2020 SEGGER Microcontroller GmbH

20.11.8.5.5 SCALE create flags

Description

Create flags used for scale objects.

Definition

```
#define GRAPH_SCALE_CF_HORIZONTAL    (0 << 0)
#define GRAPH_SCALE_CF_VERTICAL      (1 << 0)
```

Symbols

Definition	Description
GRAPH_SCALE_CF_HORIZONTAL	Creates a horizontal scale object.
GRAPH_SCALE_CF_VERTICAL	Creates a vertical scale object.

 © 2020 SEGGER Microcontroller GmbH

20.11.9 Examples

The `Sample` folder contains the following examples which show how the widget can be used:

- `WIDGET_GraphXY.c`
- `WIDGET_GraphYT.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_GraphXY.c:



Screenshot of WIDGET_GraphYT.c:



 © 2020 SEGGER Microcontroller GmbH

20.12 HEADER: Header widget

HEADER widgets are used to label columns of a table:



> **Note**
>
> All HEADER-related routines are located in the file(s) `HEADER*.c`, `HEADER.h`.
> All identifiers are prefixed HEADER.

If a pointer input device (PID) is used, the width of the HEADER items can be managed by dragging the dividers by the PID.

Behavior with mouse

If mouse support is enabled, the cursor is on and the PID is moved nearby a divider the cursor will change to signal, that the divider can be dragged at the current position.

Behavior with touch screen

If the widget is pressed nearby a divider and the cursor is on the cursor will change to signal, that the divider can now be dragged.

Screenshot of drag-able divider



Predefined cursors

There are 2 predefined cursors as shown below:

GUI_CursorHeaderM (default)	**GUI_CursorHeaderMI**
	

You can also create and use your own cursors when using a HEADER widget as described later in this chapter.

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.12.1 Configuration options

Type	Macro	Default	Description
N	HEADER_BKCOLOR_DEFAULT	0xAAAAAA	Default value of background color.
S	HEADER_CURSOR_DEFAULT	&GUI_CursorHeaderM	Default cursor.
S	HEADER_FONT_DEFAULT	&GUI_Font13_1	Default font.
N	HEADER_BORDER_H_DEFAULT	2	Horizontal space between text and border.
N	HEADER_BORDER_V_DEFAULT	0	Vertical space between text and border.

 © 2020 SEGGER Microcontroller GmbH

Type	Macro	Default	Description
B	HEADER_SUPPORT_DRAG	1	Enable/disable dragging support.
N	HEADER_TEXTCOLOR_DEFAULT	GUI_BLACK	Default value of text color.

20.12.2 Notification codes

The following events are sent from a HEADER widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	Widget has been clicked.
WM_NOTIFICATION_RELEASED	Widget has been released.
WM_NOTIFICATION_MOVED_OUT	Widget has been clicked and pointer has been moved out of the widget without releasing.

20.12.3 Keyboard reaction

The widget can not gain the input focus and does not react on keyboard input.

20.12.4 HEADER API

The table below lists the available emWin HEADER-related routines in alphabetical order. Detailed descriptions of the routines follow.

Routine	Description
HEADER_AddItem()	Adds an item to an already existing HEADER widget.
HEADER_Create()	Creates a HEADER widget. (Obsolete)
HEADER_CreateAttached()	Creates a HEADER widget attached to a window.
HEADER_CreateEx()	Creates a HEADER widget.
HEADER_CreateIndirect()	Creates a HEADER widget from a resource table entry.
HEADER_CreateUser()	Creates a HEADER widget using extra bytes as user data.
HEADER_DeleteItem()	Deletes an item from the HEADER widget.
HEADER_GetBkColor()	Returns the background color of the given HEADER widget.
HEADER_GetColumnFromPos()	Returns the index of the column matching the given X-position.
HEADER_GetDefaultBkColor()	Returns the default background color used when creating a HEADER widget.
HEADER_GetDefaultBorderH()	Returns the value used for the horizontal spacing when creating a HEADER widget.
HEADER_GetDefaultBorderV()	Returns the value used for the vertical spacing when creating a HEADER widget.
HEADER_GetDefaultCursor()	Returns a pointer to the cursor displayed when dragging the width of an item.
HEADER_GetDefaultFont()	Returns a pointer to the default font used when creating a HEADER widget.
HEADER_GetDefaultTextColor()	Returns the default text color used when creating a HEADER widget.
HEADER_GetFont()	Returns the font of the given HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
HEADER_GetHeight()	Returns the height of the given HEADER widget.
HEADER_GetItemText()	Returns the text for displaying an item with the given index.
HEADER_GetItemWidth()	Returns the item width of the given HEADER widget.
HEADER_GetNumItems()	Returns the number of items of the given HEADER widget.
HEADER_GetSel()	Returns the current selection of the HEADER widget.
HEADER_GetTextColor()	Returns the text color of the given HEADER widget.
HEADER_GetUserData()	Retrieves the data set with HEADER_SetUserData().
HEADER_SetBitmap()	Sets the bitmap used when displaying the specified item.
HEADER_SetBitmapEx()	Sets the bitmap used when displaying the specified item.
HEADER_SetBkColor()	Sets the background color of the given HEADER widget.
HEADER_SetBMP()	Sets the bitmap used when displaying the specified item.
HEADER_SetBMPEx()	Sets the bitmap used when displaying the specified item.
HEADER_SetDefaultBkColor()	Sets the default background color used when creating a HEADER widget.
HEADER_SetDefaultBorderH()	Sets the value used for the horizontal spacing when creating a HEADER widget.
HEADER_SetDefaultBorderV()	Sets the value used for the vertical spacing when creating a HEADER widget.
HEADER_SetDefaultCursor()	Sets the cursor which will be displayed when dragging the width of an HEADER item.
HEADER_SetDefaultFont()	Sets the default font used when creating a HEADER widget.
HEADER_SetDefaultTextColor()	Returns the default text color used when creating a HEADER widget.
HEADER_SetDragLimit()	Sets the limit for dragging the dividers on or off.
HEADER_SetFixed()	Fixes the given number of columns at their horizontal positions.
HEADER_SetFont()	Sets the font used when displaying the given HEADER widget.
HEADER_SetHeight()	Sets the height of the given HEADER widget.
HEADER_SetItemText()	Sets the text used when displaying the specified item.
HEADER_SetItemWidth()	Sets the width of the specified HEADER item.
HEADER_SetScrollPos()	Sets the horizontal scrolling position of the HEADER widget in pixels.
HEADER_SetStreamedBitmap()	Sets the bitmap used when displaying the specified item.
HEADER_SetStreamedBitmapEx()	Sets the bitmap used when displaying the specified item.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
HEADER_SetTextAlign()	Sets the text alignment of the specified HEADER item.
HEADER_SetTextColor()	Sets the text color used when displaying the widget.
HEADER_SetUserData()	Sets the extra data of a HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.1 HEADER_AddItem()

Description

Adds an item to an already existing HEADER widget.

Prototype

```
void HEADER_AddItem(      HEADER_Handle   hObj,
                          int             Width,
                    const char          * s,
                          int             Align);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Width	Width of the new item.
s	Text to be displayed.
Align	Text alignment mode to set. List of flags can be found under *Text alignment flags* on page 218.

Additional information

The Width-parameter can be 0. If Width = 0 the width of the new item will be calculated by the given text and by the default value of the horizontal spacing.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.2 HEADER_Create()

> **Note**
>
> This function is **deprecated**, `HEADER_CreateEx()` should be used instead.

Description

Creates a HEADER widget of a specified size at a specified location.

Prototype

```
HEADER_Handle HEADER_Create(int     x0,
                            int     y0,
                            int     xSize,
                            int     ySize,
                            WM_HWIN hParent,
                            int     Id,
                            int     Flags,
                            int     ExFlags);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the HEADER widget (in parent coordinates).
`y0`	Topmost pixel of the HEADER widget (in parent coordinates).
`xSize`	Horizontal size of the HEADER widget (in pixels).
`ySize`	Vertical size of the HEADER widget (in pixels).
`hParent`	Handle of the parent window
`Id`	`Id` of the new HEADER widget
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
`ExFlags`	(Reserved for later use)

Return value

Handle of the created HEADER widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.3 HEADER_CreateAttached()

Description

Creates a HEADER widget which is attached to an existing window.

Prototype

```
HEADER_Handle HEADER_CreateAttached(WM_HWIN hParent,
                                    int     Id,
                                    int     SpecialFlags);
```

Parameters

Parameter	Description
hObj	Handle HEADER of widget
Id	Id of the HEADER widget
SpecialFlags	(Not used, reserved for later use)

Return value

Handle of the created HEADER widget; 0 if the function fails.

Additional information

An attached HEADER widget is essentially a child window which will position itself on the parent window and operate accordingly.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.4 HEADER_CreateEx()

Description

Creates a HEADER widget of a specified size at a specified location.

Prototype

```
HEADER_Handle HEADER_CreateEx(int     x0,
                              int     y0,
                              int     xSize,
                              int     ySize,
                              WM_HWIN hParent,
                              int     WinFlags,
                              int     ExFlags,
                              int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new HEADER widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used, reserved for future use.
Id	Window ID of the widget.

Return value

Handle of the created HEADER widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.5 HEADER_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. For details the function *<WIDGET>_CreateIndirect()* on page 974 should be referred to. The element Flags is used according to the parameter `WinFlags` of the function `HEADER_CreateEx()`. The element Para is not used.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.6 HEADER_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function HEADER_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.7 HEADER_DeleteItem()

Description

Deletes an item from the HEADER widget.

Prototype

```
void HEADER_DeleteItem(HEADER_Handle hObj,
                       unsigned      Index);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Index	Index of HEADER item.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.8 HEADER_GetBkColor()

Description

Returns the background color of the given HEADER widget.

Prototype

```
GUI_COLOR HEADER_GetBkColor(HEADER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.

Return value

The background color of the given HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.9 HEADER_GetColumnFromPos()

Description

Returns the index of the column matching the given X-position.

Prototype

```
int HEADER_GetColumnFromPos(HEADER_Handle hObj,
                            int           x);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
x	X-position of the item.

Return value

= -1 Error.
≠ -1 Zero-based index of the item matching the X-position.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.10 HEADER_GetDefaultBkColor()

Description

Returns the default background color used when creating a HEADER widget.

Prototype

```
GUI_COLOR HEADER_GetDefaultBkColor(void);
```

Return value

Default background color used when creating a HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.11 HEADER_GetDefaultBorderH()

Description

Returns the value used for the horizontal spacing when creating a HEADER widget.

Prototype

```
int HEADER_GetDefaultBorderH(void);
```

Return value

Value used for the horizontal spacing when creating a HEADER widget.

Additional information

Horizontal spacing means the horizontal distance in pixel between text and the horizontal border of the item. Horizontal spacing takes effect only if the given width of a new item is 0.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.12 HEADER_GetDefaultBorderV()

Description

Returns the value used for the vertical spacing when creating a HEADER widget.

Prototype

```
int HEADER_GetDefaultBorderV(void);
```

Return value

Value used for the vertical spacing when creating a HEADER widget.

Additional information

Vertical spacing means the vertical distance in pixel between text and the vertical border of the HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.13 HEADER_GetDefaultCursor()

Description

Returns a pointer to the cursor displayed when dragging the width of an item.

Prototype

```
GUI_CURSOR *HEADER_GetDefaultCursor(void);
```

Return value

Pointer to the cursor displayed when dragging the width of an item.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.14 HEADER_GetDefaultFont()

Description

Returns a pointer to the default font used when creating a HEADER widget.

Prototype

```
GUI_FONT *HEADER_GetDefaultFont(void);
```

Return value

Pointer to the default font used when creating a HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.15 HEADER_GetDefaultTextColor()

Description

Returns the default text color used when creating a HEADER widget.

Prototype

```
GUI_COLOR HEADER_GetDefaultTextColor(void);
```

Return value

Default text color used when creating a HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.16 HEADER_GetFont()

Description

Returns the font of the given HEADER widget.

Prototype

```
GUI_FONT *HEADER_GetFont(HEADER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.

Return value

The currently set font of the given HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.17 HEADER_GetHeight()

Description

Returns the height of the given HEADER widget.

Prototype

```
int HEADER_GetHeight(HEADER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.

Return value

Height of the given HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.18 HEADER_GetItemText()

Description

Returns the text for displaying an item with the given index.

Prototype

```
int HEADER_GetItemText(HEADER_Handle   hObj,
                       unsigned        Index,
                       char          * pBuffer,
                       int             MaxSize);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Index	Index of HEADER item.
pBuffer	Pointer to a buffer to hold the retrieved text.
MaxSize	The size of pBuffer.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.19 HEADER_GetItemWidth()

Description

Returns the item width of the given HEADER widget.

Prototype

```
int HEADER_GetItemWidth(HEADER_Handle hObj,
                        unsigned int  Index);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Index	Index of the item.

Return value

Width of the item.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.20 HEADER_GetNumItems()

Description

Returns the number of items of the given HEADER widget.

Prototype

```
int HEADER_GetNumItems(HEADER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.

Return value

Number of items of the given HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.21 HEADER_GetSel()

Description

Returns the current selection of the HEADER widget.

Prototype

```
int HEADER_GetSel(HEADER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.

Return value

Current selection.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.22 HEADER_GetTextColor()

Description

Returns the text color of the given HEADER widget.

Prototype

```
GUI_COLOR HEADER_GetTextColor(HEADER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.

Return value

The text color of the given HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.23 HEADER_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.24 HEADER_SetBitmap()

Description

Sets the bitmap used when displaying the specified item.

Prototype

```
void HEADER_SetBitmap(      HEADER_Handle   hObj,
                            unsigned        Index,
                      const GUI_BITMAP    * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget
Index	Index of the item
pBitmap	Pointer to a bitmap structure to be displayed

Additional information

One item of a HEADER widget can contain text and a bitmap. Have a look at the example at HEADER_SetBitmapEx().

 © 2020 SEGGER Microcontroller GmbH

20.12.4.25 HEADER_SetBitmapEx()

Description

Sets the bitmap used when displaying the specified item.

Prototype

```
void HEADER_SetBitmapEx(      HEADER_Handle   hObj,
                              unsigned        Index,
                        const GUI_BITMAP    * pBitmap,
                              int             x,
                              int             y);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget
Index	Index of the item
pBitmap	Pointer to a bitmap structure to be displayed
x	Additional offset in x
y	Additional offset in y

Additional information

One item of a HEADER widget can contain text and a bitmap.

Example

```
...
HEADER_Handle hHeader;
GUI_Init();
HEADER_SetDefaultTextColor(GUI_YELLOW);
HEADER_SetDefaultFont(&GUI_Font8x8);
hHeader = HEADER_Create(10, 10, 100, 40, WM_HBKWIN, 1234, WM_CF_SHOW, 0);
HEADER_AddItem(hHeader, 50, "Phone", GUI_TA_BOTTOM | GUI_TA_HCENTER);
HEADER_AddItem(hHeader, 50, "Code" , GUI_TA_BOTTOM | GUI_TA_HCENTER);
HEADER_SetBitmapEx(hHeader, 0, &bmPhone, 0, -15);
HEADER_SetBitmapEx(hHeader, 1, &bmCode,  0, -15);
...
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

20.12.4.26 HEADER_SetBkColor()

Description

Sets the background color of the given HEADER widget.

Prototype

```
void HEADER_SetBkColor(HEADER_Handle hObj,
                       GUI_COLOR     Color);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Color	Background color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.27 HEADER_SetBMP()

Description

Sets the bitmap used when displaying the specified item.

Prototype

```
void HEADER_SetBMP(      HEADER_Handle   hObj,
                         unsigned int    Index,
                   const void          * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget
Index	Index of HEADER item
pBitmap	Pointer to bitmap file data

Additional information

For additional information regarding bitmap files, refer to the chapter *Displaying bitmap files* on page 385.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.28 HEADER_SetBMPEx()

Description

Sets the bitmap used when displaying the specified item.

Prototype

```
void HEADER_SetBMPEx(      HEADER_Handle   hObj,
                           unsigned int    Index,
                     const void          * pBitmap,
                           int             x,
                           int             y);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget
Index	Index of HEADER item
pBitmap	Pointer to bitmap file data
x	Additional offset in x
y	Additional offset in y

Additional information

For additional information regarding bitmap files, refer to the chapter *Displaying bitmap files* on page 385.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.29 HEADER_SetDefaultBkColor()

Description

Sets the default background color used when creating a HEADER widget.

Prototype

```
GUI_COLOR HEADER_SetDefaultBkColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Background color to be used

Return value

Previous default background color.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.30 HEADER_SetDefaultBorderH()

Description

Sets the value used for the horizontal spacing when creating a HEADER widget.

Prototype

```
int HEADER_SetDefaultBorderH(int Spacing);
```

Parameters

Parameter	Description
Spacing	Value to be used

Return value

Previous default value.

Additional information

Horizontal spacing means the horizontal distance in pixel between text and the horizontal border of the item. Horizontal spacing takes effect only if the given width of a new item is 0.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.31 HEADER_SetDefaultBorderV()

Description

Sets the value used for the vertical spacing when creating a HEADER widget.

Prototype

```
int HEADER_SetDefaultBorderV(int Spacing);
```

Parameters

Parameter	Description
Spacing	Value to be used

Return value

Previous default value.

Additional information

Vertical spacing means the vertical distance in pixel between text and the vertical border of the HEADER widget.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.32 HEADER_SetDefaultCursor()

Description

Sets the cursor which will be displayed when dragging the width of an HEADER item.

Prototype

```
GUI_CURSOR *HEADER_SetDefaultCursor(const GUI_CURSOR * pCursor);
```

Parameters

Parameter	Description
pCursor	Pointer to the cursor to be shown when dragging the width of an HEADER item

Return value

Pointer to the previous default cursor.

Additional information

There are 2 predefined cursors shown at the beginning of this chapter.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.33 HEADER_SetDefaultFont()

Description

Sets the default font used when creating a HEADER widget.

Prototype

```
GUI_FONT *HEADER_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to font to be used

Return value

Pointer to previous default font.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.34 HEADER_SetDefaultTextColor()

Description

Returns the default text color used when creating a HEADER widget.

Prototype

```
GUI_COLOR HEADER_SetDefaultTextColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
`Color`	`Color` to be used

Return value

Previous default value.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.35 HEADER_SetDragLimit()

Description

Sets the limit for dragging the dividers on or off. If the limit is on, a divider can only be dragged within the widget area. If the limit is off, it can be dragged outside the widget.

Prototype

```
void HEADER_SetDragLimit(HEADER_Handle hObj,
                         unsigned      OnOff);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
OnOff	1 for setting the drag limit on, 0 for off.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.36 HEADER_SetFixed()

Description

Fixes the given number of columns at their horizontal positions.

Prototype

```
unsigned HEADER_SetFixed(HEADER_Handle hObj,
                         unsigned      Fixed);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Fixed	Number of columns to be fixed at their horizontal positions.

Return value

Old value of fixed columns.

Additional information

Using this function makes sense if one or more columns should remain at their horizontal positions during scrolling operations.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.37 HEADER_SetFont()

Description

Sets the font used when displaying the given HEADER widget.

Prototype

```
void HEADER_SetFont(      HEADER_Handle   hObj,
                    const GUI_FONT      * pFont);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
pFont	Pointer to font to be used.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.38 HEADER_SetHeight()

Description

Sets the height of the given HEADER widget.

Prototype

```
void HEADER_SetHeight(HEADER_Handle hObj,
                      int           Height);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Height	New height.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.39 HEADER_SetItemText()

Description

Sets the text used when displaying the specified item.

Prototype

```
void HEADER_SetItemText(      HEADER_Handle   hObj,
                              unsigned int    Index,
                        const char          * s);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Index	Index of HEADER item.
s	Pointer to string to be displayed.

Additional information

One HEADER item can contain a string and a bitmap.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.40 HEADER_SetItemWidth()

Description

Sets the width of the specified HEADER item.

Prototype

```
void HEADER_SetItemWidth(HEADER_Handle hObj,
                         unsigned int  Index,
                         int           Width);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Index	Index of HEADER item.
Width	New width.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.41 HEADER_SetScrollPos()

Description

Sets the horizontal scrolling position of the HEADER widget in pixels.

Prototype

```
void HEADER_SetScrollPos(HEADER_Handle hObj,
                         int           ScrollPos);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
ScrollPos	New scroll position in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.42 HEADER_SetStreamedBitmap()

Description

Sets the bitmap used when displaying the specified item.

Prototype

```
void HEADER_SetStreamedBitmap(      HEADER_Handle       hObj,
                                    unsigned int        Index,
                              const GUI_BITMAP_STREAM * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget
Index	Index of the item
pBitmap	Pointer to streamed bitmap data to be displayed

Additional information

For additional information regarding streamed bitmap files, refer to the chapter *2-D Graphic Library* on page 243.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.43 HEADER_SetStreamedBitmapEx()

Description

Sets the bitmap used when displaying the specified item.

Prototype

```
void HEADER_SetStreamedBitmapEx(      HEADER_Handle       hObj,
                                      unsigned int        Index,
                                const GUI_BITMAP_STREAM * pBitmap,
                                      int                 x,
                                      int                 y);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget
Index	Index of the item
pBitmap	Pointer to streamed bitmap data to be displayed
x	Additional offset in x
y	Additional offset in y

Additional information

For additional information regarding streamed bitmap files, refer to the chapter *2-D Graphic Library* on page 243.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.44 HEADER_SetTextAlign()

Description

Sets the text alignment of the specified HEADER item.

Prototype

```
void HEADER_SetTextAlign(HEADER_Handle hObj,
                         unsigned int  Index,
                         int           Align);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Index	Index of HEADER item.
Align	Text alignment mode to set. List of flags can be found under *Text alignment flags* on page 218.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.45 HEADER_SetTextColor()

Description

Sets the text color used when displaying the widget.

Prototype

```
void HEADER_SetTextColor(HEADER_Handle hObj,
                         GUI_COLOR     Color);
```

Parameters

Parameter	Description
hObj	Handle of HEADER widget.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.12.4.46 HEADER_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.12.5 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_Header.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_Header.c:



 © 2020 SEGGER Microcontroller GmbH

20.13 ICONVIEW: Icon view widget

The ICONVIEW widget can be used for icon based menus often required in hand held devices like mobile telephones or pocket organizers. It shows a list of icons where each icon can be labeled with optional text. Icon view widgets support transparency and alpha blending. So any content can be shown in the background. The currently selected icon can be highlighted by a solid color or with an alpha blending effect, which lets the background shine through. If required a scroll bar can be shown.

ICONVIEW with transparency	ICONVIEW without transparency
	

Note

All ICONVIEW-related routines are located in the file(s) `ICONVIEW*.c`, `ICONVIEW*.h`. All identifiers are prefixed ICONVIEW.

20.13.1 Configuration options

Type	Macro	Default	Description
N	`ICONVIEW_BKCOLOR0_DEFAULT`	`GUI_WHITE`	Background color, unselected state.
N	`ICONVIEW_BKCOLOR1_DEFAULT`	`GUI_BLUE`	Background color, selected state.
N	`ICONVIEW_TEXTCOLOR0_DEFAULT`	`GUI_WHITE`	Text color, unselected state.
N	`ICONVIEW_TEXTCOLOR1_DEFAULT`	`GUI_WHITE`	Text color, selected state.
S	`ICONVIEW_FONT_DEFAULT`	`GUI_Font13_1`	Font to be used for drawing the labels.
N	`ICONVIEW_FRAMEX_DEFAULT`	5	Free space between the icons and the left and right border of the widget.
N	`ICONVIEW_FRAMEY_DEFAULT`	5	Free space between the icons and the top and bottom border of the widget.
N	`ICONVIEW_SPACEX_DEFAULT`	5	Free horizontal space between the icons.
N	`ICONVIEW_SPACEY_DEFAULT`	5	Free vertical space between the icons.

 © 2020 SEGGER Microcontroller GmbH

Type	Macro	Default	Description
N	ICONVIEW_ALIGN_DEFAULT	GUI_TA_HCENTER | GUI_TA_BOTTOM	Default alignment to be used for drawing the labels.

20.13.2 Predefined IDs

The following symbols define IDs which may be used to make ICONVIEW widgets distinguishable from creation.

```
#define GUI_ID_ICONVIEW0    0x250
#define GUI_ID_ICONVIEW1    0x251
#define GUI_ID_ICONVIEW2    0x252
#define GUI_ID_ICONVIEW3    0x253
#define GUI_ID_ICONVIEW4    0x254
#define GUI_ID_ICONVIEW5    0x255
#define GUI_ID_ICONVIEW6    0x256
#define GUI_ID_ICONVIEW7    0x257
#define GUI_ID_ICONVIEW8    0x258
#define GUI_ID_ICONVIEW9    0x259
```

20.13.3 Notification codes

The following events are sent from an ICONVIEW widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	Widget has been clicked.
WM_NOTIFICATION_RELEASED	Widget has been released.
WM_NOTIFICATION_MOVED_OUT	Widget has been clicked and pointer has been moved out of the widget area without releasing.
WM_NOTIFICATION_SCROLL_CHANGED	The scroll position of the optional scroll bar has been changed.
WM_NOTIFICATION_SEL_CHANGED	The selection of the widget has been changed.

20.13.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_RIGHT	Moves the selection to the next icon.
GUI_KEY_LEFT	Moves the selection to the previous icon.
GUI_KEY_DOWN	Moves the selection down.
GUI_KEY_UP	Moves the selection up.
GUI_KEY_HOME	Moves the selection to the first icon.
GUI_KEY_END	Moves the selection to the last icon.

20.13.5 ICONVIEW API

The table below lists the available emWin ICONVIEW-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
ICONVIEW_AddBitmapItem()	Adds a new bitmap icon to the widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
ICONVIEW_AddStreamedBitmapItem()	Adds a new streamed bitmap icon to the widget.
ICONVIEW_CreateEx()	Creates an ICONVIEW widget.
ICONVIEW_CreateIndirect()	Creates an ICONVIEW widget from a resource table entry.
ICONVIEW_CreateUser()	Creates an ICONVIEW widget using extra bytes as user data.
ICONVIEW_DeleteItem()	Deletes an existing item.
ICONVIEW_EnableStreamAuto	Adds a new streamed bitmap icon to the widget.
ICONVIEW_GetBkColor()	Returns the background color of the widget.
ICONVIEW_GetFont()	Returns the font of the widget.
ICONVIEW_GetItemBitmap()	Retrieves the bitmap of a specified ICONVIEW item.
ICONVIEW_GetItemText()	Retrieves the text of a specified ICONVIEW item.
ICONVIEW_GetItemUserData()	Retrieves the previously stored user data from a specific item.
ICONVIEW_GetNumItems()	Returns the number of items in the given ICONVIEW widget.
ICONVIEW_GetReleasedItem()	This function returns the index of the released ICONVIEW item.
ICONVIEW_GetSel()	Returns the zero based index of the currently selected icon.
ICONVIEW_GetTextColor()	Returns the text color of the widget.
ICONVIEW_GetUserData()	Retrieves the data set with ICONVIEW_SetUserData().
ICONVIEW_InsertBitmapItem()	Inserts a new bitmap icon to the widget.
ICONVIEW_InsertStreamedBitmapItem()	Inserts a new streamed bitmap icon to the widget.
ICONVIEW_OwnerDraw()	Default function for drawing a ICONVIEW widget.
ICONVIEW_SetBitmapItem()	Sets a bitmap to be used by a specific item.
ICONVIEW_SetBkColor()	Sets the background color of the widget.
ICONVIEW_SetFont()	Sets the font to be used for drawing the icon labels.
ICONVIEW_SetFrame()	Sets the size of the frame between the border of the widget and the icons.
ICONVIEW_SetIconAlign()	Sets the icon alignment.
ICONVIEW_SetItemText()	Sets the text of a specific item.
ICONVIEW_SetItemUserData()	Stores user data in a specific item.
ICONVIEW_SetOwnerDraw()	Sets a custom defined drawing function.
ICONVIEW_SetSel()	Sets the current selection.
ICONVIEW_SetSpace()	Sets the space between icons in x- or y-direction.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
ICONVIEW_SetStreamedBitmapItem()	Sets a streamed bitmap to be used by a specific item.
ICONVIEW_SetTextAlign()	Sets the text align of the item texts.
ICONVIEW_SetTextColor()	Sets the color to be used to draw the labels.
ICONVIEW_SetUserData()	Sets the extra data of an ICONVIEW widget.
ICONVIEW_SetWrapMode()	Sets the wrapping mode to be used for the given ICONVIEW widget.

Defines

Group of defines	Description
ICONVIEW alignment flags	Alignment flags used for ICONVIEW_SetIconAlign().
ICONVIEW color indexes	Color indexes used by the ICONVIEW widget.
ICONVIEW create flags	Create flags used for ICONVIEW widgets.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1 Functions

20.13.5.1.1 ICONVIEW_AddBitmapItem()

Before	After
	

Description

Adds a new bitmap icon to the widget.

Prototype

```
int ICONVIEW_AddBitmapItem(      ICONVIEW_Handle   hObj,
                           const GUI_BITMAP      * pBitmap,
                           const char            * pText);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
pBitmap	Pointer to a bitmap structure used to draw the icon.
pText	Text to be used to label the icon.

Return value

= 0 on success
≠ 0 on error.

Additional information

Note that the bitmap pointer needs to remain valid.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.2 ICONVIEW_AddStreamedBitmapItem()

Before	After
	

Description

Adds a new streamed bitmap icon to the widget.

Prototype

```
int ICONVIEW_AddStreamedBitmapItem(      ICONVIEW_Handle   hObj,
                                   const void            * pStreamedBitmap,
                                   const char            * pText);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
pStreamedBitmap	Pointer to a bitmap stream used to draw the icon.
pText	Text to be used to label the icon.

Return value

= 0 on success
≠ 0 on error.

Additional information

The pointer to the bitmap stream needs to remain valid.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.3 ICONVIEW_CreateEx()

Description

Creates an ICONVIEW widget of a specified size at a specified location.

Prototype

```
ICONVIEW_Handle ICONVIEW_CreateEx(int     x0,
                                  int     y0,
                                  int     xSize,
                                  int     ySize,
                                  WM_HWIN hParent,
                                  int     WinFlags,
                                  int     ExFlags,
                                  int     Id,
                                  int     xSizeItems,
                                  int     ySizeItems);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget in parent coordinates.
y0	Topmost pixel of the widget in parent coordinates.
xSize	Horizontal size of the widget in pixels.
ySize	Vertical size of the widget in pixels.
hParent	Handle of parent window. If 0, the new widget will be a child window of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *ICONVIEW create flags* on page 1438.
Id	Window ID of the widget.
xSizeItem	Horizontal icon size in pixels.
ySizeItem	Vertical icon size in pixels.

Return value

Handle of the new widget, 0 if the function fails.

Additional information

If the widget should be transparent, the parameter WinFlags should be or-combined with WM_CF_HASTRANS.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.4 ICONVIEW_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974.
The upper 16 bit of the element `Para` of the according `GUI_WIDGET_CREATE_INFO` structure are used according to the parameter `ySizeItems` of the function `ICONVIEW_CreateEx()`. The lower 16 bit of the element `Para` are used according to the parameter xSizeItems of the function `ICONVIEW_CreateEx()`. The element Flags is used according to the parameter `WinFlags` of the function `ICONVIEW_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.5 ICONVIEW_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `ICONVIEW_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.6 ICONVIEW_DeleteItem()

Description

Deletes an existing item of the ICONVIEW widget.

Prototype

```
void ICONVIEW_DeleteItem(ICONVIEW_Handle hObj,
                         unsigned        Index);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	Index of the item to be deleted.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.7 ICONVIEW_EnableStreamAuto()

Description

Enables full support for streamed bitmaps.

Prototype

```
void ICONVIEW_EnableStreamAuto(void);
```

Additional information

The ICONVIEW widget supports only index based streamed bitmaps by default. Calling this function enables support for all kinds of streamed bitmaps. This causes all drawing functions for streamed bitmaps to be referenced by the linker.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.8 ICONVIEW_GetBkColor()

Description

Returns the background color of the widget.

Prototype

```
GUI_COLOR ICONVIEW_GetBkColor(ICONVIEW_Handle hObj,
                              int             Index);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	See *ICONVIEW color indexes* on page 1437 for a full list of permitted values.

Return value

The background color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.9 ICONVIEW_GetFont()

Description

Returns the font of the widget.

Prototype

```
GUI_FONT *ICONVIEW_GetFont(ICONVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.

Return value

The font of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.10 ICONVIEW_GetItemBitmap()

Description

Retrieves the bitmap of a specified ICONVIEW item.

Prototype

```
GUI_BITMAP *ICONVIEW_GetItemBitmap(ICONVIEW_Handle hObj,
                                   int             ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
ItemIndex	Index of the item to be used.

Return value

Pointer to the bitmap of the given item.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.11 ICONVIEW_GetItemText()

Description

Retrieves the text of a specified ICONVIEW item.

Prototype

```
int ICONVIEW_GetItemText(ICONVIEW_Handle   hObj,
                         int               Index,
                         char            * pBuffer,
                         int               MaxSize);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	Index of the item to be deleted.
pBuffer	Buffer to retrieve the text.
MaxSize	Maximum length of text to copy to the buffer.

Return value

The length of the actually copied text is returned.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.12 ICONVIEW_GetItemUserData()

Description

Retrieves the previously stored user data from a specific item.

Prototype

```
U32 ICONVIEW_GetItemUserData(ICONVIEW_Handle hObj,
                             int             Index);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	Index of the item.

Return value

User data stored in the item as U32.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.13 ICONVIEW_GetNumItems()

Description

Returns the number of items in the given ICONVIEW widget.

Prototype

```
int ICONVIEW_GetNumItems(ICONVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.

Return value

Number of items.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.14 ICONVIEW_GetReleasedItem()

Description

This function returns the index of the released ICONVIEW item.

Prototype

```
int ICONVIEW_GetReleasedItem(ICONVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.

Return value

Zero based index of last released item.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.15 ICONVIEW_GetSel()

Description

Returns the zero based index of the currently selected icon.

Prototype

```
int ICONVIEW_GetSel(ICONVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.

Return value

Zero based index of the currently selected icon.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.16 ICONVIEW_GetTextColor()

Description

Returns the text color of the widget.

Prototype

```
GUI_COLOR ICONVIEW_GetTextColor(ICONVIEW_Handle hObj,
                                int             Index);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	See *ICONVIEW color indexes* on page 1437 for a full list of permitted values.

Return value

The text color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.17 ICONVIEW_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.18 ICONVIEW_InsertBitmapItem()

Description

Inserts a new bitmap icon to the widget.

Prototype

```
int ICONVIEW_InsertBitmapItem(      ICONVIEW_Handle   hObj,
                              const GUI_BITMAP      * pBitmap,
                              const char            * pText,
                                    int               Index);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
pBitmap	Pointer to a bitmap structure used to draw the icon.
pText	Text to be used to label the icon.
Index	Index position to insert the item at.

Return value

= 0 on success
≠ 0 on error.

Additional information

See ICONVIEW_AddBitmapItem() for screenshots. Note that the bitmap pointer needs to remain valid.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.19 ICONVIEW_InsertStreamedBitmapItem()

Description

Inserts a new streamed bitmap icon to the widget.

Prototype

```
int ICONVIEW_InsertStreamedBitmapItem(      ICONVIEW_Handle   hObj,
                                      const void            * pStreamedBitmap,
                                      const char            * pText,
                                            int               Index);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
pStreamedBitmap	Pointer to a bitmap stream used to draw the icon.
pText	Text to be used to label the icon.
Index	Index position to insert the item at.

Return value

= 0 on success
≠ 0 on error.

Additional information

See ICONVIEW_AddBitmapItem() for screenshots. The pointer to the bitmap stream needs to remain valid.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.20 ICONVIEW_OwnerDraw()

Description

Default function for drawing a ICONVIEW widget.

Prototype

```
int ICONVIEW_OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo);
```

Parameters

Parameter	Description
pDrawItemInfo	Pointer to a WIDGET_ITEM_DRAW_INFO structure.

Return value

Returns 0.

Additional information

This function is useful if ICONVIEW_SetOwnerDraw() has been used. It can be used from the custom drawing routine for managing all not handled commands. For more information please refer to *ICONVIEW_SetOwnerDraw()* on page .

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.21 ICONVIEW_SetBitmapItem()

Before	After
	

Description

Sets a bitmap to be used by a specific item.

Prototype

```
int ICONVIEW_SetBitmapItem(      ICONVIEW_Handle   hObj,
                                 int               Index,
                           const GUI_BITMAP      * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	Index of the item.
pBitmap	Pointer to the bitmap to be used.

Return value

Returns 0.

Additional information

The pointer to the bitmap structure needs to remain valid.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.22 ICONVIEW_SetBkColor()

Before	After
	

Description

Sets the background color of the widget.

Prototype

```
void ICONVIEW_SetBkColor(ICONVIEW_Handle hObj,
                         int             Index,
                         GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	See *ICONVIEW color indexes* on page 1437 for a full list of permitted values.
Color	Color to be used for drawing the background.

Additional information

The upper 8 bits of the 32 bit color value can be used for an alpha blending effect. For more details about alpha blending, refer to GUI_SetAlpha().

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.23 ICONVIEW_SetFont()

Before	After
	

Description

Sets the font to be used for drawing the icon labels.

Prototype

```
void ICONVIEW_SetFont(      ICONVIEW_Handle   hObj,
                      const GUI_FONT        * pFont);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
pFont	Pointer to a GUI_FONT structure to be used to draw the icon labels.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.24 ICONVIEW_SetFrame()

Before	After
	

Description

Sets the size of the frame between the border of the widget and the icons.

Prototype

```
void ICONVIEW_SetFrame(ICONVIEW_Handle hObj,
                       int             Coord,
                       int             Value);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Coord	See permitted values for this parameter below.
Value	Distance to be set.

Permitted values for parameter Coord	
GUI_COORD_X	X-direction.
GUI_COORD_Y	Y-direction.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.25 ICONVIEW_SetIconAlign()

Before	After
	

Description

Sets the icon alignment.

Prototype

```
void ICONVIEW_SetIconAlign(ICONVIEW_Handle hObj,
                           int             IconAlign);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
IconAlign	Alignment of the icons. See *ICONVIEW alignment flags* on page 1436.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.26 ICONVIEW_SetItemText()

Before	After
	

Description

Sets the text of a specific item.

Prototype

```
void ICONVIEW_SetItemText(      ICONVIEW_Handle   hObj,
                                int               Index,
                          const char            * s);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	Index of the item.
pText	Pointer to the text to be used.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.27 ICONVIEW_SetItemUserData()

Description

Stores user data in a specific item.

Prototype

```
void ICONVIEW_SetItemUserData(ICONVIEW_Handle hObj,
                              int             Index,
                              U32             UserData);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	Index of the item.
UserData	32 bit user data to be stored.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.28 ICONVIEW_SetOwnerDraw()

Description

Sets an application defined owner draw function for the widget which is responsible for drawing the widget.

Prototype

```
void ICONVIEW_SetOwnerDraw(ICONVIEW_Handle         hObj,
                           WIDGET_DRAW_ITEM_FUNC * pfDrawItem);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
pfOwnerDraw	Pointer to owner draw function.

Supported commands

- WIDGET_ITEM_CREATE
- WIDGET_DRAW_BACKGROUND
- WIDGET_ITEM_DRAW_BACKGROUND
- WIDGET_ITEM_DRAW_BITMAP
- WIDGET_ITEM_DRAW_TEXT

Additional information

This function sets a pointer to an application defined function which will be called by the widget when a data item has to be drawn or when the x or y size of a item is needed. pfDrawItem is a pointer to an application-defined function of type WIDGET_DRAW_ITEM_FUNC which is explained at the beginning of the chapter.

Example

The following example uses a bitmap for drawing the widget background:

```
static int _OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo) {
  switch (pDrawItemInfo->Cmd) {
  case WIDGET_DRAW_BACKGROUND:
    GUI_DrawBitmap(&Bitmap, 0, 0);
    break;
  default:
    return ICONVIEW_OwnerDraw(pDrawItemInfo);
  }
  return 0;
}
```

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.29 ICONVIEW_SetSel()

Before	After
	

Description

Sets the current selection.

Prototype

```
void ICONVIEW_SetSel(ICONVIEW_Handle hObj,
                     int             Sel);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Sel	New selection.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.30 ICONVIEW_SetSpace()

Before	After
	

Description

Sets the space between icons in x- or y-direction.

Prototype

```
void ICONVIEW_SetSpace(ICONVIEW_Handle hObj,
                       int             Coord,
                       int             Value);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Coord	See permitted values for this parameter below.
Value	Distance to be set.

Permitted values for parameter Coord	
GUI_COORD_X	X-direction.
GUI_COORD_Y	Y-direction.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.31 ICONVIEW_SetStreamedBitmapItem()

Before	After
	

Description

Sets a streamed bitmap to be used by a specific item.

Prototype

```
int ICONVIEW_SetStreamedBitmapItem(      ICONVIEW_Handle   hObj,
                                         int               Index,
                                   const void            * pStreamedBitmap);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	Index of the item.
pStreamedBitmap	Pointer to the bitmap stream to be used.

Additional information

The pointer to the bitmap stream needs to remain valid.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.32 ICONVIEW_SetTextAlign()

Before	After
	

Description

Sets the text align of the item texts.

Prototype

```
void ICONVIEW_SetTextAlign(ICONVIEW_Handle hObj,
                           int             TextAlign);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
TextAlign	Text alignment mode. List of flags can be found under *Text alignment flags* on page 218.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.33 ICONVIEW_SetTextColor()

Before	After
	

Description

Sets the color to be used to draw the labels.

Prototype

```
void ICONVIEW_SetTextColor(ICONVIEW_Handle hObj,
                           int             Index,
                           GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
Index	See *ICONVIEW color indexes* on page 1437 for a full list of permitted values.
Color	Color to be used

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.34 ICONVIEW_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.1.35 ICONVIEW_SetWrapMode()

Description

Sets the wrapping mode to be used for the given ICONVIEW widget.

Prototype

```
void ICONVIEW_SetWrapMode(ICONVIEW_Handle hObj,
                          GUI_WRAPMODE    WrapMode);
```

Parameters

Parameter	Description
hObj	Handle of ICONVIEW widget.
WrapMode	See table below.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.2 Defines

20.13.5.2.1 ICONVIEW alignment flags

Description

Alignment flags similar to the Text alignment flags used for aligning the icons of an ICONVIEW widget using the routine `ICONVIEW_SetIconAlign()`. These flags are also OR-combinable.

Definition

```
#define ICONVIEW_IA_HCENTER    (0 << 0)
#define ICONVIEW_IA_LEFT       (1 << 0)
#define ICONVIEW_IA_RIGHT      (2 << 0)
#define ICONVIEW_IA_VCENTER    (0 << 2)
#define ICONVIEW_IA_BOTTOM     (1 << 2)
#define ICONVIEW_IA_TOP        (2 << 2)
```

Symbols

Definition	Description
Horizontal alignment	
ICONVIEW_IA_LEFT	Align X-position left.
ICONVIEW_IA_HCENTER	Center X-position. (default)
ICONVIEW_IA_RIGHT	Align X-position right.
Vertical alignment	
ICONVIEW_IA_TOP	Align Y-position with top of characters.
ICONVIEW_IA_VCENTER	Center Y-position. (default)
ICONVIEW_IA_BOTTOM	Align Y-position with bottom pixel line of font.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.2.2 ICONVIEW color indexes

Description

Color indexes used by the ICONVIEW widget.

Definition

```
#define ICONVIEW_CI_BK          0
#define ICONVIEW_CI_UNSEL       0
#define ICONVIEW_CI_SEL         1
#define ICONVIEW_CI_DISABLED    2
```

Symbols

Definition	Description
ICONVIEW_CI_BK	Color used to draw the widget background.
ICONVIEW_CI_UNSEL	Color of an unselected item.
ICONVIEW_CI_SEL	Color of a selected item.
ICONVIEW_CI_DISABLED	Color used in disabled state.

Additional information

ICONVIEW_CI_BK is only used by the routines ICONVIEW_GetBkColor() and ICONVIEW_SetBkColor() instead of ICONVIEW_CI_UNSEL.

 © 2020 SEGGER Microcontroller GmbH

20.13.5.2.3 ICONVIEW create flags

Description

Create flags for the ICONVIEW widget. These flags can be passed to `ICONVIEW_CreateEx()` via the `ExFlags` parameter.

Definition

```
#define ICONVIEW_CF_AUTOSCROLLBAR_V    (1 << 1)
```

Symbols

Definition	Description
ICONVIEW_CF_AUTOSCROLLBAR_V	A vertical scroll bar will be added if the widget area is too small to show all icons.

 © 2020 SEGGER Microcontroller GmbH

20.13.6 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_IconView.c`

Screenshot of WIDGET_Iconview.c:



 © 2020 SEGGER Microcontroller GmbH

20.14 IMAGE: Image widget

IMAGE widgets are used to display images of different formats from internal as well as from external memory.



> **Note**
>
> All IMAGE-related routines are located in the file(s) `IMAGE*.c`, `IMAGE.h`.
> All identifiers are prefixed IMAGE.

20.14.1 Configuration options

The IMAGE widget can be configured using an OR-combination of flags as `ExFlags`-parameter at creation. A full list of flags can be found under *IMAGE create flags* on page 1452.

20.14.2 Predefined IDs

The following symbols define IDs which may be used to make IMAGE widgets distinguishable from creation.

```
#define GUI_ID_IMAGE0    0x270
#define GUI_ID_IMAGE1    0x271
#define GUI_ID_IMAGE2    0x272
#define GUI_ID_IMAGE3    0x273
#define GUI_ID_IMAGE4    0x274
#define GUI_ID_IMAGE5    0x275
#define GUI_ID_IMAGE6    0x276
#define GUI_ID_IMAGE7    0x277
#define GUI_ID_IMAGE8    0x278
#define GUI_ID_IMAGE9    0x279
```

20.14.3 Notification codes

The following events are sent from an `IMAGE` widget to its parent window as part of a `WM_NOTIFY_PARENT` message:

Message	Description
`WM_NOTIFICATION_CLICKED`	The widget has been clicked.
`WM_NOTIFICATION_RELEASED`	The widget has been released.
`WM_NOTIFICATION_MOVED_OUT`	The pointer was moved out of the widget area while the PID was in pressed state.

20.14.4 IMAGE API

The table below lists the available IMAGE-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
`IMAGE_CreateEx()`	Creates an IMAGE widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
IMAGE_CreateIndirect()	Creates a IMAGE widget from a resource table entry.
IMAGE_CreateUser()	Creates a IMAGE widget using extra bytes as user data.
IMAGE_GetImageSize()	Returns the X- and Y-size of the image set to the widget.
IMAGE_GetUserData()	Retrieves the data set with IMAGE_SetUserData().
IMAGE_SetBitmap()	Sets a bitmap to be displayed.
IMAGE_SetBMP()	Sets a BMP file to be displayed.
IMAGE_SetBMPEx()	Sets a BMP file to be displayed from external memory.
IMAGE_SetDTA()	Sets a DTA file to be displayed.
IMAGE_SetDTAEx()	Sets a DTA file to be displayed from external memory.
IMAGE_SetGIF()	Sets a GIF file to be displayed.
IMAGE_SetGIFEx()	Sets a GIF file to be displayed from external memory.
IMAGE_SetJPEG()	Sets a JPEG file to be displayed.
IMAGE_SetJPEGEx()	Sets a JPEG file to be displayed from external memory.
IMAGE_SetPNG()	Sets a PNG file to be displayed.
IMAGE_SetPNGEx()	Sets a PNG file to be displayed from external memory.
IMAGE_SetTiled()	Enables tiled mode for an IMAGE widget.
IMAGE_SetUserData()	Sets the extra data of an IMAGE widget.

Defines

Group of defines	Description
IMAGE create flags	Create flags used for IMAGE widgets.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1 Functions

20.14.4.1.1 IMAGE_CreateEx()

Description

Creates an IMAGE widget of a specified size at a specified location.

Prototype

```
IMAGE_Handle IMAGE_CreateEx(int     x0,
                            int     y0,
                            int     xSize,
                            int     ySize,
                            WM_HWIN hParent,
                            int     WinFlags,
                            int     ExFlags,
                            int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the IMAGE widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *IMAGE create flags* on page 1452.
Id	Window ID of the widget.

Return value

Handle of the created IMAGE widget; 0 if the function fails.

Additional information

If the possibility of storing user data is a matter the function IMAGE_CreateUser() should be used instead.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1.2 IMAGE_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. For details the function *<WIDGET>_CreateIndirect()* on page 974 should be referred to. The element `Flags` is used according to the parameter `WinFlags` of the function `IMAGE_CreateEx()`. The element `Para` is used according to the parameter `ExFlags` of the function `IMAGE_CreateEx()`. For a detailed description of the parameters the function `IMAGE_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1.3 IMAGE_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `IMAGE_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1.4 IMAGE_GetImageSize()

Description

Returns the X- and Y-size of the image set to the widget.

Prototype

```
int IMAGE_GetImageSize(IMAGE_Handle   hObj,
                       int          * pxSize,
                       int          * pySize);
```

Parameters

Parameter	Description
hObj	Handle of IMAGE widget.
pxSize	Pointer to an integer to store the X-size.
pySize	Pointer to an integer to store the Y-size.

Return value

0 On success.
1 On error.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1.5 IMAGE_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1.6 IMAGE_SetBitmap()

Description

Sets a bitmap to be displayed.

Prototype

```
void IMAGE_SetBitmap(      IMAGE_Handle   hObj,
                     const GUI_BITMAP   * pBitmap);
```

Parameters

Parameter	Description
hWin	Handle of IMAGE widget.
pBitmap	Pointer to the bitmap.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1.7 IMAGE_SetBMP()

20.14.4.1.8 IMAGE_SetDTA()

20.14.4.1.9 IMAGE_SetGIF()

20.14.4.1.10 IMAGE_SetJPEG()

20.14.4.1.11 IMAGE_SetPNG()

Description

These functions set a file of one of the formats listed below to be displayed:

- BMP
- DTA
- GIF
- JPEG
- PNG

Prototype

```
void IMAGE_Set<FORMAT>(      IMAGE_Handle hObj,
                       const void       * pData,
                             U32          FileSize);
```

Parameters

Parameter	Description
hObj	Handle of IMAGE widget.
pData	Pointer to the IMAGE data.
FileSize	Size of the IMAGE data.

Additional information

The PNG functionality requires the PNG library which can be downloaded from www.segger.com. Animated GIF files are displayed automatically. Please make sure that each sub image of a GIF file replaces the previous one.

With a photo editing tool, such as GIMP, it is possible to convert a GIF file into the proper format. Follow these steps to create such a GIF file with GIMP:

1. Open the GIF file
2. On the menu bar click **Filters ➔ Animation ➔ Unoptimize**
3. Export as GIF

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1.12 IMAGE_SetBMPEx()

20.14.4.1.13 IMAGE_SetDTAEx()

20.14.4.1.14 IMAGE_SetGIFEx()

20.14.4.1.15 IMAGE_SetJPEGEx()

20.14.4.1.16 IMAGE_SetPNGEx()

Description

These functions set a file of one of the formats listed below to be displayed from external memory:

- BMP
- DTA
- GIF
- JPEG
- PNG

Prototype

```
void IMAGE_Set<FORMAT>Ex(IMAGE_Handle         hObj,
                         GUI_GET_DATA_FUNC * pfGetData,
                         void              * pVoid);
```

Additional information

The PNG functionality requires the PNG library which can be downloaded from www.segger.com. Animated GIF files are displayed automatically.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1.17 IMAGE_SetTiled()

Before	After
	

Description

Enables tiled mode for an IMAGE widget. With tiled mode, the entire area of the widget is filled with the set image, even if the image is smaller than the widget area.

Prototype

```
void IMAGE_SetTiled(IMAGE_Handle hObj,
                    int          OnOff);
```

Parameters

Parameter	Description
hObj	Handle of IMAGE widget.
OnOff	1 for enabling tiled mode, 0 for disabling it.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.1.18 IMAGE_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.14.4.2 Defines

20.14.4.2.1 IMAGE create flags

Description

Create flags for the IMAGE widget. These flags can be passed to `ICONVIEW_CreateEx()` via the `ExFlags` parameter.

Definition

```
#define IMAGE_CF_MEMDEV      (1 << 0)
#define IMAGE_CF_TILE        (1 << 1)
#define IMAGE_CF_ALPHA       (1 << 2)
#define IMAGE_CF_ATTACHED    (1 << 3)
#define IMAGE_CF_AUTOSIZE    (1 << 4)
```

Symbols

Definition	Description
IMAGE_CF_MEMDEV	Makes the IMAGE widget use an internal Memory Device for drawing. Contrary to the Memory Device which is created by the Window Manager#s automatic use of Memory Devices (WM_CF_MEMDEV), this device stays valid all the time. It has to be ensured that the emWin memory pool which is defined by the function GUI_ALLOC_AssignMemory() (in GUIConf.c), is big enough to store the complete data. If the Memory Device can not be created, the image is drawn directly. This might possibly mean loss of performance.
IMAGE_CF_TILE	Uses tiling to fill up the whole area of the widget.
IMAGE_CF_ALPHA	Needs to be set if alpha blending is required (PNG).
IMAGE_CF_ATTACHED	Widget size is fixed to the parent border.
IMAGE_CF_AUTOSIZE	Widget size is taken from the attached image.

 © 2020 SEGGER Microcontroller GmbH

20.15 KNOB: Knob widget (obsolete)

> **Note**
>
> The KNOB widget is obsolete and has been replaced by the ROTARY widget!

The KNOB widget is used to change a value with a knob. The KNOB widget is transparent per default and it requires a memory device containing a drawn knob to be visible. If the memory device contains transparency, any content can be shown in the background.

Drawn knob with transparency	How it appears used as KNOB widget
	

> **Note**
>
> All KNOB-related routines are in the file(s) `KNOB.c` and `KNOB.h`.
> All identifiers are prefixed with KNOB.

Ticks and Ticksize

A Tick describes the smallest range of movement of the KNOB widget. The smallest size of one Tick (Ticksize 1) equates 1/10 of a degree. So it takes 3600 Ticks to fulfill one round. The size of one Tick can be set with the function `KNOB_SetTickSize()`.

Examples

Ticksize	Ticks for one round
60	60
36	100
300	12

20.15.1 Requirements

This widget requires the optional memory devices. Without the optional memory devices package the widget can not be used! The memory device which contains the drawn knob will not be deleted if the KNOB widget gets deleted. Make sure to delete the memory device by yourself if it is not any longer required.

Memory requirements

At least the widget uses two memory devices with a color depth of 32bpp (one with the drawn knob, one for internal use). The required amount of memory depends on using an additional memory device for the background or not. Detailed information on how to calculate memory requirements can be found in the chapter *Memory Devices* on page 666.

Approximate memory usage without a background device: `XSIZE × 4 × YSIZE × 2`

 © 2020 SEGGER Microcontroller GmbH

20.15.2 Configuration options

Type	Macro	Default	Description
N	KNOB_BKCOLOR_DEFAULT	GUI_TRANSPARENT	Background color
N	KNOB_KEYVALUE_DEFAULT	1	Range the KNOB will rotate on one key press in 1/10 of degree.
N	KNOB_OFFSET_DEFAULT	0	An offset added to initial point of the KNOB in 1/10 of degree.
N	KNOB_PERIOD_DEFAULT	1500	Time the KNOB takes to stop in ms.
N	KNOB_SNAP_DEFAULT	0	Interval where the KNOB automatically stops in 1/10 of degree.
N	KNOB_TICKSIZE_DEFAULT	1	Size of one tick in 1/10 of degree.

20.15.3 Predefined IDs

The following symbols define IDs which may be used to make KNOB widgets distinguishable from creation.

```
#define GUI_ID_KNOB0    0x300
#define GUI_ID_KNOB1    0x301
#define GUI_ID_KNOB2    0x302
#define GUI_ID_KNOB3    0x303
#define GUI_ID_KNOB4    0x304
#define GUI_ID_KNOB5    0x305
#define GUI_ID_KNOB6    0x306
#define GUI_ID_KNOB7    0x307
#define GUI_ID_KNOB8    0x308
#define GUI_ID_KNOB9    0x309
```

20.15.4 Notification codes

The following events are sent from a KNOB widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	KNOB has been clicked.
WM_NOTIFICATION_RELEASED	KNOB has been released.
WM_NOTIFICATION_MOVED_OUT	KNOB has been clicked and pointer has been moved out of the KNOB area without releasing.
WM_NOTIFICATION_VALUE_CHANGED	The value of the KNOB widget has been changed.

20.15.5 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_RIGHT	The KNOB rotates CW.
GUI_KEY_LEFT	The KNOB rotates CCW.
GUI_KEY_DOWN	The KNOB rotates CW.
GUI_KEY_UP	The KNOB rotates CCW.

20.15.6 KNOB API

The table below lists the available emWin KNOB-related routines in alphabetical order. Detailed descriptions of the routines follow.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
KNOB_AddValue()	Adds a value to the position of the KNOB widget around its rotary axis.
KNOB_CreateEx()	Creates a KNOB widget.
KNOB_CreateIndirect()	Creates a KNOB widget from a resource table entry.
KNOB_CreateUser()	Creates a KNOB widget using extra bytes as user data.
KNOB_GetUserData()	Retrieves the data set with KNOB_SetUserData().
KNOB_GetValue()	Returns the current value of the KNOB widget.
KNOB_SetBkColor()	Sets a color for the background of the KNOB widget.
KNOB_SetBkDevice()	Sets a memory device to be shown as background.
KNOB_SetDevice()	Sets a memory device which contains a drawn knob.
KNOB_SetInvert()	Inverts the value of the knob.
KNOB_SetKeyValue()	Sets a value which defines the movement range of the KNOB on one key press.
KNOB_SetOffset()	Sets an offset angle for the KNOB widget.
KNOB_SetPeriod()	Sets a time period which defines how long the KNOB will need to stop.
KNOB_SetPos()	Sets a new position for the KNOB widget around its rotary axis.
KNOB_SetRange()	Sets a range within the KNOB can be rotated.
KNOB_SetRotateHQ()	Selects high quality rotating.
KNOB_SetRotateLQ()	Selects low quality rotating.
KNOB_SetSnap()	Sets a range between snap positions where the KNOB automatically stops.
KNOB_SetTickSize()	Sets the size of one tick.
KNOB_SetUserData()	Sets the extra data of a KNOB widget.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.1 KNOB_AddValue()

Description

Adds a value to the position of the KNOB widget around its rotary axis.

Prototype

```
void KNOB_AddValue(KNOB_Handle hObj,
                   I32         Value);
```

Parameters

Parameter	Description
hObj	Handle of the KNOB widget.
Value	Value to be added to the position around the rotary axis in ticks.

Additional information

A positive Value rotates the knob counter-clockwise and a negative Value clockwise.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.2 KNOB_CreateEx()

Description

Creates a KNOB widget of a specified size at a specified location with the possibility to assign a parent window.

Prototype

```
KNOB_Handle KNOB_CreateEx(int     x0,
                          int     y0,
                          int     xSize,
                          int     ySize,
                          WM_HWIN hParent,
                          int     WinFlags,
                          int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the KNOB widget (in parent coordinates).
y0	Topmost pixel of the KNOB widget (in parent coordinates).
xSize	Horizontal size of the KNOB widget (in pixels).
ySize	Vertical size of the KNOB widget (in pixels).
hParent	Parent window of the KNOB widget.
Id	ID of the KNOB widget.
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).

Return value

Handle of the created KNOB widget.

Additional information

The created widget is not visible by default. In order to have the widget being drawn a Memory Device needs to be set first. Using the function KNOB_SetDevice() a Memory Device containing the actual knob can be set.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.3 KNOB_CreateIndirect()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateIndirect()* on page 974. The elements `Flags` and `Para` of the resource passed as parameter are not used.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.4 KNOB_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `KNOB_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.5 KNOB_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.6 KNOB_GetValue()

Description

Returns the value of the current position around its rotary axis.

Prototype

```
I32 KNOB_GetValue(KNOB_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.

Return value

Value of the current position of the KNOB around its rotary axis in 1/10 of a degree.

Additional information

The value describes the angle in relation to the starting point. The starting point is defined by the offset which is set using the function `KNOB_SetOffset()`. Depending on the configured range (`KNOB_SetRange()`) the returned value might be more than 3600.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.7 KNOB_SetBkColor()

Without background color	With background color
	

Description

Sets a color for the background of the KNOB widget.

Prototype

```
void KNOB_SetBkColor(KNOB_Handle hObj,
                     GUI_COLOR   BkColor);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
Color	Color to be set as background color.

Additional information

Default color is transparent. It is not possible to set semi-transparent colors, only opaque colors are allowed.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.8 KNOB_SetBkDevice()

Without background device	With background device
	

Description

Sets a memory device to be shown as background.

Prototype

```
void KNOB_SetBkDevice(KNOB_Handle       hObj,
                      GUI_MEMDEV_Handle hMemBk);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
hMemBk	Handle of a memory device which should be used as background.

Additional information

The widget will not delete the background device if the widget gets deleted. So make sure to delete the background device by yourself.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.9 KNOB_SetDevice()

Description

Sets a memory device which contains a drawn knob. This drawing defines the appearance of the knob.

Prototype

```
void KNOB_SetDevice(KNOB_Handle       hObj,
                    GUI_MEMDEV_Handle hMemSrc);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
hMemSrc	Handle of a memory device which is used for the appearance of the KNOB.

Additional information

The memory device must have a color depth of 32bpp. Without setting a memory device the KNOB will be invisible.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.10 KNOB_SetInvert()

Description

Inverts the output and input value for the KNOB widget.

Prototype

```
void KNOB_SetInvert(KNOB_Handle hObj,
                    U8          Invert);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
Invert	Enables or disables invert. Can be 1 or 0.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.11 KNOB_SetKeyValue()

Description

Sets a value which defines the movement range of the KNOB on one key press.

Prototype

```
void KNOB_SetKeyValue(KNOB_Handle hObj,
                      I32         KeyValue);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
KeyValue	Value is used for the movement range on one key press. Unit is 1/10 of a degree.

Additional information

If a tick size larger than 1 is set the KNOB widget uses the tick size as KeyValue. This function is used only if no tick size is set.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.12 KNOB_SetOffset()

Description

Sets an offset angle for the KNOB widget. The knob will appear rotated from the beginning of the application.

Prototype

```
void KNOB_SetOffset(KNOB_Handle hObj,
                    I32         Offset);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
Offset	Offset position of the knob around its rotary axis in 1/10 of a degree.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.13 KNOB_SetPeriod()

Description

Sets a time period which defines how long the KNOB will need to stop.

Prototype

```
void KNOB_SetPeriod(KNOB_Handle hObj,
                    I32         Period);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
Period	Time it takes to stop the KNOB in ms.

Additional information

The period can not be larger than 46340ms. Default is 1500ms.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.14 KNOB_SetPos()

Description

Sets a new position for the KNOB widget around its rotary axis.

Prototype

```
void KNOB_SetPos(KNOB_Handle hObj,
                 I32         Pos);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
Pos	New position around the rotary axis in ticks.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.15 KNOB_SetRange()

Description

Sets a range within the KNOB can be rotated.

Prototype

```
void KNOB_SetRange(KNOB_Handle hObj,
                   I32         MinRange,
                   I32         MaxRange);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
MinRange	The minimum of the movement range in ticks. This value defines the distance from the starting point to the minimum value which can be reached by rotating the KNOB widget clockwise. MinRange defines the range to move clockwise. MaxRange defines the range to move counterclockwise.
MaxRange	The maximum of the movement range in ticks. This value defines the distance from the starting point to the maximum value which can be reached by rotating the KNOB widget counterclockwise.

Additional information

The difference between MinRange and MaxRange defines the movement area. If the TickSize is set to 10 and MinRange is set to 0 and MaxRange to 720 the KNOB is able to rotate twice around its rotary axis. If MinRange and MaxRange are equal the KNOB will be able to rotate freely. Since 0 is the starting point, it is recommended to include 0 in the range.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.16 KNOB_SetRotateHQ()

20.15.6.17 KNOB_SetRotateLQ()

Description

These functions are used to choose high and low quality rotating. The LQ variant has a better performance than HQ, but the HQ variant looks better.

Prototypes

```
void KNOB_SetRotateHQ(KNOB_Handle hObj);

void KNOB_SetRotateLQ(KNOB_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.18 KNOB_SetSnap()

Description

Sets a range between snap positions where the KNOB automatically stops. After the KNOB starts rotating it calculates the closest snap position to its stopping point and stops at this snap position. If the KNOB is released between to snap positions it rotates to the closest.

Prototype

```
void KNOB_SetSnap(KNOB_Handle hObj,
                  I32         Snap);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
Snap	Sets the range between snap positions in ticks.

Additional information

If TickSize is set to 1 (default) and Snap is 300 every 30 degrees will be a snap position.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.19 KNOB_SetTickSize()

Description

Sets the tick size of the KNOB. The tick size defines the minimum movement of the knob in 1/10 of degrees.

Prototype

```
void KNOB_SetTickSize(KNOB_Handle hObj,
                      I32         TickSize);
```

Parameters

Parameter	Description
hObj	Handle of KNOB widget.
TickSize	Sets the Ticksize of the KNOB widget.

Additional information

The default TickSize is 1, it takes 3600 Ticks to fulfill one round. For example if TickSize is set to 10 the minimum movement is 1 degree and it takes 360 Ticks to fulfill one round. This function should be called before any other KNOB function.

 © 2020 SEGGER Microcontroller GmbH

20.15.6.20 KNOB_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.16 LISTBOX: List box widget

LISTBOX widgets are used to select one element of a list. A list box can be created without a surrounding frame window, as shown below, or as a child window of a FRAMEWIN widget (see the additional screenshots at the end of the section). As items in a list box are selected, they appear highlighted. Note that the background color of a selected item depends on whether the list box window has input focus.

List box with focus	List box without focus
	

Note

All LISTBOX-related routines are in the file(s) `LISTBOX*.c`, `LISTBOX.h`.
All identifiers are prefixed LISTBOX.

20.16.1 Configuration options

Type	Macro	Default	Description
N	LISTBOX_BKCOLOR0_DEFAULT	GUI_WHITE	Background color, unselected state.
N	LISTBOX_BKCOLOR1_DEFAULT	GUI_GRAY	Background color, selected state without focus.
N	LISTBOX_BKCOLOR2_DEFAULT	GUI_BLUE	Background color, selected state with focus.
S	LISTBOX_FONT_DEFAULT	&GUI_Font13_1	Font used.
N	LISTBOX_TEXTCOLOR0_DEFAULT	GUI_BLACK	Text color, unselected state.
N	LISTBOX_TEXTCOLOR1_DEFAULT	GUI_WHITE	Text color, selected state without focus.
N	LISTBOX_TEXTCOLOR2_DEFAULT	GUI_WHITE	Text color, selected state with focus.

20.16.2 Predefined IDs

The following symbols define IDs which may be used to make LISTBOX widgets distinguishable from creation.

```
#define GUI_ID_LISTBOX0    0x110
#define GUI_ID_LISTBOX1    0x111
#define GUI_ID_LISTBOX2    0x112
#define GUI_ID_LISTBOX3    0x113
#define GUI_ID_LISTBOX4    0x114
#define GUI_ID_LISTBOX5    0x115
#define GUI_ID_LISTBOX6    0x116
#define GUI_ID_LISTBOX7    0x117
#define GUI_ID_LISTBOX8    0x118
#define GUI_ID_LISTBOX9    0x119
```

20.16.3 Notification codes

The following events are sent from a LISTBOX widget to its parent window as part of a `WM_NOTIFY_PARENT` message:

Message	Description
WM_NOTIFICATION_CLICKED	LISTBOX has been clicked.

 © 2020 SEGGER Microcontroller GmbH

Message	Description
WM_NOTIFICATION_RELEASED	LISTBOX has been released.
WM_NOTIFICATION_MOVED_OUT	LISTBOX has been clicked and pointer has been moved out of the box without releasing.
WM_NOTIFICATION_SCROLL_CHANGED	The scroll position of the optional scroll bar has been changed.
WM_NOTIFICATION_SEL_CHANGED	The selection of the LISTBOX widget has changed.

20.16.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_SPACE	If the widget works in multi selection mode this key toggles the state of the current selected item.
GUI_KEY_RIGHT	If the maximum X-size of the list box items is larger than the list box itself this key scrolls the list box content to the left.
GUI_KEY_LEFT	If the maximum X-size of the list box items is larger than the list box itself this key scrolls the list box content to the right.
GUI_KEY_DOWN	Moves the selection bar down.
GUI_KEY_UP	Moves the selection bar up.

20.16.5 LISTBOX API

The table below lists the available emWin LISTBOX-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
LISTBOX_AddString()	Adds an item to a LISTBOX widget.
LISTBOX_Create()	Creates a LISTBOX widget. (Obsolete)
LISTBOX_CreateAsChild()	Creates a LISTBOX widget as a child window. (Obsolete)
LISTBOX_CreateEx()	Creates a LISTBOX widget.
LISTBOX_CreateIndirect()	Creates a LISTBOX widget from resource table entry.
LISTBOX_CreateUser()	Creates a LISTBOX widget using extra bytes as user data.
LISTBOX_DecSel()	Decrements selection.
LISTBOX_DeleteItem()	Deletes an element.
LISTBOX_EnableMotion()	Enables motion support for the given LISTBOX widget.
LISTBOX_EnableWrapMode()	Enables scrolling from the end to the beginning and vice versa.
LISTBOX_GetBkColor()	Returns the background color of the widget.
LISTBOX_GetDefaultBkColor()	Returns the default background color for new LISTBOX widgets.
LISTBOX_GetDefaultFont()	Returns the default font used for creating LISTBOX widgets.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
LISTBOX_GetDefaultScrollStepH()	Returns the default horizontal scroll step used for creating LISTBOX widgets.
LISTBOX_GetDefaultTextAlign()	Returns the default text alignment for new LISTBOX widgets.
LISTBOX_GetDefaultTextColor()	Returns the default text color for new LISTBOX widgets.
LISTBOX_GetFont()	Returns a pointer to the font used to display the text of the LISTBOX widget.
LISTBOX_GetItemDisabled()	Returns if the given item of the LISTBOX widget has been disabled.
LISTBOX_GetItemSel()	Returns the selection state of the given LISTBOX item.
LISTBOX_GetItemSpacing()	This function returns the distance between the different items of a LISTBOX.
LISTBOX_GetItemText()	Returns the text of the given item of the LISTBOX widget.
LISTBOX_GetMulti()	Returns if the multi selection mode of the given LISTBOX widget is active.
LISTBOX_GetNumItems()	Returns the number of items in a specified LISTBOX widget.
LISTBOX_GetOwner()	Returns the 'owner' of the widget.
LISTBOX_GetScrollStepH()	Returns the horizontal scroll step of the given LISTBOX widget.
LISTBOX_GetSel()	Returns the zero based index of the currently selected item in a specified LISTBOX widget.
LISTBOX_GetTextAlign()	Returns the text alignment of the given LISTBOX widget.
LISTBOX_GetTextColor()	Returns the text color of the widget.
LISTBOX_GetUserData()	Retrieves the data set with LISTBOX_SetUserData().
LISTBOX_IncSel()	Increment the selection of the LISTBOX widget (moves the selection bar of a specified LISTBOX widget down by one item).
LISTBOX_InsertString()	Inserts an element into a LISTBOX widget.
LISTBOX_InvalidateItem()	Invalidates an item of a owner drawn LISTBOX widget.
LISTBOX_OwnerDraw()	Default function to handle a LISTBOX entry.
LISTBOX_SetAutoScrollH()	Enables/disables the automatic use of a horizontal scroll bar.
LISTBOX_SetAutoScrollV()	Enables/disables the automatic use of a vertical scroll bar.
LISTBOX_SetBkColor()	Sets the background color of the LISTBOX widget.
LISTBOX_SetDefaultBkColor()	Sets the default background color for new LISTBOX widgets.
LISTBOX_SetDefaultFont()	Sets the default font used for creating LISTBOX widgets.
LISTBOX_SetDefaultScrollStepH()	Sets the default horizontal scroll step used when creating a LISTBOX widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
LISTBOX_SetDefaultTextAlign()	Sets the default text alignment for new LISTBOX widgets.
LISTBOX_SetDefaultTextColor()	Sets the default text color for new LISTBOX widgets.
LISTBOX_SetFixedScrollPos()	Enables the fixed scroll mode for the given LISTBOX widget.
LISTBOX_SetFont()	Sets the font of the LISTBOX widget.
LISTBOX_SetItemDisabled()	Modifies the disable state of the given list item of the LISTBOX widget.
LISTBOX_SetItemSel()	Modifies the selection state of the given item of the LISTBOX widget.
LISTBOX_SetItemSpacing()	Sets an additional spacing below the items of a LISTBOX widget.
LISTBOX_SetMulti()	Switches the multi selection mode of a LISTBOX on or off.
LISTBOX_SetOwnerDraw()	Sets the LISTBOX widget to be owner drawn.
LISTBOX_SetScrollbarColor()	Sets the colors of the optional scroll bar.
LISTBOX_SetScrollbarWidth()	Sets the width of the scroll bars used by the given LISTBOX widget.
LISTBOX_SetScrollStepH()	Sets the horizontal scroll step of the given LISTBOX widget.
LISTBOX_SetSel()	Sets the selected item of a specified LISTBOX widget.
LISTBOX_SetString()	Sets the content of the given item.
LISTBOX_SetTextAlign()	The function sets the text alignment used to display each item of the LISTBOX widget.
LISTBOX_SetTextColor()	Sets the text color of the LISTBOX widget.
LISTBOX_SetUserData()	Sets the extra data of a LISTBOX widget.

Defines

Group of defines	Description
LISTBOX color indexes	Color indexes used by the LISTBOX widget.
LISTBOX fixed scroll mode flags	Defines used for the fixed scroll mode of the widget.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1 Functions

20.16.5.1.1 LISTBOX_AddString()

Description

Adds an item to an already existing LISTBOX widget.

Prototype

```
void LISTBOX_AddString(      LISTBOX_Handle   hObj,
                       const char           * s);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
s	Text to display.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.2 LISTBOX_Create()

> **Note**
>
> This function is **deprecated**, `LISTBOX_CreateEx()` should be used instead.

Description

Creates a LISTBOX widget of a specified size at a specified location.

Prototype

```
LISTBOX_Handle LISTBOX_Create(const GUI_ConstString * ppText,
                                    int               x0,
                                    int               y0,
                                    int               xSize,
                                    int               ySize,
                                    int               Flags);
```

Parameters

Parameter	Description
`ppText`	Pointer to an array of string pointers containing the elements to be displayed.
`x0`	Leftmost pixel of the LISTBOX widget (in parent coordinates).
`y0`	Topmost pixel of the LISTBOX widget (in parent coordinates).
`xSize`	Horizontal size of the LISTBOX widget (in pixels).
`ySize`	Vertical size of the LISTBOX widget (in pixels).
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).

Return value

Handle of the created LISTBOX widget; 0 if the function fails.

Additional information

If the parameter `ySize` is greater than the required space for drawing the content of the widget, the y-size will be reduced to the required value. The same applies to the `xSize` parameter.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.3 LISTBOX_CreateAsChild()

> **Note**
>
> This function is **deprecated**, `LISTBOX_CreateEx()` should be used instead.

Description

Creates a LISTBOX widget as a child window.

Prototype

```
LISTBOX_Handle LISTBOX_CreateAsChild(const GUI_ConstString * ppText,
                                     WM_HWIN           hWinParent,
                                     int               x0,
                                     int               y0,
                                     int               xSize,
                                     int               ySize,
                                     int               Flags);
```

Parameters

Parameter	Description
`ppText`	Pointer to an array of string pointers containing the elements to be displayed.
`hParent`	Handle of parent window.
`x0`	X-position of the LISTBOX widget relative to the parent window.
`y0`	Y-position of the LISTBOX widget relative to the parent window.
`xSize`	Horizontal size of the LISTBOX widget (in pixels).
`ySize`	Vertical size of the LISTBOX widget (in pixels).
`Flags`	Window create flags (see *Window create flags* on page 958).

Return value

Handle of the created LISTBOX widget; 0 if the function fails.

Additional information

If the parameter `ySize` is greater than the space required for drawing the content of the widget, the Y-size will be reduced to the required value. If `ySize` = 0 the Y-size of the widget will be set to the Y-size of the client area from the parent window. The same applies for the `Xsize` parameter.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.4 LISTBOX_CreateEx()

Description

Creates a LISTBOX widget of a specified size at a specified location.

Prototype

```
LISTBOX_Handle LISTBOX_CreateEx(      int               x0,
                                      int               y0,
                                      int               xSize,
                                      int               ySize,
                                      WM_HWIN           hParent,
                                      int               WinFlags,
                                      int               ExFlags,
                                      int               Id,
                                const GUI_ConstString * ppText);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new HEADER widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used, reserved for future use.
Id	Window ID of the widget.
ppText	Pointer to an array of string pointers containing the elements to be displayed. The last entry of this array has to be NULL.

Return value

Handle of the created LISTBOX widget; 0 if the function fails.

Additional information

If an array of string pointers is set as last parameter, please make sure that the last entry in this array is NULL.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.5 LISTBOX_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element Para of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element Flags is used according to the parameter ExFlags of the function `LISTBOX_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.6 LISTBOX_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `LISTBOX_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.7 LISTBOX_DecSel()

Description

Decrement the selection of the LISTBOX widget (moves the selection bar of a specified LISTBOX widget up by one item).

Prototype

```
void LISTBOX_DecSel(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.

Additional information

Note that the numbering of items always starts from the top with a value of 0; therefore, decrementing the selection will actually move the selection one row up.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.8 LISTBOX_DeleteItem()

Description

Deletes an element from a LISTBOX widget.

Prototype

```
void LISTBOX_DeleteItem(LISTBOX_Handle hObj,
                        unsigned       Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	Zero-based index of element to be deleted.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.9 LISTBOX_EnableMotion()

Description

Enables motion support for the given LISTBOX widget.

Prototype

```
void LISTBOX_EnableMotion(LISTBOX_Handle hObj,
                          int            OnOff);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
OnOff	1 for enabling motion support, 0 for disabling motion support.

Additional information

If motion support isn't enabled for the window manager, it will be activated automatically.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.10 LISTBOX_EnableWrapMode()

Description

Enables scrolling from the end to the beginning and vice versa. That avoids scrolling from the end through the whole content of the list. If for example the last set of items of the LISTBOX are currently visible and the user attempts scrolling to the next element the beginning of the list will be shown.

Prototype

```
void LISTBOX_EnableWrapMode(LISTBOX_Handle hObj,
                            int            OnOff);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
OnOff	1 for enabling wrap mode, 0 (default) for disabling.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.11 LISTBOX_GetBkColor()

Description

Returns the background color of the widget.

Prototype

```
GUI_COLOR LISTBOX_GetBkColor(LISTBOX_Handle hObj,
                             unsigned       Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	See *LISTBOX color indexes* on page 1536 for a full list of permitted values.

Return value

The background color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.12 LISTBOX_GetDefaultBkColor()

Description

Returns the default background color for new LISTBOX widgets.

Prototype

```
GUI_COLOR LISTBOX_GetDefaultBkColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *LISTBOX color indexes* on page 1536 for a full list of permitted values.

Return value

Default background color for new LISTBOX widgets.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.13 LISTBOX_GetDefaultFont()

Description

Returns the default font used for creating LISTBOX widgets.

Prototype

```
GUI_FONT *LISTBOX_GetDefaultFont(void);
```

Return value

Pointer to the default font.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.14 LISTBOX_GetDefaultScrollStepH()

Description

Returns the default horizontal scroll step used for creating LISTBOX widgets. The horizontal scroll step defines the number of pixels to be scrolled if needed.

Prototype

```
int LISTBOX_GetDefaultScrollStepH(void);
```

Return value

Default horizontal scroll step.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.15 LISTBOX_GetDefaultTextAlign()

Description

Returns the default text alignment for new LISTBOX widgets.

Prototype

```
int LISTBOX_GetDefaultTextAlign(void);
```

Return value

Default text alignment for new LISTBOX widgets.

Additional information

For more information, refer to `LISTBOX_SetTextAlign()`.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.16 LISTBOX_GetDefaultTextColor()

Description

Returns the default text color for new LISTBOX widgets.

Prototype

```
GUI_COLOR LISTBOX_GetDefaultTextColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *LISTBOX color indexes* on page 1536 for a full list of permitted values.

Return value

Default text color for new LISTBOX widgets.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.17 LISTBOX_GetFont()

Description

Returns a pointer to the font used to display the text of the LISTBOX widget.

Prototype

```
GUI_FONT *LISTBOX_GetFont(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.

Return value

Pointer to the font used to display the text of the LISTBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.18 LISTBOX_GetItemDisabled()

Description

Returns if the given item of the LISTBOX widget has been disabled.

Prototype

```
int LISTBOX_GetItemDisabled(LISTBOX_Handle hObj,
                            unsigned       Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	Zero based index of item.

Return value

1 if item has been disabled
0 if not.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.19 LISTBOX_GetItemSel()

Description

Returns the selection state of the given LISTBOX item. The selection state of a LISTBOX item can be modified in multi selection mode only.

Prototype

```
int LISTBOX_GetItemSel(LISTBOX_Handle hObj,
                       unsigned       Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	Zero based index of item.

Return value

1 if item has been selected
0 if not.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.20 LISTBOX_GetItemSpacing()

Description

This function returns the distance between the different items of a LISTBOX.

Prototype

```
unsigned LISTBOX_GetItemSpacing(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.

Return value

The distance between the items in pixel.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.21 LISTBOX_GetItemText()

Description

Returns the text of the given item of the LISTBOX widget.

Prototype

```
void LISTBOX_GetItemText(LISTBOX_Handle   hObj,
                         unsigned         Index,
                         char           * pBuffer,
                         int              MaxSize);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	Zero based item index.
pBuffer	Pointer to buffer to store the item text.
MaxSize	Size of the buffer.

Additional information

The function copies the text of the given LISTBOX item into the given buffer.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.22 LISTBOX_GetMulti()

Description

Returns if the multi selection mode of the given LISTBOX widget is active.

Prototype

```
int LISTBOX_GetMulti(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.

Additional information

1 if active
0 if not.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.23 LISTBOX_GetNumItems()

Description

Returns the number of items in a specified LISTBOX widget.

Prototype

```
unsigned LISTBOX_GetNumItems(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.

Return value

Number of items in the LISTBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.24 LISTBOX_GetOwner()

Description

Returns the ’owner’ of the widget. If it does not have an ’owner’ it returns its parent.

Prototype

```
WM_HWIN LISTBOX_GetOwner(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.

Return value

Owner or parent of the widget.

Additional information

A LISTBOX is used to represent the list of a DROPDOWN widget in expanded state. In that case the ’owner’ is the DROPDOWN widget.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.25 LISTBOX_GetScrollStepH()

Description

Returns the horizontal scroll step of the given LISTBOX widget.

Prototype

```
int LISTBOX_GetScrollStepH(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.

Return value

Horizontal scroll step of the given LISTBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.26 LISTBOX_GetSel()

Description

Returns the zero based index of the currently selected item in a specified LISTBOX widget. In multi selection mode the function returns the index of the focused element.

Prototype

```
int LISTBOX_GetSel(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.

Return value

Zero-based index of the currently selected item.

Additional information

If no element has been selected the function returns -1.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.27 LISTBOX_GetTextAlign()

Description

Returns the text alignment of the given LISTBOX widget.

Prototype

```
int LISTBOX_GetTextAlign(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.

Return value

Text alignment of the given LISTBOX widget.

Additional information

For more information, refer to `LISTBOX_SetTextAlign()`.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.28 LISTBOX_GetTextColor()

Description

Returns the text color of the widget.

Prototype

```
GUI_COLOR LISTBOX_GetTextColor(LISTBOX_Handle hObj,
                               unsigned       Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	See *LISTBOX color indexes* on page 1536 for a full list of permitted values.

Return value

The text color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.29 LISTBOX_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.30 LISTBOX_IncSel()

Description

Increment the selection of the LISTBOX widget (moves the selection bar of a specified LISTBOX widget down by one item).

Prototype

```
void LISTBOX_IncSel(LISTBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	See table below.

Additional information

Note that the numbering of items always starts from the top with a value of 0; therefore incrementing the selection will actually move the selection one row down.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.31 LISTBOX_InsertString()

Description

Inserts an element into a LISTBOX widget.

Prototype

```
void LISTBOX_InsertString(      LISTBOX_Handle   hObj,
                          const char           * s,
                                unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
s	Pointer to string to be inserted.
Index	Zero based index of element to be inserted.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.32 LISTBOX_InvalidateItem()

Description

Invalidates an item of a owner drawn LISTBOX widget.

Prototype

```
void LISTBOX_InvalidateItem(LISTBOX_Handle hObj,
                            int            Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	Zero based index of element to be invalidated or LISTBOX_ALL_ITEMS if all items should be invalidated.

Additional information

This function only needs to be called if an item of an owner drawn LISTBOX widget has been changed. If a LISTBOX API function (like LISTBOX_SetString()) has been used to modify a LISTBOX item LISTBOX_InvalidateItem() does not need to be called. It needs to be called if the user decides, that for example the vertical size of an item has been changed. With other words if no LISTBOX API function has been used to modify the item this function needs to be called.

LISTBOX_ALL_ITEMS

If all items of a LISTBOX should be invalidated use this define as Index parameter.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.33 LISTBOX_OwnerDraw()

Description

Default function to handle a LISTBOX entry.

Prototype

```
int LISTBOX_OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo);
```

Parameters

Parameter	Description
pDrawItemInfo	Pointer to a WIDGET_ITEM_DRAW_INFO structure.

Additional information

This function is useful if LISTBOX_SetOwnerDraw() has been used. It can be used from your drawing function to retrieve the original x size of a LISTBOX entry and/or to display the text of a LISTBOX entry and should be called for all unhandled commands. For more information, refer to the section explaining user drawn widgets, LISTBOX_SetOwnerDraw() and to the provided example.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.34 LISTBOX_SetAutoScrollH()

Description

Enables/disables the automatic use of a horizontal scroll bar.

Prototype

```
void LISTBOX_SetAutoScrollH(LISTBOX_Handle hObj,
                            int            State);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
OnOff	See table below.

Permitted values for parameter OnOff	
0	Disable automatic use of a horizontal scroll bar.
1	Enable automatic use of a horizontal scroll bar.

Additional information

If enabled the LISTBOX widget checks if all elements fits into the LISTBOX widget. If not a horizontal scroll bar will be attached to the window.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.35 LISTBOX_SetAutoScrollV()

Description

Enables/disables the automatic use of a vertical scroll bar.

Prototype

```
void LISTBOX_SetAutoScrollV(LISTBOX_Handle hObj,
                            int            State);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
OnOff	See table below.

Permitted values for parameter OnOff	
0	Disable automatic use of a vertical scroll bar.
1	Enable automatic use of a vertical scroll bar.

Additional information

If enabled the LISTBOX widget checks if all elements fits into the LISTBOX widget. If not a vertical scroll bar will be added.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.36 LISTBOX_SetBkColor()

Description

Sets the background color of the LISTBOX widget.

Prototype

```
void LISTBOX_SetBkColor(LISTBOX_Handle hObj,
                        unsigned       Index,
                        GUI_COLOR      color);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	See *LISTBOX color indexes* on page 1536 for a full list of permitted values.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.37 LISTBOX_SetDefaultBkColor()

Description

Sets the default background color for new LISTBOX widgets.

Prototype

```
void LISTBOX_SetDefaultBkColor(unsigned  Index,
                               GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *LISTBOX color indexes* on page 1536 for a full list of permitted values.
Color	Desired background color.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.38 LISTBOX_SetDefaultFont()

Description

Sets the default font used for creating LISTBOX widgets.

Prototype

```
void LISTBOX_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to the font.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.39 LISTBOX_SetDefaultScrollStepH()

Description

Sets the default horizontal scroll step used when creating a LISTBOX widget.

Prototype

```
void LISTBOX_SetDefaultScrollStepH(int Value);
```

Parameters

Parameter	Description
Value	Number of pixels to be scrolled.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.40 LISTBOX_SetDefaultTextAlign()

Description

Sets the default text alignment for new LISTBOX widgets.

Prototype

```
void LISTBOX_SetDefaultTextAlign(int Align);
```

Parameters

Parameter	Description
Align	Default text alignment for new LISTBOX widgets.

Additional information

For more information, refer to `LISTBOX_SetTextAlign()`.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.41 LISTBOX_SetDefaultTextColor()

Description

Sets the default text color for new LISTBOX widgets.

Prototype

```
void LISTBOX_SetDefaultTextColor(unsigned  Index,
                                 GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *LISTBOX color indexes* on page 1536 for a full list of permitted values.
Color	Desired text color.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.42 LISTBOX_SetFixedScrollPos()

Description

Enables the fixed scroll mode for the given LISTBOX widget.

Prototype

```
void LISTBOX_SetFixedScrollPos(LISTBOX_Handle hObj,
                               U16            FixedScrollPos,
                               U8             Mode);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
FixedScrollPos	Index of the item the scroll position is fixed to.
Mode	Sets the desired mode. See *LISTBOX fixed scroll mode flags* on page 1537.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.43 LISTBOX_SetFont()

Description

Sets the font of the LISTBOX widget.

Prototype

```
void LISTBOX_SetFont(      LISTBOX_Handle   hObj,
                     const GUI_FONT       * pFont);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
pFont	Pointer to the font.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.44 LISTBOX_SetItemDisabled()

Description

Modifies the disable state of the given list item of the LISTBOX widget.

Prototype

```
void LISTBOX_SetItemDisabled(LISTBOX_Handle hObj,
                             unsigned       Index,
                             int            OnOff);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	Zero based index of the LISTBOX item.
OnOff	1 for disabled, 0 for not disabled.

Additional information

When scrolling through a LISTBOX widget disabled items will be skipped. You can not scroll to a disabled item of a LISTBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.45 LISTBOX_SetItemSel()

Description

Modifies the selection state of the given item of the LISTBOX widget.

Prototype

```
void LISTBOX_SetItemSel(LISTBOX_Handle hObj,
                        unsigned       Index,
                        int            OnOff);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	Zero based index of the LISTBOX item.
OnOff	1 for selected, 0 for not selected.

Additional information

Setting the selection state of a LISTBOX item makes only sense when using the multi selection mode. See also LISTBOX_SetMulti().

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.46 LISTBOX_SetItemSpacing()

Before	After
	

Description

Sets an additional spacing below the items of a LISTBOX widget.

Prototype

```
void LISTBOX_SetItemSpacing(LISTBOX_Handle hObj,
                            unsigned       Value);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Value	Number of pixels used as additional spacing between the items.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.47 LISTBOX_SetMulti()

Description

Switches the multi selection mode of a LISTBOX on or off.

Prototype

```
void LISTBOX_SetMulti(LISTBOX_Handle hObj,
                      int            Mode);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Mode	0 for off, 1 for on.

Additional information

The multi selection mode enables the LISTBOX widget to have more than one selected element. Using the space key would toggle the selection state of a LISTBOX item.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.48 LISTBOX_SetOwnerDraw()

Description

Sets the LISTBOX widget to be owner drawn.

Prototype

```
void LISTBOX_SetOwnerDraw(LISTBOX_Handle          hObj,
                          WIDGET_DRAW_ITEM_FUNC * pfDrawItem);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
pfDrawItem	Pointer to owner draw function.

Supported commands

- WIDGET_ITEM_GET_XSIZE
- WIDGET_ITEM_GET_YSIZE
- WIDGET_ITEM_DRAW

Additional information

This function sets a function pointer to a function which will be called by the widget if a LISTBOX item has to be drawn and when the x or y size of a item is needed. It gives you the possibility to draw anything as LISTBOX item, not just plain text. pfDrawItem is a pointer to a application-defined function of type WIDGET_DRAW_ITEM_FUNC which is explained at the beginning of the chapter.

Structure of the user defined owner draw function

The following shows the structure of a typical owner draw function. It assumes that your LISTBOX entries are 30 pixels wider than and have the same height as the item drawn by the default function:

```
static int _OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo) {
  switch (pDrawItemInfo->Cmd) {
  case WIDGET_ITEM_GET_XSIZE:
    return LISTBOX_OwnerDraw(pDrawItemInfo) + 30; /* Returns the default xSize+10
 */
  case WIDGET_ITEM_DRAW:

    /* Your code to be added to draw the LISTBOX item */

    return 0;
  }
  return LISTBOX_OwnerDraw(pDrawItemInfo);   /* Def. function for unhandled cmds
 */
}
```

 © 2020 SEGGER Microcontroller GmbH

Example



The source code of this example is available in the examples as `WIDGET_ListBoxOwnerDraw.c`.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.49 LISTBOX_SetScrollbarColor()

Before	After
	

Description

Sets the colors of the optional scroll bar.

Prototype

```
void LISTBOX_SetScrollbarColor(LISTBOX_Handle hObj,
                               unsigned       Index,
                               GUI_COLOR      Color);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	Index of desired item. See *SCROLLBAR color indexes* on page 1939 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.50 LISTBOX_SetScrollbarWidth()

Description

Sets the width of the scroll bars used by the given LISTBOX widget.

Prototype

```
void LISTBOX_SetScrollbarWidth(LISTBOX_Handle hObj,
                               unsigned       Width);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Width	Width of the scroll bar(s) used by the given LISTBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.51 LISTBOX_SetScrollStepH()

Description

Sets the horizontal scroll step of the given LISTBOX widget. The horizontal scroll step defines the number of pixels to be scrolled if needed.

Prototype

```
void LISTBOX_SetScrollStepH(LISTBOX_Handle hObj,
                            int            Value);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Value	Number of pixels to be scrolled.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.52 LISTBOX_SetSel()

Description

Sets the selected item of a specified LISTBOX widget.

Prototype

```
void LISTBOX_SetSel(LISTBOX_Handle hObj,
                    int            NewSel);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Sel	Element to be selected.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.53 LISTBOX_SetString()

Description

Sets the content of the given item.

Prototype

```
void LISTBOX_SetString(      LISTBOX_Handle   hObj,
                       const char           * s,
                             unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
s	Pointer to string containing the new content.
Index	Zero-based index of element to be changed.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.54 LISTBOX_SetTextAlign()

Before	After
	

Description

The function sets the text alignment used to display each item of the LISTBOX widget.

Prototype

```
void LISTBOX_SetTextAlign(LISTBOX_Handle hObj,
                          int            Align);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Align	Text alignment to be used. List of flags can be found under *Text alignment flags* on page 218.

Additional information

The default alignment of list boxes is GUI_TA_LEFT. Per default the height of each item depends on the height of the font used to render the LISTBOX items. So vertical text alignment makes only sense if the function LISTBOX_SetItemSpacing() is used to set an additional spacing below the items.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.55 LISTBOX_SetTextColor()

Description

Sets the text color of the LISTBOX widget.

Prototype

```
GUI_COLOR LISTBOX_SetTextColor(LISTBOX_Handle hObj,
                               unsigned       Index,
                               GUI_COLOR      Color);
```

Parameters

Parameter	Description
hObj	Handle of LISTBOX widget.
Index	Index for text color (see *LISTBOX_SetBackColor* on page).
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.1.56 LISTBOX_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.2 Defines

20.16.5.2.1 LISTBOX color indexes

Description

Color indexes used by the LISTBOX widget.

Definition

```
#define LISTBOX_CI_UNSEL       0
#define LISTBOX_CI_SEL         1
#define LISTBOX_CI_SELFOCUS    2
#define LISTBOX_CI_DISABLED    3
```

Symbols

Definition	Description
LISTBOX_CI_UNSEL	Color of unselected element.
LISTBOX_CI_SEL	Color of selected element.
LISTBOX_CI_SELFOCUS	Color of selected element with focus.
LISTBOX_CI_DISABLED	Color of disabled element.

 © 2020 SEGGER Microcontroller GmbH

20.16.5.2.2 LISTBOX fixed scroll mode flags

Description

Defines used for the fixed scroll mode of the widget. Refer to `LISTBOX_SetFixedScroll-Pos()` for more information.

Definition

```
#define LISTBOX_FM_OFF       0
#define LISTBOX_FM_ON        1
#define LISTBOX_FM_CENTER    2
```

Symbols

Definition	Description
LISTBOX_FM_OFF	Disables the fixed scroll mode.
LISTBOX_FM_ON	Enables the fixed scroll mode.
LISTBOX_FM_CENTER	Tries to keep the selected item in the center.

 © 2020 SEGGER Microcontroller GmbH

20.16.6 Examples

The Sample folder contains the following examples which show how the widget can be used:

- WIDGET_SimpleListBox.c
- WIDGET_ListBox.c

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_SimpleListBox.c



Screenshot(s) of WIDGET_ListBox.c





 © 2020 SEGGER Microcontroller GmbH

20.17 LISTVIEW: Listview widget

LISTVIEW widgets are used to select one element of a list with several columns. To manage the columns a LISTVIEW widget contains a HEADER widget. A LISTVIEW can be created without a surrounding frame window or as a child window of a FRAMEWIN widget. As items in a listview are selected, they appear highlighted. Note that the background color of a selected item depends on whether the LISTVIEW window has input focus. The table below shows the appearance of the LISTVIEW widget:

Description	LISTVIEW widget
No focus No surrounding FRAMEWIN No SCROLLBAR attached Grid lines not visible	
Has input focus No surrounding FRAMEWIN No SCROLLBAR attached Grid lines not visible	
Has input focus With surrounding FRAMEWIN No SCROLLBAR attached Grid lines not visible	
Has input focus With surrounding FRAMEWIN SCROLLBAR attached Grid lines not visible	
Has input focus With surrounding FRAMEWIN SCROLLBAR attached Grid lines visible	

 © 2020 SEGGER Microcontroller GmbH

> **Note**
>
> All LISTVIEW-related routines are located in the file(s) `LISTVIEW*.c`, `LISTVIEW.h`. All identifiers are prefixed LISTVIEW.

20.17.1 Configuration options

Type	Macro	Default	Description
N	LISTVIEW_ALIGN_DEFAULT	GUI_TA_VCENTER | GUI_TA_HCENTER	Default text alignment.
N	LISTVIEW_BKCOLOR0_DEFAULT	GUI_WHITE	Background color, unselected state.
N	LISTVIEW_BKCOLOR1_DEFAULT	GUI_GRAY	Background color, selected state without focus.
N	LISTVIEW_BKCOLOR2_DEFAULT	GUI_BLUE	Background color, selected state with focus.
N	LISTVIEW_BKCOLOR3_DEFAULT	GUI_LIGHTGRAY	Background color, disabled state.
S	LISTVIEW_FONT_DEFAULT	&GUI_Font13_1	Default font.
N	LISTVIEW_GRIDCOLOR_DEFAULT	GUI_LIGHTGRAY	Color of grid lines (if shown).
N	LISTVIEW_SCROLLSTEP_H_DEFAULT	10	Defines the number of pixels to be scrolled if needed.
N	LISTVIEW_TEXTCOLOR0_DEFAULT	GUI_BLACK	Text color, unselected state.
N	LISTVIEW_TEXTCOLOR1_DEFAULT	GUI_WHITE	Text color, selected state without focus.
N	LISTVIEW_TEXTCOLOR2_DEFAULT	GUI_WHITE	Text color, selected state with focus.
N	LISTVIEW_TEXTCOLOR3_DEFAULT	GUI_GRAY	Text color, disabled state.
N	LISTVIEW_WRAPMODE_DEFAULT	GUI_WRAPMODE_NONE	Wrapping mode.

20.17.2 Predefined IDs

The following symbols define IDs which may be used to make LISTVIEW widgets distinguishable from creation.

```
#define GUI_ID_LISTVIEW0    0x200
#define GUI_ID_LISTVIEW1    0x201
#define GUI_ID_LISTVIEW2    0x202
#define GUI_ID_LISTVIEW3    0x203
#define GUI_ID_LISTVIEW4    0x204
#define GUI_ID_LISTVIEW5    0x205
#define GUI_ID_LISTVIEW6    0x206
#define GUI_ID_LISTVIEW7    0x207
#define GUI_ID_LISTVIEW8    0x208
#define GUI_ID_LISTVIEW9    0x209
```

20.17.3 Notification codes

The following events are sent from a LISTVIEW widget to its parent window as part of a `WM_NOTIFY_PARENT` message:

Message	Description
WM_NOTIFICATION_CLICKED	Widget has been clicked.
WM_NOTIFICATION_RELEASED	Widget has been released.

 © 2020 SEGGER Microcontroller GmbH

Message	Description
WM_NOTIFICATION_MOVED_OUT	Widget has been clicked and pointer has been moved out of the widget without releasing.
WM_NOTIFICATION_SCROLL_CHANGED	The scroll position of the optional scroll bar has been changed.
WM_NOTIFICATION_SEL_CHANGED	The selection of the list box has changed.

20.17.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_UP	Moves the selection bar up.
GUI_KEY_DOWN	Moves the selection bar down.
GUI_KEY_RIGHT	If the total amount of the column width is > than the inside area of the listview, the content scrolls to the left.
GUI_KEY_LEFT	If the total amount of the column width is > than the inside area of the listview, the content scrolls to the right.

20.17.5 LISTVIEW API

The table below lists the available emWin LISTVIEW-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
LISTVIEW_AddColumn()	Adds a column to a LISTVIEW.
LISTVIEW_AddRow()	Adds a row to a LISTVIEW.
LISTVIEW_CompareDec()	Compare function for comparing 2 integer values.
LISTVIEW_CompareText()	Compare function for comparing 2 strings.
LISTVIEW_Create()	Creates a LISTVIEW widget. (Obsolete)
LISTVIEW_CreateAttached()	Creates a LISTVIEW widget attached to a window.
LISTVIEW_CreateEx()	Creates a LISTVIEW widget.
LISTVIEW_CreateIndirect()	Creates a LISTVIEW widget from a resource table entry.
LISTVIEW_CreateUser()	Creates a LISTVIEW widget using extra bytes as user data.
LISTVIEW_DecSel()	Decrements selection.
LISTVIEW_DeleteAllRows()	Deletes all rows from the given LISTVIEW widget.
LISTVIEW_DeleteColumn()	Deletes the given column.
LISTVIEW_DeleteRow()	Deletes the given row.
LISTVIEW_DisableRow()	Sets the state of the given row to disabled.
LISTVIEW_DisableSort()	Disables sorting of the given LISTVIEW widget.
LISTVIEW_EnableCellSelect()	Enables or disables cell selection mode of the given LISTVIEW widget.
LISTVIEW_EnableMotion()	Enables motion support for the given LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
LISTVIEW_EnableRow()	The function sets the state of the given row to enabled.
LISTVIEW_EnableSort()	Enables sorting for the given LISTVIEW widget.
LISTVIEW_GetBkColor()	Returns the background color of the given LISTVIEW widget.
LISTVIEW_GetFont()	Returns a pointer to the font used to display the text of the LISTVIEW widget.
LISTVIEW_GetHeader()	Returns the handle of the HEADER widget.
LISTVIEW_GetItemRect()	Returns the rectangle of the given LISTVIEW cell by copying the coordinates to the given GUI_RECT structure.
LISTVIEW_GetItemText()	Copies the text of the specified item to the given buffer.
LISTVIEW_GetItemTextLen()	Returns the length in characters of the given text item.
LISTVIEW_GetItemTextSorted()	Copies the text of the specified item to the given buffer.
LISTVIEW_GetLBorder()	Returns the size of the left border within a cell of a LISTVIEW.
LISTVIEW_GetNumColumns()	Returns the number of columns of the given LISTVIEW widget.
LISTVIEW_GetNumRows()	Returns the number of rows of the given LISTVIEW widget.
LISTVIEW_GetRBorder()	Returns the size of the right border within a cell of a LISTVIEW.
LISTVIEW_GetSel()	Returns the index of the currently selected row in a specified LISTVIEW widget.
LISTVIEW_GetSelCol()	Returns the index of the currently selected column.
LISTVIEW_GetSelUnsorted()	Returns the index of the currently selected row in unsorted state.
LISTVIEW_GetTextAlign()	Returns the currently set text alignment for the given column.
LISTVIEW_GetTextColor()	Returns the text color of the given LISTVIEW widget.
LISTVIEW_GetUserData()	Retrieves the data set with LISTVIEW_SetUserData().
LISTVIEW_GetUserDataRow()	Returns the user data of the given row.
LISTVIEW_GetWrapMode()	Returns the currently used mode for wrapping text.
LISTVIEW_IncSel()	Increments selection.
LISTVIEW_InsertRow()	Inserts a new row into the LISTVIEW at the given position.
LISTVIEW_OwnerDraw()	Default function for managing drawing operations of one cell.
LISTVIEW_RowIsDisabled()	Returns if a row has been disabled.
LISTVIEW_SetAutoScrollH()	Enables/disables the automatic use of a horizontal scroll bar.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
LISTVIEW_SetAutoScrollV()	Enables/disables the automatic use of a vertical scroll bar.
LISTVIEW_SetBkColor()	Sets the background color of the given LISTVIEW widget.
LISTVIEW_SetColumnWidth()	Sets the width of the given column.
LISTVIEW_SetCompareFunc()	Sets the compare function for the given column.
LISTVIEW_SetDefaultBkColor()	Sets the default background color for new LISTVIEW widgets.
LISTVIEW_SetDefaultFont()	Sets the default font for new LISTVIEW widgets.
LISTVIEW_SetDefaultGridColor()	Sets the default color of the grid lines for new LISTVIEW widgets.
LISTVIEW_SetDefaultTextColor()	Sets the default text color for new LISTVIEW widgets.
LISTVIEW_SetFixed()	Fixes the given number of columns at their horizontal positions.
LISTVIEW_SetFont()	Sets the font of the LISTVIEW widget.
LISTVIEW_SetGridVis()	Sets the visibility flag of the grid lines.
LISTVIEW_SetHeaderHeight()	Sets the height of the attached HEADER widget.
LISTVIEW_SetItemBitmap()	Sets a bitmap as background of the given cell.
LISTVIEW_SetItemBkColor()	Sets the background color of the given cell.
LISTVIEW_SetItemText()	Sets the text of one cell of the LISTVIEW widget specified by row and column.
LISTVIEW_SetItemTextColor()	Sets the text color of the given cell.
LISTVIEW_SetLBorder()	Sets the number of pixels used for the left border within each cell of the LISTVIEW widget.
LISTVIEW_SetOwnerDraw()	Sets an application defined owner draw function for the widget which is responsible for drawing a cell.
LISTVIEW_SetRBorder()	Sets the number of pixels used for the right border within each cell of the LISTVIEW widget.
LISTVIEW_SetRowHeight()	Sets a constant row height.
LISTVIEW_SetSel()	Sets the current selected row.
LISTVIEW_SetSelCol()	Sets the current selected column.
LISTVIEW_SetSelUnsorted()	Sets the current selection in unsorted state.
LISTVIEW_SetSort()	Sets the column and sorting order to be sorted by.
LISTVIEW_SetTextAlign()	Sets the alignment for the given column.
LISTVIEW_SetTextColor()	Sets the text color of the given LISTVIEW widget.
LISTVIEW_SetUserData()	Sets the extra data of a LISTVIEW widget.
LISTVIEW_SetUserDataRow()	Sets the user data of the given row.
LISTVIEW_SetWrapMode()	Sets the wrapping mode which should be used for the cells of the given LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

Defines

Group of defines	Description
LISTVIEW color indexes	Color indexes used by the LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1 Functions

20.17.5.1.1 LISTVIEW_AddColumn()

Description

Adds a new column to a LISTVIEW widget.

Prototype

```
int LISTVIEW_AddColumn(      LISTVIEW_Handle   hObj,
                             int               Width,
                       const char            * s,
                             int               Align);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Width	Width of the new column
s	Text to be displayed in the HEADER widget
Align	Text alignment mode to set. In case of -1 the default alignment for LISTVIEW widgets is used. List of flags can be found under *Text alignment flags* on page 218.

Additional information

The Width-parameter can be 0. If Width = 0 the width of the new column will be calculated by the given text and by the default value of the horizontal spacing. You can only add columns to an 'empty' LISTVIEW widget. If it contains 1 or more rows you can not add a new column.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.2 LISTVIEW_AddRow()

Description

Adds a new row to a LISTVIEW widget.

Prototype

```
int LISTVIEW_AddRow(      LISTVIEW_Handle   hObj,
                    const GUI_ConstString * ppText);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
ppText	Pointer to array containing the text of the LISTVIEW cells

Additional information

The ppText-array should contain one item for each column. If it contains less items the remaining cells left blank.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.3 LISTVIEW_CompareDec()

Description

Compare function for comparing 2 integer values.

Prototype

```
int LISTVIEW_CompareDec(const void * p0,
                        const void * p1);
```

Parameters

Parameter	Description
p0	Void pointer to first value.
p1	Void pointer to second value.

Return value

< 0 if value of cell 0 greater than value of cell 1.
= 0 if value of cell 0 identical to value of cell 1.
> 0 if value of cell 0 less than value of cell 1.

Additional information

The purpose of this function is to be used by the listviews sorting algorithm if the cell text represents integer values. For details about how to use this function for sorting, refer also to `LISTVIEW_SetCompareFunc()`. The `Sample` folder contains the example `WIDGET_SortedListview.c` which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.4 LISTVIEW_CompareText()

Description

Function for comparison of 2 strings.

Prototype

```
int LISTVIEW_CompareText(const void * p0,
                         const void * p1);
```

Parameters

Parameter	Description
p0	Void pointer to first text.
p1	Void pointer to second text.

Return value

> 0 if text of cell 0 greater than text of cell 1.
= 0 if text of cell 0 identical to text of cell 1.
< 0 if text of cell 0 less than text of cell 1.

Additional information

The purpose of this function is to be used by the listviews sorting algorithm. For details about how to use this function for sorting, refer also to LISTVIEW_SetCompareFunc(). The Sample folder contains the example WIDGET_SortedListview.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.5 LISTVIEW_Create()

> **Note**
>
> This function is **deprecated**, `LISTVIEW_CreateEx()` should be used instead.

Description

Creates a LISTVIEW widget of a specified size at a specified location.

Prototype

```
LISTVIEW_Handle LISTVIEW_Create(int     x0,
                                int     y0,
                                int     xSize,
                                int     ySize,
                                WM_HWIN hParent,
                                int     Id,
                                int     Flags,
                                int     ExFlags);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the HEADER widget (in parent coordinates).
`y0`	Topmost pixel of the HEADER widget (in parent coordinates).
`xSize`	Horizontal size of the HEADER widget (in pixels).
`ySize`	Vertical size of the HEADER widget (in pixels).
`hParent`	Handle of the parent window
`Id`	`Id` of the new HEADER widget
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
`SpecialFlags`	(Reserved for later use)

Return value

Handle of the created LISTVIEW widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.6 LISTVIEW_CreateAttached()

Description

Creates a LISTVIEW widget which is attached to an existing window.

Prototype

```
LISTVIEW_Handle LISTVIEW_CreateAttached(WM_HWIN hParent,
                                        int     Id,
                                        int     SpecialFlags);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Id	Id of the new LISTVIEW widget
SpecialFlags	(Not used, reserved for later use)

Return value

Handle of the created LISTVIEW widget; 0 if the function fails.

Additional information

An attached LISTVIEW widget is essentially a child window which will position itself on the parent window and operate accordingly.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.7 LISTVIEW_CreateEx()

Description

Creates a LISTVIEW widget of a specified size at a specified location.

Prototype

```
LISTVIEW_Handle LISTVIEW_CreateEx(int     x0,
                                  int     y0,
                                  int     xSize,
                                  int     ySize,
                                  WM_HWIN hParent,
                                  int     WinFlags,
                                  int     ExFlags,
                                  int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new LISTVIEW widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used, reserved for future use.
Id	Window ID of the widget.

Return value

Handle of the created LISTVIEW widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.8 LISTVIEW_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Para` of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element `Flags` is used according to the parameter `ExFlags` of the function `LISTVIEW_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.9 LISTVIEW_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function LISTVIEW_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.10 LISTVIEW_DecSel()

Description

Decrement the listview selection (moves the selection bar of a specified listview up by one item, if possible).

Prototype

```
void LISTVIEW_DecSel(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Additional information

Note that the numbering of items always starts from the top with a value of 0; therefore, decrementing the selection will actually move the selection one row up.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.11 LISTVIEW_DeleteAllRows()

Description

Deletes all rows from the given LISTVIEW widget.

Prototype

```
void LISTVIEW_DeleteAllRows(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.12 LISTVIEW_DeleteColumn()

Description

Deletes the specified column of the LISTVIEW widget.

Prototype

```
void LISTVIEW_DeleteColumn(LISTVIEW_Handle hObj,
                           unsigned        Index);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Index	Zero-based index of column to be deleted.

Additional information

Note that the numbering of items always starts from the left with a value of 0.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.13 LISTVIEW_DeleteRow()

Description

Deletes the specified row of the LISTVIEW widget.

Prototype

```
void LISTVIEW_DeleteRow(LISTVIEW_Handle hObj,
                        unsigned        Index);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Index	Zero-based index of row to be deleted.

Additional information

Note that the numbering of items always starts from the top with a value of 0.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.14 LISTVIEW_DisableRow()

Before	After
	

Description

The function sets the state of the given row to disabled.

Prototype

```
void LISTVIEW_DisableRow(LISTVIEW_Handle hObj,
                         unsigned        Row);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Row	Zero-based index of the row to be disabled.

Additional information

When scrolling through a LISTVIEW widget disabled items will be skipped. You can not scroll to a disabled listview item.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.15 LISTVIEW_DisableSort()

Description

Disables sorting of the given LISTVIEW widget. After calling this function the content of the LISTVIEW widget will be shown unsorted.

Prototype

```
void LISTVIEW_DisableSort(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Additional information

For details about how to use sorting in LISTVIEW widgets, refer to `LISTVIEW_SetCompareFunc()` and `LISTVIEW_SetSort()`. The `Sample` folder contains the example `WIDGET_SortedListview.c` which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.16 LISTVIEW_EnableCellSelect()

Before	After
	

Description

Enables or disables cell selection mode of the given LISTVIEW widget. If cell selection is enabled it is possible to select a cell via the keys up, down, left and right.

Prototype

```
void LISTVIEW_EnableCellSelect(LISTVIEW_Handle hObj,
                               unsigned        OnOff);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
OnOff	1 to enable and 0 to disable cell selection mode.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.17 LISTVIEW_EnableMotion()

Description

Enables motion support for the given LISTVIEW widget.

Prototype

```
void LISTVIEW_EnableMotion(LISTVIEW_Handle hObj,
                           int             OnOff);
```

Parameters

Parameter	Description
hObj	Handle of LISTVIEW widget.
OnOff	1 for enabling motion support, 0 for disabling motion support.

Additional information

If motion support isn't enabled for the window manager, it will be activated automatically.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.18 LISTVIEW_EnableRow()

Before	After
	

Description

The function sets the state of the given row to enabled.

Prototype

```
void LISTVIEW_EnableRow(LISTVIEW_Handle hObj,
                        unsigned        Row);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Row	Zero-based index of the row to be disabled.

Additional information

Refer to LISTVIEW_DisableRow().

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.19 LISTVIEW_EnableSort()

Description

Enables sorting for the given LISTVIEW widget. After calling this function the content of the listview can be rendered sorted after clicking on the header item of the desired column, by which the LISTVIEW widget should sort its data. Note that this works only after a compare function for the desired column has been set.

Prototype

```
void LISTVIEW_EnableSort(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Additional information

For details about how to set a compare function, refer to `LISTVIEW_SetCompareFunc()`. The `Sample` folder contains the example `WIDGET_SortedListview.c` which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.20 LISTVIEW_GetBkColor()

Description

Returns the background color of the given LISTVIEW widget.

Prototype

```
GUI_COLOR LISTVIEW_GetBkColor(LISTVIEW_Handle hObj,
                              unsigned        Index);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Index	Color index. See *LISTVIEW color indexes* on page 1619 for a full list of permitted values.

Return value

Background color of the given LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.21 LISTVIEW_GetFont()

Description

Returns a pointer to the font used to display the text of the LISTVIEW widget.

Prototype

```
GUI_FONT *LISTVIEW_GetFont(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Return value

Pointer to the font used to display the text of the LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.22 LISTVIEW_GetHeader()

Description

Returns the handle of the HEADER widget.

Prototype

```
HEADER_Handle LISTVIEW_GetHeader(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Return value

Handle of the HEADER widget.

Additional information

Each LISTVIEW widget contains a HEADER widget to manage the columns. You can use this handle to change the properties of the LISTVIEW-HEADER, for example to change the text color of the HEADER widget.

Example

```
LISTVIEW_Handle hListView = LISTVIEW_Create(10, 80, 270, 89, 0, 1234, WM_CF_SHOW, 0);
HEADER_Handle   hHeader   = LISTVIEW_GetHeader(hListView);
HEADER_SetTextColor(hHeader, GUI_GREEN);
```

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.23 LISTVIEW_GetItemRect()

Description

Returns the rectangle of the given LISTVIEW cell by copying the coordinates to the given `GUI_RECT` structure.

Prototype

```
void LISTVIEW_GetItemRect(LISTVIEW_Handle   hObj,
                          U32               Col,
                          U32               Row,
                          GUI_RECT        * pRect);
```

Parameters

Parameter	Description
`hObj`	Handle to a LISTVIEW widget
`Col`	Zero-based index of the cell's column.
`Row`	Zero-based index of the cell's row
`pRect`	Pointer to a rectangle to be filled with the item coordinates.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.24 LISTVIEW_GetItemText()

Description

Copies the text of the specified item to the given buffer.

Prototype

```
void LISTVIEW_GetItemText(LISTVIEW_Handle   hObj,
                          unsigned          Column,
                          unsigned          Row,
                          char            * pBuffer,
                          unsigned          MaxSize);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Column	Zero-based index of the cell's column.
Row	Zero-based index of the cell's row
pBuffer	Pointer to a buffer to be filled by the routine.
MaxSize	Size in bytes of the buffer.

Additional information

If the text of the cell does not fit into the buffer, the number of bytes specified by the parameter MaxSize will be copied to the buffer.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.25 LISTVIEW_GetItemTextLen()

Description

Returns the length in characters of the given text item.

Prototype

```
unsigned LISTVIEW_GetItemTextLen(LISTVIEW_Handle hObj,
                                 unsigned        Column,
                                 unsigned        Row);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Column	Zero-based index of the cell's column.
Row	Zero-based index of the cell's row

Return value

Length in characters of the given text item.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.26 LISTVIEW_GetItemTextSorted()

Description

Copies the text of the specified item to the given buffer. Parameter Row specifies the index of the sorted LISTVIEW widget.

Prototype

```
void LISTVIEW_GetItemTextSorted(LISTVIEW_Handle   hObj,
                                unsigned          Column,
                                unsigned          Row,
                                char            * pBuffer,
                                unsigned          MaxSize);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Column	Zero-based index of the cell's column.
Row	Zero-based sorted index of the cell's row.
pBuffer	Pointer to a buffer to be filled by the routine.
MaxSize	Size in bytes of the buffer.

Additional information

If the text of the cell does not fit into the buffer, the number of bytes specified by the parameter MaxSize will be copied to the buffer.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.27 LISTVIEW_GetLBorder()

Description

Returns the size of the left border within a cell of a LISTVIEW. This value can be set with `LISTVIEW_SetLBorder()`.

Prototype

```
unsigned LISTVIEW_GetLBorder(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.

Return value

Size of left border.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.28 LISTVIEW_GetNumColumns()

Description

Returns the number of columns of the given LISTVIEW widget.

Prototype

```
unsigned LISTVIEW_GetNumColumns(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Return value

Number of columns of the given LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.29 LISTVIEW_GetNumRows()

Description

Returns the number of rows of the given LISTVIEW widget.

Prototype

```
unsigned LISTVIEW_GetNumRows(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Return value

Number of rows of the given LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.30 LISTVIEW_GetRBorder()

Description

Returns the size of the right border within a cell of a LISTVIEW. This value can be set with `LISTVIEW_SetRBorder()`.

Prototype

```
unsigned LISTVIEW_GetRBorder(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.

Return value

Size of right border.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.31 LISTVIEW_GetSel()

Description

Returns the index of the currently selected row in a specified LISTVIEW widget.

Prototype

```
int LISTVIEW_GetSel(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Return value

Index of the currently selected row.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.32 LISTVIEW_GetSelCol()

Description

Returns the index of the currently selected column.

Prototype

```
int LISTVIEW_GetSelCol(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Return value

Index of the currently selected column.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.33 LISTVIEW_GetSelUnsorted()

Description

Returns the index of the currently selected row in unsorted state.

Prototype

```
int LISTVIEW_GetSelUnsorted(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget

Return value

Index of the currently selected row in unsorted state.

Additional information

This function returns the actual index of the selected row, whereas the function LISTVIEW_GetSel() only returns the index of the sorted row. The actual (unsorted) row index should be used in function calls as row index. The Sample folder contains the example WIDGET_SortedListview.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.34 LISTVIEW_GetTextAlign()

Description

Returns the currently set text alignment for the given column.

Prototype

```
int LISTVIEW_GetTextAlign(LISTVIEW_Handle hObj,
                          unsigned        ColIndex);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
ColIndex	Zero-based index of column.

Return value

= -1 On error.
≠ -1 Text alignment of given column. Refer to *Text alignment flags* on page 218.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.35 LISTVIEW_GetTextColor()

Description

Returns the text color of the given LISTVIEW widget.

Prototype

```
GUI_COLOR LISTVIEW_GetTextColor(LISTVIEW_Handle hObj,
                                unsigned        Index);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Index	Index of color. See *LISTVIEW color indexes* on page 1619 for a full list of permitted values.

Return value

Text color of the given LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.36 LISTVIEW_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.37 LISTVIEW_GetUserDataRow()

Description

Returns the user data of the given row.

Prototype

```
U32 LISTVIEW_GetUserDataRow(LISTVIEW_Handle hObj,
                            unsigned        Row);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Row	Zero-based index of row.

Return value

User data of the given row.

Additional information

Details on how to set user data for a row can be found in the description of the function LISTVIEW_SetUserDataRow().

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.38 LISTVIEW_GetWrapMode()

Description

Returns the currently used mode for wrapping text.

Prototype

```
GUI_WRAPMODE LISTVIEW_GetWrapMode(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.

Return value

Currently used wrap mode.

Additional information

Details on how to use text wrapping can be found in the description of the function LISTVIEW_SetWrapMode().

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.39 LISTVIEW_IncSel()

Description

Increment the selection of the LISTVIEW widget (moves the selection bar of a specified LISTVIEW down by one item).

Prototype

```
void LISTVIEW_IncSel(LISTVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.40 LISTVIEW_InsertRow()

Description

Inserts a new row into the LISTVIEW at the given position.

Prototype

```
int LISTVIEW_InsertRow(      LISTVIEW_Handle   hObj,
                             unsigned          Index,
                       const GUI_ConstString * ppText);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Index	Index of the new row.
ppText	Pointer to a string array containing the cell data of the new row.

Return value

0 if function succeed
1 if an error occurs.

Additional information

The ppText-array should contain one item for each column. If it contains less items the remaining cells left blank.
If the given index is ≥ the current number of rows, the function LISTVIEW_AddRow() will be used to add the new row.
The Sample folder contains the example WIDGET_SortedListview.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.41 LISTVIEW_OwnerDraw()

Description

Default function for managing drawing operations of one cell.

Prototype

```
int LISTVIEW_OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.

Return value

Depends on the command in the Cmd element of the WIDGET_ITEM_DRAW_INFO structure pointed by pDrawItemInfo.

Additional information

This function is useful if LISTVIEW_SetOwnerDraw() is used. It can be used to retrieve the original size of a data item and/or to draw the text of a data item and should be called for all commands which are not managed by the application defined owner draw function.

The following commands are managed by the default function:

- WIDGET_ITEM_GET_XSIZE
- WIDGET_ITEM_GET_YSIZE
- WIDGET_ITEM_DRAW
- WIDGET_DRAW_BACKGROUND

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.42 LISTVIEW_RowIsDisabled()

Description

Returns if a row has been disabled.

Prototype

```
unsigned LISTVIEW_RowIsDisabled(LISTVIEW_Handle hObj,
                                unsigned        Row);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Row	Zero-based index of the row to be checked.

Return value

0 Row is not disabled.
1 Row is disabled.

Additional information

Rows of a LISTVIEW widget can be disabled using LISTVIEW_DisableRow() and enabled with LISTVIEW_EnableRow().

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.43 LISTVIEW_SetAutoScrollH()

Description

Enables/disables the automatic use of a horizontal scroll bar.

Prototype

```
void LISTVIEW_SetAutoScrollH(LISTVIEW_Handle hObj,
                             int             State);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
OnOff	See table below.

Permitted values for parameter OnOff	
0	Disable automatic use of a horizontal scroll bar.
1	Enable automatic use of a horizontal scroll bar.

Additional information

If enabled the LISTVIEW checks if all columns fit into the widgets area. If not a horizontal scroll bar will be added.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.44 LISTVIEW_SetAutoScrollV()

Description

Enables/disables the automatic use of a vertical scroll bar.

Prototype

```
void LISTVIEW_SetAutoScrollV(LISTVIEW_Handle hObj,
                             int             State);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
OnOff	See table below.

Permitted values for parameter OnOff	
0	Disable automatic use of a vertical scroll bar.
1	Enable automatic use of a vertical scroll bar.

Additional information

If enabled the LISTVIEW checks if all rows fit into the widgets area. If not a vertical scroll bar will be added.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.45 LISTVIEW_SetBkColor()

Description

Sets the background color of the given LISTVIEW widget.

Prototype

```
void LISTVIEW_SetBkColor(LISTVIEW_Handle hObj,
                         unsigned int    Index,
                         GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Index	Index for background color. See *LISTVIEW color indexes* on page 1619 for a full list of permitted values.
Color	Color to be set.

Additional information

To set the background color for a single cell the function LISTVIEW_SetItemBkColor() should be used. The Sample folder contains the example WIDGET_SortedListview.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.46 LISTVIEW_SetColumnWidth()

Description

Sets the width of the given column.

Prototype

```
void LISTVIEW_SetColumnWidth(LISTVIEW_Handle hObj,
                             unsigned int    Index,
                             int             Width);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Index	Number of column
Width	New width

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.47 LISTVIEW_SetCompareFunc()

Description

Sets the compare function for the given column. A compare function needs to be set if the LISTVIEW widget should be sorted by the given column.

Prototype

```
void LISTVIEW_SetCompareFunc
               (LISTVIEW_Handle hObj,
                unsigned        Column,
                int             ( *fpCompare)(const void * p0 , const void * p1 ));
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Column	Index of the desired column for which the compare function should be set.
fpCompare	Function pointer to compare function.

Additional information

If the sorting feature of the listview widget is used, the widget uses a compare function to decide if the content of one cell is greater, equal or less than the content of the other cell.

Per default no compare function is set for the LISTVIEW columns. For each column which should be used for sorting, a compare function needs to be set. The cells of the LISTVIEW widget contain text. But sometimes the text represents data of other types like dates, integers or others. So different compare functions are required for sorting. emWin provides 2 compare functions:

- `LISTVIEW_CompareText()` Function can be used for comparing cells containing text.
- `LISTVIEW_CompareDec()` Function can be used for comparing cells which text, where the content represents integer values.

The compare function should return a value >0, if the content of the second cell is greater than the content of the first cell and <0, if the content of the second cell is less than the content of the first cell or 0 if equal.
Also user defined compare functions can be used. The prototype of a application-defined function should be defined as follows:

Prototype

```
int APPLICATION_Compare(const void * p0,
                        const void * p1);
```

Parameter	Description
p0	Pointer to NULL terminated string data of the first cell.
p1	Pointer to NULL terminated string data of the second cell.

Example

```
int APPLICATION_Compare(const void * p0, const void * p1) {
  return strcmp((const char *)p1, (const char *)p0);
}
void SetAppCompareFunc(WM_HWIN hListView, int Column) {
  LISTVIEW_SetCompareFunc(hListView, Column, APPLICATION_Compare);
}
```

 © 2020 SEGGER Microcontroller GmbH

The `Sample` folder contains the example `WIDGET_SortedListview.c` which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.48 LISTVIEW_SetDefaultBkColor()

Description

Sets the default background color for new LISTVIEW widgets.

Prototype

```
GUI_COLOR LISTVIEW_SetDefaultBkColor(unsigned  Index,
                                     GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	Index of default background color. See *LISTVIEW color indexes* on page 1619 for a full list of permitted values.
Color	Color to be set as default

Return value

Previous default background color.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.49 LISTVIEW_SetDefaultFont()

Description

Sets the default font for new LISTVIEW widgets.

Prototype

```
GUI_FONT *LISTVIEW_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to font used for new LISTVIEW widgets.

Return value

Pointer to the previous default font.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.50 LISTVIEW_SetDefaultGridColor()

Description

Sets the default color of the grid lines for new LISTVIEW widgets.

Prototype

```
GUI_COLOR LISTVIEW_SetDefaultGridColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	New default value.

Return value

Previous default grid color.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.51 LISTVIEW_SetDefaultTextColor()

Description

Sets the default text color for new LISTVIEW widgets.

Prototype

```
GUI_COLOR LISTVIEW_SetDefaultTextColor(unsigned  Index,
                                       GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	Index of default text color. See *LISTVIEW color indexes* on page 1619 for a full list of permitted values.
Color	Color to be set as default.

Return value

Previous default text color.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.52 LISTVIEW_SetFixed()

Description

Fixes the given number of columns at their horizontal positions.

Prototype

```
unsigned LISTVIEW_SetFixed(LISTVIEW_Handle hObj,
                           unsigned        Fixed);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Fixed	Number of columns to be fixed at their horizontal positions.

Return value

Old number of fixed columns.

Additional information

Using this function makes sense if one or more columns should remain at their horizontal positions during scrolling operations.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.53 LISTVIEW_SetFont()

Description

Sets the font of the LISTVIEW widget.

Prototype

```
void LISTVIEW_SetFont(      LISTVIEW_Handle   hObj,
                      const GUI_FONT        * pFont);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
pFont	Pointer to the font.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.54 LISTVIEW_SetGridVis()

Description

Sets the visibility flag of the grid lines. When creating a LISTVIEW the grid lines are disabled per default.

Prototype

```
int LISTVIEW_SetGridVis(LISTVIEW_Handle hObj,
                        int             Show);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Show	Sets the visibility of the grid lines.

Permitted values for parameter Show	
0	Not visible.
1	Visible

Return value

Previous value of the visibility flag.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.55 LISTVIEW_SetHeaderHeight()

Description

Sets the height of the attached HEADER widget.

Prototype

```
void LISTVIEW_SetHeaderHeight(LISTVIEW_Handle hObj,
                              unsigned        HeaderHeight);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Show	Height of the attached HEADER widget to be set.

Additional information

Setting the height to 0 causes the HEADER widget not to be displayed.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.56 LISTVIEW_SetItemBitmap()

Before	After
	

Description

Sets a bitmap as background of the given cell.

Prototype

```
void LISTVIEW_SetItemBitmap(      LISTVIEW_Handle   hObj,
                                  unsigned          Column,
                                  unsigned          Row,
                                  int               xOff,
                                  int               yOff,
                            const GUI_BITMAP      * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget.
Column	Number of column.
Row	Number of row.
xOff	Offset for the leftmost pixel of the bitmap to be drawn.
yOff	Offset for the topmost pixel of the bitmap to be drawn.
pBitmap	Pointer to the bitmap.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.57 LISTVIEW_SetItemBkColor()

Before	After
	

Description

Sets the background color of the given cell.

Prototype

```
void LISTVIEW_SetItemBkColor(LISTVIEW_Handle hObj,
                             unsigned        Column,
                             unsigned        Row,
                             unsigned int    Index,
                             GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Column	Number of columns.
Row	Number of rows.
Index	Index of background color. See *LISTVIEW color indexes* on page 1619 for a full list of permitted values.
Color	Color to be used.

Additional information

This function overwrites the default background color for the given cell set by LISTVIEW_SetBkColor().

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.58 LISTVIEW_SetItemText()

Description

Sets the text of one cell of the LISTVIEW widget specified by row and column.

Prototype

```
void LISTVIEW_SetItemText(      LISTVIEW_Handle   hObj,
                                unsigned          Column,
                                unsigned          Row,
                          const char            * pText);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Column	Number of column.
Row	Number of row.
s	Text to be displayed in the table cell.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.59 LISTVIEW_SetItemTextColor()

Before	After
	

Description

Sets the text color of the given cell.

Prototype

```
void LISTVIEW_SetItemTextColor(LISTVIEW_Handle hObj,
                               unsigned        Column,
                               unsigned        Row,
                               unsigned        Index,
                               GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Column	Number of column.
Row	Number of row.
Index	Index of text color. See *LISTVIEW color indexes* on page 1619 for a full list of permitted values.
Color	Color to be used.

Additional information

This function overwrites the default text color for the given cell set by LISTVIEW_SetText-Color().

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.60 LISTVIEW_SetItemTextSorted()

Description

Sets the text of the given item in a sorted LISTVIEW widget.

Prototype

```
void LISTVIEW_SetItemTextSorted(      LISTVIEW_Handle   hObj,
                                      unsigned          Column,
                                      unsigned          Row,
                                const char            * pText);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Column	Number of column.
Row	Number of row.
pText	Pointer to the given NULL terminated text.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.61 LISTVIEW_SetLBorder()

Before	After
	

Description

Sets the number of pixels used for the left border within each cell of the LISTVIEW widget.

Prototype

```
void LISTVIEW_SetLBorder(LISTVIEW_Handle hObj,
                         unsigned        BorderSize);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
BorderSize	Number of pixels to be used.

Additional information

Using this function has no effect to the HEADER widget used by the LISTVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.62 LISTVIEW_SetOwnerDraw()

Description

Sets an application defined owner draw function for the widget which is responsible for drawing a cell.

Prototype

```
void LISTVIEW_SetOwnerDraw(LISTVIEW_Handle         hObj,
                           WIDGET_DRAW_ITEM_FUNC * pfDrawItem);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
pfOwnerDraw	Pointer to owner draw function.

Supported commands

- WIDGET_ITEM_GET_XSIZE
- WIDGET_ITEM_GET_YSIZE
- WIDGET_ITEM_DRAW
- WIDGET_ITEM_DRAW_BACKGROUND

Additional information

This function sets a pointer to an application defined function which will be called by the widget when a cell has to be drawn or when the x or y size of a item is needed. It gives you the possibility to draw anything as data item, not just plain text. pfDrawItem is a pointer to an application-defined function of type WIDGET_DRAW_ITEM_FUNC which is explained at the beginning of the chapter. Also, please refer to LISTVIEW_OwnerDraw().

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.63 LISTVIEW_SetRBorder()

Before	After
	

Description

Sets the number of pixels used for the right border within each cell of the LISTVIEW widget.

Prototype

```
void LISTVIEW_SetRBorder(LISTVIEW_Handle hObj,
                         unsigned        BorderSize);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
BorderSize	Number of pixels to be used.

Additional information

Using this function has no effect to the header widget used by the listview.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.64 LISTVIEW_SetRowHeight()

Description

Sets a constant row height.

Prototype

```
unsigned LISTVIEW_SetRowHeight(LISTVIEW_Handle hObj,
                               unsigned        RowHeight);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
RowHeight	Constant row height to set. In case RowHeight = 0, the height of the current font is used instead.

Return value

Previous value of the row height set by this function.

Additional information

Per default the height of the rows depends on the height of the used font.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.65 LISTVIEW_SetSel()

Description

Sets the selected row of a specified LISTVIEW widget.

Prototype

```
void LISTVIEW_SetSel(LISTVIEW_Handle hObj,
                     int             NewSel);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Sel	Row to be selected.

Additional information

Pass -1 as parameter Sel to select no row.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.66 LISTVIEW_SetSelCol()

Description

Sets the selected column of the given LISTVIEW widget. Makes sense in combination with `LISTVIEW_EnableCellSelect()`.

Prototype

```
void LISTVIEW_SetSelCol(LISTVIEW_Handle hObj,
                        int             NewCol);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
NewCol	Column to be selected.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.67 LISTVIEW_SetSelUnsorted()

Description

Sets the index of the currently selected row in unsorted state.

Prototype

```
void LISTVIEW_SetSelUnsorted(LISTVIEW_Handle hObj,
                             int             Sel);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Sel	Zero-based selection index in unsorted state.

Additional information

This function sets the actually index of the selected row, whereas the function LISTVIEW_SetSel() sets the index of the sorted row. The actual (unsorted) row index should be used in function calls as row index.
The Sample folder contains the example WIDGET_SortedListview.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.68 LISTVIEW_SetSort()

Before	After
	

Description

This function sets the column to be sorted by and the sorting order.

Prototype

```
unsigned LISTVIEW_SetSort(LISTVIEW_Handle hObj,
                          unsigned        Column,
                          unsigned        Reverse);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Column	Column to be sorted by.
Reverse	0 for normal sorting order (greatest element at the top), 1 for reverse order.

Return value

0 if function was successfully
1 if not.

Additional information

Before calling this function a compare function needs to be set for the desired column. For details about how to set a compare function, refer to LISTVIEW_SetCompareFunc(). The Sample folder contains the example WIDGET_SortedListview.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.69 LISTVIEW_SetTextAlign()

Description

Sets the alignment for the given column.

Prototype

```
void LISTVIEW_SetTextAlign(LISTVIEW_Handle hObj,
                           unsigned int    Index,
                           int             Align);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Index	Number of column
Align	Text alignment mode to set. List of flags can be found under *Text alignment flags* on page 218.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.70 LISTVIEW_SetTextColor()

Description

Sets the text color of the given LISTVIEW widget.

Prototype

```
void LISTVIEW_SetTextColor(LISTVIEW_Handle hObj,
                           unsigned int    Index,
                           GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Index	Index for text color. See *LISTVIEW color indexes* on page 1619 for a full list of permitted values.
Color	Color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.71 LISTVIEW_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.72 LISTVIEW_SetUserDataRow()

Description

Sets the user data of the given row.

Prototype

```
void LISTVIEW_SetUserDataRow(LISTVIEW_Handle hObj,
                             unsigned        Row,
                             U32             UserData);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
Row	Row for which the user data should be set
UserData	Value to be associated with the row.

Additional information

Sets the 32-bit value associated with the row. Each row has a corresponding 32-bit value intended for use by the application.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.1.73 LISTVIEW_SetWrapMode()

Description

Sets the wrapping mode which should be used for the cells of the given LISTVIEW widget.

Prototype

```
void LISTVIEW_SetWrapMode(LISTVIEW_Handle hObj,
                          GUI_WRAPMODE    WrapMode);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
WrapMode	See table below.

 © 2020 SEGGER Microcontroller GmbH

20.17.5.2 Defines

20.17.5.2.1 LISTVIEW color indexes

Description

Color indexes to be used by the LISTVIEW widget.

Definition

```
#define LISTVIEW_CI_UNSEL       0
#define LISTVIEW_CI_SEL         1
#define LISTVIEW_CI_SELFOCUS    2
#define LISTVIEW_CI_DISABLED    3
```

Symbols

Definition	Description
LISTVIEW_CI_UNSEL	Unselected element.
LISTVIEW_CI_SEL	Selected element, without focus.
LISTVIEW_CI_SELFOCUS	Selected element, with focus.
LISTVIEW_CI_DISABLED	Disabled element.

 © 2020 SEGGER Microcontroller GmbH

20.17.6 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_ListView.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_ListView.c



 © 2020 SEGGER Microcontroller GmbH

20.18 LISTWHEEL: Listwheel widget

This widget is similar to the LISTBOX widget described earlier in this chapter. Whereas the data of a LISTBOX is selected by moving the cursor with the keyboard or by using a SCROLLBAR the LISTWHEEL works completely different: The whole data area can be moved via pointer input device (PID). Striking over the widget from top to bottom or vice versa moves the data up or downwards. When releasing the PID during the data area is moving it slows down its motion and stops by snapping in a new item at the snap position. Further the data is shown in a loop. After the last data item it continues with the first item like in a chain. So the data can be 'rotated' like a wheel:

Description	LISTWHEEL widget
Application example showing three wheels for selecting a date. The example uses the owner draw mechanism to overlay the widget with a customized alpha mask for the shading effect.	

The table above shows a screenshot of the example `WIDGET_ListWheel.c` located in the example folder `Sample\Tutorial\` of the emWin package.

> **Note**
>
> All LISTWHEEL-related routines are located in the file(s) `LISTWHEEL*.c`, `LISTWHEEL.h`. All identifiers are prefixed LISTWHEEL.

20.18.1 Configuration options

Type	Macro	Default	Description
S	LISTWHEEL_FONT_DEFAULT	GUI_Font13_1	Font used.
N	LISTWHEEL_BKCOLOR0_DEFAULT	GUI_WHITE	Background color of normal text.
N	LISTWHEEL_BKCOLOR1_DEFAULT	GUI_WHITE	Background color of selected text.
N	LISTWHEEL_TEXTCOLOR0_DEFAULT	GUI_BLACK	Text color of normal text.
N	LISTWHEEL_TEXTCOLOR1_DEFAULT	GUI_BLUE	Text color of selected text.
N	LISTWHEEL_TEXTALIGN_DEFAULT	GUI_TA_LEFT	Text alignment.
N	LISTWHEEL_DECELERATION_DEFAULT	15	Deceleration value.
N	LISTWHEEL_TIMER_PERIOD_DEFAULT	25	Timer period.

20.18.2 Predefined IDs

The following symbols define IDs which may be used to make LISTWHEEL widgets distinguishable from creation.

```
#define GUI_ID_LISTVIEW0    0x200
#define GUI_ID_LISTVIEW1    0x201
#define GUI_ID_LISTVIEW2    0x202
#define GUI_ID_LISTVIEW3    0x203
#define GUI_ID_LISTVIEW4    0x204
#define GUI_ID_LISTVIEW5    0x205
```

 © 2020 SEGGER Microcontroller GmbH

```
#define GUI_ID_LISTVIEW6    0x206
#define GUI_ID_LISTVIEW7    0x207
#define GUI_ID_LISTVIEW8    0x208
#define GUI_ID_LISTVIEW9    0x209
```

20.18.3 Notification codes

The following events are sent from the widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	Widget has been clicked.
WM_NOTIFICATION_RELEASED	Widget has been released.
WM_NOTIFICATION_MOVED_OUT	Widget has been clicked and pointer has been moved out of the widget without releasing.
WM_NOTIFICATION_SEL_CHANGED	An item has been snapped at the snap position.

20.18.4 Keyboard reaction

This widget currently does not react on keyboard input.

20.18.5 LISTWHEEL API

The table below lists the available emWin LISTWHEEL-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
LISTWHEEL_AddString()	Adds a new string.
LISTWHEEL_CreateEx()	Creates a LISTWHEEL widget.
LISTWHEEL_CreateIndirect()	Creates a LISTWHEEL widget from a resource table entry.
LISTWHEEL_CreateUser()	Creates a LISTWHEEL widget using extra bytes as user data.
LISTWHEEL_GetBkColor()	Returns the background color of the widget.
LISTWHEEL_GetFont()	Returns the font which is used to draw the data items of the given LISTWHEEL widget.
LISTWHEEL_GetItemFromPos()	Returns the index of the item matching the given position.
LISTWHEEL_GetItemText()	Returns the text of the requested data item.
LISTWHEEL_GetLBorder()	Returns the size in pixels between the left border of the widget and the beginning of the text.
LISTWHEEL_GetLineHeight()	Returns the height of one data item.
LISTWHEEL_GetNumItems()	Returns the number of data items of the given LISTWHEEL widget.
LISTWHEEL_GetPos()	Returns the zero-based index of the item which is currently snapped in.
LISTWHEEL_GetRBorder()	Returns the size in pixels between the right border of the widget and the end of the text.
LISTWHEEL_GetSel()	Returns the zero-based index of the currently selected item.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
LISTWHEEL_GetSnapPosition()	Returns the position in pixels from the top of the LISTWHEEL widget at which the data items should be 'snapped in'.
LISTWHEEL_GetTextAlign()	Returns the text alignment of the given LISTWHEEL widget.
LISTWHEEL_GetTextColor()	Returns the text color of the widget.
LISTWHEEL_GetUserData()	Retrieves the data set with LISTWHEEL_SetUserData().
LISTWHEEL_IsMoving()	Returns the current state (moving or not moving) of the given LISTWHEEL widget.
LISTWHEEL_MoveToPos()	Moves the data area of the LISTWHEEL widget to the given position.
LISTWHEEL_OwnerDraw()	Default function for managing drawing operations of one data item.
LISTWHEEL_SetBkColor()	Sets the specified background color for selected and unselected items.
LISTWHEEL_SetDeceleration()	Sets the deceleration behavior of the LISTWHEEL.
LISTWHEEL_SetFont()	Sets the font which should be used to draw the data items.
LISTWHEEL_SetLBorder()	Sets the size in pixels of the left border.
LISTWHEEL_SetLineHeight()	Sets the line height used to draw a data item.
LISTWHEEL_SetOwnerDraw()	Sets an application defined owner draw function for the widget which is responsible for drawing the widget items.
LISTWHEEL_SetPos()	Sets the data area of the LISTWHEEL widget to the given position.
LISTWHEEL_SetRBorder()	Sets the size in pixels of the right border.
LISTWHEEL_SetSel()	The function sets the selected item.
LISTWHEEL_SetSnapPosition()	The function sets the relative position from the top of the widget at which the items should snap in.
LISTWHEEL_SetText()	It removes any existing item and adds the given items passed by the function.
LISTWHEEL_SetTextAlign()	Sets the text alignment used to draw the items of the LISTWHEEL widget.
LISTWHEEL_SetTextColor()	Sets the color to be used to draw the text.
LISTWHEEL_SetTimerPeriod()	Sets the time interval after which the LISTWHEEL will be updated in milliseconds.
LISTWHEEL_SetUserData()	Sets the extra data of a LISTWHEEL widget.
LISTWHEEL_SetVelocity()	Starts moving the LISTWHEEL widget using the given velocity.

Defines

Group of defines	Description
LISTWHEEL color indexes	Color indexes used by the LISTWHEEL widget.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1 Functions

20.18.5.1.1 LISTWHEEL_AddString()

Description

Adds a new data item (typically a string) to the widget.

Prototype

```
void LISTWHEEL_AddString(      LISTWHEEL_Handle   hObj,
                         const char             * pString);
```

Parameters

Parameter	Description
hObj	Handle to a LISTVIEW widget
pString	Pointer to the string to be added.

Additional information

The width of the given text should fit into the horizontal widget area. Otherwise the text will be clipped during the drawing operation.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.2 LISTWHEEL_CreateEx()

Description

Creates a LISTWHEEL widget of a specified size at a specified location.

Prototype

```
LISTWHEEL_Handle LISTWHEEL_CreateEx(      int               x0,
                                          int               y0,
                                          int               xSize,
                                          int               ySize,
                                          WM_HWIN           hParent,
                                          int               WinFlags,
                                          int               ExFlags,
                                          int               Id,
                                    const GUI_ConstString * ppText);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new LISTVIEW widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used, reserved for future use.
Id	Window ID of the widget.
ppText	Pointer to an array of string pointers containing the elements to be displayed.

Return value

Handle of the created LISTWHEEL widget; 0 if the function fails.

Additional information

If the parameter ppText is used the last element of the array needs to be a NULL element.

Example

```
char * apText[] = {
  "Monday",
  "Tuesday",
  "Wednesday",
  "Thursday",
  "Friday",
  "Saturday",
  "Sunday",
  NULL
};
LISTWHEEL_CreateEx(10, 10, 100, 100, WM_HBKWIN, WM_CF_SHOW, 0, GUI_ID_LISTWHEEL0, apText);
```

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.3 LISTWHEEL_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element Para of the according GUI_WIDGET_CREATE_INFO structure is not used. The element Flags is used according to the parameter WinFlags of the function LISTWHEEL_CreateEx().

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.4 LISTWHEEL_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `LISTWHEEL_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.5 LISTWHEEL_GetBkColor()

Description

Returns the background color of the widget.

Prototype

```
GUI_COLOR LISTWHEEL_GetBkColor(LISTWHEEL_Handle hObj,
                               unsigned int     Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Index	See *LISTWHEEL color indexes* on page 1661 for a full list of permitted values.

Return value

The background color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.6 LISTWHEEL_GetFont()

Description

Returns the font which is used to draw the data items of the given LISTWHEEL widget.

Prototype

```
GUI_FONT *LISTWHEEL_GetFont(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.

Return value

Pointer to a GUI_FONT structure which is used to draw the data items.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.7 LISTWHEEL_GetItemFromPos()

Description

Returns the index of the item matching the given position.

Prototype

```
int LISTWHEEL_GetItemFromPos(LISTWHEEL_Handle hObj,
                             int              yPos);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
yPos	Y-position of the LISTWHEEL widget.

Return value

Index of the item matching the given position. -1, if an item index could not be determined.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.8 LISTWHEEL_GetItemText()

Description

Returns the text of the requested data item.

Prototype

```
void LISTWHEEL_GetItemText(LISTWHEEL_Handle   hObj,
                           unsigned           Index,
                           char             * pBuffer,
                           int                MaxSize);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Index	Index of the requested item.
pBuffer	Buffer for storing the text.
MaxSize	Size in bytes of the buffer.

Return value

The function copies the text of the given item into the given buffer. If the size of the buffer is too small the text will be clipped.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.9 LISTWHEEL_GetLBorder()

Description

Returns the size in pixels between the left border of the widget and the beginning of the text.

Prototype

```
int LISTWHEEL_GetLBorder(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.

Return value

Number of pixels between left border and text.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.10 LISTWHEEL_GetLineHeight()

Description

Returns the height of one data item.

Prototype

```
unsigned LISTWHEEL_GetLineHeight(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.

Return value

Height of one data item.

Additional information

This function returns the value set by the function LISTWHEEL_SetLineHeight(). A return value of zero means the height of one item depends on the size of the current font. For more details, refer to LISTWHEEL_SetLineHeight(), LISTWHEEL_GetFont() and GUI_GetYSize-OfFont().

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.11 LISTWHEEL_GetNumItems()

Description

Returns the number of data items of the given LISTWHEEL widget.

Prototype

```
int LISTWHEEL_GetNumItems(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.

Return value

Number of data items of the given LISTWHEEL widget.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.12 LISTWHEEL_GetPos()

Description

Returns the zero-based index of the item which is currently snapped in.

Prototype

```
int LISTWHEEL_GetPos(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.

Return value

Index of the item which is currently snapped in.

Additional information

The position at which the items being snapped can be set with the function LISTWHEEL_SetSnapPosition(). For more details, refer to LISTWHEEL_SetSnapPosition().

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.13 LISTWHEEL_GetRBorder()

Description

Returns the size in pixels between the right border of the widget and the end of the text.

Prototype

```
int LISTWHEEL_GetRBorder(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.

Return value

Number of pixels between right border and text.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.14 LISTWHEEL_GetSel()

Description

Returns the zero-based index of the currently selected item.

Prototype

```
int LISTWHEEL_GetSel(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.

Return value

Index of the currently selected item.

Additional information

For more information, refer to LISTWHEEL_SetSel().

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.15 LISTWHEEL_GetSnapPosition()

Description

Returns the position in pixels from the top of the LISTWHEEL widget at which the data items should be 'snapped in'.

Prototype

```
int LISTWHEEL_GetSnapPosition(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.

Return value

Snap position in pixels from the top edge of the LISTWHEEL widget.

Additional information

The default value is 0.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.16 LISTWHEEL_GetTextAlign()

Description

Returns the text alignment of the given LISTWHEEL widget.

Prototype

```
int LISTWHEEL_GetTextAlign(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.

Return value

Text alignment of the given LISTWHEEL widget.

Additional information

For more information, refer to `LISTWHEEL_SetTextAlign()`.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.17 LISTWHEEL_GetTextColor()

Description

Returns the text color of the widget.

Prototype

```
GUI_COLOR LISTWHEEL_GetTextColor(LISTWHEEL_Handle hObj,
                                 unsigned int     Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Index	See *LISTWHEEL color indexes* on page 1661 for a full list of permitted values.

Return value

The text color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.18 LISTWHEEL_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.19 LISTWHEEL_IsMoving()

Description

Returns the current state (moving or not moving) of the given LISTWHEEL widget.

Prototype

```
int LISTWHEEL_IsMoving(LISTWHEEL_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Index	See table below.

Return value

0 not moving
1 moving

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.20 LISTWHEEL_MoveToPos()

Description

Moves the data area of the LISTWHEEL widget to the given position.

Prototype

```
void LISTWHEEL_MoveToPos(LISTWHEEL_Handle hObj,
                         unsigned int     Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Index	Zero-based index of the item to which the 'wheel' should move.

Additional information

The widget starts moving by choosing the shortest way. If for example 7 items are available and item 2 is currently snapped and the widget should move to the last item it begins moving backwards until the seventh item has been reached. Detailed information on how to set a position can be found in the description of `LISTWHEEL_SetPos()`.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.21 LISTWHEEL_OwnerDraw()

Description

Default function for managing drawing operations of one data item.

Prototype

```
int LISTWHEEL_OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Index	Zero-based index of the item to which the 'wheel' should move.

Return value

Depends on the command in the Cmd element of the WIDGET_ITEM_DRAW_INFO structure pointed by pDrawItemInfo.

Additional information

This function is useful if LISTWHEEL_SetOwnerDraw() is used. It can be used to retrieve the original size of a data item and/or to draw the text of a data item and should be called for all commands which are not managed by the application defined owner draw function. For more information, refer to *User drawn widgets* on page 983, LISTWHEEL_SetOwnerDraw() and to the provided example.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.22 LISTWHEEL_SetBkColor()

Before	After
	

Description

Sets the specified background color for selected and unselected items.

Prototype

```
void LISTWHEEL_SetBkColor(LISTWHEEL_Handle hObj,
                          unsigned int     Index,
                          GUI_COLOR        Color);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Index	See *LISTWHEEL color indexes* on page 1661 for a full list of permitted values.
Color	New background color.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.23 LISTWHEEL_SetDeceleration()

Description

Sets the deceleration behavior of the LISTWHEEL. The higher the deceleration value, the less time it takes for the LISTWHEEL to stop moving.

Prototype

```
void LISTWHEEL_SetDeceleration(LISTWHEEL_Handle hObj,
                               unsigned         Deceleration);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Deceleration	Deceleration value.

Additional information

The default value of the deceleration is 15. This can be change with the configuration option LISTWHEEL_DECELERATION_DEFAULT.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.24 LISTWHEEL_SetFont()

Before	After
	

Description

Sets the font which should be used to draw the data items.

Prototype

```
void LISTWHEEL_SetFont(      LISTWHEEL_Handle   hObj,
                       const GUI_FONT         * pFont);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
pFont	Pointer to a GUI_FONT structure.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.25 LISTWHEEL_SetLBorder()

Before	After
	

Description

Sets the border size between the left edge of the widget and the beginning of the text.

Prototype

```
void LISTWHEEL_SetLBorder(LISTWHEEL_Handle hObj,
                          unsigned         BorderSize);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
BorderSize	Desired border size.

Additional information

The default value of the border size is 0.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.26 LISTWHEEL_SetLineHeight()

Before	After
	

Description

Sets the line height used to draw a data item.

Prototype

```
void LISTWHEEL_SetLineHeight(LISTWHEEL_Handle hObj,
                             unsigned         LineHeight);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
LineHeight	Desired height. Default is 0 which means the font size determines the height of a line.

Additional information

Per default the height of a line depends on the used font. The value set by this function ’overwrites’ this default behavior.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.27 LISTWHEEL_SetOwnerDraw()

Before	After
	

Description

Sets an application defined owner draw function for the widget which is responsible for drawing the widget items.

Prototype

```
void LISTWHEEL_SetOwnerDraw(LISTWHEEL_Handle        hObj,
                            WIDGET_DRAW_ITEM_FUNC * pfOwnerDraw);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
pfOwnerDraw	Pointer to owner draw function.

Supported commands

- WIDGET_ITEM_GET_XSIZE
- WIDGET_ITEM_GET_YSIZE
- WIDGET_ITEM_DRAW
- WIDGET_ITEM_DRAW_BACKGROUND
- WIDGET_ITEM_DRAW_OVERLAY

Additional information

This function sets a pointer to an application defined function which will be called by the widget when a data item has to be drawn or when the x or y size of a item is needed. It gives you the possibility to draw anything as data item, not just plain text. pfDrawItem is a pointer to an application-defined function of type WIDGET_DRAW_ITEM_FUNC which is explained at the beginning of the chapter.
The following commands are supported: WIDGET_ITEM_GET_YSIZE, WIDGET_ITEM_DRAW, WIDGET_DRAW_BACKGROUND and WIDGET_DRAW_OVERLAY.

Example

The following example routine draws 2 red indicator lines over the widget:

```
static int _OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo) {
  switch (pDrawItemInfo->Cmd) {
  case WIDGET_DRAW_OVERLAY:
    GUI_SetColor(GUI_RED);
    GUI_DrawHLine(40, 0, 99);
    GUI_DrawHLine(59, 0, 99);
    break;
  default:
    return LISTWHEEL_OwnerDraw(pDrawItemInfo);
  }
  return 0;
}
```

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.28 LISTWHEEL_SetPos()

Description

Sets the data area of the LISTWHEEL widget to the given position.

Prototype

```
void LISTWHEEL_SetPos(LISTWHEEL_Handle hObj,
                      unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Index	Zero-based index of the item to which the 'wheel' should be set.

Additional information

Detailed information on how to move the LISTWHEEL to a position can be found in the description of LISTWHEEL_MoveToPos().

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.29 LISTWHEEL_SetRBorder()

Before	After
	

Description

Sets the border size between the left edge of the widget and the beginning of the text.

Prototype

```
void LISTWHEEL_SetRBorder(LISTWHEEL_Handle hObj,
                          unsigned         BorderSize);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
BorderSize	Desired border size.

Additional information

The default value of the border size is 0.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.30 LISTWHEEL_SetSel()

Before	After
	

Description

The function sets the selected item.

Prototype

```
void LISTWHEEL_SetSel(LISTWHEEL_Handle hObj,
                      int              Sel);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Sel	Zero-based index of item to be selected.

Additional information

Only one item can be selected. Per default the item with index 0 is selected.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.31 LISTWHEEL_SetSnapPosition()

Before	After
	

Description

The function sets the relative position from the top of the widget at which the items should snap in.

Prototype

```
void LISTWHEEL_SetSnapPosition(LISTWHEEL_Handle hObj,
                               int              SnapPosition);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
SnapPosition	Relative position in pixels from the top of the widget at which the items should be snapped in.

Additional information

Per default the snap position is 0 which means the items are snapped in at the top of the widget. The function LISTWHEEL_GetPos() can be used to get the zero based index of the current item which has been snapped in.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.32 LISTWHEEL_SetText()

Before	After
	

Description

It removes any existing item and adds the given items passed by the function.

Prototype

```
void LISTWHEEL_SetText(      LISTWHEEL_Handle   hObj,
                       const GUI_ConstString  * ppText);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
ppText	Pointer to an array of strings. The last item needs to be a NULL pointer.

Additional information

Note that the last element pointed to by ppText needs to be a NULL pointer.

Example

The following example should demonstrate how the function should be used:

```
static char * _apText[] = {
  "Monday",
  "Tuesday",
  "Wednesday",
  "Thursday",
  "Friday",
  "Saturday",
  "Sunday",
  NULL
};
static void _SetContent(void) {
  LISTWHEEL_SetText(hWin, _apText);
}
```

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.33 LISTWHEEL_SetTextAlign()

Before	After
	

Description

Sets the text alignment used to draw the items of the LISTWHEEL widget.

Prototype

```
void LISTWHEEL_SetTextAlign(LISTWHEEL_Handle hObj,
                            int              Align);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Align	Alignment to be used to draw the items of the widget.

Additional information

For details about text alignment, refer to GUI_SetTextAlign().

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.34 LISTWHEEL_SetTextColor()

Before	After
	

Description

Sets the color to be used to draw the text.

Prototype

```
void LISTWHEEL_SetTextColor(LISTWHEEL_Handle hObj,
                            unsigned int     Index,
                            GUI_COLOR        Color);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Index	See table below. See *LISTWHEEL color indexes* on page 1661 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.35 LISTWHEEL_SetTimerPeriod()

Description

Sets the time interval after which the LISTWHEEL will be updated in milliseconds. By default this will be every 25ms.

Prototype

```
void LISTWHEEL_SetTimerPeriod(LISTWHEEL_Handle hObj,
                              GUI_TIMER_TIME   TimerPeriod);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
TimerPeriod	Timer period used for updating the LISTWHEEL.

Additional information

The default value of 25 can be set with the configuration option `LISTWHEEL_TIMER_PERIOD`.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.36 LISTWHEEL_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.1.37 LISTWHEEL_SetVelocity()

Description

Starts moving the LISTWHEEL widget using the given velocity.

Prototype

```
void LISTWHEEL_SetVelocity(LISTWHEEL_Handle hObj,
                           int              Velocity);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
Velocity	Starting speed.

Additional information

The velocity decreases automatically. The higher the given velocity the longer it takes for the movement to stop.

Example

This function is used in the sample applications MEMDEV_ListWheelEffects.c and WIDGET_ListWheel.c.

 © 2020 SEGGER Microcontroller GmbH

20.18.5.2 Defines

20.18.5.2.1 LISTWHEEL color indexes

Description

Color indexes to be used by the LISTWHEEL widget.

Definition

```
#define LISTWHEEL_CI_UNSEL    0
#define LISTWHEEL_CI_SEL      1
```

Symbols

Definition	Description
LISTWHEEL_CI_UNSEL	Color of unselected element.
LISTWHEEL_CI_SEL	Color of selected element.

 © 2020 SEGGER Microcontroller GmbH

20.19 MENU: Menu widget

The MENU widget can be used to create several kinds of MENUs. Each MENU item represents an application command or a submenu. MENUs can be shown horizontally and/or vertically. Menu items can be grouped using separators. Separators are supported for horizontal and vertical MENUs. Selecting a MENU item sends a `WM_MENU` message to the owner of the MENU or opens a submenu. If mouse support is enabled the MENU widget reacts on moving the mouse over the items of a MENU widget. The shipment of emWin contains an application example which shows how to use the MENU widget. It can be found under `Sample\Application\Reversi.c`. The table below shows the appearance of a horizontal MENU widget with a vertical submenu:

Description	Menu using `WIDGET_Effect_3D1L`	Menu using `WIDGET_Effect_Simple`
Color display (8666 mode)		
Monochrome display (16 gray scales)		
Black/white display		

> **Note**
>
> All MENU-related routines are located in the file(s) `MENU*.c`, `MENU.h`.
> All identifiers are prefixed MENU.

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.19.1 Menu messages

To inform its owner about selecting an item or opening a submenu the MENU widget sends a message of type `WM_MENU` to its owner.

 © 2020 SEGGER Microcontroller GmbH

20.19.1.1 WM_MENU

Description

This message is sent to inform the owner of a MENU about selecting an item or opening a submenu. Disabled MENU items will not send this message.

Data

The `Data.p` pointer of the message points to a `MENU_MSG_DATA` structure.

Example

The following example shows how to react on a `WM_MENU` message:

```
void Callback(WM_MESSAGE * pMsg) {
  MENU_MSG_DATA * pData;
  WM_HWIN hWin = pMsg->hWin;
  switch (pMsg->MsgId) {
  case WM_MENU:
    pData = (MENU_MSG_DATA *)pMsg->Data.p;
    switch (pData->MsgType) {
    case MENU_ON_ITEMACTIVATE:
      _UpdateStatusbar(pData->ItemId);
      break;
    case MENU_ON_INITMENU:
      _OnInitMenu();
      break;
    case MENU_ON_ITEMSELECT:
      switch (pData->ItemId) {
      case ID_MENU_ITEM0:
        ... /* React on selection of menu item 0 */
        break;
      case ID_MENU_ITEM1:
        ... /* React on selection of menu item 1 */
        break;
      case ...
        ...
      }
      break;
    }
    break;
  default:
    MENU_Callback(pMsg);
  }
}
```

20.19.2 Configuration options

Type	Macro	Default	Description
N	MENU_BKCOLOR0_DEFAULT	GUI_LIGHTGRAY	Background color for enabled and unselected items.
N	MENU_BKCOLOR1_DEFAULT	0x980000	Background color for enabled and selected items.
N	MENU_BKCOLOR2_DEFAULT	GUI_LIGHTGRAY	Background color for disabled items.
N	MENU_BKCOLOR3_DEFAULT	0x980000	Background color for disabled and selected items.
N	MENU_BKCOLOR4_DEFAULT	0x7C7C7C	Background color for active submenu items.

 © 2020 SEGGER Microcontroller GmbH

Type	Macro	Default	Description
N	MENU_BORDER_BOTTOM_DEFAULT	2	Border between item text and item bottom.
N	MENU_BORDER_LEFT_DEFAULT	4	Border between item text and left edge of item.
N	MENU_BORDER_RIGHT_DEFAULT	4	Border between item text and right edge of item.
N	MENU_BORDER_TOP_DEFAULT	2	Border between item text and item top.
S	MENU_EFFECT_DEFAULT	WIDGET_Effect_3D1L	Default effect.
S	MENU_FONT_DEFAULT	GUI_Font13_1	Font used.
N	MENU_TEXTCOLOR0_DEFAULT	GUI_BLACK	Text color for enabled and unselected items.
N	MENU_TEXTCOLOR1_DEFAULT	GUI_WHITE	Text color for enabled and selected items.
N	MENU_TEXTCOLOR2_DEFAULT	0x7C7C7C	Text color for disabled items.
N	MENU_TEXTCOLOR3_DEFAULT	GUI_LIGHTGRAY	Text color for disabled and selected items.
N	MENU_TEXTCOLOR4_DEFAULT	GUI_WHITE	Text color for active submenu items.

20.19.3 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_RIGHT	• If the MENU is horizontal, the selection moves one item to the right. • If the MENU is vertical and the current item is a submenu, the submenu opens and the input focus moves to the submenu. • If the MENU is vertical and the current item is not a submenu and the top level MENU is horizontal, the next item of the top level MENU opens and the input focus moves to it.
GUI_KEY_LEFT	• If the MENU is horizontal the selection moves one item to the left. • If the MENU is vertical and the MENU is not the top level MENU, the current MENU closes and the focus moves to the previous MENU. If the previous MENU is horizontal the previous submenu of it opens and the focus moves to the previous submenu.
GUI_KEY_DOWN	• If the MENU is horizontal and the current MENU item is a submenu this submenu opens. • If the MENU is vertical, the selection moves to the next item.
GUI_KEY_UP	• If the MENU is vertical, the selection moves to the previous item.
GUI_KEY_ESCAPE	• If the MENU is not the top level MENU the current MENU will be closed and the focus moves to the previous MENU. • If the MENU is the top level MENU, the current MENU item becomes unselected.
GUI_KEY_ENTER	• If the current MENU item is a submenu, the submenu opens and the focus moves to the submenu.

 © 2020 SEGGER Microcontroller GmbH

Key	Reaction
	• If the current MENU item is not a submenu, all submenus of the top level MENU closes and a MENU_ON_ITEMSELECT message will be sent to the owner of the MENU.

20.19.4 MENU API

The table below lists the available emWin MENU-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
MENU_AddItem()	Adds an item to an existing MENU widget.
MENU_Attach()	Attaches the given MENU widget at the given position with the given size to a specified WINDOW.
MENU_CreateEx()	Creates a MENU widget.
MENU_CreateIndirect()	Creates a MENU widget from a resource table entry.
MENU_CreateUser()	Creates a MENU widget using extra bytes as user data.
MENU_DeleteItem()	Deletes a given MENU item from a MENU widget.
MENU_DisableItem()	Disables the given MENU item.
MENU_EnableItem()	Enables the given MENU item.
MENU_GetBkColor()	Returns the background color of the widget.
MENU_GetDefaultBkColor()	Returns the default background color used to draw new MENU items.
MENU_GetDefaultBorderSize()	Returns the default border size used for new MENU widgets.
MENU_GetDefaultEffect()	Returns the default effect for new MENU widgets.
MENU_GetDefaultFont()	Returns a pointer to the default font used to display the MENU item text of new MENU widgets.
MENU_GetDefaultTextColor()	Returns the default text color for new MENU widgets.
MENU_GetFont()	Returns the font of the widget.
MENU_GetItem()	Retrieves information about the given MENU item.
MENU_GetItemText()	Returns the text of the given MENU item.
MENU_GetNumItems()	Returns the number of items of the given MENU widget.
MENU_GetOwner()	Returns the owner WINDOW of the given MENU widget.
MENU_GetTextColor()	Returns the text color of the widget.
MENU_GetUserData()	Retrieves the data set with MENU_SetUserData().
MENU_InsertItem()	Inserts a MENU item at the given position.
MENU_Popup()	Opens the given MENU at the given position.
MENU_SetBkColor()	Sets the background color of the given MENU widget.
MENU_SetBorderSize()	Sets the border size of the given MENU widget.
MENU_SetDefaultBkColor()	Sets the default background color used to draw new MENU items.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
MENU_SetDefaultBorderSize()	Sets the default border size used for new MENU widgets.
MENU_SetDefaultEffect()	Sets the default effect for new MENU widgets.
MENU_SetDefaultFont()	Sets the pointer to the default font used to display the MENU item text of new MENU widgets.
MENU_SetDefaultTextColor()	Sets the default text color for new MENU widgets.
MENU_SetFont()	Sets the pointer to the font used to display the item text of the MENU widget.
MENU_SetItem()	Sets the item information for the given MENU item.
MENU_SetOwner()	Sets the owner WINDOW of the MENU widget that will be informed with WM_MENU messages.
MENU_SetSel()	Sets the selected item of the given MENU widget.
MENU_SetTextColor()	Sets the text color of the given MENU widget.
MENU_SetUserData()	Sets the extra data of a MENU widget.

Data structures

Structure	Description
MENU_ITEM_DATA	This structure serves as a container to set or retrieve information about MENU items.
MENU_MSG_DATA	This structure is used in conjunction with the WM_MENU message, specific to the MENU widget.

Defines

Group of defines	Description
MENU border indexes	Border indexes used by functions to set the border properties of a MENU widget.
MENU color indexes	Color indexes used by the MENU widget.
MENU create flags	Create flags used by MENU_CreateEx().
MENU item flags	Flags used by the MENU_ITEM_DATA structure.
MENU message types	Types of messages sent via the MENU_MSG_DATA structure with the WM_MENU message.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1 Functions

20.19.4.1.1 MENU_AddItem()

Before	After
	

Description

This function adds a new item to the end of the given MENU widget.

Prototype

```
void MENU_AddItem(      MENU_Handle      hObj,
                  const MENU_ITEM_DATA * pItemData);
```

Parameters

Parameter	Description
hObj	Handle of LISTWHEEL widget.
pItemData	Pointer to a MENU_ITEM_DATA structure containing the information of the new item.

Additional information

If using a MENU widget with several submenus the Id of the MENU items should be unique. Different submenus should not contain MENU items with the same IDs. When adding items to a MENU widget and no fixed sizes are used the size of the MENU will be adapted.
Refer to *MENU_ITEM_DATA* on page 1703.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.2 MENU_Attach()

Description

Attaches the given MENU widget at the given position with the given size to a specified WINDOW.

Prototype

```
void MENU_Attach(MENU_Handle hObj,
                 WM_HWIN     hDestWin,
                 int         x,
                 int         y,
                 int         xSize,
                 int         ySize,
                 int         Flags);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
hDestWin	Handle to the WINDOW to which the MENU widget should be attached.
x	X position in window coordinates of the MENU widget.
y	Y position in window coordinates of the MENU widget.
ySize	Fixed Y size of the MENU. For details, refer to MENU_Create-Ex().
xSize	Fixed X size of the MENU. For details, refer to MENU_Create-Ex().
Flags	Reserved for future use

Additional information

After creating a MENU widget this function can be used to attach the MENU widget to an existing window.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.3 MENU_CreateEx()

Description

Creates a MENU widget of a specified size at a specified location.

Prototype

```
MENU_Handle MENU_CreateEx(int     x0,
                          int     y0,
                          int     xSize,
                          int     ySize,
                          WM_HWIN hParent,
                          int     WinFlags,
                          int     ExFlags,
                          int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Fixed horizontal size of the widget (in pixels). 0 if MENU should handle the xSize.
ySize	Fixed vertical size of the widget (in pixels). 0 if MENU should handle the ySize.
hParent	Handle of parent window. If 0, the new widget will be a child of the desktop (top-level window). In some cases it can be useful to create the MENU widget in 'unattached' state and attach it later to an existing window. For this case WM_UNATTACHED can be used as parameter.
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *MENU create flags* on page 1707.
Id	Window ID of the widget.

Return value

Handle of the created MENU widget; 0 if the function fails.

Additional information

The parameters xSize and/or ySize specifies if a fixed width and/or height should be used for the MENU widget.
If these parameters are > 0, fixed sizes should be used. If for example the MENU should be attached as a horizontal MENU to the top of a WINDOW it can be necessary to use a fixed X size which covers the whole top of the window. In this case the parameter xSize can be used to set a fixed X size of the MENU. When attaching or deleting items of a MENU with a fixed size the size of the widget does not change. If the values are 0, the MENU handles its size itself. That means the size of the MENU depends on the size of the current MENU items of a MENU widget. If items are added or removed the size of the widget will be adapted.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.4 MENU_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element Para of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element Flags is used according to the parameter ExFlags of the function `MENU_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.5 MENU_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `MENU_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.6 MENU_DeleteItem()

Before	After
	

Description

Deletes a given MENU item from a MENU widget.

Prototype

```
void MENU_DeleteItem(MENU_Handle hObj,
                     U16         ItemId);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
ItemId	Id of the MENU item to be deleted.

Additional information

If the item does not exist the function returns immediately. When deleting items from a MENU widget and no fixed sizes are used the window size will be adapted.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.7 MENU_DisableItem()

Before	After
	

Description

Disables the given MENU item.

Prototype

```
void MENU_DisableItem(MENU_Handle hObj,
                      U16         ItemId);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
ItemId	Id of the MENU item to be disabled.

Additional information

If a disabled MENU item is selected, the MENU widget does not send the WM_MENU message to the owner. A disabled submenu item can not be opened.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.8 MENU_EnableItem()

Before	After
	

Description

Enables the given MENU item.

Prototype

```
void MENU_EnableItem(MENU_Handle hObj,
                     U16         ItemId);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
ItemId	Id of the MENU item to be enabled.

Additional information

For details, refer to `MENU_DisableItem()`.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.9 MENU_GetBkColor()

Description

Returns the background color of the widget.

Prototype

```
GUI_COLOR MENU_GetBkColor(MENU_Handle hObj,
                          unsigned    ColorIndex);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
Index	See *MENU color indexes* on page 1706 for a full list of permitted values.

Return value

The background color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.10 MENU_GetDefaultBkColor()

Description

Returns the default background color used to draw new MENU items.

Prototype

```
GUI_COLOR MENU_GetDefaultBkColor(unsigned ColorIndex);
```

Parameters

Parameter	Description
ColorIndex	See *MENU color indexes* on page 1706 for a full list of permitted values.

Return value

Default background color used to draw new MENU items.

Additional information

For details, refer to `MENU_SetBkColor()`.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.11 MENU_GetDefaultBorderSize()

Description

Returns the default border size used for new MENU widgets.

Prototype

```
U8 MENU_GetDefaultBorderSize(unsigned BorderIndex);
```

Parameters

Parameter	Description
BorderIndex	See *MENU border indexes* on page 1705 for a full list of permitted values.

Return value

Default border size used for new MENU widgets.

Additional information

For details, refer to `MENU_SetBorderSize()`.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.12 MENU_GetDefaultEffect()

Description

Returns the default effect for new MENU widgets.

Prototype

```
WIDGET_EFFECT *MENU_GetDefaultEffect(void);
```

Return value

The result of the function is a pointer to a `WIDGET_EFFECT` structure.

Additional information

For more information, refer to `WIDGET_SetDefaultEffect()`.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.13 MENU_GetDefaultFont()

Description

Returns a pointer to the default font used to display the MENU item text of new MENU widgets.

Prototype

```
GUI_FONT *MENU_GetDefaultFont(void);
```

Return value

Pointer to the default font used to display the MENU item text of new MENU widgets.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.14 MENU_GetDefaultTextColor()

Description

Returns the default text color for new MENU widgets.

Prototype

```
GUI_COLOR MENU_GetDefaultTextColor(unsigned ColorIndex);
```

Parameters

Parameter	Description
`ColorIndex`	See *MENU color indexes* on page 1706 for a full list of permitted values.

Return value

Default text color for new MENU widgets.

Additional information

For details, refer to `MENU_SetDefaultTextColor()`.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.15 MENU_GetFont()

Description

Returns the font of the widget.

Prototype

```
GUI_FONT *MENU_GetFont(MENU_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.

Return value

Pointer to the font of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.16 MENU_GetItem()

Description

Retrieves information about the given MENU item.

Prototype

```
void MENU_GetItem(MENU_Handle      hObj,
                  U16              ItemId,
                  MENU_ITEM_DATA * pItemData);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
ItemId	Id of the requested MENU item.
pItemData	Pointer to a MENU_ITEM_DATA structure to be filled by the function.

Additional information

If using a MENU widget with several submenus the handle of the widget needs to be the handle of the menu/submenu containing the requested item or the handle of a higher menu/submenu.

The function sets the element pText of the MENU_ITEM_DATA structure to 0. To retrieve the MENU item text the function MENU_GetItemText() should be used. Refer to the beginning of the MENU chapter for details about the MENU_ITEM_DATA data structure.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.17 MENU_GetItemText()

Description

Returns the text of the given MENU item.

Prototype

```
void MENU_GetItemText(MENU_Handle   hObj,
                      U16           ItemId,
                      char        * pBuffer,
                      unsigned      BufferSize);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
ItemId	Id of the requested MENU item.
pBuffer	Buffer to be filled by the function.
BufferSize	Maximum number of bytes to be retrieved.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.18 MENU_GetNumItems()

Description

Returns the number of items of the given MENU widget.

Prototype

```
unsigned MENU_GetNumItems(MENU_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.

Return value

Number of items of the given MENU widget.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.19 MENU_GetOwner()

Description

Returns the owner WINDOW of the given MENU widget.

Prototype

```
WM_HWIN MENU_GetOwner(MENU_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.

Return value

Owner WINDOW of the given MENU widget.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.20 MENU_GetTextColor()

Description

Returns the text color of the widget.

Prototype

```
GUI_COLOR MENU_GetTextColor(MENU_Handle hObj,
                            unsigned    ColorIndex);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
Index	See *MENU color indexes* on page 1706 for a full list of permitted values.

Return value

The text color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.21 MENU_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.22 MENU_InsertItem()

Before	After
	

Description

Inserts a MENU item at the given position.

Prototype

```
void MENU_InsertItem(      MENU_Handle      hObj,
                           U16              ItemId,
                     const MENU_ITEM_DATA * pItemData);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
ItemId	Id of the MENU item the new item should be inserted before.
pItemData	Pointer to a MENU_ITEM_DATA structure containing the information of the new item.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.23 MENU_Popup()

Description

Opens the given MENU at the given position. After selecting a MENU item or after touching the display outside the MENU the popup MENU will be closed.

Prototype

```
void MENU_Popup(MENU_Handle hObj,
                WM_HWIN     hDestWin,
                int         x,
                int         y,
                int         xSize,
                int         ySize,
                int         Flags);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
hDestWin	Handle to the window to which the MENU should be attached.
x	X position in window coordinates of the MENU widget.
y	Y position in window coordinates of the MENU widget.
xSize	Fixed X size of the MENU. For details, refer to MENU_CreateEx().
ySize	Fixed Y size of the MENU. For details, refer to MENU_CreateEx().
Flags	Reserved for future use

Additional information

After selecting a MENU item or after touching the display outside the popup MENU the MENU will be closed. Note that the MENU will not be deleted automatically. The Sample folder contains the example WIDGET_PopupMenu.c which shows how to use the function.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.24 MENU_SetBkColor()

Before	After
	

Description

Sets the background color of the given MENU widget.

Prototype

```
void MENU_SetBkColor(MENU_Handle hObj,
                     unsigned    ColorIndex,
                     GUI_COLOR   Color);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
ColorIndex	See *MENU color indexes* on page 1706 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.25 MENU_SetBorderSize()

Before	After
	

The following code is executed between the screenshots above:

```
MENU_SetBorderSize(hMenuGame, MENU_BI_LEFT, 20);
```

Before	After
	

The following code is executed between the screenshots above:

```
MENU_SetBorderSize(hMenu, MENU_BI_LEFT, 10);
MENU_SetBorderSize(hMenu, MENU_BI_RIGHT, 10);
```

Description

Sets the border size of the given MENU widget.

Prototype

```
void MENU_SetBorderSize(MENU_Handle hObj,
                        unsigned    BorderIndex,
                        U8          BorderSize);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
BorderIndex	See *MENU border indexes* on page 1705 for a full list of permitted values.
BorderSize	Size to be used.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.26 MENU_SetDefaultBkColor()

Description

Sets the default background color used to draw new MENU items.

Prototype

```
void MENU_SetDefaultBkColor(unsigned  ColorIndex,
                            GUI_COLOR Color);
```

Parameters

Parameter	Description
`ColorIndex`	See *MENU color indexes* on page 1706 for a full list of permitted values.
`Color`	`Color` to be used.

Additional information

For details, refer to `MENU_SetBkColor()`.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.27 MENU_SetDefaultBorderSize()

Description

Sets the default border size used for new MENU widgets.

Prototype

```
void MENU_SetDefaultBorderSize(unsigned BorderIndex,
                               U8       BorderSize);
```

Parameters

Parameter	Description
BorderIndex	See *MENU border indexes* on page 1705 for a full list of permitted values.
BorderSize	Border size to be used.

Additional information

For details, refer to `MENU_SetBorderSize()`.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.28 MENU_SetDefaultEffect()

Description

Sets the default effect for new MENU widgets.

Prototype

```
void MENU_SetDefaultEffect(const WIDGET_EFFECT * pEffect);
```

Parameters

Parameter	Description
pEffect	Pointer to a WIDGET_EFFECT structure.

Additional information

For more information, refer to WIDGET_SetDefaultEffect().

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.29 MENU_SetDefaultFont()

Description

Sets the pointer to the default font used to display the MENU item text of new MENU widgets.

Prototype

```
void MENU_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to the GUI_FONT structure to be used.

Additional information

For details, refer to MENU_SetFont().

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.30 MENU_SetDefaultTextColor()

Description

Sets the default text color for new MENU widgets.

Prototype

```
void MENU_SetDefaultTextColor(unsigned  ColorIndex,
                              GUI_COLOR Color);
```

Parameters

Parameter	Description
ColorIndex	See *MENU color indexes* on page 1706 for a full list of permitted values.
Color	Color to be used

Additional information

For details, refer to MENU_SetTextColor().

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.31 MENU_SetFont()

Before	After
	

Description

Sets the pointer to the font used to display the item text of the MENU widget.

Prototype

```
void MENU_SetFont(      MENU_Handle   hObj,
                  const GUI_FONT    * pFont);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
pFont	Pointer to the GUI_FONT structure to be used.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.32 MENU_SetItem()

Before	After
	

Description

Sets the item information for the given MENU item.

Prototype

```
void MENU_SetItem(      MENU_Handle      hObj,
                        U16              ItemId,
                  const MENU_ITEM_DATA * pItemData);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
ItemId	Id of the MENU item to be changed.
pItemData	Pointer to a MENU_ITEM_DATA structure containing the new information.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.33 MENU_SetOwner()

Description

Sets the owner WINDOW of the MENU widget that will be informed with WM_MENU messages.

Prototype

```
void MENU_SetOwner(MENU_Handle hObj,
                   WM_HWIN     hOwner);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
hOwner	Handle of the owner WINDOW which should receive the WM_MENU messages of the MENU widget.

Additional information

If no owner is set the parent WINDOW of the MENU widget will receive WM_MENU messages. In case the WM_MENU messages are not intended to be sent to the parent WINDOW, this function can be used to set another recipient for the messages.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.34 MENU_SetSel()

Before	After
	

Description

Sets the selected item of the given MENU widget.

Prototype

```
int MENU_SetSel(MENU_Handle hObj,
                int         Sel);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
Sel	Zero-based index of MENU item to be selected.

Return value

The function returns the zero based index of the previous selected MENU item.

Additional information

A value <0 for parameter Sel deselects the MENU items.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.35 MENU_SetTextColor()

Before	After
	

Description

Sets the text color of the given MENU widget.

Prototype

```
void MENU_SetTextColor(MENU_Handle hObj,
                       unsigned    ColorIndex,
                       GUI_COLOR   Color);
```

Parameters

Parameter	Description
hObj	Handle of MENU widget.
ColorIndex	See *MENU color indexes* on page 1706 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.1.36 MENU_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.2 Data structures

20.19.4.2.1 MENU_ITEM_DATA

Description

This structure serves as a container to set or retrieve information about MENU items.

Type definition

```
typedef struct {
  const char * pText;
  U16          Id;
  U16          Flags;
  MENU_Handle  hSubmenu;
} MENU_ITEM_DATA;
```

Structure members

Member	Description
pText	MENU item text.
Id	Id of the MENU item.
Flags	See *MENU item flags* on page 1708.
hSubmenu	If the item represents a submenu this element contains the handle of the submenu.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.2.2 MENU_MSG_DATA

Description

This structure is used in conjunction with the WM_MENU message, specific to the MENU widget. The Data.p pointer of the message points to a MENU_MSG_DATA structure.

Type definition

```
typedef struct {
  U16  MsgType;
  U16  ItemId;
} MENU_MSG_DATA;
```

Structure members

Member	Description
MsgType	See *MENU message types* on page 1709.
ItemId	Id of MENU item.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.3 Defines

20.19.4.3.1 MENU border indexes

Description

Border indexes used by functions to set the border properties of a MENU widget.

Definition

```
#define MENU_BI_LEFT      0
#define MENU_BI_RIGHT     1
#define MENU_BI_TOP       2
#define MENU_BI_BOTTOM    3
```

Symbols

Definition	Description
MENU_BI_LEFT	Border between item text and left edge of item.
MENU_BI_RIGHT	Border between item text and right edge of item.
MENU_BI_TOP	Border between item text and item top.
MENU_BI_BOTTOM	Border between item text and item bottom.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.3.2 MENU color indexes

Description

Color indexes used by the MENU widget.

Definition

```
#define MENU_CI_ENABLED           0
#define MENU_CI_SELECTED          1
#define MENU_CI_DISABLED          2
#define MENU_CI_DISABLED_SEL      3
#define MENU_CI_ACTIVE_SUBMENU    4
```

Symbols

Definition	Description
MENU_CI_ENABLED	Color of enabled and not selected MENU items.
MENU_CI_SELECTED	Color of enabled and selected MENU items.
MENU_CI_DISABLED	Color of disabled MENU items.
MENU_CI_DISABLED_SEL	Color of disabled and selected MENU items.
MENU_CI_ACTIVE_SUB-MENU	Color of active submenu items.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.3.3 MENU create flags

Description

Create flags used when creating a MENU widget. These flags are used for the ExFlags parameter of MENU_CreateEx().

Definition

```
#define MENU_CF_HORIZONTAL    (0 << 0)
#define MENU_CF_VERTICAL      (1 << 0)
```

Symbols

Definition	Description
MENU_CF_HORIZONTAL	Creates a horizontal MENU.
MENU_CF_VERTICAL	Creates a vertical MENU.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.3.4 MENU item flags

Description

Flags used by the MENU_ITEM_DATA structure.

Definition

```
#define MENU_IF_DISABLED     (1 << 0)
#define MENU_IF_SEPARATOR    (1 << 1)
```

Symbols

Definition	Description
MENU_IF_DISABLED	Indicates that item is disabled.
MENU_IF_SEPARATOR	Indicates that item is a separator.

 © 2020 SEGGER Microcontroller GmbH

20.19.4.3.5 MENU message types

Description

Types of messages sent with the MsgType parameter of the MENU_MSG_DATA structure. A pointer to this structure is sent via the Data.p pointer of a WM_MENU message.

Definition

```
#define MENU_ON_ITEMSELECT      0
#define MENU_ON_INITMENU        1
#define MENU_ON_INITSUBMENU     2         /* Send to owner when selecting a submenu
                                             */
#define MENU_ON_OPEN            3         /* Internal message of menu widget (only
 send to submenus)                           */
#define MENU_ON_CLOSE           4         /* Internal message of menu widget (only
 send to submenus)                           */
#define MENU_IS_MENU            5         /* Internal message of menu widget. Owner
 must call WM_DefaultProc() when not handle the message */
#define MENU_ON_ITEMACTIVATE    6
#define MENU_ON_ITEMPRESSED     7
```

Symbols

Definition	Description
MENU_ON_ITEMSELECT	This message is sent to the owner of a MENU immediately after a MENU item is selected. The ItemId element of the MENU_MSG_DATA structure contains the Id of the pressed MENU item.
MENU_ON_INITMENU	This message is sent to the owner of MENU immediately before the MENU opens. This enables the application to modify the MENU before it is shown.
MENU_ON_INITSUBMENU	Internal use.
MENU_ON_OPEN	Internal use.
MENU_ON_CLOSE	Internal use.
MENU_IS_MENU	Internal use.
MENU_ON_ITEMACTIVATE	The owner window of a MENU will receive this message after a MENU item has been highlighted. The message is not sent after highlighting a submenu.
MENU_ON_ITEMPRESSED	After pressing a MENU item this message will be sent to the owner window of the widget. It will be sent also for disabled MENU items.

 © 2020 SEGGER Microcontroller GmbH

20.19.5 Example

The `Sample` folder contains the sample `WIDGET_Menu.c` which shows how the widget can be used. Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_Menu.c



 © 2020 SEGGER Microcontroller GmbH

20.20 MULTIEDIT: Multi line text widget

The MULTIEDIT widget enables you to edit text with multiple lines. You can use it as a simple text editor or to display static text. The widget supports scrolling with and without scroll bars.

> **Note**
>
> All MULTIEDIT-related routines are in the file(s) `MULTIEDIT*.c`, `MULTIEDIT.h`. All identifiers are prefixed MULTIEDIT.

The table below shows the appearance of the MULTIEDIT widget:

Description	Frame window
Edit mode, automatic horizontal scroll bar, non wrapping mode, insert mode	
Edit mode, automatic vertical scroll bar, word wrapping mode, overwrite mode	
Read only mode, word wrapping mode	

20.20.1 Configuration options

Type	Macro	Default	Description
S	`MULTIEDIT_FONT_DEFAULT`	`GUI_Font13_1`	Font used.
N	`MULTIEDIT_BKCOLOR0_DEFAULT`	`GUI_WHITE`	Background color.
N	`MULTIEDIT_BKCOLOR2_DEFAULT`	`0xC0C0C0`	Background color read only mode.
N	`MULTIEDIT_TEXTCOLOR0_DEFAULT`	`GUI_BLACK`	Text color.
N	`MULTIEDIT_TEXTCOLOR2_DEFAULT`	`GUI_BLACK`	Text color read only mode.

20.20.2 Predefined IDs

The following symbols define IDs which may be used to make MULTIEDIT widgets distinguishable from creation.

```
#define GUI_ID_MULTIEDIT0    0x190
```

 © 2020 SEGGER Microcontroller GmbH

```
#define GUI_ID_MULTIEDIT1    0x191
#define GUI_ID_MULTIEDIT2    0x192
#define GUI_ID_MULTIEDIT3    0x193
#define GUI_ID_MULTIEDIT4    0x194
#define GUI_ID_MULTIEDIT5    0x195
#define GUI_ID_MULTIEDIT6    0x196
#define GUI_ID_MULTIEDIT7    0x197
#define GUI_ID_MULTIEDIT8    0x198
#define GUI_ID_MULTIEDIT9    0x199
```

20.20.3 Notification codes

The following events are sent from the widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	Widget has been clicked.
WM_NOTIFICATION_RELEASED	Widget has been released.
WM_NOTIFICATION_MOVED_OUT	Widget has been clicked and pointer has been moved out of the widget without releasing.
WM_NOTIFICATION_SCROLL_CHANGED	The scroll position of the optional scroll bar has been changed.
WM_NOTIFICATION_VALUE_CHANGED	The text of the widget has been changed.

20.20.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_UP	Moves the cursor one line up.
GUI_KEY_DOWN	Moves the cursor one line down.
GUI_KEY_RIGHT	Moves the cursor one character to the right.
GUI_KEY_LEFT	Moves the cursor one character to the left.
GUI_KEY_END	Moves the cursor to the end of the current row.
GUI_KEY_HOME	Moves the cursor to the begin of the current row.
GUI_KEY_BACKSPACE	If the widget works in read/write mode this key deletes the character before the cursor.
GUI_KEY_DELETE	If the widget works in read/write mode this key deletes the character below the cursor.
GUI_KEY_INSERT	Toggles between insert and overwrite mode.
GUI_KEY_ENTER	If the widget works in read/write mode this key inserts a new line (\n) at the current position. If the widget works in read only mode the cursor will be moved to the beginning of the next line.
GUI_KEY_PGUP	Scrolls the MULTIEDIT page wise up.
GUI_KEY_PGDOWN	Scrolls the MULTIEDIT page wise down.

20.20.5 MULTIEDIT API

The table below lists the available emWin MULTIEDIT-related routines in alphabetical order. Detailed descriptions of the routines follow.

 © 2020 SEGGER Microcontroller GmbH

Functions

Routine	Description
MULTIEDIT_AddKey()	Adds user input to a specified MULTIEDIT widget.
MULTIEDIT_AddText()	Adds the given text at the current cursor position.
MULTIEDIT_Create()	Creates a MULTIEDIT widget. (Obsolete)
MULTIEDIT_CreateEx()	Creates a MULTIEDIT widget.
MULTIEDIT_CreateIndirect()	Creates a MULTIEDIT widget from a resource table entry.
MULTIEDIT_CreateUser()	Creates a MULTIEDIT widget using extra bytes as user data.
MULTIEDIT_EnableBlink()	Enables/disables a blinking cursor.
MULTIEDIT_GetBkColor()	Returns the background color of the widget.
MULTIEDIT_GetCursorCharPos()	Returns the number of the character at the cursor position.
MULTIEDIT_GetCursorPixelPos()	Returns the pixel position of the cursor in window coordinates.
MULTIEDIT_GetFont()	Returns the font of the widget.
MULTIEDIT_GetNumChars()	Returns the number of characters of the MULTIEDIT widget.
MULTIEDIT_GetPrompt()	Returns the current prompt text.
MULTIEDIT_GetText()	Returns the current text.
MULTIEDIT_GetTextColor()	Returns the text color of the widget.
MULTIEDIT_GetTextFromLine()	Returns the text of a given line from a given start character.
MULTIEDIT_GetTextFromPos()	Returns the text from a start and end point.
MULTIEDIT_GetTextSize()	Returns the buffer size used to store the current text (and prompt).
MULTIEDIT_GetUserData()	Retrieves the data set with MULTIEDIT_SetUserData().
MULTIEDIT_SetAutoScrollH()	Enables/disables the automatic use of a horizontal scroll bar.
MULTIEDIT_SetAutoScrollV()	Enables/disables the automatic use of a vertical scroll bar.
MULTIEDIT_SetBkColor()	Sets the background color of the given MULTIEDIT widget.
MULTIEDIT_SetBufferSize()	Sets the maximum number of bytes used by text and prompt.
MULTIEDIT_SetCursorCharPos()	This function sets the cursor to the given position where x is the character in a line and y is line.
MULTIEDIT_SetCursorOffset()	Sets the cursor position to the given character.
MULTIEDIT_SetCursorPixelPos()	This function sets the cursor to the given position, where x and y are the coordinates in pixels relative to the widget.
MULTIEDIT_SetFocusable()	Sets the focusability of the given MULTIEDIT widget.
MULTIEDIT_SetFont()	Sets the font.
MULTIEDIT_SetHBorder()	Sets the size of the horizontal border.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
MULTIEDIT_SetInsertMode()	Enables/disables the insert mode.
MULTIEDIT_SetMaxNumChars()	Sets the maximum number of characters used by text and prompt.
MULTIEDIT_SetPasswordMode()	Enables/disables the password mode.
MULTIEDIT_SetPrompt()	Sets the prompt text.
MULTIEDIT_SetReadOnly()	Enables/disables the read only mode.
MULTIEDIT_SetText()	Sets the text.
MULTIEDIT_SetTextAlign()	Sets the text alignment.
MULTIEDIT_SetTextColor()	Sets the text color.
MULTIEDIT_SetUserData()	Sets the extra data of a MULTIEDIT widget.
MULTIEDIT_SetWrapChar()	
MULTIEDIT_SetWrapNone()	Enables the non wrapping mode.
MULTIEDIT_SetWrapWord()	Enables the word wrapping mode.
MULTIEDIT_ShowCursor()	This function enables or disables the cursor of the MULTIEDIT widget.

Defines

Group of defines	Description
MULTIEDIT color indexes	Color indexes used by the MULTIEDIT widget.
MULTIEDIT create flags	Create flags used by MULTIEDIT_CreateEx().

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1 Functions

20.20.5.1.1 MULTIEDIT_AddKey()

Description

Adds user input to a specified MULTIEDIT widget.

Prototype

```
int MULTIEDIT_AddKey(MULTIEDIT_HANDLE hObj,
                     U16              Key);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
Key	Character to be added.

Return value

1 if Key has been consumed.
0 if Key was not handled.

Additional information

The specified character is added to the user input of the MULTIEDIT widget. If the maximum count of characters has been reached, another character will not be added.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.2 MULTIEDIT_AddText()

Description

Adds the given text at the current cursor position.

Prototype

```
int MULTIEDIT_AddText(      MULTIEDIT_HANDLE   hObj,
                      const char             * s);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
s	Pointer to a NULL terminated text to be added.

Additional information

If the number of characters exceeds the limit set with the function MULTIEDIT_SetMaxNumChars() the function will add only the characters of the text which fit into the widget respecting the limit.
If the the function MULTIEDIT_SetMaxNumChars() has not been called the MULTIEDIT widget increases its buffer automatically to hold the complete text.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.3 MULTIEDIT_Create()

> **Note**
>
> This function is **deprecated**, `MULTIEDIT_CreateEx()` should be used instead.

Description

Creates a `MULTIEDIT` widget of a specified size at a specified location.

Prototype

```
MULTIEDIT_HANDLE MULTIEDIT_Create(      int       x0,
                                        int       y0,
                                        int       xSize,
                                        int       ySize,
                                        WM_HWIN   hParent,
                                        int       Id,
                                        int       Flags,
                                        int       ExFlags,
                                  const char    * pText,
                                        int       MaxLen);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the MULTIEDIT widget (in parent coordinates).
`y0`	Topmost pixel of the MULTIEDIT widget (in parent coordinates).
`xSize`	Horizontal size of the MULTIEDIT widget (in pixels).
`ySize`	Vertical size of the MULTIEDIT widget (in pixels).
`hParent`	Parent window of the MULTIEDIT widget.
`Id`	ID of the MULTIEDIT widget.
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 in the chapter *The Window Manager (WM)* on page 781 for a list of available parameter values).
`ExFlags`	See *MULTIEDIT create flags* on page 1758.
`pText`	Text to be used.
`MaxLen`	Maximum number of bytes for text and prompt.
`s`	Pointer to a `NULL` terminated text to be added.

Return value

Handle of the created MULTIEDIT widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.4 MULTIEDIT_CreateEx()

Description

Creates a MULTIEDIT widget of a specified size at a specified location.

Prototype

```
MULTIEDIT_HANDLE MULTIEDIT_CreateEx(      int       x0,
                                          int       y0,
                                          int       xSize,
                                          int       ySize,
                                          WM_HWIN   hParent,
                                          int       WinFlags,
                                          int       ExFlags,
                                          int       Id,
                                          int       BufferSize,
                                    const char    * pText);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new MULTIEDIT widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *MULTIEDIT create flags* on page 1758.
Id	Window ID of the widget.
BufferSize	Initial text buffer size of the widget. Use MULTIEDIT_SetMaxNumChars() to set the maximum number of characters.
pText	Text to be used.

Return value

Handle of the created MULTIEDIT widget; 0 if the function fails.

Additional information

If the text set for the MULTIEDIT widget exceeds the number of bytes allocated at creation (BufferSize) the widget increases the buffer automatically. To avoid this the user can call MULTIEDIT_SetMaxNumChars().

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.5 MULTIEDIT_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Para` of the according `GUI_WIDGET_CREATE_INFO` structure is used according to the parameter `BufferSize` of the function `MULTIEDIT_CreateEx()`. The element Flags is used according to the parameter `ExFlags` of the function `MULTIEDIT_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.6 MULTIEDIT_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `MULTIEDIT_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.7 MULTIEDIT_EnableBlink()

Description

Enables/disables a blinking cursor.

Prototype

```
void MULTIEDIT_EnableBlink(MULTIEDIT_HANDLE hObj,
                           int              Period,
                           int              OnOff);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
Period	Blinking period
OnOff	1 enables blinking, 0 disables blinking

Additional information

This function calls `GUI_X_GetTime()`.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.8 MULTIEDIT_GetBkColor()

Description

Returns the background color of the widget.

Prototype

```
GUI_COLOR MULTIEDIT_GetBkColor(MULTIEDIT_HANDLE hObj,
                               unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
Index	See *MULTIEDIT color indexes* on page 1757 for a full list of permitted values.

Additional information

This function calls `GUI_X_GetTime()`.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.9 MULTIEDIT_GetCursorCharPos()

Description

Returns the number of the character at the cursor position.

Prototype

```
int MULTIEDIT_GetCursorCharPos(MULTIEDIT_HANDLE hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.

Return value

Number of the character at the cursor position.

Additional information

The widget returns the character position if it has the focus or not. This means the cursor position is also returned, if the cursor is currently not visible in the widget.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.10 MULTIEDIT_GetCursorPixelPos()

Description

Returns the pixel position of the cursor in window coordinates.

Prototype

```
void MULTIEDIT_GetCursorPixelPos(MULTIEDIT_HANDLE   hObj,
                                 int              * pxPos,
                                 int              * pyPos);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
pxPos	Pointer to integer variable for the X-position in window coordinates.
pyPos	Pointer to integer variable for the Y-position in window coordinates.

Additional information

The widget returns the pixel position if it has the focus or not. This means the cursor position is also returned, if the cursor is currently not visible in the widget.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.11 MULTIEDIT_GetFont()

Description

Returns the font of the widget.

Prototype

```
GUI_FONT *MULTIEDIT_GetFont(MULTIEDIT_HANDLE hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.

Return value

Pointer to the font of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.12 MULTIEDIT_GetNumChars()

Description

Returns the number of characters of the MULTIEDIT widget.

Prototype

```
int MULTIEDIT_GetNumChars(MULTIEDIT_HANDLE hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.

Return value

Number of characters present in the specified MULTIEDIT widget.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.13 MULTIEDIT_GetPrompt()

Description

Returns the current prompt text.

Prototype

```
void MULTIEDIT_GetPrompt(MULTIEDIT_HANDLE   hObj,
                         char             * sDest,
                         int                MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
sDest	Buffer for the prompt text to be returned.
MaxLen	Maximum number of bytes to be copied to sDest.

Additional information

The function copies the current prompt text to the buffer given by sDest. The maximum number of bytes copied to the buffer is given by MaxLen.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.14 MULTIEDIT_GetText()

Description

Returns the current text.

Prototype

```
void MULTIEDIT_GetText(MULTIEDIT_HANDLE   hObj,
                       char             * sDest,
                       int                MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
sDest	Buffer for the text to be returned.
MaxLen	Maximum number of bytes to be copied to sDest.

Additional information

The function copies the current text to the buffer given by sDest. The maximum number of bytes copied to the buffer is given by MaxLen.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.15 MULTIEDIT_GetTextColor()

Description

Returns the text color of the widget.

Prototype

```
GUI_COLOR MULTIEDIT_GetTextColor(MULTIEDIT_HANDLE hObj,
                                 unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
Index	See *MULTIEDIT color indexes* on page 1757 for a full list of permitted values.

Return value

The text color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.16 MULTIEDIT_GetTextFromLine()

Description

Returns the text of a given line from a given start character.

Prototype

```
int MULTIEDIT_GetTextFromLine(MULTIEDIT_HANDLE   hObj,
                              char             * sDest,
                              int                MaxLen,
                              unsigned           CharPos,
                              unsigned           Line);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
sDest	Pointer to buffer.
MaxLen	Size of buffer.
CharPos	Zero-based character position from which the text should be copied.
Line	Zero-based line number.

Return value

Number of bytes copied. -1 on error.

Additional information

Line numbers are ambiguous when using any type of wrap mode, therefore a new line is considered after a line feed character.
The text from the line is returned without any carriage return nor line feed characters at the end.

Example

```
hWin = MULTIEDIT_CreateEx(10, 10, 200, 200, WM_HBKWIN, WM_CF_SHOW, 0, GUI_ID_MULTIEDIT0, 256,
                          "Line 0.\nLine 1.\nLine 2.\nLine 3.\nLine 4.");
MULTIEDIT_GetTextFromLine(hWin, acBuffer, sizeof(acBuffer), 0, 2); // "Line 2."
MULTIEDIT_GetTextFromLine(hWin, acBuffer, sizeof(acBuffer), 1, 4); // "ine 4."
```

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.17 MULTIEDIT_GetTextFromPos()

Description

Returns the text from a start and end point. The start and end points are each specified by line number and character number, both being zero-based.

Prototype

```
int MULTIEDIT_GetTextFromPos(MULTIEDIT_HANDLE   hObj,
                             char             * sDest,
                             int                MaxLen,
                             int                CharStart,
                             int                LineStart,
                             int                CharEnd,
                             int                LineEnd);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
sDest	Pointer to buffer.
MaxLen	Size of buffer.
CharStart	Zero-based start character in the start line.
LineStart	Zero-based start line.
CharEnd	Zero-based end character in the end line. -1 equals to the last char of the line.
LineEnd	Zero-based end line. -1 equals to the last line.

Return value

Number of bytes copied. -1 on error.

Additional information

Line numbers are ambiguous when using any type of wrap mode, therefore a new line is considered after a line feed character.
When one of the four parameters CharStart, LineStart, CharEnd or LineEnd is invalid (e.g. when the entered char/line position is too high), the function either skips to the next line or returns an error.

Example

```
hWin = MULTIEDIT_CreateEx(10, 10, 200, 200, WM_HBKWIN, WM_CF_SHOW, 0, GUI_ID_MULTIEDIT0, 256,
                          "Line 0.\nLine 1.\nLine 2.\nLine 3.\nLine 4.");

MULTIEDIT_GetTextFromPos(hWin, acBuffer, sizeof(acBuffer), 3, 1, 0, 3);
// "e 1.\nLine 2.\n"

MULTIEDIT_GetTextFromPos(hWin, acBuffer, sizeof(acBuffer), 0, 0, -1, 3);
// "Line 0.\nLine 1.\nLine 2.\nLine 3."

MULTIEDIT_GetTextFromPos(hWin, acBuffer, sizeof(acBuffer), 0, 0, 0, -1);
// "Line 0.\nLine 1.\nLine 2.\nLine 3.\n"
```

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.18 MULTIEDIT_GetTextSize()

Description

Returns the buffer size used to store the current text (and prompt).

Prototype

```
int MULTIEDIT_GetTextSize(MULTIEDIT_HANDLE hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.

Return value

Buffer size used to store the current text (and prompt).

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.19 MULTIEDIT_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.20 MULTIEDIT_SetAutoScrollH()

Description

Enables/disables the automatic use of a horizontal scroll bar.

Prototype

```
void MULTIEDIT_SetAutoScrollH(MULTIEDIT_HANDLE hObj,
                              int              OnOff);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
OnOff	1 for enabling automatic use of a horizontal scroll bar, 0 for disabling.

Additional information

Enabling the use of a automatic horizontal scroll bar only makes sense with the non wrapping mode explained later in this chapter. If enabled the MULTIEDIT widget checks if the width of the non wrapped text fits into the client area. If not a horizontal scroll bar will be attached to the window.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.21 MULTIEDIT_SetAutoScrollV()

Description

Enables/disables the automatic use of a vertical scroll bar.

Prototype

```
void MULTIEDIT_SetAutoScrollV(MULTIEDIT_HANDLE hObj,
                              int              OnOff);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
OnOff	1 for enabling automatic use of a vertical scroll bar, 0 for disabling.

Additional information

If enabled the MULTIEDIT widget checks if the height of the text fits into the client area. If not a vertical scroll bar will be attached to the window.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.22 MULTIEDIT_SetBkColor()

Description

Sets the background color of the given MULTIEDIT widget.

Prototype

```
void MULTIEDIT_SetBkColor(MULTIEDIT_HANDLE hObj,
                          unsigned         Index,
                          GUI_COLOR        color);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
Index	See *MULTIEDIT color indexes* on page 1757 for a full list of permitted values.
Color	Background color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.23 MULTIEDIT_SetBufferSize()

Description

Sets the maximum number of bytes used by text and prompt.

Prototype

```
void MULTIEDIT_SetBufferSize(MULTIEDIT_HANDLE hObj,
                             int              BufferSize);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
BufferSize	Maximum number of bytes.

Additional information

The function clears the current content of the MULTIEDIT widget and allocates the given number of bytes for the text and for the prompt.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.24 MULTIEDIT_SetCursorCharPos()

Description

This function sets the cursor to the given position where x is the character in a line and y is line. 0, 0 is the very first character. 0, 1 would be the the first character of the second line and so on.

Prototype

```
void MULTIEDIT_SetCursorCharPos(MULTIEDIT_HANDLE hObj,
                                int              x,
                                int              y);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
x	X - Character position of the line.
y	Y - Index of line.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.25 MULTIEDIT_SetCursorOffset()

Description

Sets the cursor position to the given character.

Prototype

```
void MULTIEDIT_SetCursorOffset(MULTIEDIT_HANDLE hObj,
                               int              Offset);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
Offset	New cursor position.

Additional information

The number of characters used for the prompt has to be added to the parameter Offset. If a prompt is used the value for parameter Offset should not be smaller than the number of characters used for the prompt.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.26 MULTIEDIT_SetCursorPixelPos()

Description

This function sets the cursor to the given position, where x and y are the coordinates in pixels relative to the widget.

Prototype

```
void MULTIEDIT_SetCursorPixelPos(MULTIEDIT_HANDLE hObj,
                                 int              x,
                                 int              y);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
xPos	Y position in pixels.
xPos	Y position in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.27 MULTIEDIT_SetFocusable()

Description

Sets the focusability of the given MULTIEDIT widget.

Prototype

```
void MULTIEDIT_SetFocusable(MULTIEDIT_HANDLE hObj,
                            int              State);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
OnOff	1 for enabling focusability, 0 for disabling.

Additional information

The text can not be aligned to the center if the widget is focusable. To change text alignment, the function `MULTIEDIT_SetTextAlign()` can be used.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.28 MULTIEDIT_SetFont()

Description

Sets the font used to display the text and the prompt.

Prototype

```
void MULTIEDIT_SetFont(      MULTIEDIT_HANDLE   hObj,
                       const GUI_FONT         * pFont);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
pFont	Pointer to font to be used.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.29 MULTIEDIT_SetHBorder()

Description

Sets the size of the border between the text and the widget in horizontal direction.

Prototype

```
void MULTIEDIT_SetHBorder(MULTIEDIT_HANDLE hObj,
                          unsigned         HBorder);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
HBorder	Size of the border in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.30 MULTIEDIT_SetInsertMode()

Description

Enables/disables the insert mode. The default behaviour is overwrite mode.

Prototype

```
void MULTIEDIT_SetInsertMode(MULTIEDIT_HANDLE hObj,
                             int              OnOff);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
OnOff	1 for enabling insert mode, 0 for disabling.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.31 MULTIEDIT_SetMaxNumChars()

Description

Sets the maximum number of characters used by text and prompt.

Prototype

```
void MULTIEDIT_SetMaxNumChars(MULTIEDIT_HANDLE hObj,
                              unsigned         MaxNumChars);
```

Parameters

Parameter	Description
hObj	Handle of the MULTIEDIT widget.
MaxNumChars	Maximum number of characters.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.32 MULTIEDIT_SetPasswordMode()

Description

Enables/disables the password mode.

Prototype

```
void MULTIEDIT_SetPasswordMode(MULTIEDIT_HANDLE hObj,
                               int              OnOff);
```

Parameters

Parameter	Description
hObj	Handle of the MULTIEDIT widget.
OnOff	1 for enabling password mode, 0 for disabling.

Additional information

The password mode enables you to conceal the user input.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.33 MULTIEDIT_SetPrompt()

Description

Sets the prompt text.

Prototype

```
void MULTIEDIT_SetPrompt(      MULTIEDIT_HANDLE   hObj,
                         const char             * pPrompt);
```

Parameters

Parameter	Description
hObj	Handle of the MULTIEDIT widget.
sPrompt	Pointer to the new prompt text.

Additional information

The prompt text is displayed first. The cursor can not be moved into the prompt.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.34 MULTIEDIT_SetReadOnly()

Description

Enables/disables the read only mode.

Prototype

```
void MULTIEDIT_SetReadOnly(MULTIEDIT_HANDLE hObj,
                           int              OnOff);
```

Parameters

Parameter	Description
hObj	Handle of the MULTIEDIT widget.
OnOff	1 for enabling read-only mode, 0 for disabling.

Additional information

If the read only mode has been set the widget does not change the text. Only the cursor will be moved.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.35 MULTIEDIT_SetText()

Description

Sets the text to be handled by the MULTIEDIT widget.

Prototype

```
void MULTIEDIT_SetText(      MULTIEDIT_HANDLE   hObj,
                       const char             * pNew);
```

Parameters

Parameter	Description
hObj	Handle of the MULTIEDIT widget.
pNew	Pointer to the text to be handled by the MULTIEDIT widget.

Additional information

The function copies the given text to the buffer allocated when creating the widget. The current text can be retrieved by `MULTIEDIT_GetText()`.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.36 MULTIEDIT_SetTextAlign()

Description

Sets the text alignment for the given MULTIEDIT widget.

Prototype

```
void MULTIEDIT_SetTextAlign(MULTIEDIT_HANDLE hObj,
                            int              Align);
```

Parameters

Parameter	Description
hObj	Handle of the MULTIEDIT widget.
Align	See *Text alignment flags* on page 218. **Only horizontal flags are applicable!**

Additional information

The text can not be horizontally centered if the widget is focusable. To change focusability of the widget, the function MULTIEDIT_SetFocusable() can be used.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.37 MULTIEDIT_SetTextColor()

Description

Sets the text color.

Prototype

```
void MULTIEDIT_SetTextColor(MULTIEDIT_HANDLE hObj,
                            unsigned         Index,
                            GUI_COLOR        color);
```

Parameters

Parameter	Description
hObj	Handle of the MULTIEDIT widget.
Index	See *MULTIEDIT color indexes* on page 1757 for a full list of permitted values.
Color	Text color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.38 MULTIEDIT_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.39 MULTIEDIT_SetWrapChar()

Prototype

```
void MULTIEDIT_SetWrapChar(MULTIEDIT_HANDLE hObj);
```

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.40 MULTIEDIT_SetWrapNone()

Description

Enables the non wrapping mode.

Prototype

```
void MULTIEDIT_SetWrapNone(MULTIEDIT_HANDLE hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.

Additional information

’Non wrapping’ means line wrapping would be done only at new lines. If the horizontal size of the text exceeds the size of the client area the text will be scrolled.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.41 MULTIEDIT_SetWrapWord()

Description

Enables the word wrapping mode.

Prototype

```
void MULTIEDIT_SetWrapWord(MULTIEDIT_HANDLE hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.

Additional information

If the word wrapping mode has been set the text at the end of a line will be wrapped at the beginning of the last word (if possible).

 © 2020 SEGGER Microcontroller GmbH

20.20.5.1.42 MULTIEDIT_ShowCursor()

Description

This function enables or disables the cursor of the MULTIEDIT widget.

Prototype

```
int MULTIEDIT_ShowCursor(MULTIEDIT_HANDLE hObj,
                         unsigned         OnOff);
```

Parameters

Parameter	Description
hObj	Handle of MULTIEDIT widget.
OnOff	0 hide cursor, 1 show cursor

Return value

This function returns the previous state of the cursor.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.2 Defines

20.20.5.2.1 MULTIEDIT color indexes

Description

Color indexes used by the MULTIEDIT widget.

Definition

```
#define MULTIEDIT_CI_EDIT        0
#define MULTIEDIT_CI_READONLY    1
```

Symbols

Definition	Description
MULTIEDIT_CI_EDIT	Color in edit mode.
MULTIEDIT_CI_READONLY	Color in read-only mode.

 © 2020 SEGGER Microcontroller GmbH

20.20.5.2.2 MULTIEDIT create flags

Description

Create flags that define the behavior of the FRAMEWIN widget. These flags are OR-combinable and can be specified upon creation of the widget via the ExFlags parameter of MULTIEDIT_CreateEx().

Definition

```
#define MULTIEDIT_CF_READONLY           (1 << 0)
#define MULTIEDIT_CF_INSERT             (1 << 2)
#define MULTIEDIT_CF_AUTOSCROLLBAR_V    (1 << 3)
#define MULTIEDIT_CF_AUTOSCROLLBAR_H    (1 << 4)
#define MULTIEDIT_CF_PASSWORD           (1 << 5)
#define MULTIEDIT_CF_SHOWCURSOR         (1 << 6)
```

Symbols

Definition	Description
MULTIEDIT_CF_READONLY	Enables read only mode.
MULTIEDIT_CF_INSERT	Enables insert mode.
MULTIEDIT_CF_AUTOSCROLLBAR_V	Automatic use of a vertical scroll bar.
MULTIEDIT_CF_AUTOSCROLLBAR_H	Automatic use of a horizontal scroll bar.
MULTIEDIT_CF_PASSWORD	Enables password mode.
MULTIEDIT_CF_SHOWCURSOR	Shows the cursor.

 © 2020 SEGGER Microcontroller GmbH

20.20.6 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_MultiEdit.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with it.

Screenshot of WIDGET_Multiedit.c



 © 2020 SEGGER Microcontroller GmbH

20.21 MULTIPAGE: Multiple page widget

A MULTIPAGE widget is analogous to the dividers in a notebook or the labels in a file cabinet. By using a MULTIPAGE widget, an application can define multiple pages for the same area of a window or dialog box. Each page consists of a certain type of information or a group of widgets that the application displays when the user selects the corresponding page. To select a page the tab of the page has to be clicked. If not all tabs can be displayed, the MULTIPAGE widget automatically shows a small scroll bar at the edge to scroll the pages. The `Sample` folder contains the file `WIDGET_Multipage.c` which shows how to create and use the MULTIPAGE widget.

> **Note**
>
> All MULTIPAGE-related routines are located in the file(s) `MULTIPAGE*.c`, `MULTIPAGE.h`. All identifiers are prefixed MULTIPAGE.

Description	MULTIPAGE widget
MULTIPAGE widget with 3 pages, alignment top/left.	
MULTIPAGE widget with 6 pages, alignment bottom/right.	

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

 © 2020 SEGGER Microcontroller GmbH

Structure of MULTIPAGE widget

A MULTIPAGE widget with n pages consists of n+2 windows:



- 1 MULTIPAGE window
- 1 Client window
- n Page windows

The page windows will be added to the client window of the widget. The diagram at the right side shows the structure of the widget.

20.21.1 Configuration options

Type	Macro	Default	Description
N	MULTIPAGE_ALIGN_DEFAULT	MULTIPAGE_ALIGN_LEFT | MULTIPAGE_ALIGN_TOP	Default alignment.
N	MULTIPAGE_BKCOLOR0_DEFAULT	0xD0D0D0	Default background color of pages in disabled state.
N	MULTIPAGE_BKCOLOR1_DEFAULT	0xC0C0C0	Default background color of pages in enabled state.
S	MULTIPAGE_FONT_DEFAULT	&GUI_Font13_1	Default font used by the widget.
N	MULTIPAGE_TEXTCOLOR0_DEFAULT	0x808080	Default text color of pages in disabled state.
N	MULTIPAGE_TEXTCOLOR1_DEFAULT	0x000000	Default text color of pages in enabled state.

20.21.2 Predefined IDs

The following symbols define IDs which may be used to make MULTIPAGE widgets distinguishable from creation.

```
#define GUI_ID_MULTIPAGE0    0x230
#define GUI_ID_MULTIPAGE1    0x231
#define GUI_ID_MULTIPAGE2    0x232
#define GUI_ID_MULTIPAGE3    0x233
#define GUI_ID_MULTIPAGE4    0x234
#define GUI_ID_MULTIPAGE5    0x235
#define GUI_ID_MULTIPAGE6    0x236
#define GUI_ID_MULTIPAGE7    0x237
#define GUI_ID_MULTIPAGE8    0x238
#define GUI_ID_MULTIPAGE9    0x239
```

20.21.3 Notification codes

The following events are sent from the widget to its parent window as part of a WM_NOTIFY_PARENT message:

 © 2020 SEGGER Microcontroller GmbH

Message	Description
WM_NOTIFICATION_CLICKED	Widget has been clicked.
WM_NOTIFICATION_RELEASED	Widget has been released.
WM_NOTIFICATION_MOVED_OUT	Widget has been clicked and pointer has been moved out of the widget without releasing.
WM_NOTIFICATION_VALUE_CHANGED	The text of the widget has been changed.

20.21.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_PGUP	Switches to the next page.
GUI_KEY_PGDOWN	Switches to the previous page.

20.21.5 MULTIPAGE API

The table below lists the available emWin MULTIPAGE-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
MULTIPAGE_AddEmptyPage()	Adds a page to a MULTIPAGE widget without the requirement to attach a window.
MULTIPAGE_AddPage()	Adds a page to a MULTIPAGE widget.
MULTIPAGE_AttachWindow()	Attaches a window to a certain page of the MULTIPAGE widget.
MULTIPAGE_CreateEx()	Creates a MULTIPAGE widget.
MULTIPAGE_CreateIndirect()	Creates a MULTIPAGE widget from a resource table entry.
MULTIPAGE_CreateUser()	Creates a MULTIPAGE widget using extra bytes as user data.
MULTIPAGE_DeletePage()	Deletes a page from a MULTIPAGE widget.
MULTIPAGE_DisablePage()	Disables a page from a MULTIPAGE widget.
MULTIPAGE_EnablePage()	Enables a page from a MULTIPAGE widget.
MULTIPAGE_EnableScrollbar()	Configures the given MULTIPAGE widget to make use of an automatic scroll bar.
MULTIPAGE_GetBkColor()	Returns the background color.
MULTIPAGE_GetDefaultAlign()	Returns the default tab alignment for new MULTIPAGE widgets.
MULTIPAGE_GetDefaultBkColor()	Returns the default background color for new MULTIPAGE widgets.
MULTIPAGE_GetDefaultFont()	Returns a pointer to the font used to display the text in the tabs of new MULTIPAGE widgets.
MULTIPAGE_GetDefaultTextColor()	Returns the default text color used to display the text in the tabs of new MULTIPAGE widgets.
MULTIPAGE_GetFont()	Returns the font of the widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
MULTIPAGE_GetNumTabs()	Returns the number of all tabs in a MULTIPAGE widget.
MULTIPAGE_GetPageText()	Returns the text of the given page.
MULTIPAGE_GetSelection()	Returns the current selection.
MULTIPAGE_GetTabHeight()	Returns the height for all tabs.
MULTIPAGE_GetTabWidth()	Returns the width for the given tab.
MULTIPAGE_GetTextColor()	Returns the text color of the widget.
MULTIPAGE_GetUserData()	Retrieves the data set with MULTIPAGE_SetUserData().
MULTIPAGE_GetWindow()	Returns the handle of the window displayed in the given page.
MULTIPAGE_IsPageEnabled()	Returns if the given page of a MULTIEDIT widget is enabled or not.
MULTIPAGE_SelectPage()	Sets the currently selected page of a MULTIPAGE widget.
MULTIPAGE_SetAlign()	Sets the alignment for the tabs.
MULTIPAGE_SetBitmap()	Sets a bitmap to be displayed on the given tab.
MULTIPAGE_SetBitmapEx()	Sets a bitmap to be displayed at the specified position on the given tab.
MULTIPAGE_SetBkColor()	Sets the background color of the given MULTIPAGE widget.
MULTIPAGE_SetDefaultAlign()	Sets the default tab alignment for new MULTIPAGE widgets.
MULTIPAGE_SetDefaultBkColor()	Sets the default background color used for new MULTIPAGE widgets.
MULTIPAGE_SetDefaultBorderSizeX()	Sets the default border size on the x-axis.
MULTIPAGE_SetDefaultBorderSizeY()	Sets the default border size on the y-axis.
MULTIPAGE_SetDefaultFont()	Sets the default font used by new MULTIPAGE widgets.
MULTIPAGE_SetDefaultTextColor()	Sets the default text color used by new MULTIPAGE widgets.
MULTIPAGE_SetFont()	Selects the font for the widget.
MULTIPAGE_SetRotation()	Sets the rotation mode of the given widget.
MULTIPAGE_SetTabHeight()	Sets the height for all tabs.
MULTIPAGE_SetTabWidth()	Sets the width for the given tab.
MULTIPAGE_SetText()	Sets the text displayed in the tab of a given page.
MULTIPAGE_SetTextAlign()	Sets the text alignment for the given MULTIPAGE widget.
MULTIPAGE_SetTextColor()	Sets the text color.
MULTIPAGE_SetUserData()	Sets the extra data of a MULTIPAGE widget.

Defines

Group of defines	Description
MULTIPAGE alignment flags	Alignment flags used by MULTIPAGE_SetAlign().

 © 2020 SEGGER Microcontroller GmbH

Group of defines	Description
MULTIPAGE bitmap indexes	Bitmap indexes used by the MULTIPAGE widget.
MULTIPAGE color indexes	Color indexes used by the MULTIPAGE widget.
MULTIPAGE create flags	Create flags used by the MULTIPAGE widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1 Functions

20.21.5.1.1 MULTIPAGE_AddEmptyPage()

Before	After
	

Description

Adds a new page to a given MULTIPAGE widget.

Prototype

```
void MULTIPAGE_AddEmptyPage(      MULTIPAGE_Handle   hObj,
                                  WM_HWIN            hWin,
                            const char             * pText);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
hWin	Handle of window to be shown in the given page.
pText	Pointer to text to be displayed in the tab of the page.

Additional information

It is recommended, that all windows added to a MULTIPAGE widget handle the complete client area of the MULTIPAGE widget when processing the WM_PAINT message. If no window has to be added, hWin can be specified with 0.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.2 MULTIPAGE_AddPage()

Before	After
	

Description

Adds a new page to a given MULTIPAGE widget.

Prototype

```
void MULTIPAGE_AddPage(      MULTIPAGE_Handle   hObj,
                             WM_HWIN            hWin,
                       const char             * pText);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
hWin	Handle of window to be shown in the given page.
pText	Pointer to text to be displayed in the tab of the page.

Additional information

It is recommended, that all windows added to a MULTIPAGE widget handle the complete client area of the MULTIPAGE widget when processing the WM_PAINT message.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.3 MULTIPAGE_AttachWindow()

Description

Attaches a window to a certain page of the MULTIPAGE widget.

Prototype

```
WM_HWIN MULTIPAGE_AttachWindow(MULTIPAGE_Handle hObj,
                               unsigned         Index,
                               WM_HWIN          hWin);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	Index of the page the window has to be added to.
pText	Pointer to text to be displayed in the tab of the page.

Additional information

It is recommended, that all windows added to a MULTIPAGE widget handle the complete client area of the MULTIPAGE widget when processing the WM_PAINT message.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.4 MULTIPAGE_CreateEx()

Description

Creates a MULTIPAGE widget of a specified size at a specified position.

Prototype

```
MULTIPAGE_Handle MULTIPAGE_CreateEx(int     x0,
                                    int     y0,
                                    int     xSize,
                                    int     ySize,
                                    WM_HWIN hParent,
                                    int     WinFlags,
                                    int     ExFlags,
                                    int     Id);
```

Parameters

Parameter	Description
x0	X-position of the MULTIPAGE widget (in parent coordinates).
y0	Y-position of the MULTIPAGE widget (in parent coordinates).
xSize	Horizontal size of the MULTIPAGE widget (in pixels).
ySize	Vertical size of the MULTIPAGE widget (in pixels).
hParent	Handle of parent window. If 0, the new widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used yet, reserved for future use.
Id	Window ID of the MULTIPAGE widget.

Return value

Handle of the new MULTIPAGE widget.

Additional information

The size of the tabs depends on the size of the font used for the MULTIPAGE widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.5 MULTIPAGE_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element Para of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element Flags is used according to the parameter ExFlags of the function `MULTIPAGE_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.6 MULTIPAGE_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `MULTIPAGE_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.7 MULTIPAGE_DeletePage()

Before	After
	

Description

Removes a page from a MULTIPAGE widget and optional deletes the window.

Prototype

```
void MULTIPAGE_DeletePage(MULTIPAGE_Handle hObj,
                          unsigned         Index,
                          int              Delete);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	Zero based index of the page to be removed from the MULTIPAGE widget.
Delete	If >0 the window attached to the page will be deleted.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.8 MULTIPAGE_DisablePage()

Before	After
	

Description

Disables a page from a MULTIPAGE widget.

Prototype

```
void MULTIPAGE_DisablePage(MULTIPAGE_Handle hObj,
                           unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	Zero based index of the page to be disabled.

Additional information

A disabled page of a window can not be selected by clicking the tab of the page. The default state of MULTIEDIT pages is ’enabled’.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.9 MULTIPAGE_EnablePage()

Before	After
	

Description

Enables a page of a MULTIPAGE widget.

Prototype

```
void MULTIPAGE_EnablePage(MULTIPAGE_Handle hObj,
                          unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.

Additional information

The default state of MULTIEDIT pages is ’enabled’.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.10 MULTIPAGE_EnableScrollbar()

With scrollbar	Without scrollbar
	

Description

Configures the given MULTIPAGE widget to make use of an automatic scroll bar.

Prototype

```
void MULTIPAGE_EnableScrollbar(MULTIPAGE_Handle hObj,
                               unsigned         OnOff);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
OnOff	1 = Enable automatic scroll bar. 0 = Disable automatic scroll bar.

Additional information

Calling this function takes effect only before the first page has been added to the widget. The automatic scroll bar is enabled by default.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.11 MULTIPAGE_GetBkColor()

Description

Returns the background color of the widget.

Prototype

```
GUI_COLOR MULTIPAGE_GetBkColor(MULTIPAGE_Handle hObj,
                               unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	See *MULTIPAGE color indexes* on page 1811 for a full list of permitted values.

Return value

The background color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.12 MULTIPAGE_GetDefaultAlign()

Description

Returns the default tab alignment for new MULTIPAGE widgets.

Prototype

```
unsigned MULTIPAGE_GetDefaultAlign(void);
```

Return value

Default tab alignment for new MULTIPAGE widgets.

Additional information

The following table shows the alignment values returned by this function:

Alignment	Appearance of MULTIPAGE widget
MULTIPAGE_ALIGN_LEFT | MULTIPAGE_ALIGN_TOP	
MULTIPAGE_ALIGN_RIGHT | MULTIPAGE_ALIGN_TOP	
MULTIPAGE_ALIGN_LEFT | MULTIPAGE_ALIGN_BOTTOM	
MULTIPAGE_ALIGN_RIGHT | MULTIPAGE_ALIGN_BOTTOM	

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.13 MULTIPAGE_GetDefaultBkColor()

Description

Returns the default background color for new MULTIPAGE widgets.

Prototype

```
GUI_COLOR MULTIPAGE_GetDefaultBkColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *MULTIPAGE color indexes* on page 1811 for a full list of permitted values.

Return value

Default background color for new MULTIPAGE widgets.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.14 MULTIPAGE_GetDefaultFont()

Description

Returns a pointer to the font used to display the text in the tabs of new MULTIPAGE widgets.

Prototype

```
GUI_FONT *MULTIPAGE_GetDefaultFont(void);
```

Return value

Pointer to the font used to display the text in the tabs of new MULTIPAGE widgets.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.15 MULTIPAGE_GetDefaultTextColor()

Description

Returns the default text color used to display the text in the tabs of new MULTIPAGE widgets.

Prototype

```
GUI_COLOR MULTIPAGE_GetDefaultTextColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *MULTIPAGE color indexes* on page 1811 for a full list of permitted values.

Return value

Default text color used to display the text in the tabs of new MULTIPAGE widgets.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.16 MULTIPAGE_GetFont()

Description

Returns the font of the widget.

Prototype

```
GUI_FONT *MULTIPAGE_GetFont(MULTIPAGE_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.

Return value

A pointer to the font of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.17 MULTIPAGE_GetNumTabs()

Description

Returns the number of all tabs in a MULTIPAGE widget.

Prototype

```
int MULTIPAGE_GetNumTabs(MULTIPAGE_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.

Return value

Number of all tabs in a MULTIPAGE widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.18 MULTIPAGE_GetPageText()

Description

Returns the text of the given page.

Prototype

```
int MULTIPAGE_GetPageText(MULTIPAGE_Handle   hObj,
                          unsigned           Index,
                          char             * pBuffer,
                          int                MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	Index of the page.
pBuffer	User defined buffer which is filled with the page text.
MaxLen	Maximum length of the text to be copied.

Return value

Length of the copied text.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.19 MULTIPAGE_GetSelection()

Description

Returns the zero based index of the currently selected page of a MULTIPAGE widget.

Prototype

```
int MULTIPAGE_GetSelection(MULTIPAGE_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.

Return value

Zero-based index of the currently selected page of a MULTIPAGE widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.20 MULTIPAGE_GetTabHeight()

Description

Returns the height for all tabs.

Prototype

```
int MULTIPAGE_GetTabHeight(MULTIPAGE_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.

Return value

Height for all tabs in a MULTIPAGE widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.21 MULTIPAGE_GetTabWidth()

Description

Returns the width for the given tab.

Prototype

```
int MULTIPAGE_GetTabWidth(MULTIPAGE_Handle hObj,
                          int              Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	Index of the tab.

Return value

Width of a specific tab in a MULTIPAGE widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.22 MULTIPAGE_GetTextColor()

Description

Returns the text color of the widget.

Prototype

```
GUI_COLOR MULTIPAGE_GetTextColor(MULTIPAGE_Handle hObj,
                                 unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	See *MULTIPAGE color indexes* on page 1811 for a full list of permitted values.

Return value

The text color of the given widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.23 MULTIPAGE_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.24 MULTIPAGE_GetWindow()

Description

Returns the handle of the window displayed in the given page.

Prototype

```
WM_HWIN MULTIPAGE_GetWindow(MULTIPAGE_Handle hObj,
                            unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	Zero-based index of page.

Return value

Handle of the window displayed in the given page.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.25 MULTIPAGE_IsPageEnabled()

Description

Returns if the given page of a MULTIEDIT widget is enabled or not.

Prototype

```
int MULTIPAGE_IsPageEnabled(MULTIPAGE_Handle hObj,
                            unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	Zero-based index of requested page.

Return value

1 if the given page is enabled.
0 if the given page is disabled.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.26 MULTIPAGE_SelectPage()

Before	After
	

Description

Sets the currently selected page of a MULTIPAGE widget.

Prototype

```
void MULTIPAGE_SelectPage(MULTIPAGE_Handle hObj,
                          unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Index	Zero-based index of page to be selected.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.27 MULTIPAGE_SetAlign()

Before	After
	

Description

Sets the tab alignment for the given MULTIPAGE widget.

Prototype

```
void MULTIPAGE_SetAlign(MULTIPAGE_Handle hObj,
                        unsigned         Align);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Align	See *MULTIPAGE alignment flags* on page 1809 for a full list of permitted values.

Additional information

For more information, refer to `MULTIPAGE_GetDefaultAlign()`.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.28 MULTIPAGE_SetBitmap()

Before	After
	

Description

Sets a bitmap to be displayed on the given tab. The bitmap is horizontally and vertically aligned to the center of the tab.

Prototype

```
int MULTIPAGE_SetBitmap(      MULTIPAGE_Handle   hObj,
                        const GUI_BITMAP       * pBitmap,
                              int                Index,
                              int                State);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
pBitmap	Pointer to the bitmap to be used for the given tab.
Index	Index of the tab.
State	State of the tab for which the bitmap has to be used. See *MULTIPAGE bitmap indexes* on page 1810 for a full list of permitted values.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.29 MULTIPAGE_SetBitmapEx()

Before	After
	

Description

Sets a bitmap to be displayed on the given tab adjusting the position from the center to the right, left, top and bottom according to the x and y values.

Prototype

```
int MULTIPAGE_SetBitmapEx(      MULTIPAGE_Handle   hObj,
                          const GUI_BITMAP       * pBitmap,
                                int                x,
                                int                y,
                                int                Index,
                                int                State);
```

Parameters

Parameter	Description
hObj	Handle of the MULTIPAGE widget.
pBitmap	Pointer to the bitmap to be used for the given tab.
x	Adjustment value for the x position of the bitmap. 0 means horizontally centered.
y	Adjustment value for the y position of the bitmap. 0 means vertically centered.
Index	Index of the tab.
State	State of the tab for which the bitmap has to be used. See *MULTIPAGE bitmap indexes* on page 1810 for a full list of permitted values.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.30 MULTIPAGE_SetBkColor()

Before	After
	

Description

Sets the background color of the given MULTIPAGE widget.

Prototype

```
void MULTIPAGE_SetBkColor(MULTIPAGE_Handle hObj,
                          GUI_COLOR        Color,
                          unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Color	Color to be used.
Index	See *MULTIPAGE color indexes* on page 1811 for a full list of permitted values.

Additional information

The function only sets the background color for the MULTIPAGE widget. The child windows added to the widget are not affected. That means if the complete client area is drawn by windows added to the widget, only the background color of the tabs changes.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.31 MULTIPAGE_SetDefaultAlign()

Description

Sets the default tab alignment for new MULTIPAGE widgets.

Prototype

```
void MULTIPAGE_SetDefaultAlign(unsigned Align);
```

Parameters

Parameter	Description
Align	Tab alignment used for new MULTIPAGE widgets.

Additional information

For more information about the tab alignment, refer to `MULTIPAGE_GetDefaultAlign()` and `MULTIPAGE_SetAlign()`.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.32 MULTIPAGE_SetDefaultBkColor()

Description

Sets the default background color used for new MULTIPAGE widgets.

Prototype

```
void MULTIPAGE_SetDefaultBkColor(GUI_COLOR Color,
                                 unsigned  Index);
```

Parameters

Parameter	Description
Color	Color to be used.
Index	See *MULTIPAGE color indexes* on page 1811 for a full list of permitted values.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.33 MULTIPAGE_SetDefaultBorderSizeX()

Description

Sets the default border size on the x-axis.

Prototype

```
void MULTIPAGE_SetDefaultBorderSizeX(unsigned Size);
```

Parameters

Parameter	Description
Size	Border size to be used.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.34 MULTIPAGE_SetDefaultBorderSizeY()

Description

Sets the default border size on the y-axis.

Prototype

```
void MULTIPAGE_SetDefaultBorderSizeY(unsigned Size);
```

Parameters

Parameter	Description
Size	Border size to be used.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.35 MULTIPAGE_SetDefaultFont()

Description

Sets the default font used to display the text in the tabs of new MULTIPAGE widgets.

Prototype

```
void MULTIPAGE_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to GUI_FONT structure to be used.

Additional information

The horizontal and vertical size of the tabs depends on the size of the used font.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.36 MULTIPAGE_SetDefaultTextColor()

Description

Sets the default text color used to display the text in the tabs of new MULTIPAGE widgets.

Prototype

```
void MULTIPAGE_SetDefaultTextColor(GUI_COLOR Color,
                                   unsigned  Index);
```

Parameters

Parameter	Description
Color	Color to be used.
Index	See *MULTIPAGE color indexes* on page 1811 for a full list of permitted values.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.37 MULTIPAGE_SetFont()

Before	After
	

Description

Sets the font used to display the text in the tabs of a given MULTIPAGE widget.

Prototype

```
void MULTIPAGE_SetFont(      MULTIPAGE_Handle   hObj,
                       const GUI_FONT         * pFont);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
pFont	Pointer to GUI_FONT structure used to display the text in the tabs.

Additional information

The vertical and horizontal size of the tabs depend on the size of the used font and the text shown in the tabs.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.38 MULTIPAGE_SetRotation()

Before	After
	

Description

Sets the rotation mode of the given widget.

Prototype

```
void MULTIPAGE_SetRotation(MULTIPAGE_Handle hObj,
                           unsigned         Rotation);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Rotation	Rotation mode. See *MULTIPAGE create flags* on page 1812.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.39 MULTIPAGE_SetTabHeight()

Before	After
	

Description

Sets the height for all tabs.

Prototype

```
void MULTIPAGE_SetTabHeight(MULTIPAGE_Handle hObj,
                            int              Height);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Height	Height to be set.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.40 MULTIPAGE_SetTabWidth()

Before	After
	

Description

Sets the width for the given tab.

Prototype

```
void MULTIPAGE_SetTabWidth(MULTIPAGE_Handle hObj,
                           int              Width,
                           int              Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Width	Width to be set.
Index	Index of the tab.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.41 MULTIPAGE_SetText()

Before	After
	

Description

Sets the text displayed in the tab of a given page.

Prototype

```
void MULTIPAGE_SetText(      MULTIPAGE_Handle   hObj,
                       const char             * s,
                             unsigned           Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
pText	Pointer to the text to be displayed.
Index	Zero based index of the page.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.42 MULTIPAGE_SetTextAlign()

Before	After
	

Description

Sets the text alignment for the given MULTIPAGE widget.

Prototype

```
void MULTIPAGE_SetTextAlign(MULTIPAGE_Handle hObj,
                            unsigned         Align);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Align	Text alignment. See table below.

Additional information

Setting the text alignment can have a visual impact only in case the tab width was changed. Otherwise the width is set according to the width of the text.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.43 MULTIPAGE_SetTextColor()

Before	After
	

Description

Sets the color used to display the text in the tabs of a MULTIPAGE widget.

Prototype

```
void MULTIPAGE_SetTextColor(MULTIPAGE_Handle hObj,
                            GUI_COLOR        Color,
                            unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of MULTIPAGE widget.
Color	Color to be used.
Index	See *MULTIPAGE color indexes* on page 1811 for a full list of permitted values.

Additional information

Setting the text alignment can have a visual impact only in case the tab width was changed. Otherwise the width is set according to the width of the text.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.1.44 MULTIPAGE_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.2 Defines

20.21.5.2.1 MULTIPAGE alignment flags

Description

These flags are used by `MULTIPAGE_SetAlign()` and define the tab alignment of a MULTIPAGE widget. Horizontal and vertical flags are OR-combinable.

Definition

```
#define MULTIPAGE_ALIGN_LEFT      (0 << 0)
#define MULTIPAGE_ALIGN_RIGHT     (1 << 0)
#define MULTIPAGE_ALIGN_TOP       (0 << 2)
#define MULTIPAGE_ALIGN_BOTTOM    (1 << 2)
```

Symbols

Definition	Description
MULTIPAGE_ALIGN_LEFT	Aligns the tabs at the left side.
MULTIPAGE_ALIGN_RIGHT	Aligns the tabs at the right side.
MULTIPAGE_ALIGN_TOP	Aligns the tabs at the top of the widget.
MULTIPAGE_ALIGN_BOTTOM	Aligns the tabs at the bottom of the widget.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.2.2 MULTIPAGE bitmap indexes

Description

Bitmap indexes used by the MULTIPAGE widget.

Definition

```
#define MULTIPAGE_BI_SELECTED      0
#define MULTIPAGE_BI_UNSELECTED    1
#define MULTIPAGE_BI_DISABLED      2
```

Symbols

Definition	Description
MULTIPAGE_BI_SELECTED	Selected state.
MULTIPAGE_BI_UNSELECTED	Unselected state.
MULTIPAGE_BI_DISABLED	Disabled state.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.2.3 MULTIPAGE color indexes

Description

Color indexes used by the MULTIPAGE widget.

Definition

```
#define MULTIPAGE_CI_DISABLED    0
#define MULTIPAGE_CI_ENABLED     1
```

Symbols

Definition	Description
MULTIPAGE_CI_DISABLED	Color for disabled pages.
MULTIPAGE_CI_ENABLED	Color for enabled pages.

 © 2020 SEGGER Microcontroller GmbH

20.21.5.2.4 MULTIPAGE create flags

Description

Create flags used when creating a MULTIPAGE widget or when using the routine `MULTIPAGE_SetRotation()`.

Definition

```
#define MULTIPAGE_CF_ROTATE_CW    (1 << 3)
```

Symbols

Definition	Description
MULTIPAGE_CF_ROTATE_CW	Arranges the tabs at the vertical side and rotates the tab text by 90 degrees clockwise.

> **Note**
>
> When specifying **0** instead of a flag, the widget is displayed in default horizontal mode.

 © 2020 SEGGER Microcontroller GmbH

20.21.6 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_Multipage.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_Multipage.c



 © 2020 SEGGER Microcontroller GmbH

20.22 PROGBAR: Progress bar widget

PROGBAR widgets are commonly used in applications for visualization; for example, a tank fill-level indicator or an oil-pressure indicator. Example screenshots can be found at the beginning of the chapter and at end of this section.

> **Note**
>
> All PROGBAR-related routines are in the file(s) `PROGBAR*.c`, `PROGBAR.h`.
> All identifiers are prefixed PROGBAR.

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.22.1 Configuration options

Type	Macro	Default	Description
S	PROGBAR_DEFAULT_FONT	`GUI_DEFAULT_FONT`	Font used.
N	PROGBAR_DEFAULT_BARCOLOR0	`0x555555` `(dark gray)`	Left bar color.
N	PROGBAR_DEFAULT_BARCOLOR1	`0xAAAAAA` `(light gray)`	Right bar color.
N	PROGBAR_DEFAULT_TEXTCOLOR0	`0xFFFFFF`	Text color, left bar.
N	PROGBAR_DEFAULT_TEXTCOLOR1	`0x000000`	Text color, right bar.

20.22.2 Predefined IDs

The following symbols define IDs which may be used to make PROGBAR widgets distinguishable from creation.

```
#define GUI_ID_PROGBAR0    0x210
#define GUI_ID_PROGBAR1    0x211
#define GUI_ID_PROGBAR2    0x212
#define GUI_ID_PROGBAR3    0x213
#define GUI_ID_PROGBAR4    0x214
#define GUI_ID_PROGBAR5    0x215
#define GUI_ID_PROGBAR6    0x216
#define GUI_ID_PROGBAR7    0x217
#define GUI_ID_PROGBAR8    0x218
#define GUI_ID_PROGBAR9    0x219
```

20.22.3 Keyboard reaction

The widget can not gain the input focus and does not react on keyboard input.

20.22.4 PROGBAR API

The table below lists the available emWin PROGBAR-related routines in alphabetical order. Detailed descriptions of the routines follow.

 © 2020 SEGGER Microcontroller GmbH

Functions

Routine	Description
PROGBAR_Create()	Creates a PROGBAR widget. (Obsolete)
PROGBAR_CreateAsChild()	Creates a PROGBAR widget as a child window. (Obsolete)
PROGBAR_CreateEx()	Creates a PROGBAR widget.
PROGBAR_CreateIndirect()	Creates a PROGBAR widget from resource table entry.
PROGBAR_CreateUser()	Creates a PROGBAR widget using extra bytes as user data.
PROGBAR_GetBarColor()	Returns the color(s) of the PROGBAR widget.
PROGBAR_GetFont()	Returns the font of the PROGBAR widget.
PROGBAR_GetMinMax()	Returns the minimum and maximum values of the PROGBAR.
PROGBAR_GetTextColor()	Returns the text color(s) of the PROGBAR widget.
PROGBAR_GetUserData()	Retrieves the data set with PROGBAR_SetUserData().
PROGBAR_GetValue()	Returns the current value of the given PROGBAR widget.
PROGBAR_SetBarColor()	Sets the color(s) of the PROGBAR widget.
PROGBAR_SetFont()	Select the font for the text.
PROGBAR_SetMinMax()	Set the minimum and maximum values used for the bar.
PROGBAR_SetText()	Sets the text displayed inside the PROGBAR widget.
PROGBAR_SetTextAlign()	Sets the text alignment.
PROGBAR_SetTextColor()	Sets the text color of the PROGBAR widget.
PROGBAR_SetTextPos()	Sets the text position in pixels.
PROGBAR_SetUserData()	Sets the extra data of a PROGBAR widget.
PROGBAR_SetValue()	Sets the value of the PROGBAR widget.

Defines

Group of defines	Description
PROGBAR create flags	Create flags used by the PROGBAR widget.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1 Functions

20.22.4.1.1 PROGBAR_Create()

> **Note**
>
> This function is **deprecated**, `PROGBAR_CreateEx()` should be used instead.

Description

Creates a PROGBAR widget of a specified size at a specified location.

Prototype

```
PROGBAR_Handle PROGBAR_Create(int x0,
                              int y0,
                              int xSize,
                              int ySize,
                              int Flags);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the PROGBAR widget (in parent coordinates).
`y0`	Topmost pixel of the PROGBAR widget (in parent coordinates).
`xSize`	Horizontal size of the PROGBAR widget (in pixels).
`ySize`	Vertical size of the PROGBAR widget (in pixels).
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).

Return value

Handle of the created PROGBAR widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.2 PROGBAR_CreateAsChild()

> **Note**
>
> This function is **deprecated**, `PROGBAR_CreateEx()` should be used instead.

Description

Creates a PROGBAR widget as a child window.

Prototype

```
PROGBAR_Handle PROGBAR_CreateAsChild(int     x0,
                                     int     y0,
                                     int     xSize,
                                     int     ySize,
                                     WM_HWIN hParent,
                                     int     Id,
                                     int     Flags);
```

Parameters

Parameter	Description
`x0`	X-position of the PROGBAR widget relative to the parent window.
`y0`	Y-position of the PROGBAR widget relative to the parent window.
`xSize`	Horizontal size of the PROGBAR widget (in pixels).
`ySize`	Vertical size of the PROGBAR widget (in pixels).
`hParent`	Handle of parent window.
`Id`	ID to be returned.
`Flags`	Window create flags (see *Window create flags* on page 958).

Return value

Handle of the created PROGBAR widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.3 PROGBAR_CreateEx()

Description

Creates a PROGBAR widget of a specified size at a specified location.

Prototype

```
PROGBAR_Handle PROGBAR_CreateEx(int     x0,
                                int     y0,
                                int     xSize,
                                int     ySize,
                                WM_HWIN hParent,
                                int     WinFlags,
                                int     ExFlags,
                                int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the PROGBAR widget (in parent coordinates).
y0	Topmost pixel of the PROGBAR widget (in parent coordinates).
xSize	Horizontal size of the PROGBAR widget (in pixels).
ySize	Vertical size of the PROGBAR widget (in pixels).
hParent	Handle of parent window. If 0, the new PROGBAR widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *PROGBAR create flags* on page 1836.
Id	Window ID of the PROGBAR widget.

Return value

Handle of the created PROGBAR widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.4 PROGBAR_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element Para of the according GUI_WIDGET_CREATE_INFO structure is not used. The element Flags is used according to the parameter ExFlags of the function PROGBAR_CreateEx().

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.5 PROGBAR_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function PROGBAR_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.6 PROGBAR_GetBarColor()

Description

Returns the color(s) of the PROGBAR widget.

Prototype

```
GUI_COLOR PROGBAR_GetBarColor(PROGBAR_Handle hObj,
                              unsigned int   Index);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
Index	See table below. Other values are not permitted.

Permitted values for parameter Index	
0	Left/lower portion of the PROGBAR widget.
1	Right/upper portion of the PROGBAR widget.

Return value

The color(s) of the PROGBAR widget.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.7 PROGBAR_GetFont()

Description

Returns the font of the PROGBAR widget.

Prototype

```
GUI_FONT *PROGBAR_GetFont(PROGBAR_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.

Return value

The font of the PROGBAR widget.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.8 PROGBAR_GetMinMax()

Description

Copies the minimum value and maximum value of the given PROGBAR widget to the given integer pointers.

Prototype

```
void PROGBAR_GetMinMax(PROGBAR_Handle   hObj,
                       int            * pMin,
                       int            * pMax);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
pMin	Minimum value (Range: -16383 < Min ≤ 16383).
pMax	Maximum value (Range: -16383 < Max ≤ 16383).

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.9 PROGBAR_GetTextColor()

Description

Returns the text color(s) of the PROGBAR widget.

Prototype

```
GUI_COLOR PROGBAR_GetTextColor(PROGBAR_Handle hObj,
                               unsigned int   Index);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
Index	See table below. Other values are not permitted.

Permitted values for parameter Index	
0	Left/lower portion of the text.
1	Right/upper portion of the text.

Return value

The text color(s) of the PROGBAR widget.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.10 PROGBAR_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.11 PROGBAR_GetValue()

Description

Returns the current value of the given PROGBAR widget.

Prototype

```
int PROGBAR_GetValue(PROGBAR_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.

Return value

Current value of the PROGBAR widget.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.12 PROGBAR_SetBarColor()

Description

Sets the color(s) of the PROGBAR widget.

Prototype

```
void PROGBAR_SetBarColor(PROGBAR_Handle hObj,
                         unsigned int   Index,
                         GUI_COLOR      color);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
Index	See table below. Other values are not permitted.
Color	Color to set (24-bit RGB value).

Permitted values for parameter Index	
0	Left/lower portion of the PROGBAR widget.
1	Right/upper portion of the PROGBAR widget.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.13 PROGBAR_SetFont()

Description

Selects the font for the text display inside the PROGBAR widget.

Prototype

```
void PROGBAR_SetFont(      PROGBAR_Handle   hObj,
                     const GUI_FONT       * pfont);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
Index	See table below. Other values are not permitted.
Color	Color to set (24-bit RGB value).

Additional information

If this function is not called, the default font for PROGBAR widgets (the GUI default font) will be used. However, the default font of the PROGBAR widget may be changed in the GUIConf.h file. Simply define the default font as follows (example):

```
#define PROGBAR_DEFAULT_FONT &GUI_Font13_ASCII
```

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.14 PROGBAR_SetMinMax()

Description

Sets the minimum and maximum values used for the PROGBAR widget.

Prototype

```
void PROGBAR_SetMinMax(PROGBAR_Handle hObj,
                       int            Min,
                       int            Max);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
Min	Minimum value (Range: -16383 < Min ≤ 16383).
Max	Maximum value (Range: -16383 < Max ≤ 16383)

Additional information

If this function is not called, the default values of Min = 0, Max = 100 will be used.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.15 PROGBAR_SetText()

Description

Sets the text displayed inside the PROGBAR widget.

Prototype

```
void PROGBAR_SetText(      PROGBAR_Handle   hObj,
                     const char           * s);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
s	Text to display. A NULL pointer is permitted; in this case a percentage value will be displayed.

Additional information

If this function is not called, a percentage value will be displayed as the default. If you do not want to display any text at all, you should set an empty string.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.16 PROGBAR_SetTextAlign()

Description

Sets the text alignment.

Prototype

```
void PROGBAR_SetTextAlign(PROGBAR_Handle hObj,
                          int            Align);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
Align	See *Text alignment flags* on page 218. **Only horizontal flags are applicable!**

Additional information

If this function is not called, the default behavior is to display the text centered.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.17 PROGBAR_SetTextColor()

Description

Sets the text color of the PROGBAR widget.

Prototype

```
void PROGBAR_SetTextColor(PROGBAR_Handle hObj,
                          unsigned int   Index,
                          GUI_COLOR      color);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
Index	See table below. Other values are not permitted.
Color	Color to set (24-bit RGB value).

Permitted values for parameter Index	
0	Left portion of the text.
1	Right portion of the text.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.18 PROGBAR_SetTextPos()

Description

Sets the text position in pixels.

Prototype

```
void PROGBAR_SetTextPos(PROGBAR_Handle hObj,
                        int            XOff,
                        int            YOff);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
XOff	Number of pixels to move text in horizontal direction. Positive number will move text to the right.
YOff	Number of pixels to move text in vertical direction. Positive number will move text down.

Additional information

The values move the text the specified number of pixels within the widget. Normally, the default of (0,0) should be sufficient.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.19 PROGBAR_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.1.20 PROGBAR_SetValue()

Description

Sets the value of the PROGBAR widget.

Prototype

```
void PROGBAR_SetValue(PROGBAR_Handle hObj,
                      int            v);
```

Parameters

Parameter	Description
hObj	Handle of PROGBAR widget.
v	Value to set.

Additional information

The bar indicator will be calculated with regard to the max/min values. If a percentage is automatically displayed, the percentage will also be calculated using the given min/max values as follows:
`p = 100% × (v-Min)÷(Max-Min)`
The default value after creation of the widget is 0.

 © 2020 SEGGER Microcontroller GmbH

20.22.4.2 Defines

20.22.4.2.1 PROGBAR create flags

Description

Create flags used for the PROGBAR widget. These flags are specified when creating the widget with `PROGBAR_CreateEx()`.

Definition

```
#define PROGBAR_CF_HORIZONTAL    (0 << 0)
#define PROGBAR_CF_VERTICAL      (1 << 0)
```

Symbols

Definition	Description
PROGBAR_CF_VERTICAL	A vertical PROGBAR widget will be created. Vertical PROGBAR widgets do not show any text.
PROGBAR_CF_HORIZONTAL	A horizontal PROGBAR widget will be created (default).

 © 2020 SEGGER Microcontroller GmbH

20.22.5 Examples

The Sample folder contains the following examples which show how the widget can be used:

- WIDGET_SimpleProgbar.c
- WIDGET_Progbar.c

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_SimpleProgbar.c



Screenshot of WIDGET_Progbar.c



 © 2020 SEGGER Microcontroller GmbH

20.23 QRCODE: QR code widget

The QRCODE widget is used for displaying QR codes. The widget draws a QR code with the given parameters and also adds a white frame around the code which is necessary for scanning.

> **Note**
>
> All QRCODE-related routines are located in the file(s) `QRCODE.c`, `QRCODE.h`.



20.23.1 Configuration options

Type	Macro	Default	Description
N	QRCODE_COLOR_DEFAULT	GUI_WHITE	Default color to draw the bright pixels.
N	QRCODE_BKCOLOR_DEFAULT	GUI_BLACK	Default default color to draw the dark pixels.

20.23.2 Predefined IDs

The following symbols define IDs which may be used to make QRCODE widgets distinguishable from creation.

```
#define GUI_ID_QRCODE0    0x350
#define GUI_ID_QRCODE1    0x351
#define GUI_ID_QRCODE2    0x352
#define GUI_ID_QRCODE3    0x353
#define GUI_ID_QRCODE4    0x354
#define GUI_ID_QRCODE5    0x355
#define GUI_ID_QRCODE6    0x356
#define GUI_ID_QRCODE7    0x357
#define GUI_ID_QRCODE8    0x358
#define GUI_ID_QRCODE9    0x359
```

20.23.3 Keyboard reaction

The widget can not gain the input focus and does not react on keyboard input.

20.23.4 QRCODE API

The table below lists the available emWin QRCODE-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
QRCODE_CreateIndirect()	Creates a QRCODE widget from a resource table entry.
QRCODE_CreateUser()	Creates a QRCODE widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
QRCODE_SetEccLevel()	Sets the error correction level of a QRCODE widget.
QRCODE_SetNumModules	Sets the error correction level of a QRCODE widget.
QRCODE_SetPixelSize()	Sets the size of one pixel in the QRCODE widget.
QRCODE_SetText()	Sets the text to be used to draw the QRCODE widget.
QRCODE_SetWiFiText()	Sets the text of a QRCODE widget told hold WiFi login data.

Defines

Group of defines	Description
QRCODE WiFi encryption types	Macros for WiFi password encryption types.

 © 2020 SEGGER Microcontroller GmbH

20.23.4.1 Functions

20.23.4.1.1 QRCODE_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The elements `Flags` and `Para` of the resource passed as parameter are not used.

 © 2020 SEGGER Microcontroller GmbH

20.23.4.1.2 QRCODE_CreateUser()

Description

Creates a QRCODE widget.

Prototype

```
QRCODE_Handle QRCODE_CreateUser(      int       x0,
                                      int       y0,
                                      int       xSize,
                                      int       ySize,
                                      WM_HWIN   hParent,
                                      int       WinFlags,
                                      int       ExFlags,
                                      int       Id,
                                const char    * pText,
                                      int       PixelSize,
                                      int       EccLevel,
                                      int       Version,
                                      int       NumExtraBytes);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the QRCODE widget (in parent coordinates).
y0	Topmost pixel of the QRCODE widget (in parent coordinates).
xSize	Horizontal size of the QRCODE widget (in pixels).
ySize	Vertical size of the QRCODE widget (in pixels).
hParent	Parent window of the QRCODE widget.
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used yet, reserved for future use.
Id	ID of the QRCODE widget.
pText	UTF-8 text to be used for the QR-code.
PixelSize	Size in pixels of one 'Module'.
EccLevel	Error correction level to be used. See full list of available values under *ECC levels for QR codes* on page 383.
NumModules	Desired size in modules of the QR-code. If set to 0 (recommended) the size will be calculated automatically. Must be between 1 and 40. If it is less than required for the given text with the given EccLevel, the function fails.
NumExtraBytes	Number of extra bytes to be allocated.

Return value

Handle of the QRCODE widget.

 © 2020 SEGGER Microcontroller GmbH

20.23.4.1.3 QRCODE_SetEccLevel()

Description

Sets the error correction level of a QRCODE widget.

Prototype

```
void QRCODE_SetEccLevel(QRCODE_Handle hObj,
                        int           EccLevel);
```

Parameters

Parameter	Description
hObj	Handle of QRCODE widget.
EccLevel	Error correction level to be used. See full list of available values under *ECC levels for QR codes* on page 383.

 © 2020 SEGGER Microcontroller GmbH

20.23.4.1.4 QRCODE_SetNumModules

 © 2020 SEGGER Microcontroller GmbH

20.23.4.1.5 QRCODE_SetPixelSize()

Description

Sets the size of one pixel in the QRCODE widget.

Prototype

```
void QRCODE_SetPixelSize(QRCODE_Handle hObj,
                         int           PixelSize);
```

Parameters

Parameter	Description
hObj	Handle of QRCODE widget.
PixelSize	Size of one pixel to be used.

 © 2020 SEGGER Microcontroller GmbH

20.23.4.1.6 QRCODE_SetText()

Description

Sets the text to be used to draw the QRCODE widget.

Prototype

```
void QRCODE_SetText(      QRCODE_Handle   hObj,
                    const char          * pText);
```

Parameters

Parameter	Description
hObj	Handle of QRCODE widget.
pText	Text to be used for the widget.

 © 2020 SEGGER Microcontroller GmbH

20.23.4.1.7 QRCODE_SetWiFiText()

Description

Sets the text of a QRCODE widget told hold WiFi login data. When scanning the QR code with a smartphone, the phone will try to log into the specified WiFi network.

Prototype

```
void QRCODE_SetWiFiText(      QRCODE_Handle   hObj,
                        const char          * pSSID,
                              U8              Encryption,
                        const char          * pPassword,
                              U8              Hidden);
```

Parameters

Parameter	Description
hObj	Handle of QRCODE widget.
pSSID	SSID of the network.
Encryption	See *QRCODE WiFi encryption types* on page 1847.
pPassword	Password of the network.
Hidden	0 if the network is not hidden, 1 if it is hidden.

 © 2020 SEGGER Microcontroller GmbH

20.23.4.2 Defines

20.23.4.2.1 QRCODE WiFi encryption types

Description

These macros are to be used for the `Encryption` parameter of `QRCODE_SetWiFiText()`.

Definition

```
#define QRCODE_WIFI_WPA    0
#define QRCODE_WIFI_WEP    1
```

Symbols

Definition	Description
QRCODE_WIFI_WPA	If the WiFi password is WPA encrypted.
QRCODE_WIFI_WEP	If the WiFi password is WEP encrypted.

 © 2020 SEGGER Microcontroller GmbH

20.24 RADIO: Radio button widget

Radio buttons, like check boxes, are used for selecting choices. A dot appears when a RADIO button is turned on or selected. The difference from check boxes is that the user can only select one RADIO button at a time. When a button is selected, the other buttons in the widget are turned off, as shown to the right. One RADIO button widget may contain any number of buttons, which are always arranged vertically.

> **Note**
>
> All RADIO-related routines are located in the file(s) `RADIO*.c`, `RADIO.h`. All identifiers are prefixed RADIO.

The table below shows the default appearances of a RADIO button:

	Enabled	Disabled
Selected		
Unselected		

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.24.1 Configuration options

Type	Macro	Default	Description
S	RADIO_IMAGE0_DEFAULT	(see table above)	Default outer image used to show a disabled RADIO button.
S	RADIO_IMAGE1_DEFAULT	(see table above)	Default outer image used to show a enabled RADIO button.
S	RADIO_IMAGE_CHECK_DEFAULT	(see table above)	Default inner image used to mark the selected item.
N	RADIO_FONT_DEFAULT	&GUI_Font13_1	Default font used to render the text of the RADIO widget.
N	RADIO_DEFAULT_TEXT_COLOR	GUI_BLACK	Default text color of RADIO widget.
N	RADIO_DEFAULT_BKCOLOR	0xC0C0C0	Default background color of RADIO buttons if no transparency is used.
N	RADIO_FOCUSCOLOR_DEFAULT	GUI_BLACK	Default color for rendering the focus rectangle.

20.24.2 Predefined IDs

The following symbols define IDs which may be used to make RADIO widgets distinguishable from creation.

```
#define GUI_ID_RADIO0    0x150
#define GUI_ID_RADIO1    0x151
#define GUI_ID_RADIO2    0x152
#define GUI_ID_RADIO3    0x153
```

 © 2020 SEGGER Microcontroller GmbH

```
#define GUI_ID_RADIO4    0x154
#define GUI_ID_RADIO5    0x155
#define GUI_ID_RADIO6    0x156
#define GUI_ID_RADIO7    0x157
#define GUI_ID_RADIO8    0x158
#define GUI_ID_RADIO9    0x159
```

20.24.3 Notification codes

The following events are sent from a RADIO widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	RADIO button has been clicked.
WM_NOTIFICATION_RELEASED	RADIO button has been released.
WM_NOTIFICATION_MOVED_OUT	RADIO button has been clicked and pointer has been moved out of the button without releasing.
WM_NOTIFICATION_VALUE_CHANGED	Value (selection) of the RADIO widget has changed.

20.24.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_RIGHT	Increments the selection by 1.
GUI_KEY_DOWN	Increments the selection by 1.
GUI_KEY_LEFT	Decrements the selection by 1.
GUI_KEY_UP	Decrements the selection by 1.

20.24.5 RADIO API

The table below lists the available emWin RADIO-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
RADIO_Create()	Creates a RADIO widget. (Obsolete)
RADIO_CreateEx()	Creates a RADIO widget.
RADIO_CreateIndirect()	Creates a RADIO widget from resource table entry.
RADIO_CreateUser()	Creates a RADIO widget using extra bytes as user data.
RADIO_Dec()	Decrements the selection by 1.
RADIO_GetBkColor()	Returns the background color of the RADIO widget.
RADIO_GetDefaultFont()	Returns the default font used to display the optional text next to new RADIO buttons.
RADIO_GetDefaultTextColor()	Returns the default text color used to display the optional text next to new RADIO buttons.
RADIO_GetFocusColor()	Returns the color used to render the focus rectangle of the RADIO button.
RADIO_GetFont()	Returns the font set for this widget.
RADIO_GetImage()	Returns a pointer to the set image of a RADIO.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
RADIO_GetNumItems()	Returns the number of items in a RADIO widget.
RADIO_GetSpacing()	Returns the vertical spacing between the items.
RADIO_GetText()	Returns the optional text of the given RADIO widget.
RADIO_GetTextColor()	Returns the text color of the RADIO widget.
RADIO_GetUserData()	Retrieves the data set with RADIO_SetUserData().
RADIO_GetValue()	Returns the currently selected button.
RADIO_Inc()	Increments the selection by a value of 1.
RADIO_SetBkColor()	Sets the background color of the RADIO widget.
RADIO_SetDefaultFocusColor()	Sets the default focus rectangle color for new RADIO buttons.
RADIO_SetDefaultFont()	Sets the default font used to display the optional text next to new RADIO buttons.
RADIO_SetDefaultImage()	Sets the images used to draw new RADIO buttons.
RADIO_SetDefaultTextColor()	Sets the default text color used to display the optional text next to new RADIO buttons.
RADIO_SetFocusColor()	Sets the color used to render the focus rectangle of the RADIO button.
RADIO_SetFont()	Sets the font used to display the optional text next to the RADIO buttons.
RADIO_SetGroupId()	Sets the group ID of the RADIO widget.
RADIO_SetImage()	Sets the images used to draw the RADIO button.
RADIO_SetSpacing()	Sets the vertical spacing between the items.
RADIO_SetText()	Sets the text.
RADIO_SetTextColor()	Sets the text color used to show the optional text beside the RADIO buttons.
RADIO_SetUserData()	Sets the extra data of a RADIO widget.
RADIO_SetValue()	Sets the current button selection.

Defines

Group of defines	Description
RADIO bitmap indexes	Bitmap indexes used for setting the bitmaps of a RADIO widget.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1 Functions

20.24.5.1.1 RADIO_Create()

> **Note**
>
> This function is **deprecated**, `RADIO_CreateEx()` should be used instead.

Description

Creates a RADIO widget of a specified size at a specified location.

Prototype

```
RADIO_Handle RADIO_Create(int      x0,
                          int      y0,
                          int      xSize,
                          int      ySize,
                          WM_HWIN  hParent,
                          int      Id,
                          int      Flags,
                          unsigned Para);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the RADIO widget (in parent coordinates).
`y0`	Topmost pixel of the RADIO widget (in parent coordinates).
`xSize`	Horizontal size of the RADIO widget (in pixels).
`ySize`	Vertical size of the RADIO widget (in pixels).
`hParent`	Handle of parent window.
`Id`	ID to be returned.
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
`Para`	Number of buttons in the group.
`v`	Value to set.

Return value

Handle of the created RADIO widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.2 RADIO_CreateEx()

Description

Creates a RADIO widget of a specified size at a specified location.

Prototype

```
RADIO_Handle RADIO_CreateEx(int     x0,
                            int     y0,
                            int     xSize,
                            int     ySize,
                            WM_HWIN hParent,
                            int     WinFlags,
                            int     ExFlags,
                            int     Id,
                            int     NumItems,
                            int     Spacing);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new RADIO widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used, reserved for future use.
Id	Window ID of the widget.
NumItems	Number of items contained by the RADIO widget. (default is 2)
Spacing	Number of vertical pixels used for each item of the RADIO widget.

Return value

Handle of the created RADIO widget; 0 if the function fails.

Additional information

If creating a RADIO widget make sure, that the given ySize is enough to show all items. The value should be at least NumItems × Spacing. If the given value of NumItems is ≤ 0 a default value of 2 is used.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.3 RADIO_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. For details the function *<WIDGET>_CreateIndirect()* on page 974 should be referred to. The element Flags of the according GUI_WIDGET_CREATE_INFO structure is not used. The following table shows the use of the element Para:

Bits	Description
0 - 7	Number of items of the RADIO widget. If 0, a default value of 2 items is used.
8 - 15	Number of vertical pixels used for each item. If 0 the height of the default image is used.
16 - 23	Not used, reserved for future use.
24 - 31	Not used, reserved for future use.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.4 RADIO_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `RADIO_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.5 RADIO_Dec()

Before	After
	

Description

Decrements the selection by 1.

Prototype

```
void RADIO_Dec(RADIO_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.

Additional information

Note that the numbering of the buttons always starts from the top with a value of 0; therefore, decrementing the selection will actually move the selection one button up.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.6 RADIO_GetBkColor()

Description

Returns the background color of the RADIO widget.

Prototype

```
GUI_COLOR RADIO_GetBkColor(RADIO_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.

Return value

The background color of the widget.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.7 RADIO_GetDefaultFont()

Description

Returns the default font used to display the optional text next to new RADIO buttons.

Prototype

```
GUI_FONT *RADIO_GetDefaultFont(void);
```

Return value

Default font used to display the optional text next to the RADIO buttons.

Additional information

For information about how to add text to a RADIO widget, refer to `RADIO_SetText()`.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.8 RADIO_GetDefaultTextColor()

Description

Returns the default text color used to display the optional text next to new RADIO buttons.

Prototype

```
GUI_COLOR RADIO_GetDefaultTextColor(void);
```

Return value

Default text color used to display the optional text next to new RADIO buttons.

Additional information

For information about how to add text to a RADIO widget, refer to `RADIO_SetText()`.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.9 RADIO_GetFocusColor()

Description

Returns the color used to render the focus rectangle of the RADIO button.

Prototype

```
GUI_COLOR RADIO_GetFocusColor(RADIO_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.

Return value

The color of the focus rectangle.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.10 RADIO_GetFont()

Description

Returns the font set for this widget.

Prototype

```
GUI_FONT *RADIO_GetFont(RADIO_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.

Return value

A pointer to the font of the widget.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.11 RADIO_GetImage()

Description

Returns a pointer to the set image of a RADIO.

Prototype

```
GUI_BITMAP *RADIO_GetImage(RADIO_Handle hObj,
                           unsigned int Index);
```

Parameters

Parameter	Description
hObj	Handle to RADIO widget.
Index	See *RADIO bitmap indexes* on page 1883 for a full list of permitted values.

Return value

Pointer to a GUI_BITMAP structure of the set image.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.12 RADIO_GetNumItems()

Description

Returns the number of items in a RADIO widget.

Prototype

```
int RADIO_GetNumItems(RADIO_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.

Return value

Number of items in the RADIO widget.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.13 RADIO_GetSpacing()

Description

Returns the vertical spacing between the items.

Prototype

```
U16 RADIO_GetSpacing(RADIO_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.

Return value

Vertical spacing between the items.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.14 RADIO_GetText()

Description

Returns the optional text of the given RADIO widget.

Prototype

```
int RADIO_GetText(RADIO_Handle   hObj,
                  unsigned       Index,
                  char         * pBuffer,
                  int            MaxLen);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
Index	Index of the desired item.
pBuffer	Pointer to buffer to which the text will be copied.
MaxLen	Buffer size in bytes.

Return value

Length of the text copied into the buffer.

Additional information

If the desired item of the RADIO widget contains no text the function returns 0 and the buffer remains unchanged.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.15 RADIO_GetTextColor()

Description

Returns the text color of the RADIO widget.

Prototype

```
GUI_COLOR RADIO_GetTextColor(RADIO_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.

Return value

The text color of the widget.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.16 RADIO_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.17 RADIO_GetValue()

Description

Returns the currently selected button.

Prototype

```
int RADIO_GetValue(RADIO_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.

Return value

The value of the currently selected button. If no button is selected (in case of using a RADIO button group) the return value is -1.

Additional information

For information about how to use groups of RADIO buttons, refer to `RADIO_SetGroupId()`.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.18 RADIO_Inc()

Before	After
	

Description

Increments the selection by a value of 1.

Prototype

```
void RADIO_Inc(RADIO_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.

Additional information

Note that the numbering of the buttons always starts from the top with a value of 0; therefore, incrementing the selection will actually move the selection one button down.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.19 RADIO_SetBkColor()

Before	After
	

Description

Sets the background color of the RADIO widget.

Prototype

```
void RADIO_SetBkColor(RADIO_Handle hObj,
                      GUI_COLOR    Color);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
Color	Color to be used for the background. (range 0x000000 and 0xFFFFFF or a valid color define) GUI_INVALID_COLOR to make background transparent

Additional information

The background of this widget can either be filled with any available color or trans- parent. If a valid RGB color is specified, the background is filled with the color, other- wise the background (typically the content of the parent window) is visible. If the background is transparent, the widget is treated as transparent window, otherwise as non-transparent window. Note that using a background color allows more efficient (faster) rendering. If skinning is active this function should not be used.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.20 RADIO_SetDefaultFocusColor()

Description

Sets the default focus rectangle color for new RADIO buttons.

Prototype

```
GUI_COLOR RADIO_SetDefaultFocusColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
Color	Color to be used for the background. (range 0x000000 and 0xFFFFFF or a valid color define) GUI_INVALID_COLOR to make background transparent

Return value

Previous default focus rectangle color.

Additional information

For more information, refer to RADIO_SetFocusColor().

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.21 RADIO_SetDefaultFont()

Description

Sets the default font used to display the optional text next to new RADIO buttons.

Prototype

```
void RADIO_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to GUI_FONT structure used to show the text of new RADIO widgets.

Additional information

For information about how to add text to a RADIO widget, refer to RADIO_SetText().

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.22 RADIO_SetDefaultImage()

Description

Sets the images used to draw new RADIO buttons.

Prototype

```
void RADIO_SetDefaultImage(const GUI_BITMAP   * pBitmap,
                           unsigned int   Index);
```

Parameters

Parameter	Description
pBitmap	Pointer to the bitmap.
Index	See *RADIO bitmap indexes* on page 1883 for a full list of permitted values.

Additional information

Two images are used to display a RADIO button. One image is used to draw the outer frame used to display a unselected RADIO button. In dependence of the current state it will be the bitmap referenced by RADIO_BI_ACTIVE (default) or by RADIO_BI_ACTIVE. The second image (referenced by RADIO_BI_CHECK) is used to mark the currently selected button.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.23 RADIO_SetDefaultTextColor()

Description

Sets the default text color used to display the optional text next to new RADIO buttons.

Prototype

```
void RADIO_SetDefaultTextColor(GUI_COLOR TextColor);
```

Parameters

Parameter	Description
TextColor	New color to be used.

Additional information

For information about how to add text to a RADIO widget, refer to RADIO_SetText().

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.24 RADIO_SetFocusColor()

Before	After
	

Description

Sets the color used to render the focus rectangle of the RADIO button.

Prototype

```
GUI_COLOR RADIO_SetFocusColor(RADIO_Handle hObj,
                              GUI_COLOR    Color);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
Color	Color to be used for the focus rectangle.

Return value

Previous color of the focus rectangle.

Additional information

The focus rectangle is only visible if the widget has the input focus.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.25 RADIO_SetFont()

Before	After
	

Description

Sets the font used to display the optional text next to the RADIO buttons.

Prototype

```
void RADIO_SetFont(      RADIO_Handle   hObj,
                   const GUI_FONT     * pFont);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
pFont	Pointer to GUI_FONT structure to be used to display the text.

Additional information

For information about how to add text to a RADIO widget, refer to RADIO_SetText().

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.26 RADIO_SetGroupId()

Before	After
	

Description

Sets the group ID of the RADIO widget.

Prototype

```
void RADIO_SetGroupId(RADIO_Handle hObj,
                      U8           NewGroupId);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
GroupId	ID of the RADIO button group. Must be between 1 and 255. If the value is 0 the RADIO widget is not assigned to a RADIO button group.

Additional information

This command can be used to create groups of RADIO buttons. The behavior of one group is the same as the behavior of one RADIO button. This makes it possible to create for example 2 RADIO widgets side by side with 3 buttons each and build one group of them.

Example

The following example shows how to create a group of 2 RADIO widgets as shown in the screenshot at the beginning of the function description:

```
hRadio_0 = RADIO_CreateEx(10, 10, 60, 0, WM_HBKWIN, WM_CF_SHOW, 0, 1234, 3, 20);
RADIO_SetText(hRadio_0, "Red", 0);
RADIO_SetText(hRadio_0, "Green", 1);
RADIO_SetText(hRadio_0, "Blue", 2);
hRadio_1 = RADIO_CreateEx(65, 10, 60, 0, WM_HBKWIN, WM_CF_SHOW, 0, 1234, 3, 20);
RADIO_SetText(hRadio_1, "Magenta", 0);
RADIO_SetText(hRadio_1, "Cyan", 1);
RADIO_SetText(hRadio_1, "Yellow", 2);
RADIO_SetGroupId(hRadio_0, 1);
RADIO_SetGroupId(hRadio_1, 1);
```

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.27 RADIO_SetImage()

Description

Sets the images used to draw the RADIO button.

Prototype

```
void RADIO_SetImage(      RADIO_Handle   hObj,
                    const GUI_BITMAP   * pBitmap,
                          unsigned int   Index);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
pBitmap	Pointer to the bitmap.
Index	See *RADIO bitmap indexes* on page 1883.

Additional information

See `RADIO_SetDefaultImage()`.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.28 RADIO_SetSpacing()

Description

Sets the vertical spacing between the items.

Prototype

```
void RADIO_SetSpacing(RADIO_Handle hObj,
                      U16          Spacing);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
Spacing	Spacing between items in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.29 RADIO_SetText()

Description

Sets the optional text shown next to the RADIO buttons.

Prototype

```
void RADIO_SetText(      RADIO_Handle   hObj,
                   const char         * s,
                         unsigned       Index);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
pText	Pointer to the text to be shown next to the specified RADIO button.
Index	Zero based index of the RADIO button.

Before	After
	

Additional information

If using a RADIO widget without text (old style) the focus rectangle is drawn around the buttons of the widget. If using RADIO button text the focus rectangle is shown around the text of the currently selected RADIO button of the widget.

Example

The following example shows how to add the text shown in the screenshot above:

```
RADIO_SetText(hRadio_0, "Red",   0);
RADIO_SetText(hRadio_0, "Green", 1);
RADIO_SetText(hRadio_0, "Blue",  2);
```

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.30 RADIO_SetTextColor()

Before	After
	

Description

Sets the text color used to show the optional text beside the RADIO buttons.

Prototype

```
void RADIO_SetTextColor(RADIO_Handle hObj,
                        GUI_COLOR    Color);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
Color	Color used to show the text.

Additional information

For information about how to add text to a RADIO widget, refer to RADIO_SetText().

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.31 RADIO_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.1.32 RADIO_SetValue()

Description

Sets the current button selection.

Prototype

```
void RADIO_SetValue(RADIO_Handle hObj,
                    int          v);
```

Parameters

Parameter	Description
hObj	Handle of RADIO widget.
v	Value to be set.

Additional information

The topmost RADIO button in a RADIO widget always has the 0 value, the next button down is always 1, the next is 2, etc.

 © 2020 SEGGER Microcontroller GmbH

20.24.5.2 Defines

20.24.5.2.1 RADIO bitmap indexes

Description

Bitmap indexes used by routines to change the bitmaps of a RADIO widget.

Definition

```
#define RADIO_BI_INACTIVE    0
#define RADIO_BI_ACTIVE      1
#define RADIO_BI_CHECK       2
```

Symbols

Definition	Description
RADIO_BI_INACTIVE	Outer image used to show a disabled RADIO button.
RADIO_BI_ACTIVE	Outer image used to show a enabled RADIO button.
RADIO_BI_CHECK	Inner image used to mark the selected item.

 © 2020 SEGGER Microcontroller GmbH

20.24.6 Examples

The `Sample` folder contains the following example which shows how the widget can be used:

- `DIALOG_Radio.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of DIALOG_Radio.c



 © 2020 SEGGER Microcontroller GmbH

20.25 ROTARY: Rotary widget

The ROTARY widget is a reworked version of the KNOB widget, therefore they share some similarities. Just as the KNOB, the ROTARY is a widget the user can rotate. From the rotation degree values are determined which can be used within the application.



A ROTARY widget consists of a background bitmap and a marker bitmap. Optionally, the marker bitmap can be rotated while the widget is rotating, but the background bitmap does not rotate.

> **Note**
>
> All ROTARY-related routines are located in the file(s) `ROTARY.c` and `ROTARY.h`.
> All identifiers are prefixed with ROTARY.

Ticks and tick size

Just as with the KNOB widget, a ROTARY is divided into ticks. A tick describes the smallest range of movement of a ROTARY widget. The smallest size of one tick (tick size = 1) equates to 1/10 of a degree. Therefore it takes 3600 ticks to fulfill one round. The size of one tick can be set with the function `ROTARY_SetTickSize()`.

Examples	
Ticksize	Ticks for one round
60	60
36	100
300	12

Memory requirements

While the KNOB widget uses a memory device for the entire background, the ROTARY widget doesn't. This is not necessary since the background of the ROTARY is not rotated. Only the marker of a ROTARY can be rotated. If the user chooses to rotate the marker, the memory usage will be a bit higher, depending on the size of the marker bitmap.

20.25.1 Configuration options

Type	Macro	Default	Description
N	`ROTARY_PERIOD_DEFAULT`	1500	Period in ms it takes the ROTARY to stop.
N	`ROTARY_TICKSIZE_DEFAULT`	1	Size of one tick in 1/10 of degree.

20.25.2 Predefined IDs

The following symbols define IDs which may be used to make ROTARY widgets distinguishable from creation.

 © 2020 SEGGER Microcontroller GmbH

```
#define GUI_ID_ROTARY0    0x310
#define GUI_ID_ROTARY1    0x311
#define GUI_ID_ROTARY2    0x312
#define GUI_ID_ROTARY3    0x313
#define GUI_ID_ROTARY4    0x314
#define GUI_ID_ROTARY5    0x315
#define GUI_ID_ROTARY6    0x316
#define GUI_ID_ROTARY7    0x317
#define GUI_ID_ROTARY8    0x318
#define GUI_ID_ROTARY9    0x319
```

20.25.3 Notification codes

The following events are sent from a ROTARY widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	ROTARY has been clicked.
WM_NOTIFICATION_RELEASED	ROTARY has been released.
WM_NOTIFICATION_MOTION_STOPPED	Movement of the ROTARY has stopped.
WM_NOTIFICATION_MOVED_OUT	ROTARY has been clicked and pointer has been moved out of the ROTARY area without releasing.
WM_NOTIFICATION_VALUE_CHANGED	The value of the ROTARY widget has been changed.

20.25.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus. Depending on the arrow key, per press the size of one tick is either added or subtracted to the ROTARY's angle.

Key	Reaction
GUI_KEY_RIGHT	The ROTARY rotates CW.
GUI_KEY_LEFT	The ROTARY rotates CCW.
GUI_KEY_DOWN	The ROTARY rotates CW.
GUI_KEY_UP	The ROTARY rotates CCW.

20.25.5 ROTARY API

Routine	Description
ROTARY_AddAngle()	Adds an angle to a ROTARY widget.
ROTARY_AddValue()	Adds a given value to a ROTARY widget.
ROTARY_CreateEx()	Creates a ROTARY widget.
ROTARY_CreateIndirect()	Creates a ROTARY widget from a resource table entry.
ROTARY_CreateUser()	Creates a ROTARY widget using extra bytes as user data.
ROTARY_GetAngle()	Returns the current angle of a ROTARY widget.
ROTARY_GetImageSize()	Returns the size of the background image.
ROTARY_GetMarkerSize()	Returns the size of the marker bitmap.
ROTARY_GetUserData()	Retrieves the data set with ROTARY_SetUserData().
ROTARY_GetValue()	Returns the value of a ROTARY widget.
ROTARY_SetAngle()	Sets the current angle of a ROTARY widget.
ROTARY_SetBitmap()	Sets the background bitmap of a ROTARY widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
ROTARY_SetDoRotate()	Sets the marker image of a ROTARY widget to be rotated.
ROTARY_SetMarker()	Sets the marker bitmap of a ROTARY widget.
ROTARY_SetOffset()	Sets the offset of a ROTARY widget.
ROTARY_SetPeriod()	Sets the period of a ROTARY widget.
ROTARY_SetRadius()	Sets the radius of a ROTARY widget.
ROTARY_SetRange()	Sets the usable range of a ROTARY widget.
ROTARY_SetSnap()	Sets a snap position for a ROTARY widget.
ROTARY_SetTickSize()	Sets the tick size of a ROTARY widget.
ROTARY_SetUserData()	Sets the extra data of a ROTARY widget.
ROTARY_SetValue()	Sets the value of a ROTARY widget.
ROTARY_SetValueRange()	Sets the usable range of values of a ROTARY widget.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.1 ROTARY_AddAngle()

Description

Adds an angle to a ROTARY widget.

Prototype

```
void ROTARY_AddAngle(ROTARY_Handle hObj,
                     I32           Delta);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
Delta	Angle to be added.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.2 ROTARY_AddValue()

Description

Adds a given value to a ROTARY widget.

Prototype

```
void ROTARY_AddValue(ROTARY_Handle hObj,
                     I32           Delta);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
Delta	Value to be added.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.3 ROTARY_CreateEx()

Description

Creates a ROTARY widget.

Prototype

```
ROTARY_Handle ROTARY_CreateEx(int     x0,
                              int     y0,
                              int     xSize,
                              int     ySize,
                              WM_HWIN hParent,
                              int     WinFlags,
                              int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the ROTARY widget (in parent coordinates).
y0	Topmost pixel of the ROTARY widget (in parent coordinates).
xSize	Horizontal size of the ROTARY widget (in pixels).
ySize	Vertical size of the ROTARY widget (in pixels).
hParent	Parent window of the ROTARY widget.
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
Id	ID of the ROTARY widget.

Return value

Handle of ROTARY widget.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.4 ROTARY_CreateIndirect()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateIndirect()* on page 974. The elements `Flags` and `Para` of the resource passed as parameter are not used.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.5 ROTARY_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function KNOB_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.6 ROTARY_GetAngle()

Description

Returns the current angle of a ROTARY widget.

Prototype

```
I32 ROTARY_GetAngle(ROTARY_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.

Return value

Angle of the ROTARY widget.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.7 ROTARY_GetImageSize()

Description

Returns the size of the background image.

Prototype

```
int ROTARY_GetImageSize(ROTARY_Handle   hObj,
                        int           * pxSize,
                        int           * pySize);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
pxSize	Pointer to an integer to store the x-size.
pySize	Pointer to an integer to store the y-size.

Return value

0 If the routine succeeds.
1 If the routine fails.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.8 ROTARY_GetMarkerSize()

Description

Returns the size of the marker bitmap.

Prototype

```
int ROTARY_GetMarkerSize(ROTARY_Handle   hObj,
                         int           * pxSize,
                         int           * pySize);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
pxSize	Pointer to an integer to store the x-size.
pySize	Pointer to an integer to store the y-size.

Return value

0 If the routine succeeds.
1 If the routine fails.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.9 ROTARY_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.10 ROTARY_GetValue()

Description

Returns the value of a ROTARY widget. This value depends on the set range of the widget.

Prototype

```
I32 ROTARY_GetValue(ROTARY_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.

Return value

Value of the ROTARY widget.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.11 ROTARY_SetAngle()

Description

Sets the current angle of a ROTARY widget. The angle has to be within the valid range.

Prototype

```
void ROTARY_SetAngle(ROTARY_Handle hObj,
                     I32           Pos);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
Pos	Angle to be added.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.12 ROTARY_SetBitmap()

Description

Sets the background bitmap of a ROTARY widget. This bitmap won't be rotated.

Prototype

```
void ROTARY_SetBitmap(      ROTARY_Handle   hObj,
                      const GUI_BITMAP    * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
pBitmap	Pointer to a bitmap.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.13 ROTARY_SetDoRotate()

Before	After
	

Description

Sets the marker image of a ROTARY widget to be rotated.

Prototype

```
void ROTARY_SetDoRotate(ROTARY_Handle hObj,
                        U8            DoRotate);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
DoRotate	If the marker bitmap should be rotated.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.14 ROTARY_SetMarker()

Before	After
	

Description

Sets the marker bitmap of a ROTARY widget.

Prototype

```
void ROTARY_SetMarker(      ROTARY_Handle   hObj,
                      const GUI_BITMAP    * pBitmap,
                            int             Radius,
                            I32             Offset,
                            U8              DoRotate);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
pBitmap	Pointer to a bitmap to be set as marker.
Radius	Mid-point difference between widget and marker bitmap.
Offset	Angle offset for drawing marker.
DoRotate	If the marker bitmap should be rotated.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.15 ROTARY_SetOffset()

Description

Sets the offset of a ROTARY widget.

Prototype

```
void ROTARY_SetOffset(ROTARY_Handle hObj,
                      int           Offset);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
Offset	Offset to be set.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.16 ROTARY_SetPeriod()

Description

Sets the period of a ROTARY widget. This period determines when the rotation of the widget stops.

Prototype

```
void ROTARY_SetPeriod(ROTARY_Handle hObj,
                      I32           Period);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
Period	Period to be set.

Additional information

The default period is 1500ms. The maximum value for the period is 46340ms.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.17 ROTARY_SetRadius()

Before	After
	

Description

Sets the radius of a ROTARY widget.

Prototype

```
void ROTARY_SetRadius(ROTARY_Handle hObj,
                      int           Radius);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
Radius	Radius of the ROTARY widget.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.18 ROTARY_SetRange()

Description

Sets the usable range of a ROTARY widget.

Prototype

```
void ROTARY_SetRange(ROTARY_Handle hObj,
                     U32           AngPositive,
                     U32           AngNegative);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
AngPositive	Starting angle.
AngNegative	Ending angle.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.19 ROTARY_SetSnap()

Description

Sets a snap position for a ROTARY widget. A snap position is a position measured in ticks where the widget automatically stops rotating.

Prototype

```
void ROTARY_SetSnap(ROTARY_Handle hObj,
                    I32           Snap);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
Snap	Snap position to be set.

Additional information

The default value is 0. If set to 0, there is no snap position.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.20 ROTARY_SetTickSize()

Description

Sets the tick size of a ROTARY widget. The tick size is measured in 10th of degrees.

Prototype

```
void ROTARY_SetTickSize(ROTARY_Handle hObj,
                        I32           TickSize);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
TickSize	Tick size of the ROTARY widget.

Additional information

This routine has to be called before any other ROTARY related routines, except any ROTARY_Create…() routines of course.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.21 ROTARY_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.25.5.22 ROTARY_SetValue()

Before	After
	

Description

Sets the value of a ROTARY widget.

Prototype

```
void ROTARY_SetValue(ROTARY_Handle hObj,
                     I32           Value);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
Value	Value to be added.

Additional information

The angle depends on the range set with ROTARY_SetRange() and ROTARY_SetValueRange().

 © 2020 SEGGER Microcontroller GmbH

20.25.5.23 ROTARY_SetValueRange()

Description

Sets the usable range of values of a ROTARY widget.

Prototype

```
int ROTARY_SetValueRange(ROTARY_Handle hObj,
                         I32           Min,
                         I32           Max);
```

Parameters

Parameter	Description
hObj	Handle of a ROTARY widget.
Min	Minimum value.
Max	Maximum value.

Return value

0 If the routine succeeds.
1 If the routine fails.

 © 2020 SEGGER Microcontroller GmbH

20.26 SCROLLBAR: Scroll bar widget

Scroll bars are used for scrolling through list boxes or any other type of window. They may be created horizontally, as shown below, or vertically.



A scroll bar is typically attached to an existing window, for example the list box shown below:



> **Note**
>
> All SCROLLBAR-related routines are located in the file(s) `SCROLLBAR*.c`, `SCROLLBAR.h`. All identifiers are prefixed SCROLLBAR.

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.26.1 Configuration options

Type	Macro	Default	Description
N	SCROLLBAR_COLOR_SHAFT_DEFAULT	0x808080	Color of the shaft.
N	SCROLLBAR_COLOR_ARROW_DEFAULT	GUI_BLACK	Color of the arrows.
N	SCROLLBAR_COLOR_THUMB_DEFAULT	0xc0c0c0	Color of the thumb area.
N	SCROLLBAR_THUMB_SIZE_MIN_DEFAULT	4	Minimum thumb size.

20.26.2 Predefined IDs

The following symbols define IDs which may be used to make SCROLLBAR widgets distinguishable from creation.

```
#define GUI_ID_SCROLLBAR0    0x140
#define GUI_ID_SCROLLBAR1    0x141
#define GUI_ID_SCROLLBAR2    0x142
#define GUI_ID_SCROLLBAR3    0x143
#define GUI_ID_SCROLLBAR4    0x144
#define GUI_ID_SCROLLBAR5    0x145
#define GUI_ID_SCROLLBAR6    0x146
#define GUI_ID_SCROLLBAR7    0x147
#define GUI_ID_SCROLLBAR8    0x148
#define GUI_ID_SCROLLBAR9    0x149
```

20.26.3 Notification codes

The following events are sent from a scroll bar widget to its parent window as part of a `WM_NOTIFY_PARENT` message:

Message	Description
WM_NOTIFICATION_CLICKED	SCROLLBAR has been clicked.
WM_NOTIFICATION_RELEASED	SCROLLBAR has been released.

 © 2020 SEGGER Microcontroller GmbH

Message	Description
WM_NOTIFICATION_SCROLLBAR_ADDED	SCROLLBAR has just been added (attached) to an existing window. The window needs to be informed so that it can initialize the scroll bar.
WM_NOTIFICATION_VALUE_CHANGED	Value of SCROLLBAR has changed, either by moving the thumb or by pressing the arrow buttons.

20.26.4 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Message	Description
GUI_KEY_RIGHT	Increments the current value of the SCROLLBAR widget by 1.
GUI_KEY_DOWN	Increments the current value of the SCROLLBAR widget by 1.
GUI_KEY_PGDOWN	Increments the current value of the SCROLLBAR widget by a value which represents 1 page.
GUI_KEY_LEFT	Decrements the current value of the SCROLLBAR widget by 1.
GUI_KEY_UP	Decrements the current value of the SCROLLBAR widget by 1.
GUI_KEY_PGUP	Decrements the current value of the SCROLLBAR widget by a value which represents 1 page.

20.26.5 SCROLLBAR API

The table below lists the available emWin SCROLLBAR-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
SCROLLBAR_AddValue()	Increments or decrements the value of the SCROLLBAR widget by a specified value.
SCROLLBAR_Create()	Creates a SCROLLBAR widget. (Obsolete)
SCROLLBAR_CreateAttached()	Creates a SCROLLBAR widget attached to a window.
SCROLLBAR_CreateEx()	Creates a SCROLLBAR widget.
SCROLLBAR_CreateIndirect()	Creates a SCROLLBAR widget from resource table entry.
SCROLLBAR_CreateUser()	Creates a SCROLLBAR widget using extra bytes as user data.
SCROLLBAR_Dec()	Decrements the current value of the given SCROLLBAR widget by a value of 1.
SCROLLBAR_GetColor()	Returns the color attributes of the SCROLLBAR.
SCROLLBAR_GetDefaultWidth()	Returns the default width of a SCROLLBAR widget.
SCROLLBAR_GetNumItems()	Returns the number of SCROLLBAR items.
SCROLLBAR_GetPageSize()	Returns the page size.
SCROLLBAR_GetThumbSizeMin()	Returns the minimum thumb size in pixels.
SCROLLBAR_GetUserData()	Retrieves the data set with SCROLLBAR_SetUserData().

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
SCROLLBAR_GetValue()	Returns the value of the current item.
SCROLLBAR_Inc()	Increments the current value of the given SCROLLBAR widget by a value of 1.
SCROLLBAR_SetColor()	Sets the color of a SCROLLBAR widget.
SCROLLBAR_SetDefaultColor()	Sets the default colors for new SCROLLBAR widgets.
SCROLLBAR_SetDefaultWidth()	Sets the default width of SCROLLBAR widgets.
SCROLLBAR_SetNumItems()	Sets the number of items for scrolling.
SCROLLBAR_SetPageSize()	Sets the page size.
SCROLLBAR_SetState()	Sets the state of a SCROLLBAR widget.
SCROLLBAR_SetThumbSizeMin()	Sets the minimum thumb size in pixels.
SCROLLBAR_SetUserData()	Sets the extra data of a SCROLLBAR widget.
SCROLLBAR_SetValue()	Sets the value of the given SCROLLBAR widget.
SCROLLBAR_SetWidth()	Sets the width of the given SCROLLBAR widget.

Defines

Group of defines	Description
SCROLLBAR color indexes	Color indexes for SCROLLBAR widget.
SCROLLBAR create flags	Create flags to be used for creating SCROLLBAR widgets.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1 Functions

20.26.5.1.1 SCROLLBAR_AddValue()

Description

Increments or decrements the value of the SCROLLBAR widget by a specified value.

Prototype

```
void SCROLLBAR_AddValue(SCROLLBAR_Handle hObj,
                        int              Add);
```

Parameters

Parameter	Description
hObj	Handle of SCROLLBAR.
Add	Number of items to increment or decrement at one time.

Additional information

The SCROLLBAR widget cannot exceed the value set in `SCROLLBAR_SetNumItems()`. For example, if a window contains 200 items and the scroll bar is currently at value 195, incrementing the bar by 3 items will move it to value 198. However, incrementing by 10 items will only move the bar as far as value 200, which is the maximum value for this particular window.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.2 SCROLLBAR_Create()

> **Note**
>
> This function is **deprecated**, SCROLLBAR_CreateEx() should be used instead.

Description

Creates a SCROLLBAR widget of a specified size at a specified location.

Prototype

```
SCROLLBAR_Handle SCROLLBAR_Create(int     x0,
                                  int     y0,
                                  int     xSize,
                                  int     ySize,
                                  WM_HWIN hParent,
                                  int     Id,
                                  int     WinFlags,
                                  int     SpecialFlags);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the SCROLLBAR widget (in parent coordinates).
y0	Topmost pixel of the SCROLLBAR widget (in parent coordinates).
xSize	Horizontal size of the SCROLLBAR widget (in pixels).
ySize	Vertical size of the SCROLLBAR widget (in pixels).
hParent	Handle of parent window.
Id	ID to be returned.
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
SpecialFlags	Special creation flags. Permitted values are listed under SCROLLBAR_CreateEx().

Return value

Handle of the created SCROLLBAR widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.3 SCROLLBAR_CreateAttached()

Description

Creates a scroll bar which is attached to an existing window.

Prototype

```
SCROLLBAR_Handle SCROLLBAR_CreateAttached(WM_HWIN hParent,
                                          int     SpecialFlags);
```

Parameters

Parameter	Description
hParent	Handle of parent window.
SpecialFlags	Special creation flags. Permitted values are listed under SCROLLBAR_CreateEx().

Return value

Handle of the created SCROLLBAR widget; 0 if the function fails.

Additional information

An attached SCROLLBAR widget is essentially a child window which will position itself on the parent window and operate accordingly.
Vertical attached SCROLLBAR widgets will be automatically placed on the right side of the parent window; horizontal SCROLLBAR widgets on the bottom. Since no more than one horizontal and one vertical SCROLLBAR widget can be attached to a parent window, no ID needs to be passed as parameter. The following fixed ID's will automatically be assigned when an attached SCROLLBAR widget is created: GUI_ID_HSCROLL for a horizontal SCROLLBAR widget, and GUI_ID_VSCROLL for a vertical SCROLLBAR widget.

Example

Creates a list box with an attached SCROLLBAR widget:

```
LISTBOX_Handle hListBox;
hListBox = LISTBOX_Create(ListBox, 50, 50, 100, 100, WM_CF_SHOW);
SCROLLBAR_CreateAttached(hListBox, SCROLLBAR_CF_VERTICAL);
```

Screenshots of above example

The picture on the left shows the list box as it appears after creation. On the right it is shown with the attached vertical scroll bar:

Before	After
	

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.4 SCROLLBAR_CreateEx()

Description

Creates a SCROLLBAR widget of a specified size at a specified location.

Prototype

```
SCROLLBAR_Handle SCROLLBAR_CreateEx(int     x0,
                                    int     y0,
                                    int     xSize,
                                    int     ySize,
                                    WM_HWIN hParent,
                                    int     WinFlags,
                                    int     ExFlags,
                                    int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new SCROLLBAR widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	OR-combination of special creation flags. See *SCROLLBAR create flags* on page 1940 for a list of permitted values.
Id	Window ID of the widget.

Return value

Handle of the created SCROLLBAR widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.5 SCROLLBAR_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element Para of the according GUI_WIDGET_CREATE_INFO structure is not used. The element Flags is used according to the parameter ExFlags of the function SCROLLBAR_CreateEx().

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.6 SCROLLBAR_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function SCROLLBAR_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.7 SCROLLBAR_Dec()

Description

Decrements the current value of the given SCROLLBAR widget by a value of 1.

Prototype

```
void SCROLLBAR_Dec(SCROLLBAR_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.

Additional information

The definition of an “item” is application-specific, although in most cases it is equal to one line. Items are numbered top to bottom or left to right, beginning with a value of 0.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.8 SCROLLBAR_GetColor()

Description

Returns the color attribute of the given SCROLLBAR widget.

Prototype

```
GUI_COLOR SCROLLBAR_GetColor(SCROLLBAR_Handle hObj,
                             int              Index);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.
Index	See *SCROLLBAR color indexes* on page 1939 for a full list of permitted values.

Return value

The color set for the different areas of the SCROLLBAR.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.9 SCROLLBAR_GetDefaultWidth()

Description

Returns the default width used to create a SCROLLBAR widget.

Prototype

```
int SCROLLBAR_GetDefaultWidth(void);
```

Return value

Default width used to create a SCROLLBAR widget.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.10 SCROLLBAR_GetNumItems()

Description

Returns the number of SCROLLBAR items.

Prototype

```
int SCROLLBAR_GetNumItems(SCROLLBAR_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.

Return value

The number of SCROLLBAR items.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.11 SCROLLBAR_GetPageSize()

Description

Returns the page size.

Prototype

```
int SCROLLBAR_GetPageSize(SCROLLBAR_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.

Return value

The number of items specified to be one page.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.12 SCROLLBAR_GetThumbSizeMin()

Description

Returns the minimum thumb size in pixels.

Prototype

```
int SCROLLBAR_GetThumbSizeMin(void);
```

Return value

Minimum thumb size in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.13 SCROLLBAR_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.14 SCROLLBAR_GetValue()

Description

Returns the value of the current item.

Prototype

```
int SCROLLBAR_GetValue(SCROLLBAR_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.

Return value

The value of the current item.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.15 SCROLLBAR_Inc()

Description

Increments the current value of the given SCROLLBAR widget by a value of 1.

Prototype

```
void SCROLLBAR_Inc(SCROLLBAR_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.

Additional information

The definition of an “item” is application-specific, although in most cases it is equal to one line. Items are numbered top to bottom or left to right, beginning with a value of 0.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.16 SCROLLBAR_SetColor()

Before	After
	

Description

Sets the color attribute of the given SCROLLBAR widget.

Prototype

```
GUI_COLOR SCROLLBAR_SetColor(SCROLLBAR_Handle hObj,
                             int              Index,
                             GUI_COLOR        Color);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.
Index	See *SCROLLBAR color indexes* on page 1939 for a full list of permitted values.
Color	Color to be used.

Return value

Previous color used for the given index.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.17 SCROLLBAR_SetDefaultColor()

Description

Sets the default color attributes for new SCROLLBAR widgets.

Prototype

```
GUI_COLOR SCROLLBAR_SetDefaultColor(GUI_COLOR    Color,
                                    unsigned int Index);
```

Parameters

Parameter	Description
Color	Color used as default for newly created SCROLLBAR widgets.
Index	(see table under *SCROLLBAR_SetColor* on page 1929)

Return value

Previous default color.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.18 SCROLLBAR_SetDefaultWidth()

Description

Sets the default width used to create a SCROLLBAR widget.

Prototype

```
int SCROLLBAR_SetDefaultWidth(int DefaultWidth);
```

Parameters

Parameter	Description
DefaultWidth	Default width to use for new SCROLLBAR widgets.

Return value

Previous default width.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.19 SCROLLBAR_SetNumItems()

Description

Sets the number of items for scrolling.

Prototype

```
void SCROLLBAR_SetNumItems(SCROLLBAR_Handle hObj,
                           int              NumItems);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.
NumItems	Number of items to be set.

Additional information

The definition of an “item” is application-specific, although in most cases it is equal to one line. The number of items is the maximum value. The SCROLLBAR widget can not go beyond this value.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.20 SCROLLBAR_SetPageSize()

Description

Sets the page size.

Prototype

```
void SCROLLBAR_SetPageSize(SCROLLBAR_Handle hObj,
                           int              PageSize);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.
PageSize	Page size (in number of items).

Additional information

Page size is specified as the number of items to one page. If the user pages up or down, either with the keyboard or by mouse-clicking in the SCROLLBAR area, the window will be scrolled up or down by the number of items specified as one page.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.21 SCROLLBAR_SetState()

Description

Sets the state of a SCROLLBAR widget.

Prototype

```
void SCROLLBAR_SetState(      SCROLLBAR_Handle   hObj,
                        const WM_SCROLL_STATE  * pState);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.
pState	Pointer to a data structure of type WM_SCROLL_STATE.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.22 SCROLLBAR_SetThumbSizeMin()

Description

Sets the minimum thumb size in pixels.

Prototype

```
int SCROLLBAR_SetThumbSizeMin(int ThumbSizeMin);
```

Parameters

Parameter	Description
ThumbSizeMin	Minimum thumb size to be set.

Return value

Old minimum thumb size in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.23 SCROLLBAR_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.24 SCROLLBAR_SetValue()

Description

Sets the value of the given SCROLLBAR widget.

Prototype

```
void SCROLLBAR_SetValue(SCROLLBAR_Handle hObj,
                        int              v);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.
v	Value to be set.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.1.25 SCROLLBAR_SetWidth()

Description

Sets the width of the given SCROLLBAR widget.

Prototype

```
int SCROLLBAR_SetWidth(SCROLLBAR_Handle hObj,
                       int              Width);
```

Parameters

Parameter	Description
hObj	Handle of a SCROLLBAR widget.
Width	Width to be set.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.2 Defines

20.26.5.2.1 SCROLLBAR color indexes

Description

Color indexes for SCROLLBAR widget.

Definition

```
#define SCROLLBAR_CI_THUMB    0
#define SCROLLBAR_CI_SHAFT    1
#define SCROLLBAR_CI_ARROW    2
```

Symbols

Definition	Description
SCROLLBAR_CI_THUMB	Color of thumb area.
SCROLLBAR_CI_SHAFT	Color of shaft.
SCROLLBAR_CI_ARROW	Color of arrows.

 © 2020 SEGGER Microcontroller GmbH

20.26.5.2.2 SCROLLBAR create flags

Description

These flags can be used when creating a SCROLLBAR widget via `SCROLLBAR_CreateEx()`. These values can be OR-combined.

Definition

```
#define SCROLLBAR_CF_VERTICAL     (1 << 3)
#define SCROLLBAR_CF_FOCUSABLE    (1 << 4)
```

Symbols

Definition	Description
SCROLLBAR_CF_VERTICAL	Creates a vertical SCROLLBAR widget.
SCROLLBAR_CF_FOCUSABLE	Creates a focusable SCROLLBAR widget.

 © 2020 SEGGER Microcontroller GmbH

20.26.6 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_ScrollbarMove.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_ScrollbarMove.c



 © 2020 SEGGER Microcontroller GmbH

20.27 SLIDER: Slider widget

SLIDER widgets are commonly used for modifying values through the use of a slider bar. The widget consists of a slider bar and tick marks beside the bar. These tick marks can be used to snap the slider bar while dragging it. For details about how to use the tick marks for snapping refer to the function SLIDER_SetRange().



Note

All SLIDER-related routines are located in the file(s) SLIDER*.c, SLIDER.h.
All identifiers are prefixed SLIDER.

Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.27.1 Configuration options

Type	Macro	Default	Description
N	SLIDER_BKCOLOR0_DEFAULT	0xc0c0c0	Background color.
N	SLIDER_COLOR0_DEFAULT	0xc0c0c0	Slider (thumb) color.
N	SLIDER_FOCUSCOLOR_DEFAULT	GUI_BLACK	Default color for rendering the focus rectangle.

20.27.2 Predefined IDs

The following symbols define IDs which may be used to make SLIDER widgets distinguishable from creation.

```
#define GUI_ID_SLIDER0    0x130
#define GUI_ID_SLIDER1    0x131
#define GUI_ID_SLIDER2    0x132
#define GUI_ID_SLIDER3    0x133
#define GUI_ID_SLIDER4    0x134
#define GUI_ID_SLIDER5    0x135
#define GUI_ID_SLIDER6    0x136
#define GUI_ID_SLIDER7    0x137
#define GUI_ID_SLIDER8    0x138
#define GUI_ID_SLIDER9    0x139
```

20.27.3 Notification codes

The following events are sent from a SLIDER widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	SLIDER widget has been clicked.
WM_NOTIFICATION_RELEASED	SLIDER widget has been released.

 © 2020 SEGGER Microcontroller GmbH

Message	Description
WM_NOTIFICATION_VALUE_CHANGED	Value of the SLIDER widget has changed by moving the thumb.

20.27.3.1 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Description
GUI_KEY_RIGHT	Increments the current value of the SLIDER widget by one item.
GUI_KEY_LEFT	Decrements the current value of the SLIDER widget by one item.

20.27.4 SLIDER API

The table below lists the available emWin SLIDER-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
SLIDER_Create()	Creates a SLIDER widget. (Obsolete)
SLIDER_CreateEx()	Creates a SLIDER widget.
SLIDER_CreateIndirect()	Creates a SLIDER widget from resource table entry.
SLIDER_CreateUser()	Creates a SLIDER widget using extra bytes as user data.
SLIDER_Dec()	Decrements the value of the SLIDER widget.
SLIDER_EnableFocusRect()	Enables or disables the focus rectangle.
SLIDER_GetBkColor()	Returns the background color of the SLIDER widget.
SLIDER_GetFocusColor()	Return the color focus rectangle of the SLIDER widget.
SLIDER_GetRange()	The function returns the range of the given SLIDER widget.
SLIDER_GetUserData()	Returns the data set with SLIDER_SetUserData().
SLIDER_GetValue()	Returns the current value of the SLIDER widget.
SLIDER_Inc()	Increments the value of the SLIDER widget.
SLIDER_SetBkColor()	Sets the background color of the SLIDER widget.
SLIDER_SetDefaultFocusColor()	Sets the default focus rectangle color for new SLIDER widgets.
SLIDER_SetFocusColor()	Sets the color used to render the focus rectangle of the SLIDER widget.
SLIDER_SetInvertDir()	This function inverts the slider.
SLIDER_SetNumTicks()	Sets the number of tick marks of the SLIDER widget.
SLIDER_SetRange()	Sets the range of the SLIDER widget.
SLIDER_SetUserData()	Sets the extra data of a SLIDER widget.
SLIDER_SetValue()	Sets the current value of the SLIDER widget.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
SLIDER_SetWidth()	Sets the width of the SLIDER widget.

Defines

Group of defines	Description
SLIDER create flags	Create flags for SLIDER widget.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1 Functions

20.27.4.1.1 SLIDER_Create()

> **Note**
>
> This function is **deprecated**, `SLIDER_CreateEx()` should be used instead.

Description

Creates a SLIDER widget of a specified size at a specified location.

Prototype

```
SLIDER_Handle SLIDER_Create(int     x0,
                            int     y0,
                            int     xSize,
                            int     ySize,
                            WM_HWIN hParent,
                            int     Id,
                            int     WinFlags,
                            int     SpecialFlags);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the slider (in parent coordinates).
`y0`	Topmost pixel of the slider (in parent coordinates).
`xSize`	Horizontal size of the slider (in pixels).
`ySize`	Vertical size of the slider (in pixels).
`hParent`	Handle of the parent window.
`Id`	`Id` to be returned
`WinFlags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
`SpecialFlags`	Special creation flag (see indirect creation flag under *`SLIDER_CreateIndirect`* on page 1947).

Return value

Handle of the created SLIDER widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.2 SLIDER_CreateEx()

Description

Creates a SLIDER widget of a specified size at a specified location.

Prototype

```
SLIDER_Handle SLIDER_CreateEx(int     x0,
                              int     y0,
                              int     xSize,
                              int     ySize,
                              WM_HWIN hParent,
                              int     WinFlags,
                              int     ExFlags,
                              int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of the parent window. If 0, the new SLIDER widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *SLIDER create flags* on page 1966.
Id	Window ID of the widget.

Return value

Handle of the created SLIDER widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.3 SLIDER_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element Para of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element Flags is used according to the parameter ExFlags of the function `SLIDER_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.4 SLIDER_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function SLIDER_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.5 SLIDER_Dec()

Description

Decrements the current value of the SLIDER widget by one item.

Prototype

```
void SLIDER_Dec(SLIDER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.6 SLIDER_EnableFocusRect()

Description

This function enables or disables the rectangle shown when a slider has the focus.

Prototype

```
void SLIDER_EnableFocusRect(SLIDER_Handle hObj,
                            int           OnOff);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.
OnOff	Enables (1) or disables (0) the focus rect.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.7 SLIDER_GetBkColor()

Description

Returns the background color of the SLIDER widget.

Prototype

```
GUI_COLOR SLIDER_GetBkColor(SLIDER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.

Return value

The background color of the SLIDER widget.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.8 SLIDER_GetFocusColor()

Description

Return the color focus rectangle of the SLIDER widget.

Prototype

```
GUI_COLOR SLIDER_GetFocusColor(SLIDER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.

Return value

The color of the focus rectangle of the SLIDER widget.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.9 SLIDER_GetRange()

Description

The function returns the range of the given SLIDER widget.

Prototype

```
void SLIDER_GetRange(SLIDER_Handle   hObj,
                     int           * pMin,
                     int           * pMax);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.
pMin	Pointer to an int to be used to return the min-value. Should not be NULL.
pMax	Pointer to an int to be used to return the max-value. Should not be NULL.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.10 SLIDER_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.11 SLIDER_GetValue()

Description

Returns the current value of the SLIDER widget.

Prototype

```
int SLIDER_GetValue(SLIDER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.

Return value

The current value of the SLIDER widget.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.12 SLIDER_Inc()

Description

Increments the current value of the SLIDER widget by one item.

Prototype

```
void SLIDER_Inc(SLIDER_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.13 SLIDER_SetBkColor()

Description

Sets the background color of the SLIDER widget.

Prototype

```
void SLIDER_SetBkColor(SLIDER_Handle hObj,
                       GUI_COLOR     Color);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.
Color	Color to be used for the background. (range 0x000000 and 0xFFFFFF or a valid color define) GUI_INVALID_COLOR to make background transparent.

Additional information

The background of this widget can either be filled with any available color or transparent. If a valid RGB color is specified, the background is filled with the color, otherwise the background (typically the content of the parent window) is visible. If the background is transparent, the widget is treated as transparent window, otherwise as non-transparent window. Note that using a background color allows more efficient (faster) rendering.

This widget is per default a transparent window. The appearance of a transparent windows background depends on the appearance of the parent window. When a transparent window needs to be redrawn first the background will be drawn by sending a WM_PAINT message to the parent window.

If using this function with a valid color the status of the window will be changed from transparent to non transparent and if the window needs to be redrawn the background will be filled with the given color.

If GUI_INVALID_COLOR is passed to the function the status will be changed from non transparent to transparent.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.14 SLIDER_SetDefaultFocusColor()

Description

Sets the default focus rectangle color for new SLIDER widgets.

Prototype

```
GUI_COLOR SLIDER_SetDefaultFocusColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Default color to be used for new slider bars.

Return value

Previous default focus rectangle color.

Additional information

For more information, refer to *SLIDER_SetFocusColor* on page 1959.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.15 SLIDER_SetFocusColor()

Before	After
	

Description

Sets the color used to render the focus rectangle of the SLIDER widget.

Prototype

```
GUI_COLOR SLIDER_SetFocusColor(SLIDER_Handle hObj,
                               GUI_COLOR     Color);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.
Color	Color to be used for the focus rectangle.

Return value

Previous color of the focus rectangle.

Additional information

The focus rectangle is only visible if the widget has the input focus.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.16 SLIDER_SetInvertDir()

Description

This function inverts the slider.

Prototype

```
void SLIDER_SetInvertDir(SLIDER_Handle hObj,
                         int           OnOff);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.
OnOff	Enables (1) or disables (0) the inversion of the slider widget.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.17 SLIDER_SetNumTicks()

Before	After
	

Description

Sets the number of tick marks of the SLIDER widget.

Prototype

```
void SLIDER_SetNumTicks(SLIDER_Handle hObj,
                        int           NumTicks);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.
NumTicks	Number of tick marks drawn.

Additional information

After creating a SLIDER widget the default number of tick marks is 10. The tick marks have no effect to snap the slider bar while dragging it.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.18 SLIDER_SetRange()

Description

Sets the range of the SLIDER widget.

Prototype

```
void SLIDER_SetRange(SLIDER_Handle hObj,
                     int           Min,
                     int           Max);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.
Min	Minimum value.
Max	Maximum value.

Additional information

After creating a SLIDER widget the default range is set to 0 - 100.

Examples

If a value should be modified in the range of 0 - 2499 set the range as follows:

```
SLIDER_SetRange(hSlider, 0, 2499);
```

If a value should be modified in the range of 100 - 499 set the range as follows:

```
SLIDER_SetRange(hSlider, 100, 499);
```

If a value should be modified in the range of 0 to 5000 and the slider bar should change the value in steps of 250 set the range and the tick marks as follows. The result returned by SLIDER_GetValue() should be multiplied with 250:

```
SLIDER_SetRange(hSlider, 0, 20);
SLIDER_SetNumTicks(hSlider, 21);
```

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.19 SLIDER_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.20 SLIDER_SetValue()

Description

Sets the current value of the SLIDER widget.

Prototype

```
void SLIDER_SetValue(SLIDER_Handle hObj,
                     int           v);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.
v	Value to be set.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.1.21 SLIDER_SetWidth()

Before	After
	

Description

Sets the width of the SLIDER widget.

Prototype

```
void SLIDER_SetWidth(SLIDER_Handle hObj,
                     int           Width);
```

Parameters

Parameter	Description
hObj	Handle of SLIDER widget.
Width	Width to be set.

 © 2020 SEGGER Microcontroller GmbH

20.27.4.2 Defines

20.27.4.2.1 SLIDER create flags

Description

Create flags for SLIDER widgets which define the rotation of a SLIDER.

Definition

```
#define SLIDER_CF_HORIZONTAL    (0)
#define SLIDER_CF_VERTICAL      (1 << 3)
```

Symbols

Definition	Description
SLIDER_CF_HORIZONTAL	Creates a horizontal slider (default).
SLIDER_CF_VERTICAL	Creates a vertical slider.

 © 2020 SEGGER Microcontroller GmbH

20.27.5 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `DIALOG_SliderColor.c`

Note that several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of DIALOG_SliderColor.c



 © 2020 SEGGER Microcontroller GmbH

20.28 SPINBOX: Spinning box widget

SPINBOX widgets are used to manage values which need to be adjustable in a fast but still precise manner. A SPINBOX consists of 2 buttons and an embedded EDIT widget.

> **Note**
>
> All SPINBOX-related routines are located in the file(s) `SPINBOX*.c` and `SPINBOX.h`. All identifiers are prefixed SPINBOX.



Skinning...



...is available for this widget. The screenshot above shows the widget using the default skin. Details can be found in the chapter *Skinning* on page 2288.

20.28.1 Configuration options

Type	Macro	Default	Description
N	SPINBOX_DEFAULT_BUTTON_BKCOLOR0	0xAAAAAA	Background color for the button state disabled.
N	SPINBOX_DEFAULT_BUTTON_BKCOLOR1	GUI_WHITE	Background color for the button state pressed.
N	SPINBOX_DEFAULT_BUTTON_BKCOLOR2	GUI_LIGHTGRAY	Background color for the button state unpressed.
N	SPINBOX_DEFAULT_BUTTON_UCOLOR0	0xAAAAAA	Background color for the button state disabled.
N	SPINBOX_DEFAULT_BUTTON_UCOLOR1	GUI_WHITE	Background color for the button state pressed.
N	SPINBOX_DEFAULT_BUTTON_UCOLOR2	GUI_LIGHTGRAY	Background color for the button state unpressed.
N	SPINBOX_DEFAULT_BUTTON_LCOLOR0	0xAAAAAA	Background color for the button state disabled.
N	SPINBOX_DEFAULT_BUTTON_LCOLOR1	GUI_WHITE	Background color for the button state pressed.
N	SPINBOX_DEFAULT_BUTTON_LCOLOR2	GUI_LIGHTGRAY	Background color for the button state unpressed.
N	SPINBOX_DEFAULT_BUTTON_OCOLOR0	0xAAAAAA	Background color for the button state disabled.
N	SPINBOX_DEFAULT_BUTTON_OCOLOR1	GUI_WHITE	Background color for the button state pressed.
N	SPINBOX_DEFAULT_BUTTON_OCOLOR2	GUI_LIGHTGRAY	Background color for the button state unpressed.
N	SPINBOX_DEFAULT_BKCOLOR0	0xC0C0C0	Background color for the edit state enabled.
N	SPINBOX_DEFAULT_BKCOLOR1	GUI_WHITE	Background color for the edit state disabled.

 © 2020 SEGGER Microcontroller GmbH

Type	Macro	Default	Description
N	SPINBOX_DEFAULT_TEXTCOLOR0	0xC0C0C0	Background color for the edit state enabled.
N	SPINBOX_DEFAULT_TEXTCOLOR1	GUI_WHITE	Background color for the edit state disabled.
N	SPINBOX_DEFAULT_TRIANGLE_COLOR0	0xAAAAAA	Background color for the button state disabled.
N	SPINBOX_DEFAULT_TRIANGLE_COLOR1	GUI_WHITE	Background color for the button state pressed.
N	SPINBOX_DEFAULT_TRIANGLE_COLOR2	GUI_LIGHTGRAY	Background color for the button state unpressed.
N	SPINBOX_DEFAULT_STEP	1	Value will be increased/decreased by this amount when a button is clicked.
N	SPINBOX_DEFAULT_BUTTON_SIZE	0	X-Size of the buttons.
N	SPINBOX_DEFAULT_EDGE	SPINBOX_EDGE_RIGHT	Determines the position of the buttons. See table below.
N	SPINBOX_TIMER_PERIOD_START	400	Once a button is pressed for this amount of time, a timer is created to increase/decrease the value continuously.
N	SPINBOX_TIMER_PERIOD	50	Once the timer is created values are adjusted at intervals of this amount of time.

Possible values to be defined as SPINBOX_DEFAULT_EDGE	
SPINBOX_EDGE_LEFT	Buttons are displayed on the left edge of the widget.
SPINBOX_EDGE_RIGHT	Buttons are displayed on the right edge of the widget.

20.28.2 Predefined IDs

The following symbols define IDs which may be used to make SPINBOX widgets distinguishable from creation.

```
#define GUI_ID_SPINBOX0    0x280
#define GUI_ID_SPINBOX1    0x281
#define GUI_ID_SPINBOX2    0x282
#define GUI_ID_SPINBOX3    0x283
#define GUI_ID_SPINBOX4    0x284
#define GUI_ID_SPINBOX5    0x285
#define GUI_ID_SPINBOX6    0x286
#define GUI_ID_SPINBOX7    0x287
#define GUI_ID_SPINBOX8    0x288
#define GUI_ID_SPINBOX9    0x289
```

20.28.3 Notification codes

The following events are sent from the spinbox widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	Button has been clicked.
WM_NOTIFICATION_RELEASED	Button has been released.
WM_NOTIFICATION_MOVED_OUT	Pointer has been moved out of the widget area.
WM_NOTIFICATION_VALUE_CHANGED	The value of the SPINBOX widget has changed.

 © 2020 SEGGER Microcontroller GmbH

20.28.4 Keyboard reaction

The widget is able to receive the input focus. All key events are forwarded to the embedded edit widget. Detailed information can be taken from the EDIT widget section.

20.28.5 SPINBOX API

The table below lists the available emWin SPINBOX-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
SPINBOX_CreateEx()	Creates a SPINBOX widget.
SPINBOX_CreateIndirect()	Creates a SPINBOX widget. (Obsolete)
SPINBOX_CreateUser()	Creates a SPINBOX widget using extra bytes as user data.
SPINBOX_EnableBlink()	Enables/disables blinking of the cursor.
SPINBOX_GetBkColor()	Returns the background color of the SPINBOX widget.
SPINBOX_GetButtonBkColor()	Returns the background color of the buttons.
SPINBOX_GetDefaultButtonSize()	Returns the default x-size of the buttons.
SPINBOX_GetEditHandle()	Returns the handle to the attached EDIT widget.
SPINBOX_GetFont()	Returns the font of the SPINBOX widget.
SPINBOX_GetTextColor()	Returns the text color.
SPINBOX_GetUserData()	Retrieves the data which was previously set with SPINBOX_SetUserData().
SPINBOX_GetValue()	Returns the value of the SPINBOX widget.
SPINBOX_SetBkColor()	Sets the background color of the SPINBOX widget.
SPINBOX_SetButtonBkColor()	Sets the background color of the buttons.
SPINBOX_SetButtonSize()	Sets the button size of the given SPINBOX widget.
SPINBOX_SetDefaultButtonSize()	Sets the default x-size of the buttons.
SPINBOX_SetEdge()	Sets the edge to display the buttons on.
SPINBOX_SetEditMode()	Sets the spinbox widget to either edit or step mode.
SPINBOX_SetFont()	Sets the font used to display the value.
SPINBOX_SetRange()	Sets the minimum and maximum value.
SPINBOX_SetStep()	Sets the value to be used for incrementing and decrementing in 'Step' mode.
SPINBOX_SetTextColor()	Sets the color of the displayed value.
SPINBOX_SetTimerPeriod()	This function sets the time it takes before the SPINBOX widget starts increasing or decreasing its value automatically when a button keeps beeing pressed.
SPINBOX_SetUserData()	Stores user data using the extra bytes which were reserved by SPINBOX_CreateUser().
SPINBOX_SetValue()	Sets the value of the SPINBOX.

 © 2020 SEGGER Microcontroller GmbH

Defines

Group of defines	Description
SPINBOX color indexes	Color indexes used by SPINBOX widgets.
SPINBOX edge flags	Flags used by SPINBOX_SetEdge().
SPINBOX edit mode flags	Flags used by SPINBOX_SetEditMode().
SPINBOX timer indexes	Timer indexes used by SPINBOX_SetTimerPeriod().

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1 Functions

20.28.5.1.1 SPINBOX_CreateEx()

Description

Creates a SPINBOX widget.

Prototype

```
SPINBOX_Handle SPINBOX_CreateEx(int     x0,
                                int     y0,
                                int     xSize,
                                int     ySize,
                                WM_HWIN hParent,
                                int     WinFlags,
                                int     Id,
                                int     Min,
                                int     Max);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of the parent window. If 0, the widget will be created as a child of the top-level window (desktop).
WinFlags	Window create flags. In order to make the widget visible immediately WM_CF_SHOW should be used. The complete list of available parameters can be found under *Window create flags* on page 958.
Id	Window ID to be set for the widget.
Min	Minimum permitted value.
Max	Maximum permitted value.

Return value

Handle of the created SPINBOX widget. If an error occurred during creation, 0 is returned.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.2 SPINBOX_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Flags` of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The upper 16 bit of the element `Para` are used according to the parameter `Max` of the function `SPINBOX_CreateEx()`. The lower 16 bit of the element Para are used according to the parameter Min of the function `SPINBOX_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.3 SPINBOX_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function SPINBOX_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.4 SPINBOX_EnableBlink()

Description

Enables/disables blinking of the cursor.

Prototype

```
void SPINBOX_EnableBlink(SPINBOX_Handle hObj,
                         int            Period,
                         int            OnOff);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
Period	Period in which the cursor is turned off and on.
OnOff	1 enables blinking, 0 disables blinking.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.5 SPINBOX_GetBkColor()

Description

Returns the background color of the SPINBOX widget.

Prototype

```
GUI_COLOR SPINBOX_GetBkColor(SPINBOX_Handle hObj,
                             unsigned int   Index);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
Index	See *SPINBOX color indexes* on page 1997 for a full list of permitted values.

Return value

Background color of the SPINBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.6 SPINBOX_GetButtonBkColor()

Description

Returns the background color of the buttons.

Prototype

```
GUI_COLOR SPINBOX_GetButtonBkColor(SPINBOX_Handle hObj,
                                   unsigned int   Index);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
Index	See *SPINBOX color indexes* on page 1997 for a full list of permitted values.

Return value

Background color of the buttons.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.7 SPINBOX_GetDefaultButtonSize()

Description

Returns the default x-size of the buttons.

Prototype

```
U16 SPINBOX_GetDefaultButtonSize(void);
```

Return value

Default x-size of the buttons.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.8 SPINBOX_GetEditHandle()

Description

Returns the handle to the attached EDIT widget.

Prototype

```
EDIT_Handle SPINBOX_GetEditHandle(SPINBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.

Return value

Handle of the attached EDIT widget.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.9 SPINBOX_GetFont()

Description

Returns the font of the SPINBOX widget.

Prototype

```
GUI_FONT *SPINBOX_GetFont(SPINBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.

Return value

A pointer to the font of the SPINBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.10 SPINBOX_GetTextColor()

Description

Returns the color of the displayed value.

Prototype

```
GUI_COLOR SPINBOX_GetTextColor(SPINBOX_Handle hObj,
                               unsigned int   Index);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
Index	See *SPINBOX color indexes* on page 1997 for a full list of permitted values.

Return value

The color of the value to be displayed.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.11 SPINBOX_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.12 SPINBOX_GetValue()

Description

Returns the value of the SPINBOX widget.

Prototype

```
I32 SPINBOX_GetValue(SPINBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.

Return value

Value of the SPINBOX widget.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.13 SPINBOX_SetBkColor()

Before	After
	

Description

Sets the background color of the SPINBOX widget.

Prototype

```
void SPINBOX_SetBkColor(SPINBOX_Handle hObj,
                        unsigned int   Index,
                        GUI_COLOR      Color);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
Index	See *SPINBOX color indexes* on page 1997 for a full list of permitted values.
Color	Color to be used for the background.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.14 SPINBOX_SetButtonBkColor()

Before	After
	

Description

Sets the background color of the buttons.

Prototype

```
void SPINBOX_SetButtonBkColor(SPINBOX_Handle hObj,
                              unsigned int   Index,
                              GUI_COLOR      Color);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
Index	See *SPINBOX color indexes* on page 1997 for a full list of permitted values.
Color	Color to be used for the background.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.15 SPINBOX_SetButtonSize()

Before	After
	

Description

Sets the button size of the given SPINBOX widget.

Prototype

```
void SPINBOX_SetButtonSize(SPINBOX_Handle hObj,
                           unsigned       ButtonSize);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
ButtonSize	Button size in pixels to be used.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.16 SPINBOX_SetDefaultButtonSize()

Before	After
	

Description

Sets the default x-size of the buttons.

Prototype

```
void SPINBOX_SetDefaultButtonSize(U16 ButtonSize);
```

Parameters

Parameter	Description
x	New default x-size of the buttons.

Additional information

If the default button size is set to 0, the size of the button is determined automatically on creation.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.17 SPINBOX_SetEdge()

Before	After
	

Description

Sets the edge to display the buttons on.

Prototype

```
void SPINBOX_SetEdge(SPINBOX_Handle hObj,
                     U8             Edge);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
Edge	See *SPINBOX edge flags* on page 1998 for a full list of permitted values.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.18 SPINBOX_SetEditMode()

Description

Sets the spinbox widget to either edit or step mode.

Prototype

```
void SPINBOX_SetEditMode(SPINBOX_Handle hObj,
                         U8             EditMode);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
EditMode	See *SPINBOX edit mode flags* on page 1999.

Additional information

The widget supports the 'Step' mode (default) and the 'Edit' mode. 'Step' mode means each time one of the buttons is pressed the value of the box is incremented or decremented by the step value. 'Edit' mode means each single digit can be modified separately. If 'Edit' mode is selected the EDIT field becomes editable and a cursor appears. When pressing a button the focused digit will be incremented or decremented by 1. In 'Edit' mode the EDIT field also accepts digits as keyboard input.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.19 SPINBOX_SetFont()

Before	After
	

Description

Sets the font used to display the value.

Prototype

```
void SPINBOX_SetFont(      SPINBOX_Handle   hObj,
                     const GUI_FONT       * pFont);
```

Parameters

Parameter	Description
hObj	Handle to the SPINBOX widget.
pFont	Pointer to the font to be used.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.20 SPINBOX_SetRange()

Description

Sets the minimum and maximum value.

Prototype

```
void SPINBOX_SetRange(SPINBOX_Handle hObj,
                      I32            Min,
                      I32            Max);
```

Parameters

Parameter	Description
hObj	Handle to the SPINBOX widget.
Min	Minimum value.
Max	Maximum value.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.21 SPINBOX_SetStep()

Description

Sets the value to be used for incrementing and decrementing in 'Step' mode.

Prototype

```
U16 SPINBOX_SetStep(SPINBOX_Handle hObj,
                    U16            Step);
```

Parameters

Parameter	Description
hObj	Handle to the SPINBOX widget.
Step	Value to be used.

Return value

Previous used step value.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.22 SPINBOX_SetTextColor()

Before	After
	

Description

Sets the color of the displayed value.

Prototype

```
void SPINBOX_SetTextColor(SPINBOX_Handle hObj,
                          unsigned int   Index,
                          GUI_COLOR      Color);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
Index	See *SPINBOX color indexes* on page 1997 for a full list of permitted values.
Color	Color to be set for the text.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.23 SPINBOX_SetTimerPeriod()

Description

This function sets the time it takes before the SPINBOX widget starts increasing or decreasing its value automatically when a button keeps beeing pressed.

Prototype

```
void SPINBOX_SetTimerPeriod(SPINBOX_Handle hObj,
                            U32            Index,
                            U32            Period);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
Index	Timer index. See *SPINBOX timer indexes* on page 2000.
Period	Color to be set for the text.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.24 SPINBOX_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.1.25 SPINBOX_SetValue()

Before	After
	

Description

Sets the value of the SPINBOX.

Prototype

```
void SPINBOX_SetValue(SPINBOX_Handle hObj,
                      I32            Value);
```

Parameters

Parameter	Description
hObj	Handle of the SPINBOX widget.
v	Value to be set.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.2 Defines

20.28.5.2.1 SPINBOX color indexes

Description

Color indexes used for SPINBOX widgets.

Definition

```
#define SPINBOX_CI_DISABLED    0
#define SPINBOX_CI_ENABLED     1
#define SPINBOX_CI_PRESSED     2
```

Symbols

Definition	Description
SPINBOX_CI_DISABLED	Color for disabled state.
SPINBOX_CI_ENABLED	Color for enabled state.
SPINBOX_CI_PRESSED	Color for pressed state (only for buttons).

 © 2020 SEGGER Microcontroller GmbH

20.28.5.2.2 SPINBOX edge flags

Description

Flags used by the routine `SPINBOX_SetEdge()` to define the button placement of a SPINBOX widget.

Definition

```
#define SPINBOX_EDGE_RIGHT     0
#define SPINBOX_EDGE_LEFT      1
#define SPINBOX_EDGE_CENTER    2
```

Symbols

Definition	Description
SPINBOX_EDGE_RIGHT	Buttons are displayed on the left and the right edge of the widget.
SPINBOX_EDGE_LEFT	Buttons are displayed on the left edge of the widget.
SPINBOX_EDGE_CENTER	Buttons are displayed on the right edge of the widget.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.2.3 SPINBOX edit mode flags

Description

Flags used for activating edit mode for a SPINBOX widget. For more information, refer to `SPINBOX_SetEditMode()`.

Definition

```
#define SPINBOX_EM_STEP    0
#define SPINBOX_EM_EDIT    1
```

Symbols

Definition	Description
SPINBOX_EM_STEP	Pressing a button adds or subtracts the step value.
SPINBOX_EM_EDIT	Pressing a button increments or decrements a digit.

 © 2020 SEGGER Microcontroller GmbH

20.28.5.2.4 SPINBOX timer indexes

Description

Timer indexes used by the routine `SPINBOX_SetTimerPeriod()`.

Definition

```
#define SPINBOX_TI_TIMERSTART    0
#define SPINBOX_TI_TIMERINC      1
```

Symbols

Definition	Description
SPINBOX_TI_TIMERSTART	Time it takes to start auto increase/decrease of its value.
SPINBOX_TI_TIMERINC	Time between two increments/decrements.

 © 2020 SEGGER Microcontroller GmbH

20.28.6 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_Spinbox.c`

Screenshot of WIDGET_Spinbox.c



 © 2020 SEGGER Microcontroller GmbH

20.29 SWIPELIST: Swipelist widget

A SWIPELIST widget enables smooth scrolling of a list by swiping over the touchscreen or any other pointer input device (PID). Each SWIPELIST item could show several lines of text and/or a bitmap. It is also possible to assign one or more windows/widgets to each item. When swiping over the touchscreen the list follows the PID. After releasing the PID the list is decelerated smoothly until it stops. The interface of the SWIPELIST allows per default reacting on click-, release- and selection change events.

> **Note**
>
> All SWIPELIST-related routines are located in the file(s) `SWIPELIST*.c`, `SWIPELIST.h`. All identifiers are prefixed SWIPELIST.

Configuration

Prior of using the SWIPELIST widget it is necessary to enable motion support of emWin by a call of `WM_MOTION_Enable(1)`.

20.29.1 Structure of the SWIPELIST widget

The following diagram shows the detailed structure and look of an item of the SWIPELIST widget:



Information about the different diagram indices can be found in the table below.

Details	Description
B	Bottom border used for all items. (Default: 5 pixels)
BS	Size between bitmap and text (bitmap space) used for all items. (Default: 5 pixels)
L	Left border used for all items. (Default: 5 pixels)
R	Right border used for all items. (Default: 5 pixels)

 © 2020 SEGGER Microcontroller GmbH

Details	Description
S	Separator line can be set individual for all items. (Default: 1 pixel)
T	Top border used for all items. (Default: 5 pixels)

 © 2020 SEGGER Microcontroller GmbH

The following diagram shows the structure and look of a SWIPELIST widget:



SWIPELIST widgets consists of items. Separator items are items with different properties.

Details	Description
I_0	Separator item of SWIPELIST widget. (ItemIndex = 0) + text (alignment: vertical center, left)

 © 2020 SEGGER Microcontroller GmbH

Details	Description
I_1	Item of SWIPELIST widget. (ItemIndex = 1) + bitmap (alignment: top, right) + text (alignment: bottom, left)
I_2	Item of SWIPELIST widget. (ItemIndex = 2) + bitmap (alignment: bottom, left) + text (alignment: Top, left)
I_3	Item of SWIPELIST widget. (ItemIndex = 3) + bitmap (alignment: top, horizontal center) + Text (alignment: top, horizontal center)
I_4	Item of SWIPELIST widget. (ItemIndex = 4) + bitmap (alignment: bottom, horizontal center) + text (alignment: bottom, right)
S	Separator line can be set individual for all items. (Default: 1 pixel)

20.29.2 Difference between separator items and items

Separator items are useful to group items by different topics. They will be drawn (by default) with different fonts and colors.
All API-functions can be used for separator items, too.

	Item	Separator item
Fonts	One font for the header text. One font for the text.	One font for all texts.
Font colors	Two colors for the header text (SEL & UNSEL) Two colors for the text (SEL & UNSEL)	One color for all texts.
Background color	Two colors for background (SEL & UNSEL)	One color for the background.
Selection	One item can be selected at same time. This item change the look (SEL-colors)	Can not be selected.
Notification codes	WM_NOTIFICATION_CLICKED WM_NOTIFICATION_RELEASED WM_NOTIFICATION_SEL_CHANGED	None.

20.29.3 Configuration options

Type	Macro	Default	Description
N	SWIPELIST_DEFAULT_BITMAP_SPACE	5	Space between text and bitmap.
N	SWIPELIST_DEFAULT_BORDERSIZE_B	5	Border of bottom for items.
N	SWIPELIST_DEFAULT_BORDERSIZE_L	5	Border of left side for items.
N	SWIPELIST_DEFAULT_BORDERSIZE_R	5	Border of right side for items.
N	SWIPELIST_DEFAULT_BORDERSIZE_T	5	Border of top for items.
N	SWIPELIST_DEFAULT_ITEM_BK_COLOR_UNSEL	GUI_BLACK	Background color for unselected items.
N	SWIPELIST_DEFAULT_ITEM_BK_COLOR_SEL	GUI_BLUE	Background color for selected item.

 © 2020 SEGGER Microcontroller GmbH

Type	Macro	Default	Description
N	SWIPELIST_DEFAULT_ITEM_HEADER_COLOR_UNSEL	GUI_WHITE	Header text color for unselected items.
N	SWIPELIST_DEFAULT_ITEM_HEADER_COLOR_SEL	GUI_WHITE	Header text color for selected item.
S	SWIPELIST_DEFAULT_ITEM_HEADER_FONT	&GUI_Font16_1	Font for item header text.
N	SWIPELIST_DEFAULT_ITEM_SEP_COLOR	GUI_GRAY	Color of the separator line for items.
N	SWIPELIST_DEFAULT_ITEM_SEP_SIZE	1	Size of the separator line for items.
N	SWIPELIST_DEFAULT_ITEM_TEXT_COLOR_UNSEL	GUI_GRAY	Text color for unselected items.
N	SWIPELIST_DEFAULT_ITEM_TEXT_COLOR_SEL	GUI_GRAY	Text color for selected item.
S	SWIPELIST_DEFAULT_ITEM_TEXT_FONT	&GUI_Font13_1	Font for item text.
N	SWIPELIST_DEFAULT_SEP_ITEM_BK_COLOR	GUI_GRAY	Background color for separator item.
S	SWIPELIST_DEFAULT_SEP_ITEM_FONT	&GUI_Font20_1	Font for separator item.
N	SWIPELIST_DEFAULT_SEP_ITEM_TEXT_COLOR	GUI_WHITE	Text color for separator item.
N	SWIPELIST_DEFAULT_TEXT_ALIGN	GUI_TA_LEFT | GUI_TA_VCENTER	Text alignment for separator items and items.

20.29.4 Predefined IDs

The following symbols define IDs which may be used to make SWIPELIST widgets distinguishable from creation.

```
#define GUI_ID_SWIPELIST0    0x320
#define GUI_ID_SWIPELIST1    0x321
#define GUI_ID_SWIPELIST2    0x322
#define GUI_ID_SWIPELIST3    0x323
#define GUI_ID_SWIPELIST4    0x324
#define GUI_ID_SWIPELIST5    0x325
#define GUI_ID_SWIPELIST6    0x326
#define GUI_ID_SWIPELIST7    0x327
#define GUI_ID_SWIPELIST8    0x328
#define GUI_ID_SWIPELIST9    0x329
```

20.29.5 Notification codes

The following events are sent from a SWIPELIST widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	Item of SWIPELIST widget has been clicked.
WM_NOTIFICATION_RELEASED	Item of SWIPELIST widget has been released.
WM_NOTIFICATION_SEL_CHANGED	Item of SWIPELIST widget has been clicked and the pointer has been moved out of the item area.

 © 2020 SEGGER Microcontroller GmbH

20.29.6 SWIPELIST API

The table below lists the available emWin SWIPELIST-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
SWIPELIST_AddItem()	Adds a new item.
SWIPELIST_AddItemText()	Adds a text to the item.
SWIPELIST_AddSepItem()	Adds a new separator item.
SWIPELIST_CreateEx()	Creates a SWIPELIST widget.
SWIPELIST_CreateIndirect()	Creates a SWIPELIST widget from a resource table entry.
SWIPELIST_CreateUser()	Creates a SWIPELIST widget using extra bytes as user data.
SWIPELIST_DeleteItem()	Deletes an item from the SWIPELIST widget.
SWIPELIST_GetBitmap()	Returns a pointer to the optional bitmap of the item.
SWIPELIST_GetBitmapSpace()	Returns the space between text and bitmap.
SWIPELIST_GetBkColor()	Returns the background color.
SWIPELIST_GetBorderSize()	Returns the size of the border.
SWIPELIST_GetDefaultBitmapSpace()	Returns the default space between text and bitmap.
SWIPELIST_GetDefaultBkColor()	Returns the default background color.
SWIPELIST_GetDefaultBorderSize()	Returns the default border size.
SWIPELIST_GetDefaultFont()	Returns a pointer to the default font.
SWIPELIST_GetDefaultSepColor()	Returns the default color of the separator line.
SWIPELIST_GetDefaultSepSize()	Returns the default size of the separator line.
SWIPELIST_GetDefaultTextColor()	Returns the default color of the text.
SWIPELIST_GetDefaultTextAlign()	Returns the default alignment of the text.
SWIPELIST_GetDefaultThreshold()	Returns the default threshold value.
SWIPELIST_GetFont()	Returns a pointer to the font.
SWIPELIST_GetItemSize()	Returns the size (in pixels) of the given item.
SWIPELIST_GetItemUserData()	Retrieves the previously stored user data from a given item.
SWIPELIST_GetNumItems()	Returns the number of items.
SWIPELIST_GetNumText()	Returns the number of texts in a item.
SWIPELIST_GetReleasedItem()	Returns the item index of the last released item.
SWIPELIST_GetScrollPos()	Returns the scroll position of the widget.
SWIPELIST_GetSelItem()	Returns the current selected item index of the given SWIPELIST widget. Returns the current selected item.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
SWIPELIST_GetSepColor()	Returns the color of the separator line for the given item.
SWIPELIST_GetSepSize()	Returns the size of the separator line.
SWIPELIST_GetText()	Returns the text of the given item.
SWIPELIST_GetTextAlign()	Returns the text alignment.
SWIPELIST_GetTextColor()	Returns the color of the text.
SWIPELIST_GetThreshold()	Returns the threshold value of the widget.
SWIPELIST_GetUserData()	Retrieves the data set with SWIPELIST_SetUserData().
SWIPELIST_IsSepItem()	Returns if the given item is a separator item.
SWIPELIST_ItemAttachWindow()	Attaches a window to the item.
SWIPELIST_ItemDetachWindow()	Detaches a window.
SWIPELIST_OwnerDraw()	Default function for drawing the SWIPELIST widget.
SWIPELIST_SetAttachedWindowPos()	Sets the position of an attached window.
SWIPELIST_SetBitmap()	Sets a pointer to the bitmap.
SWIPELIST_SetBitmapSpace()	Sets the space between text and bitmap.
SWIPELIST_SetBkColor()	Sets the background color.
SWIPELIST_SetBorderSize()	Sets the size of the border.
SWIPELIST_SetDefaultBitmapSpace()	Sets the default space between text and bitmap.
SWIPELIST_SetDefaultBkColor()	Sets the default background color.
SWIPELIST_SetDefaultBorderSize()	Sets the default size of the border.
SWIPELIST_SetDefaultFont()	Sets a pointer to the font used as default.
SWIPELIST_SetDefaultSepColor()	Sets the default color of the separator line.
SWIPELIST_SetDefaultSepSize()	Sets the default size of the separator line.
SWIPELIST_SetDefaultTextColor()	Sets the default color of the text.
SWIPELIST_SetDefaultTextAlign()	Sets the default alignment of the text.
SWIPELIST_SetDefaultThreshold()	Sets the default threshold value.
SWIPELIST_SetFont()	Sets a pointer to the used font.
SWIPELIST_SetItemSize()	Sets the size of the item.
SWIPELIST_SetItemUserData()	Stores user data in a specific item.
SWIPELIST_SetOwnerDraw()	Sets the SWIPELIST widget to be owner drawn.
SWIPELIST_SetScrollPos()	Sets the scroll position of the SWIPELIST widget.
SWIPELIST_SetScrollPosItem()	Sets the scroll position to an item.
SWIPELIST_SetSepColor()	Sets the color of a separator line.
SWIPELIST_SetSepSize()	Sets the size of a separator line.
SWIPELIST_SetText()	Sets a text.
SWIPELIST_SetTextAlign()	Sets alignment of the text.
SWIPELIST_SetTextColor()	Sets color of the text.
SWIPELIST_SetThreshold()	Sets the threshold value.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
SWIPELIST_SetUserData()	Sets the extra data of a SWIPELIST widget.

Defines

Group of defines	Description
SWIPELIST background color indexes	Color indexes for the background of SWIPELIST widgets.
SWIPELIST bitmap alignment flags	Flags used by SWIPELIST_SetBitmap().
SWIPELIST border indexes	Border indexes used by SWIPELIST_SetBorderSize().
SWIPELIST font indexes	Font indexes for SWIPELIST widgets.
SWIPELIST item color indexes	Color indexes for SWIPELIST widgets.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1 Functions

20.29.6.1.1 SWIPELIST_AddItem()

Before	After
	

Description

Adds a new item with header text to the SWIPELIST widget.

Prototype

```
int SWIPELIST_AddItem(      SWIPELIST_Handle   hObj,
                      const char             * sText,
                            int                ItemSize);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
sText	Pointer to the text to be handled by the SWIPELIST widget.
ItemSize	Size of the item (in pixels).

Return value

0 on success
1 on error.

Additional information

If ItemSize is too small for sText the item size will be modified by the widget. If sText is 0 then no header text will be drawn.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.2 SWIPELIST_AddItemText()

Before	After
	

Description

Adds a text to the given item of the SWIPELIST widget.

Prototype

```
int SWIPELIST_AddItemText(      SWIPELIST_Handle   hObj,
                                unsigned           ItemIndex,
                          const char             * sText);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
sText	Pointer to the text to be handled by the SWIPELIST widget.

Return value

0 on success
1 on error.

Additional information

An item can have an undefined number of texts. Each text will begin in a new line. If the size of the items are to small for the new text the item size will be modified by the widget. If *SWIPELIST_AddItem* on page 2010 does not set a header text then this function will set the header text at first call.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.3 SWIPELIST_AddSepItem()

Before	After
	

Description

Adds a new separator item to the SWIPELIST widget.

Prototype

```
int SWIPELIST_AddSepItem(      SWIPELIST_Handle   hObj,
                         const char             * sText,
                               int                ItemSize);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
sText	Pointer to the text to be handled by the SWIPELIST widget.
ItemSize	Size (in pixels) of the item used as separator.

Return value

0 on success
1 on error.

Additional information

Separator items do not send any notification massages to the parent window of the SWIPELIST widget. They do not change the style if they are clicked. The separator size of the previous item will be set to 0.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.4 SWIPELIST_CreateEx()

Description

Creates a SWIPELIST widget of a specified size at a specified location.

Prototype

```
SWIPELIST_Handle SWIPELIST_CreateEx(int     x0,
                                    int     y0,
                                    int     xSize,
                                    int     ySize,
                                    WM_HWIN hParent,
                                    int     WinFlags,
                                    int     ExFlags,
                                    int     Id);
```

Parameters

Parameter	Description
x0	X-position of the button relative to the parent window.
y0	Y-position of the button relative to the parent window.
xSize	Horizontal size of the SWIPELIST widget (in pixels).
ySize	Vertical size of the SWIPELIST widget (in pixels).
hParent	Handle of parent window.
WinFlags	Window create flags. In order to make the widget visible immediately WM_CF_SHOW should be used. The complete list of available parameters can be found under *Window create flags* on page 958.
ExFlags	Not used yet, reserved for future use.
Id	Window ID of the widget.

Return value

Handle of the created SWIPELIST widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.5 SWIPELIST_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.6 SWIPELIST_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `SWIPELIST_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.7 SWIPELIST_DeleteItem()

Before	After
	

Description

Deletes an item from the SWIPELIST widget.

Prototype

```
void SWIPELIST_DeleteItem(SWIPELIST_Handle hObj,
                          unsigned         ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Additional information

If windows are attached to the item, those windows will be deleted, too.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.8 SWIPELIST_GetBitmap()

Description

Returns a pointer to the optional bitmap of the item.

Prototype

```
GUI_BITMAP *SWIPELIST_GetBitmap(SWIPELIST_Handle hObj,
                                unsigned         ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Return value

Pointer to the bitmap, 0 if no bitmap exist.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.9 SWIPELIST_GetBitmapSpace()

Description

Returns number of pixels used as space between the bitmap and the text of the SWIPELIST widget.

Prototype

```
int SWIPELIST_GetBitmapSpace(SWIPELIST_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.

Return value

Number of pixels between the bitmap and the text.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.10 SWIPELIST_GetBkColor()

Description

Returns the specific background color of the SWIPELIST widget.

Prototype

```
GUI_COLOR SWIPELIST_GetBkColor(SWIPELIST_Handle hObj,
                               unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Index	See *SWIPELIST background color indexes* on page 2076 for a full list of permitted values.

Return value

Specific background color of the SWIPELIST widget.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.11 SWIPELIST_GetBorderSize()

Description

Returns the border of the SWIPELIST widget.

Prototype

```
int SWIPELIST_GetBorderSize(SWIPELIST_Handle hObj,
                            unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Index	See *SWIPELIST border indexes* on page 2078 for a full list of permitted values.

Return value

Border size of the SWIPELIST widget.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.12 SWIPELIST_GetDefaultBitmapSpace()

Description

Returns the default number of pixels used as space between the bitmap and the text for new SWIPELIST widgets.

Prototype

```
int SWIPELIST_GetDefaultBitmapSpace(void);
```

Return value

Default number of pixels used as space between the bitmap and the text for new SWIPELIST widgets.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.13 SWIPELIST_GetDefaultBkColor()

Description

Returns the specific default background color of the SWIPELIST widget.

Prototype

```
GUI_COLOR SWIPELIST_GetDefaultBkColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *SWIPELIST background color indexes* on page 2076 for a full list of permitted values.

Return value

Specific default background color of the SWIPELIST widget.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.14 SWIPELIST_GetDefaultBorderSize()

Description

Returns the default border size (in pixels) of new SWIPELIST widgets.

Prototype

```
int SWIPELIST_GetDefaultBorderSize(unsigned Index);
```

Parameters

Parameter	Description
Index	See *SWIPELIST border indexes* on page 2078 for a full list of permitted values.

Return value

Border size used for new SWIPELIST widgets.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.15 SWIPELIST_GetDefaultFont()

Description

Returns a pointer to the specific default font used for new SWIPELIST widgets.

Prototype

```
GUI_FONT *SWIPELIST_GetDefaultFont(unsigned Index);
```

Parameters

Parameter	Description
Index	See *SWIPELIST font indexes* on page 2079 for a full list of permitted values.

Return value

Pointer to the specific default font used for new SWIPELIST widgets.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.16 SWIPELIST_GetDefaultSepColor()

Description

Returns the default color of the separator line used for all new items.

Prototype

```
GUI_COLOR SWIPELIST_GetDefaultSepColor(void);
```

Return value

Default color of the separator line used for all new items.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.17 SWIPELIST_GetDefaultSepSize()

Description

Returns the default size (in pixels) of the separator line used for all new items.

Prototype

```
unsigned SWIPELIST_GetDefaultSepSize(void);
```

Return value

Default size (in pixels) of the separator line used for all new items.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.18 SWIPELIST_GetDefaultTextColor()

Description

Returns the specific default text color used by new SWIPELIST widgets.

Prototype

```
GUI_COLOR SWIPELIST_GetDefaultTextColor(unsigned Index);
```

Parameters

Parameter	Description
Index	See *SWIPELIST background color indexes* on page 2076 for a full list of permitted values.

Return value

Specific default text color used by new SWIPELIST widgets.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.19 SWIPELIST_GetDefaultTextAlign()

Description

Returns the default text align for all new items of the SWIPELIST widget.

Prototype

```
int SWIPELIST_GetDefaultTextAlign(void);
```

Return value

Default text align for all new items of the SWIPELIST widget.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.20 SWIPELIST_GetDefaultThreshold()

Description

Returns the default threshold value used for new widgets. Please also refer to the function *SWIPELIST_SetThreshold* on page 2074.

Prototype

```
int SWIPELIST_GetDefaultThreshold(void);
```

Return value

Default threshold value.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.21 SWIPELIST_GetFont()

Description

Returns a pointer of the specified font of the SWIPELIST widget.

Prototype

```
GUI_FONT *SWIPELIST_GetFont(SWIPELIST_Handle hObj,
                            unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Index	See *SWIPELIST font indexes* on page 2079 for a full list of permitted values.

Return value

Pointer of the specified font, 0 if index is not correct.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.22 SWIPELIST_GetItemSize()

Description

Returns the size (in pixels) of the given item.

Prototype

```
int SWIPELIST_GetItemSize(SWIPELIST_Handle hObj,
                          unsigned         ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Return value

Size of the item, -1 if failed.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.23 SWIPELIST_GetItemUserData()

Description

Retrieves the previously stored user data from a given item.

Prototype

```
U32 SWIPELIST_GetItemUserData(SWIPELIST_Handle hObj,
                              unsigned         ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Return value

User data of the given item.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.24 SWIPELIST_GetNumItems()

Description

Returns the number of items in the SWIPELIST widget.

Prototype

```
int SWIPELIST_GetNumItems(SWIPELIST_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.

Return value

Number of items in the SWIPELIST widget.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.25 SWIPELIST_GetNumText()

Description

Returns the number of texts in the item of the SWIPELIST widget.

Prototype

```
int SWIPELIST_GetNumText(SWIPELIST_Handle hObj,
                         unsigned         ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Return value

Number of texts in the item of the SWIPELIST widget.

Additional information

Number of texts added with the function `SWIPELIST_AddItemText()` inclusive the header text added with the function `SWIPELIST_AddItem()`.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.26 SWIPELIST_GetReleasedItem()

Description

Returns the item index of the last released item.

Prototype

```
int SWIPELIST_GetReleasedItem(SWIPELIST_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.

Return value

Item index of the last released item, -1 if no item has been released.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.27 SWIPELIST_GetScrollPos()

Description

Returns the current scroll position (in pixels) of the SWIPELIST widget.

Prototype

```
int SWIPELIST_GetScrollPos(SWIPELIST_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.

Return value

Current scroll position (in pixels) of the SWIPELIST widget.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.28 SWIPELIST_GetSelItem()

Description

Returns the current selected item index of the given SWIPELIST widget.

Prototype

```
int SWIPELIST_GetSelItem(SWIPELIST_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.

Return value

Current selected item index, -1 if currently no item is selected.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.29 SWIPELIST_GetSepColor()

Description

Returns the color of the separator line for the given item.

Prototype

```
GUI_COLOR SWIPELIST_GetSepColor(SWIPELIST_Handle hObj,
                                unsigned         ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Return value

Color of the separator line of the given item.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.30 SWIPELIST_GetSepSize()

Description

Returns the size (in pixels) of the separator line for the given item.

Prototype

```
int SWIPELIST_GetSepSize(SWIPELIST_Handle hObj,
                         unsigned         ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Return value

Size (in pixels) of the separator line for the given item.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.31 SWIPELIST_GetText()

Description

Returns the text of the given item.

Prototype

```
void SWIPELIST_GetText(SWIPELIST_Handle   hObj,
                       unsigned           ItemIndex,
                       unsigned           TextIndex,
                       char             * pBuffer,
                       int                MaxSize);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
TextIndex	Index of an text of an item.
pBuffer	Pointer to buffer filled by the function.
MaxSize	Size of the buffer in bytes.

Additional information

The function copies the text of the given item to the buffer given by pBuffer. The maximum number of bytes copied to the buffer is given by MaxSize.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.32 SWIPELIST_GetTextAlign()

Description

Returns the text alignment of the given item.

Prototype

```
int SWIPELIST_GetTextAlign(SWIPELIST_Handle hObj,
                           unsigned         ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Return value

Text alignment of the item.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.33 SWIPELIST_GetTextColor()

Description

Returns the specific text color of the SWIPELIST widget.

Prototype

```
GUI_COLOR SWIPELIST_GetTextColor(SWIPELIST_Handle hObj,
                                 unsigned         Index);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Index	See *SWIPELIST item color indexes* on page 2080 for a full list of permitted values.

Return value

Specific text color of the SWIPELIST widget.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.34 SWIPELIST_GetThreshold()

Description

Returns the minimum number of pixels required for a swipe operation.

Prototype

```
int SWIPELIST_GetThreshold(SWIPELIST_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.

Return value

Threshold value used by the widget.

Additional information

Please also refer to *SWIPELIST_SetThreshold* on page 2074.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.35 SWIPELIST_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.36 SWIPELIST_IsSepItem()

Description

Returns if the given item is a separator item.

Prototype

```
int SWIPELIST_IsSepItem(SWIPELIST_Handle hObj,
                        U32              ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Return value

1	If the item is a separator item.
0	If the item is not a separator item.
-1	Error: Index out of bounds.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.37 SWIPELIST_ItemAttachWindow()

Before	After
	

Description

Attaches the window/widget to the given item of the SWIPELIST widget.

Prototype

```
int SWIPELIST_ItemAttachWindow(SWIPELIST_Handle hObj,
                               unsigned         ItemIndex,
                               WM_HWIN          hWin,
                               int              x0,
                               int              y0);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
hWin	Handle of the window that should be attached.
x0	X-position of the window that should be added to the item.
y0	Y-position of the window that should be added to the item.

Return value

0 on success
1 on error.

Additional information

If the size of the window is bigger then the item size the window will not be attached to the item and the function returns 1. If the given position will bring the window out of the item area the position will be fixed to the end of the item area.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.38 SWIPELIST_ItemDetachWindow()

Before	After
	

Description

Detaches the window from the item of the SWIPELIST widget.

Prototype

```
void SWIPELIST_ItemDetachWindow(SWIPELIST_Handle hObj,
                                WM_HWIN          hWin);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
hWin	Handle of the window that should be detached.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.39 SWIPELIST_OwnerDraw()

Description

Default function to draw an item of the SWIPELIST widget.

Prototype

```
int SWIPELIST_OwnerDraw(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo);
```

Parameters

Parameter	Description
pDrawItemInfo	Pointer to a WIDGET_ITEM_DRAW_INFO structure.

Additional information

This function is useful if *SWIPELIST_SetOwnerDraw* on page 2066 has been used. It can be used from the application defined drawing function to display anything of the item by the SWIPELIST widget.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.40 SWIPELIST_SetAttachedWindowPos()

Before	After
	

Description

Sets the position of the attached window in the item of the SWIPELIST.

Prototype

```
void SWIPELIST_SetAttachedWindowPos(SWIPELIST_Handle hObj,
                                    WM_HWIN          hWin,
                                    int              x0,
                                    int              y0);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
hWin	Handle of the window that is attached to an item of the SWIPELIST widget.
x0	New x-position of the window that is attached to an item.
y0	New y-position of the window that is attached to an item.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.41 SWIPELIST_SetBitmap()

Before	After
	

Description

Sets a bitmap to be displayed with the given alignment Within the item.

Prototype

```
void SWIPELIST_SetBitmap(      SWIPELIST_Handle   hObj,
                               unsigned           ItemIndex,
                               int                Align,
                         const GUI_BITMAP       * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
Align	OR-combination of bitmap alignment flags. See *SWIPELIST bitmap alignment flags* on page 2077.
pBitmap	Pointer to an bitmap structure to be displayed.

Additional information

If the alignment of the bitmap is vertical and horizontal central then no text will be displayed.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.42 SWIPELIST_SetBitmapSpace()

Before	After
	

Description

Set the space (in pixels) between the text and the bitmap of the SWIPELIST widget.

Prototype

```
void SWIPELIST_SetBitmapSpace(SWIPELIST_Handle hObj,
                              unsigned         Size);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Size	Number of pixels used as space.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.43 SWIPELIST_SetBkColor()

Before	After
	

Description

Sets the specific background color of the SWIPELIST widget.

Prototype

```
void SWIPELIST_SetBkColor(SWIPELIST_Handle hObj,
                          unsigned         Index,
                          GUI_COLOR        Color);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Index	See *SWIPELIST background color indexes* on page 2076 for a full list of permitted values.
Color	Background color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.44 SWIPELIST_SetBorderSize()

Before	After
	

Description

Sets the specific border size (in pixels) of the SWIPELIST widget.

Prototype

```
void SWIPELIST_SetBorderSize(SWIPELIST_Handle hObj,
                             unsigned         Index,
                             unsigned         Size);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Index	See *SWIPELIST border indexes* on page 2078 for a full list of permitted values.
Size	Number of pixels used as border.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.45 SWIPELIST_SetDefaultBitmapSpace()

Description

Sets the default space (in pixels) between text and bitmap for new SWIPELIST widgets.

Prototype

```
void SWIPELIST_SetDefaultBitmapSpace(unsigned Size);
```

Parameters

Parameter	Description
Size	Number of pixels used as space.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.46 SWIPELIST_SetDefaultBkColor()

Description

Sets the default color of the specific background for new SWIPELIST widget.

Prototype

```
void SWIPELIST_SetDefaultBkColor(unsigned  Index,
                                 GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *SWIPELIST background color indexes* on page 2076 for a full list of permitted values.
Color	Background color to be set.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.47 SWIPELIST_SetDefaultBorderSize()

Description

Sets the default size (in pixels) of the specific border for new SWIPELIST widgets.

Prototype

```
void SWIPELIST_SetDefaultBorderSize(unsigned Index,
                                    unsigned Size);
```

Parameters

Parameter	Description
Index	See *SWIPELIST border indexes* on page 2078 for a full list of permitted values.
Size	Number of pixels used as border.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.48 SWIPELIST_SetDefaultFont()

Description

Sets the pointer to the default font to display the specific text of new SWIPELIST widgets.

Prototype

```
void SWIPELIST_SetDefaultFont(      unsigned   Index,
                              const GUI_FONT * pFont);
```

Parameters

Parameter	Description
Index	See *SWIPELIST font indexes* on page 2079 for a full list of permitted values.
pFont	Pointer to the font to be used.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.49 SWIPELIST_SetDefaultSepColor()

Description

Sets the default color of the separator line for new items.

Prototype

```
void SWIPELIST_SetDefaultSepColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color of the separator line.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.50 SWIPELIST_SetDefaultSepSize()

Description

Sets the default size (in pixels) of the separator line for new items.

Prototype

```
void SWIPELIST_SetDefaultSepSize(unsigned Size);
```

Parameters

Parameter	Description
Size	Number of pixels used as separator line.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.51 SWIPELIST_SetDefaultTextColor()

Description

Sets the default color of the specific text for new SWIPELIST widgets.

Prototype

```
void SWIPELIST_SetDefaultTextColor(unsigned  Index,
                                   GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *SWIPELIST item color indexes* on page 2080 for a full list of permitted values.
Color	Color used for the specific text.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.52 SWIPELIST_SetDefaultTextAlign()

Description

Sets the default text alignment for new items.

Prototype

```
void SWIPELIST_SetDefaultTextAlign(int Align);
```

Parameters

Parameter	Description
Align	Text alignment to be set (see *GUI_SetTextAlign* on page 213)

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.53 SWIPELIST_SetDefaultThreshold()

Description

Sets the default threshold value to be used for new widgets. For details please also refer to *SWIPELIST_SetThreshold* on page 2074.

Prototype

```
void SWIPELIST_SetDefaultThreshold(int Threshold);
```

Parameters

Parameter	Description
Threshold	The new default value to be set for minimum amount of movement.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.54 SWIPELIST_SetFont()

Before	After
	

Description

Sets the pointer to the font used for display the specific text of the SWIPELIST widget.

Prototype

```
void SWIPELIST_SetFont(      SWIPELIST_Handle   hObj,
                             unsigned           Index,
                       const GUI_FONT         * pFont);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Index	See *SWIPELIST font indexes* on page 2079 for a full list of permitted values.
pFont	Pointer to the font to be used.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.55 SWIPELIST_SetItemSize()

Before	After
	

Description

Sets the size of the given item.

Prototype

```
void SWIPELIST_SetItemSize(SWIPELIST_Handle hObj,
                           unsigned         ItemIndex,
                           unsigned         Size);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
Size	Number of pixels used for the item.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.56 SWIPELIST_SetItemUserData()

Description

Sets a 32 bit value assigned to the given item of the SWIPELIST widget.

Prototype

```
void SWIPELIST_SetItemUserData(SWIPELIST_Handle hObj,
                               unsigned         ItemIndex,
                               U32              UserData);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
UserData	32 bit user data to be stored.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.57 SWIPELIST_SetOwnerDraw()

Description

Sets the SWIPELIST widget to be owner drawn.

Prototype

```
void SWIPELIST_SetOwnerDraw(SWIPELIST_Handle        hObj,
                            WIDGET_DRAW_ITEM_FUNC * pfDrawItem);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
pfDrawItem	Pointer to owner draw function.

Supported commands

- WIDGET_ITEM_DRAW_BACKGROUND
- WIDGET_ITEM_DRAW_TEXT
- WIDGET_ITEM_DRAW_BITMAP
- WIDGET_ITEM_DRAW_SEP

Additional information

This function sets a pointer to a function which will be called by the widget if an item of the SWIPELIST has to be drawn. It gives you the possibility to draw complete customized items. pfDrawItem is a pointer to an application defined function of type WIDGET_DRAW_ITEM_FUNC which is explained at the beginning of the chapter.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.58 SWIPELIST_SetScrollPos()

Before	After
	

Description

Sets the scroll position (in pixels) of the SWIPELIST widget.

Prototype

```
void SWIPELIST_SetScrollPos(SWIPELIST_Handle hObj,
                            int              Pos);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Pos	Number of pixels of the scroll position.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.59 SWIPELIST_SetScrollPosItem()

Before	After
	

Description

Sets the scroll position to see the given item on first position.

Prototype

```
void SWIPELIST_SetScrollPosItem(SWIPELIST_Handle hObj,
                                unsigned         ItemIndex);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.

Additional information

If the list is to short to set the scoll position to see the given item on first position, the scroll position will be set to the end of the list.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.60 SWIPELIST_SetSepColor()

Before	After
	

Description

Sets the color of the separator line of a given item.

Prototype

```
void SWIPELIST_SetSepColor(SWIPELIST_Handle hObj,
                           unsigned         ItemIndex,
                           GUI_COLOR        Color);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
Color	Color of the separator line of a specific item.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.61 SWIPELIST_SetSepSize()

Before	After
	

Description

Sets size (in pixels) of the separator line of a given item.

Prototype

```
void SWIPELIST_SetSepSize(SWIPELIST_Handle hObj,
                          unsigned         ItemIndex,
                          int              Size);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
Size	Number of pixel used for the size of the separator line.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.62 SWIPELIST_SetText()

Before	After
	

Description

Sets/Changes a text of an item.

Prototype

```
void SWIPELIST_SetText(SWIPELIST_Handle   hObj,
                       unsigned           ItemIndex,
                       unsigned           TextIndex,
                       char             * s);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
TextIndex	Index of the text in the item.
sText	Text to be displayed.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.63 SWIPELIST_SetTextAlign()

Before	After
	

Description

Sets the text alignment of a given item.

Prototype

```
void SWIPELIST_SetTextAlign(SWIPELIST_Handle hObj,
                            unsigned         ItemIndex,
                            int              Align);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
ItemIndex	Index of an item of the SWIPELIST widget.
Align	Text alignment to be set. List of flags can be found under *Text alignment flags* on page 218.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.64 SWIPELIST_SetTextColor()

Before	After
	

Description

Sets the color of the text used by the SWIPELIST widget.

Prototype

```
void SWIPELIST_SetTextColor(SWIPELIST_Handle hObj,
                            unsigned         Index,
                            GUI_COLOR        Color);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Index	See *SWIPELIST item color indexes* on page 2080 for a full list of permitted values.
Color	Color for the text.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.65 SWIPELIST_SetThreshold()

Description

Sets the minimum distance required for a scoll operation.

Prototype

```
int SWIPELIST_SetThreshold(SWIPELIST_Handle hObj,
                           int              Threshold);
```

Parameters

Parameter	Description
hObj	Handle of SWIPELIST widget.
Threshold	New threshold value.

Return value

Previous threshold value.

Additional information

Pressing the PID selects the swipelist item below the PID position. Swiping the PID in pressed state deselects the item and starts the swipe operation. The threshold value defines the minimum number of pixels required to release the selection and start swiping.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.1.66 SWIPELIST_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.2 Defines

20.29.6.2.1 SWIPELIST background color indexes

Description

Color indexes used for SWIPELIST routines to return or set the background color of SWIPELIST items.

Definition

```
#define SWIPELIST_CI_BK_ITEM_UNSEL    0
#define SWIPELIST_CI_BK_ITEM_SEL      1
#define SWIPELIST_CI_BK_SEP_ITEM      2
```

Symbols

Definition	Description
SWIPELIST_CI_BK_ITEM_UNSEL	Background of an unselected item.
SWIPELIST_CI_BK_ITEM_SEL	Background of a selected item.
SWIPELIST_CI_BK_SEP_ITEM	Background of a separator item.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.2.2 SWIPELIST bitmap alignment flags

Description

Flags to align the bitmaps of a SWIPELIST widget. These flags are used by the routine SWIPELIST_SetBitmap() and can be OR-combined.

Definition

```
#define SWIPELIST_BA_LEFT       (0 << 0)
#define SWIPELIST_BA_RIGHT      (1 << 0)
#define SWIPELIST_BA_HCENTER    (2 << 0)
#define SWIPELIST_BA_VCENTER    (3 << 2)
#define SWIPELIST_BA_TOP        (0 << 2)
#define SWIPELIST_BA_BOTTOM     (1 << 2)
```

Symbols

Definition	Description
Horizontal alignment	
SWIPELIST_BA_HCENTER	Center X-position.
SWIPELIST_BA_LEFT	Align X-position left (default).
SWIPELIST_BA_RIGHT	Align X-position right.
Vertical alignment	
SWIPELIST_BA_BOTTOM	Align Y-position with bottom pixel line of font.
SWIPELIST_BA_TOP	Align Y-position with top of characters (default).
SWIPELIST_BA_VCENTER	Center Y-position.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.2.3 SWIPELIST border indexes

Description

Border indexes to e.g. change the border size of the SWIPELIST widget. A routine that uses these index flags is `SWIPELIST_SetBorderSize()`.

Definition

```
#define SWIPELIST_BI_LEFT      0
#define SWIPELIST_BI_RIGHT     1
#define SWIPELIST_BI_TOP       2
#define SWIPELIST_BI_BOTTOM    3
```

Symbols

Definition	Description
SWIPELIST_BI_LEFT	Left border of the items.
SWIPELIST_BI_RIGHT	Right border of the items.
SWIPELIST_BI_TOP	Top border of the items.
SWIPELIST_BI_BOTTOM	Bottom border of the items.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.2.4 SWIPELIST font indexes

Description

Font indexes used for SWIPELIST routines.

Definition

```
#define SWIPELIST_FI_SEP_ITEM       0
#define SWIPELIST_FI_ITEM_HEADER    1
#define SWIPELIST_FI_ITEM_TEXT      2
```

Symbols

Definition	Description
SWIPELIST_FI_SEP_ITEM	Font used by the separator item.
SWIPELIST_FI_ITEM_HEADER	Font used by the header of the item.
SWIPELIST_FI_ITEM_TEXT	Font used by the text of the item.

 © 2020 SEGGER Microcontroller GmbH

20.29.6.2.5 SWIPELIST item color indexes

Description

Color indexes used for SWIPELIST routines to return or set the color of an item.

Definition

```
#define SWIPELIST_CI_ITEM_HEADER_UNSEL    0
#define SWIPELIST_CI_ITEM_HEADER_SEL      1
#define SWIPELIST_CI_ITEM_TEXT_UNSEL      2
#define SWIPELIST_CI_ITEM_TEXT_SEL        3
#define SWIPELIST_CI_SEP_ITEM_TEXT        4
```

Symbols

Definition	Description
SWIPELIST_CI_ITEM_HEADER_UNSEL	Color used for drawing the header text of an unselected item.
SWIPELIST_CI_ITEM_HEADER_SEL	Color used for drawing the header text of a selected item.
SWIPELIST_CI_ITEM_TEXT_UNSEL	Color used for drawing the text for an unselected item.
SWIPELIST_CI_ITEM_TEXT_SEL	Color used for drawing the text of a selected item.
SWIPELIST_CI_SEP_ITEM_TEXT	Color used for drawing the text of a separator item.

 © 2020 SEGGER Microcontroller GmbH

20.29.7 Examples

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_SwipeList.c`

Screenshot of WIDGET_SwipeList.c



 © 2020 SEGGER Microcontroller GmbH

20.30 SWITCH: Switch widget

A SWITCH widget is a toggleable switch with two states. The widget is similar to the switches seen on most modern smartphones, e.g. in a phone settings application. A SWITCH widget can have two states, a 'left' state when the thumb is on the left and a 'right' state when the thumb is on the right. Optionally, each state has its own text that is shown inside of the switch.

The widget can be clicked to be toggled, or its thumb can be dragged from one side along to the other side, as seen on most smartphones. To be able to drag the thumb, motion support has to be enabled by calling `WM_MOTION_Enable(1)`.

Left state	Right state
	

Note

All SWITCH-related routines are located in the file(s) `SWITCH*.c`, `SWITCH.h`.
All identifiers are prefixed SWITCH.

20.30.1 Configuration options

Type	Macro	Default	Description
N	SWITCH_COLORLEFT_DEFAULT	GUI_BLACK	Text color for text shown in 'left' state.
N	SWITCH_COLORRIGHT_DEFAULT	GUI_BLACK	Text color for text shown in 'right' state.
N	SWITCH_PERIOD_DEFAULT	80	Animation period for a toggle operation.

20.30.2 Predefined IDs

The following symbols define IDs which may be used to make SWITCH widgets distinguishable from creation.

```
#define GUI_ID_SWITCH0    0x330
#define GUI_ID_SWITCH1    0x331
#define GUI_ID_SWITCH2    0x332
#define GUI_ID_SWITCH3    0x333
#define GUI_ID_SWITCH4    0x334
#define GUI_ID_SWITCH5    0x335
#define GUI_ID_SWITCH6    0x336
#define GUI_ID_SWITCH7    0x337
#define GUI_ID_SWITCH8    0x338
#define GUI_ID_SWITCH9    0x339
```

20.30.3 Notification codes

The following events are sent from a BUTTON widget to its parent window as part of a `WM_NOTIFY_PARENT` message:

Message	Description
WM_NOTIFICATION_CLICKED	SWITCH has been clicked.
WM_NOTIFICATION_RELEASED	SWITCH has been released.
WM_NOTIFICATION_MOTION_STOPPED	Animation of the SWITCH has stopped.

 © 2020 SEGGER Microcontroller GmbH

Message	Description
WM_NOTIFICATION_MOVED_OUT	SWITCH has been clicked and pointer has been moved out of the SWITCH area without releasing.
WM_NOTIFICATION_VALUE_CHANGED	The state of the SWITCH widget has been changed.

20.30.4 SWITCH API

The table below lists the available SWITCH-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
SWITCH_AnimState()	Sets the SWITCH widget to the desired state and shows the toggle animation.
SWITCH_CreateIndirect()	Creates a SWITCH widget from a resource table entry.
SWITCH_CreateUser()	Creates a SWITCH widget.
SWITCH_GetDefaultFont()	Returns the default font for SWITCH widgets.
SWITCH_GetDefaultPeriod()	Returns the default period for SWITCH widgets.
SWITCH_GetDefaultTextColor()	Returns the default text color for SWITCH widgets.
SWITCH_GetState()	Returns the state of a SWITCH widget.
SWITCH_GetUserData()	Retrieves the extra data set with SWITCH_SetUserData().
SWITCH_SetBitmap()	Sets a bitmap for a state of the SWITCH widget.
SWITCH_SetDefaultFont()	Sets the default font for SWITCH widgets.
SWITCH_SetDefaultPeriod()	Sets the default period for SWITCH widgets.
SWITCH_SetDefaultTextColor()	Sets the default text color for SWITCH widgets.
SWITCH_SetFont()	Sets the font of a SWITCH widget.
SWITCH_SetMode()	Sets the mode of a SWITCH widget.
SWITCH_SetPeriod()	Sets the period to stop the animation of a SWITCH widget.
SWITCH_SetState()	Sets the state of a SWITCH widget.
SWITCH_SetText()	Sets a text on either the left or right side of the SWITCH widget.
SWITCH_SetTextColor()	Sets the text color of a SWITCH widget.
SWITCH_SetUserData()	Sets the extra data of a SWITCH widget.
SWITCH_Toggle()	Toggles the state of a SWITCH widget.

Defines

Group of defines	Description
SWITCH bitmap indexes	Bitmap indexes used by the SWITCH widget.
SWITCH color indexes	Color indexes used by the SWITCH widget.
SWITCH modes	Modes a SWITCH widget can be set to.
SWITCH text indexes	Text indexes used by the SWITCH widget.
SWITCH states	Possible states a SWITCH widget can be in.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1 Functions

20.30.4.1.1 SWITCH_AnimState()

Description

Sets the SWITCH widget to the desired state and shows the toggle animation.

Prototype

```
void SWITCH_AnimState(SWITCH_Handle hObj,
                      int           State);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.
State	See table below.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.2 SWITCH_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.3 SWITCH_CreateUser()

Description

Creates a SWITCH widget.

Prototype

```
SWITCH_Handle SWITCH_CreateUser(int     x0,
                                int     y0,
                                int     xSize,
                                int     ySize,
                                WM_HWIN hParent,
                                int     WinFlags,
                                int     ExFlags,
                                int     Id,
                                int     NumExtraBytes);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the SWITCH widget (in parent coordinates).
y0	Topmost pixel of the SWITCH widget (in parent coordinates).
xSize	Horizontal size of the SWITCH widget (in pixels).
ySize	Vertical size of the SWITCH widget (in pixels).
hParent	Parent window of the SWITCH widget.
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used yet, reserved for future use.
Id	ID of the SWITCH widget.
NumExtraBytes	Number of extra bytes to be allocated.

Return value

Handle of the SWITCH widget.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.4 SWITCH_GetDefaultFont()

Description

Returns the default font for SWITCH widgets.

Prototype

```
GUI_FONT *SWITCH_GetDefaultFont(void);
```

Return value

Default font for SWITCH widgets.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.5 SWITCH_GetDefaultPeriod()

Description

Returns the default period for SWITCH widgets. This is the duration of the animation when the SWITCH widget is clicked.

Prototype

```
unsigned SWITCH_GetDefaultPeriod(void);
```

Return value

Default period for SWITCH widgets.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.6 SWITCH_GetDefaultTextColor()

Description

Returns the default text color for SWITCH widgets.

Prototype

```
GUI_COLOR SWITCH_GetDefaultTextColor(unsigned Index);
```

Parameters

Parameter	Description
Index	Text index. See *SWITCH text indexes* on page 2107.

Return value

Default text color for SWITCH widgets.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.7 SWITCH_GetState()

Description

Returns the state of a SWITCH widget.

Prototype

```
int SWITCH_GetState(SWITCH_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.

Return value

-1	Invalid state.
SWITCH_STATE_RIGHT	'Right' state.
SWITCH_STATE_LEFT	'Left' state.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.8 SWITCH_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.9 SWITCH_SetBitmap()

Description

Sets a bitmap for a state of the SWITCH widget.

Prototype

```
void SWITCH_SetBitmap(      SWITCH_Handle   hObj,
                            unsigned int    Index,
                      const GUI_BITMAP    * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.
Index	See *SWITCH bitmap indexes* on page 2104.
pBitmap	Pointer to a bitmap.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.10 SWITCH_SetDefaultFont()

Description

Sets the default font for SWITCH widgets.

Prototype

```
void SWITCH_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to a font to be set.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.11 SWITCH_SetDefaultPeriod()

Description

Sets the default period for SWITCH widgets.

Prototype

```
void SWITCH_SetDefaultPeriod(unsigned Period);
```

Parameters

Parameter	Description
Period	Period to be set.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.12 SWITCH_SetDefaultTextColor()

Description

Sets the default text color for SWITCH widgets.

Prototype

```
void SWITCH_SetDefaultTextColor(GUI_COLOR Color,
                                unsigned  Index);
```

Parameters

Parameter	Description
Color	Color to be set.
Index	Color index. See *SWITCH color indexes* on page 2105.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.13 SWITCH_SetFont()

Before	After
	

Description

Sets the font of a SWITCH widget.

Prototype

```
void SWITCH_SetFont(      SWITCH_Handle   hObj,
                    const GUI_FONT      * pFont);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.
pFont	Pointer to a GUI_FONT.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.14 SWITCH_SetMode()

Description

Sets the mode of a SWITCH widget. The mode can be set to either disclose mode (default) or fade mode.

Prototype

```
void SWITCH_SetMode(SWITCH_Handle hObj,
                    int           Mode);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.
Mode	See *SWITCH modes* on page 2106.

Disclose mode

In disclose mode the bitmap of the new state is disclosed while the old state bitmap disappears under the thumb.



Fade mode

In fade mode both state bitmaps are faded into each other.



 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.15 SWITCH_SetPeriod()

Description

Sets the period to stop the animation of a SWITCH widget.

Prototype

```
void SWITCH_SetPeriod(SWITCH_Handle hObj,
                      I32           Period);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.
Period	Animation period. Maximum value: 46340.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.16 SWITCH_SetState()

Before	After
	

Description

Sets the state of a SWITCH widget.

Prototype

```
void SWITCH_SetState(SWITCH_Handle hObj,
                     int           State);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.
State	See *SWITCH states* on page 2108.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.17 SWITCH_SetText()

Before	After
	

Description

Sets a text on either the left or right side of the SWITCH widget.

Prototype

```
int SWITCH_SetText(      SWITCH_Handle   hObj,
                         unsigned int    Index,
                   const char          * pText);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.
Index	Text index. See *SWITCH text indexes* on page 2107.
pText	Pointer to a string.

Return value

0 If the routine succeeded.
1 If the routine failed.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.18 SWITCH_SetTextColor()

Before	After
	

Description

Sets the text color of a SWITCH widget.

Prototype

```
void SWITCH_SetTextColor(SWITCH_Handle hObj,
                         unsigned int  Index,
                         GUI_COLOR     Color);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.
Index	See *SWITCH color indexes* on page 2105 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.19 SWITCH_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.1.20 SWITCH_Toggle()

Before	After
	

Description

Toggles the state of a SWITCH widget.

Prototype

```
void SWITCH_Toggle(SWITCH_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of a SWITCH widget.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.2 Defines

20.30.4.2.1 SWITCH bitmap indexes

Description

Bitmap indexes used by the SWITCH widget for handling bitmaps.

Definition

```
#define SWITCH_BI_BK_LEFT          0
#define SWITCH_BI_BK_RIGHT         1
#define SWITCH_BI_BK_DISABLED      2
#define SWITCH_BI_THUMB_LEFT       3
#define SWITCH_BI_THUMB_RIGHT      4
#define SWITCH_BI_THUMB_DISABLED   5
```

Symbols

Definition	Description
SWITCH_BI_BK_LEFT	Background bitmap for left state.
SWITCH_BI_BK_RIGHT	Background bitmap for right state.
SWITCH_BI_BK_DISABLED	Background bitmap for disabled state.
SWITCH_BI_THUMB_LEFT	Thumb bitmap for left state.
SWITCH_BI_THUMB_RIGHT	Thumb bitmap for right state.
SWITCH_BI_THUM-B_DISABLED	Thumb bitmap for disabled state.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.2.2 SWITCH color indexes

Description

Color indexes used by the SWITCH widget.

Definition

```
#define SWITCH_CI_LEFT        0
#define SWITCH_CI_RIGHT       1
#define SWITCH_CI_DISABLED    2
```

Symbols

Definition	Description
SWITCH_CI_LEFT	Color for left state.
SWITCH_CI_RIGHT	Color for right state.
SWITCH_CI_DISABLED	Color for disabled state.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.2.3 SWITCH modes

Description

Modes a SWITCH widget can be set to. See `SWITCH_SetMode()` for more information.

Definition

```
#define SWITCH_MODE_FADE        (1 << 0)
#define SWITCH_MODE_DISCLOSE    (1 << 1)
```

Symbols

Definition	Description
SWITCH_MODE_FADE	Fade mode. Both state bitmaps are faded into each other.
SWITCH_MODE_DISCLOSE	Disclose mode. Bitmap of the new state is disclosed.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.2.4 SWITCH text indexes

Description

Text indexes used by the SWITCH widget.

Definition

```
#define SWITCH_TI_LEFT     0
#define SWITCH_TI_RIGHT    1
```

Symbols

Definition	Description
SWITCH_TI_LEFT	Text shown for the left state.
SWITCH_TI_RIGHT	Text shown for the right state.

 © 2020 SEGGER Microcontroller GmbH

20.30.4.2.5 SWITCH states

Description

List of defines of the possible states a SWITCH widget can be in.

Definition

```
#define SWITCH_STATE_LEFT     0
#define SWITCH_STATE_RIGHT    1
```

Symbols

Definition	Description
SWITCH_STATE_LEFT	Left state, the thumb is on the left side of the widget.
SWITCH_STATE_RIGHT	Right state, the thumb is on the right side of the widget.

 © 2020 SEGGER Microcontroller GmbH

20.31 TEXT: Text widget

Text widgets are typically used in order to display fields of text in dialog boxes, as shown in the message box below:



Of course, text fields may also be used for labeling other widgets, as follows:



> **Note**
>
> All TEXT-related routines are located in the file(s) `TEXT*.c`, `TEXT.h`. All identifiers are prefixed TEXT.

20.31.1 Configuration options

Type	Macro	Default	Description
N	TEXT_DEFAULT_BK_COLOR	GUI_INVALID_COLOR	Transparent background per default.
S	TEXT_DEFAULT_ROTATION	GUI_ROTATION_0	Default text rotation.
N	TEXT_DEFAULT_TEXT_COLOR	GUI_BLACK	Default text color.
N	TEXT_DEFAULT_WRAPMODE	GUI_WRAPMODE_NONE	Default wrapping mode.
S	TEXT_FONT_DEFAULT	&GUI_Font13_1	Font used.

20.31.2 Predefined IDs

The following symbols define IDs which may be used to make TEXT widgets distinguishable from creation.

```
#define GUI_ID_TEXT0    0x160
#define GUI_ID_TEXT1    0x161
#define GUI_ID_TEXT2    0x162
#define GUI_ID_TEXT3    0x163
#define GUI_ID_TEXT4    0x164
#define GUI_ID_TEXT5    0x165
#define GUI_ID_TEXT6    0x166
#define GUI_ID_TEXT7    0x167
#define GUI_ID_TEXT8    0x168
#define GUI_ID_TEXT9    0x169
```

20.31.3 Notification codes

The following events are sent from a TEXT widget to its parent window as part of a `WM_NOTIFY_PARENT` message:

Message	Description
WM_NOTIFICATION_CLICKED	The widget has been clicked.

 © 2020 SEGGER Microcontroller GmbH

Message	Description
WM_NOTIFICATION_RELEASED	The widget has been released.
WM_NOTIFICATION_MOVED_OUT	The pointer was moved out of the widget area while the PID was in pressed state.

20.31.4 Keyboard reaction

The widget can not gain the input focus and does not react on keyboard input.

20.31.5 TEXT API

The table below lists the available emWin TEXT-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
TEXT_Create()	Creates a TEXT widget. (Obsolete)
TEXT_CreateAsChild()	Creates a TEXT widget as a child window. (Obsolete)
TEXT_CreateEx()	Creates a TEXT widget.
TEXT_CreateIndirect()	Creates a TEXT widget from resource table entry.
TEXT_CreateUser()	Creates a TEXT widget using extra bytes as user data.
TEXT_GetBkColor()	Returns the current background color.
TEXT_GetDefaultFont()	Returns the default font used for TEXT widgets.
TEXT_GetDefaultRotation()	Returns the default text rotation mode.
TEXT_GetDefaultTextColor()	Returns the default text color.
TEXT_GetDefaultWrapMode()	Returns the default mode for wrapping text used for TEXT widget. Returns the default mode for wrapping text.
TEXT_GetFont()	Returns a pointer to the font used to display the text of the given TEXT widget. Returns the pointer to the font of the TEXT widget.
TEXT_GetNumLines()	Returns the number of lines currently displayed in the widget.
TEXT_GetRotation()	Returns the text rotation of a TEXT widget.
TEXT_GetText()	Copies the text of the given TEXT widget to the given buffer.
TEXT_GetTextAlign()	Returns the alignment of the given TEXT widget.
TEXT_GetTextColor()	Returns the text color of the given TEXT widget.
TEXT_GetTextOffset()	Returns the offset set for X and Y position of the text.
TEXT_GetUserData()	Retrieves the data set with TEXT_SetUserData().
TEXT_GetWrapMode()	Returns the currently used mode for wrapping text of the given TEXT widget. Returns the currently used mode for wrapping text.
TEXT_SetBkColor()	Sets the background color of the TEXT widget. Sets the background color for the text.
TEXT_SetDec()	This function sets a value which gets displayed by the TEXT widget. Sets a value to be displayed.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
TEXT_SetDefaultFont()	Sets the default font used for TEXT widgets.
TEXT_SetDefaultRotation()	Sets the default rotation mode for new TEXT widgets.
TEXT_SetDefaultTextColor()	Sets the default text color used for TEXT widgets.
TEXT_SetDefaultWrapMode()	Sets the default text wrapping mode used for new TEXT widgets.
TEXT_SetFont()	Sets the font to be used for a specified TEXT widget.
TEXT_SetRotation()	Sets the text rotation for a TEXT widget.
TEXT_SetText()	Sets the text to be used for a specified TEXT widget.
TEXT_SetTextAlign()	Sets the text alignment of a specified TEXT widget.
TEXT_SetTextColor()	Sets the text color of a specified TEXT widget.
TEXT_SetTextOffset()	Sets an X- and Y-offset for the text of a TEXT widget.
TEXT_SetUserData()	Sets the extra data of a TEXT widget.
TEXT_SetWrapMode()	Sets the wrapping mode of a specified TEXT widget.

Defines

Group of defines	Description
TEXT create flags	Create flags used by the TEXT widget.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1 Functions

20.31.5.1.1 TEXT_Create()

> **Note**
>
> This function is **deprecated**, `TEXT_CreateEx()` should be used instead.

Description

Creates a TEXT widget of a specified size at a specified location.

Prototype

```
TEXT_Handle TEXT_Create(      int    x0,
                              int    y0,
                              int    xSize,
                              int    ySize,
                              int    Id,
                              int    Flags,
                        const char * s,
                              int    Align);
```

Parameters

Parameter	Description
`x0`	Leftmost pixel of the TEXT widget (in parent coordinates).
`y0`	Topmost pixel of the TEXT widget (in parent coordinates).
`xSize`	Horizontal size of the TEXT widget (in pixels).
`ySize`	Vertical size of the TEXT widget (in pixels).
`Id`	ID to be returned.
`Flags`	Window create flags. Typically `WM_CF_SHOW` in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
`s`	Pointer to the text to be displayed.
`Align`	Alignment attribute for the text. See *TEXT create flags* on page 2145.

Return value

Handle of the created TEXT widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.2 TEXT_CreateAsChild()

> **Note**
>
> This function is **deprecated**, `TEXT_CreateEx()` should be used instead.

Description

Creates a TEXT widget as a child window.

Prototype

```
TEXT_Handle TEXT_CreateAsChild(      int       x0,
                                     int       y0,
                                     int       xSize,
                                     int       ySize,
                                     WM_HWIN   hParent,
                                     int       Id,
                                     int       Flags,
                               const char    * s,
                                     int       Align);
```

Parameters

Parameter	Description
`x0`	X-position of the PROGBAR widget relative to the parent window.
`y0`	Y-position of the PROGBAR widget relative to the parent window.
`xSize`	Horizontal size of the TEXT widget (in pixels).
`ySize`	Vertical size of the TEXT widget (in pixels).
`hParent`	Handle of parent window.
`Id`	ID to be returned.
`Flags`	Window create flags (see *Window create flags* on page 958).
`s`	Pointer to the text to be displayed.
`Align`	Alignment attribute. See *TEXT create flags* on page 2145.

Return value

Handle of the created TEXT widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.3 TEXT_CreateEx()

Description

Creates a TEXT widget of a specified size at a specified location.

Prototype

```
TEXT_Handle TEXT_CreateEx(      int       x0,
                                int       y0,
                                int       xSize,
                                int       ySize,
                                WM_HWIN   hParent,
                                int       WinFlags,
                                int       ExFlags,
                                int       Id,
                          const char    * pText);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new TEXT widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Alignment attribute for the text. See *TEXT create flags* on page 2145.
Id	Window ID of the TEXT widget.
pText	Pointer to the text to be displayed.

Return value

Handle of the created TEXT widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.4 TEXT_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Para` of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element `Flags` is used according to the parameter ExFlags of the function `TEXT_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.5 TEXT_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function TEXT_CreateEx() can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.6 TEXT_GetBkColor()

Description

Returns the current background color of the given TEXT widget.

Prototype

```
GUI_COLOR TEXT_GetBkColor(TEXT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.

Return value

The current background color.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.7 TEXT_GetDefaultFont()

Description

Returns the default font used for TEXT widgets.

Prototype

```
GUI_FONT *TEXT_GetDefaultFont(void);
```

Return value

Pointer to the default font used for TEXT widgets.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.8 TEXT_GetDefaultRotation()

Description

Returns the default text rotation mode.

Prototype

```
GUI_ROTATION *TEXT_GetDefaultRotation(void);
```

Return value

Default text rotation mode.

Additional information

Refer to *Text rotation modes* on page 220 for a list of possible values.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.9 TEXT_GetDefaultTextColor()

Description

Returns the default text color used for TEXT widgets.

Prototype

```
GUI_COLOR TEXT_GetDefaultTextColor(void);
```

Return value

Default text color.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.10 TEXT_GetDefaultWrapMode()

Description

Returns the default mode for wrapping text used for TEXT widget.

Prototype

```
GUI_WRAPMODE TEXT_GetDefaultWrapMode(void);
```

Return value

Default wrap mode.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.11 TEXT_GetFont()

Description

Returns a pointer to the font used to display the text of the given TEXT widget.

Prototype

```
GUI_FONT *TEXT_GetFont(TEXT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.

Return value

Pointer to the font used to display the text of the given TEXT widget.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.12 TEXT_GetNumLines()

Description

Returns the number of lines currently displayed in the widget.

Prototype

```
int TEXT_GetNumLines(TEXT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.

Return value

Number of lines.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.13 TEXT_GetRotation()

Description

Returns the text rotation of a TEXT widget.

Prototype

```
GUI_ROTATION *TEXT_GetRotation(TEXT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.

Return value

GUI_ROTATE_0	Text is not rotated.
GUI_ROTATE_CW	Text is rotated clockwise.
GUI_ROTATE_180	Text is rotated by 180 degrees.
GUI_ROTATE_CCW	Text is rotated counter-clockwise.
-1	On error.

Additional information

To learn more about rotating text in emWin, refer to GUI_DispStringInRectEx().

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.14 TEXT_GetText()

Description

Copies the text of the given TEXT widget to the given buffer. The 0-Byte at the end of the string is written in any case.

Prototype

```
int TEXT_GetText(TEXT_Handle   hObj,
                 char        * pDest,
                 U32           BufferSize);
```

Parameters

Parameter	Description
hObj	Handle of the TEXT widget.
pDest	Pointer to a user defined buffer.
BufferSize	Size of the buffer.

Return value

Number of bytes copied.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.15 TEXT_GetTextAlign()

Description

Returns the alignment of the given TEXT widget.

Prototype

```
int TEXT_GetTextAlign(TEXT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of the TEXT widget.

Return value

Alignment of the text.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.16 TEXT_GetTextColor()

Description

Returns the text color of the given TEXT widget.

Prototype

```
GUI_COLOR TEXT_GetTextColor(TEXT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of the TEXT widget.

Return value

Text color of the given TEXT widget.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.17 TEXT_GetTextOffset()

Description

Returns the offset set for X and Y position of the text.

Prototype

```
void TEXT_GetTextOffset(TEXT_Handle   hObj,
                        int         * pxPos,
                        int         * pyPos);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
pxPos	Pointer to an int to store the X-offset in pixels.
pyPos	Pointer to an int to store the Y-offset in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.18 TEXT_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.19 TEXT_GetWrapMode()

Description

Returns the currently used mode for wrapping text of the given TEXT widget.

Prototype

```
GUI_WRAPMODE TEXT_GetWrapMode(TEXT_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of the TEXT widget.

Return value

Currently used wrap mode.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.20 TEXT_SetBkColor()

Description

Sets the background color of the TEXT widget.

Prototype

```
void TEXT_SetBkColor(TEXT_Handle hObj,
                     GUI_COLOR   Color);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
Color	Color to be used for the background. (range 0x000000 and 0xFFFFFF or a valid color define) GUI_INVALID_COLOR to make background transparent

Additional information

The background of this widget can either be filled with any available color or transparent. If a valid RGB color is specified, the background is filled with the color, otherwise the background (typically the content of the parent window) is visible. If the background is transparent, the widget is treated as transparent window, otherwise as non-transparent window. Note that using a background color allows more efficient (faster) rendering.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.21 TEXT_SetDec()

Description

This function sets a value which gets displayed by the TEXT widget.

Prototype

```
int TEXT_SetDec(TEXT_Handle hObj,
                I32         v,
                U8          Len,
                U8          Shift,
                U8          Signed,
                U8          Space);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
v	Value to be displayed.
Len	Number of digits to be displayed. If this value is higher than the numbers to be displayed, leading zeros will be added.
Shift	This sets the position of the decimal point.
Signed	If 1, a minus or plus sign will be added to the value. If the value is negative a minus is displayed regardless of the value of this parameter.
Space	If set to 1 the leading zeros will be replaced by blank spaces.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.22 TEXT_SetDefaultFont()

Description

Sets the default font used for TEXT widgets.

Prototype

```
void TEXT_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to the font to be set as default.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.23 TEXT_SetDefaultRotation()

Description

Sets the default rotation mode for new TEXT widgets.

Prototype

```
GUI_ROTATION *TEXT_SetDefaultRotation(const GUI_ROTATION * pLCD_Api);
```

Parameters

Parameter	Description
pLCD_Api	Text rotation mode. See *Text rotation modes* on page 220 for a list of possible values.

Return value

Default text rotation mode.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.24 TEXT_SetDefaultTextColor()

Description

Sets the default text color used for TEXT widgets.

Prototype

```
void TEXT_SetDefaultTextColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.25 TEXT_SetDefaultWrapMode()

Description

Sets the default text wrapping mode used for new TEXT widgets.

Prototype

```
GUI_WRAPMODE TEXT_SetDefaultWrapMode(GUI_WRAPMODE WrapMode);
```

Parameters

Parameter	Description
WrapMode	Default text wrapping mode used for new TEXT widgets. See *GUI_WRAPMODE* on page 222.

Return value

Previous default text wrapping mode.

Additional information

The default wrapping mode for TEXT widgets is GUI_WRAPMODE_NONE. For details about text wrapping, refer to GUI_DispStringInRectWrap().

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.26 TEXT_SetFont()

Description

Sets the font to be used for a specified TEXT widget.

Prototype

```
void TEXT_SetFont(      TEXT_Handle   hObj,
                  const GUI_FONT    * pFont);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
pFont	Pointer to the font to be used.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.27 TEXT_SetRotation()

Description

Sets the text rotation for a TEXT widget.

Prototype

```
void TEXT_SetRotation(      TEXT_Handle    hObj,
                      const GUI_ROTATION * pLCD_Api);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
pLCD_Api	Text rotation mode. See full list under *Text rotation modes* on page 220.

Additional information

To learn more about rotating text in emWin, refer to `GUI_DispStringInRectEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.28 TEXT_SetText()

Description

Sets the text to be used for a specified TEXT widget.

Prototype

```
int TEXT_SetText(      TEXT_Handle   hObj,
                 const char        * s);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
s	Text to be displayed.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.29 TEXT_SetTextAlign()

Description

Sets the text alignment of a specified TEXT widget.

Prototype

```
void TEXT_SetTextAlign(TEXT_Handle hObj,
                       int         Align);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
Align	Text alignment. See *TEXT create flags* on page 2145.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.30 TEXT_SetTextColor()

Description

Sets the text color of a specified TEXT widget.

Prototype

```
void TEXT_SetTextColor(TEXT_Handle hObj,
                       GUI_COLOR   Color);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
Color	New text color.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.31 TEXT_SetTextOffset()

Description

Sets an X- and Y-offset for the text of a TEXT widget.

Prototype

```
void TEXT_SetTextOffset(TEXT_Handle hObj,
                        int         xPos,
                        int         yPos);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
xPos	X-offset in pixels.
yPos	Y-offset in pixels.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.32 TEXT_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.31.5.1.33 TEXT_SetWrapMode()

Description

Sets the wrapping mode of a specified TEXT widget.

Prototype

```
void TEXT_SetWrapMode(TEXT_Handle  hObj,
                      GUI_WRAPMODE WrapMode);
```

Parameters

Parameter	Description
hObj	Handle of TEXT widget.
WrapMode	See *GUI_WRAPMODE* on page 222 for a list of possible values.

Additional information

The default wrapping mode for TEXT widgets is GUI_WRAPMODE_NONE. For more details about text wrapping, refer to GUI_DispStringInRectWrap().

 © 2020 SEGGER Microcontroller GmbH

20.31.5.2 Defines

20.31.5.2.1 TEXT create flags

Description

Create flags used by the TEXT widget. These flags are used for the `ExFlags` parameter of `TEXT_CreateEx()`.

Definition

```
#define TEXT_CF_LEFT       (0)
#define TEXT_CF_HCENTER    (2 << 0)
#define TEXT_CF_RIGHT      (1 << 0)
#define TEXT_CF_TOP        (0)
#define TEXT_CF_VCENTER    (3 << 2)
#define TEXT_CF_BOTTOM     (1 << 2)
```

Symbols

Definition	Description
Horizontal alignment	
TEXT_CF_LEFT	Align X-position left.
TEXT_CF_HCENTER	Center X-position.
TEXT_CF_RIGHT	Align X-position right.
Vertical alignment	
TEXT_CF_TOP	Align Y-position with top of characters.
TEXT_CF_VCENTER	Center Y-position.
TEXT_CF_BOTTOM	Align Y-position with bottom pixel line of font.

Additional information

These flags are identical to the Text alignment flags and can be used the same way, meaning horizontal and vertical flags can be OR-combined.

 © 2020 SEGGER Microcontroller GmbH

20.31.6 Examples

There is no special sample for this widget, since many of the emWin samples use it:

- `DIALOG_Count.c`
- `DIALOG_Radio.c`
- `WIDGET_GraphXY.c`
- …

 © 2020 SEGGER Microcontroller GmbH

20.32 TREEVIEW: Treeview widget

A TREEVIEW widget can be used to show a hierarchical view of information like files in a directory or items of an index, whereas each item can be a node or a leaf. Each node can have a number of sub items and can be closed or opened.

A node consists of a button image, which shows a plus sign in closed state or a minus sign in open state, two item images (one for closed and one for open state) and the item text. Pressing the button image or double clicking the item image toggles the state (open or closed) of the node.

A leaf consists of an item image and the item text. The current selection can be marked by highlighting the item text or by highlighting the whole row. All items of a tree are joined by lines per default.

> **Note**
>
> All TREEVIEW-related routines are located in the file(s) `TREEVIEW*.c`, `TREEVIEW*.h`. All identifiers are prefixed TREEVIEW.

The table below shows the appearances of the TREEVIEW widget:

Description	TREEVIEW widget
TREEVIEW widget with row selection enabled.	
TREEVIEW widget with text selection enabled.	
TREEVIEW widget with some application defined bitmaps and lines off.	

 © 2020 SEGGER Microcontroller GmbH

20.32.1 Description of terms

Item

This means a TREEVIEW item which can be a leaf or a node.

Leaf

A leaf is a TREEVIEW item which is not able to have any children. It is represented by the leaf bitmap and the item text.

Node

A node is a TREEVIEW item which is able to have children. It is represented by the button bitmap, the node bitmap and the item text. The state of the node can be toggled by pressing the button bitmap or by double clicking the node bitmap or the selected area of the item. In open state the children are visible below the node at the next level of indentation.

Button bitmap

This means the bitmap visible at nodes which can be pressed to toggle the state of the node.

Item bitmap

Left beside the item text the item bitmap is shown. Which bitmap is shown depends in the item (leaf or node) and in case of a node it also depends on the state, collapsed or expanded.

Expanded state

In expanded state the children of a node are visible and the minus sign is shown in the button bitmap.

Collapsed state

In collapsed state the children of a node are hidden and the plus sign is shown in the button bitmap.

Joining lines

Lines which are used to connect the items of a tree. The lines connect the button bit- maps of the nodes and the item bitmaps of the leafs according to the hierarchy of the tree.

20.32.2 Configuration options

Type	Macro	Default	Description
S	TREEVIEW_FONT_DEFAULT	&GUI_Font13_1	Default font used to draw the text.
N	TREEVIEW_BKCOLOR0_DEFAULT	GUI_WHITE	Background color for unselected state.
N	TREEVIEW_BKCOLOR1_DEFAULT	GUI_BLUE	Background color for selected state.
N	TREEVIEW_BKCOLOR2_DEFAULT	0xC0C0C0	Background color for disabled state.
N	TREEVIEW_TEXTCOLOR0_DEFAULT	GUI_BLACK	Text color for unselected state.
N	TREEVIEW_TEXTCOLOR1_DEFAULT	GUI_WHITE	Text color for selected state.
N	TREEVIEW_TEXTCOLOR2_DEFAULT	GUI_GRAY	Text color for disabled state.

 © 2020 SEGGER Microcontroller GmbH

Type	Macro	Default	Description
N	TREEVIEW_LINECOLOR0_DEFAULT	GUI_BLACK	Line color for unselected state.
N	TREEVIEW_LINECOLOR1_DEFAULT	GUI_WHITE	Line color for selected state.
N	TREEVIEW_LINECOLOR2_DEFAULT	GUI_GRAY	Line color for disabled state.
S	TREEVIEW_IMAGE_CLOSED_DEFAULT		Item image for node in closed state.
S	TREEVIEW_IMAGE_OPEN_DEFAULT		Item image for node in open state.
S	TREEVIEW_IMAGE_LEAF_DEFAULT		Item image for leaf.
S	TREEVIEW_IMAGE_PLUS_DEFAULT		Plus sign.
S	TREEVIEW_IMAGE_MINUS_DEFAULT		Minus sign.
N	TREEVIEW_INDENT_DEFAULT	16	Number of pixels for indenting.
N	TREEVIEW_TEXT_INDENT_DEFAULT	20	Number of pixels for indenting text.

20.32.3 Predefined IDs

The following symbols define IDs which may be used to make TREEVIEW widgets distinguishable from creation.

```
#define GUI_ID_TREEVIEW0    0x240
#define GUI_ID_TREEVIEW1    0x241
#define GUI_ID_TREEVIEW2    0x242
#define GUI_ID_TREEVIEW3    0x243
#define GUI_ID_TREEVIEW4    0x244
#define GUI_ID_TREEVIEW5    0x245
#define GUI_ID_TREEVIEW6    0x246
#define GUI_ID_TREEVIEW7    0x247
#define GUI_ID_TREEVIEW8    0x248
#define GUI_ID_TREEVIEW9    0x249
```

20.32.4 Notification codes

The following events are sent from a treeview widget to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_CLICKED	TREEVIEW has been clicked.
WM_NOTIFICATION_RELEASED	TREEVIEW has been released.
WM_NOTIFICATION_MOVED_OUT	TREEVIEW has been clicked and pointer has been moved out of the widget area without releasing.
WM_NOTIFICATION_SEL_CHANGED	Value (selection) of the TREEVIEW widget has changed.

20.32.5 Keyboard reaction

The widget reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_RIGHT	If the cursor is at a closed node, the node is opened.

 © 2020 SEGGER Microcontroller GmbH

Key	Reaction
	If the cursor is at an open node the cursor moves to the first child of the node.
GUI_KEY_DOWN	The cursor moves to the next visible item below the current position.
GUI_KEY_LEFT	If the cursor is at a leaf the cursor moves to the parent node of the item. If the cursor is at an open node, the node will be closed. If the cursor is at a closed node, the cursor moves to the next parent node.
GUI_KEY_UP	The cursor moves to the previous visible item above the current position.

20.32.6 TREEVIEW API

The table below lists the available TREEVIEW-related routines of emWin in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
Common routines	
TREEVIEW_AttachItem()	Attaches an already existing item to the TREEVIEW widget.
TREEVIEW_CreateEx()	Creates a TREEVIEW widget.
TREEVIEW_CreateIndirect()	Creates a TREEVIEW widget from a resource table.
TREEVIEW_CreateUser()	Creates a TREEVIEW widget using extra bytes as user data.
TREEVIEW_DecSel()	Moves the cursor to the previous visible item.
TREEVIEW_GetDefaultBkColor()	Returns the default background color.
TREEVIEW_GetDefaultFont()	Returns the default font used to draw the item text.
TREEVIEW_GetDefaultLineColor()	Returns the default line color.
TREEVIEW_GetDefaultTextColor()	Returns the default text color.
TREEVIEW_GetItem()	Returns the requested item.
TREEVIEW_GetSel()	Returns the currently selected item.
TREEVIEW_GetUserData()	Retrieves the data set with TREEVIEW_SetUserData().
TREEVIEW_IncSel()	Moves the cursor to the next visible item of the given TREEVIEW widget.
TREEVIEW_InsertItem()	The function creates and inserts one new TREEVIEW item relative to the given item.
TREEVIEW_ScrollToSel()	Scrolls the given TREEVIEW widget to show the current selection.
TREEVIEW_SetAutoScrollH()	Enables or disables the use of an automatic horizontal scroll bar.
TREEVIEW_SetAutoScrollV()	Enables or disables the use of an automatic vertical scroll bar.
TREEVIEW_SetBitmapOffset()	Sets the offset of the plus/minus bitmap.
TREEVIEW_SetBkColor()	Sets the background color.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
TREEVIEW_SetDefaultBkColor()	Sets the default background color used for new TREEVIEW widgets.
TREEVIEW_SetDefaultFont()	Sets the default font used for new TREEVIEW widgets.
TREEVIEW_SetDefaultLineColor()	Sets the default line color used for new TREEVIEW widgets.
TREEVIEW_SetDefaultTextColor()	Sets the default text color used for new TREEVIEW widgets.
TREEVIEW_SetFont()	Sets the font to be used to draw the item text of the given TREEVIEW widget.
TREEVIEW_SetHasLines()	Manages the visibility of the joining lines between the TREEVIEW items.
TREEVIEW_SetImage()	Sets the images used to draw the TREEVIEW items.
TREEVIEW_SetIndent()	Sets the indentation of TREEVIEW items in pixels.
TREEVIEW_SetLineColor()	Sets the color used to draw the joining lines between the TREEVIEW items.
TREEVIEW_SetOwnerDraw()	Enables the TREEVIEW to be owner drawn.
TREEVIEW_SetSel()	Sets the currently selected item of the TREEVIEW widget.
TREEVIEW_SetSelMode()	Sets the selection mode of the TREEVIEW widget.
TREEVIEW_SetTextColor()	Sets the color used to draw the TREEVIEW items of the given TREEVIEW widget.
TREEVIEW_SetTextIndent()	Sets the indentation of item text in pixels.
TREEVIEW_SetUserData()	Sets the extra data of a TREEVIEW widget.
Item related routines	
TREEVIEW_ITEM_Collapse()	Collapses the given node.
TREEVIEW_ITEM_CollapseAll()	Collapses the given node and all subnodes.
TREEVIEW_ITEM_Create()	Creates a new TREEVIEW item.
TREEVIEW_ITEM_Delete()	Deletes the given TREEVIEW item.
TREEVIEW_ITEM_Detach()	Detaches the given item without deleting it.
TREEVIEW_ITEM_Expand()	Expands the given node.
TREEVIEW_ITEM_ExpandAll()	Expands the given node and all subnodes.
TREEVIEW_ITEM_GetInfo()	Returns an information structure of the given item.
TREEVIEW_ITEM_GetText()	Returns the item text.
TREEVIEW_ITEM_GetUserData()	Returns the UserData value of the treeview item.
TREEVIEW_ITEM_SetImage()	The function sets images to be used only with the given TREEVIEW item.
TREEVIEW_ITEM_SetText()	The function sets the text of the given item.
TREEVIEW_ITEM_SetUserData()	Sets the UserData value of the TREEVIEW item.

 © 2020 SEGGER Microcontroller GmbH

Data structures

Structure	Description
TREEVIEW_ITEM_INFO	Structure that contains information about a node in a TREEVIEW widget.

Defines

Group of defines	Description
TREEVIEW bitmap indexes	Bitmap indexes used by the TREEVIEW widget.
TREEVIEW color indexes	Color indexes used by the TREEVIEW widget.
TREEVIEW create flags	Create flags used by the TREEVIEW widget.
TREEVIEW item flags	Define the item type of a newly created TREEVIEW item.
TREEVIEW position flags (get)	Specify the position when retrieving a TREEVIEW item.
TREEVIEW position flags (insert)	Specify the position when creating a new TREEVIEW item.
TREEVIEW selection modes	Define the selection mode of a TREEVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1 Common routines

20.32.6.1.1 TREEVIEW_AttachItem()

Description

Attaches an already existing item to the TREEVIEW widget.

Prototype

```
int TREEVIEW_AttachItem(TREEVIEW_Handle      hObj,
                        TREEVIEW_ITEM_Handle hItem,
                        TREEVIEW_ITEM_Handle hItemAt,
                        int                  Position);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
hItem	Handle of item to be attached.
hItemAt	Handle of a currently attached item which specifies the position to be used.
Position	See *TREEVIEW position flags (insert)* on page 2206 for a full list of permitted values.

Return value

0 on success
1 on error.

Additional information

The function can be used for attaching a single item as well as for attaching a complete tree. Note that in case of attaching a tree, the root item of the tree needs to be passed as hItem. If attaching the first item to an empty treeview the parameters hItem and Position should be 0.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.2 TREEVIEW_CreateEx()

Description

Creates a TREEVIEW widget of a specified size at a specified location.

Prototype

```
TREEVIEW_Handle TREEVIEW_CreateEx(int     x0,
                                  int     y0,
                                  int     xSize,
                                  int     ySize,
                                  WM_HWIN hParent,
                                  int     WinFlags,
                                  int     ExFlags,
                                  int     Id);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the widget (in parent coordinates).
y0	Topmost pixel of the widget (in parent coordinates).
xSize	Horizontal size of the widget (in pixels).
ySize	Vertical size of the widget (in pixels).
hParent	Handle of parent window. If 0, the new TEXT widget will be a child of the desktop (top-level window).
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	See *TREEVIEW create flags* on page 2203.
Id	Window ID of the widget.

Return value

Handle of the created widget. 0, if the function fails.

Additional information

The values of parameter ExFlags can be OR-combined.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.3 TREEVIEW_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Para` of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element `Flags` is used according to the parameter `ExFlags` of the function `TREEVIEW_CreateEx()`.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.4 TREEVIEW_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `TREEVIEW_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.5 TREEVIEW_DecSel()

Before	After
	

Description

Moves the cursor to the previous visible item of the given TREEVIEW widget.

Prototype

```
void TREEVIEW_DecSel(TREEVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.

Additional information

If there is no previous visible item the cursor remains on the current position.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.6 TREEVIEW_GetDefaultBkColor()

Description

Returns the default background color used for new TREEVIEW widgets.

Prototype

```
GUI_COLOR TREEVIEW_GetDefaultBkColor(int Index);
```

Parameters

Parameter	Description
Index	See *TREEVIEW color indexes* on page 2202 for a full list of permitted values.

Return value

Default background color used for new TREEVIEW widgets.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.7 TREEVIEW_GetDefaultFont()

Description

Returns the default font used to draw the item text of new TREEVIEW widgets.

Prototype

```
GUI_FONT *TREEVIEW_GetDefaultFont(void);
```

Return value

Default font used to draw the item text of new TREEVIEW widgets.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.8 TREEVIEW_GetDefaultLineColor()

Description

Returns the default color used to draw the joining lines of new TREEVIEW widgets.

Prototype

```
GUI_COLOR TREEVIEW_GetDefaultLineColor(int Index);
```

Parameters

Parameter	Description
Index	See *TREEVIEW color indexes* on page 2202 for a full list of permitted values.

Return value

Default color used to draw the joining lines of new treeview widgets.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.9 TREEVIEW_GetDefaultTextColor()

Description

Returns the default text color used to draw the item text of new TREEVIEW widgets.

Prototype

```
GUI_COLOR TREEVIEW_GetDefaultTextColor(int Index);
```

Parameters

Parameter	Description
Index	See *TREEVIEW color indexes* on page 2202 for a full list of permitted values.

Return value

Default text color used to draw the item text of new TREEVIEW widgets.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.10 TREEVIEW_GetItem()

Description

Returns the handle of the requested treeview item.

Prototype

```
TREEVIEW_ITEM_Handle TREEVIEW_GetItem(TREEVIEW_Handle      hObj,
                                      TREEVIEW_ITEM_Handle hItem,
                                      int                  Flags);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
hItem	Handle of TREEVIEW item specifying the position to start search from.
Flags	See *TREEVIEW position flags (get)* on page 2205 for a full list of permitted values.

Return value

Handle of the requested TREEVIEW item on success, otherwise 0.

Example

The picture shows a TREEVIEW widget with several items. The following shows how parameter Flags can be used for getting TREEVIEW items relative to parameter hItem:

- TREEVIEW_GET_NEXT_SIBLING
  The next sibling of 1.1 is 1.2.
- TREEVIEW_GET_PREV_SIBLING
  The previous sibling of 1.2 is 1.1.
- TREEVIEW_GET_FIRST_CHILD
  The first child item of 1.1.1 is 1.1.1.1.
- TREEVIEW_GET_PARENT
  The parent item of 1.1 is 1.



The use of TREEVIEW_GET_FIRST and TREEVIEW_GET_LAST should be obvious. If the requested item does not exist, the function returns 0.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.11 TREEVIEW_GetSel()

Description

Returns the handle of the currently selected TREEVIEW item.

Prototype

```
TREEVIEW_ITEM_Handle TREEVIEW_GetSel(TREEVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.

Return value

Handle of the currently selected treeview item. If no item has been selected the return value is 0.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.12 TREEVIEW_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.13 TREEVIEW_IncSel()

Before	After
	

Description

Moves the cursor to the next visible item of the given TREEVIEW widget.

Prototype

```
void TREEVIEW_IncSel(TREEVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.

Additional information

If there is no next visible item the cursor remains on the current position.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.14 TREEVIEW_InsertItem()

Before	After
	

Description

The function creates and inserts one new TREEVIEW item relative to the given item.

Prototype

```
TREEVIEW_ITEM_Handle TREEVIEW_InsertItem(      TREEVIEW_Handle        hObj,
                                               int                    IsNode,
                                               TREEVIEW_ITEM_Handle   hItemPrev,
                                               int                    Position,
                                         const char                 * s);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
IsNode	See *TREEVIEW item flags* on page 2204 for a full list of permitted values.
hItemPrev	Handle of TREEVIEW item specifying the position of the new item.
Position	See *TREEVIEW position flags (insert)* on page 2206 for a full list of permitted values.
s	Text of new TREEVIEW item.

Return value

Handle of the new item on success, otherwise 0.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.15 TREEVIEW_ScrollToSel()

Before	After
	

Description

Scrolls the given TREEVIEW widget to show the current selection.

Prototype

```
void TREEVIEW_ScrollToSel(TREEVIEW_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.16 TREEVIEW_SetAutoScrollH()

Before	After
	

Description

Enables or disables the use of an automatic horizontal scroll bar.

Prototype

```
void TREEVIEW_SetAutoScrollH(TREEVIEW_Handle hObj,
                             int             State);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
State	1 for enabling an automatic horizontal scroll bar, 0 for disabling.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.17 TREEVIEW_SetAutoScrollV()

Before	After
	

Description

Enables or disables the use of an automatic vertical scroll bar.

Prototype

```
void TREEVIEW_SetAutoScrollV(TREEVIEW_Handle hObj,
                             int             State);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
State	1 for enabling an automatic vertical scroll bar, 0 for disabling.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.18 TREEVIEW_SetBitmapOffset()

Before	After
	

Description

Sets the offset of the plus/minus bitmap.

Prototype

```
void TREEVIEW_SetBitmapOffset(TREEVIEW_Handle hObj,
                              int             Index,
                              int             xOff,
                              int             yOff);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
Index	Currently the only permitted value for this parameter is TREEVIEW_BI_PM.
xOff	Horizontal offset.
yOff	Vertical offset.

Additional information

If xOff and yOff are set to 0 (default), the plus/minus bitmap is centered horizontally and vertically in the indentation space left of the actual item. The indentation space is related to the parent item (if exists) or to the left border of the widget. See “before / after” screenshots of the function TREEVIEW_SetIndent().

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.19 TREEVIEW_SetBkColor()

Before	After
	

Description

Sets the background color of the given TREEVIEW widget.

Prototype

```
void TREEVIEW_SetBkColor(TREEVIEW_Handle hObj,
                         int             Index,
                         GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
Index	See *TREEVIEW color indexes* on page 2202 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.20 TREEVIEW_SetDefaultBkColor()

Description

Sets the default background color used for new TREEVIEW widgets.

Prototype

```
void TREEVIEW_SetDefaultBkColor(int       Index,
                                GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *TREEVIEW color indexes* on page 2202 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.21 TREEVIEW_SetDefaultFont()

Description

Sets the default font used for new TREEVIEW widgets.

Prototype

```
void TREEVIEW_SetDefaultFont(const GUI_FONT * pFont);
```

Parameters

Parameter	Description
pFont	Pointer to GUI_FONT structure to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.22 TREEVIEW_SetDefaultLineColor()

Description

Sets the default line color used for new TREEVIEW widgets.

Prototype

```
void TREEVIEW_SetDefaultLineColor(int       Index,
                                  GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *TREEVIEW color indexes* on page 2202 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.23 TREEVIEW_SetDefaultTextColor()

Description

Sets the default text color used for new TREEVIEW widgets.

Prototype

```
void TREEVIEW_SetDefaultTextColor(int       Index,
                                  GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *TREEVIEW color indexes* on page 2202 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.24 TREEVIEW_SetFont()

Before	After
	

Description

Sets the font to be used to draw the item text of the given TREEVIEW widget.

Prototype

```
void TREEVIEW_SetFont(      TREEVIEW_Handle   hObj,
                      const GUI_FONT        * pFont);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
pFont	Pointer to GUI_FONT structure to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.25 TREEVIEW_SetHasLines()

Before	After
	

Description

Manages the visibility of the joining lines between the TREEVIEW items.

Prototype

```
void TREEVIEW_SetHasLines(TREEVIEW_Handle hObj,
                          int             State);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
State	1 for showing the lines, 0 for not showing the lines.

Additional information

Per default the lines are shown.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.26 TREEVIEW_SetImage()

Before	After
	

Description

Sets the images used to draw the TREEVIEW items.

Prototype

```
void TREEVIEW_SetImage(      TREEVIEW_Handle   hObj,
                             int               Index,
                       const GUI_BITMAP      * pBitmap);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
Index	See *TREEVIEW bitmap indexes* on page 2201 for a full list of permitted values.
pBitmap	Pointer to bitmap structure to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.27 TREEVIEW_SetIndent()

Before	After
	

Description

Sets the indentation of TREEVIEW items in pixels. Indentation is 16 pixels by default.

Prototype

```
int TREEVIEW_SetIndent(TREEVIEW_Handle hObj,
                       int             Indent);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
Indent	Distance (in pixels) to indent treeview items.

Return value

Previous indentation.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.28 TREEVIEW_SetLineColor()

Before	After
	

Description

Sets the color used to draw the joining lines between the TREEVIEW items.

Prototype

```
void TREEVIEW_SetLineColor(TREEVIEW_Handle hObj,
                           int             Index,
                           GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
Index	See *TREEVIEW color indexes* on page 2202 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.29 TREEVIEW_SetOwnerDraw()

Description

Enables the TREEVIEW to be owner drawn.

Prototype

```
void TREEVIEW_SetOwnerDraw(TREEVIEW_Handle         hObj,
                           WIDGET_DRAW_ITEM_FUNC * pfDrawItem);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
pfDrawItem	Pointer to the owner draw function. See *User drawn widgets* on page 983.

Supported commands

- WIDGET_ITEM_GET_XSIZE
- WIDGET_ITEM_GET_YSIZE
- WIDGET_ITEM_DRAW_BACKGROUND
- WIDGET_ITEM_DRAW_BITMAP
- WIDGET_ITEM_DRAW_TEXT
- WIDGET_ITEM_DRAW_TICKS

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.30 TREEVIEW_SetSel()

Before	After
	

Description

Sets the currently selected item of the TREEVIEW widget.

Prototype

```
void TREEVIEW_SetSel(TREEVIEW_Handle      hObj,
                     TREEVIEW_ITEM_Handle hItem);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
hItem	Handle of treeview item to be selected.

Additional information

If the given TREEVIEW item is a child of a closed node no selection is visible after calling this function.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.31 TREEVIEW_SetSelMode()

Before	After
	

Description

Sets the selection mode of the TREEVIEW widget.

Prototype

```
void TREEVIEW_SetSelMode(TREEVIEW_Handle hObj,
                         int             Mode);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
Mode	See *TREEVIEW selection modes* on page 2207.

Additional information

Default selection mode is text selection. If row selection is activated, the complete row can be used to select the item. If text selection is active, only the item text and the item bitmap can be used for selection.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.32 TREEVIEW_SetTextColor()

Before	After
	

Description

Sets the color used to draw the TREEVIEW items of the given TREEVIEW widget.

Prototype

```
void TREEVIEW_SetTextColor(TREEVIEW_Handle hObj,
                           int             Index,
                           GUI_COLOR       Color);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
Index	See *TREEVIEW color indexes* on page 2202 for a full list of permitted values.
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.33 TREEVIEW_SetTextIndent()

Before	After
	

Description

Sets the indentation of item text in pixels. Text indentation is 20 pixels by default.

Prototype

```
int TREEVIEW_SetTextIndent(TREEVIEW_Handle hObj,
                           int             TextIndent);
```

Parameters

Parameter	Description
hObj	Handle of TREEVIEW widget.
TextIndent	Text indentation to be used.

Return value

Previous text indentation.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.1.34 TREEVIEW_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2 Item related routines

20.32.6.2.1 TREEVIEW_ITEM_Collapse()

Before	After
	

Description

Collapses the given node and shows the plus sign afterwards.

Prototype

```
void TREEVIEW_ITEM_Collapse(TREEVIEW_ITEM_Handle hItem);
```

Parameters

Parameter	Description
hItem	Handle of the item to be collapsed.

Additional information

The given item needs to be a node. Otherwise the function returns immediately.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.2 TREEVIEW_ITEM_CollapseAll()

Before	All nodes collapsed	Expanded again
		

Description

Collapses the given node and all subnodes and shows the plus sign afterwards.

Prototype

```
void TREEVIEW_ITEM_CollapseAll(TREEVIEW_ITEM_Handle hItem);
```

Parameters

Parameter	Description
hItem	Handle of the item to be collapsed.

Additional information

This function collapses all subnodes, so if the given node is expanded again, all subnodes are in collapsed state.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.3 TREEVIEW_ITEM_Create()

Description

Creates a new TREEVIEW item.

Prototype

```
TREEVIEW_ITEM_Handle TREEVIEW_ITEM_Create(      int    IsNode,
                                          const char * s,
                                                U32    UserData);
```

Parameters

Parameter	Description
IsNode	See *TREEVIEW item flags* on page 2204 for a full list of permitted values.
s	Pointer to item text to be shown.
UserData	32 bit value to be used by the application.

Return value

Handle of new item on success, otherwise 0.

Additional information

After creating a treeview item it contains a copy of the text.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.4 TREEVIEW_ITEM_Delete()

Description

Deletes the given TREEVIEW item.

Prototype

```
void TREEVIEW_ITEM_Delete(TREEVIEW_ITEM_Handle hItem);
```

Parameters

Parameter	Description
hItem	Handle of item to be deleted.

Additional information

If the item is currently not attached to any TREEVIEW, the parameter hObj should be 0. The function can be used to delete a single item as well as for deleting a complete tree. In case of deleting a tree the root element of the tree should be passed to the function.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.5 TREEVIEW_ITEM_Detach()

Description

Detaches the given TREEVIEW item from the TREEVIEW widget.

Prototype

```
void TREEVIEW_ITEM_Detach(TREEVIEW_ITEM_Handle hItem);
```

Parameters

Parameter	Description
hItem	Handle of item to be detached.

Additional information

The function detaches the given item and all of its children from the TREEVIEW widget.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.6 TREEVIEW_ITEM_Expand()

Before	After
	

Description

Expands the given node and shows the minus sign afterwards.

Prototype

```
void TREEVIEW_ITEM_Expand(TREEVIEW_ITEM_Handle hItem);
```

Parameters

Parameter	Description
hItem	Handle of node to be expanded.

Additional information

The given item needs to be a node. Otherwise the function returns immediately.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.7 TREEVIEW_ITEM_ExpandAll()

Before	After
	

Description

Expands the given node and all subnodes and shows the minus sign afterwards.

Prototype

```
void TREEVIEW_ITEM_ExpandAll(TREEVIEW_ITEM_Handle hItem);
```

Parameters

Parameter	Description
hItem	Handle of node to be expanded.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.8 TREEVIEW_ITEM_GetInfo()

Description

Returns a structure with information about the given item.

Prototype

```
void TREEVIEW_ITEM_GetInfo(TREEVIEW_ITEM_Handle   hItem,
                           TREEVIEW_ITEM_INFO   * pInfo);
```

Parameters

Parameter	Description
hItem	Handle of TREEVIEW item.
pInfo	Pointer to a TREEVIEW_ITEM_INFO structure to be filled by the function.

Additional information

The elements of the information structure are explained under *TREEVIEW_ITEM_INFO* on page 2200.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.9 TREEVIEW_ITEM_GetText()

Description

Returns the item text of the given TREEVIEW item.

Prototype

```
void TREEVIEW_ITEM_GetText(TREEVIEW_ITEM_Handle   hItem,
                           U8                   * pBuffer,
                           int                    MaxNumBytes);
```

Parameters

Parameter	Description
hItem	Handle of TREEVIEW item.
pBuffer	Pointer to buffer filled by the function.
MaxNumBytes	Size of the buffer in bytes.

Additional information

If MaxNumBytes is less than the item text length the buffer is filled with the first MaxNumBytes of the item text.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.10 TREEVIEW_ITEM_GetUserData()

Description

The function return the 32 bit value associated with the given treeview item which can be used by the application program.

Prototype

```
U32 TREEVIEW_ITEM_GetUserData(TREEVIEW_ITEM_Handle hItem);
```

Parameters

Parameter	Description
hItem	Handle of TREEVIEW item.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.11 TREEVIEW_ITEM_SetImage()

Before	After
	

Description

The function sets images to be used only with the given TREEVIEW item.

Prototype

```
void TREEVIEW_ITEM_SetImage(      TREEVIEW_ITEM_Handle   hItem,
                                  int                    Index,
                            const GUI_BITMAP           * pBitmap);
```

Parameters

Parameter	Description
hItem	Handle of TREEVIEW item.
Index	See *TREEVIEW bitmap indexes* on page 2201. Only the first three values **...CLOSED**, **...OPEN** and **...LEAF** may be used.
pBitmap	Pointer to bitmap structure to be used.

Additional information

This function 'overwrites' the default images of the widget. If no individual image is set the default image is used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.12 TREEVIEW_ITEM_SetText()

Before	After
	

Description

The function sets the text of the given item.

Prototype

```
TREEVIEW_ITEM_Handle TREEVIEW_ITEM_SetText(      TREEVIEW_ITEM_Handle   hItem,
                                           const char                * s);
```

Parameters

Parameter	Description
hItem	Handle of TREEVIEW item.
s	Pointer to text to be used.

Return value

Handle of the TREEVIEW item with the new text.

Additional information

The text will be copied into the treeview item. Note that using this function changes the handle of the item. After calling this function, the new handle needs to be used.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.2.13 TREEVIEW_ITEM_SetUserData()

Description

The function sets a 32 bit value associated with the given treeview item which can be used by the application program.

Prototype

```
void TREEVIEW_ITEM_SetUserData(TREEVIEW_ITEM_Handle hItem,
                               U32                  UserData);
```

Parameters

Parameter	Description
hItem	Handle of TREEVIEW item.
UserData	32 bit value to be used by the application program.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.3 Data structures

20.32.6.3.1 TREEVIEW_ITEM_INFO

Description

Structure that contains information about a node in a TREEVIEW widget.

Type definition

```
typedef struct {
  int  IsNode;
  int  IsExpanded;
  int  HasLines;
  int  HasRowSelect;
  int  Level;
} TREEVIEW_ITEM_INFO;
```

Structure members

Member	Description
IsNode	1 if item is a node, 0 if not.
IsExpanded	1 if item (node) is open, 0 if closed.
HasLines	1 if joining lines are visible, 0 if not.
HasRowSelect	1 if row selection is active, 0 if not.
Level	Indentation level of item.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.4 Defines

20.32.6.4.1 TREEVIEW bitmap indexes

Description

Bitmap indexes used by the TREEVIEW widget. Refer to `TREEVIEW_SetImage()`.

Definition

```
#define TREEVIEW_BI_CLOSED    0
#define TREEVIEW_BI_OPEN      1
#define TREEVIEW_BI_LEAF      2
#define TREEVIEW_BI_PLUS      3
#define TREEVIEW_BI_MINUS     4
#define TREEVIEW_BI_PM        5
```

Symbols

Definition	Description
TREEVIEW_BI_CLOSED	Image of closed nodes.
TREEVIEW_BI_OPEN	Image of open nodes.
TREEVIEW_BI_LEAF	Image of leaf.
TREEVIEW_BI_PLUS	Plus sign of closed nodes.
TREEVIEW_BI_MINUS	Minus sign of open nodes.
TREEVIEW_BI_PM	Used by `TREEVIEW_SetBitmapOffset()` for setting the offset of the plus/minus bitmaps.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.4.2 TREEVIEW color indexes

Description

Color indexes used by the TREEVIEW widget.

Definition

```
#define TREEVIEW_CI_UNSEL       0
#define TREEVIEW_CI_SEL         1
#define TREEVIEW_CI_DISABLED    2
```

Symbols

Definition	Description
TREEVIEW_CI_UNSEL	Color of unselected element.
TREEVIEW_CI_SEL	Color of selected element.
TREEVIEW_CI_DISABLED	Color of disabled element.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.4.3 TREEVIEW create flags

Description

Create flags used by the TREEVIEW widget. These flags are used for the ExFlags parameter of TREEVIEW_CreateEx(). These values can be OR-combined.

Definition

```
#define TREEVIEW_CF_HIDELINES          (1 << 0)
#define TREEVIEW_CF_ROWSELECT          (1 << 1)
#define TREEVIEW_CF_AUTOSCROLLBAR_H    (1 << 2)
#define TREEVIEW_CF_AUTOSCROLLBAR_V    (1 << 3)
```

Symbols

Definition	Description
TREEVIEW_CF_HIDELINES	Joining lines are not displayed.
TREEVIEW_CF_ROWSELECT	Activates row selection mode.
TREEVIEW_CF_AUTOSCROLLBAR_H	Enables the use of an automatic horizontal scroll bar.
TREEVIEW_CF_AUTOSCROLLBAR_V	Enables the use of an automatic vertical scroll bar.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.4.4 TREEVIEW item flags

Description

Flags that define the item type of a newly created TREEVIEW item.

Definition

```
#define TREEVIEW_ITEM_TYPE_LEAF    (0 << 0)
#define TREEVIEW_ITEM_TYPE_NODE    (1 << 0)
```

Symbols

Definition	Description
TREEVIEW_ITEM_TYPE_LEAF	Used to create a leaf.
TREEVIEW_ITEM_TYPE_NODE	Used to create a node.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.4.5 TREEVIEW position flags (get)

Description

These flags are used to specify a position when retrieving an item of the TREEVIEW widget using the routine `TREEVIEW_GetItem()`.

Definition

```
#define TREEVIEW_GET_FIRST           0
#define TREEVIEW_GET_LAST            1
#define TREEVIEW_GET_NEXT_SIBLING    2
#define TREEVIEW_GET_PREV_SIBLING    3
#define TREEVIEW_GET_FIRST_CHILD     4
#define TREEVIEW_GET_PARENT          5
```

Symbols

Definition	Description
TREEVIEW_GET_FIRST	Returns the first item of the TREEVIEW widget. Parameter hItem is not required and can be 0.
TREEVIEW_GET_LAST	Returns the last item of the TREEVIEW widget. Parameter hItem is not required and can be 0.
TREEVIEW_GET_NEXT_SIBLING	Returns the next child item of the parent node of hItem.
TREEVIEW_GET_PREV_SIBLING	Returns the previous child item of the parent node of hItem.
TREEVIEW_GET_FIRST_CHILD	Returns the first child of the given node.
TREEVIEW_GET_PARENT	Returns the parent node of the given item.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.4.6 TREEVIEW position flags (insert)

Description

These flags are used to specify a position when creating and inserting a new item into the TREEVIEW widget.

Definition

```
#define TREEVIEW_INSERT_ABOVE          0
#define TREEVIEW_INSERT_BELOW          1
#define TREEVIEW_INSERT_FIRST_CHILD    2
```

Symbols

Definition	Description
TREEVIEW_INSERT_ABOVE	Attaches the item above the given position at the same indent level as the given position.
TREEVIEW_INSERT_BELOW	Attaches the item below the given position at the same indent level as the given position.
TREEVIEW_INSERT_FIRST_CHILD	Attaches the item below the given position by indenting it. The given position needs to be a node level.

 © 2020 SEGGER Microcontroller GmbH

20.32.6.4.7 TREEVIEW selection modes

Description

Flags that are used to define the selection mode of a TREEVIEW widget. Refer to `TREEVIEW_SetSelMode()` for more information.

Definition

```
#define TREEVIEW_SELMODE_ROW     1
#define TREEVIEW_SELMODE_TEXT    0
```

Symbols

Definition	Description
TREEVIEW_SELMODE_ROW	Activates row selection mode.
TREEVIEW_SELMODE_TEXT	Activates text selection mode.

 © 2020 SEGGER Microcontroller GmbH

20.32.7 Example

The `Sample` folder contains the following example which shows how the widget can be used:

- `WIDGET_TreeviewTryit.c`

> **Note**
>
> Several other examples also make use of this widget and may also be helpful to get familiar with the widget.

Screenshot of WIDGET_TreeviewTryit.c



 © 2020 SEGGER Microcontroller GmbH

20.33 WINDOW: Window widget

The WINDOW widget is used to create a dialog window from a resource table. It should be used if the dialog should not look like a frame window. The window widget acts as background and as a container for child windows: It can contain child windows and fills the background, typically with gray.
It behaves much like a frame-window without frame and title bar and is used for dialogs.

> **Note**
>
> All WINDOW-related routines are located in the file(s) `WINDOW.c`, `DIALOG.h`.

20.33.1 Configuration options

Type	Macro	Default	Description

S	`WINDOW_BKCOLOR_DEFAULT`
	`(with WIDGET_USE_FLEX_SKIN = 0)`
	`(with WIDGET_USE_FLEX_SKIN = 1)`
		`0xC0C0C0`
		`GUI_WHITE`
			Default background color for new WINDOW widgets.

20.33.2 Keyboard reaction

The widget can not gain the input focus and does not react on keyboard input.

20.33.3 WINDOW API

The table below lists the available emWin WINDOW-related routines in alphabetical order. Detailed descriptions of the routines follow.

Routine	Description
`WINDOW_CreateEx()`	Creates a WINDOW widget.
`WINDOW_CreateIndirect()`	Creates a WINDOW widget from a resource table entry.
`WINDOW_CreateUser()`	Creates a WINDOW widget using extra bytes as user data.
`WINDOW_GetUserData()`	Retrieves the data set with `WINDOW_SetUserData()`.
`WINDOW_SetBkColor()`	Sets the background color for the given WINDOW widget.
`WINDOW_SetDefaultBkColor()`	Sets the default background color used for WINDOW widgets.
`WINDOW_SetUserData()`	Sets the extra data of a WINDOW widget.

 © 2020 SEGGER Microcontroller GmbH

20.33.3.1 WINDOW_CreateEx()

Description

Creates a WINDOW widget of a specified size at a specified location.

Prototype

```
WM_HWIN WINDOW_CreateEx(int           x0,
                        int           y0,
                        int           xSize,
                        int           ySize,
                        WM_HWIN       hParent,
                        int           WinFlags,
                        int           ExFlags,
                        int           Id,
                        WM_CALLBACK * cb);
```

Parameters

Parameter	Description
x0	Leftmost pixel of the WINDOW widget (in parent coordinates)
y0	Topmost pixel of the WINDOW widget (in parent coordinates)
xSize	Size of the WINDOW widget in X
ySize	Size of the WINDOW widget in Y
hParent	Handle of parent window
WinFlags	Window create flags. Typically WM_CF_SHOW in order to make the widget visible immediately (refer to *Window create flags* on page 958 for a list of available parameter values).
ExFlags	Not used yet, reserved for future use
Id	Window ID of the WINDOW widget
cb	Pointer to callback routine.

Return value

Handle of the created WINDOW widget; 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

20.33.3.2 WINDOW_CreateIndirect()

Description

The prototype of this function is explained at the beginning of this chapter. Details can be found in the description of the function *<WIDGET>_CreateIndirect()* on page 974. The element `Para` of the according `GUI_WIDGET_CREATE_INFO` structure is not used. The element `Flags` is used according to the parameter WinFlags of the function `WINDOW_CreateEx()`. The `Sample` folder contains the file `WIDGET_Window.c` which shows how to use the WINDOW widget in a dialog resource.

 © 2020 SEGGER Microcontroller GmbH

20.33.3.3 WINDOW_CreateUser()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_CreateUser()* on page 975. For a detailed description of the parameters the function `WINDOW_CreateEx()` can be referred to.

 © 2020 SEGGER Microcontroller GmbH

20.33.3.4 WINDOW_GetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_GetUserData()* on page 976.

 © 2020 SEGGER Microcontroller GmbH

20.33.3.5 WINDOW_SetBkColor()

Description

Sets the background color for the given WINDOW widget.

Prototype

```
void WINDOW_SetBkColor(WM_HWIN   hObj,
                       GUI_COLOR Color);
```

Parameters

Parameter	Description
hObj	Handle of the WINDOW widget.
Color	Background color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.33.3.6 WINDOW_SetDefaultBkColor()

Description

Sets the default background color used for WINDOW widgets.

Prototype

```
void WINDOW_SetDefaultBkColor(GUI_COLOR Color);
```

Parameters

Parameter	Description
Color	Color to be used.

 © 2020 SEGGER Microcontroller GmbH

20.33.3.7 WINDOW_SetUserData()

Description

Prototype explained at the beginning of the chapter as *<WIDGET>_SetUserData()* on page 977.

 © 2020 SEGGER Microcontroller GmbH

Chapter 21

GUI Builder

The GUIBuilder application is a tool for creating dialogs without any knowledge of the C programming language. Instead of writing source code the widgets can be placed and sized by drag and drop. Additional properties can be added per context menu. Fine tuning can be done by editing the properties of the widgets. This does not require any knowledge of the C programming language. The dialogs can be saved as C files which can be enhanced by adding user defined code. Of course these C files with the embedded user code can be loaded and modified by the GUIBuilder.

Screenshot



 © 2020 SEGGER Microcontroller GmbH

21.1 Introduction

The following diagram shows the elements of the graphical user interface of the GUIBuilder:



Widget selection bar

This bar contains all available widgets of the GUIBuilder. They can be added by a single click into the selection bar on the desired widget or by dragging them into the editor area.

Object tree

This area shows all currently loaded dialogs and their child widgets. It can be used for selecting a widget by clicking on the according entry.

Widget properties

It shows the properties of each widget and can be used for editing them.

Editor

The editor window shows the currently selected dialog. It can be used to place and resize the dialog and its widgets.

 © 2020 SEGGER Microcontroller GmbH

21.2 Getting started

Before starting a project, the GUIBuilder needs to know the project path. Per default this is the application path of the GUIBuilder. All files are saved in this folder.

Setting up the project path

After the first execution, the GUIBuilder directory contains the configuration file `GUIBuilder.ini`. Within this file the project path can be changed by editing the value `ProjectPath`:

```
[Settings]
ProjectPath="C:
```

 © 2020 SEGGER Microcontroller GmbH

21.3 Creating a dialog

The following shows how to create a dialog and how to modify the properties of the used widgets.

21.3.1 Selecting a parent widget

Each dialog requires a valid parent widget. So it is required to start with a widget which is able to serve as a parent. Currently there are 2 widgets which can be used at this point:

Frame window widget	Window widget
	

The table above shows the according buttons of the widget selection bar. To get a widget into the editor the buttons can be single clicked, dragged with the mouse into the editor window or created by using the *New* menu.

21.3.2 Resizing and positioning in the editor

After placing a widget into the editor area it can be moved by using the mouse or the arrow keys of the keyboard. Resizing can be done by dragging the markers.



21.3.3 Modifying the widget properties

Property	Value
Name	Framewin
xPos	0
yPos	0
xSize	320
ySize	240
Extra bytes	0

The lower left area of the GUIBuilder contains the property window. After creating a new widget it shows the default properties of the widget: Name, position, size and extra bytes. These properties are available for all kinds of widgets and can not be removed. Contrary to the default properties all additional properties can be removed by the context menu or by pressing <DEL> when the according line is selected. To change a value it can be selected by the keyboard by pressing <ENTER> (if the desired line is selected and the window has the focus) or by single clicking into the value field. Further the 'Edit' entry of the context menu available with a right click can be used to start the edit operation. <ESC> can be used to abort the edit operation.

 © 2020 SEGGER Microcontroller GmbH

21.3.4 Adding additional functions to a widget

To get a context menu with the available functions for a widget either a right click in the editor window on the desired widget or a right click in the object tree can be done. Selecting a function adds a new property to the widget and starts the edit operation for the chosen function. In case of numerical or alpha numerical values the edit operation is done within the property window. In case of choosing fonts, text alignments or colors a separate selection window occurs.

Alignment selection

The alignment selection dialog shows the previous selected alignment in green. A single click within the box selects a new alignment. <ESC> aborts the selection.



Color selection

For selecting a color the Windows default color selection dialog occurs. <ESC> aborts the selection.



Font selection

The font selection dialog shows all available fonts of the GUIBuilder. The desired font can be selected by a single click on the desired font. <ESC> aborts the selection.

 © 2020 SEGGER Microcontroller GmbH



21.3.5 Deleting a widget property

This can be done easily by using the context menu of the property window or by pressing the <DEL> key if the desired property in the widget property window has the focus.

21.3.6 Deleting a widget

A widget can be deleted by pressing the <DEL> key if the widget is activated in the editor window. It can also be removed by selecting it in the object tree window and then pressing the <DEL> key. Deleting a widget automatically causes all of its child windows to be deleted as well.

21.3.7 Deleting a widget

A widget can be deleted by pressing the <DEL> key if the widget is activated in the editor window. It can also be removed by selecting it in the object tree window and then pressing the <DEL> key. Deleting a widget automatically causes all of its child windows to be deleted as well.

 © 2020 SEGGER Microcontroller GmbH

21.4 Saving the current dialog(s)

With the menu entry **File ➔ Save...** all currently loaded dialogs will be saved in the project folder. Details on how to set up the project folder can be found in the section *Getting started* on page 2219.
Each dialog will be saved as a single C file. The file names are generated automatically by the name of the dialog root widget (FRAMEWIN or WINDOW widget). The file names are build as follows:
`<Widget name>DLG.c` If for example the name of the widget is *Framewin* the file will be named FramewinDLG.c.

 © 2020 SEGGER Microcontroller GmbH

21.5 Output of the GUIBuilder

As mentioned above the result of the GUIBuilder are C files only. The following shows a small sample which is generated by the tool:

```
/*********************************************************************
*
*           SEGGER Microcontroller GmbH
*     Solutions for real time microcontroller applications
*
**********************************************************************
*
*    C-file generated by:
*
*    GUI_Builder for emWin version 5.09
*    Compiled Mar 23 2011, 09:52:04
*    (c) 2011 Segger Microcontroller GmbH
*
**********************************************************************
*
*    Internet: www.segger.com Support: support@segger.com
*
**********************************************************************
*/
//  USER START (Optionally insert additional includes)
//  USER END
#include "DIALOG.h"
/*********************************************************************
*
*    Defines
*
**********************************************************************
*/
#define ID_FRAMEWIN_0  (GUI_ID_USER + 0x0A)
#define ID_BUTTON_0   (GUI_ID_USER + 0x0B)
//  USER START (Optionally insert additional defines)
//  USER END
/*********************************************************************
*
*    Static data
*
**********************************************************************
*/
// USER START (Optionally insert additional static data)
// USER END
/*********************************************************************
*
*    _aDialogCreate
*/
static const GUI_WIDGET_CREATE_INFO _aDialogCreate[] = {
  { FRAMEWIN_CreateIndirect, "Framewin", ID_FRAMEWIN_0, 0, 0, 320, 240, 0, 0, 0 },
  { BUTTON_CreateIndirect, "Button", ID_BUTTON_0, 5, 5, 80, 20, 0, 0, 0 },
//  USER START (Optionally insert additional widgets)
//  USER END
};
/*********************************************************************
*
*    Static code
*
**********************************************************************
*/
//  USER START (Optionally insert additional static code)
//  USER END
/*********************************************************************
*
*    _cbDialog
*/
```

 © 2020 SEGGER Microcontroller GmbH

```
static void _cbDialog(WM_MESSAGE * pMsg) {
  WM_HWIN hItem;
  int Id, NCode;
  //  USER START (Optionally insert additional variables)
  //  USER END
  switch (pMsg->MsgId) {
  case WM_INIT_DIALOG:
  //
  // Initialization of 'Framewin'
  //
  hItem = pMsg->hWin;
  FRAMEWIN_SetTextAlign(hItem, GUI_TA_HCENTER | GUI_TA_VCENTER);
  FRAMEWIN_SetFont(hItem, GUI_FONT_24_ASCII);
  //
  // Initialization of 'Button'
  //
  hItem = WM_GetDialogItem(pMsg->hWin, ID_BUTTON_0);
  BUTTON_SetText(hItem, "Press me...");
  // USER START (Opt. insert additional code for further widget initialization)
  // USER END
  break;
  case WM_NOTIFY_PARENT:
    Id  = WM_GetId(pMsg->hWinSrc);
    NCode = pMsg->Data.v;
    switch(Id) {
    case ID_BUTTON_0: // Notifications sent by 'Button'
      switch(NCode) {
    case WM_NOTIFICATION_CLICKED:
     // USER START (Optionally insert code for reacting on notification message)
     // USER END
     break;
    case WM_NOTIFICATION_RELEASED:
     // USER START (Optionally insert code for reacting on notification message)
     // USER END
     break;
    // USER START (Opt. insert additional code for further notification handling)
    // USER END
    }
    break;
   // USER START (Optionally insert additional code for further IDs)
   // USER END
  }
  break;
  // USER START (Optionally insert additional message handling)
  // USER END
  default:
  WM_DefaultProc(pMsg);
  break;
 }
}
/*********************************************************************
*
*    Public code
*
**********************************************************************
*/
/*********************************************************************
*
*    CreateFramewin
*/
WM_HWIN CreateFramewin(void) {
  WM_HWIN hWin;
  hWin = GUI_CreateDialogBox(_aDialogCreate,
                 GUI_COUNTOF(_aDialogCreate), _cbDialog, WM_HBKWIN, 0, 0);
  return hWin;
}
// USER START (Optionally insert additional public code)
// USER END
```

 © 2020 SEGGER Microcontroller GmbH

```
/*************************** End of file ****************************/
```

 © 2020 SEGGER Microcontroller GmbH

21.6 Modifying the C files

As the sample code shows, it contains many sections for custom code. These are the following sections:

```
//  USER START (Optionally insert ...)
//  USER END
```

The start and end lines may not be modified. They are required for the GUIBuilder to be able to distinguish between user code and generated code. The following shows how it should work:

```
// USER START (Optionally insert additional includes)
#ifndef WIN32
  #include <ioat91sam9261.h>
#endif
// USER END
```

 © 2020 SEGGER Microcontroller GmbH

21.7 How to use the C files

As the sample output shows, the code does not contain any code which uses the dialogs or with other words makes them visible on the display. Each file contains a creation routine at the end named `Create<Widget name>()`. These routines create the according dialog. Simply call these routines to make them occur on the display.

Example

The following code shows how to draw the dialog of the previous output sample on a display:

```
#include "DIALOG.h"
/*********************************************************************
*
*    Externals
*
**********************************************************************
*/
WM_HWIN CreateFramewin(void);
/*********************************************************************
*
*    Public code
*
**********************************************************************
*/
/*********************************************************************
*
*    MainTask
*/
void MainTask(void) {
  WM_HWIN hDlg;
  GUI_Init();
  //
  // Call creation function for the dialog
  //
  hDlg = CreateFramewin();
  //
  // May do anything with hDlg
  //
  ...
  //
  // Keep program allive...
  //
  while (1) {
   GUI_Delay(10);
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

Chapter 22

Dialogs

Widgets may be created and used on their own, as they are by nature windows themselves. However, it is often desirable to use dialog boxes, which are windows that contain one or more widgets.

A dialog box (or dialog) is normally a window that appears in order to request input from the user. It may contain multiple widgets, requesting information from the user through various selections, or it may take the form of a message box which simply provides information (such as a note or warning) and an "OK" button.

For common tasks like choosing a file, choosing a color or (as mentioned before) for showing simple text messages emWin offers 'common dialogs'. These dialogs can be configured to achieve the look and feel of the application.

 © 2020 SEGGER Microcontroller GmbH

22.1 Dialog basics

Input focus

The Window Manager remembers the window or window object that was last selected by the user with the touch-screen, mouse, keyboard, or other means. This window receives keyboard input messages and is said to have the input focus.

The primary reason for keeping track of input focus is to determine where to send keyboard commands. The window which has input focus will receive events generated by the keyboard.

To move the input focus within a dialog to the next focusable dialog item the key `GUI_KEY_TAB` can be used. To move backwards `GUI_KEY_BACKTAB` can be used.

Blocking vs. non-blocking dialogs

Dialog windows can be blocking or non-blocking.

A blocking dialog blocks the thread of execution. It has input focus by default and must be closed by the user before the thread can continue. A blocking dialog does not disable other dialogs shown at the same time. With other words a blocking dialog is not a modal dialog. Blocking means, the used functions (`GUI_ExecDialogBox()` or `GUI_ExecCreatedDialog()`) does not return until the dialog is closed.

A non-blocking dialog, on the other hand, does not block the calling thread—it allows the task to continue while it is visible. The function returns immediately after creating the dialog.

Blocking functions should never be called from within a callback function. This may cause malfunction of the application.

Dialog procedure

A dialog box is a window, and it receives messages just as every other window in the system does. Most messages are handled automatically by the client callback routine of the dialog box. The others are passed to the client callback routine which is specified as a parameter upon creation. The client callback function is known as the dialog procedure.

Since a dialog itself usually consists of 2 windows (dialog and client window), messages have to be sent using the correct handle. After a dialog was created there is only one handle to the dialog. In order to access the client window, the function `WM_GetClientWindow()` should be used.

Dialog messages

There are two types of additional messages which are sent to the dialog procedure: `WM_INIT_DIALOG` and `WM_NOTIFY_PARENT`. The `WM_INIT_DIALOG` message is sent to the dialog procedure immediately before a dialog box is displayed. Dialog procedures typically use this message to initialize widgets and carry out any other initialization tasks that affect the appearance of the dialog box. The `WM_NOTIFY_PARENT` message is sent to the dialog box by its child windows in order to notify the parent of any events in order to ensure synchronization. The events sent by a child depend on its type and are documented separately for every type of widget.

 © 2020 SEGGER Microcontroller GmbH

22.2 Creating a dialog

Two basic things are required to create a dialog box: a resource table that defines the widgets to be included, and a dialog procedure which defines the initial values for the widgets as well as their behavior. Once both items exist, you need only a single function call (`GUI_CreateDialogBox()` or `GUI_ExecDialogBox()`) to actually create the dialog.

22.2.1 Resource table

Dialog boxes may be created in a blocking manner (using `GUI_ExecDialogBox()`) or as non-blocking (using `GUI_CreateDialogBox()`). A resource table must first be defined which specifies all widgets to be included in the dialog. The example shown below creates a resource table:

```
static const GUI_WIDGET_CREATE_INFO _aDialogCreate[] = {
  { FRAMEWIN_CreateIndirect, "Dialog", 0,               10,  10,  180, 230, 0,              0 },
  { BUTTON_CreateIndirect,   "OK",     GUI_ID_OK,       100,  5,  60,  20,  0,              0 },
  { BUTTON_CreateIndirect,   "Cancel", GUI_ID_CANCEL,   100, 30,  60,  20,  0,              0 },
  { TEXT_CreateIndirect,     "LText",  0,               10,  55,  48,  15,  TEXT_CF_LEFT,   0 },
  { TEXT_CreateIndirect,     "RText",  0,               10,  80,  48,  15,  TEXT_CF_RIGHT,  0 },
  { EDIT_CreateIndirect,     NULL,     GUI_ID_EDIT0,    60,  55,  100, 15,  0,             50 },
  { EDIT_CreateIndirect,     NULL,     GUI_ID_EDIT1,    60,  80,  100, 15,  0,             50 },
  { TEXT_CreateIndirect,     "Hex",    0,               10,  100, 48,  15,  TEXT_CF_RIGHT,  0 },
  { EDIT_CreateIndirect,     NULL,     GUI_ID_EDIT2,    60,  100, 100, 15,  0,              6 },
  { TEXT_CreateIndirect,     "Bin",    0,               10,  120, 48,  15,  TEXT_CF_RIGHT,  0 },
  { EDIT_CreateIndirect,     NULL,     GUI_ID_EDIT3,    60,  120, 100, 15,  0,              0 },
  { LISTBOX_CreateIndirect,  NULL,     GUI_ID_LISTBOX0, 10,  10,  48,  40,  0,              0 },
  { CHECKBOX_CreateIndirect, NULL,     GUI_ID_CHECK0,   10,  140,  0,  0,   0,              0 },
  { CHECKBOX_CreateIndirect, NULL,     GUI_ID_CHECK1,   30,  140,  0,  0,   0,              0 },
  { SLIDER_CreateIndirect,   NULL,     GUI_ID_SLIDER0,  60,  140, 100, 20,  0,              0 },
  { SLIDER_CreateIndirect,   NULL,     GUI_ID_SLIDER1,  10,  170, 150, 30,  0,              0 }
};
```

Widgets can be included in a dialog by using the <WIDGET>_CreateIndirect() function for indirect creation. Detailed information can be found in the chapter *Widgets (window objects)* on page 963

22.2.2 Dialog procedure

The example above has been created using the blank dialog procedure shown below. This is the basic template which should be used as a starting point when creating any dialog procedure:

```
/*********************************************************************
*
*    Dialog procedure
*/
static void _cbCallback(WM_MESSAGE * pMsg) {
  switch (pMsg->MsgId) {
  default:
  WM_DefaultProc(pMsg);
  }
}
```

For this example, the dialog box is displayed with the following line of code:

```
GUI_ExecDialogBox(_aDialogCreate, GUI_COUNTOF(_aDialogCreate),
                  _cbCallback, 0, 0, 0);
```

The resulting dialog box looks as follows, or similar (the actual appearance will depend on your configuration and default settings):

 © 2020 SEGGER Microcontroller GmbH



After creation of the dialog box, all widgets included in the resource table will be visible, although as can be seen in the previous screenshot, they will appear "empty". This is because the dialog procedure does not yet contain code that initializes the individual elements. The initial values of the widgets, the actions caused by them, and the interactions between them need to be defined in the dialog procedure.

22.2.2.1 Initializing the dialog

The typical next step is to initialize the widgets with their respective initial values. This is normally done in the dialog procedure as a reaction to the `WM_INIT_DIALOG` message. The program excerpt below illustrates things:

```
/*********************************************************************
*
*    Dialog procedure
*/
static void _cbCallback(WM_MESSAGE * pMsg) {
  WM_HWIN hItem;
  WM_HWIN hWin;
  hWin = pMsg->hWin;
  switch (pMsg->MsgId) {
  case WM_INIT_DIALOG:
    hItem = WM_GetDialogItem(hWin, GUI_ID_EDIT0);
    EDIT_SetText(hItem, "EDIT widget 0");
    hItem = WM_GetDialogItem(hWin, GUI_ID_EDIT1);
    EDIT_SetText(hItem, "EDIT widget 1");
    EDIT_SetTextAlign(hItem,       GUI_TA_LEFT);
    hItem = WM_GetDialogItem(hWin, GUI_ID_EDIT2);
    EDIT_SetHexMode(hItem, 0x1234, 0, 0xffff);
    hItem = WM_GetDialogItem(hWin, GUI_ID_EDIT3);
    EDIT_SetBinMode(hItem, 0x1234, 0, 0xffff);
    hItem = WM_GetDialogItem(hWin, GUI_ID_CHECK0);
    CHECKBOX_Check(WM_GetDialogItem(hWin, GUI_ID_CHECK0));
    hItem = WM_GetDialogItem(hWin, GUI_ID_CHECK1);
    WM_DisableWindow(WM_GetDialogItem(hWin, GUI_ID_CHECK1));
    CHECKBOX_Check(WM_GetDialogItem(hWin, GUI_ID_CHECK1));
    hItem = WM_GetDialogItem(hWin, GUI_ID_SLIDER0);
    SLIDER_SetWidth(WM_GetDialogItem(hWin, GUI_ID_SLIDER0), 5);
    hItem = WM_GetDialogItem(hWin, GUI_ID_SLIDER1);
    SLIDER_SetValue(WM_GetDialogItem(hWin, GUI_ID_SLIDER1), 50);
    hItem = WM_GetDialogItem(hWin, GUI_ID_LISTBOX0);
    LISTBOX_SetText(hItem, _apListBox);
    break;
  default:
```

 © 2020 SEGGER Microcontroller GmbH

```
    WM_DefaultProc(pMsg);
  }
}
```

The initialized dialog box now appears as follows, with all widgets containing their initial values:



22.2.3 Defining dialog behavior

Once the dialog has been initialized, all that remains is to add code to the dialog procedure which will define the behavior of the widgets, making them fully operable. Continuing with the same example, the final dialog procedure is shown below:

```
/*********************************************************************
*
*    Dialog procedure
*/
static void _cbCallback(WM_MESSAGE * pMsg) {
  WM_HWIN hEdit0, hEdit1, hEdit2, hEdit3;
  WM_HWIN hListBox;
  WM_HWIN hWin
  int   NCode
  int   Id;
  hWin = pMsg->hWin;
  switch (pMsg->MsgId) {
  case WM_INIT_DIALOG:
    /* Get window handles for all widgets */
    hEdit0  = WM_GetDialogItem(hWin, GUI_ID_EDIT0);
    hEdit1  = WM_GetDialogItem(hWin, GUI_ID_EDIT1);
    hEdit2  = WM_GetDialogItem(hWin, GUI_ID_EDIT2);
    hEdit3  = WM_GetDialogItem(hWin, GUI_ID_EDIT3);
    hListBox = WM_GetDialogItem(hWin, GUI_ID_LISTBOX0);
    /* Initialize all widgets */
    EDIT_SetText(hEdit0, "EDIT widget 0");
    EDIT_SetText(hEdit1, "EDIT widget 1");
    EDIT_SetTextAlign(hEdit1, GUI_TA_LEFT);
    EDIT_SetHexMode(hEdit2, 0x1234, 0, 0xffff);
    EDIT_SetBinMode(hEdit3, 0x1234, 0, 0xffff);
    LISTBOX_SetText(hListBox, _apListBox);
    WM_DisableWindow(WM_GetDialogItem(hWin, GUI_ID_CHECK1));
    CHECKBOX_Check( WM_GetDialogItem(hWin, GUI_ID_CHECK0));
    CHECKBOX_Check( WM_GetDialogItem(hWin, GUI_ID_CHECK1));
    SLIDER_SetWidth( WM_GetDialogItem(hWin, GUI_ID_SLIDER0), 5);
    SLIDER_SetValue( WM_GetDialogItem(hWin, GUI_ID_SLIDER1), 50);
```

 © 2020 SEGGER Microcontroller GmbH

```
    break;
  case WM_KEY:
    switch (((WM_KEY_INFO*)(pMsg->Data.p))->Key) {
    case GUI_ID_ESCAPE:
      GUI_EndDialog(hWin, 1);
      break;
    case GUI_ID_ENTER:
      GUI_EndDialog(hWin, 0);
      break;
    }
    break;
  case WM_NOTIFY_PARENT:
    Id  = WM_GetId(pMsg->hWinSrc);     /* Id of widget           */
    NCode = pMsg->Data.v;              /* Notification code      */
    switch (NCode) {
    case WM_NOTIFICATION_RELEASED:     /* React only if released */
      if (Id == GUI_ID_OK) {           /* OK Button              */
        GUI_EndDialog(hWin, 0);
      }
      if (Id == GUI_ID_CANCEL) {       /* Cancel Button          */
        GUI_EndDialog(hWin, 1);
      }
      break;
    case WM_NOTIFICATION_SEL_CHANGED:  /* Selection changed      */
      FRAMEWIN_SetText(hWin, "Dialog - sel changed");
      break;
    default:
      FRAMEWIN_SetText(hWin, "Dialog - notification received");
   }
   break;
  default:
   WM_DefaultProc(pMsg);
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

22.3 Dialog API

The table below lists the available dialog-related routines in alphabetical. Detailed descriptions follow:

Routine	Description
GUI_CreateDialogBox()	Creates a dialog box.
GUI_ExecCreatedDialog()	Executes an already created dialog box.
GUI_ExecDialogBox()	Creates and executes a dialog box.
GUI_EndDialog()	Ends (closes) a dialog box.

 © 2020 SEGGER Microcontroller GmbH

22.3.1 GUI_CreateDialogBox()

Description

Creates a dialog box.

Prototype

```
WM_HWIN GUI_CreateDialogBox(const GUI_WIDGET_CREATE_INFO * paWidget,
                            int                          NumWidgets,
                            WM_CALLBACK                * cb,
                            WM_HWIN                      hParent,
                            int                          x0,
                            int                          y0);
```

Parameters

Parameter	Description
paWidget	Pointer to resource table defining the widgets to be included in the dialog.
NumWidgets	Total number of widgets included in the dialog.
cb	Pointer to an application-specific callback function (dialog procedure).
hParent	Handle of parent window (0 = no parent window).
x0	X-position of the dialog relative to parent window.
y0	Y-position of the dialog relative to parent window.

Return value

Handle of the created dialog. This handle can be used to access the first widget from the resource table. This should be a FRAMEWIN or WINDOW widget.

Additional information

The parameter cb is used as callback function for the client window. If a callback function should be set for the dialog window, the function WM_SetCallback() should be used with the handle returned by GUI_CreateDialogBox(). The handle of the client window can be determined using the function WM_GetClientWindow() passing the handle of the dialog which was returned by GUI_CreateDialogBox().

 © 2020 SEGGER Microcontroller GmbH

22.3.2 GUI_ExecCreatedDialog()

Description

Executes an already created dialog box.

Prototype

```
int GUI_ExecCreatedDialog(WM_HWIN hDialog);
```

Parameters

Parameter	Description
hDialog	Handle to dialog box.

Return value

Return value which was passed to GUI_EndDialog().

Additional information

This is a blocking function. It does not return until the dialog is closed using the function GUI_EndDialog(). The WM_CF_SHOW flag is set, so the dialog is drawn the next time the Window Manager is executed.

 © 2020 SEGGER Microcontroller GmbH

22.3.3 GUI_ExecDialogBox()

Description

Creates and executes a dialog box.

Prototype

```
int GUI_ExecDialogBox(const GUI_WIDGET_CREATE_INFO * paWidget,
                      int                            NumWidgets,
                      WM_CALLBACK                  * cb,
                      WM_HWIN                        hParent,
                      int                            x0,
                      int                            y0);
```

Parameters

Parameter	Description
paWidget	Pointer to a resource table defining the widgets to be included in the dialog.
NumWidgets	Total number of widgets included in the dialog.
cb	Pointer to an application-specific callback function (dialog procedure).
hParent	Handle of parent window (0 = no parent window).
x0	X-position of the dialog relative to parent window.
y0	Y-position of the dialog relative to parent window.

Return value

Return value which was passed to `GUI_EndDialog()`.

Additional information

This function actually calls `GUI_CreateDialogBox()` and `GUI_ExecCreatedDialog()`. It is blocking and therefore does not return until the dialog is closed using the function `GUI_EndDialog()`. The `WM_CF_SHOW` flag is set, so the dialog is drawn the next time the Window Manager is executed.

 © 2020 SEGGER Microcontroller GmbH

22.3.4 GUI_EndDialog()

Description

Ends (closes) a dialog box. The dialog and its child windows will be removed from memory.

Prototype

```
void GUI_EndDialog(WM_HWIN hDialog,
                   int     r);
```

Parameters

Parameter	Description
hDialog	Handle to dialog box.
r	Value which is returned by the function GUI_ExecDialog-Box(). This value is ignored in case a non-blocking dialog is closed.

Additional information

After the next call of WM_Exec() (gets also called in GUI_Delay()) the handle hDialog is no longer valid. In case a non-blocking dialog is closed, this function works the same way the function WM_DeleteWindow() works.

 © 2020 SEGGER Microcontroller GmbH

22.4 Common dialogs

Common dialogs can be used by an application for several tasks. They can be opened by calling a simple function instead of creating a new and complex dialog by the application. The following shows the available common dialogs.

22.4.1 CALENDAR



The CALENDAR dialog can be used for selecting or setting a date. The dialog consists of 2 buttons for month wise scrolling, a text which shows the current year and month and a pad of days. A small surrounding frame is shown surrounding the current date and the current selection is highlighted. The keyboard and/or the pointer input device (PID) can be used for selecting a date. The dialog supports the Gregorian calendar which is used since 1582.

The buttons to the left and right of month and year can be modified by using the IDs of the BUTTON widgets.

The left button uses the ID `GUI_ID_BUTTON0` and right one `GUI_ID_BUTTON1`. By calling the function `WM_GetDialogItem()` with the proper ID it is possible to receive the BUTTON handle and manage the buttons as any other BUTTON widget.

22.4.1.1 Notification codes

The following events are sent from the dialog to its parent window as part of a `WM_NOTIFY_PARENT` message:

Message	Description
`CALENDAR_NOTIFICATION_MONTH_CLICKED`	Month/year-text has been clicked.
`CALENDAR_NOTIFICATION_MONTH_RELEASED`	Month/year-text has been released.
`WM_NOTIFICATION_CLICKED`	Widget has been clicked.
`WM_NOTIFICATION_RELEASED`	Widget has been released.
`WM_NOTIFICATION_SCROLL_CHANGED`	One of the scroll buttons has been pressed.
`WM_NOTIFICATION_SEL_CHANGED`	The selection has been changed.

22.4.1.2 Keyboard reaction

Key	Reaction
`GUI_KEY_PGUP`	Selection moves one month back.
`GUI_KEY_PGDOWN`	Selection moves one month forward.
`GUI_KEY_LEFT`	Selection moves to the left.
`GUI_KEY_RIGHT`	Selection moves to the right.
`GUI_KEY_UP`	Selection moves one line up.
`GUI_KEY_DOWN`	Selection moves one line down.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3 CALENDAR_API

The table below lists the available CALENDAR-related routines in alphabetical order. Detailed descriptions follow.

Functions

Routine	Description
CALENDAR_AddKey()	Adds user input to a specified CALENDAR dialog.
CALENDAR_Create()	Creates a CALENDAR dialog.
CALENDAR_GetDate()	Returns the current date.
CALENDAR_GetDaysOfMonth()	Returns the number of days in a specific month.
CALENDAR_GetSel()	Returns the currently selected date.
CALENDAR_GetWeekday()	Returns the number of the weekday of a given date.
CALENDAR_SetDate()	Sets the current date.
CALENDAR_SetSel()	Sets the currently selected date.
CALENDAR_SetDefaultBkColor()	Sets the default background color to be used for new CALENDAR dialogs.
CALENDAR_SetDefaultColor()	Sets the default color to be used for new CALENDAR dialogs.
CALENDAR_SetDefaultDays()	Sets the text to be used to label the days.
CALENDAR_SetDefaultFont()	Sets the font(s) to be used for drawing the CALENDAR items.
CALENDAR_SetDefaultMonths()	Sets the text to be used for the current month / year.
CALENDAR_SetDefaultSize()	Sets the sizes to be used by the dialog.
CALENDAR_ShowDate()	Shows a given date on the calendar.

Data structures

Structure	Description
CALENDAR_DATE	Structure used by the routine CALENDAR_GetDate() to retrieve a date.

Defines

Group of defines	Description
CALENDAR color indexes	Color indexes used by the CALENDAR dialog.
CALENDAR font indexes	Font indexes used by the CALENDAR dialog.
CALENDAR size indexes	Size indexes used by the routine CALENDAR_SetDefaultSize().

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1 Functions

22.4.1.3.1.1 CALENDAR_AddKey()

Description

Adds user input to a specified CALENDAR dialog.

Prototype

```
int CALENDAR_AddKey(WM_HWIN hWin,
                    int     Key);
```

Parameters

Parameter	Description
hWin	Handle of CALENDAR handle.
Key	Character to be added.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.2 CALENDAR_Create()

Description

Creates a CALENDAR dialog.

Prototype

```
WM_HWIN CALENDAR_Create(WM_HWIN  hParent,
                        int      xPos,
                        int      yPos,
                        unsigned Year,
                        unsigned Month,
                        unsigned Day,
                        unsigned FirstDayOfWeek,
                        int      Id,
                        int      Flags);
```

Parameters

Parameter	Description
hParent	Handle of the parent window which should receive the notification messages.
xPos	X position in pixels of the dialog in client coordinates.
yPos	Y position in pixels of the dialog in client coordinates.
Year	Current year (1582-9999).
Month	Current month (1-12).
Day	Current day (1-31).
FirstDayOfWeek	First weekday to be used (0=SA, 1=SO, … , 6=FR).
Id	Id to be used for the CALENDAR dialog.
Flags	Additional flags for the WINDOW widget.

Return value

Handle of the dialog on success, otherwise 0.

Additional information

Year, Month and Day specify the current date. Per default this is also the initial selection. FirstDayOfWeek determines an offset for the first day to be shown. Default is showing Saturday at first.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.3 CALENDAR_GetDate()

Description

Returns the current date.

Prototype

```
void CALENDAR_GetDate(WM_HWIN         hWin,
                      CALENDAR_DATE * pDate);
```

Parameters

Parameter	Description
hWin	Handle of CALENDAR dialog.
pDate	Pointer to a CALENDAR_DATE structure.

Additional information

Current date and selected date are different items. The selection can be moved by the keyboard interface and/or the PID whereas the current date can be specified when creating the dialog or by using the function CALENDAR_SetDate().

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.4 CALENDAR_GetDaysOfMonth()

Description

Returns the number of days in a specific month.

Prototype

```
int CALENDAR_GetDaysOfMonth(CALENDAR_DATE * pDate);
```

Parameters

Parameter	Description
pDate	Pointer to a CALENDAR_DATE structure.

Additional information

The members Year and Month of the parameter have to be set to get the number of days of the specified month in the specified year.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.5 CALENDAR_GetSel()

Description

Returns the currently selected date.

Prototype

```
void CALENDAR_GetSel(WM_HWIN         hWin,
                     CALENDAR_DATE * pDate);
```

Parameters

Parameter	Description
hWin	Handle of CALENDAR dialog.
pDate	Pointer to a CALENDAR_DATE structure.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.6 CALENDAR_GetWeekday()

Description

Returns the number of the weekday of a given date.

Prototype

```
int CALENDAR_GetWeekday(CALENDAR_DATE * pDate);
```

Parameters

Parameter	Description
pDate	Pointer to CALENDAR_DATE structure.

Return value

0 Saturday
1 Sunday
2 Monday
3 Tuesday
4 Wednesday
5 Thursday
6 Friday

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.7 CALENDAR_SetDate()

Before	After
	

Description

Sets the current date.

Prototype

```
void CALENDAR_SetDate(WM_HWIN         hWin,
                      CALENDAR_DATE * pDate);
```

Parameters

Parameter	Description
hWin	Handle of CALENDAR dialog.
pDate	Pointer to a CALENDAR_DATE structure.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.8 CALENDAR_SetSel()

Before	After
	

Description

Sets the currently selected date.

Prototype

```
void CALENDAR_SetSel(WM_HWIN         hWin,
                     CALENDAR_DATE * pDate);
```

Parameters

Parameter	Description
hWin	Handle of CALENDAR dialog.
pDate	Pointer to a CALENDAR_DATE structure.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.9 CALENDAR_SetDefaultBkColor()

Description

Sets the default background color to be used for new CALENDAR dialogs.

Prototype

```
void CALENDAR_SetDefaultBkColor(unsigned  Index,
                                GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *CALENDAR color indexes* on page 2258. Only **...WEEKEND**, **...WEEKDAY**, **...SEL** and **...HEADER** are applicable for a background color.
Color	Color to be used

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.10 CALENDAR_SetDefaultColor()

Description

Sets the default color to be used for new CALENDAR dialogs.

Prototype

```
void CALENDAR_SetDefaultColor(unsigned  Index,
                              GUI_COLOR Color);
```

Parameters

Parameter	Description
Index	See *CALENDAR color indexes* on page 2258. **CALENDAR_CI_HEADER** is not applicable for this routine.
Color	Color to be used

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.11 CALENDAR_SetDefaultDays()

Description

Sets the text to be used to label the days.

Prototype

```
void CALENDAR_SetDefaultDays(const char ** apDays);
```

Parameters

Parameter	Description
apDays	Pointer to an array of 7 string pointers containing the strings to be used.

Additional information

The first string of the array should point to the abbreviation of Saturday, the second to Sunday and so on. The array needs to have at least 7 strings. If there are too few strings passed to the function the behavior of emWin becomes undefined.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.12 CALENDAR_SetDefaultFont()

Description

Sets the font(s) to be used for drawing the CALENDAR items.

Prototype

```
void CALENDAR_SetDefaultFont(      unsigned   Index,
                             const GUI_FONT * pFont);
```

Parameters

Parameter	Description
Index	See *CALENDAR font indexes* on page 2259 for a full list of permitted values.
pFont	Font to be used.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.13 CALENDAR_SetDefaultMonths()

Description

Sets the text to be used for the current month / year.

Prototype

```
void CALENDAR_SetDefaultMonths(const char ** apMonths);
```

Parameters

Parameter	Description
apMonth	Pointer to an array of 12 string pointers containing the strings to be used.

Additional information

The first string of the array should point to the text for ’January’, the second to the text for ’February’ and so on. The array needs to have at least 12 strings. If there are too few strings passed to the function the behavior of emWin becomes undefined.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.14 CALENDAR_SetDefaultSize()

Description

Sets the sizes to be used by the dialog.

Prototype

```
void CALENDAR_SetDefaultSize(unsigned Index,
                             unsigned Size);
```

Parameters

Parameter	Description
Index	See *CALENDAR size indexes* on page 2260 for a full list of permitted values.
Size	Size to be used.

Additional information

The size in x of the complete dialog can be calculated as follows: xSizeDialog = 7 × CellSizeX
The size in y of the complete dialog can be calculated as follows: ySizeDialog = 7 × CellSizeY + HeaderSizeY

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.1.15 CALENDAR_ShowDate()

Description

Shows a given date on the calendar.

Prototype

```
void CALENDAR_ShowDate(WM_HWIN         hWin,
                       CALENDAR_DATE * pDate);
```

Parameters

Parameter	Description
hWin	Handle of CALENDAR dialog.
pDate	Pointer to a CALENDAR_DATE structure.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.2 Data structures

22.4.1.3.2.1 CALENDAR_DATE

Description

Structure used by the routine `CALENDAR_GetDate()` to retrieve a date.

Type definition

```
typedef struct {
  int  Year;
  int  Month;
  int  Day;
} CALENDAR_DATE;
```

Structure members

Member	Description
`Year`	`Year` of requested date.
`Month`	`Month` of requested date.
`Day`	`Day` of requested date.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.3 Defines

22.4.1.3.3.1 CALENDAR color indexes

Description

Color indexes used by the CALENDAR dialog.

Definition

```
#define CALENDAR_CI_WEEKEND    0
#define CALENDAR_CI_WEEKDAY    1
#define CALENDAR_CI_SEL        2
#define CALENDAR_CI_HEADER     3
#define CALENDAR_CI_MONTH      4
#define CALENDAR_CI_LABEL      5
#define CALENDAR_CI_FRAME      6
```

Symbols

Definition	Description
CALENDAR_CI_WEEKEND	Color to be used for weekend days.
CALENDAR_CI_WEEKDAY	Color to be used for weekdays.
CALENDAR_CI_SEL	Color to be used for the selection.
CALENDAR_CI_HEADER	Background color to be used for the header area.
CALENDAR_CI_MONTH	Color to be used for the month (and year) text.
CALENDAR_CI_LABEL	Color to be used for labeling the days.
CALENDAR_CI_FRAME	Color to be used for the frame of the current date.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.3.2 CALENDAR font indexes

Description

Font indexes used by the CALENDAR dialog.

Definition

```
#define CALENDAR_FI_CONTENT    0
#define CALENDAR_FI_HEADER     1
```

Symbols

Definition	Description
CALENDAR_FI_CONTENT	Font to be used for labeling and the numbers.
CALENDAR_FI_HEADER	Font to be used for month / year.

 © 2020 SEGGER Microcontroller GmbH

22.4.1.3.3.3 CALENDAR size indexes

Description

Size indexes used by the routine `CALENDAR_SetDefaultSize()`.

Definition

```
#define CALENDAR_SI_HEADER    0
#define CALENDAR_SI_CELL_X    1
#define CALENDAR_SI_CELL_Y    2
```

Symbols

Definition	Description
CALENDAR_SI_HEADER	Y-size in pixels used for the header area. (default is 25)
CALENDAR_SI_CELL_X	Cell size in X to be used for one item in the day pad. (default is 18)
CALENDAR_SI_CELL_Y	Cell size in Y to be used for one item in the day pad. (default is 13)

 © 2020 SEGGER Microcontroller GmbH

22.4.2 CHOOSECOLOR



The CHOOSECOLOR dialog can be used to select a color from a given color array.

22.4.2.1 Notification codes

The following events are sent from the dialog to its parent window as part of a WM_NOTIFY_PARENT message:

Message	Description
WM_NOTIFICATION_SEL_CHANGED	Sent immediately after a new color has been selected by the PID or the keyboard.
WM_NOTIFICATION_CHILD_DELETED	Sent when the dialog has been closed.
WM_NOTIFICATION_VALUE_CHANGED	Sent if the dialog was closed using the 'Ok' button with a different than the initial selection.

22.4.2.2 Keyboard reaction

The dialog reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_ESCAPE	Dialog execution will be canceled.
GUI_KEY_ENTER	Reaction depends on the focused button.
GUI_KEY_LEFT	Cursor moves to the left.
GUI_KEY_RIGHT	Cursor moves to the right.
GUI_KEY_UP	Cursor moves one line up.
GUI_KEY_DOWN	Cursor moves one line down.

22.4.2.3 CHOOSECOLOR API

The table below lists the available CHOOSECOLOR-related routines in alphabetical order. Detailed descriptions follow.

Functions

Routine	Description
CHOOSECOLOR_Create()	Creates a dialog for choosing a color and returns immediately.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
CHOOSECOLOR_GetSel()	Returns the index of the currently selected color.
CHOOSECOLOR_SetSel()	Sets the current selection.
CHOOSECOLOR_SetDefaultColor()	Sets the colors to be used to draw the surrounding frame of the colors.
CHOOSECOLOR_SetDefaultSpace()	Determines the space between the color rectangles.
CHOOSECOLOR_SetDefaultBorder()	Sets the size of the border between the colors and the dialog frame to be used.
CHOOSECOLOR_SetDefaultButtonSize()	Sets the button size to be used.

Defines

Group of defines	Description
CHOOSECOLOR color indexes	Color indexes used by the CHOOSECOLOR dialog.

 © 2020 SEGGER Microcontroller GmbH

22.4.2.3.1 Functions

22.4.2.3.1.1 CHOOSECOLOR_Create()

Description

Creates a dialog for choosing a color and returns immediately.

Prototype

```
WM_HWIN CHOOSECOLOR_Create(      WM_HWIN     hParent,
                                 int         xPos,
                                 int         yPos,
                                 int         xSize,
                                 int         ySize,
                           const GUI_COLOR * pColor,
                                 unsigned    NumColors,
                                 unsigned    NumColorsPerLine,
                                 int         Sel,
                           const char      * sCaption,
                                 int         Flags);
```

Parameters

Parameter	Description
hParent	Handle of the parent window which should receive the notification messages.
xPos	X position in pixels of the dialog in client coordinates.
yPos	Y position in pixels of the dialog in client coordinates.
xSize	X-size of the dialog in pixels.
ySize	Y-size of the dialog in pixels.
pColor	Pointer to an array of 32 bit color values containing the colors to be used.
NumColors	Number of colors to be shown.
NumColorsPerLine	Number of colors to be shown per line.
Sel	Initial index value to be used for the selection / focus.
sCaption	Title to be shown in the title bar.
Flags	Additional flags for the FRAMEWIN widget.

Return value

Handle of the dialog on success, otherwise 0.

Additional information

The following default values are used:

- If (xPos < 0) the dialog will be centered horizontally.
- If (yPos < 0) the dialog will be centered vertically.
- If (xSize = 0) the half of the display size in x will be used.
- If (ySize = 0) the half of the display size in y will be used.
- if (sCaption = NULL) 'Choose Color' will be shown in the title bar. As mentioned above the creation routine returns immediately. It becomes visible with the next call of WM_Exec() or it can be executed with GUI_ExecCreatedDialog().

 © 2020 SEGGER Microcontroller GmbH

22.4.2.3.1.2 CHOOSECOLOR_GetSel()

Description

Returns the index of the currently selected color.

Prototype

```
int CHOOSECOLOR_GetSel(WM_HWIN hObj);
```

Parameters

Parameter	Description
hObj	Handle of the CHOOSECOLOR dialog.

Return value

Index of the currently selected color.

 © 2020 SEGGER Microcontroller GmbH

22.4.2.3.1.3 CHOOSECOLOR_SetSel()

Description

Sets the current selection.

Prototype

```
void CHOOSECOLOR_SetSel(WM_HWIN hObj,
                        int     Sel);
```

Parameters

Parameter	Description
hObj	Handle of the CHOOSECOLOR dialog.
Sel	New selection to be used.

Additional information

The given selection should be smaller than the number of colors. In case of a negative value no initial selection will be shown.

 © 2020 SEGGER Microcontroller GmbH

22.4.2.3.1.4 CHOOSECOLOR_SetDefaultColor()

Before	After
	

Description

Sets the colors to be used to draw the surrounding frame of the colors.

Prototype

```
void CHOOSECOLOR_SetDefaultColor(unsigned  Index,
                                 GUI_COLOR Color);
```

Parameters

Parameter	Description
`Index`	See *CHOOSECOLOR color indexes* on page 2270 for a full list of permitted values.
`Color`	`Color` to be used.

 © 2020 SEGGER Microcontroller GmbH

22.4.2.3.1.5 CHOOSECOLOR_SetDefaultSpace()

Before	After
	

Description

Determines the space between the color rectangles.

Prototype

```
void CHOOSECOLOR_SetDefaultSpace(unsigned Index,
                                 unsigned Space);
```

Parameters

Parameter	Description
Index	See table below.
Space	Space in pixels to be used.

Permitted values for parameter Index	
GUI_COORD_X	Space in X to be used between the colors. Default value is 5.
GUI_COORD_Y	Space in Y to be used between the colors. Default value is 5.

 © 2020 SEGGER Microcontroller GmbH

22.4.2.3.1.6 CHOOSECOLOR_SetDefaultBorder()

Before	After
	

Description

Sets the size of the border between the colors and the dialog frame to be used.

Prototype

```
void CHOOSECOLOR_SetDefaultBorder(unsigned Index,
                                  unsigned Border);
```

Parameters

Parameter	Description
Index	See table below.
Border	Border to be used.

Permitted values for parameter Index	
GUI_COORD_X	Space in X to be used between border and colors. Default value is 4.
GUI_COORD_Y	Space in Y to be used between border and colors. Default value is 4.

Additional information

The horizontal value is also used to determine the space between the buttons.

 © 2020 SEGGER Microcontroller GmbH

22.4.2.3.1.7 CHOOSECOLOR_SetDefaultButtonSize()

Before	After
	

Description

Sets the button size to be used.

Prototype

```
void CHOOSECOLOR_SetDefaultButtonSize(unsigned Index,
                                      unsigned ButtonSize);
```

Parameters

Parameter	Description
Index	See table below.
ButtonSize	Size in pixels to be used.

Permitted values for parameter Index	
GUI_COORD_X	Button size in X.
GUI_COORD_Y	Button size in Y.

 © 2020 SEGGER Microcontroller GmbH

22.4.2.3.2 Defines

22.4.2.3.2.1 CHOOSECOLOR color indexes

Description

Color indexes used by the CHOOSECOLOR dialog.

Definition

```
#define CHOOSECOLOR_CI_FRAME    0
#define CHOOSECOLOR_CI_FOCUS    1
```

Symbols

Definition	Description
CHOOSECOLOR_CI_FRAME	Color to be used to draw the frame surrounding each color. Default is GUI_GRAY.
CHOOSECOLOR_CI_FOCUS	Color to be used to draw the focus rectangle. Default is GUI_BLACK.

 © 2020 SEGGER Microcontroller GmbH

22.4.3 CHOOSEFILE



The CHOOSEFILE dialog can be used for browsing through a directory and for selecting a file. It uses a user defined callback routine for retrieving data. So it can be used with any file system.

22.4.3.1 Configurating options

Type	Macro	Default	Description
N	CHOOSEFILE_DELIM	\	Default delimiter to be used.

22.4.3.2 Keyboard reaction

The dialog reacts to the following keys if it has the input focus:

Key	Reaction
GUI_KEY_TAB	The next widget of the dialog gains the input focus.
GUI_KEY_BACKTAB	The previous widget of the dialog gains the input focus.
GUI_KEY_ENTER	The behavior depends on the currently focused widget.
GUI_KEY_ESCAPE	Dialog will be canceled.

22.4.3.3 Path- and file names

The maximum length of path- and file names is limited to 256 bytes.

22.4.3.4 CHOOSEFILE API

The table below lists the available CHOOSEFILE-related routines in alphabetical order. Detailed descriptions of the routines follow.

Functions

Routine	Description
CHOOSEFILE_Create()	Creates a CHOOSEFILE dialog using the given parameters.
CHOOSEFILE_EnableToolTips()	Enables ToolTips for CHOOSEFILE dialogs.
CHOOSEFILE_SetButtonText()	Uses text instead of the default image.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
CHOOSEFILE_SetDefaultButtonText()	Sets the default text to be used for new dialogs.
CHOOSEFILE_SetDelim()	Sets the delimiter used within a path.
CHOOSEFILE_SetToolTips()	Sets the text to be shown by the ToolTips.
CHOOSEFILE_SetTopMode()	Makes the button bar visible at the top of the dialog.

Data structures

Structure	Description
CHOOSEFILE_INFO	

Defines

Group of defines	Description
CHOOSEFILE button indexes	Bitmap indexes used by the CHOOSEFILE dialog.

 © 2020 SEGGER Microcontroller GmbH

22.4.3.4.1 Functions

22.4.3.4.1.1 CHOOSEFILE_Create()

Description

Creates a CHOOSEFILE dialog using the given parameters.

Prototype

```
WM_HWIN CHOOSEFILE_Create(      WM_HWIN           hParent,
                                int               xPos,
                                int               yPos,
                                int               xSize,
                                int               ySize,
                          const char            * apRoot[],
                                int               NumRoot,
                                int               SelRoot,
                          const char            * sCaption,
                                int               Flags,
                                CHOOSEFILE_INFO * pInfo);
```

Parameters

Parameter	Description
hParent	Handle of parent window.
xPos	X position in pixels of the dialog in client coordinates.
yPos	Y position in pixels of the dialog in client coordinates.
xSize	X-size of the dialog in pixels.
ySize	Y-size of the dialog in pixels.
apRoot	Pointer to an array of strings containing the root directories to be used.
NumRoot	Number of root directories.
SelRoot	Initial index of the root directory to be used.
sCaption	Title to be shown in the title bar.
Flags	Additional flags for the FRAMEWIN widget.
pInfo	Pointer to a CHOOSEFILE_INFO structure.

Parameter apRoot

This parameter should point to an array of string pointers containing the root directories shown in the DROPDOWN widget of the dialog. The directory names do not need to have a delimiter (slash or backslash) at the end. They are copied by the function to their own locations and do not need to remain valid after creating the dialog. Empty strings are not supported and could lead to an undefined behavior of the dialog.

Prototype of GetData() function

```
int ( * ((CHOOSEFILE_INFO * pInfo);
```

Parameter	Description
pInfo	Pointer to a CHOOSEFILE_INFO structure.

Details about GetData() function

The GetData() function pointed by the element pfGetData has to be provided by the application. This function is responsible to pass information about the requested file to the dialog. It gets a pointer to a CHOOSEFILE_INFO structure which contains all details of the requested file.

 © 2020 SEGGER Microcontroller GmbH

The following elements are passed by the dialog to the application:

- **Cmd** Determines if information about the first or the next file should be returned.
- **pRoot** Pointer to a string containing the path of the directory to be used. The `GetData()` function then has to use the following elements for providing information about the requested file to the dialog:
- **pAttrib** Should point to a string which is shown in the 'Type' column. Because the CHOOSEFILE dialog can be used with any file system there are no special flags but a string which should be passed by the application to the dialog.
- **pName** Should point to a string which contains the file name without path and extension. Shown in the 'Name' column of the dialog.
- **pExt** Should point to a string which contains the extension of the file shown in the 'Type' column of the dialog.
- **SizeL** Should be set to the lower 32 bit of the file length.
- **SizeH** Should be set to the upper 32 bit of the file length in case of file larger than 4.294.967.295 bytes.
- **`Flags`** If the requested file is a directory this element has to be set to `CHOOSEFILE_FLAG_DIRECTORY`. Otherwise it has to be 0.

Return value

Handle of the dialog on success, otherwise 0.

Additional information

The following default values are used:

- If (`xPos` < 0) the dialog will be centered horizontally.
- If (`yPos` < 0) the dialog will be centered vertically.
- If (`xSize` = 0) the half of the display size in x will be used.
- If (`ySize` = 0) the half of the display size in y will be used.
- if (`sCaption` = `NULL`) 'Choose File' will be shown in the title bar.

Example of GetData() function

The following shows an example of the GetData() function which can be used with WIN32. The sample folder also contains a sample which can be used with emFile. Here the WIN32 example:

```
static const struct {
  U32 Mask;
  char c;
} _aAttrib[] = {
  { FILE_ATTRIBUTE_READONLY , 'R' },
  { FILE_ATTRIBUTE_HIDDEN   , 'H' },
  { FILE_ATTRIBUTE_SYSTEM   , 'S' },
  { FILE_ATTRIBUTE_DIRECTORY, 'D' },
  { FILE_ATTRIBUTE_ARCHIVE  , 'A' },
  { FILE_ATTRIBUTE_NORMAL   , 'N' },
};
static int _GetData(CHOOSEFILE_INFO * pInfo) {
  static HANDLE hFind;
  static int NewDir;
  static char acDrive [_MAX_DRIVE];
  static char acDir   [_MAX_DIR];
  static char acName  [_MAX_FNAME];
  static char acExt   [_MAX_EXT];
  static char acMask  [_MAX_PATH];
  static char acPath  [_MAX_PATH];
  static char acAttrib[10] = {0};
  WIN32_FIND_DATA Context;
  int i, r;
  char c;
  switch (pInfo->Cmd) {
  case CHOOSEFILE_FINDFIRST:
    if (hFind != 0) {
```

 © 2020 SEGGER Microcontroller GmbH

```
      FindClose(hFind);
    }
    //
    // Split path into drive and directory
    //
    _splitpath(pInfo->pRoot, acDrive, acDir, NULL, NULL);
    NewDir = 1;
    //
    // Do not 'break' here...
    //
  case CHOOSEFILE_FINDNEXT:
    if (NewDir) {
      _makepath(acMask, acDrive, acDir, NULL, NULL);
      strcat(acMask, pInfo->pMask);
      hFind = FindFirstFile(acMask, &Context);
      if (hFind == INVALID_HANDLE_VALUE) {
        FindClose(hFind);
        hFind = 0;
        return 1;
      }
    } else {
      r = FindNextFile(hFind, &Context);
      if (r == 0) {
        FindClose(hFind);
        hFind = 0;
        return 1;
      }
    }
    NewDir = 0;
    //
    // Generate attribute string (pInfo->pAttrib)
    //
    for (i = 0; i < GUI_COUNTOF(_aAttrib); i++) {
      c = (Context.dwFileAttributes & _aAttrib[i].Mask) ? _aAttrib[i].c : '-';
      acAttrib[i] = c;
    }
    //
    // Make name and extension (pInfo->pName, pInfo->pExt)
    //
    if ((Context.dwFileAttributes & FILE_ATTRIBUTE_DIRECTORY) == 0) {
      _splitpath(Context.cFileName, NULL, NULL, acName, acExt);
    } else {
      strcpy(acName, Context.cFileName);
      acExt[0] = 0;
    }
    //
    // Pass data to dialog
    //
    pInfo->pAttrib = acAttrib;
    pInfo->pName   = acName;
    pInfo->pExt    = acExt;
    pInfo->SizeL   = Context.nFileSizeLow;
    pInfo->SizeH   = Context.nFileSizeHigh;
    pInfo->Flags   = (Context.dwFileAttributes & FILE_ATTRIBUTE_DIRECTORY)
                     ? CHOOSEFILE_FLAG_DIRECTORY : 0;
  }
  return 0;
}
```

 © 2020 SEGGER Microcontroller GmbH

22.4.3.4.1.2 CHOOSEFILE_EnableToolTips()

Before	After
	

Description

Enables ToolTips for CHOOSEFILE dialogs.

Prototype

```
void CHOOSEFILE_EnableToolTips(void);
```

Additional information

The text of the ToolTips can be configured. Details can be found in the description of `CHOOSEFILE_SetToolTips`.

 © 2020 SEGGER Microcontroller GmbH

22.4.3.4.1.3 CHOOSEFILE_SetButtonText()

Before	After
	

Description

Uses text instead of the default image.

Prototype

```
void CHOOSEFILE_SetButtonText(      WM_HWIN    hWin,
                                    unsigned   ButtonIndex,
                              const char     * pText);
```

Parameters

Parameter	Description
hWin	Handle of the CHOOSEFILE dialog.
ButtonIndex	See *CHOOSEFILE button indexes* on page 2284 for a full list of permitted values.
pText	Pointer to a string to be used.

Additional information

The function copies the string(s) into its own memory location(s). The size of the buttons depend on the used text. The dialog makes sure, that all buttons which use text instead of an image have the same size.

 © 2020 SEGGER Microcontroller GmbH

22.4.3.4.1.4 CHOOSEFILE_SetDefaultButtonText()

Description

Sets the default text to be used for new dialogs.

Prototype

```
void CHOOSEFILE_SetDefaultButtonText(      unsigned   ButtonIndex,
                                     const char     * pText);
```

Parameters

Parameter	Description
ButtonIndex	See *CHOOSEFILE button indexes* on page 2284 for a full list of permitted values.
pText	Text to be used per default.

 © 2020 SEGGER Microcontroller GmbH

22.4.3.4.1.5 CHOOSEFILE_SetDelim()

Description

Sets the delimiter used within a path. Default is a backslash.

Prototype

```
void CHOOSEFILE_SetDelim(char Delim);
```

Parameters

Parameter	Description
Delim	Delimiter to be used.

 © 2020 SEGGER Microcontroller GmbH

22.4.3.4.1.6 CHOOSEFILE_SetToolTips()

Before	After
	

Description

Sets the text to be shown by the ToolTips.

Prototype

```
void CHOOSEFILE_SetToolTips(const TOOLTIP_INFO * pInfo,
                            int            NumItems);
```

Parameters

Parameter	Description
pInfo	Pointer to an array of TOOLTIP_INFO structures.
NumItems	Number of items pointed by pInfo.

Additional information

The elements of the TOOLTIP_INFO structure are described in the section *ToolTips* on page 794.

 © 2020 SEGGER Microcontroller GmbH

22.4.3.4.1.7 CHOOSEFILE_SetTopMode()

Before	After
	

Description

Makes the button bar visible at the top of the dialog.

Prototype

```
void CHOOSEFILE_SetTopMode(unsigned OnOff);
```

Parameters

Parameter	Description
OnOff	1 for top mode, 0 (default) for bottom mode.

 © 2020 SEGGER Microcontroller GmbH

22.4.3.4.2 Data structures

22.4.3.4.3 CHOOSEFILE_INFO

Description

Structure that contains information for creating a CHOOSEFILE dialog.

Type definition

```
typedef struct {
  int               Cmd;
  const char      * pMask;
  char            * pName;
  char            * pExt;
  char            * pAttrib;
  U32               SizeL;
  U32               SizeH;
  U32               Flags;
  char              pRoot[CHOOSEFILE_MAXLEN];
  int             (* pfGetData)(CHOOSEFILE_INFO * pInfo);
} CHOOSEFILE_INFO;
```

Structure members

Member	Description
Cmd	Command for GetData() function. See below.
pMask	This parameter is passed to the GetData() function and contains a mask which can be used for filtering the search result.
pName	Pointer to the file name of the requested file.
pExt	Pointer to the extension of the requested file.
pAttrib	Pointer to the attribute string of the requested file.
SizeL	Lower 32 bit of the file size.
SizeH	Upper 32 bit of the file size.
Flags	If the requested file is a directory it should be set to CHOOSEFILE_FLAG_DIRECTORY, otherwise it should be set to 0.
pRoot	Pointer to a string containing the complete path of the currently used directory.
pfGetData	Pointer to the GetData() function to be used.

Permitted values for element Cmd	
CHOOSEFILE_FINDFIRST	The first entry of the current directory should be returned.
CHOOSEFILE_FINDNEXT	The next entry of the current directory should be returned.

Element CHOOSEFILE_FINDFIRST

This command is sent to the given callback routine to get the first entry of the current directory. The element pRoot of the CHOOSEFILE_INFO structure pointed by the parameter pInfo of the callback function contains the path to be used.
The following elements of the CHOOSEFILE_INFO structure should be used by the application to return information of the requested file: pName, pExt, pAttrib, SizeL, SizeH and Flags. The parameter pAttrib contains a string to be shown in the 'Attrib' column. This string has to be build by the application. So each attributes independent of the used file system can be shown.
All strings used to return information about the file are copied by the dialog into its own memory locations.

 © 2020 SEGGER Microcontroller GmbH

If no file could be found the `GetData()` function should return 1.

Element CHOOSEFILE_FINDNEXT

This command is sent to the given callback routine to get the next entry of the chosen directory. If no further file could be found the `GetData()` function should return 1.

 © 2020 SEGGER Microcontroller GmbH

22.4.3.4.4 Defines

22.4.3.4.4.1 CHOOSEFILE button indexes

 © 2020 SEGGER Microcontroller GmbH

22.4.4 MESSAGEBOX

A MESSAGEBOX is used to show a message in a frame window with a title bar, as well as an "OK" button which must be pressed in order to close the window. It requires only one line of code to create or to create and execute a message box.

> **Note**
>
> All MESSAGEBOX-related routines are in the file(s) `MESSAGEBOX*.c`, `MESSAGEBOX.h` and `GUI.h`.

Simple message boxes



22.4.4.1 Configuration options

Type	Macro	Default	Description
N	MESSAGEBOX_BORDER	4	Distance between the elements of a message box and the elements of the client window frame.
N	MESSAGEBOX_XSIZEOK	50	X-size of the "OK" button.
N	MESSAGEBOX_YSIZEOK	20	Y-size of the "OK" button.
S	MESSAGEBOX_BKCOLOR	GUI_WHITE	Color of the client window background.

22.4.4.2 Keyboard reaction

The widget consists of a FRAMEWIN, a TEXT and a BUTTON widget. When executing a message box the BUTTON widget gains the input focus. Detailed information on how keyboard events are handled by the BUTTON widget can be found in the section *BUTTON: Button widget* on page 985.

22.4.4.3 MESSAGEBOX API

The table below lists the available emWin MESSAGEBOX-related routines in alphabetical order. Detailed descriptions follow.

Routine	Description
GUI_MessageBox()	Creates and displays a message box.
MESSAGEBOX_Create()	Creates a message box.

 © 2020 SEGGER Microcontroller GmbH

22.4.4.3.1 GUI_MessageBox()

Description

Creates and displays a message box.

Prototype

```
int GUI_MessageBox(const char * sMessage,
                   const char * sCaption,
                         int    Flags);
```

Parameters

Parameter	Description
sMessage	Message to display.
sCaption	Caption for the title bar of the frame window.
Flags	See table below.

Permitted values for parameter Flags	
GUI_MESSAGEBOX_CF_MOVEABLE	The message box can be moved by dragging the title bar or the frame.
0	No function.

Additional information

This function offers the possibility to create and execute a MESSAGEBOX with one line of code. An example implementation can be found in the sample application DIALOG_MessageBox.c which is located in the Sample folder. Details about dragging can be found in the description of FRAMEWIN_SetMoveable().

 © 2020 SEGGER Microcontroller GmbH

22.4.4.3.2 MESSAGEBOX_Create()

Description

Creates a message box.

Prototype

```
WM_HWIN MESSAGEBOX_Create(const char * sMessage,
                          const char * sCaption,
                                int    Flags);
```

Parameters

Parameter	Description
sMessage	Message to display.
sCaption	Caption for the title bar of the frame window.
Flags	See table below.

Permitted values for parameter Flags	
GUI_MESSAGEBOX_CF_MODAL	Creates a modal message box. The default is creating a non modal message box.

Return value

Handle of the message box window.

Additional information

The function creates a message box consisting of a frame window with the caption text in the title bar, a text widget with the message text and a button widget representing the 'OK' button. After creating the message box the dialog behavior may be changed by using a user defined callback function or the properties of the box items can be modified using the widget API functions.

The following IDs can be used for accessing the items:

ID	Description
GUI_ID_TEXT0	ID of the TEXT widget containing the message text.
GUI_ID_OK	ID of the 'OK' BUTTON widget.

The frame window can be accessed by the handle returned by this function. The function GUI_ExecCreatedDialog() should be used to execute the message box.

 © 2020 SEGGER Microcontroller GmbH

Chapter 23

Skinning

Skinning is a method of changing the appearance of one or multiple widgets. It allows changing the look by using a dedicated skin which defines how the widgets are rendered. This makes it easy to change the appearance of a complete group of widgets in a similar way by changing only the skin.
Without skinning, widget member functions have to be used to change the look for each single widget or the callback function has to be overwritten.



 © 2020 SEGGER Microcontroller GmbH

23.1 What is a 'skin'

A skin is just a simple callback function which is available for drawing all details of a widget. It works by exactly same way as a ’user draw function’ of a widget, an older method of widget customization which was available before skinning was implemented.

 © 2020 SEGGER Microcontroller GmbH

23.2 From using API functions to skinning

There are different methods to change the appearance of a widget. Widget API functions, user draw functions, skinning and overwriting the callback function can be used to modify the appearance of a widget. The decision of the method to be used depends on what should be changed. The following explains what can be achieved with each method.

Using widget API functions

The default API functions can be used to change attributes like size, color, font or bitmaps used to draw a widget using the classical design. The following screenshot shows a typical sample of what can be done:

Before	After
	

Some attributes can be changed but the basic appearance stays the same.

User draw functions

Some widgets like LISTBOX, FRAMEWIN, GRAPH or BUTTON widgets offer user draw functions. These functions can be used to draw some additional details or to replace the default drawing method for some items. The following screenshot shows a user drawn title area of a frame window. The user draw function renders the gradient in the title area, which can't be achieved with the widget API functions:

Before	After
	

Skinning

Contrary to the methods mentioned above skinning covers the drawing of the whole widget and not only some details. We also used this opportunity to lift the appearance of the skinnable widgets which look much more up-to-date as the classical widget design. The following table shows the look of the about box from above in comparison with the new default skin:

 © 2020 SEGGER Microcontroller GmbH

Classical design	Default skin
	

Overwriting the callback function of a widget

Before skinning was implemented, the only method of changing the complete appearance of a widget was overwriting the callback function of a widget. This gives full control over the complete message processing of the widget. It can be used in combination with the other methods. The main disadvantage of overwriting the callback function is that lots of code needs to be written by the user. This process is prone to error.

Using widget API for skinned widgets

Some functions do not have an effect anymore on widget properties. For example, the function `BUTTON_SetColor()` doesn't work with the Flex skin, due to the fact that the BUTTON doesn't consist of a single color anymore.

 © 2020 SEGGER Microcontroller GmbH

23.3 Skinnable widgets

Skinning only makes sense if a widget consists of several widget specific details. It does not make sense for each kind of widget. A TEXT widget for example does not require a separate skin, because it consists only of the text itself.
Currently the following widgets support skinning:

- BUTTON
- CHECKBOX
- DROPDOWN
- FRAMEWIN
- HEADER
- MENU
- MULTIPAGE
- PROGBAR
- RADIO
- SCROLLBAR
- SLIDER
- SPINBOX

 © 2020 SEGGER Microcontroller GmbH

23.4 Using a skin

The shipment of emWin contains a ready-to-use default skin for all above listed skinnable widgets. They have been named <WIDGET>_SKIN_FLEX.
The following table shows the available default skins for all skinnable widgets:

Widget	Default skin
BUTTON	BUTTON_SKIN_FLEX
CHECKBOX	CHECKBOX_SKIN_FLEX
DROPDOWN	DROPDOWN_SKIN_FLEX
FRAMEWIN	FRAMEWIN_SKIN_FLEX
HEADER	HEADER_SKIN_FLEX
MENU	MENU_SKIN_FLEX
MULTIPAGE	MULTIPAGE_SKIN_FLEX
PROGBAR	PROGBAR_SKIN_FLEX
RADIO	RADIO_SKIN_FLEX
SCROLLBAR	SCROLLBAR_SKIN_FLEX
SLIDER	SLIDER_SKIN_FLEX
SPINBOX	SPINBOX_SKIN_FLEX

23.4.1 Runtime configuration

To use these skins the function <WIDGET>_SetSkin(<WIDGET>_SKIN_FLEX) can be used. Further it is possible to set a default skin by <WIDGET>_SetDefaultSkin() which is used automatically for each new widget.

Switching from classic design to a skin

The most recommended way of using a skin is first setup the widget behavior and then creating the widget.

Example

The following example shows how a skin can be used:

```
BUTTON_SetSkin(hButton, BUTTON_SKIN_FLEX); // Sets the skin for the given widget
BUTTON_SetDefaultSkin(BUTTON_SKIN_FLEX);   // Sets the default skin for new widgets
```

Additional information

<WIDGET>_SetSkin()	can be called at any time causing the given widget to use the set skinning routine.
<WIDGET>_SetDefaultSkin()	has to be called before creating the widget which should use the set skinning routine.
<WIDGET>_SetDefaultSkin()	should be used when multiple or all widgets should use the same skinning routine.

23.4.2 Compile time configuration

If Skinning should be used by default the compile time configuration macro WIDGET_USE_FLEX_SKIN needs to be defined as 1 in GUIConf.h.

Example

To use skinning per default the macro should be added to the file GUIConf.h:

 © 2020 SEGGER Microcontroller GmbH

```
#define WIDGET_USE_FLEX_SKIN 1
```

 © 2020 SEGGER Microcontroller GmbH

23.5 Simple changes to the look of the 'Flex' skin

Similar to the API functions available for changing the attributes of the classical look the attributes of the ’Flex’ skin can also be changed. This can be done without knowing all details of the skinning mechanism.
The function(s) <WIDGET>_SetSkinFlexProps() explained in detail later in this chapter can be used to change the attributes. For each skin exist functions for getting and setting the attributes.

Example

The following code shows how to change the attributes of the button skin:

```
BUTTON_GetSkinFlexProps(&Props, BUTTON_SKINFLEX_FOCUSED);
Props.aColorFrame[0] = 0x007FB13C;
Props.aColorFrame[1] = 0x008FfF8F;
Props.Radius  = 6;
BUTTON_SetSkinFlexProps(&Props, BUTTON_SKINFLEX_FOCUSED);
WM_InvalidateWindow(hWin);
```

Since skin properties are general to a certain type of widget, setting skin properties does not invalidate any window. Widgets which are affected by any changes have to be invalidated as shown above.

Screenshot

Before	After
	

 © 2020 SEGGER Microcontroller GmbH

23.6 Major changes to the 'Flex' skin

The drawing mechanism of the default design without skinning is a ’black box’ for the application designer. The same is true for skinning if no major changes of the default look are required. If changing the attributes of the default skin is not sufficient to realize the required look, it is required to understand the details of the drawing mechanism of skinning.

23.6.1 The skinning callback mechanism

The drawing mechanism for all skinnable widgets is very similar and looks as follows:

```
int <WIDGET>_DrawSkin(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo) {
  switch (pDrawItemInfo->Cmd) {
  case WIDGET_ITEM_DRAW_BACKGROUND:
    /* Draw the background */
    break;
  case WIDGET_ITEM_DRAW_TEXT:
    /* Draw the text */
    break;
  case WIDGET_ITEM_CREATE:
    /* Additional function calls required to create the widget */
    break;
  ...
}
```

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	Cmd	Command to be processed.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate in window coordinates.
int	y0	Topmost coordinate in window coordinates.
int	x1	Rightmost coordinate in window coordinates.
int	y1	Bottommost coordinate in window coordinates.
void *	p	Data pointer to widget specific information.

This scheme is identical to all skinnable widgets. The callback function receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The structure pointed by pDrawItemInfo contains a command which has to be processed, a handle to the widget and further information whose meaning may vary by widget. The skinning callback function has to react with drawing a dedicated detail or with returning a dedicated value. How to use the drawing information in detail is explained later in this chapter.

23.6.2 Changing the look of the default skin

Understanding the above callback mechanism is important because changing a skin can easily be done by deriving a new skin from an existing one. A small example should show how the look of the default skin of a widget can be changed. Assuming the default look of the frame window skin should be changed because an icon should be shown on the left side of the title bar. The default appearance of the FRAMEWIN skin is as follows:



 © 2020 SEGGER Microcontroller GmbH

This should be changed to the following:



This can be done easily by using a customized skin derived from the default skin. The following code shows how this can be achieved. It shows a custom skinning callback function which is used as skin by the function FRAMEWIN_SetSkin(). Because the icon should be drawn in the text area of the frame window the function overwrites the default behavior of the text drawing:

```
 case WIDGET_ITEM_DRAW_TEXT:
  ...
All other tasks should be performed by the default skin:
 default:
  return FRAMEWIN_DrawSkinFlex(pDrawItemInfo);
```

Example

```
static int _DrawSkinFlex_FRAME(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo) {
  char acBuffer[20];
  GUI_RECT Rect;
  switch (pDrawItemInfo->Cmd) {
  case WIDGET_ITEM_DRAW_TEXT:
  //
  // Draw icon at the left side
  //
  GUI_DrawBitmap(&_bmLogo_30x15, pDrawItemInfo->x0, pDrawItemInfo->y0);
  //
  // Draw text beneath
  //
  FRAMEWIN_GetText(pDrawItemInfo->hWin, acBuffer, sizeof(acBuffer));
  GUI_SetColor(GUI_BLACK);
  Rect.x0 = pDrawItemInfo->x0   // Default position of text
          + _bmLogo_30x15.XSize // + X-size of icon
          + 4;                  // + small gap between icon and text
  Rect.y0 = pDrawItemInfo->y0;
  Rect.x1 = pDrawItemInfo->x1;
  Rect.y1 = pDrawItemInfo->y1;
  GUI_DispStringInRect(acBuffer, &Rect, GUI_TA_VCENTER);
    break;
  default:
  //
  // Use the default skinning routine for processing all other commands
  //
  return FRAMEWIN_DrawSkinFlex(pDrawItemInfo);
  }
  return 0;
}
void _SetSkin(WM_HWIN) {
  //
  // Set the derived
  //
  FRAMEWIN_SetSkin(hFrame, _DrawSkinFlex_FRAME);
}
```

 © 2020 SEGGER Microcontroller GmbH

23.6.3 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. There are several commands which are sent to the skinning routine of a widget, but only a set of commands is sent to a certain type of widget. Further the exact meaning may vary according to the widget. How to react to commands is explained in the widget specific sections of this chapter. The following table gives an overview of the commands which are sent to the skinning routines:

Command Id (Cmd)	Description
Creation messages	
WIDGET_ITEM_CREATE	Sent to each skinnable widget after it has been created but before it is drawn.
Information messages	
WIDGET_ITEM_GET_BORDERSIZE_B	Used to get the size of the bottom border.
WIDGET_ITEM_GET_BORDERSIZE_L	Used to get the size of the left border.
WIDGET_ITEM_GET_BORDERSIZE_R	Used to get the size of the right border.
WIDGET_ITEM_GET_BORDERSIZE_T	Used to get the size of the top border.
WIDGET_ITEM_GET_BUTTONSIZE	Used to get the button size.
WIDGET_ITEM_GET_XSIZE	Used to get the X-size.
WIDGET_ITEM_GET_YSIZE	Used to get the Y-size.
Drawing messages	
WIDGET_ITEM_DRAW_ARROW	Used to draw an arrow.
WIDGET_ITEM_DRAW_BACKGROUND	Used to draw the background.
WIDGET_ITEM_DRAW_BITMAP	Used to draw a bitmap.
WIDGET_ITEM_DRAW_BUTTON	Used to draw the button area.
WIDGET_ITEM_DRAW_BUTTON_L	Used to draw the left button area.
WIDGET_ITEM_DRAW_BUTTON_R	Used to draw the right button area.
WIDGET_ITEM_DRAW_FOCUS	Used to draw the focus rectangle.
WIDGET_ITEM_DRAW_FRAME	Used to draw the frame of a widget.
WIDGET_ITEM_DRAW_OVERLAP	Used to draw the overlapping region.
WIDGET_ITEM_DRAW_SEP	Used to draw a separator.
WIDGET_ITEM_DRAW_SHAFT	Used to draw the shaft area.
WIDGET_ITEM_DRAW_SHAFT_L	Used to draw the left shaft area.
WIDGET_ITEM_DRAW_SHAFT_R	Used to draw the right shaft area.
WIDGET_ITEM_DRAW_TEXT	Used to draw the text.
WIDGET_ITEM_DRAW_THUMB	Used to draw the thumb area.
WIDGET_ITEM_DRAW_TICKS	Used to draw tick marks.

 © 2020 SEGGER Microcontroller GmbH

23.7 General Skinning API

The table below lists available skinning-related routines in alphabetical order. These functions are common to all skinnable widgets, and are listed here in order to avoid repetition. Detailed descriptions of the routines follow. The additional skinning member functions available for each widget may be found in later sections.

Routine	Description
<WIDGET>_DrawSkinFlex()	Skinning callback function of the default skin.
<WIDGET>_GetSkinFlexProps()	Returns the current properties of the skin.
<WIDGET>_SetDefaultSkin()	Sets the default skin used for new widgets.
<WIDGET>_SetDefaultSkinClassic()	Sets the classical design as default for new widgets.
<WIDGET>_SetSkin()	Sets a skin for the given widget.
<WIDGET>_SetSkinClassic()	Sets the classical design for the given widget.
<WIDGET>_SetSkinFlexProps()	Sets the properties of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.7.1 <WIDGET>_DrawSkinFlex()

Description

These functions are the skinning callback functions of the default skin and are responsible to draw the complete widget.

Prototype

```
int <WIDGET>_DrawSkinFlex(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo);
```

Parameters

Parameter	Description
pDrawItemInfo	Pointer to a data structure of type WIDGET_ITEM_DRAW_INFO.

Additional information

A derived skin can use this function for drawing details of the default skin.

 © 2020 SEGGER Microcontroller GmbH

23.7.2 <WIDGET>_GetSkinFlexProps()

Description

These functions return the attributes of the default skin. The widget specific descriptions later in this chapter explain the skin attributes in detail.

Prototype

```
void <WIDGET>_GetSkinFlexProps(<WIDGET>_SKINFLEX_PROPS * pProps,
                               int                       Index);
```

Parameters

Parameter	Description
pProps	Pointer to a skin specific configuration structure of type <WIDGET>_SKINFLEX_PROPS to be filled by the function.
Index	Widget state (pressed, active, selected, …) for which the details should be retrieved.

 © 2020 SEGGER Microcontroller GmbH

23.7.3 <WIDGET>_SetDefaultSkin()

Description

These functions set the default skin which is used for new widgets of the dedicated type.

Prototype

```
void <WIDGET>_SetDefaultSkin(WIDGET_DRAW_ITEM_FUNC * pfDrawSkin);
```

Parameters

Parameter	Description
pfDrawSkin	Pointer to a skinning callback function of type WIDGET_DRAW_ITEM_FUNC.

Additional information

The given pointer should point to the skinning callback routine to be used for all new widgets. Details can be found in the description of *<WIDGET>_SetSkin()* on page 2304.

 © 2020 SEGGER Microcontroller GmbH

23.7.4 <WIDGET>_SetDefaultSkinClassic()

Description

These functions set the classical design for all new widgets of the dedicated type.

Prototype

```
void <WIDGET>_SetDefaultSkinClassic(void);
```

Additional information

The behavior of widgets which use the classical design is completely identical to the behavior before implementing the skinning feature.

 © 2020 SEGGER Microcontroller GmbH

23.7.5 <WIDGET>_SetSkin()

Description

These functions can be used for setting a skin for the given widget.

Prototype

```
void <WIDGET>_SetSkin(<WIDGET>_Handle         hObj,
                      WIDGET_DRAW_ITEM_FUNC * pfDrawSkin);
```

Parameters

Parameter	Description
hObj	Handle to the dedicated widget.
pfDrawSkin	Pointer to a skinning callback function of type WIDGET_DRAW_ITEM_FUNC.

WIDGET_DRAW_ITEM_FUNC

```
typedef int WIDGET_DRAW_ITEM_FUNC(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo);
```

Additional information

Default widget API functions may have no effect in case a skin is used.

 © 2020 SEGGER Microcontroller GmbH

23.7.6 <WIDGET>_SetSkinClassic()

Description

These functions switch to the classical design without skinning for the given widget.

Prototype

```
void <WIDGET>_SetSkinClassic(<WIDGET>_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to the dedicated widget.

Additional information

Additional information can be found in the description of *<WIDGET>_SetDefaultSkinClassic()* on page 2303.

 © 2020 SEGGER Microcontroller GmbH

23.7.7 <WIDGET>_SetSkinFlexProps()

Description

With these functions some attributes of the default skin can be changed without deriving an own skin. The widget specific descriptions later in this chapter will explain in detail what can be changed.

Prototype

```
void <WIDGET>_SetSkinFlexProps(const <WIDGET>_SKINFLEX_PROPS * pProps,
                               int                             Index);
```

Parameters

Parameter	Description
pProps	Pointer to a skin specific configuration structure of type <WIDGET>_SKINFLEX_PROPS.
Index	Details of the state (pressed, active, selected, …) for which the details should be valid.

 © 2020 SEGGER Microcontroller GmbH

23.8 BUTTON_SKIN_FLEX

The following picture shows the details of the skin:



The BUTTON skin consists of a rounded border and a rectangular inner area which is filled by 2 gradients. The surrounding border is drawn by 2 colors.

Detail	Description
A	Top color of top gradient.
B	Bottom color of top gradient.
C	Top color of bottom gradient.
D	Bottom color of bottom gradient.
E	Outer color of surrounding frame.
F	Inner color of surrounding frame.
G	Color of area between surrounding frame and inner rectangular area.
R	Radius of rounded corner.
T	Optional text.

23.8.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type `BUTTON_SKINFLEX_PROPS` are used:

Elements of structure BUTTON_SKINFLEX_PROPS

Data type	Element	Description
`U32`	`aColorFrame[3]`	[0] - Outer color of surrounding frame. [1] - Inner color of surrounding frame. [2] - Color of area between frame and inner area.
`U32`	`aColorUpper[2]`	[0] - First (upper) color of upper gradient. [1] - Second (lower) color of upper gradient.
`U32`	`aColorLower[2]`	[0] - First (upper) color of lower gradient. [1] - Second (lower) color of lower gradient.
`int`	`Radius`	Radius of rounded corner.

23.8.2 Configuration options

The default appearance of the skin can be defined using custom configuration structures of the type `BUTTON_SKINFLEX_PROPS` in `GUIConf.h`. The following table shows the identifiers which are used for the different states of the skinned BUTTON widget:

Macro	Description
`BUTTON_SKINPROPS_PRESSED`	Defines the default attributes used for pressed state.

 © 2020 SEGGER Microcontroller GmbH

Macro	Description
BUTTON_SKINPROPS_FOCUSED	Defines the default attributes used for focused state.
BUTTON_SKINPROPS_ENABLED	Defines the default attributes used for enabled state.
BUTTON_SKINPROPS_DISABLED	Defines the default attributes used for disabled state.

23.8.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
BUTTON_DrawSkinFlex()	Skinning callback function of BUTTON_SKIN_FLEX. (Explained at the beginning of the chapter)
BUTTON_GetSkinFlexProps()	Returns the properties of the given button skin. (Explained at the beginning of the chapter)
BUTTON_SetDefaultSkin()	Sets the default skin used for new button widgets. (Explained at the beginning of the chapter)
BUTTON_SetDefaultSkinClassic()	Sets the classical design as default for new button widgets. (Explained at the beginning of the chapter)
BUTTON_SetSkin()	Sets a skin for the given button widget. (Explained at the beginning of the chapter)
BUTTON_SetSkinClassic()	Sets the classical design for the given button widget. (Explained at the beginning of the chapter)
BUTTON_SetSkinFlexProps()	Sets the properties of the given button skin.

 © 2020 SEGGER Microcontroller GmbH

23.8.3.1 BUTTON_SetSkinFlexProps()

Before	After
	

Description

Sets the properties of the given button skin.

Prototype

```
void BUTTON_SetSkinFlexProps(const BUTTON_SKINFLEX_PROPS * pProps,
                             int                         Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type BUTTON_SKINFLEX_PROPS.
Index	See table below.

Permitted values for parameter Index	
BUTTON_SKINFLEX_PI_PRESSED	Properties for pressed state.
BUTTON_SKINFLEX_PI_FOCUSED	Properties for focused state.
BUTTON_SKINFLEX_PI_ENABLED	Properties for enabled state.
BUTTON_SKINFLEX_PI_DISABLED	Properties for disabled state.

Additional information

The function passes a pointer to a BUTTON_SKINFLEX_PROPS structure. It can be used to set up the colors and the radius of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.8.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the BUTTON_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_BACKGROUND	The skinning function should draw the background.
WIDGET_ITEM_DRAW_BITMAP	The skinning function should draw the optional button bitmap.
WIDGET_ITEM_DRAW_TEXT	The skinning function should draw the optional button text.

The WIDGET_ITEM_DRAW_INFO structure is explained at the beginning of the chapter.

23.8.4.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.8.4.2 WIDGET_ITEM_DRAW_BACKGROUND

The background of the widget should be drawn.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	See table below.
int	x0	Leftmost coordinate in window coordinates, normally 0.
int	y0	Topmost coordinate in window coordinates, normally 0.
int	x1	Rightmost coordinate in window coordinates.
int	y1	Bottommost coordinate in window coordinates.

Permitted values for element ItemIndex	
BUTTON_SKINFLEX_PI_PRESSED	The widget is pressed.
BUTTON_SKINFLEX_PI_FOCUSED	The widget is not pressed but focused.
BUTTON_SKINFLEX_PI_ENABLED	The widget is not focused but enabled.
BUTTON_SKINFLEX_PI_DISABLED	The widget is disabled.

23.8.4.3 WIDGET_ITEM_DRAW_BITMAP

The optional button bitmap should be drawn.

WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2310.

Additional information

The function BUTTON_GetBitmap() can be used to get the optional button bitmap.

 © 2020 SEGGER Microcontroller GmbH

23.8.4.4 WIDGET_ITEM_DRAW_TEXT

The optional button text should be drawn.

WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2310.

Additional information

The function `BUTTON_GetText()` can be used to get the optional text.

 © 2020 SEGGER Microcontroller GmbH

23.9 CHECKBOX_SKIN_FLEX

The following picture shows the details of the skin:



The button area of the CHECKBOX skin consists of a frame and a rectangular inner area which is filled by a gradient. The frame is drawn by 3 colors. If it is checked, a checkmark is shown in the center of the box:

Detail	Description
A	First color of frame.
B	Second color of frame.
C	Third color of frame.
D	Upper color of gradient.
E	Lower color of gradient.
F	Color of checkmark.
R	Focus rectangle.
S	Size in pixels of button area.
T	Optional text.

23.9.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type `CHECKBOX_SKINFLEX_PROPS` are used:

Elements of structure CHECKBOX_SKINFLEX_PROPS

Data type	Element	Description
`U32`	`aColorFrame[3]`	[0] - Outer color of frame. [1] - Middle color of frame. [2] - Inner color of frame.
`U32`	`aColorInner[2]`	[0] - First (upper) color of gradient. [1] - Second (lower) color of gradient.
`U32`	`ColorCheck`	Color of checkmark.
`int`	`ButtonSize`	Size in pixels of the button area. (Obsolete. Use the functions `CHECKBOX_GetSkinFlexButtonSize()` and `CHECKBOX_SetSkinFlexButtonSize()`)

23.9.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in `GUIConf.h`. The following table shows the available configuration options:

 © 2020 SEGGER Microcontroller GmbH

Macro	Description
CHECKBOX_SKINPROPS_ENABLED	Defines the default attributes used for enabled state.
CHECKBOX_SKINPROPS_DISABLED	Defines the default attributes used for disabled state.

23.9.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
CHECKBOX_DrawSkinFlex()	Skinning callback function of CHECKBOX_SKIN_FLEX. (Explained at the beginning of the chapter)
CHECKBOX_GetSkinFlexButtonSize()	Returns the button size of the specified CHECKBOX widget.
CHECKBOX_GetSkinFlexProps()	Returns the properties of the given checkbox skin. (Explained at the beginning of the chapter)
CHECKBOX_SetDefaultSkin()	Sets the default skin used for new checkbox widgets. (Explained at the beginning of the chapter)
CHECKBOX_SetDefaultSkinClassic()	Sets the classical design as default for new checkbox widgets. (Explained at the beginning of the chapter)
CHECKBOX_SetSkin()	Sets a skin for the given checkbox widget. (Explained at the beginning of the chapter)
CHECKBOX_SetSkinClassic()	Sets the classical design for the given checkbox widget. (Explained at the beginning of the chapter)
CHECKBOX_SetSkinFlexButtonSize()	Sets the button size of the specified CHECKBOX widget.
CHECKBOX_SetSkinFlexProps()	The function can be used to change the properties of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.9.3.1 CHECKBOX_GetSkinFlexButtonSize()

Description

Returns the button size of the specified CHECKBOX widget.

Prototype

```
int CHECKBOX_GetSkinFlexButtonSize(CHECKBOX_Handle hObj);
```

Parameters

Parameter	Description
hObj	Handle to a CHECKBOX widget.

Return value

Button size.

 © 2020 SEGGER Microcontroller GmbH

23.9.3.2 CHECKBOX_SetSkinFlexButtonSize()

Before	After
	

Description

Sets the button size of the specified CHECKBOX widget.

Prototype

```
void CHECKBOX_SetSkinFlexButtonSize(CHECKBOX_Handle hObj,
                                    int             ButtonSize);
```

Parameters

Parameter	Description
hObj	Handle to a CHECKBOX widget.
ButtonSize	Size to be set.

 © 2020 SEGGER Microcontroller GmbH

23.9.3.3 CHECKBOX_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change the properties of the skin.

Prototype

```
void CHECKBOX_SetSkinFlexProps(const CHECKBOX_SKINFLEX_PROPS * pProps,
                               int                           Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type CHECKBOX_SKINFLEX_PROPS.
Index	See table below.

Permitted values for parameter Index	
CHECKBOX_SKINFLEX_PI_ENABLED	Properties for enabled state.
CHECKBOX_SKINFLEX_PI_DISABLED	Properties for disabled state.

Additional information

The function passes a pointer to a CHECKBOX_SKINFLEX_PROPS structure. It can be used to set up the colors of the skin. Please note that the size of the widgets using the skin won't be changed if for example the new button size is different to the old button size. This can not be done by the skin, because it does not 'know' which widget is using it. If required resizing should be done by the application, for example with WM_ResizeWindow(). The function *CHECKBOX_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.9.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the CHECKBOX_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_BUTTON	The background of the button area should be drawn.
WIDGET_ITEM_DRAW_BITMAP	The checkmark of the button area should be drawn.
WIDGET_ITEM_DRAW_FOCUS	The focus rectangle should be drawn.
WIDGET_ITEM_DRAW_TEXT	The optional text should be drawn.

23.9.4.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.9.4.2 WIDGET_ITEM_DRAW_BUTTON

The button area of the widget without checkmark should be drawn. It is typically drawn at the left side of the widget area.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	x0	Leftmost coordinate of widget area in window coordinates, normally 0.
int	y0	Topmost coordinate of widget area in window coordinates, normally 0.
int	x1	Rightmost coordinate of widget area in window coordinates.
int	y1	Bottommost coordinate of widget area in window coordinates.

The content of hWin, x0, y0, x1 and y1 is the same for all commands of this skin.

23.9.4.3 WIDGET_ITEM_DRAW_BITMAP

The checkmark should be drawn in the center of the button area.

Elements of structure WIDGET_ITEM_DRAW_INFO

Element	Description
ItemIndex	1 - The widget is checked. 2 - Second checked state when using a 3 state button.
hWin,x0,y0,x1,y1	These elements are described under *WIDGET_ITEM_DRAW_BUTTON* on page 2317.

23.9.4.4 WIDGET_ITEM_DRAW_FOCUS

The focus rectangle should be drawn around the text.

 © 2020 SEGGER Microcontroller GmbH

Elements of structure WIDGET_ITEM_DRAW_INFO

Element	Description
p	The void pointer points to the zero terminated optional text of the widget.
hWin,x0,y0,x1,y1	These elements are described under *WIDGET_ITEM_DRAW_BUTTON* on page 2317.

Additional information

The element p can be casted to a text pointer. Details can be found in the description of *WIDGET_ITEM_DRAW_TEXT* on page 2311.

23.9.4.5 WIDGET_ITEM_DRAW_TEXT

The optional text should be drawn. The text is typically drawn at the right side of the button area.

Elements of structure WIDGET_ITEM_DRAW_INFO

Element	Description
p	The void pointer points to the zero terminated optional text of the widget.
hWin,x0,y0,x1,y1	These elements are described under *WIDGET_ITEM_DRAW_BUTTON* on page 2317.

Additional information

To get a text pointer the element p can be casted to a text pointer:

```
char * s;
s = (char *)pDrawItemInfo->p;
GUI_DispString(s);
```

 © 2020 SEGGER Microcontroller GmbH

23.10 DROPDOWN_SKIN_FLEX

The following picture shows the details of the skin:



The DROPDOWN skin consists of a rounded frame and a rectangular inner area which is filled by two gradients. The rounded frame is drawn by 3 colors. At the right side a small triangle is drawn. Between text and triangle a small separator is drawn:

Detail	Description
A	First color of frame.
B	Second color of frame.
C	Third color of frame.
D	Top color of top gradient.
E	Bottom color of top gradient.
F	Top color of bottom gradient.
G	Bottom color of bottom gradient.
H	Separator between text and triangle.
I	Triangle.
R	Radius of rounded corner.
T	Optional text.

The dropdown widget in open state consists of an additional LISTBOX widget. The skin does not affect the LISTBOX.

23.10.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type `DROPDOWN_SKINFLEX_PROPS` are used:

Elements of structure DROPDOWN_SKINFLEX_PROPS

Data type	Element	Description
`U32`	`aColorFrame[3]`	[0] - Outer color of surrounding frame. [1] - Inner color of surrounding frame. [2] - Color of area between frame and inner area.
`U32`	`aColorUpper[2]`	[0] - Top color of top gradient. [1] - Bottom color of top gradient.
`U32`	`aColorLower[2]`	[0] - Top color of bottom gradient. [1] - Bottom color of bottom gradient.
`U32`	`ColorArrow`	Color used to draw the arrow.
`U32`	`ColorText`	Color used to draw the text.
`U32`	`ColorSep`	Color used to draw the separator.
`int`	`Radius`	Radius of rounded corner.

 © 2020 SEGGER Microcontroller GmbH

23.10.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in GUIConf.h. The following table shows the available configuration options:

Macro	Description
DROPDOWN_SKINPROPS_OPEN	Defines the default attributes used for open state.
DROPDOWN_SKINPROPS_FOCUSED	Defines the default attributes used for focused state.
DROPDOWN_SKINPROPS_ENABLED	Defines the default attributes used for enabled state.
DROPDOWN_SKINPROPS_DISABLED	Defines the default attributes used for disabled state.

23.10.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
DROPDOWN_DrawSkinFlex()	Skinning callback function of DROPDOWN_SKIN_FLEX. (Explained at the beginning of the chapter)
DROPDOWN_GetSkinFlexProps()	Returns the properties of the given dropdown skin. (Explained at the beginning of the chapter)
DROPDOWN_SetDefaultSkin()	Sets the default skin used for new dropdown widgets. (Explained at the beginning of the chapter)
DROPDOWN_SetDefaultSkinClassic()	Sets the classical design as default for new dropdown widgets. (Explained at the beginning of the chapter)
DROPDOWN_SetSkin()	Sets a skin for the given dropdown widget. (Explained at the beginning of the chapter)
DROPDOWN_SetSkinClassic()	Sets the classical design for the given dropdown widget. (Explained at the beginning of the chapter)
DROPDOWN_SetSkinFlexProps()	The function can be used to change the properties of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.10.3.1 DROPDOWN_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change the properties of the skin.

Prototype

```
void DROPDOWN_SetSkinFlexProps(const DROPDOWN_SKINFLEX_PROPS * pProps,
                               int                           Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type DROPDOWN_SKINFLEX_PROPS.
Index	See table below.

Permitted values for parameter Index	
DROPDOWN_SKINFLEX_PI_OPEN	Properties for open state.
DROPDOWN_SKINFLEX_PI_FOCUSED	Properties for focused state.
DROPDOWN_SKINFLEX_PI_ENABLED	Properties for enabled state.
DROPDOWN_SKINFLEX_PI_DISABLED	Properties for disabled state.

Additional information

The function passes a pointer to a DROPDOWN_SKINFLEX_PROPS structure. It can be used to set up the colors and the radius of the skin. The function *DROPDOWN_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.10.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the DROPDOWN_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_ARROW	The skinning function should draw the arrow.
WIDGET_ITEM_DRAW_BACKGROUND	The skinning function should draw the background.
WIDGET_ITEM_DRAW_TEXT	The skinning function should draw the optional button text.

23.10.4.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.10.4.2 WIDGET_ITEM_DRAW_ARROW

The triangle (arrow) at the right side should be drawn.

Elements of structure WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2310.

23.10.4.3 WIDGET_ITEM_DRAW_BACKGROUND

The background of the widget should be drawn.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	See table below.
int	x0	Leftmost coordinate in window coordinates, normally 0.
int	y0	Topmost coordinate in window coordinates, normally 0.
int	x1	Rightmost coordinate in window coordinates.
int	y1	Bottommost coordinate in window coordinates.

Permitted values for element ItemIndex	
DROPDOWN_SKINFLEX_PI_EXPANDED	The widget is expanded.
DROPDOWN_SKINFLEX_PI_FOCUSED	The widget is in not pressed but focused.
DROPDOWN_SKINFLEX_PI_ENABLED	The widget is in not focused but enabled.
DROPDOWN_SKINFLEX_PI_DISABLED	The widget is disabled.

23.10.4.4 WIDGET_ITEM_DRAW_TEXT

The text of the currently selected string should be drawn within the button area of the dropdown widget. The text is typically drawn at the left side of the button area.

 © 2020 SEGGER Microcontroller GmbH

Elements of structure WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2322.

 © 2020 SEGGER Microcontroller GmbH

23.11 FRAMEWIN_SKIN_FLEX

The following picture shows the details of the skin:



The FRAMEWIN skin consists of a title bar, rounded corners at the top, a gradient used to draw the background of the title bar, a border whose size is configurable and a separator between title bar and client area:

Detail	Description
A	Outer color of surrounding frame.
B	Inner color of surrounding frame.
C	Color of area between frame and inner area.
Gt	Top color of top title bar gradient.
Gb	Bottom color of title bar gradient.
Bt	Top size of border.
Bb	Bottom size of border.
Bl	Left size of border.
Br	Right size of border.
W	Area of client window.
R	Radius of rounded corner.
T	Optional text.

23.11.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type FRAMEWIN_SKINFLEX_PROPS are used:

 © 2020 SEGGER Microcontroller GmbH

Elements of structure FRAMEWIN_SKINFLEX_PROPS

Data type	Element	Description
U32	aColorFrame[3]	[0] - Outer color of surrounding frame. [1] - Inner color of surrounding frame. [2] - Color of area between frame and inner area.
U32	aColorTitle[2]	[0] - Top color of top title bar gradient. [1] - Bottom color of title bar gradient.
int	Radius	Radius of rounded corners.
int	SpaceX	Optional space in X between title text and border of title gradient.
int	BorderSizeL	Left size of border.
int	BorderSizeR	Right size of border.
int	BorderSizeT	Top size of border.
int	BorderSizeB	Bottom size of border.

23.11.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in GUIConf.h. The following table shows the available configuration options:

Macro	Description
FRAMEWIN_SKINPROPS_ACTIVE	Defines the default attributes used for active state.
FRAMEWIN_SKINPROPS_INACTIVE	Defines the default attributes used for inactive state.

23.11.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
FRAMEWIN_DrawSkinFlex()	Skinning callback function of FRAMEWIN_SKIN_FLEX. (Explained at the beginning of the chapter)
FRAMEWIN_GetSkinFlexProps()	Returns the properties of the given FRAMEWIN skin. (Explained at the beginning of the chapter)
FRAMEWIN_SetDefaultSkin()	Sets the default skin used for new framewin widgets. (Explained at the beginning of the chapter)
FRAMEWIN_SetDefaultSkinClassic()	Sets the classical design as default for new framewin widgets. (Explained at the beginning of the chapter)
FRAMEWIN_SetSkin()	Sets a skin for the given framewin widget. (Explained at the beginning of the chapter)
FRAMEWIN_SetSkinClassic()	Sets the classical design for the given framewin widget. (Explained at the beginning of the chapter)
FRAMEWIN_SetSkinFlexProps()	The function can be used to change the properties of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.11.3.1 FRAMEWIN_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change the properties of the skin.

Prototype

```
void FRAMEWIN_SetSkinFlexProps(const FRAMEWIN_SKINFLEX_PROPS * pProps,
                               int                           Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type FRAMEWIN_SKINFLEX_PROPS.
Index	See table below.

Permitted values for parameter Index	
FRAMEWIN_SKINFLEX_PI_ACTIVE	Properties for active state.
FRAMEWIN_SKINFLEX_PI_INACTIVE	Properties for inactive state.

Additional information

The function passes a pointer to a FRAMEWIN_SKINFLEX_PROPS structure. It can be used to set up the colors, radius and border size of the skin. The function *FRAMEWIN_GetSkinFlexProps()* can be used to get the current attributes of the skin. When creating a frame window using this skin the values for inactive state are used for calculating size and position of the client window.

 © 2020 SEGGER Microcontroller GmbH

23.11.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the FRAMEWIN_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_BACKGROUND	The skinning function should draw the title background.
WIDGET_ITEM_DRAW_FRAME	The skinning function should draw the frame.
WIDGET_ITEM_DRAW_SEP	The skinning function should draw the separator.
WIDGET_ITEM_DRAW_TEXT	The skinning function should draw the title text.
WIDGET_ITEM_GET_BORDERSIZE_L	The skinning function should return the left border size.
WIDGET_ITEM_GET_BORDERSIZE_R	The skinning function should return the right border size.
WIDGET_ITEM_GET_BORDERSIZE_T	The skinning function should return the top border size.
WIDGET_ITEM_GET_BORDERSIZE_B	The skinning function should return the bottom border size.
WIDGET_ITEM_GET_RADIUS	The skinning function should return the radius of the corners.

23.11.4.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.11.4.2 WIDGET_ITEM_DRAW_BACKGROUND

The skinning routine should draw the background of the title area.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	See table below.
int	x0	Leftmost coordinate of title area in window coordinates.
int	y0	Topmost coordinate of title area in window coordinates.
int	x1	Rightmost coordinate of title area in window coordinates.
int	y1	Bottommost coordinate of title area in window coordinates.

Permitted values for element ItemIndex

FRAMEWIN_SKINFLEX_PI_ACTIVE	The widget is in active state.
FRAMEWIN_SKINFLEX_PI_INACTIVE	The widget is in inactive state.

 © 2020 SEGGER Microcontroller GmbH

23.11.4.3 WIDGET_ITEM_DRAW_FRAME

The skinning routine should draw the complete border without the title area and the separator.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	See table below.
int	x0	Leftmost coordinate in window coordinates, normally 0.
int	y0	Topmost coordinate in window coordinates, normally 0.
int	x1	Rightmost coordinate in window coordinates (xSize of window - 1).
int	y1	Bottommost coordinate in window coordinates (ySize of window - 1).

Permitted values for element ItemIndex

FRAMEWIN_SKINFLEX_PI_ACTIVE	The widget is in active state.
FRAMEWIN_SKINFLEX_PI_INACTIVE	The widget is in inactive state.

23.11.4.4 WIDGET_ITEM_DRAW_TEXT

The skinning routine should draw title text.

Elements of structure WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2327.

23.11.4.5 WIDGET_ITEM_GET_BORDERSIZE_L

23.11.4.6 WIDGET_ITEM_GET_BORDERSIZE_R

23.11.4.7 WIDGET_ITEM_GET_BORDERSIZE_T

23.11.4.8 WIDGET_ITEM_GET_BORDERSIZE_B

The skinning routine should return the size of the according border.

 © 2020 SEGGER Microcontroller GmbH

23.12 HEADER_SKIN_FLEX

The following picture shows the details of the skin:



The HEADER skin consists of a bar with a thin border which is divided into separate items. The background of the bar consists of a top and a bottom gradient. Each item can have a text, a bitmap and an indicator which can be used for example to show the sorting order:

Detail	Description
A	Top color of top gradient.
B	Bottom color of top gradient.
C	Top color of bottom gradient.
D	Bottom color of bottom gradient.
E	First color of frame.
F	Second color of frame.
I	Indicator.
T	Text (optional).
P	Bitmap (optional).

23.12.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type `HEADER_SKINFLEX_PROPS` are used:

Elements of structure HEADER_SKINFLEX_PROPS

Data type	Element	Description
U32	`aColorFrame[2]`	[0] - First color of frame and separators. [1] - Second color of frame and separators.
U32	`aColorUpper[2]`	[0] - Top color of top gradient. [1] - Bottom color of top gradient.
U32	`aColorLower[2]`	[0] - Top color of bottom gradient. [1] - Bottom color of bottom gradient.
U32	`ColorArrow`	Color of indicator.

23.12.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in `GUIConf.h`. The following table shows the available configuration options:

Macro	Description
`HEADER_SKINPROPS`	Defines the default attributes used for drawing the skin.

 © 2020 SEGGER Microcontroller GmbH

23.12.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
HEADER_DrawSkinFlex()	Skinning callback function of HEADER_SKIN_FLEX. (Explained at the beginning of the chapter)
HEADER_GetSkinFlexProps()	Returns the properties of the given HEADER skin. (Explained at the beginning of the chapter)
HEADER_SetDefaultSkin()	Sets the default skin used for new HEADER widgets. (Explained at the beginning of the chapter)
HEADER_SetDefaultSkinClassic()	Sets the classical design as default for new HEADER widgets. (Explained at the beginning of the chapter)
HEADER_SetSkin()	Sets a skin for the given HEADER widget. (Explained at the beginning of the chapter)
HEADER_SetSkinClassic()	Sets the classical design for the given HEADER widget. (Explained at the beginning of the chapter)
HEADER_SetSkinFlexProps()	The function can be used to change the properties of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.12.3.1 HEADER_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change the properties of the skin.

Prototype

```
void HEADER_SetSkinFlexProps(const HEADER_SKINFLEX_PROPS * pProps,
                             int                         Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type HEADER_SKINFLEX_PROPS.
Index	See table below.

Additional information

The function passes a pointer to a HEADER_SKINFLEX_PROPS structure. It can be used to set up the colors of the skin. The function *HEADER_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.12.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the HEADER_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_ARROW	The indicator arrow of the header item should be drawn.
WIDGET_ITEM_DRAW_BACKGROUND	The background of the header item should be drawn.
WIDGET_ITEM_DRAW_BITMAP	The bitmap of the header item should be drawn.
WIDGET_ITEM_DRAW_OVERLAP	The overlapping region of the widget should be drawn.
WIDGET_ITEM_DRAW_TEXT	The test of the header item should be drawn.

23.12.4.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.12.4.2 WIDGET_ITEM_DRAW_ARROW

The skinning routine should draw the optional direction indicator. This message is sent only if the indicator of the header item is enabled.

Elements of structure WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2327.

23.12.4.3 WIDGET_ITEM_DRAW_BACKGROUND

The skinning routine should draw the background of an item area.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Is always 0.
int	x0	Leftmost coordinate of item area in window coordinates.
int	y0	Topmost coordinate of item area in window coordinates.
int	x1	Rightmost coordinate of item area in window coordinates.
int	y1	Bottommost coordinate of item area in window coordinates.

23.12.4.4 WIDGET_ITEM_DRAW_BITMAP

The skinning routine should draw the optional item bitmap. The message is only sent in case of an existing bitmap.

 © 2020 SEGGER Microcontroller GmbH

Elements of structure WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2332.

23.12.4.5 WIDGET_ITEM_DRAW_OVERLAP

The skinning routine should draw the overlapping region.

Elements of structure WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2332.

23.12.4.6 Widget_ITEM_DRAW_TEXT

The skinning routine should draw the optional item text. The message is only sent in case of an existing text.

Elements of structure WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2332.

 © 2020 SEGGER Microcontroller GmbH

23.13 MENU_SKIN_FLEX

The following picture shows the details of the skin:



The MENU skin covers horizontal as well as vertical MENU widgets. Since both variations require the ability to be handled differently, most items can be colored separately. The background is drawn by a gradient for horizontal MENU widgets. The vertical version only consists of a single background color. Selected and selected items having a submenu are drawn using a gradient an a frame. All vertical items are surrounded by a frame. Horizontal items are just underlined. Vertical items with a submenu consist of an arrow indicating the submenu. Separators are drawn using 2 lines with 2 different colors. The item text is displayed using the same color for all items.

Detail	Description
A	Top color of the background gradient. (horizontal)
B	Bottom color of the background gradient. (horizontal)
C	Background color. (vertical)
D	Frame color. (horizontal)
E	Frame color. (vertical)
F	Bottom color of the background gradient for selected items. (horizontal)
G	Top color of the background gradient for selected items. (horizontal)
H	Bottom color of the background gradient for selected items. (vertical)
I	Top color of the background gradient for selected items. (vertical)
J	Frame color for selected items. (horizontal)
K	Frame color for selected items. (vertical)
L	Left separator color. (horizontal)
M	Right separator color. (horizontal)
N	Top separator color. (vertical)
O	Bottom separator color. (vertical)
P	Color of the arrow indicating submenus.
Q	Color of the text.

 © 2020 SEGGER Microcontroller GmbH

23.13.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration a structure of the type MENU_SKINFLEX_PROPS must be used:

Elements of structure MENU_SKINFLEX_PROPS

Data type	Element	Description
		Background
U32	aBkColorH[2]	Horizontal: [0] - Top color of background gradient. [1] - Bottom color of horizontal background gradient.
U32	BkColorV	Background color. (vertical)
U32	FrameColorH	Frame color. (horizontal)
U32	FrameColorV	Frame color. (vertical)
		Selection
U32	aSelColorH[2]	Horizontal: [0] - Top color of the background gradient for selected items. [1] - Bottom color of the background gradient for selected items.
U32	aSelColorV[2]	Vertical: [0] - Top color of the background gradient for selected items. [1] - Bottom color of the background gradient for selected items.
U32	FrameColorSelH	Frame color for selected items. (horizontal)
U32	FrameColorSelV	Frame color for selected items. (vertical)
		Separator
U32	aSepColorH[2]	Horizontal: [0] - Left separator color. [1] - Right separator color.
U32	aSepColorV[2]	Vertical: [0] - Top separator color. [1] - Bottom separator color.
		General
U32	ArrowColor	Color of the arrow indicating submenus.
U32	TextColor	Color of the text.

23.13.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in GUIConf.h. The following table shows the available configuration options:

Macro	Description
MENU_SKINPROPS_ACTIVE_SUBMENU	Defines the default attributes which are used to draw the item in case its submenu is active.
MENU_SKINPROPS_DISABLED	Defines the default attributes which are used to draw the item in disabled state.

 © 2020 SEGGER Microcontroller GmbH

Macro	Description
MENU_SKINPROPS_DISABLED_SEL	Defines the default attributes which are used to draw the item in case it is selected in disabled state.
MENU_SKINPROPS_ENABLED	Defines the default attributes which are used to draw the item in enabled state.
MENU_SKINPROPS_SELECTED	Defines the default attributes which are used to draw the item in selected state.

23.13.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
MENU_DrawSkinFlex()	Skinning callback function of MENU_SKIN_FLEX. (Explained at the beginning of the chapter)
MENU_GetSkinFlexProps()	Returns the properties of the given MENU skin. (Explained at the beginning of the chapter)
MENU_SetDefaultSkin()	Sets the default skin used for new MENU widgets. (Explained at the beginning of the chapter)
MENU_SetDefaultSkinClassic()	Sets the classical design as default for new MENU widgets. (Explained at the beginning of the chapter)
MENU_SetSkin()	Sets a skin for the given MENU widget. (Explained at the beginning of the chapter)
MENU_SetSkinClassic()	Sets the classical design for the given MENU widget. (Explained at the beginning of the chapter)
MENU_SetSkinFlexProps()	The function can be used to change the colors of the skin.
MENU_SkinEnableArrow()	Toggles the drawing of an arrow.

 © 2020 SEGGER Microcontroller GmbH

23.13.3.1 MENU_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change the colors of the skin.

Prototype

```
void MENU_SetSkinFlexProps(const MENU_SKINFLEX_PROPS * pProps,
                           int                         Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type MENU_SKINFLEX_PROPS.
Index	See table below.

Permitted values for parameter Index	
MENU_SKINFLEX_PI_ENABLED	Properties for enabled state.
MENU_SKINFLEX_PI_SELECTED	Properties for selected state.
MENU_SKINFLEX_PI_DISABLED	Properties for disabled state.
MENU_SKINFLEX_PI_DISABLED_SEL	Properties for disabled selected state.
MENU_SKINFLEX_PI_ACTIVE_SUBMENU	Properties for active submenu state.

Additional information

The function passes a pointer to a MENU_SKINFLEX_PROPS structure. It can be used to set up the colors of the skin. The function *MENU_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.13.3.2 MENU_SkinEnableArrow()

Before	After
	

Description

Toggles the drawing of an arrow.

Prototype

```
void MENU_SkinEnableArrow(MENU_Handle hObj,
                          int         OnOff);
```

Parameters

Parameter	Description
hObj	Handle the MENU widget.
OnOff	1 to enable drawing of arrows. 0 to disable drawing of arrows.

Additional information

Arrows are drawn only…

- …if the item is part of a vertical MENU widget.
- …if the item consists of a submenu.
- …if drawing of arrows is enabled using this function.

 © 2020 SEGGER Microcontroller GmbH

23.13.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the MENU_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_ARROW	The skinning function should draw the arrow.
WIDGET_ITEM_DRAW_BACKGROUND	The skinning function should draw the background.
WIDGET_ITEM_DRAW_FRAME	The skinning function should draw the frame.
WIDGET_ITEM_DRAW_SEP	The skinning function should draw the separator.
WIDGET_ITEM_DRAW_TEXT	The skinning function should draw the text.

23.13.4.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.13.4.2 WIDGET_ITEM_DRAW_ARROW

The skinning routine should draw the arrow.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of the according item (≥ 0).
int	x0	Leftmost coordinate of the item area in window coordinates.
int	y0	Topmost coordinate of the item area in window coordinates.
int	x1	Rightmost coordinate of the item area in window coordinates.
int	y1	Bottommost coordinate of the item area in window coordinates.

Additional information

This message is sent only in case drawing arrows is enabled. Drawing is enabled by default when using MENU_SKIN_FLEX. Detailed information on how to enable/disable drawing of arrows can be found in the description of the function *MENU_SkinEnableArrow* on page 2338.

Additional information

This message is sent only in case drawing arrows is enabled. Drawing is enabled by default when using MENU_SKIN_FLEX. Detailed information on how to enable/disable drawing of arrows can be found in the description of the function *MENU_SkinEnableArrow* on page 2338.

23.13.4.3 WIDGET_ITEM_DRAW_BACKGROUND

The skinning routine should draw the background.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.

 © 2020 SEGGER Microcontroller GmbH

Data type	Element	Description
int	ItemIndex	Index of the according item (≥ 0) or -1.
int	x0	Leftmost coordinate of the item area in window coordinates.
int	y0	Topmost coordinate of the item area in window coordinates.
int	x1	Rightmost coordinate of the item area in window coordinates.
int	y1	Bottommost coordinate of the item area in window coordinates.

Additional information

This message is sent once per each item of the MENU widget. In case a horizontal MENU widget is not completely covered by items, WIDGET_ITEM_DRAW_BACKGROUND is sent one more time with ItemIndex = -1 and the coordinates of the unused area right of the last item.

23.13.4.4 WIDGET_ITEM_DRAW_FRAME

The skinning routine should draw the surrounding frame.

Elements of structure WIDGET_ITEM_DRAW_INFO

See *WIDGET_ITEM_DRAW_ARROW* on page 2339.

23.13.4.5 WIDGET_ITEM_DRAW_TEXT

The skinning routine should draw the text.

Elements of structure WIDGET_ITEM_DRAW_INFO

See *WIDGET_ITEM_DRAW_ARROW* on page 2339.

 © 2020 SEGGER Microcontroller GmbH

23.14 MULTIPAGE_SKIN_FLEX

The following picture shows the details of the skin:



The MULTIPAGE skin consists of the tabs which are drawn using a frame and 2 horizontal gradients as background. The according text is displayed on top of the background:

Detail	Description
A	Background color for selected items.
B	Top color of top gradient.
C	Bottom color of top gradient.
D	Top color of bottom gradient.
E	Bottom color of bottom gradient.
F	Frame color.
G	Text color.

23.14.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type `MULTIPAGE_SKINFLEX_PROPS` are used:

Elements of structure MULTIPAGE_SKINFLEX_PROPS

Data type	Element	Description
`U32`	`BkColor`	Background color for selected items.
`U32`	`aBkUpper[2]`	[0] - Top color of top gradient. [1] - Bottom color of top gradient.
`U32`	`aBkLower[2]`	[0] - Top color of bottom gradient. [1] - Bottom color of bottom gradient.
`U32`	`FrameColor`	Frame color.
`U32`	`TextColor`	Text color.

 © 2020 SEGGER Microcontroller GmbH

23.14.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in GUIConf.h. The following table shows the available configuration options:

Macro	Description
MULTIPAGE_SKINPROPS_ENABLED	Defines the default attributes for drawing enabled tabs.
MULTIPAGE_SKINPROPS_SELECTED	Defines the default attributes for drawing selected tabs.
MULTIPAGE_SKINPROPS_DISABLED	Defines the default attributes for drawing disabled tabs.

23.14.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
MULTIPAGE_DrawSkinFlex()	Skinning callback function of MULTIPAGE_SKIN_FLEX. (Explained at the beginning of the chapter)
MULTIPAGE_GetSkinFlexProps()	Returns the properties of the given MULTIPAGE skin. (Explained at the beginning of the chapter)
MULTIPAGE_SetDefaultSkin()	Sets the default skin used for new MULTIPAGE widgets. (Explained at the beginning of the chapter)
MULTIPAGE_SetDefaultSkinClassic()	Sets the classical design as default for new MULTIPAGE widgets. (Explained at the beginning of the chapter)
MULTIPAGE_SetSkin()	Sets a skin for the given MULTIPAGE widget. (Explained at the beginning of the chapter)
MULTIPAGE_SetSkinClassic()	Sets the classical design for the given MULTIPAGE widget. (Explained at the beginning of the chapter)
MULTIPAGE_SetSkinFlexProps()	The function can be used to change the colors of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.14.3.1 MULTIPAGE_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change the colors of the skin.

Prototype

```
void MULTIPAGE_SetSkinFlexProps(const MULTIPAGE_SKINFLEX_PROPS * pProps,
                                int                            Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type MULTIPAGE_SKINFLEX_PROPS.
Index	See table below.

Permitted values for parameter Index	
MULTIPAGE_SKINFLEX_PI_ENABLED	Properties for enabled state.
MULTIPAGE_SKINFLEX_PI_SELECTED	Properties for selected state.
MULTIPAGE_SKINFLEX_PI_DISABLED	Properties for disabled state.

Additional information

The function passes a pointer to a MULTIPAGE_SKINFLEX_PROPS structure. It can be used to set up the colors of the skin. The function *MULTIPAGE_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.14.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the MULTIPAGE_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_BACKGROUND	The skinning function should draw the background.
WIDGET_ITEM_DRAW_FRAME	The skinning function should draw the frame.
WIDGET_ITEM_DRAW_TEXT	The skinning function should draw the text.

All commands make use of the WIDGET_ITEM_DRAW_INFO structure, which contains the required information to draw the widget using a skin.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of the item to display.
int	x0	Leftmost coordinate of the client area/current tab in window coordinates.
int	y0	Topmost coordinate of the client area/current tab in window coordinates.
int	x1	Rightmost coordinate of the client area/current tab in window coordinates.
int	y1	Bottommost coordinate of the client area/current tab in window coordinates.
void *	p	Pointer to a MULTIPAGE_SKIN_INFO structure.

Elements of structure MULTIPAGE_SKIN_INFO

Data type	Element	Description
GUI_ROTATION *	pRotation	GUI_ROTATE_0, if the MULTIPAGE widget is horizontal. GUI_ROTATE_CW, if the MULTIPAGE widget is vertical.
unsigned	Align	Current alignment of the MULTIPAGE widget. Contains an or-combination of the bit definitions listed below.
int	Sel	Index of the currently selected item. This helps to determine if the currently processed item is selected and therefore might require to be drawn in a different way.
U16	State	Current state of the MULTIPAGE widget. See table below.
U8	FrameFlags	Determines which lines of the frame need to be drawn using an or-combination of the bit definitions listed below.
U8	PageStatus	State of the current page.

Possible bits set in the element Align	
MULTIPAGE_ALIGN_RIGHT	If set, items must be aligned to the right. Otherwise items must be aligned to the left.

 © 2020 SEGGER Microcontroller GmbH

MULTIPAGE_ALIGN_BOTTOM	If set, items must be aligned to the bottom. Otherwise items must be aligned to the left.

Possible bits set in the element State	
WIDGET_STATE_VERTICAL	If set, items must be drawn in vertical order. Otherwise items must be drawn in horizontal order.

Possible bits set in the element FrameFlags	
MULTIPAGE_SKIN_FRAME_TOP	If set, the top line of the frame needs to be drawn.
MULTIPAGE_SKIN_FRAME_BOTTOM	If set, the bottom line of the frame needs to be drawn.
MULTIPAGE_SKIN_FRAME_LEFT	If set, the left line of the frame needs to be drawn.
MULTIPAGE_SKIN_FRAME_RIGHT	If set, the right line of the frame needs to be drawn.

Possible bits set in the element PageStatus	
MULTIPAGE_STATE_ENABLED	If set, items must be drawn in vertical order. Otherwise items must be drawn in horizontal order.

23.14.4.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.14.4.2 WIDGET_ITEM_DRAW_BACKGROUND

The skinning routine should draw the background of the given tab.

23.14.4.3 WIDGET_ITEM_DRAW_FRAME

The skinning routine should draw the surrounding frame. In case ItemIndex is given with -1 the frame of the client window has to be drawn. In case of ItemIndex ≥ 0, a single tab should be drawn. The coordinates in the WIDGET_ITEM_DRAW_INFO structure are set according to the ItemIndex.

23.14.4.4 WIDGET_ITEM_DRAW_TEXT

The skinning routine should draw the text.

 © 2020 SEGGER Microcontroller GmbH

23.15 PROGBAR_SKIN_FLEX

The following picture shows the details of the skin:



The PROGBAR skin consists of a bar with a thin border. The background is drawn by 4 gradients, a top and a bottom gradient at the left and at the right side and a text which shows the current state per default:

Detail	Description
A	Top color of top left gradient.
B	Bottom color of top left gradient.
C	Top color of bottom left gradient.
D	Bottom color of bottom left gradient.
E	Top color of top right gradient.
F	Bottom color of top right gradient.
G	Top color of bottom right gradient.
H	Bottom color of bottom right gradient.
I	Color of frame.
T	Text (optional).

23.15.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type PROGBAR_SKINFLEX_PROPS are used:

Elements of structure PROGBAR_SKINFLEX_PROPS

Data type	Element	Description
U32	aColorUpperL[2]	[0] - Top color of top gradient. [1] - Bottom color of top gradient.
U32	aColorLowerL[2]	[0] - Top color of bottom gradient. [1] - Bottom color of bottom gradient.
U32	aColorUpperR[2]	[0] - Top color of top gradient. [1] - Bottom color of top gradient.
U32	aColorLowerR[2]	[0] - Top color of bottom gradient. [1] - Bottom color of bottom gradient.
U32	ColorFrame	Color of frame.
U32	ColorText	Color of text.

 © 2020 SEGGER Microcontroller GmbH

23.15.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in GUIConf.h. The following table shows the available configuration options:

Macro	Description
PROGBAR_SKINPROPS	Defines the default attributes used for drawing the skin.

23.15.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
PROGBAR_DrawSkinFlex()	Skinning callback function of PROGBAR_SKIN_FLEX. (Explained at the beginning of the chapter)
PROGBAR_GetSkinFlexProps()	Returns the properties of the given PROGBAR skin. (Explained at the beginning of the chapter)
PROGBAR_SetDefaultSkin()	Sets the default skin used for new PROGBAR widgets. (Explained at the beginning of the chapter)
PROGBAR_SetDefaultSkinClassic()	Sets the classical design as default for new PROGBAR widgets. (Explained at the beginning of the chapter)
PROGBAR_SetSkin()	Sets a skin for the given PROGBAR widget. (Explained at the beginning of the chapter)
PROGBAR_SetSkinClassic()	Sets the classical design for the given PROGBAR widget. (Explained at the beginning of the chapter)
PROGBAR_SetSkinFlexProps()	The function can be used to change the colors of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.15.3.1 PROGBAR_SetSkinFlexProps()

Before	After
	

Additional information

The function passes a pointer to a PROGBAR_SKINFLEX_PROPS structure. It can be used to set up the colors of the skin. The function *PROGBAR_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.15.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the PROGBAR_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_BACKGROUND	The skinning function should draw the background.
WIDGET_ITEM_DRAW_FRAME	The skinning function should draw the frame.
WIDGET_ITEM_DRAW_TEXT	The skinning function should draw the text.

23.15.4.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.15.4.2 WIDGET_ITEM_DRAW_BACKGROUND

The skinning routine should draw the background.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Is always 0.
int	x0	Leftmost coordinate of widget area in window coordinates.
int	y0	Topmost coordinate of widget area in window coordinates.
int	x1	Rightmost coordinate of widget area in window coordinates.
int	y1	Bottommost coordinate of widget area in window coordinates.
void *	p	Pointer to a PROGBAR_SKINFLEX_INFO structure.

Elements of structure PROGBAR_SKINFLEX_INFO

Data type	Element	Description
int	IsVertical	0 if the progress bar is horizontal, 1 if it is vertical.
int	Index	See table below.
const char *	pText	Pointer to the text to be drawn.

Permitted values for element Index	
PROGBAR_SKINFLEX_L	Horizontal progress bar: The left part should be drawn. Vertical progress bar: The top part should be drawn.
PROGBAR_SKINFLEX_R	Horizontal progress bar: The right part should be drawn. Vertical progress bar: The bottom part should be drawn.

Additional information

The message is sent twice, once for the left/top part and once for the right/bottom part of the progress bar. The information in the PROGBAR_SKINFLEX_INFO structure pointed by element p of the WIDGET_ITEM_DRAW_INFO structure can be used to get the information what

 © 2020 SEGGER Microcontroller GmbH

exactly should be drawn. The parameters x0, y0, x1 and y1 of the WIDGET_ITEM_DRAW_INFO structure mark only the area which should be drawn, left/right or top/bottom.

23.15.4.3 WIDGET_ITEM_DRAW_FRAME

The skinning routine should draw the surrounding frame.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Is always 0.
int	x0	Leftmost coordinate of widget area in window coordinates.
int	y0	Topmost coordinate of widget area in window coordinates.
int	x1	Rightmost coordinate of widget area in window coordinates.
int	y1	Bottommost coordinate of widget area in window coordinates.

23.15.4.4 WIDGET_ITEM_DRAW_TEXT

The skinning routine should draw the text.

Elements of structure WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_FRAME* on page 2350.

 © 2020 SEGGER Microcontroller GmbH

23.16 RADIO_SKIN_FLEX

The following picture shows the details of the skin:



The RADIO skin consists of a configurable button and a text for each item. If the widget has the input focus the currently selected item text is surrounded by a focus rectangle:

Detail	Description
A	Outer color of button frame.
B	Middle color of button frame.
C	Inner color of button frame.
D	Inner color of button.
F	Focus rectangle.
S	Size of button.
T	Item text.

23.16.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type `RADIO_SKINFLEX_PROPS` are used:

Elements of structure RADIO_SKINFLEX_PROPS

Data type	Element	Description
`U32`	`aColorButton[4]`	[0] - Outer color of button frame. [1] - Middle color of button frame. [2] - Inner color of button frame. [3] - Inner color of button.
`int`	`ButtonSize`	Size of the button in pixels. Only even values are allowed. If an odd value is entered, the value will be reduced by 1.

 © 2020 SEGGER Microcontroller GmbH

23.16.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in GUIConf.h. The following table shows the available configuration options:

Macro	Description
RADIO_SKINPROPS_CHECKED	Defines the default attributes used for checked state.
RADIO_SKINPROPS_UNCHECKED	Defines the default attributes used for unchecked state.

23.16.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
RADIO_DrawSkinFlex()	Skinning callback function of RADIO_SKIN_FLEX. (Explained at the beginning of the chapter)
RADIO_GetSkinFlexProps()	Returns the properties of the given RADIO skin. (Explained at the beginning of the chapter)
RADIO_SetDefaultSkin()	Sets the default skin used for new RADIO widgets. (Explained at the beginning of the chapter)
RADIO_SetDefaultSkinClassic()	Sets the classical design as default for new RADIO widgets. (Explained at the beginning of the chapter)
RADIO_SetSkin()	Sets a skin for the given RADIO widget. (Explained at the beginning of the chapter)
RADIO_SetSkinClassic()	Sets the classical design for the given RADIO widget. (Explained at the beginning of the chapter)
RADIO_SetSkinFlexProps()	The function can be used to change the colors of the skin and the size of the button.

 © 2020 SEGGER Microcontroller GmbH

23.16.3.1 RADIO_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change the colors of the skin and the size of the button.

Prototype

```
void RADIO_SetSkinFlexProps(const RADIO_SKINFLEX_PROPS * pProps,
                            int                          Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type RADIO_SKINFLEX_PROPS.
Index	Should be 0.

Additional information

The function passes a pointer to a RADIO_SKINFLEX_PROPS structure. It can be used to set up the colors and the button size of the skin. The function *RADIO_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.16.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the RADIO_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_BUTTON	The skinning function should draw the button of one item.
WIDGET_ITEM_DRAW_FOCUS	The skinning function should draw the focus rectangle.
WIDGET_ITEM_DRAW_TEXT	The skinning function should draw the text of one item.
WIDGET_ITEM_GET_BUTTONSIZE	The skinning function should return the button size.

WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

WIDGET_ITEM_DRAW_BUTTON

The skinning routine should draw the button of one item.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the button area in window coordinates.
int	y0	Topmost coordinate of the button area in window coordinates.
int	x1	Rightmost coordinate of the button area in window coordinates.
int	y1	Bottommost coordinate of the button area in window coordinates.

23.16.4.1 WIDGET_ITEM_DRAW_FOCUS

The skinning routine should draw the focus rectangle around the text of the currently selected item.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the focus rectangle in window coordinates.
int	y0	Topmost coordinate of the focus rectangle in window coordinates.
int	x1	Rightmost coordinate of the focus rectangle in window coordinates.

 © 2020 SEGGER Microcontroller GmbH

Data type	Element	Description
int	y1	Bottommost coordinate of the focus rectangle in window coordinates.

Additional information

The given rectangular area in x0, y0, x1 and y1 considers the font settings and the item text.

23.16.4.2 WIDGET_ITEM_DRAW_TEXT

The skinning routine should draw the text of one item.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the text area in window coordinates.
int	y0	Topmost coordinate of the text area in window coordinates.
int	x1	Rightmost coordinate of the text area in window coordinates.
int	y1	Bottommost coordinate of the text area in window coordinates.

Additional information

The given rectangular area in x0, y0, x1 and y1 considers the font settings and the item text.

23.16.4.3 WIDGET_ITEM_GET_BUTTONSIZE

The skinning routine should return the button size.

 © 2020 SEGGER Microcontroller GmbH

23.17 SCROLLBAR_SKIN_FLEX



The SCROLLBAR skin consists of a left and a right button with an arrow, a shaft area and a thumb with a grasp:

Detail	Description
A	Top color of top gradient.
B	Bottom color of top gradient.
C	Top color of bottom gradient.
D	Bottom color of bottom gradient.
E	Top color of shaft gradient.
F	Bottom color of shaft gradient.
G	Grasp of thumb area.
H	Button arrow.
I	Outer frame color.
J	Inner frame color.
K	Color of frame edges.
L	Left button.
T	Thumb area.
R	Right button.
S	Shaft area.

23.17.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type SCROLLBAR_SKINFLEX_PROPS are used:

Elements of structure SCROLLBAR_SKINFLEX_PROPS

Data type	Element	Description
U32	aColorFrame[3]	[0] - Outer frame color. [1] - Inner frame color. [2] - Color of frame edges
U32	aColorUpper[2]	[0] - Top color of top gradient. [1] - Bottom color of top gradient.
U32	aColorLower[2]	[0] - Top color of bottom gradient. [1] - Bottom color of bottom gradient.
U32	aColorShaft[2]	[0] - Top color of shaft gradient. [1] - Bottom color of shaft gradient.
U32	ColorArrow	Color of button arrow.
U32	ColorGrasp	Color of grasp.

 © 2020 SEGGER Microcontroller GmbH

23.17.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in GUIConf.h. The following table shows the available configuration options:

Macro	Description
SCROLLBAR_SKINPROPS_PRESSED	Defines the default attributes used for pressed state.
SCROLLBAR_SKINPROPS_UNPRESSED	Defines the default attributes used for unpressed state.

23.17.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
SCROLLBAR_DrawSkinFlex()	Skinning callback function of SCROLLBAR_SKIN_FLEX. (Explained at the beginning of the chapter)
SCROLLBAR_GetSkinFlexProps()	Returns the properties of the given SCROLLBAR skin. (Explained at the beginning of the chapter)
SCROLLBAR_SetDefaultSkin()	Sets the default skin used for new SCROLLBAR widgets. (Explained at the beginning of the chapter)
SCROLLBAR_SetDefaultSkinClassic()	Sets the classical design as default for new SCROLLBAR widgets. (Explained at the beginning of the chapter)
SCROLLBAR_SetSkin()	Sets a skin for the given SCROLLBAR widget. (Explained at the beginning of the chapter)
SCROLLBAR_SetSkinClassic()	Sets the classical design for the given SCROLLBAR widget. (Explained at the beginning of the chapter)
SCROLLBAR_SetSkinFlexProps()	The function can be used to change the colors of the skin and the size of the button.

 © 2020 SEGGER Microcontroller GmbH

23.17.3.1 SCROLLBAR_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change the colors of the skin and the size of the button.

Prototype

```
void SCROLLBAR_SetSkinFlexProps(const SCROLLBAR_SKINFLEX_PROPS * pProps,
                                int                            Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type SCROLLBAR_SKINFLEX_PROPS.
Index	Should be 0.

Permitted values for parameter Index	
SCROLLBAR_SKINFLEX_PI_PRESSED	Properties for pressed state.
SCROLLBAR_SKINFLEX_PI_UNPRESSED	Properties for unpressed state.

Additional information

The function passes a pointer to a SCROLLBAR_SKINFLEX_PROPS structure. It can be used to set up the colors of the skin. The function *SCROLLBAR_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.17.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the SCROLLBAR_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_BUTTON_L	The skinning function should draw the left button.
WIDGET_ITEM_DRAW_BUTTON_R	The skinning function should draw the right button.
WIDGET_ITEM_DRAW_OVERLAP	The skinning function should draw the overlapping area.
WIDGET_ITEM_DRAW_SHAFT_L	The skinning function should draw the left part of the shaft.
WIDGET_ITEM_DRAW_SHAFT_R	The skinning function should draw the right part of the shaft.
WIDGET_ITEM_DRAW_THUMB	The skinning function should draw the thumb.
WIDGET_ITEM_GET_BUTTONSIZE	The skinning function should return the button size.

23.17.4.1 WIDGET_ITEM_DRAW_BUTTON_L

23.17.4.2 WIDGET_ITEM_DRAW_BUTTON_R

The skinning routine should draw a button.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the button in window coordinates.
int	y0	Topmost coordinate of the button in window coordinates.
int	x1	Rightmost coordinate of the button in window coordinates.
int	y1	Bottommost coordinate of the button in window coordinates.
void *	p	Pointer to a SCROLLBAR_SKINFLEX_INFO structure.

Elements of structure SCROLLBAR_SKINFLEX_INFO

Datatype	Element	Description
int	IsVertical	0 if the progress bar is horizontal, 1 if it is vertical.
int	State	See table below.

Permitted values for element State	
PRESSED_STATE_NONE	Nothing is pressed.
PRESSED_STATE_RIGHT	The right button is pressed.
PRESSED_STATE_LEFT	The left button is pressed.
PRESSED_STATE_THUMB	The thumb is pressed.

 © 2020 SEGGER Microcontroller GmbH

23.17.4.3 WIDGET_ITEM_DRAW_OVERLAP

The skinning routine should draw the thumb.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the overlapping area in window coordinates.
int	y0	Topmost coordinate of the overlapping area in window coordinates.
int	x1	Rightmost coordinate of the overlapping area in window coordinates.
int	y1	Bottommost coordinate of the overlapping area in window coordinates.

Additional information

An overlapping area can exist if a dialog has a vertical and a horizontal scroll bar at the borders. Normally the overlapping region looks identical to the shaft area.

Example

The following screenshot shows a window with 2 scroll bars which have an overlapping region at the lower right corner of the client window:



23.17.4.4 WIDGET_ITEM_DRAW_SHAFT_L

23.17.4.5 WIDGET_ITEM_DRAW_SHAFT_R

The skinning routine should draw a shaft area.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the shaft area in window coordinates.
int	y0	Topmost coordinate of the shaft area in window coordinates.
int	x1	Rightmost coordinate of the shaft area in window coordinates.
int	y1	Bottommost coordinate of the shaft area in window coordinates.

 © 2020 SEGGER Microcontroller GmbH

23.17.4.6 WIDGET_ITEM_DRAW_THUMB

The skinning routine should draw the thumb.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the thumb area in window coordinates.
int	y0	Topmost coordinate of the thumb area in window coordinates.
int	x1	Rightmost coordinate of the thumb area in window coordinates.
int	y1	Bottommost coordinate of the thumb area in window coordinates.
void *	p	Pointer to a SCROLLBAR_SKINFLEX_INFO structure.

SCROLLBAR_SKINFLEX_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BUTTON_L* on page 2359.

23.17.4.7 WIDGET_ITEM_GET_BUTTONSIZE

The skinning routine should return the button size. The button size means the following:

- A horizontal scroll bar should return the height of the scroll bar.
- A vertical scroll bar should return the width of the scroll bar.

Example

The following code can be used to return the right values in most cases:

```
int _SkinningCallback(const WIDGET_ITEM_DRAW_INFO * pDrawItemInfo) {
  SCROLLBAR_SKINFLEX_INFO * pSkinInfo;
  pSkinInfo = (SCROLLBAR_SKINFLEX_INFO *)pDrawItemInfo->p;
  switch (pDrawItemInfo->Cmd) {
  case WIDGET_ITEM_GET_BUTTONSIZE:
    return (pSkinInfo->IsVertical) ?
  pDrawItemInfo->x1 - pDrawItemInfo->x0 + 1 :
  pDrawItemInfo->y1 - pDrawItemInfo->y0 + 1;
  ...
 }
}
```

 © 2020 SEGGER Microcontroller GmbH

23.18 SLIDER_SKIN_FLEX

The following picture shows the details of the skin:



The SLIDER skin consists of a shaft with slider and tick marks above. Further a focus rectangle is shown if the widget has the input focus. The slider is drawn by a frame and a gradient:

Detail	Description
A	Outer color of slider frame.
B	Inner color of slider frame
C	Top color of gradient.
D	Bottom color of gradient.
E	First color of shaft.
F	Second color of shaft.
G	Third color of shaft.
H	Focus rectangle.
I	Tick marks.
J	Size of a tick mark.
K	Size of the shaft.

23.18.1 Configuration structure

To set up the default appearance of the skin or to change it at run time configuration structures of type `SLIDER_SKINFLEX_PROPS` are used:

Elements of structure SLIDER_SKINFLEX_PROPS

Data type	Element	Description
`U32`	`aColorFrame[2]`	[0] - Outer frame color. [1] - Inner frame color.
`U32`	`aColorInner[2]`	[0] - Top color of gradient. [1] - Bottom color of gradient.
`U32`	`aColorShaft[3]`	[0] - First frame color of shaft. [1] - Second frame color of shaft. [2] - Inner color of shaft.
`U32`	`ColorTick`	Color of tick marks.
`U32`	`ColorFocus`	Color of focus rectangle.
`int`	`TickSize`	Size of tick marks.

 © 2020 SEGGER Microcontroller GmbH

Data type	Element	Description
int	ShaftSize	Size of shaft.

23.18.2 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in GUIConf.h. The following table shows the available configuration options:

Macro	Description
SLIDER_SKINPROPS_PRESSED	Defines the default attributes used for pressed state.
SLIDER_SKINPROPS_UNPRESSED	Defines the default attributes used for unpressed state.

23.18.3 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
SLIDER_DrawSkinFlex()	Skinning callback function of SLIDER_SKIN_FLEX. (Explained at the beginning of the chapter)
SLIDER_GetSkinFlexProps()	Returns the properties of the given SLIDER skin. (Explained at the beginning of the chapter)
SLIDER_SetDefaultSkin()	Sets the default skin used for new SLIDER widgets. (Explained at the beginning of the chapter)
SLIDER_SetDefaultSkinClassic()	Sets the classical design as default for new SLIDER widgets. (Explained at the beginning of the chapter)
SLIDER_SetSkin()	Sets a skin for the given SLIDER widget. (Explained at the beginning of the chapter)
SLIDER_SetSkinClassic()	Sets the classical design for the given SLIDER widget. (Explained at the beginning of the chapter)
SLIDER_SetSkinFlexProps()	The function can be used to change colors, tick mark and shaft size of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.18.3.1 SLIDER_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change colors, tick mark and shaft size of the skin.

Prototype

```
void SLIDER_SetSkinFlexProps(const SLIDER_SKINFLEX_PROPS * pProps,
                             int                         Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type SLIDER_SKINFLEX_PROPS.
Index	Should be 0.

Permitted values for parameter Index	
SLIDER_SKINFLEX_PI_PRESSED	Properties for pressed state.
SLIDER_SKINFLEX_PI_UNPRESSED	Properties for unpressed state.

Additional information

The function passes a pointer to a SLIDER_SKINFLEX_PROPS structure. It can be used to set up the colors of the skin. The function *SLIDER_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.18.4 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the SLIDER_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_FOCUS	The skinning function should draw the focus rectangle.
WIDGET_ITEM_DRAW_SHAFT	The skinning function should draw the shaft.
WIDGET_ITEM_DRAW_THUMB	The skinning function should draw the slider.
WIDGET_ITEM_DRAW_TICKS	The skinning function should draw the tick marks.

23.18.4.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.18.4.2 WIDGET_ITEM_DRAW_FOCUS

The skinning routine should draw the focus rectangle.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the widget in window coordinates.
int	y0	Topmost coordinate of the widget in window coordinates.
int	x1	Rightmost coordinate of the widget in window coordinates.
int	y1	Bottommost coordinate of the widget in window coordinates.

23.18.4.3 WIDGET_ITEM_DRAW_SHAFT

The skinning routine should draw the shaft.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the widget + 1 in window coordinates.
int	y0	Topmost coordinate of the widget + 1 in window coordinates.
int	x1	Rightmost coordinate of the widget - 1 in window coordinates.
int	y1	Bottommost coordinate of the widget - 1 in window coordinates.

 © 2020 SEGGER Microcontroller GmbH

23.18.4.4 WIDGET_ITEM_DRAW_THUMB

The skinning routine should draw the slider itself.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the slider in window coordinates.
int	y0	Topmost coordinate of the slider in window coordinates.
int	x1	Rightmost coordinate of the slider in window coordinates.
int	y1	Bottommost coordinate of the slider in window coordinates.
void *	p	Pointer to a SLIDER_SKINFLEX_INFO structure.

Elements of structure SLIDER_SKINFLEX_INFO

Data type	Element	Description
int	Width	Width of the slider.
int	IsPressed	1 if the slider is pressed, 0 if not.
int	IsVertical	0 if the slider is horizontal, 1 if it is vertical.

23.18.4.5 WIDGET_ITEM_DRAW_TICKS

The skinning routine should draw the tick marks.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	Index of item to be drawn.
int	x0	Leftmost coordinate of the widget + 1 in window coordinates.
int	y0	Topmost coordinate of the widget + 1 in window coordinates.
int	x1	Rightmost coordinate of the widget - 1 in window coordinates.
int	y1	Bottommost coordinate of the widget - 1 in window coordinates.
void *	p	Pointer to a SLIDER_SKINFLEX_INFO structure.

Elements of structure SLIDER_SKINFLEX_INFO

Data type	Element	Description
int	Width	With of the slider.
int	NumTicks	Number of ticks to be drawn.
int	Size	Length of the tick mark line.
int	IsPressed	1 if the slider is pressed, 0 if not.
int	IsVertical	0 if the slider is horizontal, 1 if it is vertical.

 © 2020 SEGGER Microcontroller GmbH

23.19 SPINBOX_SKIN_FLEX

The following picture shows the details of the skin:



The SPINBOX skin consists of a rounded border and 2 rectangular inner areas which are drawn in dependence of the size of the EDIT widget. The background color of the EDIT widget is set to the set color of the inner area of the SPINBOX widget. The 2 buttons are drawn each with a gradient of 2 colors.

Detail	Description
A	Outer color of surrounding frame.
B	Inner color of surrounding frame.
C	Color of the displayed value.
D	Color of the text cursor (always inverse).
E	Color of the button frame.
F	2 color gradient of the upper button.
G	Arrow color.
H	2 color gradient of the lower button.
I	Background color.

Configuration structure

To set up the default appearance of the skin or to change it at run time, configuration structures of type `SPINBOX_SKINFLEX_PROPS` are used:

Elements of structure SPINBOX_SKINFLEX_PROPS

Data type	Element	Description
`GUI_COLOR`	`aColorFrame[2]`	[0] - Outer color of the surrounding frame. [1] - Inner color of the surrounding frame.
`GUI_COLOR`	`aColorUpper[2]`	[0] - Upper gradient color of the upper button. [1] - Lower gradient color of the upper button.
`GUI_COLOR`	`aColorLower[2]`	[0] - Upper gradient color of the lower button. [1] - Lower gradient color of the lower button.
`GUI_COLOR`	`ColorArrow`	Color of the button arrows.
`GUI_COLOR`	`ColorBk`	Color of the background.

 © 2020 SEGGER Microcontroller GmbH

Data type	Element	Description
GUI_COLOR	ColorText	Color of the text.
GUI_COLOR	ColorButtonFrame	Color of the button frame.

23.19.1 Configuration options

The default appearance of the skin can be determined by setting custom configuration structures of the above type in GUIConf.h. The following table shows the available configuration options:

Macro	Description
SPINBOX_SKINPROPS_PRESSED	Defines the default attributes used for pressed state.
SPINBOX_SKINPROPS_FOCUSED	Defines the default attributes used for focused state.
SPINBOX_SKINPROPS_ENABLED	Defines the default attributes used for enabled state.
SPINBOX_SKINPROPS_DISABLED	Defines the default attributes used for disabled state.

23.19.2 Skinning API

The table below lists the available routines in alphabetical order:

Routine	Description
SPINBOX_DrawSkinFlex()	Skinning callback function of SPINBOX_SKIN_FLEX. (Explained at the beginning of the chapter)
SPINBOX_GetSkinFlexProps()	Returns the properties of the given spinbox skin. (Explained at the beginning of the chapter)
SPINBOX_SetDefaultSkin()	Sets the default skin used for new spinbox widgets. (Explained at the beginning of the chapter)
SPINBOX_SetDefaultSkinClassic()	Sets the classical design as default for new spinbox widgets. (Explained at the beginning of the chapter)
SPINBOX_SetSkin()	Sets a skin for the given spinbox widget. (Explained at the beginning of the chapter)
SPINBOX_SetSkinClassic()	Sets the classical design for the given spinbox widget. (Explained at the beginning of the chapter)
SPINBOX_SetSkinFlexProps()	The function can be used to change the properties of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.19.2.1 SPINBOX_SetSkinFlexProps()

Before	After
	

Description

The function can be used to change the properties of the skin.

Prototype

```
void SPINBOX_SetSkinFlexProps(const SPINBOX_SKINFLEX_PROPS * pProps,
                              int                            Index);
```

Parameters

Parameter	Description
pProps	Pointer to a structure of type SPINBOX_SKINFLEX_PROPS.
Index	Should be 0.

Permitted values for parameter Index	
SPINBOX_SKINFLEX_PI_PRESSED	Properties for pressed state.
SPINBOX_SKINFLEX_PI_FOCUSED	Properties for focused state.
SPINBOX_SKINFLEX_PI_ENABLED	Properties for enabled state.
SPINBOX_SKINFLEX_PI_DISABLED	Properties for disabled state.

Additional information

The function passes a pointer to a SPINBOX_SKINFLEX_PROPS structure. It can be used to set up the colors and the radius of the skin. The function *SPINBOX_GetSkinFlexProps()* can be used to get the current attributes of the skin.

 © 2020 SEGGER Microcontroller GmbH

23.19.3 List of commands

The skinning routine receives a pointer to a WIDGET_ITEM_DRAW_INFO structure. The Cmd member of this structure contains the command which needs to be processed. The following table shows all commands passed to the SPINBOX_SKIN_FLEX callback function:

Command	Description
WIDGET_ITEM_CREATE	Is sent immediately after creating the widget.
WIDGET_ITEM_DRAW_BACKGROUND	The skinning function should draw the background.
WIDGET_ITEM_DRAW_BUTTON_U	The skinning function should draw the upper button.
WIDGET_ITEM_DRAW_BUTTON_D	The skinning function should draw the lower button.
WIDGET_ITEM_DRAW_FRAME	The skinning function should draw the surrounding frame.

The WIDGET_ITEM_DRAW_INFO structure is explained at the beginning of the chapter.

23.19.3.1 WIDGET_ITEM_CREATE

The skinning routine should, if necessary, set up skin related properties like e.g. transparency or text alignment.

23.19.3.2 WIDGET_ITEM_DRAW_BACKGROUND

The background should be drawn.

Elements of structure WIDGET_ITEM_DRAW_INFO

Data type	Element	Description
WM_HWIN	hWin	Handle to the widget.
int	ItemIndex	See table below.
int	x0	Leftmost window coordinate, normally 0.
int	y0	Topmost window coordinate, normally 0.
int	x1	Rightmost window coordinate.
int	y1	Bottommost window coordinate.

Permitted values for element ItemIndex	
SPINBOX_SKINFLEX_PI_PRESSED	The widget is pressed.
SPINBOX_SKINFLEX_PI_FOCUSED	The widget is not pressed but focused.
SPINBOX_SKINFLEX_PI_ENABLED	The widget is not focused but enabled.
SPINBOX_SKINFLEX_PI_DISABLED	The widget is disabled.

23.19.3.3 WIDGET_ITEM_DRAW_BUTTON_U

The upper button should be drawn.

WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2370.

23.19.3.4 WIDGET_ITEM_DRAW_BUTTON_D

The lower button should be drawn.

 © 2020 SEGGER Microcontroller GmbH

WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2370.

WIDGET_ITEM_DRAW_FRAME

The surrounding frame should be drawn.

WIDGET_ITEM_DRAW_INFO

A detailed description of the elements can be found under *WIDGET_ITEM_DRAW_BACKGROUND* on page 2370.

 © 2020 SEGGER Microcontroller GmbH

Chapter 24

Multiple Buffering

Multiple Buffering is a method of using more than one frame buffer. Basically it works as follows: With multiple buffers enabled there is a front buffer which is used by the display controller to generate the picture on the screen and one or more back buffers which are used for the drawing operations. After completing the drawing operations the back buffer becomes the visible front buffer.

With two buffers, one front and one back buffer, it is normally called “double buffering”, with two back buffers and one front buffer it is called “triple buffering”.

In general it is a method which is able to avoid several unwanted effects:

- The visible process of drawing a screen item by item
- Flickering effects caused by overlapping drawing operations
- Tearing effects caused by writing operations outside the vertical blanking period

The following section explains in detail how it works, the requirements to be able to use this feature, how to configure emWin and the advantage of “triple buffering” against “double buffering”. Further it explains how to configure the optional Window Manager for automatic use of Multiple Buffering.

 © 2020 SEGGER Microcontroller GmbH

24.1 How it works

Multiple Buffering is the use of more than one frame buffer, so that the display ever shows a screen which is already completely rendered, even if a drawing operation is in process. When starting the process of drawing the current content of the front buffer is copied into a back buffer. After that all drawing operations take effect only on this back buffer. After the drawing operation has been completed the back buffer becomes the front buffer. Making the back buffer the visible front buffer normally only requires the modification of the frame buffer start address register of the display controller.
Now it should be considered that a display is being refreshed continuously by the display controller approximately 60 times per second. After each period there is a vertical synchronization signal, normally known as VSYNC signal. The best moment to make the back buffer the new front buffer is this signal. If not considering the VSYNC signal tearing effects can occur.

Tearing effect



24.1.1 Double Buffering

With double buffering only 2 buffers are available: One front and one back buffer. When starting the drawing operation the current content of the front buffer is copied into the back buffer. After completing the operation the back buffer should become the visible front buffer. As explained above the best moment for doing this is reacting on the VSYNC signal of the display controller. Here the disadvantage of double buffering against triple buffering is revealed: Either the frame buffer start address is changed immediately at the end of the drawing operation or after waiting until the next VSYNC signal. This means that either tearing effects could occur or the performance slows down because of waiting for the next VSYNC signal.

24.1.2 Triple Buffering

As the name implies there are 3 buffers available: One front and 2 back buffers. When starting the drawing operation the current content of the front buffer is copied into the first back buffer. After completing the operation the back buffer should become the visible front buffer. Contrary to the double buffer solution it is not required to switch to the buffer immediately. Switching to the new front buffer could be done on the next VSYNC signal of the display controller which can be achieved by an interrupt service routine (ISR). Most of the display controllers which are able to deal with more than one frame buffer provide the VSYNC signal as interrupt source. Within the ISR the pending front buffer should become visible. Until the pending front buffer becomes visible it is not used for further drawing operations. If a further drawing operation is initiated before the pending front buffer has become visible the second back buffer is used for the drawing operation. If a new buffer

 © 2020 SEGGER Microcontroller GmbH

is ready until waiting for the VSYNC signal it becomes the new pending front buffer and so on. This always protects the front buffer against writing operations.
It should be mentioned that changing the display buffer start address on some display controllers only takes effect when drawing the next frame. In this case the solution without ISR works as well as with ISR. Only if changing the address takes effect directly an ISR is required to avoid tearing effects.

 © 2020 SEGGER Microcontroller GmbH

24.2 Requirements

The following list shows the requirements for using multiple buffers:

- The display controller should support multiple frame buffers.
- Enough video RAM for multiple frame buffers should be available.
- If tearing effects should be avoided it should be possible to react on the VSYNC signal of the display controller and triple buffering is recommended to achieve the best performance.

 © 2020 SEGGER Microcontroller GmbH

24.3 Limitations

Multiple Buffering can not be used with virtual screens.

 © 2020 SEGGER Microcontroller GmbH

24.4 Configuration

In general there are 2 routines in the configuration file `LCDConf.c` which need to be modified, the display configuration routine `LCD_X_Config()` and the driver callback function `LCD_X_DisplayDriver()`.

24.4.1 LCD_X_Config()

Basically one thing needs to be done here: Enabling the use of multiple buffers.

Basic configuration

The first thing which has to be done before creating the display driver device is configuring the multiple buffer interface. This is normally done in `LCD_X_Config()`. It is strictly required to enable Multiple Buffering before creating the display driver device as shown in the following code snippet:

```
void LCD_X_Config(void) {
  //
  // Initialize MultiBuffering
  //
  GUI_MULTIBUF_Config(NUM_BUFFERS);
  //
  // Set display driver and color conversion
  //
  GUI_DEVICE_CreateAndLink(DISPLAY_DRIVER, COLOR_CONVERSION, 0, 0);
  ...
}
```

Callback routine for copying the buffers

Further a callback routine for copying the buffers can be set. As explained above at the beginning of the drawing operation it is required to copy the content of the current front buffer to the back buffer. Normally a simple memcpy operation is used to do this. But if the used display controller for example consists of a BitBLT-engine which is able to do the copy operation it could be desired to use it for the copy operation. Or a DMA based routine should be used to do the copy operation. In these cases a custom defined callback function can be used for this operation. It can be installed after creating the display driver device as shown in the following code snippet:

```
static void _CopyBuffer(int LayerIndex, int IndexSrc, int IndexDst) {
  unsigned long BufferSize, AddrSrc, AddrDst;

  //
  //  Calculate the size of one frame buffer
  //
  BufferSize = (XSIZE * YSIZE * BITSPERPIXEL) / 8;
  //
  //  Calculate source- and destination address
  //
  AddrSrc  = _VRamBaseAddr + BufferSize * IndexSrc;
  AddrDst  = _VRamBaseAddr + BufferSize * IndexDst;
  memcpy((void *)AddrDst, (void *)AddrSrc, BufferSize);
}
void LCD_X_Config(void) {
  //
  // Initialize multibuffering
  //
  GUI_MULTIBUF_Config(NUM_BUFFERS);
  //
  // Set display driver and color conversion
  //
  GUI_DEVICE_CreateAndLink(DISPLAY_DRIVER, COLOR_CONVERSION, 0, 0);
  //
```

 © 2020 SEGGER Microcontroller GmbH

```
  // Set custom callback function for copy operation
  //
  LCD_SetDevFunc(0, LCD_DEVFUNC_COPYBUFFER, (void (*)())_CopyBuffer);
}
```

The above sample implementation makes no sense, because the simple call of memcpy() equals the default behavior of the display driver. It makes only sense to use a custom copy buffer function if there is any possibility to accelerate the copy operation.

Buffers in non-consecutive RAM areas

If the RAM on a device is not large enough to hold all buffers used for multiple buffering consecutively, it is possible to pass multiple RAM addresses to emWin. By calling `LCD_SetBufferPtr()` it is possible to tell emWin the addresses of every single buffer location.

```
static const U32 _aBufferPTR[] = {
  0x00000100, // Begin of On-Chip RAM
  0x00800000  // Begin of Expansion RAM
};
LCD_SetBufferPtrEx(0, (void **)_aBufferPTR);
```

24.4.2 LCD_X_DisplayDriver()

After the drawing process has been completed the back buffer should become visible. The display driver sends a `LCD_X_SHOWBUFFER` command to the display driver callback function. The callback function then has to react on the command and should make sure that the buffer becomes visible. This can be done either by an ISR or by directly writing the right address into the frame buffer start address of the display controller.

With ISR

The following code snippet shows a sample implementation:

```
static void _ISR_EndOfFrame(void) {
  unsigned long Addr, BufferSize;
  if (_PendingBuffer >= 0) {
    //
    // Calculate address of the given buffer
    //
    BufferSize = (XSIZE * YSIZE * BITSPERPIXEL) / 8;
    Addr       = _VRamBaseAddr + BufferSize * pData->Index;
    //
    // Make the given buffer visible
    //
    AT91C_LCDC_BA1 = Addr;
    //
    // Send a confirmation that the buffer is visible now
    //
    GUI_MULTIBUF_Confirm(_PendingBuffer);
    _PendingBuffer = -1;
  }
}
int LCD_X_DisplayDriver(unsigned LayerIndex, unsigned Cmd, void * p) {
  LCD_X_SHOWBUFFER_INFO * pData;
  switch (Cmd) {
  ...
  case LCD_X_SHOWBUFFER:
    pData = (LCD_X_SHOWBUFFER_INFO *)p;
    //
    // Remember buffer index to be used by ISR
    //
    _PendingBuffer = pData->Index;
    break;
  }
```

 © 2020 SEGGER Microcontroller GmbH

```
}
```

The above implementation assumes the existence of an ISR which is executed at the next VSYNC signal.

Without ISR

If there is no ISR available alternatively the address can be set directly with the disadvantage that tearing effects could occur.
The following code snippet shows a sample implementation:

```
int LCD_X_DisplayDriver(unsigned LayerIndex, unsigned Cmd, void * p) {
 LCD_X_SHOWBUFFER_INFO * pData;
 unsigned long      BufferSize;
 unsigned long      Addr;
 switch (Cmd) {
 ...
 case LCD_X_SHOWBUFFER: {
  pData = (LCD_X_SHOWBUFFER_INFO *)p;
  //
  // Calculate address of the given buffer
  //
  BufferSize = (XSIZE * YSIZE * BITSPERPIXEL) / 8;
  Addr       = _VRamBaseAddr + BufferSize * pData->Index;
  //
  // Make the given buffer visible
  //
  AT91C_LCDC_BA1 = Addr;
  //
  // Send a confirmation that the buffer is visible now
  //
  GUI_MULTIBUF_Confirm(pData->Index);
  break;
 }
}
```

 © 2020 SEGGER Microcontroller GmbH

24.5 Automatic use of multiple buffers with the WM

The optional Window Manager (WM) is able to use the multiple buffer feature automatically. The function `WM_MULTIBUF_Enable()` can be used to enable this function. If enabled the WM first switches to the back buffer before redrawing the invalid windows. After drawing all invalid windows the new screen becomes visible. This hides the process of drawing a screen window by window.

 © 2020 SEGGER Microcontroller GmbH

24.6 Multiple Buffering API

The following table lists the available routines of the multiple buffer support.

Routine	Description
GUI_MULTIBUF_Begin()	Needs to be called immediately before the drawing process.
GUI_MULTIBUF_BeginEx()	Needs to be called immediately before the drawing process in the given layer.
GUI_MULTIBUF_Config()	The function needs to be called during initialization in order to enable the use of Multiple Buffering.
GUI_MULTIBUF_ConfigEx()	The function needs to be called during initialization in order to enable the use of Multiple Buffering for the given layer.
GUI_MULTIBUF_Confirm()	This function needs to be called immediately after a new buffer has become visible.
GUI_MULTIBUF_ConfirmEx()	This function needs to be called immediately after a new buffer has become visible in the given layer.
GUI_MULTIBUF_End()	This function needs to be called after the new screen has been completely drawn.
GUI_MULTIBUF_EndEx()	This function needs to be called after the new screen has been completely drawn for the given layer.
GUI_MULTIBUF_GetNumBuffers()	The function returns the number of buffers configured.
GUI_MULTIBUF_GetNumBuffersEx()	The function returns the number of buffers configured for the given layer.
GUI_MULTIBUF_UseSingleBuffer()	Lets the multi buffering use one frame for all layers.

 © 2020 SEGGER Microcontroller GmbH

24.6.1 GUI_MULTIBUF_Begin()

Description

Needs to be called immediately before the drawing process.

Prototype

```
void GUI_MULTIBUF_Begin(void);
```

Additional information

This function makes sure that the current front buffer will be copied into the back buffer which then is used for all subsequent drawing operations. The copy operation is normally done by the display driver itself. As explained earlier this can also be achieved by a custom callback function.

 © 2020 SEGGER Microcontroller GmbH

24.6.2 GUI_MULTIBUF_BeginEx()

Description

Needs to be called immediately before the drawing process in the given layer.

Prototype

```
void GUI_MULTIBUF_BeginEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer to be used.

 © 2020 SEGGER Microcontroller GmbH

24.6.3 GUI_MULTIBUF_Config()

Description

The function needs to be called during initialization in order to enable the use of Multiple Buffering. This is done typically from within `LCD_X_Config()`.

Prototype

```
void GUI_MULTIBUF_Config(int NumBuffers);
```

Parameters

Parameter	Description
`NumBuffers`	Number of buffers to be used. The following numbers are self-explanatory: 2 - Double buffering 3 - Triple buffering

Additional information

The function needs to be called before creating the display driver device.

 © 2020 SEGGER Microcontroller GmbH

24.6.4 GUI_MULTIBUF_ConfigEx()

Description

The function needs to be called during initialization in order to enable the use of Multiple Buffering for the given layer. This is done typically from within `LCD_X_Config()`.

Prototype

```
void GUI_MULTIBUF_ConfigEx(int LayerIndex,
                           int NumBuffers);
```

Parameters

Parameter	Description
`LayerIndex`	Layer to be used.
`NumBuffers`	Number of buffers to be used. The following numbers are self-explanatory: 2 - Double buffering 3 - Triple buffering

 © 2020 SEGGER Microcontroller GmbH

24.6.5 GUI_MULTIBUF_Confirm()

Description

This function needs to be called immediately after a new buffer has become visible.

Prototype

```
void GUI_MULTIBUF_Confirm(int BufferIndex);
```

Parameters

Parameter	Description
Index	Index of buffer which has been made visible.

Additional information

The function is typically called by the ISR which switches to the new front buffer or by the display driver callback function.

 © 2020 SEGGER Microcontroller GmbH

24.6.6 GUI_MULTIBUF_ConfirmEx()

Description

This function needs to be called immediately after a new buffer has become visible in the given layer.

Prototype

```
void GUI_MULTIBUF_ConfirmEx(int LayerIndex,
                            int BufferIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer to be used.
Index	Index of buffer which has been made visible.

 © 2020 SEGGER Microcontroller GmbH

24.6.7 GUI_MULTIBUF_End()

Description

This function needs to be called after the new screen has been completely drawn.

Prototype

```
void GUI_MULTIBUF_End(void);
```

Additional information

When calling this function the display driver sends an LCD_X_SHOWBUFFER command to the display driver callback routine which then has to make the given buffer the front buffer.

 © 2020 SEGGER Microcontroller GmbH

24.6.8 GUI_MULTIBUF_EndEx()

Description

This function needs to be called after the new screen has been completely drawn for the given layer.

Prototype

```
void GUI_MULTIBUF_EndEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer to be used.

 © 2020 SEGGER Microcontroller GmbH

24.6.9 GUI_MULTIBUF_GetNumBuffers()

Description

The function returns the number of buffers configured.

Prototype

```
int GUI_MULTIBUF_GetNumBuffers(void);
```

Return value

The number of buffers configured for the current layer.

 © 2020 SEGGER Microcontroller GmbH

24.6.10 GUI_MULTIBUF_GetNumBuffersEx()

Description

The function returns the number of buffers configured for the given layer.

Prototype

```
int GUI_MULTIBUF_GetNumBuffersEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer to be used.

Return value

The number of buffers configured for the specified layer.

 © 2020 SEGGER Microcontroller GmbH

24.6.11 GUI_MULTIBUF_UseSingleBuffer()

Description

Lets the multi buffering use one frame for all layers.

Prototype

```
void GUI_MULTIBUF_UseSingleBuffer(void);
```

Additional information

The function needs to be called before creating the display driver device.

 © 2020 SEGGER Microcontroller GmbH

Chapter 25

Virtual screens / Virtual pages

A virtual screen means a display area greater than the physical size of the display. It requires additional video memory and allows instantaneous switching between different screens even on slow CPUs. The following chapter shows

- the requirements for using virtual screens,
- how to configure emWin
- and how to take advantage of virtual screens.

If a virtual display area is configured, the visible part of the display can be changed by setting the origin.

 © 2020 SEGGER Microcontroller GmbH

25.1 Introduction



The virtual screen support of emWin can be used for panning or for switching between different video pages.

Panning

If the application uses one screen which is larger than the display, the virtual screen API functions can be used to make the desired area visible.

Virtual pages

Virtual pages are a way to use the display RAM as multiple pages. If an application for example needs 3 different screens, each screen can use its own page in the display RAM. In this case, the application can draw the second and the third page before they are used. After that the application can switch very fast between the different pages using the virtual screen API functions of emWin. The only thing the functions have to do is setting the right display start address for showing the desired screen. In this case the virtual Y-size typically is a multiple of the display size in Y.

 © 2020 SEGGER Microcontroller GmbH

25.2 Requirements

The virtual screen feature requires hardware with more display RAM than required for a single screen and the ability of the hardware to change the start position of the display output.

Video RAM

The used display controller should support video RAM for the virtual area. For example if the display has a resolution of 320x240 and a color depth of 16 bits per pixel and 2 screens should be supported, the required size of the video RAM can be calculated as follows:

```
Size = LCD_XSIZE × LCD_YSIZE × LCD_BITSPERPIXEL ÷ 8 × NUM_SCREENS
Size = 320 × 240 × 16 ÷ 8 × 2
Size = 307200 Bytes
```

Configurable display start position

The used display controller needs a configurable display start position. This means the display driver even has a register for setting the frame buffer start address or it has a command to set the upper left display start position.

 © 2020 SEGGER Microcontroller GmbH

25.3 Configuration

Virtual screens should be configured during the initialization. The function `LCD_SetVSizeEx()` needs to be used to define the virtual display size. Further it is required to react on the command `LCD_X_SETORG` in the driver callback routine by setting the right frame buffer start address.

 © 2020 SEGGER Microcontroller GmbH

25.3.1 LCD_SetVSizeEx()

Description

Sets the size of the virtual display area.

Prototype

```
int LCD_SetVSizeEx(int LayerIndex,
                   int xSize,
                   int ySize);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
xSize	X-Size in pixels of the virtual area of the given layer.
ySize	Y-Size in pixels of the virtual area of the given layer.

Return value

0 on success.
1 on error.

Additional information

The function requires a display driver which is able to manage dynamically changes of the virtual display size. If the display driver does not support this feature the function fails.

 © 2020 SEGGER Microcontroller GmbH

25.4 Examples

In the following a few examples are shown to make clear how to use virtual screens with emWin.

25.4.1 Basic example

The following example shows how to use a virtual screen of 128x192 and a display of 128x64 for instantaneous switching between 3 different screens.

Configuration

```
LCD_SetSizeEx (0, 128, 64);
LCD_SetVSizeEx(0, 128, 192);
```

Application

```
GUI_SetColor(GUI_RED);
GUI_FillRect(0,  0, 127, 63);
GUI_SetColor(GUI_GREEN);
GUI_FillRect(0, 64, 127, 127);
GUI_SetColor(GUI_BLUE);
GUI_FillRect(0, 128, 127, 191);
GUI_SetColor(GUI_WHITE);
GUI_SetTextMode(GUI_TM_TRANS);
GUI_DispStringAt("Screen 0", 0,  0);
GUI_DispStringAt("Screen 1", 0, 64);
GUI_DispStringAt("Screen 2", 0, 128);
GUI_SetOrg(0, 64); /* Set origin to screen 1 */
GUI_SetOrg(0, 128); /* Set origin to screen 2 */
```

Output

The table below shows the output of the display:

Description	Display output	Contents of virtual area
Before executing `GUI_SetOrg(0, 64)`		
After executing `GUI_SetOrg(0, 64)`		
After executing `GUI_SetOrg(0, 128)`		

25.4.2 Real time example using the Window Manager

The shipment of emWin contains an example which shows how to use virtual screens in a real time application. It can be found under `Sample\Tutorial\VSCREEN_RealTime.c`:

 © 2020 SEGGER Microcontroller GmbH

Screen 0 / Page 0	Screen 1 / Page 1
	

After showing a short introduction, the example creates 2 screens on 2 separate pages as shown above. The first screen shows a dialog which includes a graphical representation of 2 temperature curves. When pressing the "Set color" button, the application switches instantaneously to the second screen, even on slow CPUs. After pressing the "OK" button of the "Adjust color" dialog, the application switches back to the first screen.
For more details, see the source code of the example.

Viewer Screenshot of the above example



If using the viewer both screens can be shown at the same time. The screenshot above shows the visible display at the left side and the contents of the whole configured virtual display RAM at the right side.

25.4.3 Dialog example using the Window Manager

The second advanced example is available in the folder Sample/GUI/VSCREEN_MultiPage. It uses the virtual screen to show 4 screens on 3 different video pages. The application consists of the following screens:

 © 2020 SEGGER Microcontroller GmbH

Main screen / Page 0	Setup screen / Page 1
	
Calibration screen / Page 2	**About screen / Page 2**
	

After a short intro screen the "Main Screen" is shown on the display using page 0. After the "Setup" button is pressed, the "Setup" screen is created on page 1. After the screen has been created, the application makes the screen visible by switching to page 1. The "Calibration" and the "About" screen both use page 2. If the user presses one of the buttons "Calibration" or "About" the application switches to page 2 and shows the dialog.

Viewer Screenshot of the above example



The viewer can show all pages at the same time. The screenshot above shows the visible display at the left side and the contents of the whole layer (virtual display RAM) with the pages 0 - 2 at the right side.

 © 2020 SEGGER Microcontroller GmbH

25.4.4 Virtual screen API

The following table lists the available routines of the virtual screen support.

Routine	Description
GUI_GetOrg()	Returns the display start position.
GUI_SetOrg()	Sets the display start position.

 © 2020 SEGGER Microcontroller GmbH

25.4.4.1 GUI_GetOrg()

Description

Returns the display start position.

Prototype

```
void GUI_GetOrg(int * px,
                int * py);
```

Parameters

Parameter	Description
px	Pointer to variable of type int to store the X position of the display start position.
py	Pointer to variable of type int to store the Y position of the display start position.

Additional information

The function stores the current display start position into the variables pointed by the given pointers.

 © 2020 SEGGER Microcontroller GmbH

25.4.4.2 GUI_SetOrg()

Description

Sets the display start position.

Prototype

```
void GUI_SetOrg(int x,
                int y);
```

Parameters

Parameter	Description
x	New X position of the display start position.
y	New Y position of the display start position.

 © 2020 SEGGER Microcontroller GmbH

Chapter 26

MultiLayer / MultiDisplay support

Multiple displays and multiple layers can be utilized via emWin MultiLayer support. If the hardware supports multiple layers, MultiLayer support can be used. If the hardware does not include such a function, multiple layers can be implemented using the emWin SoftLayer feature.

MultiLayer and MultiDisplay support work the same way. Each layer / display can be accessed with its own color settings, its own size and its own display driver. Initialization of more than one layer is quite simple: The maximum number of available layers `GUI_NUM_LAYERS` should be defined in GUIConf.h and each layer needs a display driver device which should be created during the initialization in the configuration routine `LCD_X_Config()`. There is no limitation regarding the maximum number of available layers.

All SoftLayers use an internal driver which works with 32bpp. The SoftLayer composite is converted to the color setting of the display. SoftLayers and MultiLayer support can not be used in combination. Therefor SoftLayers have to be configured slightly different from MultiLayers.

 © 2020 SEGGER Microcontroller GmbH

26.1 Introduction

This chapter deals with multiple hardware layers (MultiLayer), multiple software layers (SoftLayer) and multiple displays (MultiDisplay). Since a lot of information is valid for each of those features, the following sections will just refer to it as layers unless there are functional differences.
Windows and drawing operations can be placed and performed on any layer. emWinView can output every single layer and the composite view in a separate window.

26.1.1 Selecting a layer for drawing operations

When drawing directly, per default layer 0 is used. Other layers can be selected by using the function `GUI_SelectLayer()`.

Example

The following example shows how to select a layer for drawing operations:

```
void MainTask(void) {
  GUI_Init();
  //
  // Draw something on default layer 0
  //
  GUI_SetBkColor(GUI_GREEN);
  GUI_Clear();
  GUI_DispStringHCenterAt("Layer 0", 100, 46);
  //
  // Draw something on layer 1
  //
  GUI_SelectLayer(1);
  GUI_SetBkColor(GUI_RED);
  GUI_Clear();
  GUI_SetColor(GUI_BLUE);
  GUI_FillRect(20, 20, 179, 79);
  GUI_SetColor(GUI_WHITE);
  GUI_SetTextMode(GUI_TM_TRANS);
  GUI_DispStringHCenterAt("Layer 1", 100, 46);
  while(1) {
    GUI_Delay(100);
  }
}
```

Screenshot of the above example



26.1.2 Selecting a layer for a window

The Window Manager automatically keeps track of which window is located in which layer. This is done in a fairly easy way: If the Window Manager is used, every layer has a top

 © 2020 SEGGER Microcontroller GmbH

level (desktop) window. Any other window in this layer is visible only if it is a descendant of the according desktop window. Windows are connected to a certain layer depending on if they are a descendant of the layer's desktop window.

Example

The following example shows how to create 3 windows on 2 different desktop windows:

```
//
// Create 1 child window on desktop 0
//
hWin0 = WM_CreateWindowAsChild( 10, 20, 80, 70,
        WM_GetDesktopWindowEx(0), WM_CF_SHOW, _cbWin0, 0);
//
// Create 2 child windows on desktop 1
//
hWin1 = WM_CreateWindowAsChild( 10, 20, 80, 70,
        WM_GetDesktopWindowEx(1), WM_CF_SHOW, _cbWin1, 0);
hWin2 = WM_CreateWindowAsChild(110, 20, 80, 70,
        WM_GetDesktopWindowEx(1), WM_CF_SHOW, _cbWin2, 0);
```

The following table shows the screenshot and the window hierarchy of the above example:

Screenshot	Window hierarchy
	

26.1.2.1 Moving a window from one layer to another

This can sometime be very desirable and can easily be accomplished: If a window is detached from its parent (The desktop window of one layer or any descendant of this desktop window) and attached to a window which lies in another layer, this window actually moves from one layer to another layer.

Example

The following example shows how to attach a window to a new parent window:

```
//
// Create 1 child window on desktop 0
//
hWin0 = WM_CreateWindowAsChild( 10, 20, 80, 70,
        WM_GetDesktopWindowEx(0), WM_CF_SHOW, _cbWin0, 0);
//
// Create 2 child windows on desktop 1
//
hWin1 = WM_CreateWindowAsChild( 10, 20, 80, 70,
        WM_GetDesktopWindowEx(1), WM_CF_SHOW, _cbWin1, 0);
hWin2 = WM_CreateWindowAsChild(110, 20, 80, 70,
```

 © 2020 SEGGER Microcontroller GmbH

```
        WM_GetDesktopWindowEx(1), WM_CF_SHOW, _cbWin2, 0);
GUI_Delay(1000);
//
// Detach window 2 from desktop 1 and attach it to desktop 0
//
WM_AttachWindow(hWin2, WM_GetDesktopWindowEx(0));
```

The following table shows the screenshot and the window hierarchy of the above example before attaching the window to the new parent:

Screenshot	Window hierarchy
	

The next table shows the screenshot and the window hierarchy of the above example after attaching the window to the new parent:

Screenshot	Window hierarchy
	

 © 2020 SEGGER Microcontroller GmbH

26.2 Using MultiLayer support

emWin does not distinguish between multiple layers or multiple displays. When using multiple layers normally the size and the driver for each layer is the same. The viewer shows each layer in a separate window. The composite window of the viewer shows all layers; layers with higher index are on top of layers with lower index and can have transparent pixels:



26.2.1 Transparency

Transparency means that at the position of pixels with color index 0 in a layer > 0, the color of the background layer is visible. Since for all but layer 0 Index 0 means transparency, Index 0 can not be used to display colors. This also means that the color conversion should never yield 0 as best match for a color, since this would result in a transparent pixel. This means that only some fixed palette modes or a custom palette mode should be used and that you need to be careful when defining your own palette. You need to make sure that the color conversion (24 bit RGB -> Index) never yields 0 as result.

Fixed palette modes

The only available fixed palette modes including transparency (not Alpha Blending) are `GUICC_M1555I` and `GUICC_8666_1`. Details about fixed palette modes can be found in the chapter *Colors* on page 617.

Custom palette mode

If a custom palette should be used in a layer > 0, the first color should not be used from the color conversion routines. The following shows an example definition for a custom palette with 15 gray scales:

```
static const LCD_COLOR _aColors_16[] = {
  GUI_TRANSPARENT, 0x000000, 0x222222, 0x333333,
  0x444444, 0x555555, 0x666666, 0x777777,
  0x888888, 0x999999, 0xAAAAAA, 0xBBBBBB,
  0xCCCCCC, 0xDDDDDD, 0xEEEEEE, 0xFFFFFF
};
static const LCD_PHYSPALETTE _aPalette_16 = {
 16, _aColors_16
};
void LCD_X_Config(void) {
  //
  // Set display driver and color conversion for 1st layer
  //
  .
  .
  .
  //
  // Set user palette data (only required if no fixed palette is used)
  //
  LCD_SetLUTEx(1, _aPalette_16);
}
```

 © 2020 SEGGER Microcontroller GmbH

The description of the function LCD_SetLUTEx() can be found under *Custom palette mode* on page 642.

Example

The following example shows how to use transparency. It draws 3 color bars in layer 0. Layer 1 is filled with white and 3 transparent items are drawn.

```
GUI_SelectLayer(0);
GUI_SetColor(GUI_RED);
GUI_FillRect(0, 0, 199, 33);
GUI_SetColor(GUI_GREEN);
GUI_FillRect(0, 34, 199, 66);
GUI_SetColor(GUI_BLUE);
GUI_FillRect(0, 67, 199, 99);
GUI_SelectLayer(1);
GUI_SetBkColor(GUI_WHITE);
GUI_Clear();
GUI_SetColor(GUI_BLACK);
GUI_DispStringHCenterAt("Layer 1", 100, 4);
GUI_SetColor(GUI_TRANSPARENT);
GUI_FillCircle(100, 50, 35);
GUI_FillRect(10, 10, 40, 90);
GUI_FillRect(160, 10, 190, 90);
```

Screenshots of above example

The table below shows the contents of the separate layers and the composite view, as the result appears on the display:

Layer 0	Layer 1	Display
		

26.2.2 Alpha blending

Alpha blending is a method of combining two colors for transparency effects. Assumed 2 colors C0 and C1 should be combined with alpha blending A (a value between 0 and 1 where 0 means invisible and 1 means 100% visible) the resulting color C_r can be calculated as follows:

$$C_r = C_0 \times (1 - A) + C_1 \times A$$

Logical colors are handled internally as 32 bit values. The lower 24 bits are used for the color information and the alpha blending is managed in the upper 8 bits. An alpha value of 0x00 means opaque and 0xFF means completely transparent (invisible).

Different methods

There are 3 different methods of managing the alpha information:

- **Layer alpha blending:** On systems with layer alpha blending the alpha value is fixed to the layer and can be set with the function LCD_SetAlphaEx() .
- **Lookup table (LUT) alpha blending:** This kind of alpha blending uses the LUT for managing the alpha information.
- **Pixel alpha blending:** Each pixel of the layer which has to be combined with the background consists of alpha blending information.

 © 2020 SEGGER Microcontroller GmbH

Fixed palette modes

For LUT alpha blending the fixed palette modes 822216 and 84444 can be used. Pixel alpha blending is supported only in 32 bpp mode using the fixed palette mode 8888. For details about the fixed palette modes, refer to the chapter *Colors* on page 617.

Example

The following example shows how to use pixel alpha blending. It draws a circle in layer 0 and a yellow triangle build of horizontal lines with a vertical gradient of alpha values:

```
GUI_SetColor(GUI_BLUE);
GUI_FillCircle(100, 50, 49);
GUI_SelectLayer(1);
GUI_SetBkColor(GUI_TRANSPARENT);
GUI_Clear();
for (i = 0; i < 100; i++) {
  U32 Alpha;
  Alpha = (i * 255 / 100) << 24;
  GUI_SetColor(GUI_YELLOW | Alpha);
  GUI_DrawHLine(i, 100 - i, 100 + i);
}
```

Screenshots of above example

The table below shows the contents of the separate layers and the composite view, as the result appears on the display:

Layer 0	Layer 1	Display
		

26.2.3 Hardware cursors

The term “Hardware cursor” means the use of cursor images in a separate layer with a transparent background. If a hardware supports multiple layers and the ability of layer positioning emWin can be configured to use a separate layer for managing the cursor. The main advantages of this kind of cursor support are a better performance because only a few registers need to be changed on a movement and the ability of custom drawings in the cursor layer. For details about usage, refer to *GUI_AssignCursorLayer* on page 2418.

26.2.4 MultiLayer example

For information about a multi-layer example, see the chapter *Simulation* on page 109. Further, the `Sample` folder contains the following example which shows how to use multiple layer support:

- `MULTILAYER_AlphaChromaMove.c`

 © 2020 SEGGER Microcontroller GmbH

Screenshot of above example



26.2.5 Configuring MultiLayer support

LCD Configuration of the above MultiLayer example

```
void LCD_X_Config(void) {
  //
  // Set display driver and color conversion for first layer ...
  //
  GUI_DEVICE_CreateAndLink(GUIDRV_LIN_16, // Display driver
                           GUICC_655,     // Color conversion
                           0, 0);
  //
  //  ... and configure it
  //
  LCD_SetSizeEx  (0, 400, 234);           // Physical display size in pixels
  LCD_SetVRAMAddrEx(0, (void *)0xc00000); // Video RAM start address
  //
  // Set display driver and color conversion for second layer ...
  //
  GUI_DEVICE_CreateAndLink(GUIDRV_LIN_8,  // Display driver
                           GUICC_86661,   // Color conversion
                           0, 1);
  //
  // ... and configure it
  //
  LCD_SetSizeEx(1, 400, 234);             // Physical display size in pixels
  LCD_SetVRAMAddrEx(1, (void *)0xc00000); // Video RAM start address
}
```

 © 2020 SEGGER Microcontroller GmbH

26.3 Using MultiDisplay support

Each display can be accessed with its own driver and with its own settings.

26.3.1 Enabling MultiDisplay support

To enable the MultiDisplay support you have to define the maximum number of layers in `GUIConf.h`:

```
#define GUI_NUM_LAYERS 2 /* Enables support for 2 displays/layers */
```

Further you have to create and configure a display driver device for each layer.

26.3.2 Run-time screen rotation

In some cases it may be necessary to change the display orientation at run-time. The MultiDisplay support allows to do this. In this case the file LCDConf.c should contain a display configuration for each required display orientation. Switching the display orientation then works as follows:

- Select the configuration with the required display orientation with `GUI_SelectLayer()`.
- If the rotation requires a reinitialization of the display controller the right driver function for reinitializing should be called. This is `LCD_L0_Init()` for layer 0 and `LCD_L0_x_Init()` for higher layers, where "x" means the zero based index of the configuration.

26.3.3 MultiDisplay example

The example below shows a screenshot of the simulation with 2 displays. The fist display is a 8bpp color display with a size of 320 × 240 pixels. The driver is `GUIDRV_Lin_8`. The second display is a 1bpp black and white display with a size of 240 × 128 pixels. The driver is `GUIDRV_SLin_1.c`:



 © 2020 SEGGER Microcontroller GmbH

26.3.4 Configuring MultiDisplay support

Configuration of the above example

```
void LCD_X_Config(void) {
  //
  // Set display driver and color conversion for first layer ...
  //
  GUI_DEVICE_CreateAndLink(GUIDRV_LIN_8,  // Display driver
                           GUICC_8666,    // Color conversion
                           0, 0);
  //
  // ... and configure it
  //
  LCD_SetSizeEx(0, 320, 240);             // Physical display size in pixels
  LCD_SetVRAMAddrEx(0, (void *)0xc00000); // Video RAM start address
  //
  // Set display driver and color conversion for second layer ...
  //
  GUI_DEVICE_CreateAndLink(GUIDRV_SLIN_1, // Display driver
                           GUICC_1,       // Color conversion
                           0, 1);
  //
  // ... and configure it
  //
  LCD_SetSizeEx(1, 240, 128);             // Physical display size in pixels
}
```

 © 2020 SEGGER Microcontroller GmbH

26.4 Using SoftLayers

In case multiple hardware layers are not supported, emWin offers the possibility to make use of software layers. The advantage of softlayers is they can be used on any target hardware meeting the memory requirements. The disadvantage is additional CPU load to render the layers. Rendering is done automatically by executing the GUI. Alternatively the function `GUI_SOFTLAYER_Refresh()` can be called to immediately refresh the layers.
emWin SoftLayers are highly optimized. Layers are refreshed only if there is at least one dirty area. Drawing operations are tracked automatically to create/extend according dirty areas. A refresh is processed by dividing dirty areas in sub-rectangles which affect the same layers for faster color calculation. This way processing all layers unnecessarily for all pixels is avoided.
If there are dirty areas, pixel data is processed from the bottom to the top starting with the top opaque layer. Layers below the top opaque layer would not have any impact on the result.

Mixing example (opaque and non-overlapping layers)

Assuming there is a configuration including 4 SoftLayers. Drawing operations have been done, so a dirty area exists. Layer 1 is opaque, layer 2 does not overlap the dirty area and layer 3 contains semi-transparent pixels. In this case the SoftLayer logic would ignore layer 0 and layer 2, so the only thing to do would be mixing the colors from layer 1 and 3.

Mixing example (composite color and several semi-transparent layers)

Assuming there is a configuration including 4 SoftLayers in which the layers contain either transparency, semi-transparency or are not affected by the dirty area at all, the composite color is used as "opaque layer". In this case the composite color is mixed with the content of layer 0. The result would be mixed with the content of layer 1. In turn the result would be mixed with the content of layer 2. And so on…

26.4.1 Using SoftLayers within a simulation environment

In a simulation environment SoftLayers have to be set up differently from HardLayers. Below information should be a help for configuring the simulation properly for the use of SoftLayers. The according function descriptions can be found in the chapter *Simulation* on page 109.

Composite color

SoftLayers consist of their own composite color which can be set using the function `GUI_SOFTLAYER_Enable()` or `GUI_SOFTLAYER_SetCompositeColor()`. The function `GUI_SIM_SetCompositeColor()` does not have an effect with SoftLayers.

Composite size

The function `SIM_GUI_SetCompositeSize()` can be used for setting the size of the composite view. Calling this function is required for SoftLayer use.

Transparency mode

In order to benefit from transparency effects, Layers can be configured for a certain transparency mode using the function `SIM_GUI_SetTransMode()`. Transparency can be implemented either via *"zero transparency"* or via *"pixel alpha"*.

SIMConf.c example

```
void SIM_X_Config() {
  SIM_GUI_SetCompositeSize(480, 272);  // Set size of composite window
  SIM_GUI_SetTransMode(1, GUI_TRANSMODE_PIXELALPHA);
  SIM_GUI_SetTransMode(2, GUI_TRANSMODE_PIXELALPHA);
  SIM_GUI_SetTransMode(3, GUI_TRANSMODE_PIXELALPHA);
}
```

 © 2020 SEGGER Microcontroller GmbH

26.4.2 Memory requirements

emWin SoftLayers require storing additional information in RAM which can be subdivided in display related memory and layer related memory. The memory is taken from the memory pool which is assigned to emWin using `GUI_ALLOC_AssignMemory()` in function `GUI_X_Config()` (`GUIConf.c`).

Required display related memory

Depending on the display size and color depth, SoftLayers require storing data for the following items:

- SoftLayer driver context.
- 32bpp buffer with the size of the display width.
- Frame buffer with the size and color depth of the display.

The required display related memory can be calculated using the following formula:

```
ReqMem = 68 Bytes + xSizeDisp × 4 + xSizeDisp × ySizeDisp × BytesPerPixelDisp
```

Required layer related memory

Depending on the SoftLayer configuration, SoftLayers require additional memory to store one complete frame for each layer at a color depth of 32bpp.
The required display related memory can be calculated using the following formula:

```
ReqMem += xSize0 × ySize0 × 4 + xSize1 × ySize1 × 4 + ... (and so on)
```

Explanation of terms

Term	Explanation
`68 Bytes`	Required for context information in the SoftLayer driver.
`xSizeDisp`	X-size of the display.
`ySizeDisp`	Y-size of the display.
`BytesPerPixelDisp`	Number of bytes per pixel used by the display.
`xSize0`	X-size of layer 0.
`ySize0`	Y-size of layer 0.

26.4.3 Configuring SoftLayers

SoftLayers need to be configured different from hardware layers. In order to set up the desired layers a data structure of type `GUI_SOFTLAYER_CONFIG` needs to be filled and passed to the function `GUI_SOFTLAYER_Enable()`. SoftLayers do not require each layer to have a separate driver device. There is an internal SoftLayer driver which is automatically used for all layers.

LCDConf.c

```
void LCD_X_Config(void) {
  GUI_SOFTLAYER_CONFIG aConfig[] = {
    {   0,   0, 480, 272, 1 },
    {   0,   0, 120, 108, 1 },
    {   0,   0, 120,  74, 1 },
    {  30,  30, 420,  35, 1 },
  };
  //
  // Set display driver and color conversion for 1st layer
  //
  GUI_DEVICE_CreateAndLink(DISPLAY_DRIVER, COLOR_CONVERSION, 0, 0);
  //
  // Display driver configuration
```

 © 2020 SEGGER Microcontroller GmbH

```
  //
  LCD_SetSizeEx    (0, XSIZE_PHYS,   YSIZE_PHYS);
  LCD_SetVSizeEx   (0, VXSIZE_PHYS,  VYSIZE_PHYS);
  LCD_SetVRAMAddrEx(0, (void *)VRAM_ADDR);
  //
  // SoftLayer activation after existing single layer configuration
  //
  GUI_SOFTLAYER_Enable(aConfig, GUI_COUNTOF(aConfig), GUI_DARKBLUE);
}
```

 © 2020 SEGGER Microcontroller GmbH

26.5 MultiLayer API

The table below lists the available MultiLayer related routines in alphabetical order. Detailed descriptions follow:

Functions

Routine	Description
General MultiLayer functions	
GUI_AssignCursorLayer()	The function assigns a layer to be used as cursor layer.
GUI_GetLayerPosEx()	Returns the X- and Y-position of the given layer.
GUI_SelectLayer()	Selects a layer for drawing operations.
GUI_SetLayerAlphaEx()	Sets the alpha blending of the given layer.
GUI_SetLayerPosEx()	Sets the X- and Y-position of the given layer.
GUI_SetLayerSizeEx()	Sets the X- and Y-size of the given layer.
GUI_SetLayerVisEx()	Sets the visibility of the given layer.
LCD_GetNumLayers()	Returns the number of layers configured in your configuration.
SoftLayer specific functions	
GUI_SOFTLAYER_Enable()	Enables and configures SoftLayers.
GUI_SOFTLAYER_Refresh()	Refreshes layers by rerendering the dirty area.
GUI_SOFTLAYER_SetCompositeColor()	Sets the composite color.
GUI_SOFTLAYER_MULTIBUF_Enable()	Enables the automatic use of Multiple Buffering with SoftLayers.

Data structures

Structure	Description
GUI_SOFTLAYER_CONFIG	Data structure used by GUI_SOFTLAYER_Enable() to configurate a soft layer.

 © 2020 SEGGER Microcontroller GmbH

26.5.1 General MultiLayer functions

26.5.1.1 GUI_AssignCursorLayer()

Description

The function assigns a layer to be used as cursor layer.

Prototype

```
void GUI_AssignCursorLayer(unsigned LayerIndex,
                           unsigned CursorLayer);
```

Parameters

Parameter	Description
Index	Layer index.
CursorLayer	Layer to be used to manage the cursor.

Additional information

Using a hardware cursor means a layer is used as cursor layer. Contrary to the default cursor handling, where the cursor is drawn in the same video memory area as all other items, a hardware cursor is drawn in a separate layer. In this case emWin makes sure the background color of the hardware cursor layer is set to transparency and the selected cursor will be drawn into the layer. Whereas the default cursor management requires more or less calculation time to draw the cursor and to manage the background, moving a hardware cursor requires only the modification of a few registers. Note that using this function requires that the display driver supports layer positioning.

 © 2020 SEGGER Microcontroller GmbH

26.5.1.2 GUI_GetLayerPosEx()

Description

Returns the X- and Y-position of the given layer.

Prototype

```
int GUI_GetLayerPosEx(unsigned   LayerIndex,
                      int      * pxPos,
                      int      * pyPos);
```

Parameters

Parameter	Description
Index	Layer index.
pxPos	Pointer to an integer to be used to return the X position of the given layer.
pyPos	Pointer to an integer to be used to return the Y position of the given layer.

Additional information

To be able to use this function the hardware and the used display driver need to support layer positioning. If the driver does not support this feature the function returns immediately.

 © 2020 SEGGER Microcontroller GmbH

26.5.1.3 GUI_SelectLayer()

Description

Selects a layer for drawing operations.

Prototype

```
unsigned GUI_SelectLayer(unsigned Index);
```

Parameters

Parameter	Description
Index	Layer index.

Return value

Index of the previously selected layer.

 © 2020 SEGGER Microcontroller GmbH

26.5.1.4 GUI_SetLayerAlphaEx()

Description

Sets the alpha blending of the given layer.

Prototype

```
int GUI_SetLayerAlphaEx(unsigned LayerIndex,
                        int      Alpha);
```

Parameters

Parameter	Description
Index	Layer index.
Alpha	Alpha blending value of the given layer.

Return value

0 on success
1 on error.

Additional information

To be able to use this function the hardware and the used display driver need to support layer alpha blending. If the driver does not support this feature the function returns immediately. The usable range of alpha values depends on the hardware. In many cases the range of alpha values is limited, for example 0 - 0x3f. emWin does not know something about limitations and passes the given value to the driver. It is the responsibility of the application to make sure that the given value is in a legal range.

 © 2020 SEGGER Microcontroller GmbH

26.5.1.5 GUI_SetLayerPosEx()

Description

Sets the X- and Y-position of the given layer.

Prototype

```
int GUI_SetLayerPosEx(unsigned LayerIndex,
                      int      xPos,
                      int      yPos);
```

Parameters

Parameter	Description
Index	Layer index.
xPos	New X position of the given layer.
yPos	New Y position of the given layer.

Additional information

To be able to use this function the hardware and the used display driver need to support layer positioning. If the driver does not support this feature the function returns immediately.

 © 2020 SEGGER Microcontroller GmbH

26.5.1.6 GUI_SetLayerSizeEx()

Description

Sets the X- and Y-size of the given layer.

Prototype

```
int GUI_SetLayerSizeEx(unsigned LayerIndex,
                       int      xSize,
                       int      ySize);
```

Parameters

Parameter	Description
Index	Layer index.
xSize	New horizontal size in pixels of the given layer.
ySize	New vertical size in pixels of the given layer.

Additional information

To be able to use this function the hardware and the used display driver need to support layer sizing. If the driver does not support this feature the function returns immediately.

 © 2020 SEGGER Microcontroller GmbH

26.5.1.7 GUI_SetLayerVisEx()

Description

Sets the visibility of the given layer.

Prototype

```
int GUI_SetLayerVisEx(unsigned LayerIndex,
                      int      OnOff);
```

Parameters

Parameter	Description
Index	Layer index.
OnOff	1 if layer should be visible, 0 for invisible.

Additional information

To be able to use this function the hardware and the used display driver need to support this feature. If the driver does not support this feature the function returns immediately.

 © 2020 SEGGER Microcontroller GmbH

26.5.1.8 LCD_GetNumLayers()

Description

Returns the number of layers configured in your configuration.

Prototype

```
int LCD_GetNumLayers(void);
```

Return value

Number of layers configured in your configuration.

 © 2020 SEGGER Microcontroller GmbH

26.5.2 SoftLayer specific functions

26.5.2.1 GUI_SOFTLAYER_Enable()

Description

Enables and configures SoftLayers.

Prototype

```
int GUI_SOFTLAYER_Enable(GUI_SOFTLAYER_CONFIG * pConfig,
                         int                    NumLayers,
                         GUI_COLOR              CompositeColor);
```

Parameters

Parameter	Description
pConfig	Pointer to a GUI_SOFTLAYER_CONFIG data structure.
NumLayers	Number of layers to create using the config data.
CompositeColor	The composite color is used in case certain areas do not contain opaque colors.

Return value

0 on success
1 on error.

Additional information

This function may be called only from within the function LCD_X_Config(). The function LCD_X_Config() is called automatically from GUI_Init().

 © 2020 SEGGER Microcontroller GmbH

26.5.2.2 GUI_SOFTLAYER_Refresh()

Description

Refreshes layers by rerendering the dirty area.

Prototype

```
int GUI_SOFTLAYER_Refresh(void);
```

Return value

0	if nothing was done
1	if something was done
2	on error.

Additional information

This function is called from the function `GUI_Exec1()` if SoftLayers are enabled. After a refresh was performed, the dirty area gets cleared.

 © 2020 SEGGER Microcontroller GmbH

26.5.2.3 GUI_SOFTLAYER_SetCompositeColor()

Description

Sets the composite color.

Prototype

```
void GUI_SOFTLAYER_SetCompositeColor(U32 Color);
```

Parameters

Parameter	Description
`Color`	`Color` to be set as composite color.

Additional information

The function `SIM_GUI_SetCompositeColor()` does not have an effect with SoftLayers.

 © 2020 SEGGER Microcontroller GmbH

26.5.2.4 GUI_SOFTLAYER_MULTIBUF_Enable()

Description

Enables the automatic use of Multiple Buffering with SoftLayers.

Prototype

```
int GUI_SOFTLAYER_MULTIBUF_Enable(int OnOff);
```

Parameters

Parameter	Description
OnOff	0 to disable MultiBuffering support, 1 to enable MultiBuffering support.

Return value

The function returns the previous setting.

0	if MultiBuffering has not been used
1	if MultiBuffering has already been used.

Additional information

If Multiple Buffering is enabled, the function `GUI_SOFTLAYER_Refresh()` automatically calls the function `GUI_MULTIBUF_BeginEx()` and `GUI_MULTIBUF_EndEx()`.

 © 2020 SEGGER Microcontroller GmbH

26.5.3 Data structures

26.5.3.1 GUI_SOFTLAYER_CONFIG

Description

Data structure used by `GUI_SOFTLAYER_Enable()` to configurate a soft layer.

Type definition

```
typedef struct {
  int  xPos;
  int  yPos;
  int  xSize;
  int  ySize;
  int  Visible;
} GUI_SOFTLAYER_CONFIG;
```

Structure members

Member	Description
xPos	X-position.
yPos	Y-position.
xSize	X-size.
ySize	Y-size.
Visible	1 = visible, 0 = not visible.

 © 2020 SEGGER Microcontroller GmbH

Chapter 27

Pointer Input Devices

emWin provides support for pointer-input-devices. Pointer input devices can be touch-screen, mouse or joystick. The basic emWin package includes a driver for analog touch-screens, a PS2 mouse driver, as well as an example joystick driver. Other types of touch-panel and mouse devices can also be used with the appropriate drivers.
The software for input devices is located in the subdirectory `GUI\Core`.

 © 2020 SEGGER Microcontroller GmbH

27.1 Description

Pointer input devices are devices such as mice, touch-screens and joysticks. Multiple pointer input devices can be used in a single application to enable simultaneous mouse/touch-screen/joystick use. Basically all a PID driver does is calling the routine `GUI_PID_StoreState()` whenever an event (such as a moved mouse, or a pressed touch screen) has been detected.
PID events are stored in a FIFO which is processed by the Window Manager. If the Window Manager is not used (respectively deactivated), the application is responsible for reacting on PID events.

 © 2020 SEGGER Microcontroller GmbH

27.2 Pointer input device API

The table below lists the pointer input device routines in alphabetical order. Detailed descriptions follow.

> **Note**
>
> This API is used by the PID-driver; if you use a PID-driver shipped with emWin, your code does not need to call these routines.

Routine	Description
GUI_PID_GetCurrentState()	Fills the given GUI_PID_STATE structure with the most recently stored PID state.
GUI_PID_GetState()	Fills the given GUI_PID_STATE structure with the current state information and returns if the input device is currently pressed.
GUI_PID_IsEmpty()	Returns if the PID buffer is empty.
GUI_PID_IsPressed()	Returns if the most recent state of the PID is pressed.
GUI_PID_SetHook()	Sets an optional function to be called immediately before storing a new PID event into the input buffer.
GUI_PID_StoreState()	Stores the current state of the pointer input device.

Data structure

The structure of type GUI_PID_STATE referenced by the parameter pState is filled by the routine with the current values. The structure is explained *earlier in this manual.*

 © 2020 SEGGER Microcontroller GmbH

27.2.1 GUI_PID_GetCurrentState()

Description

Fills the given GUI_PID_STATE structure with the most recently stored PID state.

Prototype

```
void GUI_PID_GetCurrentState(GUI_PID_STATE * pState);
```

Parameters

Parameter	Description
pState	Pointer to a GUI_PID_STATE structure.

Additional information

This function performs a non-destructive read on the PID FIFO.

 © 2020 SEGGER Microcontroller GmbH

27.2.2 GUI_PID_GetState()

Description

Fills the given GUI_PID_STATE structure with the current state information and returns if the input device is currently pressed.

Prototype

```
int GUI_PID_GetState(GUI_PID_STATE * pState);
```

Parameters

Parameter	Description
pState	Pointer to a GUI_PID_STATE structure.

Return value

1 if input device is currently pressed
0 if not pressed.

Additional information

This function does a destructive read on the PID FIFO: If the FIFO contains unread values, it reads and eliminates the first value in the FIFO . If the FIFO is empty, it returns the last value written to it. If no value has ever been written into the PID FIFO, all values in pState are set to 0.

Example

```
GUI_PID_STATE State;
GUI_PID_GetState(&State);
```

 © 2020 SEGGER Microcontroller GmbH

27.2.3 GUI_PID_IsEmpty()

Description

Returns if the PID buffer is empty.

Prototype

```
int GUI_PID_IsEmpty(void);
```

Return value

1	if the PID buffer is empty.
0	if entries were found in the PID buffer.

 © 2020 SEGGER Microcontroller GmbH

27.2.4 GUI_PID_IsPressed()

Description

Returns if the most recent state of the PID is pressed.

Prototype

```
int GUI_PID_IsPressed(void);
```

Return value

1	if input device is currently pressed
0	if not pressed.

Additional information

This function does not modify the `PID FIFO`.

 © 2020 SEGGER Microcontroller GmbH

27.2.5 GUI_PID_SetHook()

Description

Sets an optional function to be called immediately before storing a new PID event into the input buffer.

Prototype

```
void GUI_PID_SetHook(void ( *pfHook)(GUI_PID_STATE * ));
```

Parameters

Parameter	Description
pfHook	Pointer to a function which is called immediately before a new PID event is added to the input buffer.

Additional information

This function is usefull if it is required to have widgets within multiple layers. Dependent on the given coordinates the element 'Layer' could be modified before the data is added to the input buffer. Please be aware that this function is called by directly by `GUI_PID_StoreState()`. In case of using a touch ISR it is called from that ISR. Calling further GUI functions within the hook function is not allowed.

 © 2020 SEGGER Microcontroller GmbH

27.2.6 GUI_PID_StoreState()

Description

Stores the current state of the pointer input device.

Prototype

```
void GUI_PID_StoreState(const GUI_PID_STATE * pState);
```

Parameters

Parameter	Description
pState	Pointer to a structure of type GUI_PID_STATE.

Additional information

This function can be used from an interrupt service routine. The PID input manager of emWin contains a FIFO buffer which is able to hold up to 5 PID events per default. If a different size is required this value can be changed. Details can be found in the section *Advanced GUI configuration options* on page 2901.

 © 2020 SEGGER Microcontroller GmbH

27.3 Mouse driver

Mouse support consists of two “layers”: a generic layer and a mouse driver layer. Generic routines refer to those functions which always exist, no matter what type of mouse driver you use. The available mouse driver routines, on the other hand, will call the appropriate generic routines as necessary, and may only be used with the PS2 mouse driver supplied with emWin. If you write your own driver, it is responsible for calling the generic routines. The generic mouse routines will in turn call the corresponding PID routines.

27.3.1 Generic mouse driver API

The table below lists the generic mouse routines in alphabetical order. These functions may be used with any type of mouse driver. Detailed descriptions follow.

Routine	Description
GUI_MOUSE_GetState()	Returns the current state of the mouse.
GUI_MOUSE_StoreState()	Stores the current state of the mouse.

 © 2020 SEGGER Microcontroller GmbH

27.3.1.1 GUI_MOUSE_GetState()

Description

Returns the current state of the mouse.

Prototype

```
int GUI_MOUSE_GetState(GUI_PID_STATE * pState);
```

Parameters

Parameter	Description
pState	Pointer to a structure of type GUI_PID_STATE.

Return value

1 if mouse is currently pressed.
0 if not pressed.

Additional information

This function will call GUI_PID_GetState().

 © 2020 SEGGER Microcontroller GmbH

27.3.1.2 GUI_MOUSE_StoreState()

Description

Stores the current state of the mouse.

Prototype

```
void GUI_MOUSE_StoreState(const GUI_PID_STATE * pState);
```

Parameters

Parameter	Description
pState	Pointer to a structure of type GUI_PID_STATE.

Additional information

This function will call GUI_PID_StoreState(). This function can be used from an interrupt service routine.

Example

```
GUI_PID_STATE State;
State.x = _MousepositionX; /* Screen position in X of mouse device */
State.y = _MousepositionY; /* Screen position in Y of mouse device */
State.Pressed = 0;
if (_LeftButtonPressed) {
  State.Pressed |= 1;      /* Set bit 0 if left button is pressed */
}
if (_RightButtonPressed) {
  State.Pressed |= 2;      /* Set bit 1 if right button is pressed */
}
GUI_MOUSE_StoreState(&State);
```

 © 2020 SEGGER Microcontroller GmbH

27.3.2 PS2 mouse driver

The driver supports any type of PS2 mouse

27.3.2.1 Using the PS2 mouse driver

The driver is very easy to use. In the startup code, the initialization function `GUI_MOUSE_DRIVER_PS2_Init()` should be called. The application should somehow notice when a byte is received from the mouse. When this happens, the function `GUI_MOUSE_DRIVER_PS2_OnRx()` should be called and the byte received passed as parameter. The driver in turn then calls `GUI_PID_StoreState` as required. The reception of the byte is typically handled in an interrupt service routine.
An example ISR could look as follows: (Note that this is of course different for different systems)

```
void interrupt OnRx(void) {
  char Data;
  Data = UART_REG;                  // Read data from the hardware
  GUI_MOUSE_DRIVER_PS2_OnRx(Data);  // Pass it on to the driver
}
```

27.3.2.2 PS2 mouse driver API

The table below lists the available mouse driver routines in alphabetical order.

Routine	Description
GUI_MOUSE_DRIVER_PS2_Init()	Initializes the mouse driver.
GUI_MOUSE_DRIVER_PS2_OnRx()	Must be called from receive interrupt routines.

 © 2020 SEGGER Microcontroller GmbH

27.3.2.2.1 GUI_MOUSE_DRIVER_PS2_Init()

Description

Initializes the mouse driver.

Prototype

```
void GUI_MOUSE_DRIVER_PS2_Init(void);
```

 © 2020 SEGGER Microcontroller GmbH

27.3.2.2.2 GUI_MOUSE_DRIVER_PS2_OnRx()

Description

Must be called from receive interrupt routines.

Prototype

```
void GUI_MOUSE_DRIVER_PS2_OnRx(unsigned char Data);
```

Parameters

Parameter	Description
Data	Byte of data received by ISR.

Additional information

The PS2 mouse driver is a serial driver, meaning it receives 1 byte at a time. You need to ensure that this function is called from your receive interrupt routine every time a byte (1 character) is received.

 © 2020 SEGGER Microcontroller GmbH

27.4 Touch screen driver

A touch screen driver will typically simply call `GUI_PID_StoreState()` as described earlier. Any type of touch screen can be supported this way. It is the responsibility of the user to write the driver code (which is usually fairly simple).
The most common way of interfacing a touch screen is the 4-pin analog interface, for which a driver is supplied.

27.4.1 Generic touch screen API

The generic touch screen API is used with any type of driver (analog, digital, etc.). A driver calls the appropriate routines as necessary. If you write your own driver, it has to call the generic routines.
The table below lists the generic touch-screen routines in alphabetical order. These functions may be used with any type of touch-screen driver. Detailed descriptions follow.

Routine	Description
`GUI_TOUCH_GetState()`	Returns the current state of the touch-screen.
`GUI_TOUCH_StoreState()`	Stores the current state of the touch screen using X- and Y-coordinates as parameters.
`GUI_TOUCH_StoreStateEx()`	Stores the current state of the touch screen.

 © 2020 SEGGER Microcontroller GmbH

27.4.1.1 GUI_TOUCH_GetState()

Description

Returns the current state of the touch-screen.

Prototype

```
int GUI_TOUCH_GetState(GUI_PID_STATE * pState);
```

Parameters

Parameter	Description
pState	Pointer to a structure of type GUI_PID_STATE.

Return value

1 if touch-screen is currently pressed.
0 if not pressed.

 © 2020 SEGGER Microcontroller GmbH

27.4.1.2 GUI_TOUCH_StoreState()

Description

Stores the current state of the touch screen using X- and Y-coordinates as parameters.

Prototype

```
void GUI_TOUCH_StoreState(int x,
                          int y);
```

Parameters

Parameter	Description
x	X-position.
y	Y-position.

Additional information

This function can be used from an interrupt service routine. It calls the function `GUI_PID_StoreState()`. It is assumed that the touch panel is not pressed, if this function is called with negative values. A detailed example of a touch handling routine can be found in `Sample\GUI_X\GUI_X_Touch_StoreState.c`.

Example

```
int x, y;
if (_TouchIsPressed) {
  x = _TouchPositionX; /* Current position in X of touch device */
  y = _TouchPositionY; /* Current position in Y of touch device */
} else {
  x = y = -1;          /* Use -1 if touch is not pressed */
}
GUI_TOUCH_StoreState(x, y);
```

 © 2020 SEGGER Microcontroller GmbH

27.4.1.3 GUI_TOUCH_StoreStateEx()

Description

Stores the current state of the touch screen.

Prototype

```
void GUI_TOUCH_StoreStateEx(const GUI_PID_STATE * pState);
```

Parameters

Parameter	Description
pState	Pointer to a structure of type GUI_PID_STATE.

Additional information

This function will call GUI_PID_StoreState(). A detailed example of a touch handling routine can be found in Sample\GUI_X\GUI_X_Touch_StoreState.c.

Example

```
GUI_PID_STATE State;
State.x = _TouchPositionX;
State.y = _TouchPositionY;
if (_TouchIsPressed) {
  State.Pressed = 1;
} else {
  State.Pressed = 0;
}
GUI_TOUCH_StoreStateEx(&State);
```

 © 2020 SEGGER Microcontroller GmbH

27.4.2 The analog touch screen driver

The emWin touch-screen driver handles analog input (from an 8-bit or better A/D converter), debouncing and calibration of the touch-screen. The touch-screen driver continuously monitors and updates the touch-panel through the use of the function `GUI_TOUCH_Exec()`, which calls the appropriate generic touchscreen API routines when it recognizes that an action has been performed or something has changed.

How an analog touch screen works

The touch panel consists of 2 thin conducting layers of glass, normally insulated from each other. If the user presses the touch panel, the two layers are connected at that point. If a voltage is applied to the Y-layer, when pressed, a voltage can be measured at the X+/X-terminals. This voltage depends on the touch position. The same thing holds true the other way round. If a voltage is applied to the X-layer, when pressed, a voltage can be measured at the Y+/Y-terminals.



27.4.2.1 Setting up the analog touch screen

Putting a touch panel into operation should be done in the following steps:

- Implementing the hardware routines
- Implementing regular calls to `GUI_TOUCH_Exec()`
- Verifying proper operation with the oscilloscope
- Using example to determine calibration values
- Adding a call of `GUI_TOUCH_Calibrate()` to the initialization routine `LCD_X_Config()` using the determined values

The following shows a detailed description of each step.

Implementing the hardware routines

The first step of implementing a touch screen should be filling the hardware routines with code. These routines are:

- `GUI_TOUCH_X_ActivateX()` and `GUI_TOUCH_X_ActivateY()`
- `GUI_TOUCH_X_MeasureX()` and `GUI_TOUCH_X_MeasureY()`

A module `GUI_TOUCH_X.c` containing the empty routines is located in the folder `Sample\GUI_X`. You can use this module as a starting point. The activate routines should prepare the measurement by switching on the measurement voltage. `GUI_TOUCH_X_ActivateX()` for example should prepare the measurement in Y by switching on the measurement voltage in X. Further it should switch of the voltage in Y and disable the measurement in X. The measurement routines should return the measurement result of a A/D converter. Later in this chapter you will find an example implementation of the hardware routines.

 © 2020 SEGGER Microcontroller GmbH

Implementing regular calls to GUI_TOUCH_Exec()

The second step of implementing a touch screen is to make sure, that the function `GUI_TOUCH_Exec()` will be called in regular intervals. The application should call it about 100 times/second. If a real-time operating system is used, the easiest way to make sure this function is called is to create a separate task. When not using a multitasking system, an interrupt service routine may do the job. The function `GUI_TOUCH_Exec()` measures x- and y-axis in turns. So complete measurements are done once both axes were measured.

Verifying proper operation with the oscilloscope

After implementing the call of `GUI_TOUCH_Exec()` make sure the hardware works. The easiest way to do this is to measure the supply and measurement voltages of the touch panel with a oscilloscope. The following table shows a typical result. The first column shows the supply voltage of an axis, the second column shows the result of measuring the measurement voltage when pressing in the middle of the touch panel.

Supply voltage	Measurement voltage
	

Use example to determine calibration values

The third step is to get the minimum and maximum values of the A/D converter. emWin needs this values to convert the measurement result to the touch position in pixels. These 4 values are:

Value	How to get them
`GUI_TOUCH_AD_TOP`	Press the touch at the top and write down the analog input value in Y.
`GUI_TOUCH_AD_BOTTOM`	Press the touch at the bottom and write down the analog input value in Y.
`GUI_TOUCH_AD_LEFT`	Press the touch at the left and write down the analog input value in X.
`GUI_TOUCH_AD_RIGHT`	Press the touch at the right and write down the analog input value in X.

The example folder of emWin contains a small program which can be used to get these values from your touch panel. It is located in the folder `Sample\Tutorial` and its name is `TOUCH_Sample.c`. Run this example on your hardware. The output should be similar to the screenshot at the right side.

 © 2020 SEGGER Microcontroller GmbH



Use GUI_TOUCH_Calibrate() with the above values

The last step is adding a call to `GUI_TOUCH_Calibrate()` using the calibration values. The recommended location for calibrating the touch screen is the initialization routine `LCD_X_Config()` which is located in `LCDConf.c`. similar to following example:

```
#define GUI_TOUCH_AD_TOP    877
#define GUI_TOUCH_AD_BOTTOM 273
#define GUI_TOUCH_AD_LEFT   232
#define GUI_TOUCH_AD_RIGHT  918
.
.
.
void LCD_X_Config(void) {
  //
  // Initialize display driver
  //
  .
  .
  .
  //
  // Set orientation of touch screen (only required when using
  //
  TouchOrientation = (GUI_MIRROR_X * LCD_GetMirrorX()) |
                     (GUI_MIRROR_Y * LCD_GetMirrorY()) |
                     (GUI_SWAP_XY * LCD_GetSwapXY())   ;
  GUI_TOUCH_SetOrientation(TouchOrientation);
  //
  // Calibrate touch screen
  //
  GUI_TOUCH_Calibrate(GUI_COORD_X, 0, 240, GUI_TOUCH_AD_TOP , GUI_TOUCH_AD_BOTTOM);
  GUI_TOUCH_Calibrate(GUI_COORD_Y, 0, 320, GUI_TOUCH_AD_LEFT, GUI_TOUCH_AD_RIGHT);
}
```

27.4.2.2 Runtime calibration

In practice the exact values for the configuration file can be determined only for one touch panel. Because there are small differences between the parts of a series it could be very needful to calibrate each device at run-time. This can be done by using the function `GUI_TOUCH_Calibrate()`. The `Sample` folder contains the example `TOUCH_Calibrate.c` which shows, how a touch screen can be calibrated at run time:

 © 2020 SEGGER Microcontroller GmbH



27.4.2.3 Hardware routines

The following four hardware-dependent functions need to be added to your project if you use the driver supplied with emWin, as they are called by `GUI_TOUCH_Exec()` when polling the touch-panel. A suggested place is in the file `GUI_X.c`. These functions are as follows:

Routine	Description
`GUI_TOUCH_X_ActivateX()`	Prepares measurement for Y-axis.
`GUI_TOUCH_X_ActivateY()`	Prepares measurement for X-axis.
`GUI_TOUCH_X_MeasureX()`	Returns the X-result of the A/D converter.
`GUI_TOUCH_X_MeasureY()`	Returns the Y-result of the A/D converter.

 © 2020 SEGGER Microcontroller GmbH

27.4.2.3.1 GUI_TOUCH_X_ActivateX()

27.4.2.3.2 GUI_TOUCH_X_ActivateY()

Description

These routines are called from `GUI_TOUCH_Exec()` to activate the measurement of the X- and the Y-axes. `GUI_TOUCH_X_ActivateX()` switches on the measurement voltage to the X-axis; `GUI_TOUCH_X_ActivateY()` switches on the voltage to the Y- axis. Switching on the voltage in X means the value for the Y-axis can be measured and vice versa.

Prototypes

```
void GUI_TOUCH_X_ActivateX(void);

void GUI_TOUCH_X_ActivateY(void);
```

 © 2020 SEGGER Microcontroller GmbH

27.4.2.3.3 GUI_TOUCH_X_MeasureX()

27.4.2.3.4 GUI_TOUCH_X_MeasureY()

Description

These routines are called from `GUI_TOUCH_Exec()` to return the measurement values from the A/D converter for the X- and the Y-axes.

Prototypes

```
int GUI_TOUCH_X_MeasureX(void);

int GUI_TOUCH_X_MeasureY(void);
```

Example implementation

The following shows an example implementation of the touch hardware routines for a Renesas M16C/80 controller:

```
void GUI_TOUCH_X_ActivateX(void) {
  U8 Data;
  asm("fclr i");                    /* Disable interrupts            */
  Data = P10;                       /* Read port data                */
  Data |=  (1 << 2)  | (1 << 3);    /* Switch on power in X
                                       and enable measurement in Y   */
  Data &= ~((1 << 4) | (1 << 5));   /* Switch off power in Y
                                       and disable measurement in X  */
  P10  = Data;                      /* Write port data               */
  asm("fset i");                    /* Enable interrupts             */
}
void GUI_TOUCH_X_ActivateY(void) {
  U8 Data;
  asm("fclr i");                    /* Disable interrupts            */
  Data = P10;                       /* Read port data                */
  Data |=  (1 << 5)  | (1 << 4);    /* Switch on power in Y
                                       and enable measurement in X   */
  Data &= ~((1 << 3) | (1 << 2));   /* Switch off power in X
                                       and disable measurement in Y  */
  P10  = Data;                      /* Write port data               */
  asm("fset i");                    /* Enable interrupts             */
}
static void ReadADCx(int channel) {
  ADCON0 = channel                  /* Select channel 0-7            */
         | (0 << 3)                 /* One shot mode                 */
         | (0 << 6)                 /* A-D conversion start (0=stop) */
         | (0 << 7);                /* FAD/4 select                  */
  ADCON1 = (0 << 0)                 /* A-D sweep select (XX)         */
         | (0 << 2)                 /* No sweep mode                 */
         | (0 << 3)                 /* 8 bit mode                    */
         | (0 << 4)                 /* FAD4 select                   */
         | (1 << 5)                 /* VRef connected                */
         | (0 << 6);                /* Anex0/1 not used              */
  ADCON2 = (1 << 0);                /* Use example and hold          */
  ADIC   = 0;                       /* Reset IR flag                 */
  ADCON0 |= (1 << 6);               /* Start conversion              */
  while  ((ADIC & (1 << 3)) == 0); /* Wait for end of conversion    */
  ADCON0 &= ~(6 << 0);              /* Start conversion = 0          */
}
int GUI_TOUCH_X_MeasureX(void) {
  ReadADCx(0);
  return AD0;
}
int GUI_TOUCH_X_MeasureY(void) {
  ReadADCx(1);
  return AD1;
```

 © 2020 SEGGER Microcontroller GmbH

```
}
```

 © 2020 SEGGER Microcontroller GmbH

27.4.2.4 Driver API for analog touch screens

The table below lists the available analog touch screen driver routines in alphabetical order. These functions only apply if you are using the driver included with emWin.

Routine	Description
GUI_TOUCH_Calibrate()	Changes the calibration at runtime.
GUI_TOUCH_Exec()	Polls the touch-screen by calling the TOUCH_X routines to activate the measurement of the X- and Y-axes.
GUI_TOUCH_GetxPhys()	Returns a measurement value of the x-coordinate given from the A/D-converter.
GUI_TOUCH_GetyPhys()	Returns a measurement value of the y-coordinate given from the A/D-converter.
GUI_TOUCH_SetOrientation()	The function configures the touch screen orientation.

 © 2020 SEGGER Microcontroller GmbH

27.4.2.4.1 GUI_TOUCH_Calibrate()

Description

Changes the calibration at runtime.

Prototype

```
int GUI_TOUCH_Calibrate(int Coord,
                        int Log0,
                        int Log1,
                        int Phys0,
                        int Phys1);
```

Parameters

Parameter	Description
Coord	GUI_COORD_X for X-axis, GUI_COORD_Y for Y-axis.
Log0	Logical value 0 in pixels.
Log1	Logical value 1 in pixels.
Phys0	A/D converter value for Log0.
Phys1	A/D converter value for Log1.

Additional information

The function takes as parameters the axis to be calibrated, two logical values in pixels for this axis and two corresponding physical values of the A/D converter. Since the logical value Log0 usually is set to 0, Log1 should contain the (x- or y-)size decreased by 1.

 © 2020 SEGGER Microcontroller GmbH

27.4.2.4.2 GUI_TOUCH_Exec()

Description

Polls the touch-screen by calling the TOUCH_X routines to activate the measurement of the X- and Y-axes. It is required that this function is called for about 100 times per second, since there is only one axis measured per call. Therefore a complete measurement of the touch screen is done with 2 calls of GUI_TOUCH_Exec().

Prototype

```
void GUI_TOUCH_Exec(void);
```

Additional information

If you are using a real-time operating system, the easiest way to make sure this function is called is to create a separate task. When not using a multitask system, you can use an interrupt service routine to do the job. This function calls GUI_TOUCH_StoreState().

 © 2020 SEGGER Microcontroller GmbH

27.4.2.4.3 GUI_TOUCH_GetxPhys()

27.4.2.4.4 GUI_TOUCH_GetyPhys()

Description

Returns a measurement value of the y-coordinate given from the A/D-converter.

Prototype

```
int GUI_TOUCH_GetyPhys(void);
```

Return value

Measurement value of the x- or y-coordinate.

Additional information

A sample which shows how to use these functions is located in the folder `Sample\Tutorial` with the name `TOUCH_Sample.c`. Run this example on your hardware.

 © 2020 SEGGER Microcontroller GmbH

27.4.2.4.5 GUI_TOUCH_SetOrientation()

Description

The function configures the touch screen orientation. If the touch screen for example already has been configured to work with the default orientation and the display now needs to be turned or mirrored, this function can be used to configure the touch driver to use the same orientation as the display without changing anything at the hardware routines.

Prototype

```
void GUI_TOUCH_SetOrientation(unsigned Orientation);
```

Parameters

Parameter	Description
Orientation	One or more "OR"-combined values of the values to be found under *Orientation flags* on page 2638.

Permitted values for parameter Orientation	
GUI_MIRROR_X	Mirroring the X-axis.
GUI_MIRROR_Y	Mirroring the Y-axis.
GUI_SWAP_XY	Swapping X- and Y-axis.

Additional information

Please note that this function has no effect when passing touch in-out to emWin by using the functions GUI_PID_StoreState(), GUI_TOUCH_StoreState() and GUI_TOUCH_StoreStateEx().

 © 2020 SEGGER Microcontroller GmbH

27.4.2.5 Configuring the analog touch-screen driver

The touch screen driver is completely run-time configurable.
`GUI_TOUCH_Calibrate()` should be used to specify the physical values returned by the A/D converter for 2 positions per axis. If the display needs to be turned or mirrored, `GUI_TOUCH_SetOrientation()` can be used to set a new orientation without changing anything at the hardware routines.
Configuring the touch screen should be done before emWin manages any touch input.

Example

```
#define TOUCH_AD_LEFT  0x3c0
#define TOUCH_AD_RIGHT 0x034
#define TOUCH_AD_TOP  0x3b0
#define TOUCH_AD_BOTTOM 0x034
Orientation = (GUI_MIRROR_X * LCD_GetMirrorXEx(0)) |
              (GUI_MIRROR_Y * LCD_GetMirrorYEx(0)) |
              (GUI_SWAP_XY  * LCD_GetSwapXYEx (0)) ;
GUI_TOUCH_SetOrientation(Orientation);
GUI_TOUCH_Calibrate(GUI_COORD_X, 0, 319, TOUCH_AD_LEFT, TOUCH_AD_RIGHT);
GUI_TOUCH_Calibrate(GUI_COORD_Y, 0, 239, TOUCH_AD_TOP, TOUCH_AD_BOTTOM);
```

 © 2020 SEGGER Microcontroller GmbH

27.5 Touch screen Calibration

Normally a touch screen is mounted over the display. That means the data measured by the touch screen need to be translated into pixel coordinates of the display. To be able to do that transformation, the calibration algorithm needs to calculate transformation coefficients first. That can be done with a different number of points. The more points are available for coefficient calculation, the better the result. If rotation should be considered, at least 3 points are required for coefficient calculation.

2-Point Calibration

The classical calibration algorithm of emWin uses 2-point calibration. That means the calibration is done by passing 2 reference points (pixel coordinates) and 2 sample values (measurement results) for each axis to the calibration routine. Normally those points are near to the min- and max-values of each axis. The resulting calibration coefficients of a 2-point-calibration do not consider rotation. Only scaling and transformation could be considered. The following diagram shows the recommended position of the points to be used:



3-Point Calibration

A third calibration point makes it possible to consider scaling, transformation and rotation between reference- and sample values. The following diagram shows the recommended positon of the points to be used:



N-Point Calibration

The more points are available, the better is the result of coefficient calculation. The following diagrams show the recommended positions for a 5- and a 9-point calibration:

 © 2020 SEGGER Microcontroller GmbH



27.5.1 Using calibration with the analog touch screen driver

The analog touch screen driver shipped with emWin automatically uses the touch screen calibration routines. To be able to use it the calibration has to be initialized by calculating the calibration coefficients. That could be done by calling `GUI_TOUCH_Calibrate()` explained in chapter *The analog touch screen driver* on page 2450 for a 2-point calibration. If 3 or more points should be used the function `GUI_TOUCH_CalcCoefficients()` should be called.

27.5.2 Using calibration with a custom touch screen driver

If there is an already existing a touch screen driver available and the internal analog touch screen driver of emWin is not used, the way of using the calibration routines is different. The most simple way is calling `GUI_TOUCH_CalcCoefficients()` for coefficient calculation. The second step is calling `GUI_TOUCH_EnableCalibration()`. That makes sure, that all touch events will be calibrated automatically before they are stored into the PID-buffer of emWin. It is also possible to use the calibration API functions by the application before an event is stored into the PID buffer.

27.5.3 Calibration API

The table below lists the available calibration routines in alphabetical order.

Routine	Description
`GUI_TOUCH_CalcCoefficients()`	This routine is required for initializing the process of calibration.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUI_TOUCH_CalibratePoint()	The function converts the given sample point into screen coordinates in pixels and checks if the given values are within the display area.
GUI_TOUCH_EnableCalibration()	This function may be used if the calibration routines should be used with a custom touch screen driver.
GUI_TOUCH_TransformPoint()	Calibrates the given point without any check.

 © 2020 SEGGER Microcontroller GmbH

27.5.3.1 GUI_TOUCH_CalcCoefficients()

Description

This routine is required for initializing the process of calibration. To be able to calibrate a point via `GUI_TOUCH_CalibratePoint()` or `GUI_TOUCH_TransformPoint()` coefficient values are required for transforming the given values into pixel coordinates. These coefficients are calculated by the given reference values and the according sample values passed to this routine. As explained at the beginning of this subchapter coefficient calculation can be done with at least 2 points. To achieve the best possible result it is recommended to use 3 or more points.

Prototype

```
int GUI_TOUCH_CalcCoefficients(int   NumPoints,
                               int * pxRef,
                               int * pyRef,
                               int * pxSample,
                               int * pySample,
                               int   xSize,
                               int   ySize);
```

Parameters

Parameter	Description
`NumPoints`	Number of points used for calculating the calibration coefficients.
`pxRef`	Pointer to an array of reference values for X-axis.
`pyRef`	Pointer to an array of reference values for Y-axis.
`pxSample`	Pointer to an array of sample values for X-axis.
`pySample`	Pointer to an array of sample values for Y-axis.
`xSize`	X-size in pixels of the touch screen.
`ySize`	Y-size in pixels of the touch screen.

Return value

0 on success.
1 on error.

 © 2020 SEGGER Microcontroller GmbH

27.5.3.2 GUI_TOUCH_CalibratePoint()

Description

The function converts the given sample point into screen coordinates in pixels and checks if the given values are within the display area. If not an error is returned.

Prototype

```
int GUI_TOUCH_CalibratePoint(int * px,
                             int * py);
```

Parameters

Parameter	Description
px	Pointer to a sample coordinate of the X-axis.
py	Pointer to a sample coordinate of the Y-axis.

Return value

0 on success
1 on error.

Additional information

Coefficients need to be calculated first.

 © 2020 SEGGER Microcontroller GmbH

27.5.3.3 GUI_TOUCH_EnableCalibration()

Description

This function may be used if the calibration routines should be used with a custom touch screen driver. When using a custom touch screen driver normally `GUI_TOUCH_StoreState()` or `GUI_TOUCH_StoreStateEx()` is used for putting touch events into the PID-buffer of emWin. The default behavior of emWin is storing the coordinates into the buffer without calibration. If enabled each coordinate will be calibrated before it is stored into the buffer.

Prototype

```
void GUI_TOUCH_EnableCalibration(int OnOff);
```

Parameters

Parameter	Description
`OnOff`	1 for enabling calibration, 0 for disabling (default).

Additional information

When using the analog touch screen driver of emWin this function is not required.

 © 2020 SEGGER Microcontroller GmbH

27.5.3.4 GUI_TOUCH_TransformPoint()

Description

Calibrates the given point without any check.

Prototype

```
int GUI_TOUCH_TransformPoint(int * px,
                             int * py);
```

Parameters

Parameter	Description
px	Pointer to a sample coordinate of the X-axis.
py	Pointer to a sample coordinate of the Y-axis.

Return value

0 on success
1 on error.

Additional information

Coefficients need to be calculated first.

 © 2020 SEGGER Microcontroller GmbH

27.6 Joystick input example

The following example shows how the pointer input device API can be used to process the input from a joystick:

```
/*********************************************************************
*
*         _JoystickTask
*
* Purpose:
*   Periodically read the Joystick and inform emWin using
*   GUI_PID_StoreState.
*   It supports dynamic acceleration of the pointer.
*   The Joystick is a simple, standard 5 switch (digital) type.
*
*/
static void _JoystickTask(void) {
  GUI_PID_STATE State;
  int Stat;
  int StatPrev = 0;
  int TimeAcc = 0;   // Dynamic acceleration value
  int xMax, yMax;

  xMax = LCD_GetXSize() - 1;
  yMax = LCD_GetYSize() - 1;
  while (1) {
    Stat = HW_ReadJoystick();
    //
    // Handle dynamic pointer acceleration
    //
    if (Stat == StatPrev) {
      if (TimeAcc < 10) {
        TimeAcc++;
      }
    } else {
      TimeAcc = 1;
    }
    if (Stat || (Stat != StatPrev)) {
      //
      // Compute the new coordinates
      //
      GUI_PID_GetState(&State);
      if (Stat & JOYSTICK_LEFT) {
        State.x -= TimeAcc;
      }
      if (Stat & JOYSTICK_RIGHT) {
        State.x += TimeAcc;
      }
      if (Stat & JOYSTICK_UP) {
        State.y -= TimeAcc;
      }
      if (Stat & JOYSTICK_DOWN) {
        State.y += TimeAcc;
      }
      //
      // Make sure coordinates are still in bounds
      //
      if (State.x < 0) {
        State.x = 0;
      }
      if (State.y < 0) {
        State.y = 0;
      }
      if (State.x >= xMax) {
        State.x = xMax;
      }
      if (State.y > yMax) {
```

 © 2020 SEGGER Microcontroller GmbH

```
        State.y = yMax;
      }
      //
      // Inform emWin
      //
      State.Pressed = (Stat & JOYSTICK_ENTER) ? 1: 0;
      GUI_PID_StoreState(&State);
      StatPrev = Stat;
    }
    OS_Delay(40);
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

Chapter 28

MultiTouch support (MT)

Initially the concept of emWin was based on a single touch and keyboard interface. Since smartphones with MultiTouch capabilities became more and more attractive, it was a need to implement MultiTouch capabilities also to emWin. The emWin implementation is able to recognize up to 10 touch points, whereas the maximum number of touch points is limited by the target hardware.

Single touch screens usually consist of resistive touch panels. Most of the MultiTouch panels are capacitive panels which behave different to resistive panels. Whereas a resistive touch panel needs a noticeable pressure, a capacitive panel just requires a smooth touch for recognizing the touch event.

MultiTouch support is an add-on and not part of the emWin basic package. It has to be purchased separately. The emWin Simulation supports the MultiTouch feature, so it is possible to evaluate MultiTouch samples which are provided on www.segger.com. To do so it is necessary to have a MultiTouch display connected to the computer.

The following chapter shows the implementation of MultiTouch functionality in emWin.

 © 2020 SEGGER Microcontroller GmbH

28.1 Introduction

A MultiTouch panel enables the application to react on multiple touch point inputs simultaneously. The implementation of MT support in emWin offers different consecutive levels of MT access:

- Basic buffer access
- Gesture support (requires the Window Manager)
- Automatic window animation (requires the Window Manager) Gesture support requires basic buffer access, window animation is based on gesture support.

Basic buffer access

The MT buffer is able to store a configurable number of MT events. The buffer access API functions consists of functions for storing new events, polling the buffer, setting the touch screen orientation and basically enabling MT support. A detailed description of the available API functions follows later.

Gesture support

This level of MT support is responsible for gesture recognition and requires the window manager. If a gesture is detected, a `WM_GESTURE` message with more detailed information is send to the according window. It can be used to modify any kind of data. Detailed descriptions how to use the gesture messages follow later.

Window animation

emWin also offers the possibility for automatic window animation via gesture support. Windows can be moved and resized automatically by gesture input. This can be achieved simply by setting the according flags when creating the window. It does not include automatic resizing of fonts and objects shown in the window. This need to be done by the application based on a factor which is passed to/from the application. Details follow later in this chapter.

 © 2020 SEGGER Microcontroller GmbH

28.2 Getting started

Only a few things need to be considered to be able to use MT support. It needs to be enabled, the MT buffer needs to be filled and it must be ensured that the buffer is polled by emWin if gesture support or window animation is required.

Enabling MS support

To be able to use MT support it needs to be enabled once. It is recommended to do that immediately after the initialization:

```
void MainTask(void) {
  GUI_Init();
  GUI_MTOUCH_Enable(1);
}
```

Filling the MT buffer

Further it is required to fill the MT buffer with MT events. That can be done either by an existing MT driver like `GUIMTDRV_TangoC32` or by filling the buffer by a custom driver. In case of using a custom driver the function `GUI_MTOUCH_StoreEvent()` needs to be used to do that. The function will be explained later in detail.

Polling the MT buffer

Once MT support has been enabled, the window manager (WM) automatically polls the MT buffer. That is done when executing an emWin update function (typically `GUI_Exec()`, `GUI_Delay()` or `WM_Exec()`). If no gesture support is required the buffer can also be polled manually by the functions `GUI_MTOUCH_GetEvent()` and `GUI_MTOUCH_GetTouchInput()`. In case of automatic polling by emWin the gesture detecting module will automatically send `WM_GESTURE` messages to the according window.

 © 2020 SEGGER Microcontroller GmbH

28.3 Using basic buffer access

The functions explained later under *Basic buffer access API* on page 2480 can be used for that. Polling works as follows:

Polling an MT event from the buffer

`GUI_MTOUCH_GetEvent()` should be used to get an existing MT event from the buffer. It passes a pointer to a `GUI_MTOUCH_EVENT` structure to the function to be filled with information like the number of touch points of the current event. If the function fails there is no existing event. Otherwise the `GUI_MTOUCH_EVENT` structure contains the number of touch points associated to the event.

Getting the touch points of an MT event

`GUI_MTOUCH_GetTouchInput()` should be used for getting the point information for each single touch point. It passes a pointer to a `GUI_MTOUCH_INPUT` structure to the function to be filled by the function. That information comprises position, ID and flags.

Example 1

The following code shows a very simple function which continuously polls the MT buffer and draws each touch point:

```
#include "GUI.h"
void MainTask(void) {
  GUI_MTOUCH_EVENT Event;
  GUI_MTOUCH_INPUT Input;
  unsigned i;
  GUI_Init();
  GUI_MTOUCH_Enable(1);
  GUI_SetPenSize(5);
  do {
    if (GUI_MTOUCH_GetEvent(&Event) == 0) {
      for (i = 0; i < Event.NumPoints; i++) {
        GUI_MTOUCH_GetTouchInput(&Event, &Input, i);
        GUI_DrawPoint(Input.x, Input.y);
      }
    }
    GUI_Delay(1);
 } while (1);
}
```

Screenshot of above sample



 © 2020 SEGGER Microcontroller GmbH

Example 2

The sample folder of emWin contains the sample `MTOUCH_ScratchAndGestures.c`. It can be used to get more familiar with processing basic buffer access and MT support. It contains a scratchpad sub sample which detects multiple points and uses their IDs for assigning a unique color.

Screenshot



 © 2020 SEGGER Microcontroller GmbH

28.4 Using gestures

Gestures in emWin are based on motion detection via MultiTouch panel. Each gesture starts by detecting the first touch input and ends on releasing it.

Requirements

To be able to use gesture support, the following needs to be considered:

- MT support needs to be enabled.
- Gesture support needs to be enabled via `WM_GESTURE_Enable()`.
- The flag `WM_CF_GESTURE` needs to be set by the according window.

Supported gestures

The following table gives an overview of the currently supported gestures:

Gesture	Touch points	Description
Panning	1	Dependent on the first motion detection the gesture supports motion on one axis (X or Y) or both simultaneous.
Zooming	2	This gesture is started when detecting a relative motion between 2 touch points and can be used to scale an object. Can be combined with rotating and panning.
Rotating	2	When detecting initially a change of the angle between 2 touch points rotation gesture is started. Can be combined with zooming and panning.

Processing gesture input

Gesture input is send to the according window by a `WM_GESTURE` message. For detailed gesture information a pointer to a structure of type `WM_GESTURE_INFO` (explained in detail below) is passed to the window. The "Flags" element of that structure is used to specify the kind of information passed to the window.

The supported flags are listed under *MultiTouch gesture flags* on page 2492.

The structure explained under *`WM_GESTURE_INFO`* on page 2489 explains all elements which are relevant for processing gesture messages. The `pZoomInfo` element should not be used by the application.

Example

The sample folder of emWin contains the sample `MTOUCH_ScratchAndGestures.c`. It can be used to get more familiar with processing gestures and MT support. It contains a sub sample which animates a small vector graphic by gesture functions.

 © 2020 SEGGER Microcontroller GmbH

Screenshot



 © 2020 SEGGER Microcontroller GmbH

28.5 Window animation

Automatic window animation can be used to scale and pan windows automatically by gesture input. Currently that feature can be used for bare windows and can not be used with any of the widgets. Scaling of objects shown within scaled windows need to be done by the application. For that purpose the element "Factor" of the `WM_GESTURE_INFO` structure can be used as explained in the following.

Requirements

To be able to use automatic window animation, the following needs to be considered:

- MT support needs to be enabled.
- Gesture support needs to be enabled via `WM_GESTURE_Enable()`.
- The window flags `WM_CF_GESTURE` and `WM_CF_ZOOM` need to be set.
- The window has to pass a pointer to a `WM_ZOOM_INFO` structure on demand.

Reacting on gestures

Processing automatic window animation is similar to bare gesture support with the difference, that the object to be animated is the window itself which is modified automatically by emWin. But to be able to do this automatic animation the window manager needs additional information. This is done by passing a pointer to a `WM_ZOOM_INFO` structure to the WM. It is passed by the `pZoomInfo` element of the structure `WM_GESTURE_INFO`.

Limits

The window to be animated can be moved and scaled by using the parent window as a kind of view port. If the size of the animated window is larger than the parent the WM makes sure that the zoomed window covers the complete area of the parent window. If it is smaller the WM makes sure, that it is not moved over the parents border.

Scalable fonts

Text can be rendered at different sizes using scalable TrueType fonts. This requires a fast CPU and a reasonable amount of RAM and ROM. Details can be found in the chapter *TrueType Font (TTF) format* on page 470.

 © 2020 SEGGER Microcontroller GmbH

28.6 Basic buffer access API

The table below lists the available MT buffer access routines in alphabetical order. Detailed descriptions follow:

Functions

Routine	Description
GUI_MTOUCH_Enable()	This routine needs to be called to enable the MT buffer.
GUI_MTOUCH_GetEvent()	Returns an event and removes it from the buffer.
GUI_MTOUCH_GetTouchInput()	This function is responsible for getting information of a dedicated touch point.
GUI_MTOUCH_IsEmpty()	Returns if the MT buffer is empty or not.
GUI_MTOUCH_SetOrientation()	This function can be used to set the touch screen orientation, e.g.
GUI_MTOUCH_StoreEvent()	Routine to be used by the touch screen driver to store a new event with associated touch points into the MT buffer.

Data structures

Structure	Description
GUI_MTOUCH_EVENT	Data structure used by GUI_MTOUCH_GetEvent() to store a multi touch event in.
GUI_MTOUCH_INPUT	Data structure used by GUI_MTOUCH_GetEvent() to store a multi touch event in.
WM_GESTURE_INFO	Stores the information about a gesture.
WM_ZOOM_INFO	

Defines

Group of defines	Description
MultiTouch flags	Data structure used by GUI_MTOUCH_GetEvent() to store a multi touch event in.
MultiTouch gesture flags	Flags used for processing gesture input.

 © 2020 SEGGER Microcontroller GmbH

28.6.1 Functions

28.6.1.1 GUI_MTOUCH_Enable()

Description

This routine needs to be called to enable the MT buffer.

Prototype

```
void GUI_MTOUCH_Enable(int OnOff);
```

Parameters

Parameter	Description
OnOff	1 for enabling the buffer, 0 for disabling.

 © 2020 SEGGER Microcontroller GmbH

28.6.1.2 GUI_MTOUCH_GetEvent()

Description

Returns an event and removes it from the buffer.

Prototype

```
int GUI_MTOUCH_GetEvent(GUI_MTOUCH_EVENT * pEvent);
```

Parameters

Parameter	Description
pEvent	Pointer to a structure of type GUI_MTOUCH_EVENT to be filled by the function.

Return value

0 on success
1 if the function fails. Can be used to check if an event was available or not.

Additional information

The most important information returned by that function is the availability of an event and how many touch points are available. Further the time stamp may be of interest which is filled automatically on storing an event into the buffer.

 © 2020 SEGGER Microcontroller GmbH

28.6.1.3 GUI_MTOUCH_GetTouchInput()

Description

This function is responsible for getting information of a dedicated touch point. It requires a pointer to a GUI_MTOUCH_EVENT structure previously filled by GUI_MTOUCH_GetEvent() and a pointer to a GUI_MTOUCH_INPUT structure to be filled by this function with the touchpoint details.

Prototype

```
int GUI_MTOUCH_GetTouchInput(GUI_MTOUCH_EVENT * pEvent,
                             GUI_MTOUCH_INPUT * pInput,
                             unsigned           Index);
```

Parameters

Parameter	Description
pEvent	Pointer to the event structure filled by GUI_MTOUCH_GetEvent().
pBuffer	Pointer to a structure of type GUI_MTOUCH_INPUT to be filled by the function.
Index	Index of the requested touch point.

Return value

0 on success
1 on error.

Additional information

The parameter Index needs to be < the available number of touch points. A unique Id is normally managed the touch controller which is passed by the Id element of GUI_MTOUCH_INPUT.

 © 2020 SEGGER Microcontroller GmbH

28.6.1.4 GUI_MTOUCH_IsEmpty()

Description

Returns if the MT buffer is empty or not.

Prototype

```
int GUI_MTOUCH_IsEmpty(void);
```

Return value

1	if buffer is empty.
0	if it contains MT events.

 © 2020 SEGGER Microcontroller GmbH

28.6.1.5 GUI_MTOUCH_SetOrientation()

Description

This function can be used to set the touch screen orientation, e.g. if the display does not operate by the default orientation or if the display orientation is different to the MT orientation.

Prototype

```
void GUI_MTOUCH_SetOrientation(int Orientation);
```

Parameters

Parameter	Description
Orientation	One or more “OR” combined values of the table below

 © 2020 SEGGER Microcontroller GmbH

28.6.1.6 GUI_MTOUCH_StoreEvent()

Description

Routine to be used by the touch screen driver to store a new event with associated touch points into the MT buffer. The number of available touch points is passed by the NumPoints element of the structure pointed by pEvent. pInput then points to an array of GUI_MTOUCH_INPUT structures containing the information of each touch point.

Prototype

```
void GUI_MTOUCH_StoreEvent(GUI_MTOUCH_EVENT * pEvent,
                           GUI_MTOUCH_INPUT * pInput);
```

Parameters

Parameter	Description
pEvent	Pointer to a structure of type GUI_MTOUCH_EVENT.
pInput	Pointer to the first element of an array of GUI_MTOUCH_INPUT structures.

Additional information

The number of possible touch points is limited per default to 10. The new event will automatically get a time stamp information which can be used later.

> **Note**
>
> Make sure that the element Id of GUI_MTOUCH_INPUT is ≠ 0.

 © 2020 SEGGER Microcontroller GmbH

28.6.2 Data structures

28.6.2.1 GUI_MTOUCH_EVENT

Description

Data structure used by `GUI_MTOUCH_GetEvent()` to store a multi touch event in.

Type definition

```
typedef struct {
  int             LayerIndex;
  unsigned        NumPoints;
  GUI_TIMER_TIME  TimeStamp;
  PTR_ADDR        hInput;
} GUI_MTOUCH_EVENT;
```

Structure members

Member	Description
`LayerIndex`	Layer index of touched layer (normally 0).
`NumPoints`	Number of available touch points.
`TimeStamp`	Time stamp in ms of that event.
`hInput`	Internal use.

 © 2020 SEGGER Microcontroller GmbH

28.6.2.2 GUI_MTOUCH_INPUT

Description

Data structure used by `GUI_MTOUCH_GetEvent()` to store a multi touch event in.

Type definition

```
typedef struct {
  I32  x;
  I32  y;
  U32  Id;
  U16  Flags;
} GUI_MTOUCH_INPUT;
```

Structure members

Member	Description
x	X-position in pixels of the touch point.
y	Y-position in pixels of the touch point.
Id	Unique Id, should be provided by the touch driver. Make sure that this element is ≠ 0.
Flags	See *MultiTouch flags* on page 2491.

 © 2020 SEGGER Microcontroller GmbH

28.6.2.3 WM_GESTURE_INFO

Description

Stores the information about a gesture.

Type definition

```
typedef struct {
  int            Flags;
  GUI_POINT      Point;
  GUI_POINT      Center;
  I32            Angle;
  I32            Factor;
  WM_ZOOM_INFO * pZoomInfo;
} WM_GESTURE_INFO;
```

Structure members

Member	Description
Flags	Information regarding gesture type. See *MultiTouch gesture flags* on page 2492.
Point	Relative movement to be processed by the application.
Center	Center point for zooming.
Angle	Relative angle difference to be processed by the application.
Factor	When starting a zoom gesture the application has to set the element to the initial value for the gesture. After that during the gesture it contains the updated value to be processed by the application.
pZoomInfo	Pointer to be set to a valid location of a WM_ZOOM_INFO structure. The application should keep sure, that the location remains valid during the gesture.

 © 2020 SEGGER Microcontroller GmbH

28.6.2.4 WM_ZOOM_INFO

Type definition

```
typedef struct {
  I32        FactorMin;
  I32        FactorMax;
  U32        xSize;
  U32        ySize;
  U32        xSizeParent;
  U32        ySizeParent;
  I32        Factor0;
  int        xPos0;
  int        yPos0;
  GUI_POINT  Center0;
} WM_ZOOM_INFO;
```

Structure members

Member	Description
FactorMin	Minimum factor to be used (<< 16).
FactorMax	Maximum factor to be used (<< 16).
xSize	Native xSize of window to be zoomed in pixels.
ySize	Native ySize of window to be zoomed in pixels.
xSizeParent	Internal use.
ySizeParent	Internal use.
Factor0	Internal use.
xPos0	Internal use.
yPos0	Internal use.
Center0	Internal use.

 © 2020 SEGGER Microcontroller GmbH

28.6.3 Defines

28.6.3.1 MultiTouch flags

Description

Data structure used by `GUI_MTOUCH_GetEvent()` to store a multi touch event in.

Definition

```
#define GUI_MTOUCH_FLAG_DOWN    (1 << 0)
#define GUI_MTOUCH_FLAG_MOVE    (1 << 1)
#define GUI_MTOUCH_FLAG_UP      (1 << 2)
```

Symbols

Definition	Description
GUI_MTOUCH_FLAG_DOWN	New touch point has touched the surface.
GUI_MTOUCH_FLAG_MOVE	Touch point has been moved.
GUI_MTOUCH_FLAG_UP	Touch point has released the surface.

 © 2020 SEGGER Microcontroller GmbH

28.6.3.2 MultiTouch gesture flags

Description

Flags used for processing gesture input.

Definition

```
#define WM_GF_BEGIN     (1 << 0)
#define WM_GF_END       (1 << 1)
#define WM_GF_PAN       (1 << 2)
#define WM_GF_ZOOM      (1 << 3)
#define WM_GF_ROTATE    (1 << 4)
#define WM_GF_DTAP      (1 << 5)
```

Symbols

Definition	Description
WM_GF_BEGIN	This flag is set when sending the first message for the gesture.
WM_GF_END	A panning gesture is detected. The element “Point” of WM_GESTURE_INFO contains the relative movement in pixels to be processed by the application.
WM_GF_PAN	Rotation is active. The element “Angle” of WM_GESTURE_INFO contains the relative movement in degrees (<< 16) to be processed by the application. To be able to achieve a smooth rotation the value is passed in 1/65536 degrees. If movement should be considered simultaneously the element “Point” contains also the relative movement.
WM_GF_ZOOM	Zooming is active. When starting a zooming gesture the element “Factor” of WM_GESTURE_INFO has to be set to the initial value to be used by the gesture. During the gesture the same element contains the updated value to be processed by the application. If movement should be considered simultaneously the element “Point” contains also the relative movement.
WM_GF_ROTATE	Set when releasing a touch point at the end of a gesture.
WM_GF_DTAP	Internal use.

 © 2020 SEGGER Microcontroller GmbH

Chapter 29

Keyboard Input

emWin provides support for any kind of keyboards. Any type of keyboard driver is compatible with emWin.
The software for keyboard input is located in the subdirectory `GUI\Core` and part of the basic package.

 © 2020 SEGGER Microcontroller GmbH

29.1 Description

A keyboard input device uses ASCII character coding in order to be able to distinguish between characters. For example, there is only one "A" key on the keyboard, but an uppercase "A" and a lowercase "a" have different ASCII codes (`0x41` and `0x61`, respectively).

emWin predefined character codes

emWin also defines character codes for other "virtual" keyboard operations. These codes are listed in the table below, and defined in an identifier table in `GUI.h`. A character code in emWin can therefore be any extended ASCII character value or any of the following predefined emWin values.

Predefined virtual key code	Description
GUI_KEY_BACKSPACE	Backspace key.
GUI_KEY_TAB	Tab key.
GUI_KEY_BACKTAB	Shift + Tab key.
GUI_KEY_ENTER	Enter/return key.
GUI_KEY_LEFT	Left arrow key.
GUI_KEY_UP	Up arrow key.
GUI_KEY_RIGHT	Right arrow key.
GUI_KEY_DOWN	Down arrow key.
GUI_KEY_HOME	Home key (move to beginning of current line).
GUI_KEY_END	End key (move to end of current line).
GUI_KEY_SHIFT	Shift key.
GUI_KEY_CONTROL	Control key.
GUI_KEY_ESCAPE	Escape key.
GUI_KEY_INSERT	Insert key.
GUI_KEY_DELETE	Delete key.
GUI_KEY_SPACE	Space key.
GUI_KEY_PGUP	Page up key.
GUI_KEY_PGDOWN	Page down key.

 © 2020 SEGGER Microcontroller GmbH

29.2 Driver layer API

The keyboard driver layer handles keyboard messaging functions. These routines notify the Window Manager when specific keys (or combinations of keys) have been pressed or released. The table below lists the driver-layer keyboard routines in alphabetical order. Detailed descriptions follow.

Routine	Description
GUI_StoreKeyMsg()	Stores a key message in the keyboard buffer.
GUI_SendKeyMsg()	Sends a key message to the window with the input focus.

 © 2020 SEGGER Microcontroller GmbH

29.2.1 GUI_StoreKeyMsg()

Description

Stores a key message in the keyboard buffer.

Prototype

```
void GUI_StoreKeyMsg(int Key,
                     int PressedCnt);
```

Parameters

Parameter	Description
Key	May be any extended ASCII character (between 0x20 and 0xFF) or any predefined emWin character code.
Pressed	Key state. See table below.

Permitted values for parameter Pressed	
1	Pressed state.
0	Released (unpressed) state.

Additional information

This function can be used from an interrupt service routine. The keyboard input manager of emWin contains a FIFO buffer which is able to hold up to 10 keyboard events per default. If a different size is required this value can be changed. Details can be found in the section *Advanced GUI configuration options* on page 2901.
The Window Manager polls the keyboard buffer automatically and sends according keyboard messages to the currently focussed window.

 © 2020 SEGGER Microcontroller GmbH

29.2.2 GUI_SendKeyMsg()

Description

Sends a key message to the window with the input focus. If no window has the input focus, the function `GUI_StoreKeyMsg()` is called to store the data to the input buffer.

Prototype

```
void GUI_SendKeyMsg(int Key,
                    int PressedCnt);
```

Parameters

Parameter	Description
`Key`	May be any extended ASCII character (between `0x20` and `0xFF`) or any predefined emWin character code.
`Pressed`	`Key` state (see `GUI_StoreKeyMsg()`).

Additional information

This function should not be called from an interrupt service routine.

 © 2020 SEGGER Microcontroller GmbH

29.3 Application layer API

The table below lists the application-layer keyboard routines in alphabetical order. Detailed descriptions follow.

Routine	Description
GUI_ClearKeyBuffer()	Clears the key buffer.
GUI_GetKey()	Returns the current content of the key buffer.
GUI_GetKeyState()	Returns the current key state.
GUI_StoreKey()	Stores a key in the buffer.
GUI_WaitKey()	Waits for a key to be pressed.

 © 2020 SEGGER Microcontroller GmbH

29.3.1 GUI_ClearKeyBuffer()

Description

Clears the key buffer.

Prototype

```
void GUI_ClearKeyBuffer(void);
```

 © 2020 SEGGER Microcontroller GmbH

29.3.2 GUI_GetKey()

Description

Returns the current content of the key buffer.

Prototype

```
int GUI_GetKey(void);
```

Return value

Codes of characters in the key buffer; 0 if no key is buffered.

 © 2020 SEGGER Microcontroller GmbH

29.3.3 GUI_GetKeyState()

Description

Returns the current key state.

Prototype

```
void GUI_GetKeyState(GUI_KEY_STATE * pState);
```

Parameters

Parameter	Description
pState	This structure is filled by the function. See elements below.

Elements of structure GUI_KEY_STATE

Data type	Element	Description
int	Key	Key code.
int	Pressed	1, if the key is pressed. 0, if the key is not pressed. -1, if the state could not be determined.

 © 2020 SEGGER Microcontroller GmbH

29.3.4 GUI_StoreKey()

Description

Stores a key in the buffer.

Prototype

```
void GUI_StoreKey(int Key);
```

Parameters

Parameter	Description
Key	May be any extended ASCII character (between 0x20 and 0xFF) or any predefined emWin character code.

Additional information

This function is typically called by the driver and not by the application itself.

 © 2020 SEGGER Microcontroller GmbH

29.3.5 GUI_WaitKey()

Description

Waits for a key to be pressed.

Prototype

```
int GUI_WaitKey(void);
```

Return value

The pressed key.

Additional information

The application is “blocked”, meaning it will not return until a key is pressed.

 © 2020 SEGGER Microcontroller GmbH

Chapter 30

Sprites

A **sprite** is an image which can be shown above all other graphics on the screen. A sprite preserves the screen area it covers. It can be moved or removed at any time, fully restoring the screen content. Animation by use of multiple images is possible. Sprites are completely independent from all other drawing operations as well as window operations: sprites do not affect drawing or window operations; drawing or window operations do not affect sprites. Sprites can be seen as objects which are sitting "on top" of the screen, similar to cursors.



 © 2020 SEGGER Microcontroller GmbH

30.1 Introduction

emWin Sprites are implemented as a pure software solution. No additional hardware is required to use emWin Sprites. They can be shown, moved and deleted without affecting already visible graphics.

Memory requirements

Each sprite needs a memory area for saving the display data 'behind' the sprite to be able to restore the background on moving operations or on removing the sprite. Further a memory area for a color cache is required. The size of the color cache depends on the number of colors used in the sprite image. So the complete number of bytes required for a sprite can be calculated as follows:

```
SizeOfSpriteObject (~30 bytes) + (XSize × YSize + NumberOfBitmapColors) ×
 REQUIRED_BYTES_PER_PIXEL
```

Maximum number of Sprites

The number of simultaneous visible sprites is not limited by emWin. It depends only on the available memory.

Performance

Note that drawing a sprite is more computer-bound than drawing a simple bitmap, because it has to manage the background data and intersections with other sprites.

Z-order

Z-order is an ordering of overlapping two-dimensional objects, in this case the sprites. When two sprites overlap, their Z-order determines which one appears on top of the other. The sprite created at last is the topmost sprite.

 © 2020 SEGGER Microcontroller GmbH

30.2 Sprite API

The table below lists the available Sprite-related routines in alphabetical order. Detailed descriptions follow:

Routine	Description
GUI_SPRITE_Create()	Creates a Sprite at the given position in the current layer.
GUI_SPRITE_CreateAnim()	Creates an animated Sprite at the given position in the current layer.
GUI_SPRITE_CreateEx()	Creates a Sprite at the given position in the desired layer.
GUI_SPRITE_CreateExAnim()	Creates an animated Sprite at the given position in the current layer.
GUI_SPRITE_CreateHidden()	Creates a hidden Sprite at the given position in the current layer.
GUI_SPRITE_CreateHiddenEx()	Creates a hidden Sprite at the given position in the given layer.
GUI_SPRITE_Delete()	Deletes the given Sprite.
GUI_SPRITE_GetState()	Returns if the given Sprite is visible or not.
GUI_SPRITE_Hide()	Hides the given Sprite.
GUI_SPRITE_SetBitmap()	Sets a new image for drawing the Sprite.
GUI_SPRITE_SetBitmapAndPosition()	Sets the position and the image at once.
GUI_SPRITE_SetLoop()	Enables/Disables infinite animation of the given Sprite.
GUI_SPRITE_SetPosition()	Moves the Sprite to the new position.
GUI_SPRITE_Show()	Shows the given Sprite.
GUI_SPRITE_StartAnim()	Starts the animation of the given Sprite.
GUI_SPRITE_StopAnim()	Stops the animation of the given Sprite.

 © 2020 SEGGER Microcontroller GmbH

30.2.1 GUI_SPRITE_Create()

Description

Creates a Sprite at the given position in the current layer.

Prototype

```
GUI_HSPRITE GUI_SPRITE_Create(const GUI_BITMAP * pBM,
                              int          x,
                              int          y);
```

Parameters

Parameter	Description
pBM	Pointer to a bitmap structure to be used for drawing the Sprite.
x	X-position of the Sprite in screen coordinates.
y	Y-position of the Sprite in screen coordinates.

Return value

Handle of the new Sprite, 0 on failure.

Additional information

The bitmap addressed by the parameter pBM needs to agree with the following requirements:

- It should not be compressed.
- It needs to be transparent.
- It needs to be a palette based bitmap with 1, 2, 4 or 8bpp or, if semi transparency is required, a true color bitmap. Other bitmaps or insufficient memory cause the function to fail.

 © 2020 SEGGER Microcontroller GmbH

30.2.2 GUI_SPRITE_CreateAnim()

Description

Creates an animated Sprite at the given position in the current layer.

Prototype

```
GUI_HSPRITE GUI_SPRITE_CreateAnim(const GUI_BITMAP ** ppBm,
                                  int              x,
                                  int              y,
                                  unsigned         Period,
                                  const unsigned    * pPeriod,
                                  int              NumItems);
```

Parameters

Parameter	Description
ppBM	Pointer to an array of bitmap pointers to be used for drawing the Sprite.
x	X-position of the Sprite in screen coordinates.
y	Y-position of the Sprite in screen coordinates.
Period	Period to be used to switch between the images.
pPeriod	Pointer to an array containing the periods to be used to switch between the images.
NumItems	Number of images.

Return value

Handle of the new Sprite, 0 on failure.

Additional information

The bitmaps addressed by the parameter ppBM needs to agree with the following requirements:

- They need to have exactly the same X- and Y-size.
- They should not be compressed.
- They need to be transparent.
- They need to be palette based bitmaps with 1, 2, 4 or 8bpp or, if semi-transparency is required, true color bitmaps. Using bitmaps which do not match above criteria causes the function to fail as well as insufficient memory. The parameter pPeriod is required, only if the periods for the images are different. If the same period should be used for all images the parameter Period should be used. In this case pPeriod can be NULL. In case pPeriod is used, the animation will stop at the according image if one of the timer values is 0.

 © 2020 SEGGER Microcontroller GmbH

30.2.3 GUI_SPRITE_CreateEx()

Description

Creates a Sprite at the given position in the desired layer.

Prototype

```
GUI_HSPRITE GUI_SPRITE_CreateEx(const GUI_BITMAP * pBM,
                                int           x,
                                int           y,
                                int           Layer);
```

Parameters

Parameter	Description
pBM	Pointer to a bitmap structure to be used for drawing the Sprite.
x	X-position of the Sprite in screen coordinates.
y	Y-position of the Sprite in screen coordinates.
Layer	Layer of Sprite.

Return value

Handle of the new Sprite, 0 on failure.

Additional information

Additional information can be found under GUI_SPRITE_Create().

 © 2020 SEGGER Microcontroller GmbH

30.2.4 GUI_SPRITE_CreateExAnim()

Description

Creates an animated Sprite at the given position in the current layer.

Prototype

```
GUI_HSPRITE GUI_SPRITE_CreateExAnim(const GUI_BITMAP ** ppBm,
                                          int           x,
                                          int           y,
                                          unsigned      Period,
                                    const unsigned    * pPeriod,
                                          int           NumItems,
                                          int           LayerIndex);
```

Parameters

Parameter	Description
ppBM	Pointer to an array of bitmap pointers to be used for drawing the Sprite.
x	X-position of the Sprite in screen coordinates.
y	Y-position of the Sprite in screen coordinates.
Period	Period to be used to switch between the images.
pPeriod	Pointer to an array containing values to be used to switch between the images.
NumItems	Number of images.
LayerIndex	Layer of Sprite.

Return value

Handle of the new Sprite, 0 on failure.

Additional information

Additional information can be found under GUI_SPRITE_CreateAnim().

 © 2020 SEGGER Microcontroller GmbH

30.2.5 GUI_SPRITE_CreateHidden()

Description

Creates a hidden Sprite at the given position in the current layer.

Prototype

```
GUI_HSPRITE GUI_SPRITE_CreateHidden(const GUI_BITMAP * pBM,
                                    int           x,
                                    int           y);
```

Parameters

Parameter	Description
pBM	Pointer to a bitmap structure to be used for drawing the Sprite.
x	X-position of the Sprite in screen coordinates.
y	Y-position of the Sprite in screen coordinates.

Return value

Handle of the new Sprite, 0 on failure.

Additional information

More details can be found in the description of `GUI_SPRITE_Create()`.

 © 2020 SEGGER Microcontroller GmbH

30.2.6 GUI_SPRITE_CreateHiddenEx()

Description

Creates a hidden Sprite at the given position in the given layer.

Prototype

```
GUI_HSPRITE GUI_SPRITE_CreateHiddenEx(const GUI_BITMAP * pBM,
                                      int          x,
                                      int          y,
                                      int          Layer);
```

Parameters

Parameter	Description
pBM	Pointer to a bitmap structure to be used for drawing the Sprite.
x	X-position of the Sprite in screen coordinates.
y	Y-position of the Sprite in screen coordinates.
Layer	Layer to be used.

Return value

Handle of the new Sprite, 0 on failure.

Additional information

More details can be found in the description of GUI_SPRITE_Create().

 © 2020 SEGGER Microcontroller GmbH

30.2.7 GUI_SPRITE_Delete()

Description

Deletes the given Sprite.

Prototype

```
void GUI_SPRITE_Delete(GUI_HSPRITE hSprite);
```

Parameters

Parameter	Description
hSprite	Handle of Sprite to be deleted.

Additional information

The function deletes the Sprite from the memory and restores its background automatically.

 © 2020 SEGGER Microcontroller GmbH

30.2.8 GUI_SPRITE_GetState()

Description

Returns if the given Sprite is visible or not.

Prototype

```
int GUI_SPRITE_GetState(GUI_HSPRITE hSprite);
```

Parameters

Parameter	Description
hSprite	Handle of Sprite.

Return value

1 if the Sprite is visible.
0 if not.

 © 2020 SEGGER Microcontroller GmbH

30.2.9 GUI_SPRITE_Hide()

Description

Hides the given Sprite.

Prototype

```
void GUI_SPRITE_Hide(GUI_HSPRITE hSprite);
```

Parameters

Parameter	Description
hSprite	Handle of Sprite to hide.

Additional information

The function removes the given Sprite from the list of visible Sprites.

 © 2020 SEGGER Microcontroller GmbH

30.2.10 GUI_SPRITE_SetBitmap()

Description

Sets a new image for drawing the Sprite.

Prototype

```
int GUI_SPRITE_SetBitmap(      GUI_HSPRITE   hSprite,
                         const GUI_BITMAP  * pBM);
```

Parameters

Parameter	Description
hSprite	Handle of Sprite.
pBM	Pointer to a bitmap structure to be used for drawing the Sprite.

Return value

0 on success
1 on error.

Additional information

The new bitmap must have exact the same size as the previous one. Passing a pointer to a bitmap of a different size causes the function to fail. The function immediately replaces the visible Sprite image on the screen. No further operation is required for showing the new image.

 © 2020 SEGGER Microcontroller GmbH

30.2.11 GUI_SPRITE_SetBitmapAndPosition()

Description

Sets the position and the image at once.

Prototype

```
int GUI_SPRITE_SetBitmapAndPosition(      GUI_HSPRITE   hSprite,
                                    const GUI_BITMAP  * pBM,
                                          int           x,
                                          int           y);
```

Parameters

Parameter	Description
hSprite	Handle of Sprite.
pBM	Pointer to the new bitmap structure to be used to draw the Sprite.
x	New X-position in screen coordinates.
y	New Y-position in screen coordinates.

Return value

0 on success
1 on error.

Additional information

It makes a difference on using the functions GUI_SPRITE_SetBitmap() and GUI_SPRITE_SetPosition() one after another or using this function. Whereas the image on the screen will be rendered twice on calling GUI_SPRITE_SetBitmap() and GUI_SPRITE_SetPosition() it is rendered only once on using this function, which can be used very well in animations.

 © 2020 SEGGER Microcontroller GmbH

30.2.12 GUI_SPRITE_SetLoop()

Description

Enables/Disables infinite animation of the given Sprite.

Prototype

```
int GUI_SPRITE_SetLoop(GUI_HSPRITE hSprite,
                       int         OnOff);
```

Parameters

Parameter	Description
hSprite	Handle of the Sprite.
OnOff	1 to enable infinite animation. 0 to disable it.

Return value

-1 if the function failed.
0 if infinite animation was not previously set.
1 if infinite animation was previously set.

 © 2020 SEGGER Microcontroller GmbH

30.2.13 GUI_SPRITE_SetPosition()

Description

Moves the Sprite to the new position.

Prototype

```
void GUI_SPRITE_SetPosition(GUI_HSPRITE hSprite,
                            int         x,
                            int         y);
```

Parameters

Parameter	Description
hSprite	Handle of Sprite.
x	New X-position in screen coordinates.
y	New Y-position in screen coordinates.

Additional information

The function moves the given Sprite to the new position.

 © 2020 SEGGER Microcontroller GmbH

30.2.14 GUI_SPRITE_Show()

Description

Shows the given Sprite.

Prototype

```
void GUI_SPRITE_Show(GUI_HSPRITE hSprite);
```

Parameters

Parameter	Description
hSprite	Handle of Sprite.

Additional information

The function adds the given Sprite to the list of visible Sprites.

 © 2020 SEGGER Microcontroller GmbH

30.2.15 GUI_SPRITE_StartAnim()

Description

Starts the animation of the given Sprite.

Prototype

```
int GUI_SPRITE_StartAnim(GUI_HSPRITE hSprite);
```

Parameters

Parameter	Description
hSprite	Handle of Sprite.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

30.2.16 GUI_SPRITE_StopAnim()

Description

Stops the animation of the given Sprite.

Prototype

```
int GUI_SPRITE_StopAnim(GUI_HSPRITE hSprite);
```

Parameters

Parameter	Description
hSprite	Handle of Sprite.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

Chapter 31

Cursors

emWin includes a system-wide cursor which may be changed to other, predefined styles. Also automatically animated cursors are supported. Although the cursor always exists, it is hidden by default. It will not be visible until a call is made to show it, and may be hidden again at any point.

 © 2020 SEGGER Microcontroller GmbH

31.1 Available cursors

The following cursor styles are currently available. If a call to `GUI_CURSOR_Show()` is made and no style is specified with `GUI_CURSOR_Select()`, the default cursor will be a medium arrow.

Arrow cursors		Cross cursors	
`GUI_CursorArrowS` Small arrow		`GUI_CursorCrossS` Small cross	
`GUI_CursorArrowM` Medium arrow (default cursor)		`GUI_CursorCrossM` Medium cross	
`GUI_CursorArrowL` Large arrow		`GUI_CursorCrossL` Large cross	

Inverted arrow cursors		Inverted cross cursors	
`GUI_CursorArrowSI` Small inverted arrow		`GUI_CursorCrossSI` Small inverted cross	
`GUI_CursorArrowMI` Medium inverted arrow		`GUI_CursorCrossMI` Medium inverted cross	
`GUI_CursorArrowLI` Large inverted arrow		`GUI_CursorCrossLI` Large inverted cross	

Animated cursors	
`GUI_CursorAnimHourglassM` Medium animated hourglass	

 © 2020 SEGGER Microcontroller GmbH

31.2 Cursor API

The table below lists the available cursor-related routines in alphabetical order. Detailed descriptions follow:

Functions

Routine	Description
GUI_CURSOR_GetState()	Returns if the cursor is currently visible or not.
GUI_CURSOR_Hide()	Hides the cursor.
GUI_CURSOR_Select()	Sets a specified cursor style.
GUI_CURSOR_SelectAnim()	Sets an animated cursor.
GUI_CURSOR_SetPosition()	Sets the cursor position.
GUI_CURSOR_Show()	Shows the cursor.

Data structures

Structure	Description
GUI_CURSOR_ANIM	Structure that stores information about a cursor animation used by GUI_CURSOR_SelectAnim().

 © 2020 SEGGER Microcontroller GmbH

31.2.1 Functions

31.2.1.1 GUI_CURSOR_GetState()

Description

Returns if the cursor is currently visible or not.

Prototype

```
int GUI_CURSOR_GetState(void);
```

Return value

1	if the cursor is visible.
0	if not.

 © 2020 SEGGER Microcontroller GmbH

31.2.1.2 GUI_CURSOR_Hide()

Description

Hides the cursor.

Prototype

```
void GUI_CURSOR_Hide(void);
```

Additional information

This is the default cursor setting. If the cursor should be visible, the function `GUI_CURSOR_Show()` needs to be called.

 © 2020 SEGGER Microcontroller GmbH

31.2.1.3 GUI_CURSOR_Select()

Description

Sets a specified cursor style.

Prototype

```
GUI_CURSOR *GUI_CURSOR_Select(const GUI_CURSOR * pCursor);
```

Parameters

Parameter	Description
pCursor	Pointer to the cursor to be selected.

Permitted values for parameter pCursor (Predefined cursors)	
GUI_CursorArrowS	Small arrow.
GUI_CursorArrowM	Medium arrow.
GUI_CursorArrowL	Large arrow.
GUI_CursorArrowSI	Small inverted arrow.
GUI_CursorArrowMI	Medium inverted arrow.
GUI_CursorArrowLI	Large inverted arrow.
GUI_CursorCrossS	Small cross.
GUI_CursorCrossM	Medium cross.
GUI_CursorCrossL	Large cross.
GUI_CursorCrossSI	Small inverted cross.
GUI_CursorCrossMI	Medium inverted cross.
GUI_CursorCrossLI	Large inverted cross.

Additional information

If this function is not called, the default cursor is a medium arrow.

 © 2020 SEGGER Microcontroller GmbH

31.2.1.4 GUI_CURSOR_SelectAnim()

Description

Sets an animated cursor.

Prototype

```
int GUI_CURSOR_SelectAnim(const GUI_CURSOR_ANIM * pCursorAnim);
```

Parameters

Parameter	Description
pCursorAnim	Pointer to a GUI_CURSOR_ANIM structure used for the animation.

Permitted values for parameter pCursor (Predefined cursors)	
GUI_CursorAnimHourglassM	Animated hourglass, medium size.

 © 2020 SEGGER Microcontroller GmbH

31.2.1.5 GUI_CURSOR_SetPosition()

Description

Sets the cursor position.

Prototype

```
void GUI_CURSOR_SetPosition(int xNewPos,
                            int yNewPos);
```

Parameters

Parameter	Description
x	X-position of the cursor.
y	Y-position of the cursor.

Additional information

Normally this function is called internally by the Window Manager and does not need to be called from the application.

 © 2020 SEGGER Microcontroller GmbH

31.2.1.6 GUI_CURSOR_Show()

Description

Shows the cursor.

Prototype

```
void GUI_CURSOR_Show(void);
```

Additional information

The default setting for the cursor is hidden; therefore this function must be called if you want the cursor to be visible.

 © 2020 SEGGER Microcontroller GmbH

31.2.2 Data structures

31.2.2.1 GUI_CURSOR_ANIM

Description

Structure that stores information about a cursor animation used by GUI_CURSOR_SelectAnim().

Type definition

```
typedef struct {
  const GUI_BITMAP **  ppBm;
  int                  xHot;
  int                  yHot;
  unsigned             Period;
  const unsigned     * pPeriod;
  int                  NumItems;
} GUI_CURSOR_ANIM;
```

Structure members

Member	Description
ppBm	Pointer to an array of pointers to bitmaps to be used for the animated cursor.
xHot	X-position of hot spot. Details can be found below.
yHot	Y-position of hot spot. Details can be found below.
Period	Period to be used to switch between the images.
pPeriod	Pointer to an array containing the periods to be used to switch between the images.
NumItems	Number of images used for the animation.

Additional information

The bitmaps addressed by ppBM need to fulfill with the following requirements:

- They need to have exactly the same X- and Y-size.
- They should not be compressed.
- They need to be transparent.
- They need to be palette based bitmaps with 1, 2, 4 or 8bpp.

Other bitmaps or insufficient memory cause the function to fail.

The pPeriod is only required if the periods for the images are different. If the same period should be used for all images Period should be used instead of pPeriod. In this case pPeriod should be NULL.

xHot and yHot determine the hot spot position of the cursor. This means the relative position in X and Y from the upper left corner of the image to the position of the pointer input device.

Customized cursors can be realized by passing a pointer to a custom defined GUI_CURSOR_ANIM structure.

 © 2020 SEGGER Microcontroller GmbH

Chapter 32

Anti-aliasing

Lines are approximated by a series of pixels that must lie at display coordinates. They can therefore appear jagged, particularly lines which are nearly horizontal or nearly vertical. This jaggedness is called aliasing.
Anti-aliasing is the smoothing of lines and curves. It reduces the jagged, stair-step appearance of any line that is not exactly horizontal or vertical. emWin supports different anti-aliasing qualities, anti-aliased fonts and high-resolution coordinates. Support for anti-aliasing is a separate software item and is not included in the emWin basic package. The software for anti-aliasing is located in the subdirectory `GUI\AntiAlias`.

 © 2020 SEGGER Microcontroller GmbH

32.1 Introduction

Anti-aliasing smooths curves and diagonal lines by “blending” the background color with that of the foreground. The higher the number of shades used between background and foreground colors, the better the anti-aliasing result (and the longer the computation time).

 © 2020 SEGGER Microcontroller GmbH

32.2 Quality of anti-aliasing

The quality of anti-aliasing is set by the routine `GUI_AA_SetFactor()`, which is explained later in this chapter. For an idea of the relationship between the anti-aliasing factor and the corresponding result, take a look at the image pictured.



The first line is drawn without anti-aliasing (factor 1). The second line is drawn anti-aliased using factor 2. This means that the number of shades from foreground to background is 2 × 2 = 4. The next line is drawn with an anti-aliasing factor of 3, so there are 3 × 3 = 9 shades, and so on. Factor 4 should be sufficient for most applications. Increasing the anti-aliasing factor further does not improve the result significantly, but increases the calculation time dramatically.

 © 2020 SEGGER Microcontroller GmbH

32.3 Anti-aliased fonts

Two types of anti-aliased fonts, low-quality (2bpp) and high-quality (4bpp), are supported. The routines required to display these fonts are automatically linked when using them. The following table shows the effect on drawing the character C without anti-aliasing and with both types of anti-aliased fonts:

Font type	Black on white	White on black
Standard (no anti-aliasing) 1 bpp 2 shades		
Low-quality (anti-aliased) 2 bpp 4 shades		
High-quality (anti-aliased) 4 bpp 16 shades		

Anti-aliased fonts can be created using the Font Converter. The general purpose of using anti-aliased fonts is to improve the appearance of text. While the effect of using high-quality anti-aliasing will be visually more pleasing than low-quality anti-aliasing, computation time and memory consumption will increase proportionally. Low-quality (2bpp) fonts require twice the memory of non-anti-aliased (1bpp) fonts; high-quality (4bpp) fonts require four times the memory.

32.3.1 Character representation in font files

The pixels of anti-aliased fonts are represented by intensity values of 2 bits (2bpp fonts) and 4 bits (4bpp fonts). Those values are used to calculate the pixel intensities (a value between 0 and 255) for mixing the foreground with the background. The intensities are calculated per default as follows:

2bpp

```
Intensity = <value in font> × (255 ÷ 3)
```

4bpp

```
Intensity = <value in font> × (255 ÷ 15)
```

32.3.2 Gamma correction

If the above described linear calculation does not lead into the expected appearance, the intensities could be set by the customer. To be able to do that gamma correction should be enabled by `GUI_AA_EnableGammaAA4()` and user defined values should be set by `GUI_AA_SetGammaAA4()`.

 © 2020 SEGGER Microcontroller GmbH

32.4 High-resolution coordinates

When drawing items using anti-aliasing, the same coordinates are used as for regular (non-anti-aliasing) drawing routines. This is the default mode. It is not required to consider the anti-aliasing factor in the function arguments. An anti-aliased line from (50, 100) to (100, 50) would be drawn with the following function call:

```
GUI_AA_DrawLine(50, 100, 100, 50);
```

The high-resolution feature of emWin lets you use the virtual space determined by the anti-aliasing factor and your display size. The advantage of using high-resolution coordinates is that items can be placed not only at physical positions of your display but also "between" them. The virtual space of a high-resolution pixel is illustrated below based on an anti-aliasing factor of 3:



To draw a line from pixel (50, 100) to (100, 50) in high-resolution mode with anti-aliasing factor 3, you would write:

```
GUI_AA_DrawLine(150, 300, 300, 150);
```

High-resolution coordinates must be enabled with the routine `GUI_AA_EnableHiRes()`, and may be disabled with `GUI_AA_DisableHiRes()`. Both functions are explained later in the

 © 2020 SEGGER Microcontroller GmbH

chapter. For example programs using the high-resolution feature, see the examples at the end of the chapter.

 © 2020 SEGGER Microcontroller GmbH

32.5 Anti-aliasing API

The table below lists the available routines in the anti-aliasing package, in alphabetical order within their respective categories. Detailed descriptions of the routines can be found in the sections that follow.

Routine	Description
Control functions	
GUI_AA_DisableHiRes()	Disables high-resolution coordinates.
GUI_AA_EnableHiRes()	Enables high-resolution coordinates.
GUI_AA_GetFactor()	Returns the current antialiasing quality factor.
GUI_AA_PreserveTrans()	Makes sure that alpha channel remains after drawing operations.
GUI_AA_SetFactor()	Sets the antialiasing quality factor.
Drawing functions	
GUI_AA_DrawArc()	Displays an antialiased arc at a specified position in the current window.
GUI_AA_DrawCircle()	This functions draws an anti aliased circle.
GUI_AA_DrawLine()	Displays an antialiased line at a specified position in the current window.
GUI_AA_DrawPolyOutline()	Displays the outline of an antialiased polygon defined by a list of points, at a specified position in the current window and with a specified thickness.
GUI_AA_DrawPolyOutlineEx()	Displays the outline of an antialiased polygon defined by a list of points, at a specified position in the current window and with a specified thickness.
GUI_AA_DrawRoundedRect()	Draws the outline of an antialiased rectangle with rounded corners using the current pen size.
GUI_AA_DrawRoundedRectEx()	Draws the outline of an antialiased rectangle with rounded corners using the current pen size.
GUI_AA_FillCircle()	Displays a filled, antialiased circle at a specified position in the current window.
GUI_AA_FillEllipse()	Displays a filled, antialiased ellipse at a specified position in the current window.
GUI_AA_FillPolygon()	Fills an antialiased polygon defined by a list of points, at a specified position in the current window.
GUI_AA_FillRoundedRect()	Draws a filled and antialiased rectangle with rounded corners.
GUI_AA_FillRoundedRectEx()	Draws a filled and antialiased rectangle with rounded corners.
GUI_AA_SetDrawMode()	This function determines how the background color is fetched for mixing.
Gamma correction	
GUI_AA_EnableGammaAA4()	Enables custom defined intensity values for 4bpp antialiased fonts.
GUI_AA_GetGammaAA4()	Retrieves the currently used intensity values.
GUI_AA_SetGammaAA4()	Sets the intensity values to be used.

 © 2020 SEGGER Microcontroller GmbH

32.5.1 Control functions

32.5.1.1 GUI_AA_DisableHiRes()

Description

Disables high-resolution coordinates.

Prototype

```
void GUI_AA_DisableHiRes(void);
```

Additional information

High-resolution coordinates are disabled by default.

 © 2020 SEGGER Microcontroller GmbH

32.5.1.2 GUI_AA_EnableHiRes()

Description

Enables high-resolution coordinates.

Prototype

```
void GUI_AA_EnableHiRes(void);
```

 © 2020 SEGGER Microcontroller GmbH

32.5.1.3 GUI_AA_GetFactor()

Description

Returns the current antialiasing quality factor.

Prototype

```
int GUI_AA_GetFactor(void);
```

Return value

The current antialiasing factor.

 © 2020 SEGGER Microcontroller GmbH

32.5.1.4 GUI_AA_PreserveTrans()

Description

For a detailed description please refer to *GUI_PreserveTrans* on page 288.

Prototype

```
unsigned GUI_AA_PreserveTrans(unsigned OnOff);
```

Parameter	Description
OnOff	1 enables transparency preserving, 0 disables it.

Return value

Old state.

 © 2020 SEGGER Microcontroller GmbH

32.5.1.5 GUI_AA_SetFactor()

Description

Sets the antialiasing quality factor.

Prototype

```
void GUI_AA_SetFactor(int Factor);
```

Parameters

Parameter	Description
Factor	Antialiasing quality factor to use. Minimum: 1 (no antialiasing); default: 3; maximum: 6.

Additional information

For good quality and performance, it is recommended to use an antialiasing quality factor of 2-4.

 © 2020 SEGGER Microcontroller GmbH

32.5.2 Drawing functions

32.5.2.1 GUI_AA_DrawArc()

Description

Displays an antialiased arc at a specified position in the current window.

Prototype

```
void GUI_AA_DrawArc(int x0,
                    int y0,
                    int rx,
                    int ry,
                    int a0,
                    int a1);
```

Parameters

Parameter	Description
x0	Horizontal position of the center.
y0	Vertical position of the center.
rx	Horizontal radius.
ry	Vertical radius.
a0	Starting angle (degrees).
a1	Ending angle (degrees).

Limitations

Currently the ry parameter is not available. The rx parameter is used instead.

Additional information

If working in high-resolution mode, position and radius must be in high-resolution coordinates. Otherwise they must be specified in pixels.

 © 2020 SEGGER Microcontroller GmbH

32.5.2.2 GUI_AA_DrawCircle()

Description

This functions draws an anti aliased circle.

Prototype

```
void GUI_AA_DrawCircle(int x0,
                       int y0,
                       int r);
```

Parameters

Parameter	Description
x0	X-center position.
y0	Y-center position.
r	Radius to be used.

Additional information

This function uses the set pensize to draw the circle.

 © 2020 SEGGER Microcontroller GmbH

32.5.2.3 GUI_AA_DrawLine()

Description

Displays an antialiased line at a specified position in the current window.

Prototype

```
void GUI_AA_DrawLine(int x0,
                     int y0,
                     int x1,
                     int y1);
```

Parameters

Parameter	Description
x0	X-starting position.
y0	Y-starting position.
x1	X-end position.
y1	Y-end position.

Additional information

If working in high-resolution mode, the coordinates must be in high-resolution coordinates. Otherwise they must be specified in pixels.

 © 2020 SEGGER Microcontroller GmbH

32.5.2.4 GUI_AA_DrawPolyOutline()

Description

Displays the outline of an antialiased polygon defined by a list of points, at a specified position in the current window and with a specified thickness. The number of points is limited to 10.

Prototype

```
void GUI_AA_DrawPolyOutline(const GUI_POINT * pSrc,
                                  int         NumPoints,
                                  int         Thickness,
                                  int         x,
                                  int         y);
```

Parameters

Parameter	Description
pPoint	Pointer to the polygon to display.
NumPoints	Number of points specified in the list of points.
Thickness	Thickness of the outline.
x	X-position of origin.
y	Y-position of origin.

Additional information

The polyline drawn is automatically closed by connecting the endpoint to the starting point. The starting point must not be specified a second time as an endpoint. If working in high-resolution mode, the coordinates must be in high-resolution coordinates. Otherwise they must be specified in pixels. Per default the number of points processed by this function is limited to 10. If the polygon consists of more than 10 points the function GUI_AA_DrawPolyOutlineEx should be used.

Example

```
#define countof(Array) (sizeof(Array) / sizeof(Array[0]))
static GUI_POINT aPoints[] = {
  {  0,  0 },
  { 15, 30 },
  {  0, 20 },
  {-15, 30 }
};
void Sample(void) {
  GUI_AA_DrawPolyOutline(aPoints, countof(aPoints), 3, 150, 40);
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

32.5.2.5 GUI_AA_DrawPolyOutlineEx()

Description

Displays the outline of an antialiased polygon defined by a list of points, at a specified position in the current window and with a specified thickness.

Prototype

```
void GUI_AA_DrawPolyOutlineEx(const GUI_POINT * pSrc,
                              int         NumPoints,
                              int         Thickness,
                              int         x,
                              int         y,
                              GUI_POINT * pBuffer);
```

Parameters

Parameter	Description
pPoint	Pointer to the polygon to display.
NumPoints	Number of points specified in the list of points.
Thickness	Thickness of the outline.
x	X-position of origin.
y	Y-position of origin.
pBuffer	Pointer to a buffer of GUI_POINT elements.

Additional information

The number of polygon points is not limited by this function. Internally the function needs a buffer of GUI_POINT elements for calculation purpose. The number of points of the buffer needs to be ≥ the number of points of the polygon. For more details, refer to GUI_AA_DrawPolyOutline().

 © 2020 SEGGER Microcontroller GmbH

32.5.2.6 GUI_AA_DrawRoundedRect()

Description

Draws the outline of an antialiased rectangle with rounded corners using the current pen size.

Prototype

```
void GUI_AA_DrawRoundedRect(int x0,
                            int y0,
                            int x1,
                            int y1,
                            int r);
```

Parameters

Parameter	Description
x0	X-position of the upper left corner.
y0	Y-position of the upper left corner.
x1	X-position of the lower right corner.
y1	Y-position of the lower right corner.
r	Radius to be used for the rounded corners.

Example

```
#include "GUI.h"
void MainTask(void) {
  GUI_Init();
  GUI_SetBkColor(GUI_WHITE);
  GUI_Clear();
  GUI_SetColor(GUI_DARKBLUE);
  GUI_SetPenSize(5);
  GUI_AA_DrawRoundedRect(10, 10, 50, 50, 5);
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

32.5.2.7 GUI_AA_DrawRoundedRectEx()

Description

Draws the outline of an antialiased rectangle with rounded corners using the current pen size.

Prototype

```
void GUI_AA_DrawRoundedRectEx(GUI_RECT * pRect,
                              int        r);
```

Parameters

Parameter	Description
pRect	Pointer to the rectangle to draw.
r	Radius to be used for the rounded corners.

 © 2020 SEGGER Microcontroller GmbH

32.5.2.8 GUI_AA_FillCircle()

Description

Displays a filled, antialiased circle at a specified position in the current window.

Prototype

```
void GUI_AA_FillCircle(int x0,
                       int y0,
                       int r);
```

Parameters

Parameter	Description
x0	X-position of the center of the circle in pixels of the client window.
y0	Y-position of the center of the circle in pixels of the client window.
r	Radius of the circle (half of the diameter).

Additional information

If working in high-resolution mode, the coordinates must be in high-resolution coordinates. Otherwise they must be specified in pixels.

 © 2020 SEGGER Microcontroller GmbH

32.5.2.9 GUI_AA_FillEllipse()

Description

Displays a filled, antialiased ellipse at a specified position in the current window.

Prototype

```
void GUI_AA_FillEllipse(int x0,
                        int y0,
                        int rx,
                        int ry);
```

Parameters

Parameter	Description
x0	X-position of the center of the ellipse in pixels of the client window.
y0	Y-position of the center of the ellipse in pixels of the client window.
rx	Radius in X of the ellipse.
ry	Radius in Y of the ellipse.

Additional information

If working in high-resolution mode, the coordinates must be in high-resolution coordinates. Otherwise they must be specified in pixels.

 © 2020 SEGGER Microcontroller GmbH

32.5.2.10 GUI_AA_FillPolygon()

Description

Fills an antialiased polygon defined by a list of points, at a specified position in the current window.

Prototype

```
void GUI_AA_FillPolygon(const GUI_POINT * pPoints,
                        int         NumPoints,
                        int         x0,
                        int         y0);
```

Parameters

Parameter	Description
pPoint	Pointer to the polygon to display.
NumPoints	Number of points specified in the list of points.
x	X-position of origin.
y	Y-position of origin.

Additional information

The polyline drawn is automatically closed by connecting the endpoint to the starting point. The starting point must not be specified a second time as an endpoint. If working in high-resolution mode, the coordinates must be in high-resolution coordinates. Otherwise they must be specified in pixels.

 © 2020 SEGGER Microcontroller GmbH

32.5.2.11 GUI_AA_FillRoundedRect()

Description

Draws a filled and antialiased rectangle with rounded corners.

Prototype

```
void GUI_AA_FillRoundedRect(int x0,
                            int y0,
                            int x1,
                            int y1,
                            int r);
```

Parameters

Parameter	Description
x0	X-position of the upper left corner.
y0	Y-position of the upper left corner.
x1	X-position of the lower right corner.
y1	Y-position of the lower right corner.
r	Radius to be used for the rounded corners.

Example

```
#include "GUI.h"
void MainTask(void) {
  GUI_Init();
  GUI_SetBkColor(GUI_WHITE);
  GUI_Clear();
  GUI_SetColor(GUI_DARKBLUE);
  GUI_AA_FillRoundedRect(10, 10, 54, 54, 5);
}
```

Screenshot of above example



 © 2020 SEGGER Microcontroller GmbH

32.5.2.12 GUI_AA_FillRoundedRectEx()

Description

Draws a filled and antialiased rectangle with rounded corners.

Prototype

```
void GUI_AA_FillRoundedRectEx(GUI_RECT * pRect,
                              int        r);
```

Parameters

Parameter	Description
pRect	Pointer to the rectangle to draw.
r	Radius to be used for the rounded corners.

 © 2020 SEGGER Microcontroller GmbH

32.5.2.13 GUI_AA_SetDrawMode()

Description

This function determines how the background color is fetched for mixing.

Prototype

```
int GUI_AA_SetDrawMode(int Mode);
```

Parameters

Parameter	Description
Mode	Mode to be used (see table below)

Permitted values for parameter Mode	
GUI_AA_TRANS	Default behavior. Anti-aliased pixels are mixed with the current content of the frame buffer.
GUI_AA_NOTRANS	Anti-aliased pixels are mixed with the current background color set with GUI_SetBkColor().

Return value

0 on success
1 if Mode did not contain a permitted value.

Additional information

The default behavior of antialiasing in emWin is mixing pixels with the current content of the frame buffer. But under certain circumstances using the currently set background color (GUI_SetBkColor()) for mixing may be an advantage. This makes it possible to redraw antialiased items completely without having to redraw the background.

 © 2020 SEGGER Microcontroller GmbH

32.5.3 Gamma correction

32.5.3.1 GUI_AA_EnableGammaAA4()

Description

Enables custom defined intensity values for 4bpp antialiased fonts. As described at the beginning of that chapter per default the intensities are calculated by a linear manner. After enabling gamma correction the intensities could be set by `GUI_AA_SetGammaAA4()`.

Prototype

```
void GUI_AA_EnableGammaAA4(int OnOff);
```

Parameters

Parameter	Description
`OnOff`	1 for enabling gamma correction, 0 for using linear default values.

 © 2020 SEGGER Microcontroller GmbH

32.5.3.2 GUI_AA_GetGammaAA4()

Description

Retrieves the currently used intensity values.

Prototype

```
void GUI_AA_GetGammaAA4(U8 * pGamma);
```

Parameters

Parameter	Description
pGamma	The pointer should point to an array of U8 values.

Additional information

The function copies the currently used set of values into the given buffer.

 © 2020 SEGGER Microcontroller GmbH

32.5.3.3 GUI_AA_SetGammaAA4()

Description

Sets the intensity values to be used.

Prototype

```
void GUI_AA_SetGammaAA4(U8 * pGamma);
```

Parameters

Parameter	Description
pGamma	The pointer should point to an array of 16 intensity values.

Additional information

The function copies the values to an emWin internal buffer.

 © 2020 SEGGER Microcontroller GmbH

32.6 Examples

32.6.1 Different anti-aliasing factors

The following example creates diagonal lines with and without anti-aliasing. The source code is available as AA_Lines.c in the examples shipped with emWin.

```
/*********************************************************************
*                 SEGGER Microcontroller GmbH & Co. KG                *
*        Solutions for real time microcontroller applications         *
*                                                                     *
*                     emWin example code                              *
*                                                                     *
**********************************************************************
----------------------------------------------------------------------
File        : AA_Lines.c
Purpose     : Shows lines with different antialiasing qualities
----------------------------------------------------------------------
*/
#include "GUI.h"
/*********************************************************************
*
*        Show lines with different antialiasing qualities
*
**********************************************************************
*/
static void DemoAntialiasing(void) {
  int i, x1, x2, y;
  y = 2;
  //
  // Set drawing attributes
  //
  GUI_SetColor(GUI_BLACK);
  GUI_SetBkColor(GUI_WHITE);
  GUI_Clear();
  x1 = 10;
  x2 = 90;
  //
  // Draw lines without antialiasing
  //
  GUI_DispStringHCenterAt("\nNormal", (x1 + x2) / 2, 10);
  for (i = 1; i < 12; i++) {
    GUI_SetPenSize(i);
    GUI_DrawLine(x1, 40 + i * 15, x2, 40 + i * 15 +  y);
  }
  x1 = 110;
  x2 = 190;
  //
  // Draw lines with antialiasing quality factor 2
  //
  GUI_AA_SetFactor(2);
  GUI_DispStringHCenterAt("Antialiased\n\nusing factor 2", (x1 + x2) / 2, 10);
  for (i = 1; i < 12; i++) {
    GUI_SetPenSize(i);
    GUI_AA_DrawLine(x1, 40 + i * 15, x2, 40 + i * 15 +  y);
  }
  x1 = 210;
  x2 = 290;
  //
  // Draw lines with antialiasing quality factor 6
  //
  GUI_AA_SetFactor(6);
  GUI_DispStringHCenterAt("Antialiased\n\nusing factor 6", (x1 + x2) / 2, 10);
  for (i = 1; i < 12; i++) {
    GUI_SetPenSize(i);
    GUI_AA_DrawLine(x1, 40 + i * 15, x2, 40 + i * 15 +  y);
```

 © 2020 SEGGER Microcontroller GmbH

```
  }
}
/*********************************************************************
*
*       MainTask
*
*********************************************************************
*/
void MainTask(void) {
  GUI_Init();
  DemoAntialiasing();
  while(1)
    GUI_Delay(100);
}
```

Screenshot of above example



32.6.2 Lines placed on high-resolution coordinates

This example shows anti-aliased lines placed on high-resolution coordinates. It is available as `AA_HiResPixels.c`.

```
/*********************************************************************
*                SEGGER Microcontroller GmbH & Co. KG                *
*        Solutions for real time microcontroller applications        *
*                                                                    *
*                     emWin example code                             *
*                                                                    *
**********************************************************************
----------------------------------------------------------------------
File        : AA_HiResPixels.c
Purpose     : Demonstrates high resolution pixels
----------------------------------------------------------------------
*/
#include "GUI.H"
/*********************************************************************
*
*       Show lines placed on high resolution pixels
*
*********************************************************************
*/
static void ShowHiResPixels(void) {
  int i, Factor;
  Factor = 5;
  GUI_SetBkColor(GUI_WHITE);
```

 © 2020 SEGGER Microcontroller GmbH

```
  GUI_SetColor(GUI_BLACK);
  GUI_Clear();
  GUI_SetLBorder(50);
  GUI_DispStringAt("This example uses high resolution pixels.\n", 50, 10);
  GUI_DispString  ("Not only the physical pixels are used.\n");
  GUI_DispString  ("Enabling high resolution simulates more\n");
  GUI_DispString  ("pixels by using antialiasing.\n");
  GUI_DispString  ("Please take a look at the magnified output\n");
  GUI_DispString  ("to view the result.\n");
  GUI_SetPenSize(2);
  GUI_AA_EnableHiRes();       /* Enable high resolution */
  GUI_AA_SetFactor(Factor);   /* Set quality factor */
  //
  // Drawing lines using high resolution pixels
  //
  for (i = 0; i < Factor; i++) {
    int x = (i + 1) * 5 * Factor + i - 1;
    GUI_AA_DrawLine(x, 50, x, 199);
  }
}
/*********************************************************************
*
*        MainTask
*
**********************************************************************
*/
void MainTask(void) {
  GUI_Init();
  ShowHiResPixels();
  while(1) {
    GUI_Delay(100);
  }
}
```

Magnified screenshot of above example



32.6.3 Moving pointer using high-resolution anti-aliasing

This example illustrates the use of high-resolution anti-aliasing by drawing a rotating pointer that turns 0.1 degrees with each step. There is no screenshot of this example because the effects of high-resolution anti-aliasing are only visible in the movement of the pointers. Without high-resolution the pointer appears to make short “jumps”, whereas in high-resolution mode there is no apparent jumping. The example can be found as `AA_HiResAntialiasing.c`.

```
/*********************************************************************
*                SEGGER Microcontroller GmbH & Co. KG                *
*        Solutions for real time microcontroller applications        *
*                                                                    *
*                     emWin example code                             *
*                                                                    *
```

 © 2020 SEGGER Microcontroller GmbH

```
/*********************************************************************
----------------------------------------------------------------------
File        : AA_HiResAntialiasing.c
Purpose     : Demonstrates high resolution antialiasing
----------------------------------------------------------------------
*/
#include "GUI.H"
/*********************************************************************
*
*        Data
*
*********************************************************************
*/
#define countof(Obj) (sizeof(Obj)/sizeof(Obj[0]))
static const GUI_POINT aPointer[] = {
  {  0,  3 },
  { 85,  1 },
  { 90,  0 },
  { 85, -1 },
  {  0, -3 }
};
static GUI_POINT aPointerHiRes[countof(aPointer)];
typedef struct {
  GUI_AUTODEV_INFO AutoInfo;
  GUI_POINT aPoints[countof(aPointer)];
  int Factor;
} PARAM;
/*********************************************************************
*
*        Drawing routines
*
*********************************************************************
*/
static void DrawHiRes(void * p) {
  PARAM * pParam = (PARAM *)p;
  if (pParam->AutoInfo.DrawFixed) {
    GUI_ClearRect(0, 0, 99, 99);
  }
  GUI_AA_FillPolygon(pParam->aPoints,    countof(aPointer),
                     5 * pParam->Factor, 95 * pParam->Factor);
}
static void Draw(void * p) {
  PARAM * pParam = (PARAM *)p;
  if (pParam->AutoInfo.DrawFixed) {
    GUI_ClearRect(100, 0, 199, 99);
  }
  GUI_AA_FillPolygon(pParam->aPoints, countof(aPointer), 105, 95);
}
/*********************************************************************
*
*        Demonstrate high resolution by drawing rotating pointers
*
*********************************************************************
*/
static void ShowHiresAntialiasing(void) {
  GUI_AUTODEV aAuto[2];
  PARAM       Param;
  int         i;
  Param.Factor = 3;
  GUI_DispStringHCenterAt("Using\nhigh\nresolution\nmode", 50, 120);
  GUI_DispStringHCenterAt("Not using\nhigh\nresolution\nmode", 150, 120);
  //
  // Create GUI_AUTODEV objects
  //
  for (i = 0; i < countof(aAuto); i++) {
    GUI_MEMDEV_CreateAuto(&aAuto[i]);
  }
  //
```

 © 2020 SEGGER Microcontroller GmbH

```
  // Calculate pointer for high resolution
  //
  for (i = 0; i < countof(aPointer); i++) {
    aPointerHiRes[i].x = aPointer[i].x * Param.Factor;
    aPointerHiRes[i].y = aPointer[i].y * Param.Factor;
  }
  GUI_AA_SetFactor(Param.Factor); /* Set antialiasing factor */
  while(1) {
    for (i = 0; i < 1800; i++) {
      float Angle = (i >= 900) ? 1800 - i : i;
      Angle *= 3.1415926f / 1800;
      //
      // Draw pointer with high resolution
      //
      GUI_AA_EnableHiRes();
      GUI_RotatePolygon(Param.aPoints, aPointerHiRes, countof(aPointer), Angle);
      GUI_MEMDEV_DrawAuto(&aAuto[0], &Param.AutoInfo, DrawHiRes, &Param);
      //
      // Draw pointer without high resolution
      //
      GUI_AA_DisableHiRes();
      GUI_RotatePolygon(Param.aPoints, aPointer, countof(aPointer), Angle);
      GUI_MEMDEV_DrawAuto(&aAuto[1], &Param.AutoInfo, Draw, &Param);
      GUI_Delay(2);
    }
  }
}
/*********************************************************************
*
*       MainTask
*
**********************************************************************
*/
void MainTask(void) {
  GUI_Init();
  ShowHiresAntialiasing();
}
```

 © 2020 SEGGER Microcontroller GmbH

Chapter 33

Language Support

Text written in a language like Arabic, Thai or Chinese contains characters, which are normally not part of the fonts shipped with emWin. This chapter explains the basics like the Unicode standard, which defines all available characters worldwide and the UTF-8 encoding scheme, which is used by emWin to decode text with Unicode characters. It also explains how to enable bidirectional (and right to left) text support to be able to render Arabic or Hebrew scripts. A further subchapter explains how to render text with Shift-JIS (Japanese Industry Standard) encoding.

 © 2020 SEGGER Microcontroller GmbH

33.1 Unicode

Unicode is an international standard defined by the Unicode consortium. For each meaningful character or text element of all known cultures it contains a unique digital code point. Further it contains the bidirectional algorithm for right-to-left scripts like Hebrew and Arabic, which are also supported by emWin.

The Unicode Standard defines a codespace of 1,114,112 code points in the range from 0 to 0x10FFFF containing a repertoire of more than 128,000 characters covering more than 135 scripts. This codespace is divided into seventeen planes, numbered 0 to 16. emWin supports the complete *Basic Multilingual Plane* (BMP, plane 0) which covers the code points from 0x0000 to 0xFFFF. This BMP contains characters for almost all modern languages, and a large number of special characters. Characters outside the BMP are currently not supported.

33.1.1 UTF-8 encoding

ISO/IEC 10646-1 defines a multi-octet character set called the Universal Character Set (UCS) which encompasses most of the world's writing systems. Multi-octet characters, however, are not compatible with many current applications and protocols, and this has led to the development of a few UCS transformation formats (UTF), each with different characteristics.

UTF-8 has the characteristic of preserving the full ASCII range, providing compatibility with file systems, parsers and other software that rely on ASCII values but are transparent to other values.

In emWin, UTF-8 characters are encoded using sequences of 1 to 3 octets. If the high-order bit is set to 0, the remaining 7 bits being used to encode the character value. In a sequence of n octets, n > 1, the initial octet has the n higher-order bits set to 1, followed by a bit set to 0. The remaining bit(s) of that octet contain bits from the value of the character to be encoded. The following octet(s) all have the higher-order bit set to 1 and the following bit set to 0, leaving 6 bits in each to contain bits from the character to be encoded.

The following table shows the encoding ranges:

Character range	UTF-8 Octet sequence
0000 - 007F	0xxxxxxx
0080 - 07FF	110xxxxx 10xxxxxx
0800 - FFFF	1110xxxx 10xxxxxx 10xxxxxx

Encoding example

The text "Halöle" contains ASCII characters and European extensions. The following hex dump shows this text as UTF-8 encoded text:

```
48 61 6C C3 B6 6C 65
```

Programming examples

If we want to display a text containing non-ASCII characters, we can do this by manually computing the UTF-8 codes for the non-ASCII characters in the string. However, if your compiler supports UTF-8 encoding (Sometimes called multi-byte encoding), even non-ASCII characters can be used directly in strings.

```
//
// Example using ASCII encoding:
//
GUI_UC_SetEncodeUTF8();       /* required only once to activate UTF-8*/
GUI_DispString("Hal\xc3\xb6le");
//
// Example using UTF-8 encoding:
```

 © 2020 SEGGER Microcontroller GmbH

```
//
GUI_UC_SetEncodeUTF8();       /* required only once to activate UTF-8*/
GUI_DispString("Halöle");
```

33.1.2 Unicode characters

The character output routine used by emWin (`GUI_DispChar()`) does always take an unsigned 16-bit value (U16) and has the basic ability to display a character defined by Unicode. It simply requires a font which contains the character you want to display.

33.1.3 UTF-8 strings

This is the most recommended way to display Unicode. You do not have to use special functions to do so. If UTF-8-encoding is enabled each function of emWin which handles with strings decodes the given text as UTF-8 text.

33.1.3.1 Using U2C.exe to convert UTF-8 text into C code

The `Tool` subdirectory of emWin contains the tool `U2C.exe` to convert UTF-8 text to C code. It reads an UTF-8 text file and creates a C file with C strings. The following steps show how to convert a text file into C strings and how to display them with emWin:

Step 1: Creating a UTF-8 text file

Save the text to be converted in UTF-8 format. You can use `Notepad.exe` to do this. Load the text under Notepad.exe:

Japanese:
1 - エンコーディング
2 - テキスト
3 - サポート
English:
1 - encoding
2 - text
3 - support

Choose **File ➔ Save As...**. The file dialog should contain a combo box to set the encoding format. Choose "`UTF-8`" and save the text file.

Step 2: Converting the text file into a C-code file

Start `U2C.exe`. After starting the program you need to select the text file to be converted. After selecting the text file the name of the C file should be selected. Output of `U2C.exe`:

```
"Japanese:"
"1 - \xe3\x82\xa8\xe3\x83\xb3\xe3\x82\xb3\xe3\x83\xbc"
    "\xe3\x83\x87\xe3\x82\xa3\xe3\x83\xb3\xe3\x82\xb0"
"2 - \xe3\x83\x86\xe3\x82\xad\xe3\x82\xb9\xe3\x83\x88"
"3 - \xe3\x82\xb5\xe3\x83\x9d\xe3\x83\xbc\xe3\x83\x88"
"English:"
"1 - encoding"
"2 - text"
"3 - support"
```

Step 3: Using the output in the application code

The following example shows how to display the UTF-8 text with emWin:

```
#include "GUI.h"
static const char * _apStrings[] = {
```

 © 2020 SEGGER Microcontroller GmbH

```
  "Japanese:",
  "1 - \\xe3\\x82\\xa8\\xe3\\x83\\xb3\\xe3\\x82\\xb3\\xe3\\x83\\xbc"
      "\\xe3\\x83\\x87\\xe3\\x82\\xa3\\xe3\\x83\\xb3\\xe3\\x82\\xb0",
  "2 - \\xe3\\x83\\x86\\xe3\\x82\\xad\\xe3\\x82\\xb9\\xe3\\x83\\x88",
  "3 - \\xe3\\x82\\xb5\\xe3\\x83\\x9d\\xe3\\x83\\xbc\\xe3\\x83\\x88",
  "English:",
  "1 - encoding",
  "2 - text",
  "3 - support"
};
void MainTask(void) {
  int i;
  GUI_Init();
  GUI_SetFont(&GUI_Font16_1HK);
  GUI_UC_SetEncodeUTF8();
  for (i = 0; i < GUI_COUNTOF(_apStrings); i++) {
    GUI_DispString(_apStrings[i]);
    GUI_DispNextLine();
  }
  while(1) {
    GUI_Delay(500);
  }
}
```

33.1.4 Unicode API

The table below lists the available routines in alphabetical order within their respective categories. Detailed descriptions of the routines can be found in the sections that follow.

Routine	Description
UTF-8 functions	
GUI_UC_ConvertUC2UTF8()	Converts the given double byte Unicode string into UTF-8 format.
GUI_UC_ConvertUTF82UC()	Converts the given UTF-8 string into Unicode format.
GUI_UC_EnableBIDI()	This function enables support for bidirectional text.
GUI_UC_EnableThai()	This function enables support for Thai script.
GUI_UC_Encode()	This function encodes a given character with the current encoding settings.
GUI_UC_GetBaseDir()	Returns the current basic text direction.
GUI_UC_GetCharCode()	This function decodes a character from a given text.
GUI_UC_GetCharSize()	This function returns the number of bytes used to encode the given character.
GUI_UC_SetBaseDir()	Sets the basic text direction to be used.
GUI_UC_SetEncodeSJIS()	Enables SJIS character encoding.
GUI_UC_SetEncodeNone()	Disables character encoding.
GUI_UC_SetEncodeUTF8()	Enables UTF-8 encoding.
Double byte functions	
GUI_UC_DispString()	This function displays the given double byte string.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1 UTF-8 functions

33.1.4.1.1 GUI_UC_ConvertUC2UTF8()

Description

Converts the given double byte Unicode string into UTF-8 format.

Prototype

```
int GUI_UC_ConvertUC2UTF8(const U16  * s,
                                int    Len,
                                char * pBuffer,
                                int    BufferSize);
```

Parameters

Parameter	Description
s	Pointer to Unicode string to be converted.
Len	Number of Unicode characters to be converted.
pBuffer	Pointer to a buffer to write in the result.
BufferSize	Buffer size in bytes.

Return value

The function returns the number of bytes written to the buffer.

Additional information

UTF-8 encoded characters can use up to 3 bytes. To be on the save side the recommended buffer size is: `Number of Unicode characters × 3`.
If the buffer is not big enough for the whole result, the function returns when the buffer is full.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.2 GUI_UC_ConvertUTF82UC()

Description

Converts the given UTF-8 string into Unicode format.

Prototype

```
int GUI_UC_ConvertUTF82UC(const char * s,
                                int    Len,
                                U16  * pBuffer,
                                int    BufferSize);
```

Parameters

Parameter	Description
s	Pointer to UFT-8 string to be converted.
Len	Length in bytes of the string to be converted.
pBuffer	Pointer to a buffer to write in the result.
BufferSize	Buffer size in words.

Return value

The function returns the number of Unicode characters written to the buffer.

Additional information

If the buffer is not big enough for the whole result, the function returns when the buffer is full.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.3 GUI_UC_EnableBIDI()

Description

This function enables support for bidirectional text.

Prototype

```
int GUI_UC_EnableBIDI(int OnOff);
```

Parameters

Parameter	Description
OnOff	1 to enable BIDI support, 0 to disable it.

Return value

The previous state of BIDI support.

Additional information

Once this function is linked approximately 97 KBytes of ROM are additionally used (about 25 KBytes of code and 72 KByte const data). The BiDi module uses a look up table for some characters. This table requires about 72 KByte of ROM. It is possible to reduce the size of this table by enabling (1) or disabling (0) code points with the following:

```
#define GUI_BIDI_SUPPORT_RANGE_<X> 0
```

Where <X> can be: 0, 1, 2, 3, 4, A, D, F

For example:

```
#define GUI_BIDI_SUPPORT_RANGE_2 0
#define GUI_BIDI_SUPPORT_RANGE_F 0
```

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.4 GUI_UC_EnableThai()

Description

This function enables support for Thai script.

Prototype

```
int GUI_UC_EnableThai(int OnOff);
```

Parameters

Parameter	Description
OnOff	1 to enable Thai support, 0 to disable it.

Return value

The previous state of Thai support.

Additional information

If Thai support is enabled emWin observes 2 situations:

1. If a consonant is followed by a lower vowel the pixel area below the base line must be clipped.
2. If a tone mark should be drawn after an upper vowel the tone mark has to be shifted up to make it visible above the tone mark.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.5 GUI_UC_Encode()

Description

This function encodes a given character with the current encoding settings.

Prototype

```
int GUI_UC_Encode(char * s,
                  U16    Char);
```

Parameters

Parameter	Description
s	Pointer to a buffer to store the encoded character.
Char	Character to be encoded.

Return value

The number of bytes stored to the buffer.

Additional information

The function assumes that the buffer has at least 3 bytes for the result.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.6 GUI_UC_GetBaseDir()

Description

Returns the current basic text direction.

Prototype

```
int GUI_UC_GetBaseDir(void);
```

Return value

Basic text direction.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.7 GUI_UC_GetCharCode()

Description

This function decodes a character from a given text.

Prototype

```
U16 GUI_UC_GetCharCode(const char * s);
```

Parameters

Parameter	Description
s	Pointer to the text to be encoded.

Return value

The encoded character.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.8 GUI_UC_GetCharSize()

Description

This function returns the number of bytes used to encode the given character.

Prototype

```
int GUI_UC_GetCharSize(const char * s);
```

Parameters

Parameter	Description
s	Pointer to the text to be encoded.

Return value

Number of bytes used to encode the given character.

Additional information

This function is used to determine how much bytes a pointer has to be incremented to point to the next character.

Example

The following example shows how to use the function:

```
static void _Display2Characters(const char * pText) {
  int Size;
  U16 Character;
  Size       = GUI_UC_GetCharSize(pText);  // Size to increment pointer
  Character  = GUI_UC_GetCharCode(pText);  // Get first character code
  GUI_DispChar(Character);                 // Display first character
  pText     += Size;                       // Increment pointer
  Character  = GUI_UC_GetCharCode(pText);  // Get next character code
  GUI_DispChar(Character);                 // Display second character
}
```

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.9 GUI_UC_SetBaseDir()

Description

Sets the basic text direction to be used.

Prototype

```
void GUI_UC_SetBaseDir(int Dir);
```

Parameters

Parameter	Description
Dir	(see table below)

Permitted values for element Dir	
GUI_BIDI_BASEDIR_LTR	Basic text direction is 'left to right'.
GUI_BIDI_BASEDIR_RTL	Basic text direction is 'right to left'.
GUI_BIDI_BASEDIR_AUTO	Basic text direction is calculated automatically: If the first character with strong directionality is RTL the basic text direction is set to RTL.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.10 GUI_UC_SetEncodeSJIS()

Description

Enables SJIS character encoding.

Prototype

```
void GUI_UC_SetEncodeSJIS(void);
```

Additional information

This function call is required before using an SJIS font.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.11 GUI_UC_SetEncodeNone()

Description

Disables character encoding.

Prototype

```
void GUI_UC_SetEncodeNone(void);
```

Additional information

After calling this function each byte of a text will be handled as one character. This is the default behavior of emWin.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.1.12 GUI_UC_SetEncodeUTF8()

Description

Enables UTF-8 encoding.

Prototype

```
void GUI_UC_SetEncodeUTF8(void);
```

Additional information

After calling `GUI_UC_SetEncodeUTF8()` each string related routine of emWin encodes a given sting in accordance to the UTF-8 transformation.

 © 2020 SEGGER Microcontroller GmbH

33.1.4.2 Double byte functions

33.1.4.2.1 GUI_UC_DispString()

Description

This function displays the given double byte string.

Prototype

```
void GUI_UC_DispString(const U16 * s);
```

Parameters

Parameter	Description
s	Pointer to double byte string.

Additional information

If you need to display double byte strings you should use this function. Each character has to be defined by a 16 bit value.

 © 2020 SEGGER Microcontroller GmbH

33.2 Text- and language resource files

To be able to change the text of an application without modifying one line of code the text- and language resource file API functions can be used. They offer the possibility to use one or more simple text files or one CSV (**C**omma **S**eparated **V**alue) file containing text in multiple languages. These files can reside in addressable RAM or at any non addressable medium like NAND flash or a file system.

33.2.1 Unicode support

If the used range of characters exceeds the ASCII set the text files should contain UTF-8 text. Other encodings like UC16 are not supported by this module.

33.2.2 Loading files from RAM

When using the files directly from RAM emWin does not allocate the required strings again. It uses the RAM location of the files directly. But because text- and CSV files do not contain zero delimited strings, emWin modifies the given text by replacing the line delimiters (CRLF) (text files) or field delimiters (CSV files) by a zero byte. Therefore the files have to reside in RAM, not in ROM.

33.2.3 Loading files from non addressable areas

It is also possible to use the files from non addressable areas or any other location in ROM. In these cases emWin uses a GetData function for getting the file data. In the first step (`GUI_LANG_LoadTextEx()`, `GUI_LANG_LoadCSVEx()`) emWin only remembers size and file offset of the text locations within the files. Only when accessing the text with `GUI_LANG_GetText()` the text will be allocated in RAM, read from the file and converted in a legal zero delimited string.

Each time a string gets return by `GUI_LANG_GetText()` it stores the string in the RAM. Once a string is located in the RAM the function returns the string from the RAM. This makes the reading process much faster. If there is not much RAM available it is possible to use the function `GUI_LANG_GetTextBuffered()`. This function uses a buffer of a fixed size and does not keep the string to be displayed in RAM. On the other hand this requires more reading accesses and is slower than reading the string from RAM.

33.2.4 Rules for CSV files

Because the term 'CSV file' does not exactly determine the file format, here are the rules which have to be obeyed:

- Each record is located on a separate line, delimited by a line break (CRLF).
- The last record in the file may or may not have an ending line break.
- Within each record, there may be one or more fields, separated by delimiters. Each line should contain the same number of fields throughout the file. Spaces are considered part of a field. The last field in the record must not be followed by a delimiter.
- Default field delimiter is a comma. This may be changed using the function `GUI_LANG_SetSep()`.
- Each field may or may not be enclosed in double quotes. If fields are not enclosed with double quotes, then double quotes may not appear inside the fields.
- Fields containing line breaks (CRLF), double quotes, and commas should be enclosed in double-quotes.
- If double-quotes are used to enclose fields, then a double-quote appearing inside a field must be escaped by preceding it with another double quote.

33.2.5 Rules for text files

A text file is a simple file where each line contains one text element. Rules to obey:

- Each line contains one text item.
- Each line must be delimited by a line break (CRLF).

 © 2020 SEGGER Microcontroller GmbH

- Text items containing line breaks are not supported.

33.2.6 Text- and language resource file API

The table below shows the available routines in alphabetical order. Detailed descriptions of the routines follow.

Routine	Description
Text file functions	
GUI_LANG_LoadText()	Loads a text file from a RAM location.
GUI_LANG_LoadTextEx()	Loads a text file using the given GetData function from any area.
CSV file functions	
GUI_LANG_LoadCSV()	Loads a CSV file from a RAM location.
GUI_LANG_LoadCSVEx()	Loads a CSV file from any location by using a GetData function.
Common functions	
GUI_LANG_Clear()	Frees all allocated resources.
GUI_LANG_GetLang()	Returns the current language index.
GUI_LANG_GetNumItems()	Returns the number of available text items of the given language.
GUI_LANG_GetText()	Returns a pointer to the requested text item of the current language.
GUI_LANG_GetTextBuffered()	Copies the requested text of the current language into the given buffer.
GUI_LANG_GetTextBufferedEx()	Copies the requested text of the given language into the given buffer.
GUI_LANG_GetTextEx()	Returns a pointer to the requested text item.
GUI_LANG_GetTextLen()	Returns the length of a text item of the current language.
GUI_LANG_GetTextLenEx()	Returns the length of a text item.
GUI_LANG_SetLang()	Sets the language to be used by the function GUI_LANG_GetText().
GUI_LANG_SetMaxNumLang()	Sets the maximum number of languages to be used.
GUI_LANG_SetSep()	Sets the separator to be used when reading a CSV file.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.1 Text file functions

33.2.6.1.1 GUI_LANG_LoadText()

Description

Loads a text file from a RAM location.

Prototype

```
int GUI_LANG_LoadText(U8  * pFileData,
                      U32   FileSize,
                      int   IndexLang);
```

Parameters

Parameter	Description
pFileData	Pointer to the first byte of the file.
FileSize	Size of the given file in bytes.
IndexLang	Index of the language.

Return value

0 on success.
1 on error.

Additional information

The given file needs to reside in RAM. As explained at the beginning of the chapter emWin converts the given text items into zero delimited strings.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.1.2 GUI_LANG_LoadTextEx()

Description

Loads a text file using the given GetData function from any area.

Prototype

```
int GUI_LANG_LoadTextEx(GUI_GET_DATA_FUNC * pfGetData,
                        void              * p,
                        int                 IndexLang);
```

Parameters

Parameter	Description
pfGetData	Pointer to a _GetData() function to be used for file access.
p	Pointer passed to the _GetData() function.
IndexLang	Index of the language.

Return value

0 on success.
1 on error.

Additional information

Data is accessed by the given GetData function. The pointer p can be used by the application.

Prototype of the 'GetData' function

```
int GUI_GET_DATA_FUNC(      void   * p,
                      const U8   * * ppData,
                            unsigned NumBytesReq,
                            U32      Off);
```

Parameter	Description
p	Application defined void pointer.
ppData	The location the pointer points to has to be filled by the 'GetData' function.
NumBytesReq	Number of requested bytes.
Off	Offset to be used to address the requested bytes within the file.

Example

The following shows a sample implementation of the GetData function for use under Windows:

```
static int _GetData(void * pVoid, const U8 ** ppData, unsigned NumBytes, U32 Off) {
  DWORD  NumBytesRead;
  HANDLE hFile;
  U8   * pData;
  pData = (U8 *)*ppData;
  hFile = *(HANDLE *)pVoid;
  if (SetFilePointer(hFile, Off, 0, FILE_BEGIN) == 0xFFFFFFFF) {
    return 0;
  }
  if (!ReadFile(hFile, pData, NumBytes, &NumBytesRead, 0)) {
    return 0;
  }
  return NumBytesRead;
}
```

 © 2020 SEGGER Microcontroller GmbH

33.2.6.2 CSV file functions

33.2.6.2.1 GUI_LANG_LoadCSV()

Description

Loads a CSV file from a RAM location.

Prototype

```
int GUI_LANG_LoadCSV(U8  * pFileData,
                     U32   FileSize);
```

Parameters

Parameter	Description
pFileData	Pointer to the first byte of the file.
FileSize	Size of the given file in bytes.

Return value

The function returns the number of available languages of the given file.

Additional information

The given file needs to reside in RAM. As explained at the beginning of the chapter emWin converts the given text items to zero delimited strings. This function call first deletes all existing text resources. It is not possible to use a text file including one language and a CSV file including further languages. Either text files or CSV files should be used.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.2.2 GUI_LANG_LoadCSVEx()

Description

Loads a CSV file from any location by using a GetData function.

Prototype

```
int GUI_LANG_LoadCSVEx(GUI_GET_DATA_FUNC * pfGetData,
                       void              * p);
```

Parameters

Parameter	Description
pfGetData	Pointer to a _GetData() function to be used for file access.
p	Pointer passed to the _GetData() function.

Return value

The function returns the number of available languages.

Additional information

As explained at the beginning of the chapter emWin converts the given text items to zero delimited strings. This function call first deletes all existing text resources. It is not possible to use a text file including one language and a CSV file including further languages. Either text files or CSV files should be used. If the return value is 0 it might be possible that the maximum number of lanuages is too small. Call GUI_LANG_SetMaxNumLang() to increase the number of lanuages.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3 Common functions

33.2.6.3.1 GUI_LANG_Clear()

Description

Frees all allocated resources.

Prototype

```
void GUI_LANG_Clear(void);
```

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.2 GUI_LANG_GetLang()

Description

Returns the current language index.

Prototype

```
int GUI_LANG_GetLang(void);
```

Return value

Current index of the language.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.3 GUI_LANG_GetNumItems()

Description

Returns the number of available text items of the given language.

Prototype

```
int GUI_LANG_GetNumItems(int IndexLang);
```

Parameters

Parameter	Description
IndexLang	Index of the given language.

Return value

Number of available text items of the given language.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.4 GUI_LANG_GetText()

Description

Returns a pointer to the requested text item of the current language.

Prototype

```
char *GUI_LANG_GetText(int IndexText);
```

Parameters

Parameter	Description
IndexText	Index of the text item to be returned.

Return value

Pointer to the requested text item.

Additional information

If a GetData function is used, the first time a text item is requested it will be allocated, read and converted once. In case of using a GetData function this could save memory if not all text items are used by the application.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.5 GUI_LANG_GetTextBuffered()

Description

Copies the requested text of the current language into the given buffer.

Prototype

```
int GUI_LANG_GetTextBuffered(int    IndexText,
                             char * pBuffer,
                             int    SizeOfBuffer);
```

Parameters

Parameter	Description
IndexText	Index of the text item to be returned.
pBuffer	Pointer to an application defined buffer.
SizeOfBuffer	Size of the application defined buffer.

Return value

0 on success.
1 if the text could not be found.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.6 GUI_LANG_GetTextBufferedEx()

Description

Copies the requested text of the given language into the given buffer.

Prototype

```
int GUI_LANG_GetTextBufferedEx(int    IndexText,
                               int    IndexLang,
                               char * pBuffer,
                               int    SizeOfBuffer);
```

Parameters

Parameter	Description
IndexText	Index of the text item to be returned.
IndexLang	Index of the language.
pBuffer	Pointer to an application defined buffer.
SizeOfBuffer	Size of the application defined buffer.

Return value

0 on success.
1 if the text could not be found.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.7 GUI_LANG_GetTextEx()

Description

Returns a pointer to the requested text item.

Prototype

```
char *GUI_LANG_GetTextEx(int IndexText,
                         int IndexLang);
```

Parameters

Parameter	Description
IndexText	Index of the text item to be returned.
IndexLang	Index of the requested language.

Return value

Pointer to the requested text item.

Additional information

If a GetData function is used, the first time a text item is requested it will be allocated, read and converted once. In case of using a GetData function this could save memory if not all text items are used by the application.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.8 GUI_LANG_GetTextLen()

Description

Returns the length of a text item of the current language.

Prototype

```
int GUI_LANG_GetTextLen(int IndexText);
```

Parameters

Parameter	Description
IndexText	Index of the text item.

Return value

-1 Error. =! -1: Length of the text item.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.9 GUI_LANG_GetTextLenEx()

Description

Returns the length of a text item.

Prototype

```
int GUI_LANG_GetTextLenEx(int IndexText,
                          int IndexLang);
```

Parameters

Parameter	Description
IndexText	Index of the text item.
IndexLang	Index of the language.

Return value

-1 Error. =! -1: Length of the text item.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.10 GUI_LANG_SetLang()

Description

Sets the language to be used by the function `GUI_LANG_GetText()`.

Prototype

```
int GUI_LANG_SetLang(int IndexLang);
```

Parameters

Parameter	Description
IndexLang	Index of the language to be used.

Return value

Previous index of the language.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.11 GUI_LANG_SetMaxNumLang()

Description

Sets the maximum number of languages to be used.

Prototype

```
unsigned GUI_LANG_SetMaxNumLang(unsigned MaxNumLang);
```

Parameters

Parameter	Description
MaxNumLang	Maximum number of languages

Return value

Previous maximum number of languages.

Additional information

This function has to be called before any other function of the language module is called. A good place for the function call would be `GUI_X_Config()`.

 © 2020 SEGGER Microcontroller GmbH

33.2.6.3.12 GUI_LANG_SetSep()

Description

Sets the separator to be used when reading a CSV file.

Prototype

```
U16 GUI_LANG_SetSep(U16 Sep);
```

Parameters

Parameter	Description
Sep	Separator to be used for CSV files.

Return value

Previously used separator.

Additional information

The default separator is a comma. Some applications use TABs or semicolons as separator. This function can be used to change the separator. It does not check if the given separator makes sense. So it is the applications responsibility to set the right value. The function has no effect on reading text files.

 © 2020 SEGGER Microcontroller GmbH

33.3 Right to left- and bidirectional text

Whereas most scripts are written from the left to the right (LTR), there are some scripts like Hebrew and Arabic which are written from the right to the left (RTL). Bidirectional (BIDI) text contains text with both directionalities. To be able to apply the correct visual alignment, a couple of rules need to be followed to get the right visual alignment of the text. BIDI text support is part of the emWin basic package.

33.3.1 Bidirectional text algorithm

The Unicode consortium has defined the rules for combining RTL- and LTR text in the Unicode standard. It prescribes an algorithm for how to convert the logical sequence of characters into the correct visual presentation observing a set of rules. emWin follows up these rules to get the right visual order before drawing the text. It observes the rules of the bidirectional text algorithm of the Unicode standard 8.0.0.

Example

The following example shows how bidirectional text is rendered by emWin:

UTF-8 text	Rendering
`\xd8\xb9\xd9\x84\xd8\xa7 1, 2, 345 \xd8\xba\xd9\x86\xd9\x8a XYZ \xd8\xa3\xd9\x86\xd8\xa7`	

33.3.2 Basic text direction

It is important to set the appropriate base direction for text so that the bidirectional algorithm produces the expected ordering of the text. The visual order of text, especially text with brackets and single RTL characters, depends on the basic text direction.

Example

The following example shows a simple text with different basic text directions:

Basic text direction	Rendering
`GUI_BIDI_BASEDIR_RTL`	
`GUI_BIDI_BASEDIR_AUTO`	

33.3.3 Mirroring

emWin also supports mirroring of some neutral characters in RTL aligned text. This is important if for example RTL aligned text contains parenthesis. The mirroring is done by replacing the code of the character to be mirrored with the code of a mirror partner whose image fits to the mirrored image. This is done by a fast way using a table containing all characters with existing mirror partners. Note that support for mirroring further characters is not supported.

33.3.4 Requirements

The bidirectional text alignment uses approx. 80 KB of ROM and approx. 800 bytes of additional stack.

 © 2020 SEGGER Microcontroller GmbH

33.4 Arabic support



The basic difference between western languages and Arabic is, that Arabic scripts are written from the right to the left and that it does not know uppercase and lowercase characters. Further the character codes of the text are not identical with the character index in the font file used to render the character, because the notation forms of the characters depend on the positions in the text. Arabic support is part of the emWin basic package.

33.4.1 Notation forms

The Arabic base character set is defined in the Unicode standard within the range from 0x0600 to 0x06FF. Unfortunately these character codes can not directly be used to get the character of the font for drawing it, because the notation form depends on the character position in the text. One character can have up to 4 different notation forms:

- One, if it is at the beginning of a word **(initial)**
- One, if it is at the end of a word **(final)**
- One, if it is in the middle of a word **(medial)**
- One, if the character stands alone **(isolated)**

But not each character is allowed to be joined to the left and to the right (double- joined). The character Hamza for example always needs to be separated and Alef is only allowed at the end or separated. Character combinations of the letters Lam and Alef should be transformed to a ligature. This means one character substitutionally for the combination of Lam and Alef.

The above description shows, that the notation form is normally not identical to the character code of the text. The following table shows how emWin transforms the characters to the notation form in dependence of the text position:

Base	Isolated	Final	Initial	Medial	Character
0x0621	0xFE80	-	-	-	Hamza
0x0622	0xFE81	0xFE82	-	-	Alef with Madda above
0x0623	0xFE83	0xFE84	-	-	Alef with Hamza above
0x0624	0xFE85	0xFE86	-	-	Waw with Hamza above
0x0625	0xFE87	0xFE88	-	-	Alef with Hamza below
0x0626	0xFE89	0xFE8A	0xFE8B	0xFE8C	Yeh with Hamza above
0x0627	0xFE8D	0xFE8E	-	-	Alef
0x0628	0xFE8F	0xFE90	0xFE91	0xFE92	Beh
0x0629	0xFE93	0xFE94	-	-	Teh Marbuta
0x062A	0xFE95	0xFE96	0xFE97	0xFE98	Teh
0x062B	0xFE99	0xFE9A	0xFE9B	0xFE9C	Theh
0x062C	0xFE9D	0xFE9E	0xFE9F	0xFEA0	Jeem

 © 2020 SEGGER Microcontroller GmbH

Base	Isolated	Final	Initial	Medial	Character
0x062D	0xFEA1	0xFEA2	0xFEA3	0xFEA4	Hah
0x062E	0xFEA5	0xFEA6	0xFEA7	0xFEA8	Khah
0x062F	0xFEA9	0xFEAA	-	-	Dal
0x0630	0xFEAB	0xFEAC	-	-	Thal
0x0631	0xFEAD	0xFEAE	-	-	Reh
0x0632	0xFEAF	0xFEB0	-	-	Zain
0x0633	0xFEB1	0xFEB2	0xFEB3	0xFEB4	Seen
0x0634	0xFEB5	0xFEB6	0xFEB7	0xFEB8	Sheen
0x0635	0xFEB9	0xFEBA	0xFEBB	0xFEBC	Sad
0x0636	0xFEBD	0xFEBE	0xFEBF	0xFEC0	Dad
0x0637	0xFEC1	0xFEC2	0xFEC3	0xFEC4	Tah
0x0638	0xFEC5	0xFEC6	0xFEC7	0xFEC8	Zah
0x0639	0xFEC9	0xFECA	0xFECB	0xFECC	Ain
0x063A	0xFECD	0xFECE	0xFECF	0xFED0	Ghain
0x0641	0xFED1	0xFED2	0xFED3	0xFED4	Feh
0x0642	0xFED5	0xFED6	0xFED7	0xFED8	Qaf
0x0643	0xFED9	0xFEDA	0xFEDB	0xFEDC	Kaf
0x0644	0xFEDD	0xFEDE	0xFEDF	0xFEE0	Lam
0x0645	0xFEE1	0xFEE2	0xFEE3	0xFEE4	Meem
0x0646	0xFEE5	0xFEE6	0xFEE7	0xFEE8	Noon
0x0647	0xFEE9	0xFEEA	0xFEEB	0xFEEC	Heh
0x0648	0xFEED	0xFEEE	-	-	Waw
0x0649	0xFEEF	0xFEF0	-	-	Alef Maksura
0x064A	0xFEF1	0xFEF2	0xFEF3	0xFEF4	Yeh
0x067E	0xFB56	0xFB57	0xFB58	0xFB59	Peh
0x0686	0xFB7A	0xFB7B	0xFB7C	0xFB7D	Tcheh
0x0698	0xFB8A	0xFB8B	-	-	Jeh
0x06A9	0xFB8E	0xFB8F	0xFB90	0xFB91	Keheh
0x06AF	0xFB92	0xFB93	0xFB94	0xFB95	Gaf
0x06CC	0xFBFC	0xFBFD	0xFBFE	0xFBFF	Farsi Yeh

33.4.2 Ligatures

Character combinations of Lam and Alef needs to be transformed to ligatures. The following table shows how emWin transforms these combinations into ligatures, if the first letter is a Lam (code 0x0644):

Second letter	Ligature (final)	Ligature (elsewhere)
0x622, Alef with Madda above	0xFEF6	0xFEF5
0x623, Alef with Hamza above	0xFEF8	0xFEF7
0x625, Alef with Hamza below	0xFEFA	0xFEF9
0x627, Alef	0xFEFC	0xFEFB

 © 2020 SEGGER Microcontroller GmbH

33.4.3 How to enable Arabic support

Per default emWin writes text always from the left to the right and there will be no Arabic character transformation as described above. To enable support for bidirectional text and Arabic character transformation, add the following line to your application:

```
GUI_UC_EnableBIDI(1);
```

If enabled, emWin follows the rules of the bidirectional algorithm, described by the Unicode consortium, to get the right visual order before drawing text.

33.4.4 Example

The `Sample` folder contains the example `FONT_Arabic`, which shows how to draw Arabic text. It contains an emWin font with Arabic characters and some small Arabic text examples.

33.4.5 Font files used with Arabic text

Font files used to render Arabic text need to include at least all characters defined in the Arabic range `0x600-0x6FF` and the notation forms and ligatures listed in the tables of this chapter.

 © 2020 SEGGER Microcontroller GmbH

33.5 Thai language support



The Thai alphabet uses 44 consonants and 15 basic vowel characters. These are horizontally placed, left to right, with no intervening space, to form syllables, words, and sentences. Vowels are written above, below, before, or after the consonant they modify, although the consonant always sounds first when the syllable is spoken. The vowel characters (and a few consonants) can be combined in various ways to produce numerous compound vowels (diphthongs and triphthongs).

33.5.1 Requirements

As explained above the Thai language makes an extensive usage of compound characters. To be able to draw compound characters in emWin, a new font type is needed, which contains all required character information like the image size, image position and cursor incrementation value. From version 4.00 emWin supports a new font type with this information. This also means that older font types can not be used to draw Thai text.

> **Note**
>
> The standard fonts of emWin do not contain font files with Thai characters. To create a Thai font file, the Font Converter of version 3.04 or newer is required.

Memory

The Thai language support does not need additional ROM nor RAM.

33.5.2 How to enable Thai support

Support of the Thai language has to be enabled by calling `GUI_UC_EnableThai()`.

33.5.3 Example

The `Sample` folder contains the example `FONT_ThaiText.c`, which shows how to draw Thai text. It contains an emWin font with Thai characters and some small Thai text examples.

33.5.4 Font files used with Thai text

Font files used to render Thai text need to include at least all characters defined in the Thai range `0xE00-0xE7F`.

 © 2020 SEGGER Microcontroller GmbH

33.6 Shift JIS support

Shift JIS (Japanese Industry Standard) is a character encoding method for the Japanese language. It is the most common Japanese encoding method. Shift JIS encoding makes generous use of 8-bit characters, and the value of the first byte is used to distinguish single- and multiple-byte characters.

The Shift JIS support of emWin is only needed if text with Shift JIS encoding needs to be rendered.

You need no special function calls to draw a Shift JIS string. The main requirement is a font file which contains the Shift JIS characters.

33.6.1 Creating Shift JIS fonts

The Font Converter can generate a Shift JIS font for emWin from any Windows font. When using a Shift JIS font, the functions used to display Shift JIS characters are linked automatically with the library.

Detailed information on how to create Shift-JIS fonts and implement them in a project can be found in the chapter *Font Converter* on page 534.

 © 2020 SEGGER Microcontroller GmbH

33.7 Limitations

Currently emWin is not able to make text transitions required for drawing Devanagari and similar scripts. It does not contain an engine for complete complex script support. Because of this only RTF and Arabic transitions are supported.

 © 2020 SEGGER Microcontroller GmbH

Chapter 34

Display drivers

A display driver supports a particular family of display controllers and all displays which are connected to one or more of these controllers. The drivers can be configured by modifying their configuration files whereas the driver itself does not need to be modified. The configuration files contain all required information for the driver including how the hardware is accessed and how the controller(s) are connected to the display.

This chapter provides an overview of the display drivers available for emWin. It explains the following in terms of each driver:

- Which display controllers can be accessed, as well as supported color depths and types of interfaces.
- RAM requirements.
- Driver specific functions.
- How to access the hardware.
- Special configuration switches.
- Special requirements for particular display controllers.

 © 2020 SEGGER Microcontroller GmbH

34.1 Available display drivers

Since emWin V5 the driver interface has changed. Old display drivers, developed for emWin V4 or earlier, are not longer supported.
The display driver interface was changed in order to be able to configure drivers at run-time. This was required because emWin is often used as a precompiled library which should not have to be changed when using a different display.

> **Note**
>
> Creating a precompiled library including the source files of a compile time configurable driver precludes configurability using the library.

To be able to support as many display controllers as possible in a short period, we migrated some of the older drivers to the new interface. Not all migrated display drivers are runtime configurable. The listings below show the sets of available runtime and compile time configurable display drivers.

34.1.1 Driver file naming convention

All files belonging to the same display driver begin with the name of the driver. So all files called `<DriverName>*.*` describe the whole driver.

Example

The following files describe the `GUIDRV_IST3088` display driver:

- `GUIDRV_IST3088.c`
- `GUIDRV_IST3088.h`
- `GUIDRV_IST3088_4.c`
- `GUIDRV_IST3088_Private.h`
- `GUIDRV_IST3088_X_4.c`

34.1.2 Run-time configurable drivers

The following table lists the currently available run-time configurable drivers developed for the current interface of emWin:

Driver	Supported display controller / Purpose of driver	Supported bits/pixel
`GUIDRV_BitPlains`	This driver can be used for solutions without display controller. It manages separate 'bitplains' for each color bit. Initially it has been developed to support a solution for an R32C/111 which drives a TFT display without display controller. It can be used for each solution which requires the color bits in separate plains.	1 - 8
`GUIDRV_DCache`	Cache driver for managing a double cache. It manages the cache data separately from the driver and converts the data line by line immediately before a drawing operation is required. This driver makes it possible to use for example a 16bpp display driver in 1bpp mode with a cache which only requires 1 bit per pixel.	1 (can be enhanced on demand)
`GUIDRV_Dist`	This driver supports displays with multiple controllers.	Depends on the actual display drivers.
`GUIDRV_FlexColor`	Epson S1D19122 FocalTech FT1509 Himax HX8353, HX8325A, HX8357, HX8340, HX8347, HX8352A, HX8352B, HX8301, HX8367 Hitachi HD66772 Ilitek ILI9320, ILI9325, ILI9328, ILI9335, ILI9338, ILI9340, ILI9341, ILI9342, ILI9163, ILI9481, ILI9486, ILI9488, ILI9220, ILI9221, ILI9806H LG Electronics LGDP4531, LGDP4551, LGDP4525 Lucid Display Technology LDT7138	16, 18

 © 2020 SEGGER Microcontroller GmbH

Driver	Supported display controller / Purpose of driver	Supported bits/pixel
	Novatek NT39122 OriseTech SPFD5408, SPFD54124C, SPFD5414D Raio RA8870, RA8875 Renesas R61505, R61516, R61526, R61580 Samsung S6E63D6, S6D0117 Sitronix ST7628, ST7637, ST7687, ST7735, ST7712, ST7775, ST7789 Solomon SSD1284, SSD1289, SSD1298, SSD1355, SSD2119, SSD1963, SSD1961, SSD1351, SSD1353 Syncoam SEPS525	
GUIDRV_IST3088	Integrated Solutions Technology IST3088, IST3257	4
GUIDRV_Lin	This driver supports every display controller with linear addressable video memory with a direct (full bus) interface. This means that the video RAM is directly addressable by the address lines of the CPU. The driver contains no controller specific code. So it can also be used for solutions without display controller which require a driver which only manages the video RAM.	1, 2, 4, 8, 16, 24, 32
GUIDRV_S1D13L01	Epson S1D13L01	8, 16
GUIDRV_S1D13L02	Epson S1D13L02	16
GUIDRV_S1D13L04	Epson S1D13L04	24, 32
GUIDRV_S1D13513	Epson S1D13513	24, 32
GUIDRV_S1D13748	Epson S1D13748	16
GUIDRV_S1D13781	Epson S1D13781	8, 16
GUIDRV_S1D15G00	Epson S1D15G00	12
GUIDRV_SH_MEM	Display driver for Sharp memory LCDs with 8- or 10 bit address interface.	1, 3
GUIDRV_SLin	Epson S1D13700, S1D13305 (indirect interface only!) RAIO 8835 Solomon SSD1325, SSD1362, SSD1848 Toshiba T6963 UltraChip UC1617	1, 2
GUIDRV_SLinEPD	Solomon SSD1673	-
GUIDRV_SPage	Avant Electronics SBN0064G Epson S1D15605, S1D15606, S1D15607, S1D15608, S1D15705, S1D15710, S1D15714, S1D15E05, S1D15E06, S1D15719, S1D15721 Hitachi HD61202 Integrated Solutions Technology IST3020, IST3501 New Japan Radio Company NJU6676 Novatek NT7502, NT7534, NT7538, NT75451 Samsung S6B0108 (KS0108), S6B0713, S6B0719, S6B0724, S6B1713 Sino Wealth SH1101A Sitronix ST75160, ST7522, ST75256, ST75320, ST7565, ST7567, ST7591 Solomon SSD1303, SSD1305, SSD1309, SSD1316, SSD1805, SSD1815, SSD1821 Sunplus SPLC501C UltraChip UC1601, UC1606, UC1608, UC1610, UC1611, UC1628, UC1638, UC1701	1, 2, 4
GUIDRV_SSD1322	Solomon SSD1322	-
GUIDRV_SSD1926	Solomon SSD1926	8
GUIDRV_UC1698G	UltraChip UC1698G	5

34.1.3 Compile-time configurable drivers

The following table lists the currently available drivers which has already been migrated to the current version of emWin:

 © 2020 SEGGER Microcontroller GmbH

Driver	Supported display controller / Purpose of driver	Supported bits/pixel
GUIDRV_CompactColor_16	Ampire FSA506 Epson S1D13742, S1D13743, S1D19122 FocalTech FT1509 Himax HX8301, HX8312A, HX8325A, HX8340, HX8347, HX8352, HX8352B, HX8353 Hitachi HD66766, HD66772, HD66789 Ilitek ILI9161, ILI9220, ILI9221, ILI9320, ILI9325, ILI9326, ILI9328, ILI9342, ILI9481 LG Electronics LGDP4531, LGDP4551 MagnaChip D54E4PA7551 Novatek NT39122, NT7573 OriseTech SPFD5408, SPFD54124C, SPFD5414D, SPFD5420A Renesas R61505, R61509, R61516, R61526, R61580, R63401 Samsung S6D0110A, S6D0117, S6D0128, S6D0129, S6D04H0 Sharp LCY-A06003, LR38825 Sitronix ST7628, ST7637, ST7712, ST7715, ST7735, ST7787, ST7789 Solomon SSD1284, SSD1289, SSD1298, SSD1355, SSD1961, SSD1963, SSD2119 Toshiba JBT6K71	16
GUIDRV_Fujitsu_16	Fujitsu MB87J2020 (Jasmine) Fujitsu MB87J2120 (Lavender)	1, 2, 4, 8, 16
GUIDRV_Page1bpp	Epson S1D10605, S1D15605, S1D15705, S1D15710, S1D15714, S1D15721, S1D15E05, S1D15E06, SED1520, SED1560, SED1565, SED1566, SED1567, SED1568, SED1569, SED1575 Hitachi HD61202 IST IST3020 New Japan Radio Company NJU6676, NJU6679 Novatek NT7502, NT7534, NT7538, NT75451 Philips PCF8810, PCF8811, PCF8535, PCD8544 Samsung KS0108B, KS0713, KS0724, S6B0108B, S6B0713, S6B0719, S6B0724, S6B1713 Sino Wealth SH1101A Sitronix ST7522, ST7565, ST7567 Solomon SSD1303, SSD1805, SSD1815, SSD1821 ST Microelectronics ST7548, STE2001, STE2002 Sunplus SPLC501C UltraChip UC1601, UC1606, UC1608, UC1701	1
GUIDRV_07X1	Novatek NT7506, NT7508 Samsung KS0711, KS0741, S6B0711, S6B0741 Sitronix ST7541, ST7571 Solomon SSD1854 ST Microelectronics STE2010 Tomato TL0350A	2
GUIDRV_6331	Samsung S6B33B0X, S6B33B1X, S6B33B2X	16
GUIDRV_7528	Sitronix ST7528	4
GUIDRV_7529	Sitronix ST7529	1, 4, 5

Note

Some LCD-controllers may be supported twice, by a runtime and by a compile time configurable driver. In that case it is highly recommended to use/buy the runtime configurable driver, because those drivers are the successors pf the compile time configurable drivers.

34.1.4 Special purpose drivers

The basic package contains a driver which does not support a specific display controller. It can be used as template for a new driver or for measurement purpose:

 © 2020 SEGGER Microcontroller GmbH

Driver	LCD Controller	Supported bits/pixel
GUIDRV_Template	Driver template. Can be used as a starting point for writing a new driver. Part of the basic package.	-

 © 2020 SEGGER Microcontroller GmbH

34.2 CPU / Display controller interface

Different display controllers can have different CPU interfaces. Basically there are two different interfaces:

- Direct interface
- Indirect interface

Whereas the direct interface accesses the video memory directly by the address bus of the CPU, the indirect interface requires a more complex communication with the display controller to get access to the video memory. This can be done by different kinds of connections:

- Parallel access
- 4 pin SPI interface
- 3 pin SPI interface
- I2C bus interface

The following explains these interfaces and how to configure them. Note that not all configuration macros are always required. For details about which macros are required, refer to *Detailed display driver descriptions* on page 2643.

34.2.1 Direct interface

Some display controllers (especially those for displays with higher resolution) require a full address bus, which means they are connected to at least 14 address bits. In a direct interface configuration, video memory is directly accessible by the CPU; the address bus is connected to the display controller.
The only knowledge required when configuring a direct interface is information about the address range (which will generate a CHIP-SELECT signal for the LCD controller) and whether 8-, 16- or 32-bit accesses should be used (bus-width to the display controller). In other words, you need to know the following:

- Base address for video memory access
- Base address for register access
- Distance between adjacent video memory locations (usually 1/2/4-byte)
- Distance between adjacent register locations (usually 1/2/4-byte)
- Type of access (8/16/32-bit) for video memory
- Type of access (8/16/32-bit) for registers

Typical block diagram



34.2.2 Indirect interface - Parallel bus

Most controllers for smaller displays use an indirect interface to connect to the CPU. With an indirect interface, only one address bit (usually A0) is connected to the LCD controller. Some of these controllers are very slow, so that the hardware designer may decide to connect it to input/output (I/O) pins instead of the address bus.

 © 2020 SEGGER Microcontroller GmbH

Typical block diagram



8 (16) data bits, one address bit and 2 or 3 control lines are used to connect the CPU and one LCD controller. Four macros inform the LCD driver how to access each controller used. If the LCD controller(s) is connected directly to the address bus of the CPU, configuration is simple and usually consists of no more than one line per macro. If the LCD controller(s) is connected to I/O pins, the bus interface must be simulated, which takes about 5-10 lines of program per macro (or a function call to a routine which simulates the bus interface). The signal **A0** is also called **C/D** (Command/Data), **D/I** (Data/Instruction) or **RS** (Register select), depending on the display controller.

34.2.2.1 Example routines for connection to I/O pins

Examples can be found in the folder `Sample\LCD_X_Port`:

- `LCD_X_6800.c`, port routines for the 6800 parallel interface.
- `LCD_X_8080.c`, port routines for the 8080 parallel interface.

34.2.3 Indirect interface - 4 pin SPI

Using a 4 pin SPI interface is very similar to a parallel interface. To connect a LCD display using 4 pin SPI interface the lines A0, CLK, DATA, and CS must be connected to the CPU.

Typical block diagram



34.2.3.1 Example routines for connection to I/O pins

An example can be found in the folder `Sample\LCD_X_Port`:

- `LCD_X_SERIAL.c`, port routines for a serial interface.

This sample uses port pins for the communication. This works very slow but can be used with each CPU. This should be optimized by the customer by using the hardware support of the CPU for this kind of communication.

34.2.4 Indirect interface - 3 pin SPI

To connect a LCD display using 4 pin SPI interface the lines CLK, DATA, and CS must be connected to the CPU.

 © 2020 SEGGER Microcontroller GmbH

Typical block diagram



34.2.4.1 Example routines for connection to I/O pins

This interface does not have a separate line for distinguish between data and commands to be transmitted to the display controller. There is no standardized method to manage this. Some controllers use an additional bit for distinguish between data and command, other controllers work different.
Examples can be found in the folder `Sample\LCD_X_Port`:

- `LCD_X_Serial_3Pin.c`, port routines for a 3 pin serial interface.
- `LCD_X_Serial_3Wire.c`, port routines for a 3 pin serial interface.

34.2.5 Indirect interface - I2C bus

This kind of interface use only 2 lines and a standardized protocol for the communication with the display controller.

Typical block diagram



34.2.5.1 Example routines for connection to I/O pins

An example can be found in the folder `Sample\LCD_X_Port`:

- `LCD_X_I2CBUS.c`, port routines for a I2C bus interface.

Similar to the serial communication examples this example uses port lines for the communication which works not very fast. If the CPU support this kind of communication these routines should be optimized by using the hardware functions.

 © 2020 SEGGER Microcontroller GmbH

34.3 Hardware interface configuration

The following explains how to configure the hardware communication between display driver and display controller.

34.3.1 Direct interface

Drivers which make use of a direct interface are usually configured by specifying the address of the video memory. In order to do so the function `LCD_SetVRAMAddrEx()` can be called. Details can be found in the section *Display driver API* on page 2780.

34.3.2 Indirect interface

There are 2 kinds of display drivers:

- Run-time configurable drivers
- Compile-time configurable drivers

Configuring these kinds of drivers works differently:

- Run-time configuration means the driver can be compiled without being configured. The configuration is done at run-time. This type of driver can still be configured at run-time when placed in a library.
- A compile-time configurable driver requires the configuration in a configuration header file, which is included at compile-time of the driver.

34.3.2.1 Run-time configuration

Run-time configurable drivers do not need to be configured at compile time. So this drivers can be used in a precompiled library.
Each driver has its own function(s) for setting up the hardware interface. This is done by passing a pointer to a `GUI_PORT_API` structure containing function pointers to the hardware routines to be used:

34.3.2.1.1 Elements of structure GUI_PORT_API

8 bit interface

Element	Data type	Description
pfWrite8_A0	`void (*)(U8 Data)`	Pointer to a function which writes one byte to the controller with C/D line low.
pfWrite8_A1	`void (*)(U8 Data)`	Pointer to a function which writes one byte to the controller with C/D line high.
pfWriteM8_A0	`void (*)(U8 * pData, int NumItems)`	Pointer to a function which writes multiple bytes to the controller with C/D line low.
pfWriteM8_A1	`void (*)(U8 * pData, int NumItems)`	Pointer to a function which writes multiple bytes to the controller with C/D line high.
pfRead8_A0	`U8 (*)(void)`	Pointer to a function which reads one byte from the controller with C/D line low.
pfRead8_A1	`U8 (*)(void)`	Pointer to a function which reads one byte from the controller with C/D line high.

 © 2020 SEGGER Microcontroller GmbH

Element	Data type	Description
pfReadM8_A0	void (*)(U8 * pData, int NumItems)	Pointer to a function which reads multiple bytes from the controller with C/D line low.
pfReadM8_A1	void (*)(U8 * pData, int NumItems)	Pointer to a function which reads multiple bytes from the controller with C/D line high.

16 bit interface

Element	Data type	Description
pfWrite16_A0	void (*)(U16 Data)	Pointer to a function which writes one 16 bit value to the controller with C/D line low.
pfWrite16_A1	void (*)(U16 Data)	Pointer to a function which writes one 16 bit value to the controller with C/D line high.
pfWriteM16_A0	void (*)(U16 * pData, int NumItems)	Pointer to a function which writes multiple 16 bit values to the controller with C/D line low.
pfWriteM16_A1	void (*)(U16 * pData, int NumItems)	Pointer to a function which writes multiple 16 bit values to the controller with C/D line high.
pfRead16_A0	U16 (*)(void)	Pointer to a function which reads one 16 bit value from the controller with C/D line low.
pfRead16_A1	U16 (*)(void)	Pointer to a function which reads one 16 bit value from the controller with C/D line high.
pfReadM16_A0	void (*)(U16 * pData, int NumItems)	Pointer to a function which reads multiple 16 bit values from the controller with C/D line low.
pfReadM16_A1	void (*)(U16 * pData, int NumItems)	Pointer to a function which reads multiple 16 bit values from the controller with C/D line high.
pfReadM32_A1	void (*)(U32 * pData, int NumItems)	Pointer to a function which reads multiple 32 bit values from the controller with C/D line high.

32 bit interface

Element	Data type	Description
pfWrite32_A0	void (*)(U32 Data)	Pointer to a function which writes one 32 bit value to the controller with C/D line low.
pfWrite32_A1	void (*)(U32 Data)	Pointer to a function which writes one 32 bit value to the controller with C/D line high.

 © 2020 SEGGER Microcontroller GmbH

Element	Data type	Description
pfWriteM32_A0	void (*)(U32 * pData, int NumItems)	Pointer to a function which writes multiple 32 bit values to the controller with C/D line low.
pfWriteM32_A1	void (*)(U32 * pData, int NumItems)	Pointer to a function which writes multiple 32 bit values to the controller with C/D line high.
pfRead32_A0	U32 (*)(void)	Pointer to a function which reads one 32 bit value from the controller with C/D line low.
pfRead32_A1	U32 (*)(void)	Pointer to a function which reads one 32 bit value from the controller with C/D line high.
pfReadM32_A0	void (*)(U32 * pData, int NumItems)	Pointer to a function which reads multiple 32 bit values from the controller with C/D line low.
pfReadM32_A1	void (*)(U32 * pData, int NumItems)	Pointer to a function which reads multiple 32 bit values from the controller with C/D line high.

SPI interface

Element	Data type	Description
pfSetCS	void (*)(U8 NotActive)	Pointer to a function which is able to toggle the CS signal of the controller.

This structure contains function pointers for 8-, 16- and 32 bit access. Not all function pointers are used by each driver. The required functions are listed in the description of the according display driver.

Example

The following shows a configuration example for the driver GUIDRV_SLin. It creates and configures the driver, initializes the required function pointers of the GUI_PORT_API structure and passes them to the driver:

```
GUI_DEVICE * pDevice;
CONFIG_SLIN Config = {0};
GUI_PORT_API PortAPI = {0};
//
// Set display driver and color conversion
//
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SLIN_2, GUICC_2, 0, 0);
//
// Common display driver configuration
//
LCD_SetSizeEx (0, XSIZE, YSIZE);
LCD_SetVSizeEx(0, XSIZE, YSIZE);
//
// Driver specific configuration
//
Config.UseCache  = 1;
GUIDRV_SLin_Config(pDevice, &Config);
```

 © 2020 SEGGER Microcontroller GmbH

```
//
// Select display controller
//
GUIDRV_SLin_SetS1D13700(pDevice);
//
// Setup hardware access routines
//
PortAPI.pfWrite16_A0  = _Write0;
PortAPI.pfWrite16_A1  = _Write1;
PortAPI.pfWriteM16_A0 = _WriteM0;
PortAPI.pfRead16_A1   = _Read1;
GUIDRV_SLin_SetBus8(pDevice, &PortAPI);
```

Details can be found in the descriptions of the run-time configurable drivers.

34.3.2.2 Compile-time configuration

A compile-time configurable driver requires its configuration in a header file. This configuration file is included when compiling the display driver. The compile-time configurable drivers use distinct macros for accessing the hardware. It depends on the interface details which macros are used. The following shows which macros are used by which kind of interface.

Macros used by an indirect interface

The following table shows the used hardware access macros:

Type	Macro	Description
F	LCD_READ_A0	Reads a byte from LCD controller with A0 - line low.
F	LCD_READ_A1	Reads a byte from LCD controller with A0 - line high.
F	LCD_WRITE_A0	Writes a byte to the display controller with A0 - line low.
F	LCD_WRITE_A1	Writes a byte to the display controller with A0 - line high.
F	LCD_WRITEM_A1	Writes several bytes to the LCD controller with A0 - line high.

Macros used by a 4 pin SPI interface

The following table shows the used hardware access macros:

Type	Macro	Description
F	LCD_WRITE_A0	Writes a byte to the display controller with A0 (C/D) - line low.
F	LCD_WRITE_A1	Writes a byte to the display controller with A0 (C/D) - line high.
F	LCD_WRITEM_A1	Writes several bytes to the LCD controller with A0 (C/D) - line high.

Macros used by a 3 pin SPI interface

The following table shows the used hardware access macros:

Type	Macro	Description
F	LCD_WRITE	Writes a byte to the display controller.
F	LCD_WRITEM	Writes several bytes to the LCD controller.

Macros used by a I2C bus interface

The following table shows the used hardware access macros:

Type	Macro	Description
F	LCD_READ_A0	Reads a status byte from LCD controller.
F	LCD_READ_A1	Reads a data byte from LCD controller.
F	LCD_WRITE_A0	Writes a instruction byte to the display controller.
F	LCD_WRITE_A1	Writes a data byte to the display controller.

 © 2020 SEGGER Microcontroller GmbH

Type	Macro	Description
F	LCD_WRITEM_A1	Writes several data bytes to the LCD controller.

34.3.2.2.1 LCD_READ_A0

Description

Reads a byte from LCD controller with A0 (C/D) - line low.

Type

Function replacement

Prototype

```
#define LCD_READ_A0(Result)
```

Parameter	Description
Result	Result read. This is not a pointer, but a placeholder for the variable in which the value will be stored.

34.3.2.2.2 LCD_READ_A1

Description

Reads a byte from LCD controller with A0 (C/D) - line high.

Type

Function replacement

Prototype

```
#define LCD_READ_A1(Result)
```

Parameter	Description
Result	Result read. This is not a pointer, but a placeholder for the variable in which the value will be stored.

34.3.2.2.3 LCD_WRITE_A0

Description

Writes a byte to the display controller with A0 (C/D) - line low.

Type

Function replacement

Prototype

```
#define LCD_WRITE_A0(Byte)
```

Parameter	Description
Byte	Byte to write.

 © 2020 SEGGER Microcontroller GmbH

34.3.2.2.4 LCD_WRITE_A1

Description

Writes a byte to the display controller with A0 (C/D) - line low.

Type

Function replacement

Prototype

```
#define LCD_WRITE_A1(Byte)
```

Parameter	Description
Byte	Byte to write.

34.3.2.2.5 LCD_WRITEM_A1

Description

Writes several bytes to the LCD controller with A0 (C/D) - line high.

Type

Function replacement

Prototype

```
#define LCD_WRITEM_A1(paBytes, NumberOfBytes)
```

Parameter	Description
paBytes	Placeholder for the pointer to the first data byte.
NumberOfBytes	Number of data bytes to be written.

34.3.2.2.6 LCD_WRITE

Description

Writes a byte to the LCD controller.

Type

Function replacement

Prototype

```
#define LCD_WRITE(Byte)
```

Parameter	Description
Byte	Byte to write.

34.3.2.2.7 LCD_WRITEM

Description

Writes several bytes to the LCD controller.

Type

Function replacement

 © 2020 SEGGER Microcontroller GmbH

Prototype

```
#define LCD_WRITEM(paBytes, NumberOfBytes)
```

Parameter	Description
paBytes	Placeholder for the pointer to the first data byte.
NumberOfBytes	Number of data bytes to be written.

 © 2020 SEGGER Microcontroller GmbH

34.4 Non readable displays

Some display controllers with an indirect interface do not support reading back display data. Especially displays which are connected via SPI interface often have this limitation. In this case we recommend using a display data cache. For details how to enable a display data cache, refer to *Detailed display driver descriptions* on page 2643.
On systems with a very small RAM it is sometimes not possible to use a display data cache. If a display is not readable and a display data cache can not be used some features of emWin will not work. The list below shows these features:

- Cursors and Sprites
- XOR-operations, required for text cursors in EDIT and MULTIEDIT widgets
- Alpha blending
- Antialiasing

This is valid for all drivers where one data unit (8 or 16 bit) represents one pixel. Display drivers, where one data unit represents more than one pixel, can not be used if no display data cache is available and the display is not readable. An example is the `GUIDRV_Page1bpp` driver where one byte represents 8 pixels.

 © 2020 SEGGER Microcontroller GmbH

34.5 Display orientation

If the original display orientation does not match the requirements, there are different ways to change the display orientation:

- Driver based configuration of the desired orientation
- Runtime rotation
- Using `GUI_SetOrientation()`

34.5.1 Driver based configuration of display orientation

If the display driver supports different orientations it is recommended to use the driver for setting up the right orientation. The way how to configure the display orientation then depends on the display driver to be used. Whereas the display orientation of the most common drivers is run-time configurable some drivers need to be configured at compile time.

34.5.1.1 Run-time configuration

The display orientation of the most common driver is determined by creating the display driver device in `LCD_X_Config()` using the proper macro. The according macros are listed within the description of *`GUIDRV_Lin`* on page 2676.

34.5.1.2 Compile-time configuration

The display orientation of some drivers with indirect interface like `GUIDRV_CompactColor_16` needs to be configured at compile time in the configuration file of the driver.

Display orientations

There are 8 possible display orientations; the display can be turned 0°, 90°, 180° or 270° and can also be viewed from top or from bottom. The default orientation is 0° and top view. These 4 × 2 = 8 different display orientations can also be expressed as a combination of 3 binary switches: X-mirroring, Y-mirroring and X/Y swapping. For this purpose, the binary configuration macros listed below can be used with each driver in any combination. If your display is not oriented well, take a look at the config switches in the table below to make it work properly. The orientation is handled as follows: Mirroring in X and Y first, then swapping (if selected).

Display	Orientation macros in driver configuration file	Display	Orientation macros in driver configuration file
	No orientation macro required		`#define LCD_MIRROR_Y 1`
	`#define LCD_MIRROR_X 1`		`#define LCD_MIRROR_X 1` `#define LCD_MIRROR_Y 1`
	`#define LCD_SWAP_XY 1`		`#define LCD_SWAP_XY 1` `#define LCD_MIRROR_Y 1`

 © 2020 SEGGER Microcontroller GmbH

Display	Orientation macros in driver configuration file	Display	Orientation macros in driver configuration file

	`#define LCD_SWAP_XY 1`
	`#define LCD_MIRROR_X 1`
			`#define LCD_SWAP_XY 1`
			`#define LCD_MIRROR_X 1`
			`#define LCD_MIRROR_Y 1`

Details on how to use multiple orientations simultaneously can be found in the section *Run-time screen rotation* on page 2412.

34.5.2 Runtime rotation

The runtime rotation functions make it possible to change the current driver at runtime. It allows to add up to 7 drivers to the primarily configured (default) driver of a layer. Basically usage is the following:

- Basic driver setup (default driver) in `LCD_X_Config()`.
- Add additional drivers to be used for different orientations.
- Optionally set a configuration callback routine.
- Use the API functions to change the driver.

When selecting a driver the current one will be deleted and unlinked and a new one is created and linked into the device chain of the layer. Immediately after creating a new driver the configuration callback function is called before the driver will be initialized.
The color configuration to be used when creating and linking a driver is taken from the default driver.

The following set of functions may be used:

Routine	Description
`LCD_ROTATE_AddDriver()`	Adds a driver to be used for display rotation.
`LCD_ROTATE_AddDriverEx()`	Adds a driver to be used for display rotation of the given layer.
`LCD_ROTATE_DecSel()`	Decrements the current selection.
`LCD_ROTATE_DecSelEx()`	Decrements the current selection of the given layer.
`LCD_ROTATE_IncSel()`	Increments the current selection.
`LCD_ROTATE_IncSelEx()`	Increments the current selection of the given layer.
`LCD_ROTATE_SetCallback()`	Sets a function to be called immediately after a driver has been selected.
`LCD_ROTATE_SetSel()`	Selects the driver with the given index to be used.
`LCD_ROTATE_SetSelEx()`	Selects the driver with the given index to be used for the given layer.

 © 2020 SEGGER Microcontroller GmbH

34.5.2.1 LCD_ROTATE_AddDriver()

Description

Adds a driver to be used for display rotation. It is recommended that it is a variant of the default driver with different orientation.

Prototype

```
int LCD_ROTATE_AddDriver(const GUI_DEVICE_API * pDriver);
```

Parameters

Parameter	Description
pDriver	Pointer to a display driver API.

Return value

0 on success.
1 on error.

 © 2020 SEGGER Microcontroller GmbH

34.5.2.2 LCD_ROTATE_AddDriverEx()

Description

Adds a driver to be used for display rotation of the given layer. It is recommended that it is a variant of the default driver with different orientation.

Prototype

```
int LCD_ROTATE_AddDriverEx(const GUI_DEVICE_API * pDeviceAPI,
                           int                    LayerIndex);
```

Parameters

Parameter	Description
pDriver	Pointer to a display driver API.
LayerIndex	Layer index to be used.

Return value

0 on success.
1 on error.

 © 2020 SEGGER Microcontroller GmbH

34.5.2.3 LCD_ROTATE_DecSel()

Description

Decrements the current selection. If the current driver is the default driver it selects the driver last added.

Prototype

```
int LCD_ROTATE_DecSel(void);
```

Return value

0	on success.
1	on error.

 © 2020 SEGGER Microcontroller GmbH

34.5.2.4 LCD_ROTATE_DecSelEx()

Description

Decrements the current selection of the given layer. If the current driver is the default driver it selects the driver last added.

Prototype

```
int LCD_ROTATE_DecSelEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer index to be used.

Return value

0 on success.
1 on error.

 © 2020 SEGGER Microcontroller GmbH

34.5.2.5 LCD_ROTATE_IncSel()

Description

Increments the current selection. If the current driver is the last driver it selects the default driver.

Prototype

```
int LCD_ROTATE_IncSel(void);
```

Return value

0	on success.
1	on error.

 © 2020 SEGGER Microcontroller GmbH

34.5.2.6 LCD_ROTATE_IncSelEx()

Description

Increments the current selection of the given layer. If the current driver is the last driver it selects the default driver.

Prototype

```
int LCD_ROTATE_IncSelEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer index to be used.

Return value

0 on success.
1 on error.

 © 2020 SEGGER Microcontroller GmbH

34.5.2.7 LCD_ROTATE_SetCallback()

Description

Sets a function to be called immediately after a driver has been selected. It is called immediately after creation and before initializing.

Prototype

```
int LCD_ROTATE_SetCallback(void ( *pcbConfig)(GUI_DEVICE * , int , int ),
                           int  LayerIndex);
```

Parameters

Parameter	Description
pCbOnConfig	Function to be called to configure driver.

Return value

0 on success.
1 on error.

Additional information

Main purpose of that function is to set a routine which is called by emWin to configure all properties of the driver. It is called immediately after selecting a driver. At least the display size has to be configured. In general it has to configure all things which normally are set in `LCD_X_Config()`.

 © 2020 SEGGER Microcontroller GmbH

34.5.2.8 LCD_ROTATE_SetSel()

Description

Selects the driver with the given index to be used.

Prototype

```
int LCD_ROTATE_SetSel(int Index);
```

Parameters

Parameter	Description
Index	Zero-based index of the driver to be used.

Return value

0 on success.
1 on error.

 © 2020 SEGGER Microcontroller GmbH

34.5.2.9 LCD_ROTATE_SetSelEx()

Description

Selects the driver with the given index to be used for the given layer.

Prototype

```
int LCD_ROTATE_SetSelEx(int Index,
                        int LayerIndex);
```

Parameters

Parameter	Description
Index	Zero-based index of the driver to be used.
LayerIndex	Layer to be used.

Return value

0 on success.
1 on error.

 © 2020 SEGGER Microcontroller GmbH

34.5.3 Function based configuration of display orientation

Another possibility to set up the display orientation is to call `GUI_SetOrientation()`. Using these functions is recommended if the display driver can not be used.

Routine	Description
`GUI_SetOrientation()`	This function changes the display orientation by using a rotation device.
`GUI_SetOrientationEx()`	This function changes the orientation in the specified layer by using a rotation device.

 © 2020 SEGGER Microcontroller GmbH

34.5.3.1 GUI_SetOrientation()

Description

This function changes the display orientation by using a rotation device.

Prototype

```
int GUI_SetOrientation(int Orientation);
```

Parameters

Parameter	Description
Orientation	See the table below for an overview of valid values.

Resulting display	Value to use for GUI_SetOrientation()	Resulting display	Value to use for GUI_SetOrientation()
	0		GUI_MIRROR_Y
	GUI_MIRROR_X		GUI_MIRROR_X | GUI_MIRROR_Y
	GUI_SWAP_XY		GUI_SWAP_XY | GUI_MIRROR_Y
	GUI_SWAP_XY | GUI_MIRROR_X		GUI_SWAP_XY | GUI_MIRROR_X | GUI_MIRROR_Y

Return value

0 on success.
1 on error.

Additional information

The rotation device covers the complete virtual screen within an internal screen buffer. Because of this the use of this function requires additional memory for this additional screen buffer. The number of required bytes can be calculated as follows:

```
Virtual xSize × Virtual ySize × BytesPerPixel
```

The number of bytes per pixel is for configurations from 1-8bpp 1, for systems with more than 8bpp up to 16bpp 2 and for systems with more than 16bpp 4. Each drawing operation first updates this buffer. After this the affected pixels are passed to the display driver device.

 © 2020 SEGGER Microcontroller GmbH

34.5.3.2 GUI_SetOrientationEx()

Description

This function changes the orientation in the specified layer by using a rotation device.

Prototype

```
int GUI_SetOrientationEx(int Orientation,
                         int LayerIndex);
```

Parameters

Parameter	Description
`Orientation`	Refer to *`GUI_SetOrientation`* on page 2636 for an overview of valid values.
`LayerIndex`	Index of the layer which `Orientation` has to be (re-)configured.

Return value

0 on success.
1 on error.

Additional information

See `GUI_SetOrientation()`.

 © 2020 SEGGER Microcontroller GmbH

34.5.4 Orientation flags

Description

Flags used by several GUI functions to define the display orientation.

Definition

```
#define GUI_MIRROR_X    (1 << 0)
#define GUI_MIRROR_Y    (1 << 1)
#define GUI_SWAP_XY     (1 << 2)
```

Symbols

Definition	Description
GUI_MIRROR_X	Mirroring the X-axis.
GUI_MIRROR_Y	Mirroring the Y-axis.
GUI_SWAP_XY	Swapping X- and Y-axis.

 © 2020 SEGGER Microcontroller GmbH

34.6 Display driver callback function

A display driver requires a callback function. It is called by the driver for several tasks. One task is putting the display driver into operation which is also explained in the chapter *Configuration* on page 2396. It is also called for other tasks which require hardware related operations like switching the display on and off or setting a lookup table entry.

> **Note**
>
> Refer to `LCD_X_DisplayDriver()` for a full API description of the function.

34.6.1 Commands passed to the callback function

The following explains the common commands passed to the callback function. For details about display driver specific commands, refer to *Detailed display driver descriptions* on page 2643. They are described under the topic 'Additional callback commands'.

34.6.1.1 LCD_X_INITCONTROLLER

Description

As mentioned above the application should initialize the display controller and put it into operation if the callback routine receives this command. No parameters are passed on this command. Typically an initialization routine which initializes the registers of the display controller should be called in reaction of this command.

Parameters

None.

34.6.1.2 LCD_X_ON

Description

This command switches the display on.

Parameters

None.

34.6.1.3 LCD_X_OFF

Description

This command switches the display off.

Parameters

None.

34.6.1.4 LCD_X_SETALPHA

Description

Sets the required layer alpha value. Should be used to set up the layer alpha register.

Parameters

`pData` points to a data structure of type `LCD_X_SETALPHA_INFO`.

 © 2020 SEGGER Microcontroller GmbH

Elements of structure LCD_X_SETALPHA_INFO

Data type	Element	Description
int	Alpha	Alpha value to be used. 255 for transparent and 0 for opaque.

34.6.1.5 LCD_X_SETLUTENTRY

Description

A lookup table entry should be set. The typical reaction should be writing an entry into the lookup table of the display controller.

Parameters

pData points to a data structure of type LCD_X_SETLUTENTRY_INFO.

Elements of structure LCD_X_SETLUTENTRY_INFO

Data type	Element	Description
LCD_COLOR	Color	RGB value of the color to be written to the LUT. Note that the format required by the hardware could be different to the RGB format.
U8	Pos	Zero based index of the LUT entry to be set.

34.6.1.6 LCD_X_SETORG

Description

The function is used in relation with virtual screens. It is called if the origin of the display should be set. A typical reaction can be modifying the frame buffer start address.

Parameters

pData points to a data structure of type LCD_X_SETORG_INFO.

Elements of structure LCD_X_SETORG_INFO

Data type	Element	Description
int	xPos	New X-position of the physical display position within the virtual screen.
int	yPos	New Y-position of the physical display position within the virtual screen.

34.6.1.7 LCD_X_SETPOS

Description

This function is used in relation with setting up the layer position. Please note that normally a layer could not exceed the physical range of a display. But it is possible to achieve the effect of a layer positioned outside of the display without modifying the content of the frame buffer. Such an effect could be used for example for moving a picture into the visible area of the display and/or for shifting it out of the display without any additional CPU load for repainting.
If for example a layer should look like starting with a negative X/Y-coordinate, for example (-10, -5) that values could not be used directly for setting up the registers of the layer position. The physical layer coordinate needs to be (0, 0) in that case. To achieve the effect of a negative position an offset needs to be added to the framebuffer start address. Further the visible length and height of the layer need to be adapted by subtracting the intersection

 © 2020 SEGGER Microcontroller GmbH

in X and Y. If the given coordinates (for example passed to GUI_SetLayerPosEx()) lead into a completely invisible layer emWin automatically sends a LCD_X_SETVIS command.

Parameters

pData points to a data structure of type LCD_X_SETPOS_INFO.

Elements of structure LCD_X_SETPOS_INFO

Data type	Element	Description
int	xPos	Physical X-position to be used to set up the layer position register.
int	yPos	Physical Y-position to be used to set up the layer position register.
int	xLen	Physical X-size of the layer.
int	yLen	Physical Y-size of the layer.
int	BytesPerPixel	Bytes used for one pixel.
U32	Off	Offset to be added to the framebuffer start address.

Requirements

To be able to use that functionality the following must be possible:

- A stride register should exist which defines the number of bytes from one line of frame buffer data to the next line.
- It must be possible to set up the frame buffer start address to any pixel address.
- The size of the visual area of the layer must be configurable.

34.6.1.8 LCD_X_SETSIZE

Description

Used to set up the size of a layer at runtime.

Parameters

pData points to a data structure of type LCD_X_SETSIZE_INFO.

Elements of structure LCD_X_SETSIZE_INFO

Data type	Element	Description
int	xSize	New X-size to be used for the given layer.
int	ySize	New Y-size to be used for the given layer.

Additional information

After changing the size of a layer at runtime normally the content of the layer needs to be repainted. Please note that this is not done automatically.

34.6.1.9 LCD_X_SETVIS

Description

Used to set up the visibility of a layer at runtime.

Parameters

pData points to a data structure of type LCD_X_SETVIS_INFO.

 © 2020 SEGGER Microcontroller GmbH

Elements of structure LCD_X_SETVIS_INFO

Data type	Element	Description
int	OnOff	1 if layer should be visible, 0 for invisible.

34.6.1.10 LCD_X_SETVRAMADDR

Description

This command is passed by the driver to tell the callback routine the start address of the video RAM. The typical reaction should be writing the address to the frame buffer start address register.

Parameters

pData points to a data structure of type LCD_X_SETVRAMADDR_INFO.

Elements of structure LCD_X_SETVRAMADDR_INFO

Data type	Element	Description
void *	pVRAM	Points to the start address of the video RAM. This address is typically written to the video RAM base address register of the display controller.

34.6.1.11 LCD_X_SHOWBUFFER

Description

This command is used in relation with multiple buffers. It tells the callback routine that the buffer with the given index should become visible.

Parameters

pData points to a data structure of type LCD_X_SETVRAMADDR_INFO.

Elements of structure LCD_X_SHOWBUFFER_INFO

Data type	Element	Description
int	Index	Index of buffer which should become visible as soon as possible.

Additional information

Making the buffer visible could be done by setting the right framebuffer start address immediately or by doing that within an ISR which is called in the vertical non display period.

 © 2020 SEGGER Microcontroller GmbH

34.7 Detailed display driver descriptions

34.7.1 GUIDRV_BitPlains

This driver has been developed for systems without display controller. It manages each color bit in a separate plain. This means if the color depth is for example 4 bits per pixel the driver manages 4 bit plains each containing one bit.
Initially the driver has been made to drive monochrome and color TFTs with an R323C/111 CPU via SPI interface. But the driver can be used also for similar applications.
The driver does only manage the content of the bit plains. It does not contain any display controller specific code.

34.7.1.1 Supported hardware

Controllers

None.

Bits per pixel

The driver has been developed for a color depth of 1 to 8 bits per pixel.

Interface

It is required to write an application defined routine which uses the content of the bit plains to generate the color signals for the display. The driver comes with a sample for the R32C/111 CPU which refreshes the display via timer interrupt routine using the SPI interface.

34.7.1.2 Driver selection

To use `GUIDRV_BitPlains` for the given display, the following command can be used e.g.:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_BITPLAINS, GUICC_M111, 0, 0);
```

More information about using the proper palette mode can be found in the chapter *Colors* on page 617.

 © 2020 SEGGER Microcontroller GmbH

34.7.1.3 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the display. The display memory is divided into separate plains for each bit of the colors. This means that bit 0 of each pixel is stored in plain 0, the bit 1 in plain 1 and so on. The advantage of this method is that each color bit of the display data can be accessed very quickly.

34.7.1.4 RAM requirements

The required size of the display memory area can be calculated as follows:

```
Size = BitsPerPixel × (LCD_XSIZE + 7) ÷ 8 × LCD_YSIZE
```

> **Note**
>
> The pointers to the bit plain areas need to be passed to the configuration routine of the driver. They are not allocated within the driver but from application side.

34.7.1.5 Hardware configuration

Normally, the hardware interface is an interrupt service routine (ISR) which updates the display. The driver comes with an example written in "C" code. This routine should serve as an example.

34.7.1.6 Additional run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_BitPlains_Config()	This function passes a pointer to a CONFIG_BITPLAINS structure to the driver.
LCD_SetVRAMAddrEx()	Sets the address of the video RAM.

 © 2020 SEGGER Microcontroller GmbH

Elements of structure CONFIG_VRAM_BITPLAINS

Data type	Element	Description
U8 *	apVRAM	Array of pointers to the memory locations to be used by the driver for each bit plain. If the driver for example works in 2bpp mode only the first 2 pointers are used (One plain for each bit of the color information).

 © 2020 SEGGER Microcontroller GmbH

34.7.1.7 GUIDRV_BitPlains_Config()

Description

This function passes a pointer to a CONFIG_BITPLAINS structure to the driver.

Prototype

```
void GUIDRV_BitPlains_Config(GUI_DEVICE       * pDevice,
                             CONFIG_BITPLAINS * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_BITPLAINS structure explained below.

Elements of structure CONFIG_BITPLAINS

Data type	Element	Description
int	Mirror	Config switch to mirror the bits of the display data.

Configuration example

```
//
// Data arrays to be used by the display driver
//
static U8 _aPlain_0[BYTES_PER_LINE * YSIZE_PHYS];
static U8 _aPlain_1[BYTES_PER_LINE * YSIZE_PHYS];
static U8 _aPlain_2[BYTES_PER_LINE * YSIZE_PHYS];
//
// Structure to be passed to the driver
//
static struct {
  U8 * apVRAM[8];
} _VRAM_Desc = {
  _aPlain_0,
  _aPlain_1,
  _aPlain_2,
};
void LCD_X_Config(void) {
  //
  // Set display driver and color conversion for 1st layer
  //
  GUI_DEVICE_CreateAndLink(GUIDRV_BITPLAINS, COLOR_CONVERSION, 0, 0);
  //
  // Display driver configuration
  //
  if (LCD_GetSwapXY()) {
    LCD_SetSizeEx (0, YSIZE_PHYS, XSIZE_PHYS);
    LCD_SetVSizeEx(0, YSIZE_PHYS, XSIZE_PHYS);
  } else {
    LCD_SetSizeEx (0, XSIZE_PHYS, YSIZE_PHYS);
    LCD_SetVSizeEx(0, XSIZE_PHYS, YSIZE_PHYS);
  }
  //
  // Initialize VRAM access of the driver
  //
  LCD_SetVRAMAddrEx(0, (void *)&_VRAM_Desc);
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.2 GUIDRV_DCache

GUIDRV_DCache has been developed to minimize the communication between emWin and the display controller. It uses 2 caches to be able to check exactly which pixels have been changed between locking and unlocking the cache. When locking the cache the driver makes a copy of the current cache. When unlocking it, it checks exactly which pixels have been changed. Only the changed pixels will be send to the controller.
Using this double cache driver makes sense if the performance bottleneck is the communication between CPU and display controller.
The driver can not be used stand alone. It is required to use a 'real' display driver for the drawing operations.
GUIDRV_DCache is part of the emWin basic package.

34.7.2.1 Supported hardware

The double cache driver is able to work with each runtime configurable display driver which works with 16bpp color format.

34.7.2.2 Driver selection

To be able to use this driver the following call has to be made:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_DCACHE, GUICC_1, 0, Layer);
```

34.7.2.3 RAM requirements

As the drivers name implies it uses 2 caches. Currently only a color depth of 1bpp is supported by the driver. The RAM usage can be calculated as follows:

```
Size = 2 × (LCD_XSIZE + 7) ÷ 8 × LCD_YSIZE
```

34.7.2.4 Run-time configuration

First the 'real' driver should be created and configured:

```
pDriver = GUI_DEVICE_Create(DISPLAY_DRIVER, GUICC_XXX, 0, Layer);
//
// Configuration of #real# driver
//
.
.
.
```

GUICC_XXX means any 16bpp color conversion scheme. After that the double cache driver can be created and configured:

```
//
// Create and configure (double) cache driver, ...
//
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_DCACHE, GUICC_1, 0, Layer);
//
// ... set size, ...
//
LCD_SetSizeEx (0, XSIZE_PHYS,  YSIZE_PHYS);
LCD_SetVSizeEx(0, VXSIZE_PHYS, VYSIZE_PHYS);
//
// ...set color depth, ...
//
GUIDRV_DCache_SetMode1bpp(pDevice);
```

Then the 'real' driver should be added for doing the drawing operations:

 © 2020 SEGGER Microcontroller GmbH

```
//
// ... and add real driver.
//
GUIDRV_DCache_AddDriver(pDevice, pDriver);
```

34.7.2.5 Configuration API

Routine	Description
GUIDRV_DCache_AddDriver()	Adds the 'real' driver to the DCache driver which is used for the drawing operations.
GUIDRV_DCache_SetMode1bpp()	Sets the 1bpp mode for the DCache driver.

 © 2020 SEGGER Microcontroller GmbH

34.7.2.5.1 GUIDRV_DCache_AddDriver()

Description

Adds the ’real’ driver to the DCache driver which is used for the drawing operations.

Prototype

```
void GUIDRV_DCache_AddDriver(GUI_DEVICE * pDevice,
                             GUI_DEVICE * pDriver);
```

Parameters

Parameter	Description
pDevice	Pointer to the DCache driver device.
pDriver	Pointer to the real driver device.

Additional information

The used driver should work in 16bpp mode because the double cache driver currently only supports 16bpp output.

 © 2020 SEGGER Microcontroller GmbH

34.7.2.5.2 GUIDRV_DCache_SetMode1bpp()

Description

Sets the 1bpp mode for the DCache driver.

Prototype

```
void GUIDRV_DCache_SetMode1bpp(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the DCache driver device.

Additional information

Currently the DCache driver works only with a color depth of 1bpp.

 © 2020 SEGGER Microcontroller GmbH

34.7.3 GUIDRV_Dist

GUIDRV_Dist has been developed to support displays with multiple controllers. It is able to support multiple display areas each driven by a separate display controller. The distribution driver passes the drawing operations to the according display driver. This also works with overlapping operations. In these cases the operations are divided into sub operations for each affected controller. GUIDRV_Dist is part of the emWin basic package.

34.7.3.1 Supported hardware

The distribution driver is able to work with each runtime configurable display driver. Please note that it is required that each of the configured display drivers use the same color conversion as the distribution driver.

34.7.3.2 Driver selection

To be able to use this driver the following call has to be made:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_DIST, COLOR_CONVERSION, 0, Layer);
```

34.7.3.3 RAM requirements

None.

34.7.3.4 Run-time configuration

After the driver has been created the actual display drivers should be also created and added to the distribution device:

```
pDevice0 = GUI_DEVICE_Create(DISPLAY_DRIVER, COLOR_CONVERSION, 0, -1);
pDevice1 = GUI_DEVICE_Create(DISPLAY_DRIVER, COLOR_CONVERSION, 0, -1);
GUIDRV_Dist_AddDriver(pDevice, pDevice0, &Rect0);
GUIDRV_Dist_AddDriver(pDevice, pDevice1, &Rect1);
```

 © 2020 SEGGER Microcontroller GmbH

34.7.3.5 GUIDRV_Dist_AddDriver()

Description

Adds a display driver to the distribution driver.

Prototype

```
void GUIDRV_Dist_AddDriver(GUI_DEVICE * pDevice,
                           GUI_DEVICE * pDriver,
                           GUI_RECT   * pRect);
```

Parameters

Parameter	Description
pDevice	Pointer to the already created distribution device.
pDriver	Pointer to the already created driver device to be added.
pRect	Pointer to the rectangle in which outputs have to affect the driver.

Configuration example

```
void LCD_X_Config(void) {
  //
  // Set display driver and color conversion for 1st layer
  //
  pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_DIST, COLOR_CONVERSION, 0, 0);
  //
  // Display size configuration
  //
  LCD_SetSizeEx (0, XSIZE_PHYS,  YSIZE_PHYS);
  LCD_SetVSizeEx(0, VXSIZE_PHYS, VYSIZE_PHYS);
  //
  // Create first display driver
  //
  pDevice0 = GUI_DEVICE_Create(DISPLAY_DRIVER, COLOR_CONVERSION, 0, -1);
  //
  // Configuration of first driver
  //
  ...
  //
  // Create second display driver
  //
  pDevice1 = GUI_DEVICE_Create(DISPLAY_DRIVER, COLOR_CONVERSION, 0, -1);
  //
  // Configuration of second driver
  //
  ...
  //
  // Add display drivers to distribution driver
  //
  Rect0.x0 = 0;
  Rect0.y0 = 160;
  Rect0.x1 = 223;
  Rect0.y1 = 319;
  GUIDRV_Dist_AddDriver(pDevice, pDevice0, &Rect0);
  Rect1.x0 = 0;
  Rect1.y0 = 0;
  Rect1.x1 = 223;
  Rect1.y1 = 159;
  GUIDRV_Dist_AddDriver(pDevice, pDevice1, &Rect1);
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.4 GUIDRV_FlexColor

34.7.4.1 Supported hardware

Controllers

The supported display controllers are listed in the description of the function *GUIDRV_FlexColor_SetFunc* on page 2657.

Bits per pixel

Supported color depth is 16, 18 and 24 bpp.

Interfaces

The driver supports 8-bit, 9-bit, 16-bit and 18-bit indirect interface.

34.7.4.2 Driver selection

To be able to use this driver the following call has to be made:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_FLEXCOLOR, COLOR_CONVERSION, 0, Layer);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

34.7.4.3 Display data RAM organization



 © 2020 SEGGER Microcontroller GmbH

34.7.4.4 RAM requirements

This display driver requires approx. 500 Bytes to work and a line buffer. The size of the line buffer gets calculated as follow:

```
LCD_XSIZE × ((BitsPerPixel + 7) ÷ 8)
```

It can also be used with and without a display data cache, containing a complete copy of the content of the display data RAM. The amount of memory used by the cache is:

```
LCD_XSIZE × LCD_YSIZE × BytesPerPixel
```

BytesPerPixel is 2 for 16bpp mode and 4 for 18bpp mode. Using a cache avoids reading operations from the display controller in case of XOR drawing operations and further it speeds up string output operations.

34.7.4.5 Run-time configuration API

The following table lists the available run-time configuration routines:

Routine	Description
LCD_SetDevFunc()	The function sets additional and / or user defined functions of the display driver.

34.7.4.6 Commands supported by LCD_SetDevFunc

Command	Description
LCD_DEVFUNC_READMPIXELS	Can be used to set a custom defined routine for reading multiple pixels from the display controller.
LCD_DEVFUNC_READPIXEL	Can be used to set a custom defined routine for reading a single pixel from the display controller.

Further information about the LCD layer routines can be found under *Display driver API* on page 2780.

Important note on reading back pixel data from the controller

Because of the plurality of the supported display controllers and their operation modes the driver has not been tested with each interface of each supported controller. The behavior of the controller when reading back pixel data often depends on custom configuration and hardware details. Because of that it could happen, that the driver has no appropriate reading function(s) available. In that case the above explained function LCD_SetDevFunc() can be used to set application defined functions for reading back pixel data.
The main problem for the driver here is not getting data from the driver. Getting the color bits in the right order is the problem here. The custom defined functions need to supply 'pixel index' values. This index format needs to comply to the index format determined by the color conversion routines configured for the driver device. Because the data supplied by the hardware interface functions of the driver in most cases does not have the right index format, the reading routines need to convert that raw data into the required pixel index format determined by the driver device configuration. For details about the hardware interface functions please also refer to GUIDRV_FlexColor_SetFunc() and its parameter pHW_API. For details about the pixel index format please also refer to GUI_DEVICE_CreateAndLink() and its parameter pColorConvAPI and the chapter *Colors* on page 617. A sample configuration which shows how custom reading functions can be achieved is available in the configuration file sample folder shipped with the driver.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7 Configuration API

Routine	Description
Common configuration routines	
GUIDRV_FlexColor_SetFunc()	Configures bus, cache, and hardware routines.
GUIDRV_FlexColor_Config()	Configures orientation and offset of the SEG- and COM-lines.
GUIDRV_FlexColor_SetOrientation()	Sets a new orientation for the given layer.
Detailed interface selection	
GUIDRV_FlexColor_SetInterface66712_B9()	Set up bus interface (TYPE_I, TYPE_II).
GUIDRV_FlexColor_SetInterface66712_B18()	Set up bus interface (TYPE_I, TYPE_II).
GUIDRV_FlexColor_SetInterface66715_B9()	Set up bus interface (TYPE_I, TYPE_II).
GUIDRV_FlexColor_SetInterface66715_B18()	Set up bus interface (TYPE_I, TYPE_II).
Configuration of read back function	
GUIDRV_FlexColor_SetReadFunc66709_B16()	Read back function settings.
GUIDRV_FlexColor_SetReadFunc66712_B9()	Read back function settings.
GUIDRV_FlexColor_SetReadFunc66712_B16()	Read back function settings.
GUIDRV_FlexColor_SetReadFunc66715_B9()	Read back function settings.
GUIDRV_FlexColor_SetReadFunc66715_B16()	Read back function settings.
GUIDRV_FlexColor_SetReadFunc66720_B16()	Read back function settings.
GUIDRV_FlexColor_SetReadFunc66772_B8()	Read back function settings.
GUIDRV_FlexColor_SetReadFunc66772_B16()	Read back function settings.

The above set of configuration functions set up the detailed behavior of the driver. In short they do the following:

GUIDRV_FlexColor_SetFunc()

Configures the LCD-controller to be used, color depth and cache settings.

GUIDRV_FlexColor_Config()

Configures display orientation, dummy reads and first SEG- and COM-lines.

GUIDRV_FlexColor_SetInterface()

Configures the bus interface to be used.

GUIDRV_FlexColor_SetReadFunc()

Configures the behavior when reading back pixel data.

Calling sequence

The following shows a recommended sequence of configuration function calls:

```
GUI_DEVICE_CreateAndLink()
GUIDRV_FlexColor_Config()
LCD_SetSizeEx()
LCD_SetVSizeEx()
GUIDRV_FlexColor_SetInterface()
```

 © 2020 SEGGER Microcontroller GmbH

```
GUIDRV_FlexColor_SetReadFunc()
GUIDRV_FlexColor_SetFunc()
```

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.1 GUIDRV_FlexColor_SetFunc()

Description

Configures bus width, cache usage and hardware routines.

Prototype

```
void GUIDRV_FlexColor_SetFunc(GUI_DEVICE   * pDevice,
                              GUI_PORT_API * pHW_API,
                              void           ( *pfFunc)(GUI_DEVICE * ),
                              void           ( *pfMode)(GUI_DEVICE * ));
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device structure.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.
pfFunc	Controller selection macro. See table below.
pfMode	See table below.

Permitted values for parameter pfFunc Supported display controller	
GUIDRV_FLEXCOLOR_F66702	Set up the driver to use one of the following controllers: • Solomon SSD1284, SSD1289, SSD1298
GUIDRV_FLEXCOLOR_F66708	Set up the driver to use one of the following controllers: • FocalTech FT1509 • Ilitek ILI9320, ILI9325, ILI9328, ILI9335 • LG Electronics LGDP4531, LGDP4551 • OriseTech SPFD5408 • Renesas R61505, R61580
GUIDRV_FLEXCOLOR_F66709	Set up the driver to use one of the following controllers: • Epson S1D19122 • Himax HX8353, HX8325A, HX8357, HX8369 • Ilitek ILI9338, ILI9340, ILI9341, ILI9342, ILI9163, ILI9481, ILI9486, ILI9488, ILI9806H • Lucid Display Technology LDT7138 • Novatek NT39122 • Orisetech SPFD54124C, SPFD5414D • Renesas R61516, R61526 • Sitronix ST7628, ST7637, ST7687, ST7715, ST7735, ST7789, ST7796 • Solomon SSD1355
GUIDRV_FLEXCOLOR_F66712	Set up the driver to use one of the following controllers: • Himax HX8340, HX8347, HX8352, HX8367
GUIDRV_FLEXCOLOR_F66714	Set up the driver to use the following controller: • Solomon SSD2119
GUIDRV_FLEXCOLOR_F66715	Set up the driver to use one of the following controllers: • Himax HX8352B
GUIDRV_FLEXCOLOR_F66718	Set up the driver to use the following controller: • Syncoam SEPS525
GUIDRV_FLEXCOLOR_F66719	Set up the driver to use the following controller: • Samsung S6E63D6
GUIDRV_FLEXCOLOR_F66720	Set up the driver to use one of the following controllers: • Solomon SSD1961, SSD1963
GUIDRV_FLEXCOLOR_F66721	Set up the driver to use one of the following controller:

 © 2020 SEGGER Microcontroller GmbH

	• RAIO RA8870, RA8875
GUIDRV_FLEXCOLOR_F66722	Set up the driver to use one of the following controller: • Solomon SSD1351, SSD1353
GUIDRV_FLEXCOLOR_F66723	Set up the driver to use one of the following controller: • Lucid Display Technology LDT7138
GUIDRV_FLEXCOLOR_F66724	Set up the driver to use one of the following controllers: • Sitronix ST7775
GUIDRV_FLEXCOLOR_F66725	Set up the driver to use one of the following controllers: • UltraChip UC1698
GUIDRV_FLEXCOLOR_F66772	Set up the driver to use one of the following controllers: • Himax HX8301 • Ilitek ILI9220, ILI9221 • LG Electronics LGDP4525 • Samsung S6D0117 • Sitronix ST7712 • Hitachi HD66772

The display controllers listed in the table above are the currently known controllers compatible to the driver. Please note that the used numbers of the selection macros are compatible to some of the LCD_CONTROLLER macro of the driver GUIDRV_CompactColor_16. This makes it easy to migrate from the compile time configurable GUIDRV_CompactColor_16 to the runtime configurable GUIDRV_FlexColor.

Permitted values for parameter pfMode	
GUIDRV_FLEXCOLOR_M16C0B8	16bpp, no cache, 8 bit bus
GUIDRV_FLEXCOLOR_M16C1B8	16bpp, cache, 8 bit bus
GUIDRV_FLEXCOLOR_M16C0B16	16bpp, no cache, 16 bit bus
GUIDRV_FLEXCOLOR_M16C1B16	16bpp, cache, 16 bit bus
GUIDRV_FLEXCOLOR_M18C0B9	18bpp, no cache, 9 bit bus
GUIDRV_FLEXCOLOR_M18C1B9	18bpp, cache, 9 bit bus
GUIDRV_FLEXCOLOR_M18C0B18	18bpp, no cache, 18 bit bus
GUIDRV_FLEXCOLOR_M18C1B18	18bpp, cache, 18 bit bus
GUIDRV_FLEXCOLOR_M24C0B8	24bpp, no cache, 8 bit bus

Each controller selection supports different operation modes. The table below shows the supported modes for each controller:

Selection macro	M16C0B8	M16C1B8	M16C0B16	M16C1B16	M18C0B9	M18C1B9	M18C0B18	M18C1B18	M24C0B8
GUIDRV_FLEXCOLOR_F66702	X	X	X	X	-	-	-	-	-
GUIDRV_FLEXCOLOR_F66708	X	X	X	X	-	-	-	-	-
GUIDRV_FLEXCOLOR_F66709	X	X	X	X	-	-	-	-	X
GUIDRV_FLEXCOLOR_F66712	X	X	X	X	X	X	X	X	-
GUIDRV_FLEXCOLOR_F66714	X	X	X	X	X	X	-	-	-
GUIDRV_FLEXCOLOR_F66715	X	X	X	X	X	X	X	X	-
GUIDRV_FLEXCOLOR_F66718	X	X	X	X	X	X	-	-	-
GUIDRV_FLEXCOLOR_F66719	X	X	X	X	-	-	-	-	-
GUIDRV_FLEXCOLOR_F66720	X	X	X	X	-	-	-	-	X
GUIDRV_FLEXCOLOR_F66721	X	X	X	X	-	-	-	-	-
GUIDRV_FLEXCOLOR_F66722	X	X	-	-	-	-	-	-	-

 © 2020 SEGGER Microcontroller GmbH

Selection macro	M16C0B8	M16C1B8	M16C0B16	M16C1B16	M18C0B9	M18C1B9	M18C0B18	M18C1B18	M24C0B8
GUIDRV_FLEXCOLOR_F66723	X	X	-	-	-	-	-	-	-
GUIDRV_FLEXCOLOR_F66724	X	X	X	X	-	-	-	-	-
GUIDRV_FLEXCOLOR_F66725	X	X	-	-	-	-	-	-	-
GUIDRV_FLEXCOLOR_F66772	X	X	X	X	-	-	-	-	-

Legend

X	supported
-	not supported

34.7.4.7.1.1 Required GUI_PORT_API routines

The required GUI_PORT_API routines depend on the used interface. If a cache is used the routines for reading data are unnecessary for each interface:

8 bit interface

Element	Data type
pfWrite8_A0	void (*)(U8 Data)
pfWrite8_A1	void (*)(U8 Data)
pfWriteM8_A1	void (*)(U8 * pData, int NumItems)
pfRead8_A1	U8 (*)(void)
pfReadM8_A1	void (*)(U8 * pData, int NumItems)

16 bit interface

Element	Data type
pfWrite16_A0	void (*)(U16 Data)
pfWrite16_A1	void (*)(U16 Data)
pfWriteM16_A1	void (*)(U16 * pData, int NumItems)
pfRead16_A1	U16 (*)(void)
pfReadM16_A1	void (*)(U16 * pData, int NumItems)

18 bit interface

Element	Data type
pfWrite32_A0	void (*)(U32 Data)
pfWrite32_A1	void (*)(U32 Data)
pfWriteM32_A1	void (*)(U32 * pData, int NumItems)
pfRead32_A1	U32 (*)(void)
pfReadM32_A1	void (*)(U32 * pData, int NumItems)

9 bit interface

The following describes the behavior of the 9 bit bus variant of the driver. When working with a 9 bit interface the display controller uses the lines D17-D10 or lines D7-D0 (8 bit) for accessing the command register and D17-D9 or D8-D0 (9 bit) for passing data. This means the lines D17-D9 or D8-D0 are connected to the interface lines of the CPU.

 © 2020 SEGGER Microcontroller GmbH

The driver passes 16 bit values to the hardware routines. In dependence of the selected driver interface (TYPE_I or TYPE_II) the bits 7-0 (TYPE_I) or the bits 8-1 (TYPE_II) already contain the right values to be passed to the controller. No further shift operation is required in the hardware routines.
To be able to process pixel data as fast as possible, the driver passes two 16 bit data values per pixel (0000000R RRRRRGGG and 0000000G GGBBBBBB) to the hardware routines. Only the first 9 bits contain pixel data. So nothing need to be shifted in the hardware routines.
In case of using the 9 bit interface the driver requires 16 bit hardware routines for communicating with the controller.

Element	Data type	Description
pfWrite16_A0	void (*)(U16 Data)	Routine used to set up the index register. Dependent on used bus interface DB8-DB1 or DB7-DB0 are used.
pfWrite16_A1	void (*)(U16 Data)	Routine used to pass register parameters. Dependent on used bus interface DB8-DB1 or DB7-DB0 are used.
pfWriteM16_A1	void (*)(U16 * pData, int NumItems)	Data to be written (DB0-DB9)
pfReadM16_A1	void (*)(U16 * pData, int NumItems)	Data read (DB0-DB9)

34.7.4.7.1.2 GUIDRV_FLEXCOLOR_F66721

In addition to the hardware interface functions described above, the driver requires the following functions in case it is configured for a 66721-type controller. These controllers require reading the controller status. According to the used interface these functions are:

8 bit interface

Element	Data type
pfRead8_A0	U8 (*)(void);

16 bit interface

Element	Data type
pfRead16_A0	U16 (*)(void);

Further these controllers do not support setting the orientation by the driver using GUIDRV_FlexColor_Config(). This needs to be done in the initialization by setting the Display Configuration Register 0x20 (DPCR) accordingly.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.2 GUIDRV_FlexColor_Config()

Description

Configures orientation and offset of the SEG- and COM-lines.

Prototype

```
void GUIDRV_FlexColor_Config(GUI_DEVICE       * pDevice,
                             CONFIG_FLEXCOLOR * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the device to configure.
pConfig	Pointer to a CONFIG_FLEXCOLOR structure. See element list below.

Elements of structure CONFIG_FLEXCOLOR

Data type	Element	Description
int	FirstSEG	First segment line.
int	FirstCOM	First common line.
int	Orientation	One or more "OR"-combined values of the values to be found under *Orientation flags* on page 2638.
U16	RegEntryMode	Normally the display controller uses 3 bits of one register to define the required display orientation. Normally these are the bits ID0, ID1 and AM. To be able to control the content of the other bits the RegEntryMode element can be used. The driver combines this value with the required orientation bits during the initialization process.
int	NumDummyReads	Defines the number of reading operations which have to be done until valid data can be retrieved. Please note that only values ≠ 0 are accepted. If the controller does not need one or more dummy reads, -1 should be used here.

Permitted values for parameter Orientation	
GUI_MIRROR_X	Mirroring the X-axis
GUI_MIRROR_Y	Mirroring the Y-axis
GUI_SWAP_XY	Swapping X- and Y-axis

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.3 GUIDRV_FlexColor_SetOrientation()

Description

Sets the orientation of the screen when using `GUIDRV_FlexColor`.

Prototype

```
int GUIDRV_FlexColor_SetOrientation(int Orientation,
                                    int LayerIndex);
```

Parameters

Parameter	Description
`Orientation`	The orientation to be used.
`LayerIndex`	The index of the layer the orientation should be set for.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.4 GUIDRV_FlexColor_SetInterface66712_B9()

34.7.4.7.5 GUIDRV_FlexColor_SetInterface66715_B9()

Description

Sets the type of interface to be used.

Prototypes

```
void GUIDRV_FlexColor_SetInterface66712_B9(GUI_DEVICE * pDevice,
                                           int          Type);

void GUIDRV_FlexColor_SetInterface66715_B9(GUI_DEVICE * pDevice,
                                           int          Type);
```

Parameters

Parameter	Description
pDevice	Pointer to the device to configure.
Type	Type of the interface to be used. See possible types below.

Permitted values for parameter Type	
GUIDRV_FLEXCOLOR_IF_TYPE_I	Uses lines DB7-DB0 for register access and lines DB8-DB0 for data access. (default)
GUIDRV_FLEXCOLOR_IF_TYPE_II	Uses lines DB8 to DB1 for register access and lines DB8-DB0 for data access.

Additional information

The difference between the interfaces affects the register access to the controller. Normally there are 2 kinds of possible interfaces available when working with the 18 bit bus interface. TYPE_I uses the lines D7 to D0 for register access whereas TYPE_II uses the lines D8 to D1.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.6 GUIDRV_FlexColor_SetInterface66712_B18()

34.7.4.7.7 GUIDRV_FlexColor_SetInterface66715_B18()

Description

Sets the type of interface to be used.

Prototypes

```
void GUIDRV_FlexColor_SetInterface66712_B18(GUI_DEVICE * pDevice,
                                            int          Type);

void GUIDRV_FlexColor_SetInterface66715_B18(GUI_DEVICE * pDevice,
                                            int          Type);
```

Parameters

Parameter	Description
pDevice	Pointer to the device to configure.
Type	Type of the interface to be used. See possible types below.

Permitted values for parameter Type	
GUIDRV_FLEXCOLOR_IF_TYPE_I	Uses lines DB7-DB0 for register access and lines DB8-DB0 for data access. (default)
GUIDRV_FLEXCOLOR_IF_TYPE_II	Uses lines DB8 to DB1 for register access and lines DB8-DB0 for data access.

Additional information

The difference between the interfaces affects the register access to the controller. Normally there are 2 kinds of possible interfaces available when working with the 18 bit bus interface. TYPE_I uses the lines D7 to D0 for register access whereas TYPE_II uses the lines D8 to D1.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.8 GUIDRV_FlexColor_SetReadFunc66709_B16()

Description

Sets the function(s) to be used for reading back pixel data. To be called before GUIDRV_FlexColor_SetFunc().

Prototype

```
void GUIDRV_FlexColor_SetReadFunc66709_B16(GUI_DEVICE * pDevice,
                                           int          Func);
```

Parameters

Parameter	Description
pDevice	Pointer to the device to configure.
Func	Type of the interface to be used. See possible types below.

Permitted values for parameter Func	
GUIDRV_FLEXCOLOR_READ_FUNC_I	3 cycles and data conversion required. (default)
GUIDRV_FLEXCOLOR_READ_FUNC_II	2 cycles and no conversion required.
GUIDRV_FLEXCOLOR_READ_FUNC_III	3 cycles and data conversion required.

Additional information

The difference between the interfaces affects only reading back pixels. The right interface depends on the used controller.

GUIDRV_FLEXCOLOR_READ_FUNC_I

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	-	-	-	-	-	-	-	-	B4	B3	B2	B1	B0	-	-	-
3rd	G5	G4	G3	G2	G1	G0	-	-	R4	R3	R2	R1	R0	-	-	-

In dependence of controller settings red and blue could be swapped.

GUIDRV_FLEXCOLOR_READ_FUNC_II

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	B4	B3	B2	B1	B0	G5	G4	G3	G2	G1	G0	R4	R3	R2	R1	R0

In dependence of controller settings red and blue could be swapped.

 © 2020 SEGGER Microcontroller GmbH

GUIDRV_FLEXCOLOR_READ_FUNC_III

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	B4	B3	B2	B1	B0	-	-	-	G5	G4	G3	G2	G1	G0	-	-
3rd	R4	R3	R2	R1	R0	-	-	-	-	-	-	-	-	-	-	-

In dependence of controller settings red and blue could be swapped.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.9 GUIDRV_FlexColor_SetReadFunc66712_B9()

34.7.4.7.10 GUIDRV_FlexColor_SetReadFunc66715_B9()

Description

Sets the function(s) to be used for reading back pixel data. To be called before GUIDRV_FlexColor_SetFunc().

Prototypes

```
void GUIDRV_FlexColor_SetReadFunc66712_B9(GUI_DEVICE * pDevice,
                                          int          Func);

void GUIDRV_FlexColor_SetReadFunc66715_B9(GUI_DEVICE * pDevice,
                                          int          Func);
```

Parameters

Parameter	Description
pDevice	Pointer to the device to configure.
Type	Type of the interface to be used. See possible types below.

Permitted values for parameter Func	
GUIDRV_FLEXCOLOR_READ_FUNC_I	3 cycles and data conversion required. (default)
GUIDRV_FLEXCOLOR_READ_FUNC_II	3 cycles and data conversion required.

Additional information

The right function to be used depends on the behavior of the used controller.

GUIDRV_FLEXCOLOR_READ_FUNC_I

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	-	-	-	-	-	-	-	B5	B4	B3	B2	B1	B0	G5	G4	G3
3rd	-	-	-	-	-	-	-	G2	G1	G0	R5	R4	R3	R2	R1	R0

In dependence of controller settings red and blue could be swapped.

GUIDRV_FLEXCOLOR_READ_FUNC_II

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	B5	B4	B3	B2	B1	B0	-	-	G5	G4	G3	G2	G1	G0	-	-
3rd	R5	R4	R3	R2	R1	R0	-	-	-	-	-	-	-	-	-	-

In dependence of controller settings red and blue could be swapped.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.11 GUIDRV_FlexColor_SetReadFunc66712_B16()

34.7.4.7.12 GUIDRV_FlexColor_SetReadFunc66715_B16()

Description

Sets the function(s) to be used for reading back pixel data. To be called before GUIDRV_FlexColor_SetFunc().

Prototype

```
void GUIDRV_FlexColor_SetReadFunc66712_B16(GUI_DEVICE * pDevice,
                                           int          Func);

void GUIDRV_FlexColor_SetReadFunc66715_B16(GUI_DEVICE * pDevice,
                                           int          Func);
```

Parameters

Parameter	Description
pDevice	Pointer to the device to configure.
Type	Type of the interface to be used. See possible types below.

Permitted values for parameter Func	
GUIDRV_FLEXCOLOR_READ_FUNC_I	4 cycles and data conversion required. (default)
GUIDRV_FLEXCOLOR_READ_FUNC_II	4 cycles and data conversion required.
GUIDRV_FLEXCOLOR_READ_FUNC_III	3 cycles and data conversion required.

Additional information

The right function to be used depends on the behavior of the used controller.

GUIDRV_FLEXCOLOR_READ_FUNC_I

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	-	-	-	-	-	-	-	-	B4	B3	B2	B1	B0	-	-	-
3rd	-	-	-	-	-	-	-	-	G5	G4	G3	G2	G1	G0	-	-
4th	-	-	-	-	-	-	-	-	R4	R3	R2	R1	R0	-	-	-

In dependence of controller settings red and blue could be swapped.

GUIDRV_FLEXCOLOR_READ_FUNC_II

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	-	-	-	-	-	-	-	-	G5	G4	G3	G2	G1	G0	-	-
3rd	-	-	-	-	-	-	-	-	B4	B3	B2	B1	B0	-	-	-

 © 2020 SEGGER Microcontroller GmbH

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
4th	-	-	-	-	-	-	-	-	R4	R3	R2	R1	R0	-	-	-

In dependence of controller settings red and blue could be swapped.

GUIDRV_FLEXCOLOR_READ_FUNC_III

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	B4	B3	B2	B1	B0	-	-	-	G5	G4	G3	G2	G1	G0	-	-
3rd	R4	R3	R2	R1	R0	-	-	-	-	-	-	-	-	-	-	-

In dependence of controller settings red and blue could be swapped.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.13 GUIDRV_FlexColor_SetReadFunc66720_B16()

Description

Sets the function(s) to be used for reading back pixel data. To be called before GUIDRV_FlexColor_SetFunc().

Prototype

```
void GUIDRV_FlexColor_SetReadFunc66720_B16(GUI_DEVICE * pDevice,
                                           int          Func);
```

Parameters

Parameter	Description
pDevice	Pointer to the device to configure.
Type	Type of the interface to be used. See possible types below.

Permitted values for parameter Func	
GUIDRV_FLEXCOLOR_READ_FUNC_I	3 cycles and data conversion required. (default)
GUIDRV_FLEXCOLOR_READ_FUNC_II	2 cycles and no conversion required.

Additional information

The right function to be used depends on the behavior of the used controller. Whereas …_FUNC_I extracts the index value by assembling it from the second and third word received from the controller, …_FUNC_II uses the second word as it is. Please note that the right interface depends on the behavior of the used controller.

GUIDRV_FLEXCOLOR_READ_FUNC_I

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	-	-	-	-	-	-	-	-	B4	B3	B2	B1	B0	-	-	-
3rd	G5	G4	G3	G2	G1	G0	-	-	R4	R3	R2	R1	R0	-	-	-

In dependence of controller settings red and blue could be swapped.

GUIDRV_FLEXCOLOR_READ_FUNC_II

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	B4	B3	B2	B1	B0	G5	G4	G3	G2	G1	G0	R4	R3	R2	R1	R0

In dependence of controller settings red and blue could be swapped.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.14 GUIDRV_FlexColor_SetReadFunc66772_B8()

Description

Sets the function(s) to be used for reading back pixel data. To be called before GUIDRV_FlexColor_SetFunc().

Prototype

```
void GUIDRV_FlexColor_SetReadFunc66772_B8(GUI_DEVICE * pDevice,
                                          int          Func);
```

Parameters

Parameter	Description
pDevice	Pointer to the device to configure.
Type	Type of the interface to be used. See possible types below.

Permitted values for parameter Func	
GUIDRV_FLEXCOLOR_READ_FUNC_I	3 cycles and no conversion required. (default)
GUIDRV_FLEXCOLOR_READ_FUNC_II	3 cycles and conversion required.

Additional information

The right function to be used depends on the behavior of the used controller. Whereas …_FUNC_I extracts the index value by assembling it from the second and third word received from the controller, …_FUNC_II uses the second word as it is. Please note that the right interface depends on the behavior of the used controller.

GUIDRV_FLEXCOLOR_READ_FUNC_I

Cycle	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read							
2nd	B4	B3	B2	B1	B0	G5	G4	G3
3rd	G2	G1	G0	R4	R3	R2	R1	R0

In dependence of controller settings red and blue could be swapped.

GUIDRV_FLEXCOLOR_READ_FUNC_II

Cycle	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read							
2nd	R4	R3	R2	R1	R0	G5	G4	G3
3rd	G2	G1	G0	B4	B3	B2	B1	B0

In dependence of controller settings red and blue could be swapped.

 © 2020 SEGGER Microcontroller GmbH

34.7.4.7.15 GUIDRV_FlexColor_SetReadFunc66772_B16()

Description

Sets the function(s) to be used for reading back pixel data. To be called before GUIDRV_FlexColor_SetFunc().

Prototype

```
void GUIDRV_FlexColor_SetReadFunc66772_B16(GUI_DEVICE * pDevice,
                                           int          Func);
```

Parameters

Parameter	Description
pDevice	Pointer to the device to configure.
Type	Type of the interface to be used. See possible types below.

Permitted values for parameter Func	
GUIDRV_FLEXCOLOR_READ_FUNC_I	2 cycles and no conversion required. (default)
GUIDRV_FLEXCOLOR_READ_FUNC_II	2 cycles and conversion required.

Additional information

The right function to be used depends on the behavior of the used controller. Whereas …_FUNC_I extracts the index value by assembling it from the second and third word received from the controller, …_FUNC_II uses the second word as it is. Please note that the right interface depends on the behavior of the used controller.

GUIDRV_FLEXCOLOR_READ_FUNC_I

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	B4	B3	B2	B1	B0	G5	G4	G3	G2	G1	G0	R4	R3	R2	R1	R0

GUIDRV_FLEXCOLOR_READ_FUNC_II

Cycle	D15	D14	D13	D12	D11	D10	D9	D8	D7	D6	D5	D4	D3	D2	D1	D0
1st	Dummy read															
2nd	R4	R3	R2	R1	R0	G5	G4	G3	G2	G1	G0	B4	B3	B2	B1	B0

In dependence of controller settings red and blue can be swapped.

 © 2020 SEGGER Microcontroller GmbH

34.7.5 GUIDRV_IST3088

34.7.5.1 Supported hardware

Controllers

This driver works with the following display controllers:

- Integrated Solutions Technology IST3088, IST3257

Bits per pixel

The supported color depth is 4 bpp.

Interfaces

The driver supports the 16-bit indirect interface.

34.7.5.2 Driver selection

To use GUIDRV_IST3088 for the given display, the following command should be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_IST3088_4, GUICC_4, 0, 0);
```

34.7.5.3 Display data RAM organization



The delineation above shows the relation between the display memory and the SEG and COM lines of the LCD.

34.7.5.4 RAM requirements

This display driver can be used with and without a display data cache, containing a complete copy of the content of the display data RAM. The amount of memory (in bytes) used by the cache is:

```
LCD_XSIZE × LCD_YSIZE ÷ 2.
```

 © 2020 SEGGER Microcontroller GmbH

34.7.5.5 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_IST3088_SetBus16()	Tells the driver to use the 16 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

 © 2020 SEGGER Microcontroller GmbH

34.7.5.5.1 GUIDRV_IST3088_SetBus16()

Description

Tells the driver to use the 16 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_IST3088_SetBus16(GUI_DEVICE   * pDevice,
                             GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

34.7.5.6 Required GUI_PORT_API routines

Element	Data types
pfWrite16_A0	void (*)(U16 Data)
pfWrite16_A1	void (*)(U16 Data)
pfWriteM16_A1	void (*)(U16 * pData, int NumItems)

34.7.5.7 Special requirements

The driver needs to work in the fixed palette mode GUICC_4. The driver does not work with other palettes or fixed palette modes. You should use GUICC_4 as color conversion.

 © 2020 SEGGER Microcontroller GmbH

34.7.6 GUIDRV_Lin

This driver supports all display controllers with linear video memory accessible via direct interface. It can be used with and without a display controller. The driver does only manage the contents of the video memory. It does not send any commands to the display controller or assumes any specific registers. So it is independent of the register interface of the display controller and can be used for managing each linear mapped video memory.

34.7.6.1 Supported hardware

Controllers

The driver supports all systems with linear mapped video memory.

Bits per pixel

Supported color depths are 1, 2, 4, 8, 16, 24 and 32 bits per pixel.

Interfaces

The driver supports a full bus interface from the CPU to the video memory. The video memory needs to be accessible 8, 16 or 32 bit wise.

34.7.6.2 Color depth and display orientation

The driver consists of several files. They are named _[0]_[BPP].c. where the optional 0 stands for the desired display orientation and BPP for the color depth. The following table shows configuration macros which should be used for selecting the desired driver orientation during the initialization:

Identifier	Color depth and orientation
GUIDRV_LIN_1	1bpp, default orientation
GUIDRV_LIN_2	2bpp, default orientation
GUIDRV_LIN_4	4bpp, default orientation
GUIDRV_LIN_8	8bpp, default orientation
GUIDRV_LIN_OX_8	8bpp, X axis mirrored
GUIDRV_LIN_OXY_8	8bpp, X and Y axis mirrored
GUIDRV_LIN_16	16bpp, default orientation
GUIDRV_LIN_OX_16	16bpp, X axis mirrored
GUIDRV_LIN_OXY_16	16bpp, X and Y axis mirrored
GUIDRV_LIN_OY_16	16bpp, Y axis mirrored
GUIDRV_LIN_OS_16	16bpp, X and Y swapped
GUIDRV_LIN_OSX_16	16bpp, X axis mirrored, X and Y swapped
GUIDRV_LIN_OSY_16	16bpp, Y axis mirrored, X and Y swapped
GUIDRV_LIN_24	24bpp, default orientation
GUIDRV_LIN_OX_24	24bpp, X axis mirrored
GUIDRV_LIN_OXY_24	24bpp, X and Y axis mirrored
GUIDRV_LIN_OY_24	24bpp, Y axis mirrored
GUIDRV_LIN_OS_24	24bpp, X and Y swapped
GUIDRV_LIN_OSX_24	24bpp, X axis mirrored, X and Y swapped
GUIDRV_LIN_OSY_24	24bpp, Y axis mirrored, X and Y swapped
GUIDRV_LIN_32	32bpp, default orientation
GUIDRV_LIN_OX_32	32bpp, X axis mirrored

 © 2020 SEGGER Microcontroller GmbH

Identifier	Color depth and orientation
GUIDRV_LIN_OXY_32	32bpp, X and Y axis mirrored
GUIDRV_LIN_OY_32	32bpp, Y axis mirrored
GUIDRV_LIN_OS_32	32bpp, X and Y swapped
GUIDRV_LIN_OSX_32	32bpp, X axis mirrored, X and Y swapped
GUIDRV_LIN_OSY_32	32bpp, Y axis mirrored, X and Y swapped

The table above shows identifiers which can be used to select the driver. Each combination of orientation and color depth is possible. Please note that currently not all combinations are shipped with the driver. If the required combination is not available, please send a request to obtain the required combination.

34.7.6.3 Driver selection

To use for the given display, the following command can be used e.g.:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_LIN_OX_16, GUICC_565, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

 © 2020 SEGGER Microcontroller GmbH

34.7.6.4 Display data RAM organization



The picture above shows the relation between the display memory and the pixels of the LCD in terms of the color depth and the endian mode.

Little endian video mode

Least significant bits are used and output first. The least significant bits are for the first (left-most) pixel.

Big endian video mode

Most significant bits are used and output first. The most significant bits are for the first (left-most) pixel.

 © 2020 SEGGER Microcontroller GmbH

34.7.6.5 RAM requirements

None.

34.7.6.6 Compile-time configuration

The following table lists the macros which must be defined for hardware access:

Macro	Description
LCD_ENDIAN_BIG	Should be set to 1 for big endian mode, 0 (default) for little endian mode.

34.7.6.7 Run-time configuration

The following table lists the available run-time configuration routines:

Routine	Description
LCD_SetDevFunc()	The function sets additional and / or user defined functions of the display driver.
LCD_SetSizeEx()	Sets the physical size of the visible area of the given display/layer.
LCD_SetVRAMAddrEx()	Sets the address of the video RAM.
LCD_SetVSizeEx()	Sets the size of the virtual display area.

34.7.6.8 Commands supported by LCD_SetDevFunc()

The following table shows the supported values of the function:

Value	Description
LCD_DEVFUNC_COPYBUFFER	Can be used to set a custom defined routine for copying buffers. Makes only sense in combination with multiple buffers.
LCD_DEVFUNC_COPYRECT	Can be used to set a custom defined routine for copying rectangular areas of the display.
LCD_DEVFUNC_DRAWBMP_1BPP	Can be used to set a custom routine for drawing 1bpp bitmaps.
LCD_DEVFUNC_DRAWBMP_8BPP	Can be used to set a custom routine for drawing 8bpp bitmaps.
LCD_DEVFUNC_DRAWBMP_32BPP	Can be used to set a custom routine for drawing 32bpp bitmaps.
LCD_DEVFUNC_FILLRECT	Can be used to set a custom defined routine for filling rectangles. Makes sense if for example a BitBLT engine should be used for filling operations.

Further information about the LCD layer routines can be found under *Display driver API* on page 2780.

34.7.6.9 Configuration example

The following shows how to create a display driver device with this driver and how to configure it:

```
void LCD_X_Config(void) {
  //
  // Set display driver and color conversion
  //
  GUI_DEVICE_CreateAndLink(GUIDRV_LIN_8,    // Display driver
                           GUICC_8666,      // Color conversion
```

 © 2020 SEGGER Microcontroller GmbH

```
                            0, 0);
  //
  // Display driver configuration
  //
  LCD_SetSizeEx    (0, 320,  240);          // Physical display size in pixels
  LCD_SetVSizeEx   (0, 320,  480);          // Virtual  display size in pixels
  LCD_SetVRAMAddrEx(0, (void *)0x20000000); // Video RAM start address
}
```

34.7.6.10 Using the Lin driver in systems with cache memory

The rules to follow are quite simple:

Rule 1

All caches (if applicable, as in your case) should be fully enabled. This means I- and D-caches in systems with separate caches.

Rule 2

All code and data should be placed in cacheable areas to achieve maximum performance. If other parts of the application require some or all data to be placed in non- cacheable areas, this is not a problem but may degrade performance.

Rule 3

The cache settings for the frame buffer memory (which is really a shared memory area, accessed by both the CPU and the LCD-controller DMA) should make sure, that write operations are ’write-through’ operations. The physical memory should be always up to date, so that the DMA-access of the LCD-controller always get the current content of the frame buffer. In case of a ’write-back’ cache a write operation only changes the content of the cache, which is written to the physical memory not before the cache location is superseded. In many systems with MMU, this can be achieved by mapping the RAM twice into the virtual address space: At its normal address, the RAM is cacheable and bufferable, at the second address, it is cacheable but not bufferable. The address of the VRAM given to the driver should be the non bufferable address.

'write-through' cache not available

If the CPU does not support a ’write-through’ cache please refer to chapter *Framebuffer located in data cache area of CPU* on page 2924. It explains how multiple buffering and a cache clearance function can be used.

 © 2020 SEGGER Microcontroller GmbH

34.7.7 GUIDRV_S1D13L04

34.7.8 GUIDRV_S1D13513

> **Note**
>
> From a technical point of view both drivers are identically.
> - <DRV> = ’L04’: `GUIDRV_S1D13L04`
> - <DRV> = ’513’: `GUIDRV_S1D13513`

34.7.8.1 Supported hardware

Controllers

This driver supports the Epson S1D13<DRV> only.

Bits per pixel

The supported color depth is 24 (Main and PIP1 layer) and 32 bpp (PIP2 layer).

Interfaces

The driver supports the 16-bit indirect interface only.

34.7.8.2 Driver selection

To use `GUIDRV_S1D13`<DRV> the following command should be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_S1D13<DRV>_32, GUICC_M888, 0, 0);
```

The `Sample` folder contains a configuration sample which shows in detail how to configure the driver.

 © 2020 SEGGER Microcontroller GmbH

34.7.8.3 Display data RAM organization



Relationship between memory and the SEG and COM lines.

34.7.8.4 RAM requirements

Approximately 2 KB.

34.7.8.5 Basic function

The driver uses the indirect interface mode of the S1D13<DRV>. It uses 3 registers for accessing the controller:

- Index register, tells the controller which SFR should be accessed.
- Status register, used to get the busy status of the controller.
- Data register for writing/reading data to/from SFRs/frame buffer.

34.7.8.6 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_S1D13L04_Config() GUIDRV_S1D13513_Config()	Passes a pointer to a CONFIG_S1D13<DRV> structure to the driver.
GUIDRV_S1D13L04_SetBus16() GUIDRV_S1D13513_SetBus16()	Configures the driver to use the 16 bit indirect interface by passing a pointer to a GUI_PORT_API structure.

 © 2020 SEGGER Microcontroller GmbH

34.7.8.6.1 GUIDRV_S1D13L04_Config()

34.7.8.6.2 GUIDRV_S1D13513_Config()

Description

Configures the driver to work according to the passed CONFIG_S1D13<DRV> structure.

Prototype

```
void GUIDRV_S1D13<DRV>_Config(GUI_DEVICE        * pDevice,
                              CONFIG_S1D13<DRV> * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_S1D13<DRV> structure described below.

Elements of structure CONFIG_S1D13<DRV>

Data type	Element	Description
U32	BufferOffset	This offset added to the VideoRAM start address, results in the start address used for the selected PIP layer.
int	UseLayer	(see table below)

Permitted values for UseLayer	
GUIDRV_S1D13<DRV>_USE_PIP1	PIP1 should be used
GUIDRV_S1D13<DRV>_USE_PIP2	PIP2 should be used

 © 2020 SEGGER Microcontroller GmbH

34.7.8.6.3 GUIDRV_S1D13L04_SetBus16()

34.7.8.6.4 GUIDRV_S1D13513_SetBus16()

Description

Tells the driver to use the 16 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_S1D13513_SetBus16(GUI_DEVICE   * pDevice,
                              GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

Required GUI_PORT_API routines

Data type	Element	Description
void (*)(U16 Data)	pfWrite16_A0	Pointer to a function which writes one word to the index register.
void (*)(U16 Data)	pfWrite16_A1	Pointer to a function which writes one word to the data register.
void (*)(U16 * pData, int NumItems)	pfWriteM16_A1	Pointer to a function which writes multiple words to the data register.
U16 (*)(void)	pfRead16_A0	Pointer to a function which reads one word from the index register.
U16 (*)(void)	pfRead16_A1	Pointer to a function which reads one word from the data register.
void (*)(U16 * pData, int NumItems)	pfReadM16_A1	Pointer to a function which reads multiple words from the data register.
void (*)(void)	pfFlushBuffer	Pointer to a function which waits until the busy flag of the status register is cleared (0).

Special requirements

The driver needs to work with the fixed palette modes explained above. It further requires a function which waits until the busy flag of the status register is cleared.

 © 2020 SEGGER Microcontroller GmbH

34.7.9 GUIDRV_S1D13L02

34.7.10 GUIDRV_S1D13748

> **Note**
>
> From a technical point of view both drivers are identically.
> - <DRV> = ’L02’: `GUIDRV_S1D13L02`
> - <DRV> = ’748’: `GUIDRV_S1D13748`

34.7.10.1 Supported hardware

Controllers

This driver has been tested with the Epson S1D13<DRV>.

Bits per pixel

The supported color depth is 16 bpp.

Interfaces

The driver supports the 16-bit indirect interface.

34.7.10.2 Basic function

The driver currently supports indirect mode only. Only 2 registers, namely register 0 and 2 are used.

Hardware interface

AB[1] = GND
AB[2] = Used as Address pin
AB[3] = GND

AB[3:0]	Register
000	Index
001	Status
010	Data
011	Reserved
100	GPIO Status
101	GPIO Config
110	GPIO Input Enable
111	GPIO Pull-down Control

Reset

The RESET pin should be connected to the system reset. The RESET pin of the Microcontroller / CPU is usually called NRESET.

34.7.10.3 Driver selection

To use `GUIDRV_S1D13<DRV>` for the given display, the following command should be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_S1D13<DRV>, GUICC_M565, 0, 0);
```

 © 2020 SEGGER Microcontroller GmbH

34.7.10.4 Display data RAM organization



Relationship between memory and the SEG and COM lines.

34.7.10.5 RAM requirements

Approximately 500 bytes.

34.7.10.6 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_S1D13L02_Config() GUIDRV_S1D13748_Config()	Passes a pointer to a CONFIG_S1D13<DRV> structure to the driver.
GUIDRV_S1D13L02_SetBus16() GUIDRV_S1D13748_SetBus16()	Configures the driver to use the 16 bit indirect interface by passing a pointer to a GUI_PORT_API structure.

 © 2020 SEGGER Microcontroller GmbH

34.7.10.6.1 GUIDRV_S1D13L02_Config()

34.7.10.6.2 GUIDRV_S1D13748_Config()

Description

Configures the driver to work according to the passed CONFIG_S1D13<DRV> structure.

Prototype

```
void GUIDRV_S1D13<DRV>_Config(GUI_DEVICE        * pDevice,
                              CONFIG_S1D13<DRV> * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_S1D13<DRV> structure described below.

Elements of structure CONFIG_S1D13<DRV>

Data type	Element	Description
U32	BufferOffset	This offset added to the VideoRAM start address, results in the start address used for the selected PIP layer.
int	UseLayer	PIP layer to be used.

 © 2020 SEGGER Microcontroller GmbH

34.7.10.6.3 GUIDRV_S1D13L02_SetBus16()

34.7.10.6.4 GUIDRV_S1D13748_SetBus16()

Description

Tells the driver to use the 16 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_S1D13748_SetBus16(GUI_DEVICE   * pDevice,
                              GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

34.7.10.7 Required GUI_PORT_API routines

Data type	Element	Description
void (*)(U16 Data)	pfWrite16_A0	Pointer to a function which writes one word to the controller with C/D line low.
void (*)(U16 Data)	pfWrite16_A1	Pointer to a function which writes one word to the controller with C/D line high.
void (*)(U16 * pData, int NumItems)	pfWriteM16_A1	Pointer to a function which writes multiple words to the controller with C/D line high.
U16 (*)(void)	pfRead16_A1	Pointer to a function which reads one word from the controller with C/D line high.
void (*)(U16 * pData, int NumItems)	pfReadM16_A1	Pointer to a function which reads multiple words from the controller with C/D line high.

34.7.10.8 Special requirements

The driver needs to work with the fixed palette mode GUICC_M565. The driver does not work with other palettes or fixed palette modes.

 © 2020 SEGGER Microcontroller GmbH

34.7.11 GUIDRV_S1D13L01

34.7.12 GUIDRV_S1D13781

> **Note**
>
> From a technical point of view both drivers are identically.
> - <DRV> = ’L01’: GUIDRV_S1D13L01
> - <DRV> = ’781’: GUIDRV_S1D13781

34.7.12.1 Supported hardware

Controllers

This driver has been tested with the Epson S1D13<DRV>.

Bits per pixel

Currently the supported color depth is 8 and 16 bpp. This can be enhanced on demand.

Interfaces

Currently the driver supports only the 8-bit indirect serial host interface. Can be enhanced on demand.

34.7.12.2 Display orientation

The driver can be used with different orientations. The following table shows the configuration macros which can be used to create and link the driver during the initialization:

Identifier	Color depth and orientation
GUIDRV_S1D13<DRV>_8C0	8bpp, default orientation
GUIDRV_S1D13<DRV>_OXY_8C0	8bpp, X and Y axis mirrored
GUIDRV_S1D13<DRV>_OSY_8C0	8bpp, X axis mirrored, X and Y swapped
GUIDRV_S1D13<DRV>_OSX_8C0	8bpp, Y axis mirrored, X and Y swapped
GUIDRV_S1D13<DRV>_16C0	16bpp, default orientation
GUIDRV_S1D13<DRV>_OXY_16C0	16bpp, X and Y axis mirrored
GUIDRV_S1D13<DRV>_OSY_16C0	16bpp, X axis mirrored, X and Y swapped
GUIDRV_S1D13<DRV>_OSX_16C0	16bpp, Y axis mirrored, X and Y swapped

The table above shows identifiers which can be used to select the driver.

34.7.12.3 Driver selection

To use GUIDRV_S1D13<DRV> for the given display, the following command should be used for the 8bpp version:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_S1D13<DRV>_8C0, GUICC_8666, 0, 0);
```

To use the 16bpp version use the following command:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_S1D13<DRV>_16C0, GUICC_M565, 0, 0);
```

 © 2020 SEGGER Microcontroller GmbH

34.7.12.4 Display data RAM organization



Relationship between memory and the SEG and COM lines for 8bpp mode.



Relationship between memory and the SEG and COM lines for 16bpp mode.

34.7.12.5 RAM requirements

Approximately 1 KB.

34.7.12.6 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_S1D13L01_Config() GUIDRV_S1D13781_Config()	Passes a pointer to a CONFIG_S1D13<DRV> structure to the driver.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUIDRV_S1D13L01_SetBusSPI() GUIDRV_S1D13781_SetBusSPI()	Configures the driver to use the 8 bit indirect serial host interface by passing a pointer to a GUI_PORT_API structure.
GUIDRV_S1D13L01_SetOrientation() GUIDRV_S1D13781_SetOrientation()	Sets a new orientation for the given layer.

 © 2020 SEGGER Microcontroller GmbH

34.7.12.6.1 GUIDRV_S1D13L01_Config()

34.7.12.6.2 GUIDRV_S1D13781_Config()

Description

Configures the driver to work according to the passed CONFIG_S1D13<DRV> structure.

Prototype

```
void GUIDRV_S1D13<DRV>_Config(GUI_DEVICE        * pDevice,
                              CONFIG_S1D13<DRV> * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_S1D13<DRV> structure described below.

Elements of structure CONFIG_S1D13<DRV>

Data type	Element	Description
U32	BufferOffset	This offset added to the VideoRAM start address, results in the start address used for the selected PIP layer.
int	WriteBufferSize	Number of bytes used for the write buffer. The buffer should be large enough to be able to store at least one line of data + 5 bytes. Because the layer size can be changed dynamically, it is required to set up the buffer size during the configuration. The default value of the buffer size is 500 bytes.
int	UseLayer	Should be 1 if PIP layer should be used.
int	WaitUntilVNDP	Used for Multiple Buffering configurations only. If set to 1 the driver waits until the next vertical non display period has been reached. This can be used to reduce flickering effects with fast animations.

 © 2020 SEGGER Microcontroller GmbH

34.7.12.6.3 GUIDRV_S1D13L01_SetBusSPI()

34.7.12.6.4 GUIDRV_S1D13781_SetBusSPI()

Description

Tells the driver to use the 8 bit indirect serial host interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_S1D13781_SetBusSPI(GUI_DEVICE   * pDevice,
                               GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

 © 2020 SEGGER Microcontroller GmbH

34.7.12.6.5 GUIDRV_S1D13L01_SetOrientation()

34.7.12.6.6 GUIDRV_S1D13781_SetOrientation()

Description

This function set the given orientation for the given layer.

Prototype

```
int GUIDRV_S1D13781_SetOrientation(int Orientation,
                                   int LayerIndex);
```

Parameters

Parameter	Description
Orientation	The orientation to be used.
LayerIndex	Index of the layer the orientation should be set for.

Return value

0 on success
1 on error.

34.7.12.7 Required GUI_PORT_API routines

Data type	Element	Description
void (*)(U8 Data)	pfWrite8_A0	Pointer to a function which writes one byte to the controller with C/D line low.
void (*)(U8 Data)	pfWrite8_A1	Pointer to a function which writes one byte to the controller with C/D line high.
void (*)(U8 * pData, int NumItems)	pfWriteM8_A1	Pointer to a function which writes multiple bytes to the controller with C/D line high.
U8 (*)(void)	pfRead8_A1	Pointer to a function which reads one byte from the controller with C/D line high.
void (*)(U8 * pData, int NumItems)	pfReadM8_A1	Pointer to a function which reads multiple bytes from the controller with C/D line high.
void (*)(U8 NotActive)	pfSetCS	Routine which is able to toggle the CS signal of the controller: NotActive = 1 means CS = high NotActive = 0 means CS = low

34.7.12.8 Optional functions

The following table shows the optional LCD-functions which are available with this driver:

Routine	Description
GUI_GetLayerPosEx()	Returns the X- and Y-position of the given layer.
GUI_SetLayerPosEx()	Sets the X- and Y-position of the given layer.
GUI_SetLayerSizeEx()	Sets the X- and Y-size of the given layer.
GUI_SetLayerVisEx()	Sets the visibility of the given layer.
LCD_SetAlphaEx()	Sets the layer alpha value of the given layer.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
LCD_SetChromaEx()	Sets the colors to be used for the chroma mode.
LCD_SetChromaModeEx()	Enables the chroma mode of the given layer.

More details about the optional functions can be found in *MultiLayer API* on page 2417.

34.7.12.9 Additional information

The display driver automatically initializes the following registers:

Register	Description
0x60824	X-size of main layer.
0x60828	Y-size of main layer.
0x60840	Main layer settings.

This means the above registers do not need to be initialized by the applications initialization code for the display controller.

 © 2020 SEGGER Microcontroller GmbH

34.7.13 GUIDRV_S1D15G00

34.7.13.1 Supported hardware

Controllers

The driver supports the Epson S1D15G00 controller.

Bits per pixel

Supported color depth is 12bpp.

Interfaces

The driver supports the 8 bit indirect interface.

34.7.13.2 Driver selection

To use `GUIDRV_S1D15G00` for the given display, the following command should be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_S1D15G00, GUICC_M444_12, 0, 0);
```

34.7.13.3 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the LCD.

34.7.13.4 RAM requirements

This display driver can be used with and without a display data cache, containing a complete copy of the contents of the LCD data RAM. The amount of memory used by the cache is:

```
LCD_XSIZE × LCD_YSIZE × 2 bytes
```

Using a cache is recommended only if a lot of drawing operations uses the XOR drawing mode. A cache would avoid reading the display data in this case. Normally the use of a cache is not recommended.

 © 2020 SEGGER Microcontroller GmbH

34.7.13.5 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_S1D15G00_Config()	Passes a pointer to a CONFIG_S1D15G00 structure to the driver.
GUIDRV_S1D15G00_SetBus8()	Tells the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

 © 2020 SEGGER Microcontroller GmbH

34.7.13.5.1 GUIDRV_S1D15G00_Config()

Description

Passes a pointer to a CONFIG_S1D15G00 structure to the driver.

Prototype

```
void GUIDRV_S1D15G00_Config(GUI_DEVICE      * pDevice,
                            CONFIG_S1D15G00 * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_S1D15G00 structure described below.

Elements of structure CONFIG_S1D15G00

Data type	Element	Description
int	FirstSEG	First segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	FirstCOM	First common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	UseCache	Enables or disables use of a data cache. Should be set to 1 for enabling and to 0 for disabling.

 © 2020 SEGGER Microcontroller GmbH

34.7.13.5.2 GUIDRV_S1D15G00_SetBus8()

Description

Tells the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_S1D15G00_SetBus8(GUI_DEVICE   * pDevice,
                             GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

34.7.13.6 Required GUI_PORT_API routines

Data type	Element	Description
void (*)(U8 Data)	pfWrite8_A0	Pointer to a function which writes one byte to the controller with C/D line low.
void (*)(U8 Data)	pfWrite8_A1	Pointer to a function which writes one byte to the controller with C/D line high.
void (*)(U8 * pData, int NumItems)	pfWriteM8_A1	Pointer to a function which writes multiple bytes to the controller with C/D line high.
U8 (*)(void)	pfRead8_A1	Pointer to a function which reads one byte from the controller with C/D line high.

34.7.13.7 Configuration example

```
#define XSIZE 130
#define YSIZE 130
GUI_PORT_API _PortAPI;
void LCD_X_Config(void) {
  GUI_DEVICE * pDevice;
  CONFIG_S1D15G00 Config = {0};
  //
  // Set display driver and color conversion for 1st layer
  //
  pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_S1D15G00, GUICC_M444_12, 0, 0);
  //
  // Display driver configuration
  //
  LCD_SetSizeEx (0, XSIZE,  YSIZE);
  LCD_SetVSizeEx(0, XSIZE,  YSIZE);
  //
  // Driver specific configuration
  //
  Config.FirstCOM  = 2;
  GUIDRV_S1D15G00_Config(pDevice, &Config);
  //
  // Setup hardware access routines
  //
  _PortAPI.pfWrite8_A0  = _Write_A0;
  _PortAPI.pfWrite8_A1  = _Write_A1;
  _PortAPI.pfWriteM8_A1 = _WriteM_A1;
  GUIDRV_S1D15G00_SetBus8(pDevice, &_PortAPI);
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.14 GUIDRV_SH_MEM

The driver supports Sharp Memory LCDs. Those kind of displays do not support reading back the display content. Further this LCDs do not support writing single pixels. The smallest unit for a writing operation is one complete line of pixels. Because of that a cache is required in the driver. To achieve the best possible performance it is recommended to lock and unlock the cache before/after large drawing operations.

VCOM signal

Sharp Memory LCDs require a VCOM signal which should be toggled with a frequency of approx. 500-1000ms. That could be achieved per hardware (EXTMODE=H) or per software (EXTMODE=L). EXTMODE is the configuration pin of the LCD.

EXTMODE = H

There are 2 possible ways to achieve toggling the EXTCOMIN signal. One solution is toggling the signal by a timer interrupt or a similar routine which is called with the required frequency. The second solution is using the function `GUIDRV_SH_MEM_Config()` explained later and uses a custom function called periodically by the driver.

EXTMODE = L

In that case the driver uses the software interface of the Sharp Memory LCD to toggle the V-bit. The function `GUIDRV_SH_MEM_Config()` should be used to set the desired period.

34.7.14.1 Supported hardware

Displays

Sharp Memory LCDs (b/w and 3bpp) with 8- or 10 bit address interface and compatible displays.

Bits per pixel

Supported color depth is 1 and 3bpp.

Interfaces

The driver supports the indirect serial interface required for using that kind of LCDs.

34.7.14.2 Display orientation

The driver consists of several files. They are named `_[0].c` where the optional `0` stands for the desired display orientation. The following table shows the configuration macros which should be used to select the desired display orientation during the initialization:

Identifier	Color depth and orientation
`GUIDRV_SH_MEM`	1bpp, default orientation
`GUIDRV_SH_MEM_0SX`	1bpp, X and Y axis swapped, X mirrored (rotated CCW 90 degrees)
`GUIDRV_SH_MEM_0SY`	1bpp, X and Y axis swapped, Y mirrored (rotated CW 90 degrees)
`GUIDRV_SH_MEM_0XY`	1bpp, X and Y axis mirrored (turned by 180 degrees)
`GUIDRV_SH_MEM_3`	3bpp, default orientation
`GUIDRV_SH_MEM_0SX_3`	3bpp, X and Y axis swapped, X mirrored (rotated CCW 90 degrees)
`GUIDRV_SH_MEM_0SY_3`	3bpp, X and Y axis swapped, Y mirrored (rotated CW 90 degrees)
`GUIDRV_SH_MEM_0XY_3`	3bpp, X and Y axis mirrored (turned by 180 degrees)

 © 2020 SEGGER Microcontroller GmbH

34.7.14.3 Driver selection

The following command could be used in LCD_X_Config():

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SH_MEM, GUICC_1, 0, 0);
```

34.7.14.4 Display data RAM organization 1bpp



The picture above shows the relation between the display memory and the SEG and COM lines of the LCD.

34.7.14.5 Display data RAM organization 3bpp



The picture above shows the relation between the display memory and the SEG and COM lines of the LCD.

34.7.14.6 RAM requirements

This display driver requires a display data cache containing a complete copy of the content of the LCD data RAM. The amount of memory used by the cache in bytes is:

```
LCD_YSIZE × (LCD_XSIZE × BitsPerPixel + 7) ÷ 8 + (LCD_YSIZE + 7) ÷ 8
```

34.7.14.7 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUIDRV_SH_MEM_Config()	Passes a pointer to a CONFIG_SH_MEM structure to the driver.
GUIDRV_SH_MEM_SetBus8()	Tells the driver to use the 8 bit indirect interface and passes pointer to a GUI_PORT_API structure to the driver.
GUIDRV_SH_MEM_3_Config()	Passes a pointer to a CONFIG_SH_MEM structure to the driver.
GUIDRV_SH_MEM_3_SetBus8()	Tells the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

 © 2020 SEGGER Microcontroller GmbH

34.7.14.7.1 GUIDRV_SH_MEM_Config()

34.7.14.7.2 GUIDRV_SH_MEM_3_Config()

Description

Passes a pointer to a CONFIG_SH_MEM structure to the driver.

Prototype

```
void GUIDRV_SH_MEM_3_Config(GUI_DEVICE    * pDevice,
                            CONFIG_SH_MEM * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_SH_MEM structure described below.

Elements of structure CONFIG_SH_MEM

Data type	Element	Description
unsigned	Period	Period for toggling VCOM. In case of 'ExtMode' is set to 1 the driver calls pfToggleVCOM with the given frequency. In case of 'ExtMode' is 0 it toggles the V-bit of the software interface.
unsigned	ExtMode	Should be set to the same value as the EXTMODE pin of the LCD. If set to 1 the function pointed by pfToggleVCOM is called periodically for toggling the VCOM pin by a custom function.
unsigned	ExtMode	(see table below)
void (*)(void)	pfToggleVCOM	Function for toggling the EXTCOMIN line of the display.
unsigned	AddressBitOrder	Inverts the bit order of the address.

Permitted values for BitMode	
GUIDRV_SH_MEM_8BITMODE	Default setting right for the most Memory LCDs.
GUIDRV_SH_MEM_10BITMODE	Must be used to support memory LCDs with 10 bit address interface like LS032B7DD02.

 © 2020 SEGGER Microcontroller GmbH

34.7.14.7.3 GUIDRV_SH_MEM_SetBus8()

34.7.14.7.4 GUIDRV_SH_MEM_3_SetBus8()

Description

Tells the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_SH_MEM_3_SetBus8(GUI_DEVICE   * pDevice,
                             GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

 © 2020 SEGGER Microcontroller GmbH

34.7.14.8 Required GUI_PORT_API routines

Data type	Element	Description
`void (*)(U8 NotActive)`	pfSetCS	Pointer to a function which is able to toggle the CS signal of the controller.
`void (*)(U8 * pData, int NumItems)`	pfWriteM8_A1	Pointer to a function which writes multiple bytes to the controller.

34.7.14.9 Configuration Example

```
#define XSIZE 128
#define YSIZE 128
GUI_PORT_API _PortAPI;
void LCD_X_Config(void) {
  GUI_DEVICE * pDevice;
  GUI_PORT_API PortAPI = {0};
  CONFIG_SH_MEM Config = {0};
  //
  // Set display driver and color conversion
  //
  pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SH_MEM, GUICC_1, 0, 0);
  //
  // Common display driver configuration
  //
  if (LCD_GetSwapXY()) {
    LCD_SetSizeEx (0, YSIZE_PHYS, XSIZE_PHYS);
  } else {
    LCD_SetSizeEx (0, XSIZE_PHYS, YSIZE_PHYS);
  }
  //
  // Setup hardware access routines
  //
  PortAPI.pfWriteM8_A1 = _WriteM1;
  PortAPI.pfSetCS      = _SetCS;
  GUIDRV_SH_MEM_SetBus8(pDevice, &PortAPI);
  //
  // VCom management
  //
  Config.Period = 500;
  GUIDRV_SH_MEM_Config(pDevice, &Config);
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.15 GUIDRV_SLin

34.7.15.1 Supported hardware

Controllers

The driver works with the following display controllers:

- Epson S1D13700, S1D13305 (indirect interface only!)
- RAIO 8835
- Solomon SSD1325, SSD1848
- Ultrachip UC1617
- Toshiba T6963

Bits per pixel

Supported color depth is 1, 2 and 4 bits per pixel. Please consider that the supported controllers normally do not support all possible color depths to be used with the driver.

Interfaces

The driver supports the 8 bit indirect interface.

34.7.15.2 Color depth and display orientation

The driver can be used with different orientations and color depths. The following table shows the configuration macros which can be used to create and link the driver during the initialization:

Identifier	Color depth and orientation
GUIDRV_SLIN_1	1bpp, default orientation
GUIDRV_SLIN_0Y_1	1bpp, Y axis mirrored
GUIDRV_SLIN_0X_1	1bpp, X axis mirrored
GUIDRV_SLIN_0XY_1	1bpp, X and Y axis mirrored
GUIDRV_SLIN_0S_1	1bpp, X and Y swapped
GUIDRV_SLIN_0SY_1	1bpp, X and Y swapped, Y axis mirrored
GUIDRV_SLIN_0SX_1	1bpp, X and Y swapped, X axis mirrored
GUIDRV_SLIN_0SXY_1	1bpp, X and Y swapped, X and Y axis mirrored
GUIDRV_SLIN_2	2bpp, default orientation
GUIDRV_SLIN_0Y_2	2bpp, Y axis mirrored
GUIDRV_SLIN_0X_2	2bpp, X axis mirrored
GUIDRV_SLIN_0XY_2	2bpp, X axis mirrored, Y axis mirrored
GUIDRV_SLIN_0S_2	2bpp, X and Y swapped
GUIDRV_SLIN_0SY_2	2bpp, X and Y swapped, Y axis mirrored
GUIDRV_SLIN_0SX_2	2bpp, X and Y swapped, X axis mirrored
GUIDRV_SLIN_0SXY_2	2bpp, X and Y swapped, Y and X axis mirrored
GUIDRV_SLIN_4	4bpp, default orientation
GUIDRV_SLIN_0Y_4	4bpp, Y axis mirrored
GUIDRV_SLIN_0X_4	4bpp, X axis mirrored
GUIDRV_SLIN_0XY_4	4bpp, X axis mirrored, Y axis mirrored
GUIDRV_SLIN_0S_4	4bpp, X and Y swapped
GUIDRV_SLIN_0SY_4	4bpp, X and Y swapped, Y axis mirrored
GUIDRV_SLIN_0SX_4	4bpp, X and Y swapped, X axis mirrored

 © 2020 SEGGER Microcontroller GmbH

Identifier	Color depth and orientation
GUIDRV_SLIN_OSXY_4	4bpp, X and Y swapped, Y and X axis mirrored

34.7.15.3 Driver selection

To use GUIDRV_SLin for the given display, the following command can be used e.g.:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SLIN_OX_1, GUICC_1, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

34.7.15.4 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the display.

34.7.15.5 RAM requirements

This display driver may be used with or without a display data cache, containing a complete copy of the frame buffer. If no cache is used, the driver only requires approx. 256 bytes of RAM.
It is recommended to use this driver with a data cache for faster LCD-access. The additional amount of memory used by the cache may be calculated as follows:

```
Size of RAM (in bytes) = BitsPerPixel × (LCD_XSIZE + 7) ÷ 8 × LCD_YSIZE
```

34.7.15.6 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_SLin_Config()	Passes a pointer to a CONFIG_SLIN structure to the driver.
GUIDRV_SLin_SetBus8()	Tells the driver to use the 8 bit indirect interface and passes pointer to a GUI_PORT_API structure to the driver.
GUIDRV_SLin_SetS1D13700()	Set up the driver to use one of the following controllers: • Epson S1D13700, S1D13305

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
	• RAIO 8835
GUIDRV_SLin_SetSSD1325()	Set up the driver to use one of the following controllers: • Solomon SSD1325
GUIDRV_SLin_SetSSD1848()	Set up the driver to use one of the following controllers: • Solomon SSD1848
GUIDRV_SLin_SetT6963()	Set up the driver to use one of the following controllers: • Toshiba T6963
GUIDRV_SLin_SetUC1617()	Set up the driver to use one of the following controllers: • Ultrachip UC1617

 © 2020 SEGGER Microcontroller GmbH

34.7.15.6.1 GUIDRV_SLin_Config()

Description

Passes a pointer to a CONFIG_SLIN structure to the driver.

Prototype

```
void GUIDRV_SLin_Config(GUI_DEVICE  * pDevice,
                        CONFIG_SLIN * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_SLIN structure described below.

Elements of structure CONFIG_SLIN

Data type	Element	Description
int	FirstSEG	First segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	FirstCOM	First common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	UseCache	Enables or disables use of a data cache. Should be set to 1 for enabling and to 0 for disabling.
int	UseDualScan	Used only for the T6963. This element should be set to 1 in case a dual screen LCD is used.
int	UseMirror	Used only for the SSD1848. Should be normally 1.

 © 2020 SEGGER Microcontroller GmbH

34.7.15.6.2 GUIDRV_SLin_SetBus8()

Description

Tells the driver to use the 16 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_Slin_SetBus8(GUI_DEVICE   * pDevice,
                         GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

Required GUI_PORT_API routines

Element	Data type
pfWrite8_A0	void (*)(U8 Data)
pfWrite8_A1	void (*)(U8 Data)
pfWriteM8_A0	void (*)(U8 * pData, int NumItems)
pfWriteM8_A1	void (*)(U8 * pData, int NumItems)
pfRead8_A1	U8 (*)(void)

 © 2020 SEGGER Microcontroller GmbH

34.7.15.6.3 GUIDRV_SLin_SetS1D13700()

Description

Tells the driver that an Epson S1D13700 or S1D13305 controller should be used. Works also for RAIO 8835.

Prototype

```
void GUIDRV_SLin_SetS1D13700(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device

 © 2020 SEGGER Microcontroller GmbH

34.7.15.6.4 GUIDRV_SLin_SetSSD1325()

Description

Tells the driver that a Solomon SSD1325 controller should be used.

Prototype

```
void GUIDRV_SLin_SetSSD1325(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device

 © 2020 SEGGER Microcontroller GmbH

34.7.15.6.5 GUIDRV_SLin_SetSSD1848()

Description

Tells the driver that a Solomon SSD1848 controller should be used.

Prototype

```
void GUIDRV_SLin_SetSSD1848(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device

 © 2020 SEGGER Microcontroller GmbH

34.7.15.6.6 GUIDRV_SLin_SetT6963()

Description

Tells the driver that a Toshiba T6963 controller should be used.

Prototype

```
void GUIDRV_SLin_SetT6963(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device

 © 2020 SEGGER Microcontroller GmbH

34.7.15.6.7 GUIDRV_SLin_SetUC1617()

Description

Tells the driver that an Ultrachip UC1617 controller should be used.

Prototype

```
void GUIDRV_SLin_SetUC1617(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device

 © 2020 SEGGER Microcontroller GmbH

34.7.15.7 Configuration example

```
#define YSIZE 240
void LCD_X_Config(void) {
  GUI_DEVICE * pDevice;
  CONFIG_SLIN  Config  = {0};
  GUI_PORT_API PortAPI = {0};
  //
  // Set display driver and color conversion
  //
  pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SLIN_2, GUICC_2, 0, 0);
  //
  // Common display driver configuration
  //
  LCD_SetSizeEx (0, XSIZE, YSIZE);
  LCD_SetVSizeEx(0, XSIZE, YSIZE);
  //
  // Driver specific configuration
  //
  Config.UseCache  = 1;
  GUIDRV_SLin_Config(pDevice, &Config);
  //
  // Select display controller
  //
  GUIDRV_SLin_SetS1D13700(pDevice);
  //
  // Setup hardware access routines
  //
  PortAPI.pfWrite16_A0  = _Write0;
  PortAPI.pfWrite16_A1  = _Write1;
  PortAPI.pfWriteM16_A0 = _WriteM0;
  PortAPI.pfRead16_A1   = _Read1;
  GUIDRV_SLin_SetBus8(pDevice, &PortAPI);
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.16 GUIDRV_SLinEPD

34.7.16.1 Description

This driver is written to drive an electronic paper display (EPD) controller. Since EPD controller do not behave like typical LCD controllers it requires some special treatment.

Updating the display

Since most devices using an EPD are designed to have a low power consumption emWin puts the EPD controller into a deep sleep mode after performing a screen update. When writing to the display emWin sends a `LCD_X_INITCONTROLLER` command to the driver callback `LCD_X_DisplayDriver()` to wake up the controller. Therefore `LCD_X_DisplayDriver()` gets called multiple times with `LCD_X_INITICONTROLLER` command.

The user has two options to update the screen after performing drawing operations with emWin.

- Call `LCD_Refresh()`
- Configure the driver for auto update mode

Per default the driver does not update the screen automatically and the user has to call `LCD_Refresh()` manually after performing the last drawing operation.

The `GUIDRV_SLinEPD` driver offers an auto update mode. When using this mode the driver checks periodically for changes in the driver cache and updates the screen automatically if changes are detected. This mode can be enabled by setting an auto update period with the function `GUIDRV_SLinEPD_Config()`.

Partial update

Per default the driver refreshes the entire display if `LCD_Refresh()` gets called or the a change is detected in auto update mode.
With the function `GUIDRV_SLinEPD_EnablePartialMode()` it is possible to update only changed areas of the screen to reduce BUS traffic.
Due to the nature of EPDs this mode might cause artifacts on the screen showing the previous content. This is caused by non initialized pixels on the EPD.

34.7.16.2 Supported hardware

Controllers

The driver works with the following display controllers:

- Solomon SSD1673

Bits per pixel

The driver currently supports 1 bpp color depth.

Interfaces

The driver supports the indirect interface (8 bit) of the display controller. Parallel, 4-pin SPI or I2C bus can be used.

34.7.16.3 Color depth and display orientation

The driver can be used with different orientations and 1bpp color depth. Each configuration requires a display driver cache. The following table shows the configuration macros which can be used to create and link the driver during the initialization:

Identifier	Color depth	Cache	Orientation
`GUIDRV_SLINEPD_1`	1bpp	Yes	default
`GUIDRV_SLINEPD_OY_1`	1bpp	Yes	Y axis mirrored

 © 2020 SEGGER Microcontroller GmbH

Identifier	Color depth	Cache	Orientation
GUIDRV_SLINEPD_0X_1	1bpp	Yes	X axis mirrored
GUIDRV_SLINEPD_0XY_1	1bpp	Yes	X and Y axis mirrored
GUIDRV_SLINEPD_0S_1	1bpp	Yes	X and Y swapped
GUIDRV_SLINEPD_0SY_1	1bpp	Yes	X and Y swapped, Y axis mirrored
GUIDRV_SLINEPD_0SX_1	1bpp	Yes	X and Y swapped, X axis mirrored
GUIDRV_SLINEPD_0SXY_1	1bpp	Yes	X and Y swapped, X and Y axis mirrored

34.7.16.4 Driver selection

To use GUIDRV_SLinEPD for the given display, the following call may be used in the function LCD_X_Config:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SLINEPD_1, GUICC_1, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

34.7.16.5 Display data RAM organization



34.7.16.6 RAM requirements

This display driver requires a display data cache. The data cache contains a complete copy of the LCD data RAM. The amount of memory used by the cache may be calculated as follows:

```
LCD_PIXELPERBYTE == 8
Size of RAM (in bytes) = ((LCD_XSIZE + (LCD_PIXELPERBYTE - 1))
 \divide LCD_PIXELPERBYTE) \times LCD_YSIZE
```

34.7.16.7 Run-time configuration

The table below shows the available run-time configuration routines for this driver:

Routine	Description
GUIDRV_SLinEPD_Config()	Passes a CONFIG_SLINEPD structure to the driver.
GUIDRV_SLinEPD_EnablePartialMode()	This function enables the partial update mode.
GUIDRV_SLinEPD_SetBus8()	Sets the interface for the driver.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUIDRV_SLinEPD_SetSSD1673()	Selects SSD1673 to be driven by the driver.

 © 2020 SEGGER Microcontroller GmbH

34.7.16.7.1 GUIDRV_SLinEPD_Config()

Description

Passes a CONFIG_SLINEPD structure to the driver.

Prototype

```
void GUIDRV_SLinEPD_Config(GUI_DEVICE     * pDevice,
                           CONFIG_SLINEPD * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_SLINEPD structure described below.

Additional information

This driver has an auto update mode. This mode uses a timer which checks periodically if the data in the cache have changed. If this is the reason the timer causes the driver to perform an update of the LCD.
If this function is not called the driver does not use the auto update mode.

 © 2020 SEGGER Microcontroller GmbH

34.7.16.7.2 GUIDRV_SLinEPD_EnablePartialMode()

Description

This function enables the partial update mode.

Prototype

```
void GUIDRV_SLinEPD_EnablePartialMode(int OnOff);
```

Parameters

Parameter	Description
OnOff	Enables (1) or disables (0) the partial update mode.

 © 2020 SEGGER Microcontroller GmbH

34.7.16.7.3 GUIDRV_SLinEPD_SetBus8()

Description

Tells the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_SLinEPD_SetBus8(GUI_DEVICE   * pDevice,
                            GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

 © 2020 SEGGER Microcontroller GmbH

34.7.16.7.4 GUIDRV_SLinEPD_SetSSD1673()

Description

Configures the driver to use one of the following controllers:

- Solomon SSD1673

Prototype

```
void GUIDRV_SLinEPD_SetSSD1673(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.16.8 Configuration example

```
void LCD_X_Config(void) {
  GUI_DEVICE     * pDevice;
  GUI_PORT_API     PortAPI = {0};
  CONFIG_SLINEPD   Config = {0};
  //
  // Set display driver and color conversion for 1st layer
  //
  pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SLINEPD_1, GUICC_1, 0, 0);
  //
  // Display driver configuration
  //
  if (LCD_GetSwapXY()) {
    LCD_SetSizeEx (0, YSIZE_PHYS, XSIZE_PHYS);
    LCD_SetVSizeEx(0, YSIZE_PHYS, XSIZE_PHYS);
  } else {
    LCD_SetSizeEx (0, XSIZE_PHYS, YSIZE_PHYS);
    LCD_SetVSizeEx(0, XSIZE_PHYS, YSIZE_PHYS);
  }
  //
  // Choose controller
  //
  GUIDRV_SLinEPD_SetSSD1673(pDevice);
  //
  // Set up port API
  //
  PortAPI.pfWrite8_A0  = _Write8_A0;
  PortAPI.pfWrite8_A1  = _Write8_A1;
  PortAPI.pfWriteM8_A1 = _WriteM8_A1;
  PortAPI.pfRead8_A0   = _Read8_A0;
  GUIDRV_SLinEPD_SetBus8(pDevice, &PortAPI);
  //
  // Auto-Update
  //
  Config.AutoUpdatePeriod = 1000;
  GUIDRV_SLinEPD_Config(pDevice, &Config);
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.17 GUIDRV_SPage

34.7.17.1 Supported hardware

Controllers

The driver works with the following display controllers:

- Avant Electronics SBN0064G
- Epson S1D15E05, S1D15E06, S1D15605, S1D15606, S1D15607, S1D15608, S1D15705, S1D15710, S1D15714, S1D15719, S1D15721
- Integrated Solutions Technology IST3020, IST3501
- New Japan Radio Company NJU6676
- Novatek NT7502, NT7534, NT7538, NT75451
- Samsung S6B0713, S6B0719, S6B0724, S6B1713
- Sino Wealth SH1101A
- Sitronix ST7522, ST75256, ST75320, ST7565, ST7567, ST7570, ST7591
- Solomon SSD1303, SSD1305, SSD1306, SSD1309, SSD1805, SSD1815
- Sunplus SPLC501C
- UltraChip UC1601, UC1606, UC1608, UC1611, UC1628, UC1638, UC1701

Bits per pixel

The driver currently supports 1, 2 and 4 bpp resolutions.

Interfaces

The driver supports the indirect interface (8 bit) of the display controller. Parallel, 4-pin SPI or I2C bus can be used.

34.7.17.2 Color depth and display orientation

The driver can be used with different orientations and color depths. Each configuration can be used with or without a display driver cache. The following table shows the configuration macros which can be used to create and link the driver during the initialization:

Identifier	Color depth	Cache	Orientation
GUIDRV_SPAGE_1C0	1bpp	No	default
GUIDRV_SPAGE_0Y_1C0	1bpp	No	Y axis mirrored
GUIDRV_SPAGE_0X_1C0	1bpp	No	X axis mirrored
GUIDRV_SPAGE_0XY_1C0	1bpp	No	X and Y axis mirrored
GUIDRV_SPAGE_0S_1C0	1bpp	No	X and Y swapped
GUIDRV_SPAGE_0SY_1C0	1bpp	No	X and Y swapped, Y axis mirrored
GUIDRV_SPAGE_0SX_1C0	1bpp	No	X and Y swapped, X axis mirrored
GUIDRV_SPAGE_0SXY_1C0	1bpp	No	X and Y swapped, X and Y axis mirrored
GUIDRV_SPAGE_1C1	1bpp	Yes	default
GUIDRV_SPAGE_0Y_1C1	1bpp	Yes	Y axis mirrored
GUIDRV_SPAGE_0X_1C1	1bpp	Yes	X axis mirrored
GUIDRV_SPAGE_0XY_1C1	1bpp	Yes	X and Y axis mirrored
GUIDRV_SPAGE_0S_1C1	1bpp	Yes	X and Y swapped
GUIDRV_SPAGE_0SY_1C1	1bpp	Yes	X and Y swapped, Y axis mirrored
GUIDRV_SPAGE_0SX_1C1	1bpp	Yes	X and Y swapped, X axis mirrored
GUIDRV_SPAGE_0SXY_1C1	1bpp	Yes	X and Y swapped, X and Y axis mirrored
GUIDRV_SPAGE_2C0	2bpp	No	default

 © 2020 SEGGER Microcontroller GmbH

Identifier	Color depth	Cache	Orientation
GUIDRV_SPAGE_OY_2C0	2bpp	No	Y axis mirrored
GUIDRV_SPAGE_OX_2C0	2bpp	No	X axis mirrored
GUIDRV_SPAGE_OXY_2C0	2bpp	No	X and Y axis mirrored
GUIDRV_SPAGE_OS_2C0	2bpp	No	X and Y swapped
GUIDRV_SPAGE_OSY_2C0	2bpp	No	X and Y swapped, Y axis mirrored
GUIDRV_SPAGE_OSX_2C0	2bpp	No	X and Y swapped, X axis mirrored
GUIDRV_SPAGE_OSXY_2C0	2bpp	No	X and Y swapped, X and Y axis mirrored
GUIDRV_SPAGE_2C1	2bpp	Yes	default
GUIDRV_SPAGE_OY_2C1	2bpp	Yes	Y axis mirrored
GUIDRV_SPAGE_OX_2C1	2bpp	Yes	X axis mirrored
GUIDRV_SPAGE_OXY_2C1	2bpp	Yes	X and Y axis mirrored
GUIDRV_SPAGE_OS_2C1	2bpp	Yes	X and Y swapped
GUIDRV_SPAGE_OSY_2C1	2bpp	Yes	X and Y swapped, Y axis mirrored
GUIDRV_SPAGE_OSX_2C1	2bpp	Yes	X and Y swapped, X axis mirrored
GUIDRV_SPAGE_OSXY_2C1	2bpp	Yes	X and Y swapped, X and Y axis mirrored
GUIDRV_SPAGE_4C0	4bpp	No	default
GUIDRV_SPAGE_OY_4C0	4bpp	No	Y axis mirrored
GUIDRV_SPAGE_OX_4C0	4bpp	No	X axis mirrored
GUIDRV_SPAGE_OXY_4C0	4bpp	No	X and Y axis mirrored
GUIDRV_SPAGE_OS_4C0	4bpp	No	X and Y swapped
GUIDRV_SPAGE_OSY_4C0	4bpp	No	X and Y swapped, Y axis mirrored
GUIDRV_SPAGE_OSX_4C0	4bpp	No	X and Y swapped, X axis mirrored
GUIDRV_SPAGE_OSXY_4C0	4bpp	No	X and Y swapped, X and Y axis mirrored
GUIDRV_SPAGE_4C1	4bpp	Yes	default
GUIDRV_SPAGE_OY_4C1	4bpp	Yes	Y axis mirrored
GUIDRV_SPAGE_OX_4C1	4bpp	Yes	X axis mirrored
GUIDRV_SPAGE_OXY_4C1	4bpp	Yes	X and Y axis mirrored
GUIDRV_SPAGE_OS_4C1	4bpp	Yes	X and Y swapped
GUIDRV_SPAGE_OSY_4C1	4bpp	Yes	X and Y swapped, Y axis mirrored
GUIDRV_SPAGE_OSX_4C1	4bpp	Yes	X and Y swapped, X axis mirrored
GUIDRV_SPAGE_OSXY_4C1	4bpp	Yes	X and Y swapped, X and Y axis mirrored

Important note for mirroring

As far as we know nearly all supported controllers of this driver support hardware mirroring for X- and Y-axis. If one or both of axis need to be mirrored it is highly recommended to use the hardware commands for mirroring within the initialization sequence of the controller, because software mirroring could cause a negative effect on the performance.

34.7.17.3 Driver selection

To use GUIDRV_SPage for the given display, the following call may be used in the function LCD_X_Config:

 © 2020 SEGGER Microcontroller GmbH

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SPAGE_4C0, GUICC_4, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

34.7.17.4 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the display.

34.7.17.5 RAM requirements

This display driver can be used with or without a display data cache. The data cache contains a complete copy of the LCD data RAM. If no cache is used, there are no additional RAM requirements.
It is highly recommended to use this driver with a data cache for faster LCD-access. Not using a cache degrades the performance of this driver seriously. The amount of memory used by the cache may be calculated as follows:

```
Size of RAM (in bytes) = (LCD_YSIZE + (8 ÷ LCD_BITSPERPIXEL - 1)) ÷ 8 ×
 LCD_BITSPERPIXEL × LCD_XSIZE
```

34.7.17.6 Run-time configuration

The table below shows the available run-time configuration routines for this driver:

Routine	Description
GUIDRV_SPage_Config()	Passes a pointer to a CONFIG_SPAGE structure.
GUIDRV_SPage_SetBus8()	Configures the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver.

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
GUIDRV_SPage_Set1502()	Set up the driver to use one of the following controllers: • Avant Electronics SBN0064G • Hitachi HD61202 • S6B0108 (KS0108)
GUIDRV_SPage_Set1510()	Set up the driver to use one of the following controllers: • Epson S1D15605, S1D15606, S1D15607, S1D15608, S1D15705, S1D15710, S1D15714 • Integrated Solutions Technology IST3020 • New Japan Radio Company NJU6676 • Novatek NT7502, NT7534, NT7538, NT75451 • OriseTech SPLC502B • Samsung S6B0713, S6B0719, S6B0724, S6B1713 • Sino Wealth SH1101A • Sitronix ST7522, ST7565, ST7567, ST7570, ST7571 • Solomon SSD1303, SSD1305, SSD1805, SSD1815, SSD1821 • Sunplus SPLC501C • UltraChip UC1601, UC1606, UC1608, UC1701
GUIDRV_SPage_Set1512()	Set up the driver to use one of the following controllers: • Epson S1D15E05, S1D15E06, S1D15719, S1D15721 • Integrated Solutions Technology IST3501
GUIDRV_SPage_SetST75256()	Set up the driver to use the following controllers: • Sitronix ST75256, ST75160
GUIDRV_SPage_SetST75320()	Set up the driver to use the following controller: • Sitronix ST75320
GUIDRV_SPage_SetST7591()	Set up the driver to use the following controller: • Sitronix ST7591
GUIDRV_SPage_SetUC1610()	Set up the driver to use the following controller: • UltraChip UC1610
GUIDRV_SPage_SetUC1611()	Set up the driver to use the following controller: • UltraChip UC1611
GUIDRV_SPage_SetUC1628()	Set up the driver to use the following controller: • UltraChip UC1628
GUIDRV_SPage_SetUC1638()	Set up the driver to use the following controller: • UltraChip UC1638

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.1 GUIDRV_SPage_Config()

Description

Passes a pointer to a CONFIG_SPAGE structure to the driver.

Prototype

```
void GUIDRV_SPage_Config(GUI_DEVICE   * pDevice,
                         CONFIG_SPAGE * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_SPAGE structure described below.

Elements of structure CONFIG_SPAGE

Data type	Element	Description
int	FirstSEG	First segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	FirstCOM	First common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.2 GUIDRV_SPage_SetBus8()

Description

Tells the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_SPage_SetBus8(GUI_DEVICE   * pDevice,
                          GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

Required GUI_PORT_API routines

Element	Data type
pfWrite8_A0	void (*)(U8 Data)
pfWrite8_A1	void (*)(U8 Data)
pfWriteM8_A1	void (*)(U8 * pData, int NumItems)
pfRead8_A1	U8 (*)(void)

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.3 GUIDRV_SPage_Set1502()

Description

Configures the driver to use one of the following controllers:

- Avant Electronics SBN0064G
- Hitachi HD61202
- Samsung S6B0108, KS0108

Prototype

```
void GUIDRV_SPage_Set1502(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.4 GUIDRV_SPage_Set1510()

Description

Configures the driver to use one of the following controllers:

- Epson S1D15605, S1D15606, S1D15607, S1D15608, S1D15705, S1D15710, S1D15714
- Integrated Solutions Technology IST3020
- New Japan Radio Company NJU6676
- Novatek NT7502, NT7534, NT7538, NT75451
- Samsung S6B0713, S6B0719, S6B0724, S6B1713
- Sino Wealth SH1101A
- Sitronix ST7522, ST7565, ST7567, ST7570, ST7571
- Solomon SSD1303, SSD1305, SSD1306, SSD1309, SSD1805, SSD1815, SSD1821
- Sunplus SPLC501C
- UltraChip UC1601, UC1606, UC1608, UC1701

Prototype

```
void GUIDRV_SPage_Set1510(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.5 GUIDRV_SPage_Set1512()

Description

Configures the driver to use one of the following controllers:

- Epson S1D15E05, S1D15E06, S1D15719, S1D15721

Prototype

```
void GUIDRV_SPage_Set1512(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.6 GUIDRV_SPage_SetST75256()

Description

Configures the driver to use the Sitronix ST75256 controller.

Prototype

```
void GUIDRV_SPage_SetST75256(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.7 GUIDRV_SPage_SetST75320()

Description

Configures the driver to use the Sitronix ST75320 controller.

Prototype

```
void GUIDRV_SPage_SetST75320(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.8 GUIDRV_SPage_SetST7591()

Description

Configures the driver to use the Sitronix ST7591 controller.

Prototype

```
void GUIDRV_SPage_SetST7591(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.9 GUIDRV_SPage_SetUC1610()

Description

Configures the driver use to the UltraChip UC1610 controller.

Prototype

```
void GUIDRV_SPage_SetUC1610(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.10 GUIDRV_SPage_SetUC1611()

Description

Configures the driver use to the UltraChip UC1611 controller.

Prototype

```
void GUIDRV_SPage_SetUC1611(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.11 GUIDRV_SPage_SetUC1628()

Description

Configures the driver use to the UltraChip UC1628 controller.

Prototype

```
void GUIDRV_SPage_SetUC1628(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.6.12 GUIDRV_SPage_SetUC1638()

Description

Configures the driver use to the UltraChip UC1638 controller.

Prototype

```
void GUIDRV_SPage_SetUC1638(GUI_DEVICE * pDevice);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.

 © 2020 SEGGER Microcontroller GmbH

34.7.17.7 Configuration Example

```
void LCD_X_Config(void) {
  GUI_PORT_API   PortAPI = {0};
  CONFIG_SPAGE   Config  = {0};
  GUI_DEVICE   * pDevice;
  //
  // Set display driver and color conversion for 1st layer
  //
  pDevice = GUI_DEVICE_CreateAndLink(DISPLAY_DRIVER, COLOR_CONVERSION, 0, 0);
  //
  // Display size configuration
  //
  if (LCD_GetSwapXY()) {
    LCD_SetSizeEx (0, YSIZE_PHYS,   XSIZE_PHYS);
    LCD_SetVSizeEx(0, VYSIZE_PHYS,  VXSIZE_PHYS);
  } else {
    LCD_SetSizeEx (0, XSIZE_PHYS,   YSIZE_PHYS);
    LCD_SetVSizeEx(0, VXSIZE_PHYS,  VYSIZE_PHYS);
  }
  //
  // Driver configuration
  //
  Config.FirstSEG = 0;//256 - 224;
  GUIDRV_SPage_Config(pDevice, &Config);
  //
  // Configure hardware routines
  //
  PortAPI.pfWrite8_A0  = _Write8_A0;
  PortAPI.pfWrite8_A1  = _Write8_A1;
  PortAPI.pfWriteM8_A1 = _WriteM8_A1;
  PortAPI.pfReadM8_A1  = LCD_X_8080_8_ReadM01;
  GUIDRV_SPage_SetBus8(pDevice, &PortAPI);
  //
  // Controller configuration
  //
  GUIDRV_SPage_SetUC1611(pDevice);
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.18 GUIDRV_SSD1322

34.7.18.1 Supported hardware

Controllers

The driver works with the following display controllers:

- Solomon SSD1322

Bits per pixel

The driver currently supports 4 bpp color depth.

Interfaces

The driver supports the indirect interface (8 bit) of the display controller.

34.7.18.2 Driver selection

To use GUIDRV_SSD1322 for the given display, the following command can be used e.g.:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SSD1322, GUICC_4, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

34.7.18.3 Display data RAM organization



34.7.18.4 RAM requirements

This display driver requires a display data cache, containing a complete copy of the LCD data RAM. The amount of memory used by the cache may be calculated as follows:

```
Size of RAM (in bytes) = ((LCD_XSIZE + 1) / 2) \times LCD_YSIZE
```

34.7.18.5 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_SSD1322_Config()	Passes a pointer to a CONFIG_SSD1322 structure to the driver.
GUIDRV_SSD1322_SetBus8()	Tells the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

 © 2020 SEGGER Microcontroller GmbH

34.7.18.5.1 GUIDRV_SSD1322_Config()

Description

Passes a pointer to a CONFIG_SSD1322 structure to the driver.

Prototype

```
void GUIDRV_SSD1322_Config(GUI_DEVICE     * pDevice,
                           CONFIG_SSD1322 * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_SSD1322 structure described below.

Elements of structure CONFIG_SSD1322

Data type	Element	Description
int	FirstSEG	First segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	FirstCOM	First common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.

 © 2020 SEGGER Microcontroller GmbH

34.7.18.5.2 GUIDRV_SSD1322_SetBus8()

Description

Tells the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_SSD1322_SetBus8(GUI_DEVICE   * pDevice,
                            GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

 © 2020 SEGGER Microcontroller GmbH

34.7.18.6 Required GUI_PORT_API routines

Data type	Element	Description
`void (*)(U8 Data);`	pfWrite8_A0	Pointer to a function which writes one byte to the controller with C/D line low.
`void (*)(U8 Data);`	pfWrite8_A1	Pointer to a function which writes one byte to the controller with C/D line high.
`void (*)(U8 * pData, int NumItems);`	pfWriteM8_A1	Pointer to a function which writes multiple bytes to the controller with C/D line high.
`U8 (*)(void);`	pfRead8_A1	Pointer to a function which reads one byte from the controller with C/D line high.
`void (*)(U8 * pData, int NumItems);`	pfReadM8_A1	Pointer to a function which reads multiple bytes from the controller with C/D line high.

34.7.18.7 Configuration example

```
void LCD_X_Config(void) {
  CONFIG_SSD1322   Config = {0};
  GUI_DEVICE     * pDevice;
  GUI_PORT_API     PortAPI = {0};
  //
  // Set display driver and color conversion for 1st layer
  //
  pDevice = GUI_DEVICE_CreateAndLink(DISPLAY_DRIVER, COLOR_CONVERSION, 0, 0);
  //
  // Display size configuration
  //
  if (LCD_GetSwapXY()) {
    LCD_SetSizeEx (0, YSIZE_PHYS,   XSIZE_PHYS);
    LCD_SetVSizeEx(0, VYSIZE_PHYS,  VXSIZE_PHYS);
  } else {
    LCD_SetSizeEx (0, XSIZE_PHYS,   YSIZE_PHYS);
    LCD_SetVSizeEx(0, VXSIZE_PHYS,  VYSIZE_PHYS);
  }
  //
  // Driver configuration
  //
  Config.FirstSEG = 112;
  GUIDRV_SSD1322_Config(pDevice, &Config);
  //
  // Configure hardware routines
  //
  PortAPI.pfWrite8_A0  = LCD_X_SPI4_Write0;
  PortAPI.pfWrite8_A1  = LCD_X_SPI4_Write1;
  PortAPI.pfWriteM8_A1 = LCD_X_SPI4_WriteM1;
  PortAPI.pfRead8_A1   = LCD_X_SPI4_Read1;
  PortAPI.pfReadM8_A1  = LCD_X_SPI4_ReadM1;
  GUIDRV_SSD1322_SetBus8(pDevice, &PortAPI);
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.19 GUIDRV_SSD1926

34.7.19.1 Supported hardware

Controllers

This driver works with the Solomon SSD1926 display controller.

Bits per pixel

Currently supported color depth is 8. The display controller supports up to 32 bits per pixel. The driver can be extended on demand if support for an other color depth is required.

Interfaces

The driver supports the 16 bit indirect interface.

34.7.19.2 Color depth and display orientation

This driver can be used with different orientations. The following table shows the configuration macros which can be used to create and link the driver during the initialization:

Identifier	Color depth and orientation
GUIDRV_SSD1926_8	8bpp, default orientation
GUIDRV_SSD1926_0Y_8	8bpp, Y axis mirrored
GUIDRV_SSD1926_0X_8	8bpp, X axis mirrored
GUIDRV_SSD1926_0XY_8	8bpp, X and Y axis mirrored
GUIDRV_SSD1926_0S_8	8bpp, X and Y swapped
GUIDRV_SSD1926_0SY_8	8bpp, X and Y swapped, Y axis mirrored
GUIDRV_SSD1926_0SX_8	8bpp, X and Y swapped, X axis mirrored
GUIDRV_SSD1926_0SXY_8	8bpp, X and Y swapped, X and Y axis mirrored

34.7.19.3 Driver selection

To use GUIDRV_SSD1926 for the given display, the following command can be used e.g.:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_SSD1926, GUICC_323, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

34.7.19.4 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the display.

 © 2020 SEGGER Microcontroller GmbH

34.7.19.5 RAM requirements

This display driver may be used with or without a display data cache, containing a complete copy of the LCD data RAM. If no cache is used, there are no additional RAM requirements. It is recommended to use this driver with a data cache for faster LCD-access. The amount of memory used by the cache may be calculated as follows:

```
Size of RAM (in bytes) = LCD_XSIZE \times LCD_YSIZE
```

34.7.19.6 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_SSD1926_Config()	Passes a pointer to a CONFIG_SSD1926 structure to the driver.
GUIDRV_SSD1926_SetBus16()	Tells the driver to use the 16 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

 © 2020 SEGGER Microcontroller GmbH

34.7.19.6.1 GUIDRV_SSD1926_Config()

Description

Passes a pointer to a CONFIG_SSD1926 structure to the driver.

Prototype

```
void GUIDRV_SSD1926_Config(GUI_DEVICE     * pDevice,
                           CONFIG_SSD1926 * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_SSD1926 structure described below.

Elements of structure CONFIG_SSD1926

Data type	Element	Description
int	FirstSEG	First segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	FirstCOM	First common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	UseCache	Enables or disables use of a data cache. Should be set to 1 for enabling and to 0 for disabling.

 © 2020 SEGGER Microcontroller GmbH

34.7.19.6.2 GUIDRV_SSD1926_SetBus16()

Description

Tells the driver to use the 16 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_SSD1926_SetBus16(GUI_DEVICE   * pDevice,
                             GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. See required routines below.

34.7.19.7 Required GUI_PORT_API routines

Data type	Element	Description
void (*)(U16 Data)	pfWrite16_A0	Pointer to a function which writes one word to the controller with C/D line low.
void (*)(U16 Data)	pfWrite16_A1	Pointer to a function which writes one word to the controller with C/D line high.
void (*)(U16 * pData, int NumItems)	pfWriteM16_A0	Pointer to a function which writes multiple words to the controller with C/D line low.
void (*)(U16 * pData, int NumItems)	pfWriteM16_A1	Pointer to a function which writes multiple words to the controller with C/D line high.
U16 (*)(void)	pfRead16_A1	Pointer to a function which reads one word from the controller with C/D line high.

34.7.19.8 Configuration Example

```
#define XSIZE 320L
#define YSIZE 240L
GUI_PORT_API _PortAPI;
void LCD_X_Config(void) {
  GUI_DEVICE * pDevice_0;
  CONFIG_SSD1926 Config_0 = {0};
  //
  // Set display driver and color conversion
  //
  pDevice_0 = GUI_DEVICE_CreateAndLink(GUIDRV_SSD1926_8, GUICC_8666, 0, 0);
  //
  // Common display driver configuration
  //
  LCD_SetSizeEx (0, XSIZE, YSIZE);
  LCD_SetVSizeEx(0, XSIZE, YSIZE);
  //
  // Set driver specific configuration items
  //
  Config_0.UseCache  = 1;
  //
  // Set hardware access routines
  //
  _PortAPI.pfWrite16_A0  = LCD_X_8080_16_Write00_16;
  _PortAPI.pfWrite16_A1  = LCD_X_8080_16_Write01_16;
  _PortAPI.pfWriteM16_A0 = LCD_X_8080_16_WriteM00_16;
  _PortAPI.pfWriteM16_A1 = LCD_X_8080_16_WriteM01_16;
```

 © 2020 SEGGER Microcontroller GmbH

```
  _PortAPI.pfRead16_A1   = LCD_X_8080_16_Read01_16;
  GUIDRV_SSD1926_SetBus16(pDevice, &_PortAPI);
  //
  // Pass configuration structure to driver
  //
  GUIDRV_SSD1926_Config(pDevice, &Config_0);
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.20 GUIDRV_UC1698G

34.7.20.1 Supported Hardware

Controllers

This driver has been tested with the UltraChip UC1698G.

Bits per pixel

5 bpp grayscales.

Interfaces

The driver supports the 8- and 16-bit indirect interface.

34.7.20.2 Color depth and display orientation

The driver consists of several files. They are named _[O]_[BPP]C[CACHE].c. The [O] is optional and stands for the desired display orientation. [BPP] means the color depth to use and [CACHE] is defined with 1 to use a cache and 0 to work without cache. The following table shows the driver files and the configuration macros which should be used to create and link the driver during the initialization:

Identifier	Color depth and orientation
GUIDRV_UC1698G_5C0	5bpp, no cache, default orientation.
GUIDRV_UC1698G_0Y_5C0	5bpp, no cache, Y axis mirrored.
GUIDRV_UC1698G_0X_5C0	5bpp, no cache, X axis mirrored.
GUIDRV_UC1698G_0XY_5C0	5bpp, no cache, Y and X axis mirrored.
GUIDRV_UC1698G_0S_5C0	5bpp, no cache, X and Y axis swapped.
GUIDRV_UC1698G_0SY_5C0	5bpp, no cache, Y axis mirrored, X and Y axis swapped.
GUIDRV_UC1698G_0SX_5C0	5bpp, no cache, X axis mirrored, X and Y axis swapped.
GUIDRV_UC1698G_0SXY_5C0	5bpp, no cache, X and Y axis mirrored, X and Y axis swapped.
GUIDRV_UC1698G_5C1	5bpp, cache, default orientation.
GUIDRV_UC1698G_0Y_5C1	5bpp, cache, Y axis mirrored.
GUIDRV_UC1698G_0X_5C1	5bpp, cache, X axis mirrored.
GUIDRV_UC1698G_0XY_5C1	5bpp, cache, Y and X axis mirrored.
GUIDRV_UC1698G_0S_5C1	5bpp, cache, X and Y axis swapped.
GUIDRV_UC1698G_0SY_5C1	5bpp, cache, Y axis mirrored, X and Y axis swapped.
GUIDRV_UC1698G_0SX_5C1	5bpp, cache, X axis mirrored, X and Y axis swapped.
GUIDRV_UC1698G_0SXY_5C1	5bpp, cache, X and Y axis mirrored, X and Y axis swapped.

34.7.20.3 Driver selection

To use for the given display, the following command can be used e.g.:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_UC1698G_5C1, GUICC_5, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

 © 2020 SEGGER Microcontroller GmbH

34.7.20.4 Display data RAM organization



The picture above shows the relation between the display memory and the pixels of the LCD in terms of the color depth.

34.7.20.5 RAM requirements

This display driver requires approx. 500 Bytes to work. It can also be used with and without a display data cache, containing a complete copy of the content of the display data RAM. The amount of memory used by the cache is:

```
(LCD_XSIZE + 2) ÷ 3 × LCD_YSIZE × 2
```

Using a cache avoids reading operations from the display controller in case of XOR drawing operations and further it speeds up string output operations.

34.7.20.6 Run-time configuration

The table below shows the available run-time configuration routines of this driver:

Routine	Description
GUIDRV_UC1698G_Config()	Passes a pointer to a CONFIG_UC1698G structure to the driver.
GUIDRV_UC1698G_SetBus8()	Tells the driver to use the 8 bit indirect interface and passes pointer to a GUI_PORT_API structure to the driver.
GUIDRV_UC1698G_SetBus16()	Tells the driver to use the 16 bit indirect interface and passes pointer to a GUI_PORT_API structure to the driver.

 © 2020 SEGGER Microcontroller GmbH

34.7.20.6.1 GUIDRV_UC1698G_Config()

Description

Configures the driver to work according to the passed CONFIG_UC1698G structure.

Prototype

```
void GUIDRV_UC1698G_Config(GUI_DEVICE     * pDevice,
                           CONFIG_UC1698G * pConfig);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pConfig	Pointer to a CONFIG_UC1698G structure described below.

Elements of structure CONFIG_UC1698G

Data type	Element	Description
int	FirstSEG	First segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	FirstCOM	First common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation. The value is normally 0.
int	NumDummyReads	Number of dummy reads to do before the actual read operation.

 © 2020 SEGGER Microcontroller GmbH

34.7.20.6.2 GUIDRV_UC1698G_SetBus8()

Description

Tells the driver to use the 8 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_UC1698G_SetBus8(GUI_DEVICE   * pDevice,
                            GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. The required routines are listed below.

 © 2020 SEGGER Microcontroller GmbH

34.7.20.6.3 GUIDRV_UC1698G_SetBus16()

Description

Tells the driver to use the 16 bit indirect interface and passes a pointer to a GUI_PORT_API structure to the driver containing function pointers to the hardware routines to be used.

Prototype

```
void GUIDRV_UC1698G_SetBus16(GUI_DEVICE   * pDevice,
                             GUI_PORT_API * pHW_API);
```

Parameters

Parameter	Description
pDevice	Pointer to the driver device.
pHW_API	Pointer to a GUI_PORT_API structure. The required routines are listed below.

 © 2020 SEGGER Microcontroller GmbH

34.7.20.7 Required GUI_PORT_API routines

The required GUI_PORT_API routines depend on the used interface. If a cache is used the routines for reading data are unnecessary for each interface:

8 bit interface

Data type	Element	Description
`void (*)(U8 Data);`	pfWrite8_A0	Pointer to a function which writes one byte to the controller with C/D line low.
`void (*)(U8 Data);`	pfWrite8_A1	Pointer to a function which writes one byte to the controller with C/D line high.
`void (*)(U8 * pData, int NumItems);`	pfWriteM8_A0	Pointer to a function which writes multiple bytes to the controller with C/D line low.
`void (*)(U8 * pData, int NumItems);`	pfWriteM8_A1	Pointer to a function which writes multiple bytes to the controller with C/D line high.
`U8 (*)(void);`	pfRead8_A0	Pointer to a function which reads one byte from the controller with C/D line low.
`U8 (*)(void);`	pfRead8_A1	Pointer to a function which reads one byte from the controller with C/D line high.
`void (*)(U8 * pData, int NumItems);`	pfReadM8_A1	Pointer to a function which reads multiple bytes from the controller with C/D line high.

16 bit interface

Data type	Element	Description
`void (*)(U16 Data);`	pfWrite16_A0	Pointer to a function which writes one word to the controller with C/D line low.
`void (*)(U16 Data);`	pfWrite16_A1	Pointer to a function which writes one word to the controller with C/D line high.
`void (*)(U16 * pData, int NumItems);`	pfWriteM16_A0	Pointer to a function which writes multiple words to the controller with C/D line low.
`void (*)(U16 * pData, int NumItems);`	pfWriteM16_A1	Pointer to a function which writes multiple words to the controller with C/D line high.
`U16 (*)(void);`	pfRead16_A0	Pointer to a function which reads one word from the controller with C/D line low.
`U16 (*)(void);`	pfRead16_A1	Pointer to a function which reads one word from the controller with C/D line high.
`void (*)(U16 * pData, int NumItems);`	pfReadM16_A1	Pointer to a function which reads multiple words from the controller with C/D line high.

 © 2020 SEGGER Microcontroller GmbH

34.7.21 GUIDRV_CompactColor_16

34.7.21.1 Supported Hardware

Controllers

This driver works with the following display controllers:

- Ampire FSA506
- Epson S1D13742, S1D13743, S1D19122
- FocalTech FT1509
- Himax HX8301, HX8312A, HX8325A, HX8340, HX8347, HX8352, HX8352B, HX8353
- Hitachi HD66766, HD66772, HD66789
- Ilitek ILI9161, ILI9220, ILI9221, ILI9320, ILI9325, ILI9326, ILI9328, ILI9342, ILI9481
- LG Electronics LGDP4531, LGDP4551
- MagnaChip D54E4PA7551
- Novatek NT39122, NT7573
- OriseTech SPFD5408, SPFD54124C, SPFD5414D, SPFD5420A
- Renesas R61505, R61509, R61516, R61526, R61580, R63401
- Samsung S6D0110A, S6D0117, S6D0128, S6D0129, S6D04H0
- Sharp LCY-A06003, LR38825
- Sitronix ST7628, ST7637, ST7687, ST7712, ST7715, ST7735, ST7787, ST7789
- Solomon SSD1284, SSD1289, SSD1298, SSD1355, SSD1961, SSD1963, SSD2119
- Toshiba JBT6K71

Bits per pixel

Supported color depth is 16 bpp.

Interfaces

The driver supports the indirect interface (8- and 16-bit) and the 3 pin SPI interface. Default mode is 8-bit indirect.

34.7.21.2 Driver selection and configuration

To be able to use this driver the following macro definition needs to be added to the configuration file `LCDConf.h`:

```
#define LCD_USE_COMPACT_COLOR_16
```

After this define has been added the display driver assumes the driver specific configuration file `LCDConf_CompactColor_16.h` in the configuration folder. All further compile time configuration macros should be defined in this file. To create a driver device using the `GUIDRV_CompactColor_16` for the given display, e.g. the following command can be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_COMPACT_COLOR_16, GUICC_565, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

 © 2020 SEGGER Microcontroller GmbH

34.7.21.3 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the display.

34.7.21.4 RAM requirements

This display driver can be used with and without a display data cache, containing a complete copy of the contents of the display data RAM. The amount of memory used by the cache is:

```
LCD_XSIZE \times LCD_YSIZE \times 2 bytes
```

Using a cache is only recommended if it is intended to use a lot of drawing operations using the XOR drawing mode. A cache would avoid reading the display data in this case. Normally the use of a cache is not recommended.

The driver uses a write buffer for drawing multiple pixels of the same color. If multiple pixels of the same color should be drawn, the driver first fills the buffer and then performs a single call of the `LCD_WRITEM_A1` macro to transfer the data to the display controller at once. The default buffer size is 500 bytes.

34.7.21.5 Compile-time configuration

Controller selection

To select the desired controller the macro `LCD_CONTROLLER` should be used in the configuration file `LCDConf_CompactColor_16.h`. The following table shows the values to be used to select the appropriate controller:

Number	Supported controller
66700	Sharp LR38825
66701	• Ilitek ILI9326 • OriseTech SPFD5420A • Renesas R61509, R63401
66702	Solomon SSD1284, SSD1289, SSD1298
66703	Toshiba JBT6K71
66704	Sharp LCY-A06003
66705	Samsung S6D0129

 © 2020 SEGGER Microcontroller GmbH

Number	Supported controller
66706	MagnaChip D54E4PA7551
66707	Himax HX8312
66708	• FocalTech FT1509 • Ilitek ILI9320, ILI9325, ILI9328 • LG Electronics LGDP4531, LGDP4551 • OriseTech SPFD5408 • Renesas R61505, R61580
66709	• Epson S1D19122 • Himax HX8353 • Ilitek ILI9342, ILI9481 • Novatek NT39122 • Orisetech SPFD54124C, SPFD5414D • Renesas R61516, R61526 • Samsung S6D04H0 • Sitronix ST7628, ST7637, ST7687, ST7715, ST7735 • Solomon SSD1355, SSD1961, SSD1963
66710	Novatek NT7573
66711	Epson S1D13742, S1D13743
66712	Himax HX8347, HX8352
66713	Himax HX8340
66714	Solomon SSD2119
66715	Himax HX8352B
66716	Ampire FSA506
66717	Sitronix ST7787, ST7789
66766	• Hitachi HD66766 • Ilitec ILI9161 • Samsung S6D0110A
66772	• Himax HX8301 • Hitachi HD66772 • Ilitec ILI9220, ILI9221 • Samsung S6D0117, S6D0128 • Sitronix ST7712
66789	Hitachi HD66789

Display configuration

The following table shows the available configuration macros:

Macro	Description
LCD_MIRROR_X	Activate to mirror X-axis.
LCD_MIRROR_Y	Activate to mirror Y-axis.
LCD_SWAP_XY	Activate to swap X- and Y-axis.

For details, refer to *Display orientation* on page 2700.

Hardware access

The following table shows the available configuration macros which can be defined in this file for configuring the hardware access:

Macro	Description
LCD_NUM_DUMMY_READS	Number of required dummy reads if a read operation should be executed. The default value is 2. If using a serial interface the display controllers

 © 2020 SEGGER Microcontroller GmbH

Macro	Description
	HD66766 and HD66772 need 5 dummy reads. Sharp LR38825 needs 3 dummy reads with a 8-bit bus.
LCD_REG01	This macro is only required if a Himax HX8312A is used. Unfortunately the register 0x01 (Control register 1) contains orientation specific settings as well as common settings. So this macro should contain the contents of this register.
LCD_SERIAL_ID	With a serial 3 wire interface this macro defines the ID signal of the device ID code. It should be 0 (default) or 1. **Please note:** This macro is only used with the 3 wire protocol for Hitachi HD66772, Samsung S6D0117, Himax HX8301 and Ilitek ILI9220.
LCD_USE_SERIAL_3PIN	This configuration macro has been implemented to support the 3 wire serial interface of the following controllers: Hitachi HD66772, Samsung S6D0117, Himax HX8301, Ilitek ILI9220. Should be set to 1 if the 3 wire serial interface is used. Default is 0. **Please note:** Do not use this macro with other display controllers!
LCD_USE_PARALLEL_16	Should be set to 1 if the 16 bit parallel interface is used. Default is 0.
LCD_WRITE_BUFFER_SIZE	Defines the size of the write buffer. Using a write buffer increases the performance of the driver. If multiple pixels should be written with the same color, the driver first fills the buffer and then writes the content of the buffer using LCD_WRITEM_A1 instead of multiple calls of LCD_WRITE_A1. The default buffer size is 500 bytes.
LCD_WRITE_A0	Write a byte to display controller with RS-line low.
LCD_WRITE_A1	Write a byte to display controller with RS-line high.
LCD_READM_A1	Read multiple bytes (8 bit parallel interface) or multiple words (16 bit parallel interface) from display controller with RS-line high.
LCD_WRITEM_A1	Write multiple bytes (8 bit parallel interface) or multiple words (16 bit parallel interface) to display controller with RS-line high.
LCD_WRITEM_A0	Write multiple bytes (8 bit parallel interface) or multiple words (16 bit parallel interface) to display controller with RS-line low.

The 'Driver Output Mode' and 'Entry Mode' registers are initialized automatically.

34.7.21.6 Additional configuration switches

The following table shows optional configuration switches available for this driver:

Macro	Description
LCD_CACHE	When set to 0, no display data cache is used, which slows down the speed of the driver. Default is 1 (cache activated).
LCD_FIRSTCOM0	This macro can be used to define the first common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display doc.
LCD_FIRSTSEG0	This macro can be used to define the first segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display doc.
LCD_SUPPORT_CACHECONTROL	When set to 1, LCD_ControlCache() can be used.

34.7.21.7 Configuration example

The following shows how to select the driver and how it can be configured:

LCDConf.h

As explained above it should include the following for selecting the driver:

 © 2020 SEGGER Microcontroller GmbH

```
#define LCD_USE_COMPACT_COLOR_16
```

LCDConf_CompactColor_16.h

This file contains the display driver specific configuration and could look as the following:

```
//
// General configuration of LCD
//
#define LCD_CONTROLLER      66709 // Renesas R61516
#define LCD_BITSPERPIXEL       16
#define LCD_USE_PARALLEL_16     1
#define LCD_MIRROR_Y            1
//
// Indirect interface configuration
//
void LCD_X_Write01_16(unsigned short c);
void LCD_X_Write00_16(unsigned short c);
void LCD_X_WriteM01_16(unsigned short * pData, int NumWords);
void LCD_X_WriteM00_16(unsigned short * pData, int NumWords);
void LCD_X_ReadM01_16 (unsigned short * pData, int NumWords);
#define LCD_WRITE_A1(Word) LCD_X_Write01_16(Word)
#define LCD_WRITE_A0(Word) LCD_X_Write00_16(Word)
#define LCD_WRITEM_A1(Word, NumWords) LCD_X_WriteM01_16(Word, NumWords)
#define LCD_WRITEM_A0(Word, NumWords) LCD_X_WriteM00_16(Word, NumWords)
#define LCD_READM_A1(Word, NumWords)  LCD_X_ReadM01_16(Word, NumWords)
```

LCDConf.c

The following shows how to create a display driver device with this driver and how to configure it:

```
void LCD_X_Config(void) {
  //
  // Set display driver and color conversion
  //
  GUI_DEVICE_CreateAndLink(GUIDRV_COMPACT_COLOR_16, // Display driver
                           GUICC_M565,              // Color conversion
                           0, 0);
  //
  // Display driver configuration
  //
  LCD_SetSizeEx(0, 240, 320);
  // Physical display size in pixels
}
```

 © 2020 SEGGER Microcontroller GmbH

34.7.22 GUIDRV_Fujitsu_16

This driver supports the Fujitsu Graphic display controllers. It has been tested with "Jasmine", but it should also work with "Lavender", since all relevant registers are compatible.

34.7.22.1 Supported hardware

Controllers

This driver works with the following display controllers:

- Fujitsu Jasmine
- Fujitsu Lavender

Bits per pixel

Supported color depths are 1, 2, 4, 8 and 16 bpp.

Interfaces

The driver has been tested with a 32 bit interface to the CPU. If a 16 bit interface is used, the 32-bit accesses can be replaced by 2 16-bit accesses.

34.7.22.2 Driver selection and configuration

To be able to use this driver the following macro definition needs to be added to the configuration file `LCDConf.h`:

```
#define LCD_USE_FUJITSU_16
```

After this define has been added the display driver assumes the driver specific con- figuration file `LCDConf_Fujitsu_16.h` in the configuration folder. All further compile time configuration macros should be defined in this file. To create a driver device using the `GUIDRV_Fujitsu_16` for the given display, e.g. the following command can be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_FUJITSU_16, GUICC_556, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

34.7.22.3 Available configuration macros (compile time configuration)

Controller selection

To select the desired controller the macro `LCD_CONTROLLER` should be used in the configuration file `LCDConf_Fujitsu_16.h`. The following table shows the values to be used to select the appropriate controller:

Number	Supported controller
8720	Fujitsu Jasmine
8721	Fujitsu Lavender

34.7.22.4 Display data RAM organization

The display controller uses DRAM in an optimized, non-linear way (described in the Fujitsu documentation). Direct memory access is not used by the driver.

34.7.22.5 RAM requirements

About 16 bytes for some static variables.

 © 2020 SEGGER Microcontroller GmbH

34.7.22.6 Hardware configuration

This driver requires a direct interface for hardware access as described in the chapter *Configuration* on page 2396. The following table lists the macros which must be defined for hardware access:

Macro	Description
LCD_READ_REG	Read a register of the display controller. (as 32 bit value) (optional)
LCD_WRITE_REG	Write a register of the display controller. (as 32 bit value) (optional)

The driver contains a default for hardware access macros, which configures 32 bit access on the Fujitsu demonstration platform (Using an MB91361 or MB91362 and a Jasmine chip at address 0x30000000); if the target hardware is compatible with these settings, then LCD_READ_REG(), LCD_WRITE_REG() do not need to be defined.

Color format (R/B swap)

It seems that on some target systems, Red and blue are swapped. This can be changed via software if the config switch LCD_SWAP_RB is toggled in the configuration file.

Hardware initialization

The display controller requires a complicated initialization. Example code is available from Fujitsu in the GDC module. This code is not part of the driver, since it depends on the actual chip used, on the clock settings, the display and a lot of other things. We recommend using the original Fujitsu code, since the documentation of the chips is not sufficient to write this code. Before calling GUI_Init(), the GDC should be initialized using this code (typically called as GDC_Init(0xff)).

Example

LCDConf.h for VGA display, 8bpp, Jasmine:

```
#define LCD_XSIZE         640 // X-resolution of LCD, Logical color
#define LCD_YSIZE         480 // Y-resolution of LCD, Logical color
#define LCD_BITSPERPIXEL    8
#define LCD_CONTROLLER   8720 // Jasmine
```

34.7.22.7 Additional configuration switches

The following table shows optional configuration macros available for this driver:

Macro	Description
LCD_ON	Function replacement macro which switches the display on.
LCD_OFF	Function replacement macro which switches the display off.

 © 2020 SEGGER Microcontroller GmbH

34.7.23 GUIDRV_Page1bpp

34.7.23.1 Supported hardware

Controllers

This driver works with the following display controllers:

- Epson S1D10605, S1D15605, S1D15705, S1D15710, S1D15714, S1D15721, S1D15E05, S1D15E06, SED1520, SED1560, SED1565, SED1566, SED1567, SED1568, SED1569, SED1575
- Hitachi HD61202
- Integrated Solutions Technology IST3020
- New Japan Radio Company NJU6676, NJU6679
- Novatek NT7502, NT7534, NT7538, NT75451
- Philips PCF8810, PCF8811, PCF8535, PCD8544
- Samsung KS0108B, KS0713, KS0724, S6B0108B, S6B0713, S6B0719, S6B0724, S6B1713
- Sino Wealth SH1101A
- Sitronix ST7522, ST7565, ST7567
- Solomon SSD1303, SSD1805, SSD1815, SSD1821
- ST Microelectronics ST7548, STE2001, STE2002
- Sunplus SPLC501C
- UltraChip UC1601, UC1606, UC1608, UC1701

It should be assumed that it will also work with every similar organized controller.

Bits per pixel

Supported color depth is 1bpp.

Interfaces

The driver supports the indirect interface (8 bit) of the display controller. Parallel, 4-pin SPI or I2C bus can be used.

34.7.23.2 Driver selection and configuration

To be able to use this driver the following macro definition needs to be added to the configuration file `LCDConf.h`:

```
#define LCD_USE_PAGE1BPP
```

After this define has been added the display driver assumes the driver specific configuration file `LCDConf_Page1bpp.h` in the configuration folder. All further compile time configuration macros should be defined in this file. To create a driver device using the `GUIDRV_Page1bpp` for the given display, e.g. the following command can be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_PAGE1BPP, GUICC_1, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

34.7.23.3 Compile-time configuration

Controller selection

To select the desired controller the macro `LCD_CONTROLLER` should be used in the configuration file `LCDConf_Page1bpp.h`. The following table shows the values to be used to select the appropriate controller:

Number	Supported controller
1501	• Samsung KS0713, KS0724, S6B0713, S6B0724

 © 2020 SEGGER Microcontroller GmbH

Number	Supported controller
	• UltraChip UC1601, UC1606
1502	Samsung KS0108B S6B0108B
1503	Hitachi HD61202
1504	Philips PCF8810, PCF8811
1505	Philips PCF8535
1506	New Japan Radio Company NJU6679
1507	Philips PCD8544
1508	Epson S1D15710
1509	Solomon SSD1303 OLED controller
1510	• Epson S1D15714 • Integrated Solutions Technology IST3020 • New Japan Radio Company NJU6676 • Novatek NT7538, NT75451 • Samsung S6B0719 • Sino Wealth SH1101A • Sitronix ST7522, ST7565, ST7567 • Solomon SSD1805, SSD1821 • UltraChip UC1608, UC1701
1511	Epson S1D15721
1512	Epson S1D15E05, S1D15E06
1513	ST Microelectronics ST7548, STE2001, STE2002
1520	Epson SED1520
1560	Epson SED1560
1565	• Epson SED1565, S1D10605, S1D15605 • Novatek NT7502, NT7534 • Samsung S6B1713 • Solomon SSD1815 • Sunplus SPLC501C
1566	Epson SED1566
1567	Epson SED1567
1568	Epson SED1568
1569	Epson SED1569
1575	Epson SED1575, S1D15705

34.7.23.4 RAM requirements

This display driver can be used with or without a display data cache in the most cases. If one display contains more than 1 display controller you can not disable the cache. The data cache contains a complete copy of the contents of the display data RAM. If a cache is not used, there are no additional RAM requirements.
It is recommended to use this driver with a data cache for faster display-access. The amount of memory used by the cache may be calculated as follows:

```
Size of RAM (in bytes) = (LCD_YSIZE + 7) ÷ 8 × LCD_XSIZE
```

34.7.23.5 Additional driver functions

LCD_ControlCache

The detailed description of this function can be found *on page 2817*.

 © 2020 SEGGER Microcontroller GmbH

34.7.23.6 Hardware configuration

This driver accesses the hardware via indirect interface as described in the chapter *Configuration* on page 2396. The following table lists the macros which must be defined for hardware access:

Macro	Description
LCD_READ_A0	Read a byte from the display controller with A-line low.
LCD_READ_A1	Read a byte from the display controller with A-line high.
LCD_WRITE_A0	Write a byte to the display controller with A-line low.
LCD_WRITE_A1	Write a byte to the display controller with A-line high.
LCD_WRITEM_A1	Write multiple bytes to the display controller with A-line high.

Display orientation

Some of the supported display controllers supports hardware mirroring of x/y axis. It is recommended to use these functions instead of the display orientation macros of emWin.
If mirroring of the X axis is needed, the command 0xA1 (ADC select reverse) should be used in the initialization macro. This causes the display controller to reverse the assignment of column address to segment output. If the display size in X is smaller than the number of segment outputs of the display controller, the macro LCD_FIRSTSEG0 can be used to add an offset to the column address to make sure, the right RAM address of the display controller is accessed.
If mirroring of the Y axis is needed the command 0xC8 (SHL select revers) should be used in the initialization macro and the macro LCD_FIRSTCOM0 should be used to define the offset needed to access the right RAM address of the display controller.

34.7.23.7 Additional configuration switches

The following table shows optional configuration switches available for this driver:

Macro	Description
LCD_CACHE	When set to 0, no display data cache is used, which slows down the speed of the driver. Default is 1 (cache activated).
LCD_FIRSTCOM0	This macro can be used to define the first common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display doc.
LCD_FIRSTSEG0	This macro can be used to define the first segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display doc.
LCD_SUPPORT_CACHECONTROL	When set to 1, LCD_ControlCache() can be used.

 © 2020 SEGGER Microcontroller GmbH

34.7.24 GUIDRV_07X1

34.7.24.1 Supported hardware

Controllers

This driver works with the following display controllers:

- Novatek NT7506, NT7508
- Samsung KS0711, KS0741, S6B0711, S6B0741
- Sitronix ST7541, ST7571
- Solomon SSD1854
- ST Microelectronics STE2010
- Tomato TL0350A

Bits per pixel

Supported color depth is 2 bpp.

Interface

The controller supports either the 8-bit parallel interface as well as the 4-pin or 3-pin serial peripheral interface (SPI). The current version of the driver supports the 8-bit parallel or 4-pin SPI interface. 3 pin SPI is currently not supported.

34.7.24.2 Driver selection and configuration

To be able to use this driver the following macro definition needs to be added to the configuration file `LCDConf.h`:

```
#define LCD_USE_07X1
```

After this define has been added the display driver assumes the driver specific configuration file `LCDConf_07X1.h` in the configuration folder. All further compile time configuration macros should be defined in this file. To create a driver device using the `GUIDRV_07X1` for the given display, e.g. the following command can be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_07X1, GUICC_2, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

Controller selection

To select the desired controller the macro `LCD_CONTROLLER` should be used in the configuration file `LCDConf_07X1.h`. The following table shows the values to be used to select the appropriate controller:

Number	Supported controller
701	• Novatek NT7506 • Solomon SSD1854
702	ST Microelectronics STE2010
711	Samsung KS0711, S6B0711
741	• Novatek NT7508 • Samsung KS0741, S6B0741 • Sitronix ST7541, ST7571 • Tomato TL0350A

 © 2020 SEGGER Microcontroller GmbH

34.7.24.3 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the display. The display memory is divided into two panes for each pixel. The lower bit of each pixel is stored in pane 0 and the higher bit is stored in pane 1.

34.7.24.4 RAM requirements

This display driver may be used with or without a display data cache, containing a complete copy of the contents of the display data RAM. If a cache is not used, there are no additional RAM requirements.
It is recommended to use this driver with a data cache for faster display-access. The amount of memory used by the cache may be calculated as follows:

```
Size of RAM (in bytes) = (LCD_YSIZE + 7) / 8 × LCD_XSIZE × 2
```

34.7.24.5 Additional driver functions

LCD_ControlCache

The detailed function description can be found *on page 2817*.

34.7.24.6 Hardware configuration

This driver accesses the hardware using the indirect interface as described in the chapter *Configuration* on page 2396. The following table lists the macros which must be defined for hardware access:

Macro	Description
LCD_READ_A0	Read a byte from display controller with A-line low. (Used only if working without cache)

 © 2020 SEGGER Microcontroller GmbH

Macro	Description
LCD_READ_A1	Read a byte from display controller with A-line high. (Used only if working without cache)
LCD_WRITE_A0	Write a byte to display controller with A-line low.
LCD_WRITE_A1	Write a byte to display controller with A-line high.
LCD_WRITEM_A1	Write multiple bytes to display controller with A-line high.

Display orientation

The supported display controllers supports hardware mirroring of x/y axis. It is recommended to use these functions instead of the display orientation macros of emWin. If mirroring of the X axis is needed, the command `0xA1` (ADC select reverse) should be used in the initialization macro. This causes the display controller to reverse the assignment of column address to segment output. If the display size in X is smaller than the number of segment outputs of the display controller, the macro `LCD_FIRSTSEG0` can be used to add an offset to the column address to make sure, the right RAM address of the LCD controller is accessed. If mirroring of the Y axis is needed the command `0xC8` (SHL select revers) should be used in the initialization macro and the macro `LCD_FIRSTCOM0` should be used to define the offset needed to access the right RAM address of the display controller.

34.7.24.7 Additional configuration switches

The following table shows optional configuration switches available for this driver:

Macro	Description
LCD_FIRSTCOM0	This macro can be used to define the first common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation.
LCD_FIRSTSEG0	This macro can be used to define the first segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation.

 © 2020 SEGGER Microcontroller GmbH

34.7.25 GUIDRV_6331

34.7.25.1 Supported hardware

Controllers

This driver works with the following display controllers:

- Samsung S6B33B0X, S6B33B1X, S6B33B2X

Bits per pixel

Supported color depth is 16 bpp.

Interfaces

The driver supports the indirect interface (8 bit) of the display controller. Parallel or 4-pin SPI bus can be used.

34.7.25.2 Driver selection and configuration

To be able to use this driver the following macro definition needs to be added to the configuration file `LCDConf.h`:

```
#define LCD_USE_6331
```

After this define has been added the display driver assumes the driver specific configuration file `LCDConf_6331.h` in the configuration folder. All further compile time configuration macros should be defined in this file. To create a driver device using the `GUIDRV_6331` for the given display, e.g. the following command can be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_6331, GUICC_565, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

Controller selection

To select the desired controller the macro `LCD_CONTROLLER` should be used in the configuration file `LCDConf_6331.h`. The table below shows the values to be used to select the appropriate controller:

Number	Supported controller
6331	Samsung S6B33B0X, S6B33B1X, S6B33B2X

 © 2020 SEGGER Microcontroller GmbH

34.7.25.3 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the LCD.

34.7.25.4 RAM requirements

This display driver can be used with or without a display data cache, containing a complete copy of the LCD data RAM. The amount of memory used by the cache is:

```
LCD_XSIZE × LCD_YSIZE × 2 bytes.
```

34.7.25.5 Hardware configuration

This driver accesses the hardware with the indirect interface. The following table lists the macros which must be defined for hardware access:

Macro	Description
LCD_WRITE_A0	Write a byte to display controller with A-line low.
LCD_WRITE_A1	Write a byte to display controller with A-line high.
LCD_WRITEM_A1	Write multiple bytes to display controller with A-line high.
LCD_DRIVER_OUTPUT_MODE_DLN	'Display Line Number' (DLN) selection bits of the 'Driver Output Mode Set' instruction. Details can be found in the display controller documentation.
LCD_DRIVER_ENTRY_MODE_16B	Data bus width selection bit of the 'Entry Mode Set' instruction. Details can be found in the display controller documentation.

The 'Driver Output Mode' and 'Entry Mode' are initializes automatically.

34.7.25.6 Additional configuration switches

The following table shows optional configuration switches available for this driver:

 © 2020 SEGGER Microcontroller GmbH

Macro	Description
LCD_CACHE	When set to 0, no display data cache is used, which slows down the speed of the driver. Default is 1 (cache activated).

34.7.25.7 Special requirements

The driver needs to work with the fixed palette mode 565. The driver does not work with other palettes or fixed palette modes. Further the driver needs to swap the red and the blue part of the color index. You should use the following macro definitions in the configuration file LCDConf.h:

```
#define LCD_FIXEDPALETTE 565
#define LCD_SWAP_RB        1
```

 © 2020 SEGGER Microcontroller GmbH

34.7.26 GUIDRV_7528

34.7.26.1 Supported hardware

Controllers

This driver works with the Sitronix ST7528 display controller.

Bits per pixel

Supported color depth is 4 bpp.

Interfaces

The driver supports the 8 bit parallel (simple bus) 4-pin SPI interface.

34.7.26.2 Driver selection and configuration

To be able to use this driver the following macro definition needs to be added to the configuration file `LCDConf.h`:

```
#define LCD_USE_7528
```

After this define has been added the display driver assumes the driver specific configuration file `LCDConf_7528.h` in the configuration folder. All further compile time configuration macros should be defined in this file. To create a driver device using the `GUIDRV_7528` for the given display, e.g. the following command can be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_7528, GUICC_4, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

Controller selection

To select the desired controller the macro `LCD_CONTROLLER` should be used in the configuration file `LCDConf_7528.h`. The following table shows the values to be used to select the appropriate controller:

Number	Supported controller
7528	Sitronix ST7528

 © 2020 SEGGER Microcontroller GmbH

34.7.26.3 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the LCD. The display memory is divided into four panes for each pixel. The least significant bit (LSB) of each pixel is stored in pane 0 and the MSB is stored in pane 3.

34.7.26.4 RAM requirements

This LCD driver may be used with or without a display data cache. If the cache is used it holds a complete copy of the contents of the LCD data RAM. If cache is not used, there are no additional RAM requirements.
It is recommended to use this driver with a data cache for faster LCD-access. The amount of memory used by the cache may be calculated as follows:

```
Size of RAM (in bytes) = (LCD_YSIZE + 7) ÷ 8 × LCD_XSIZE × 4
```

A cache is required in SPI mode, because SPI does not allow reading of display contents.

34.7.26.5 Hardware configuration

This driver accesses the hardware with the indirect interface. The following table lists the macros which must be defined for hardware access:

Macro	Description
LCD_WRITE_A0	Write a byte to LCD controller with A-line low.
LCD_WRITE_A1	Write a byte to LCD controller with A-line high.

 © 2020 SEGGER Microcontroller GmbH

Macro	Description
LCD_WRITEM_A1	Write multiple bytes to display controller with A-line high.
LCD_READ_A1	Read a single byte from display controller with A-line high. Required only if no display data cache is configured.
LCD_READM_A1	Read multiple bytes from display controller with A-line high. Required only if no display data cache is configured.

34.7.26.6 Additional configuration switches

The following table shows optional configuration switches available for this driver:

Macro	Description
LCD_FIRSTCOM0	This macro can be used to define the first common address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation.
LCD_FIRSTSEG0	This macro can be used to define the first segment address to be used in the data RAM of the display controller. The value can be determined experimentally or taken from the display documentation.
LCD_NUM_COM0	A Sitronix ST7528 controller can operate in 2 modes. Mode 0 with 132 segment and 128 common outputs and mode 1 with 160 segment and 100 common outputs. which mode is used depends on hardware, the mode can not be changed via command. Defines the number of available common outputs of the display controller. Possible values for Sitronix ST7528 are: • 128 (default, mode 0) • 100 (mode 1)
LCD_NUM_SEG0	Defines the number of available segment outputs of the display controller. Possible values for Sitronix ST7528 are: • 132 (default, mode 0) • 160 (mode 1)
LCD_CACHE	When set to 0, no display data cache is used, which slows down the speed of the driver. Default is 1 (cache activated).

 © 2020 SEGGER Microcontroller GmbH

34.7.27 GUIDRV_7529

34.7.27.1 Supported hardware

Controllers

This driver works with the Sitronix ST7529 display controller.

Bits per pixel

Supported color depths are 5 bpp (default), 4 bpp and 1bpp.

Interfaces

The driver supports the indirect interface (8 and 16 bit) of the display controller. Parallel, 3-pin SPI or 4-pin SPI access can be used.

34.7.27.2 Driver selection and configuration

To be able to use this driver the following macro definition needs to be added to the configuration file `LCDConf.h`:

```
#define LCD_USE_7529
```

After this define has been added the display driver assumes the driver specific configuration file `LCDConf_7529.h` in the configuration folder. All further compile time configuration macros should be defined in this file. To create a driver device using the `GUIDRV_7529` for the given display, e.g. the following command can be used:

```
pDevice = GUI_DEVICE_CreateAndLink(GUIDRV_7529, GUICC_5, 0, 0);
```

Detailed information about palette modes can be found in the chapter *Colors* on page 617.

Controller selection

To select the desired controller the macro `LCD_CONTROLLER` should be used in the configuration file `LCDConf_7529.h`. The following table shows the values to be used to select the appropriate controller:

Number	Supported controller
7529	Sitronix ST7529

 © 2020 SEGGER Microcontroller GmbH

34.7.27.3 Display data RAM organization



The picture above shows the relation between the display memory and the SEG and COM lines of the LCD.

34.7.27.4 RAM requirements

This display driver can be used with or without a display data cache, containing a complete copy of the LCD data RAM. If no cache is used, there are no additional RAM requirements. It is optional (but recommended) to use this driver with a data cache for faster LCD-access. The amount of memory used by the cache may be calculated as follows:

```
5bpp mode:
Size of RAM (in bytes) =  (LCD_XSIZE + 2) ÷ 3 × 3 × LCD_YSIZE
4bpp mode:
Size of RAM (in bytes) = ((LCD_XSIZE + 2) ÷ 3 × 3 + 1) ÷ 2 × LCD_YSIZE
1bpp mode:
Size of RAM (in bytes) = ((LCD_XSIZE + 2) ÷ 3 × 3 + 7) ÷ 8 × LCD_YSIZE
```

 © 2020 SEGGER Microcontroller GmbH

34.7.27.5 Hardware configuration

This driver accesses the hardware with the indirect interface. The following table lists the macros which must be defined for hardware access:

Macro	Description
LCD_WRITE_A0	Write a byte to LCD controller with A-line low.
LCD_WRITE_A1	Write a byte to LCD controller with A-line high.
LCD_WRITEM_A1	Write multiple bytes to display controller with A-line high.
LCD_READM_A1	Read multiple bytes from display controller with A-line high. Required only if no display data cache is configured.
LCD_FIRSTPIXEL0	If the display size in X is smaller than the number of segment outputs of the display controller, this macro can be used for defining the first visible pixel of the display. It should be used if the first segment lines of the display controller are not connected to the display.

34.7.27.6 Additional configuration switches

The following table shows optional configuration switches available for this driver:

Macro	Description
LCD_CACHE	When set to 0, no display data cache is used, which slows down the speed of the driver. Default is 1 (cache activated).

 © 2020 SEGGER Microcontroller GmbH

34.7.28 GUIDRV_Template - Template for a new driver

This driver is part of the basic package and can be easily adapted to each display controller. It contains the complete functionality needed for a display driver.

Adapting the template driver

To adapt the driver to a currently not supported display controller you only have to adapt the routines `_SetPixelIndex()` and `_GetPixelIndex()`. The upper layers calling this routines already make sure that the given coordinates are in range, so that no check on the parameters needs to be performed.
If a display is not readable the function `_GetPixelIndex()` won't be able to read back the contents of the display data RAM. In this case a display data cache should be implemented in the driver, so that the contents of each pixel is known by the driver. If no data cache is available in this case some functions of emWin will not work right. These are all functions which need to invert pixels. Especially the XOR draw mode and the drawing of text cursors (which also uses the XOR draw mode) will not work right. A simple application which does not use the XOR draw mode will also work without adapting the function `_GetPixelIndex()`. In a second step it should be optimized to improve drawing speed.

 © 2020 SEGGER Microcontroller GmbH

34.8 LCD layer and display driver API

This chapter explains functions used to set and get certain layer attributes, for example size, visibility or alpha value of a layer, where each layer is represented by a display driver configured in `LCD_X_Config()`. The chapter also describes how to manage the content of a display driver cache.
Please note that most of the following functions are not thread-safe. Therefore it is recommended to use `GUI_LOCK/GUI_UNLOCK` before/after using them in multitask environments.

34.8.1 Display driver API

The table below lists the available routines in alphabetical order. Detailed descriptions follow.

Routine	Description
“Get” group	
LCD_GetBitsPerPixel()	Returns the number of bits per pixel.
LCD_GetBitsPerPixelEx()	Returns the number of bits per pixel of given layer/display.
LCD_GetNumColors()	Return the number of available colors.
LCD_GetNumColorsEx()	Returns the number of available colors of given layer/display.
LCD_GetPosEx()	Returns the position of the given layer in x and y direction.
LCD_GetVRAMAddr()	Returns the address of the framebuffer.
LCD_GetVRAMAddrEx()	Returns the address of the framebuffer for the given layer.
LCD_GetVXSize()	Return virtual X-size of LCD in pixels.
LCD_GetVXSizeEx()	Returns virtual X-size of given layer/display in pixels.
LCD_GetVYSize()	Return virtual Y-size of LCD in pixels.
LCD_GetVYSizeEx()	Returns virtual Y-size of given layer/display in pixels.
LCD_GetXMag()	Returns the magnification factor in x.
LCD_GetXMagEx()	Returns the magnification factor of given layer/display in x.
LCD_GetXSize()	Return physical X-size of LCD in pixels.
LCD_GetXSizeEx()	Returns physical X-size of given layer/display in pixels.
LCD_GetYMag()	Returns the magnification factor in y.
LCD_GetYMagEx()	Returns the magnification factor of given layer/display in y.
LCD_GetYSize()	Return physical Y-size of LCD in pixels.
LCD_GetYSizeEx()	Returns physical Y-size of given layer/display in pixels.
“Set” group	
LCD_SetAlphaEx()	Sets the layer alpha value.*1
LCD_SetAlphaModeEx()	Enables layer alpha mode.*1
LCD_SetChromaEx()	Sets colors to be used for chroma mode.*1
LCD_SetChromaModeEx()	Enables chroma mode.*1
LCD_SetPosEx()	Sets the layer position of the given layer in x and y direction.
LCD_SetVisEx()	Sets the visibility of a layer.*1

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
Configuration group	
LCD_SetBufferPtr()	This function is used to set an array with buffer addresses for the currently selected layer.
LCD_SetBufferPtrEx()	This function is used to set an array with buffer addresses for the layer with the given index.
LCD_Off()	Switches the display off.*1
LCD_OffEx()	Switches the given display off.*1
LCD_On()	Switches the display on.*1
LCD_OnEx()	Switches the given display on.*1
LCD_Refresh()	Refreshes the currently selected layer.*1
LCD_RefreshEx()	Refreshes the layer with the given index.*1
LCD_SetDevFunc()	Sets optional or custom defined routines for the display driver.*1
LCD_SetMaxNumColors()	Sets the maximum number of colors used in palette based bitmaps.
LCD_SetSizeEx()	Sets the physical size of the visible area of the given display/layer.
LCD_SetVRAMAddrEx()	Sets the address of the video RAM of the given layer.*1
LCD_SetVSizeEx()	Sets the size of the virtual display area of the given layer.*1
Cache group	
LCD_ControlCache()	Locks, unlocks and flushes the cache of the display controller if it is supported.

Note

1. Optional function, not supported by each driver.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1 "Get" group

34.8.1.1.1 LCD_GetBitsPerPixel()

Description

Returns the number of bits per pixel.

Prototype

```
int LCD_GetBitsPerPixel(void);
```

Return value

Number of bits per pixel.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.2 LCD_GetBitsPerPixelEx()

Description

Returns the number of bits per pixel.

Prototype

```
int LCD_GetBitsPerPixelEx(int LayerIndex);
```

Parameters

Parameter	Description
Index	Layer index.

Return value

Number of bits per pixel.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.3 LCD_GetNumColors()

Description

Returns the number of currently available colors on the LCD.

Prototype

```
U32 LCD_GetNumColors(void);
```

Return value

Number of available colors.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.4 LCD_GetNumColorsEx()

Description

Returns the number of currently available colors on the LCD.

Prototype

```
U32 LCD_GetNumColorsEx(int LayerIndex);
```

Parameters

Parameter	Description
Index	Layer index.

Return value

Number of available colors.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.5 LCD_GetPosEx()

Description

Returns the position of the given layer in x and y direction.

Prototype

```
int LCD_GetPosEx(int   LayerIndex,
                 int * pxPos,
                 int * pyPos);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
pxPos	Contains layer position in x direction.
pyPos	Contains layer position in y direction.

Return value

0 on success
1 on error.

Additional information

The content of the passed pointer is getting filled with values for x and y direction of the given layer.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.6 LCD_GetVRAMAddr()

Description

Returns the address of the framebuffer.

Prototype

```
void *LCD_GetVRAMAddr(void);
```

Return value

Void pointer to the framebuffer.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.7 LCD_GetVRAMAddrEx()

Description

Returns the address of the framebuffer for the given layer.

Prototype

```
void *LCD_GetVRAMAddrEx(int LayerIndex);
```

Parameters

Parameter	Description
Index	Layer index.

Return value

Void pointer to the framebuffer of the given layer.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.8 LCD_GetVXSize()

34.8.1.1.9 LCD_GetVYSize()

Description

Returns the virtual X- or Y-size, respectively, of the LCD in pixels. In most cases, the virtual size is equal to the physical size.

Prototypes

```
int LCD_GetVXSize(void);
```

```
int LCD_GetVYSize(void);
```

Return value

Virtual X/Y-size of the display.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.10 LCD_GetVXSizeEx()

34.8.1.1.11 LCD_GetVYSizeEx()

Description

Returns the virtual X- or Y-size, respectively, of the LCD in pixels. In most cases, the virtual size is equal to the physical size.

Prototypes

```
int LCD_GetVXSizeEx(int Index);

int LCD_GetVYSizeEx(int Index);
```

Parameters

Parameter	Description
Index	Layer index.

Return value

Virtual X/Y-size of the display.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.12 LCD_GetXMag()

34.8.1.1.13 LCD_GetYMag()

Description

Returns the magnification factor in X- or Y-axis, respectively.

Prototypes

```
int LCD_GetXMag(void);
```

```
int LCD_GetYMag(void);
```

Return value

Magnification factor in X- or Y-axis.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.14 LCD_GetXMagEx()

34.8.1.1.15 LCD_GetYMagEx()

Description

Returns the magnification factor in X- or Y-axis, respectively.

Prototypes

```
int LCD_GetXMagEx(int Index);
```

```
int LCD_GetYMagEx(int Index);
```

Parameters

Parameter	Description
Index	Layer index.

Return value

Magnification factor in X- or Y-axis.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.16 LCD_GetXSize()

34.8.1.1.17 LCD_GetYSize()

Description

Returns the physical X- or Y-size, respectively, of the LCD in pixels.

Prototypes

```
int LCD_GetXSize(void);
```

```
int LCD_GetYSize(void);
```

Return value

Physical X/Y-size of the display.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.1.18 LCD_GetXSizeEx()

34.8.1.1.19 LCD_GetYSizeEx()

Description

Returns the physical X- or Y-size, respectively, of the LCD in pixels.

Prototypes

```
int LCD_GetXSizeEx(int Index);
```

```
int LCD_GetYSizeEx(int Index);
```

Parameters

Parameter	Description
Index	Layer index.

Return value

Physical X/Y-size of the display.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.2 "Set" group

34.8.1.2.1 LCD_SetAlphaEx()

Description

Sets the layer alpha value of the given layer.

Prototype

```
int LCD_SetAlphaEx(int LayerIndex,
                   int Alpha);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
Alpha	Alpha value (0-255) to be used. 0 means opaque, 255 fully transparent.

Return value

0 on success
1 on error.

Additional information

This feature could only be available if the hardware supports layer alpha blending and if the driver callback function reacts on LCD_X_SETALPHA. Please note that the actual reaction on the given parameter(s) takes place in the driver callback function and depends on the customers implementation. The callback function is responsible for managing the appropriate SFRs to do the operation.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.2.2 LCD_SetAlphaModeEx()

Description

Enables the layer alpha mode of the given layer.

Prototype

```
int LCD_SetAlphaModeEx(int LayerIndex,
                       int AlphaMode);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
AlphaMode	1 for enabling layer alpha mode, 0 for pixel alpha mode (should be default).

Return value

0	on success
1	on error.

Additional information

This feature could only be available if the hardware supports layer alpha blending and if the driver callback function reacts on LCD_X_SETALPHAMODE. Please note that the actual reaction on the given parameter(s) takes place in the driver callback function and depends on the customers implementation. The callback function is responsible for managing the appropriate SFRs to do the operation. Default behavior of a layer should be pixel alpha mode.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.2.3 LCD_SetChromaEx()

Description

Sets the colors to be used for the chroma mode.

Prototype

```
int LCD_SetChromaEx(int       LayerIndex,
                    LCD_COLOR ChromaMin,
                    LCD_COLOR ChromaMax);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
ChromaMin	See description below.
ChromaMax	See description below.

Return value

0 on success
1 on error.

Additional information

This feature could only be available if the hardware supports chroma blending and if the driver callback function reacts on LCD_X_SETCHROMA. The hardware implementations of chroma modes are very different. Because of that the function of the parameters ChromaMin and ChromaMax also could have different meanings. In many cases chroma blending only supports one specific transparent color. In that case only the first parameter ChromaMin should be used. Other systems support a range of color bits to be used or a color and a mask. Please note that the actual reaction on the given parameter(s) takes place in the driver callback function and depends on the customers implementation. The callback function is responsible for managing the appropriate SFRs to do the operation.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.2.4 LCD_SetChromaModeEx()

Description

Enables the chroma mode of the given layer.

Prototype

```
int LCD_SetChromaModeEx(int LayerIndex,
                        int ChromaMode);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
ChromaMode	1 for enabling chroma mode, 0 for disabling (default)

Return value

0 on success
1 on error.

Additional information

This feature could only be available if the hardware supports chroma blending and if the driver callback function reacts on LCD_X_SETCHROMAMODE. Please note that the actual reaction on the given parameter(s) takes place in the driver callback function and depends on the customers implementation. The callback function is responsible for managing the appropriate SFRs to do the operation.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.2.5 LCD_SetPosEx()

Description

Sets the layer position of the given layer in x and y direction.

Prototype

```
int LCD_SetPosEx(int LayerIndex,
                 int xPos,
                 int yPos);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
xPos	New position in x direction.
yPos	New position in y direction.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.2.6 LCD_SetVisEx()

Description

Sets the visibility of the given layer.

Prototype

```
int LCD_SetVisEx(int LayerIndex,
                 int OnOff);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
OnOff	1 for visible (default), 0 for invisible.

Return value

0	on success
1	on error.

Additional information

This function works properly only if the display driver callback function appropriately reacts to the command LCD_X_SETVIS. This in turn requires the display driver callback function to manage the appropriate SFRs accordingly. How to do this in detail is explained in the documentation of the display controller.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3 Configuration group

34.8.1.3.1 LCD_SetBufferPtr()

Description

This function is used to set an array with buffer addresses for the currently selected layer. This allows incoherent buffers for multi-buffering.

Prototype

```
int LCD_SetBufferPtr(void ** pBufferPTR);
```

Parameters

Parameter	Description
pBufferPTR	An array with addresses to the different buffers.

Return value

0 on success
1 on error.

Additional information

The number of entries in the array must fit to the numbers of buffers set for multi-buffering.

Example

```
...
static const U32 _aBufferPTR[] = {
  0x00000000,  // Begin first buffer
  0x00800000   // Begin second buffer
};
LCD_SetBufferPtr(_aBufferPTR);
...
```

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.2 LCD_SetBufferPtrEx()

Description

This function is used to set an array with buffer addresses for the layer with the given index. This allows incoherent buffers for multi-buffering.

Prototype

```
int LCD_SetBufferPtrEx(int     LayerIndex,
                       void ** pBufferPTR);
```

Parameters

Parameter	Description
LayerIndex	Index of the layer the buffers are for.
pBufferPTR	An array with addresses to the different buffers.

Return value

0	on success
1	on error.

Additional information

The number of entries in the array must fit to the numbers of buffers set for multi-buffering.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.3 LCD_Off()

Description

Switches the currently selected display off.

Return value

0	on success.
1	on error.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.4 LCD_OffEx()

Description

Switches the given display off.

Prototype

```
int LCD_OffEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Index of the layer/display.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.5 LCD_On()

Description

Switches the currently selected display on.

Prototype

```
void LCD_On(void);
```

Return value

0	on success.
1	on error.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.6 LCD_OnEx()

Description

Switches the given display on.

Prototype

```
int LCD_OnEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer index.

Return value

0 on success
1 on error.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.7 LCD_Refresh()

Description

Refreshes the currently selected layer by flushing the entire cache to the LCD.

Prototype

```
int LCD_Refresh(void);
```

Return value

0	on success
1	on error.

Additional information

This function is only available when using a driver with a cache.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.8 LCD_RefreshEx()

Description

Refreshes the given layer by flushing the entire cache to the LCD.

Prototype

```
int LCD_RefreshEx(int LayerIndex);
```

Parameters

Parameter	Description
LayerIndex	Layer index.

Return value

0 on success
1 on error.

Additional information

This function is only available when using a driver with a cache.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.9 LCD_SetDevFunc()

Description

The function sets additional and / or user defined functions of the display driver.

Prototype

```
int LCD_SetDevFunc(int  LayerIndex,
                   int  IdFunc,
                   void ( *pDriverFunc)());
```

Parameters

Parameter	Description
LayerIndex	Layer index.
IdFunc	See table below.
pDriverFunc	Pointer to function which should be used.

Permitted values for element IdFunc	
LCD_DEVFUNC_COPYBUFFER	Can be used to set a custom defined routine for copying buffers. Makes only sense in combination with multiple buffers.
LCD_DEVFUNC_COPYRECT	Can be used to set a custom defined routine for copying rectangular areas.
LCD_DEVFUNC_DRAWBMP_1BPP	Can be used to set a custom routine for drawing 1bpp bitmaps. Makes sense if a custom routine should be used for drawing text and 1bpp bitmaps.
LCD_DEVFUNC_DRAWBMP_8BPP	Can be used to set a custom routine for drawing 8bpp bitmaps. Makes sense if a custom routine should be used for drawing 8bpp bitmaps.
LCD_DEVFUNC_FILLRECT	Can be used to set a custom defined routine for filling rectangles. Makes sense if for example a BitBLT engine should be used for filling operations. Can be used to set a custom defined routine for reading a single pixel from the display controller.
LCD_DEVFUNC_READMPIXELS	Can be used to set a custom defined routine for reading multiple pixels from the display controller.
LCD_DEVFUNC_READPIXEL	Can be used to set a custom defined routine for reading a single pixel from the display controller.
LCD_DEVFUNC_REFRESH	Can be used to set a custom defined routine for refreshing the LCD.

LCD_DEVFUNC_COPYBUFFER

Can be used to set up a function which copies a frame buffer to the desired location. This can make sense if for example a BitBLT engine is available to do the job. The function pointed by pDriverFunc should be of the following type:

```
void CopyBuffer(int LayerIndex,
                int IndexSrc,
                int IndexDst);
```

 © 2020 SEGGER Microcontroller GmbH

Parameter	Description
LayerIndex	Layer index.
IndexSrc	Index of the source frame buffer to be copied.
IndexDst	Index of the destination frame buffer to be overwritten.

LCD_DEVFUNC_COPYRECT

Can be used to set up a function which copies a rectangular area of the screen to the desired location. This can make sense if for example a BitBLT engine is available to do the job. The function pointed by pDriverFunc should be of the following type:

```
void CopyRect(int LayerIndex,
              int x0,
              int y0,
              int x1,
              int y1,
              int xSize,
              int ySize);
```

Parameter	Description
LayerIndex	Layer index.
x0	Leftmost pixel of the source rectangle.
y0	Topmost pixel of the source rectangle.
x1	Leftmost pixel of the destination rectangle.
y1	Topmost pixel of the destination rectangle.
xSize	X-size of the rectangle.
ySize	Y-size of the rectangle.

LCD_DEVFUNC_DRAWBMP_1BPP

Can be used to set up a function which draws 1bpp bitmaps which includes also text. This can make sense if for example a BitBLT engine is available to do the job. The function pointed by pDriverFunc should be of the following type:

```
void DrawBMP1(      int              LayerIndex,
                    int              x,
                    int              y,
                    U8 const       * p,
                    int              Diff,
                    int              xSize,
                    int              ySize,
                    int              BytesPerLine,
              const LCD_PIXELINDEX * pTrans);
```

Parameter	Description
LayerIndex	Layer index.
x	Leftmost coordinate in screen coordinates of the bitmap to be drawn.
y	Topmost coordinate in screen coordinates of the bitmap to be drawn.
p	Pointer to the pixel data of the bitmap.
Diff	Offset to the first pixel pointed by parameter p. Supported values are 0-7.
xSize	X-size in pixels of the bitmap to be drawn.
ySize	Y-size in pixels of the bitmap to be drawn.
BytesPerLine	Number of bytes of one line of bitmap data.

 © 2020 SEGGER Microcontroller GmbH

Parameter	Description
pTrans	Pointer to an array of color indices to be used to draw the bitmap data. The first color index defines the background color, the second color index defines the foreground color.

Return value

0 on success
1 on error.

Additional information

Please note that it depends on the display driver which values for parameter IdFunc are supported or not.

LCD_DEVFUNC_DRAWBMP_8BPP

Can be used to set up a function which draws 8bpp palette based bitmaps. This can make sense if for example a BitBLT engine is available to do the job. The function pointed by pDriverFunc should be of the following type:

```
void DrawBMP8(      int              LayerIndex,
                    int              x,
                    int              y,
                    U8 const       * p,
                    int              xSize,
                    int              ySize,
                    int              BytesPerLine,
              const LCD_PIXELINDEX * pTrans);
```

Parameter	Description
LayerIndex	Layer index.
x	Leftmost coordinate in screen coordinates of the bitmap to be drawn.
y	Topmost coordinate in screen coordinates of the bitmap to be drawn.
p	Pointer to the pixel data of the bitmap.
xSize	X-size in pixels of the bitmap to be drawn.
ySize	Y-size in pixels of the bitmap to be drawn.
BytesPerLine	Number of bytes of one line of bitmap data.
pTrans	Pointer to an array of color indices to be used to draw the bitmap data. These colors are addressed by the index values of the pixels.

Return value

0 on success
1 on error.

Additional information

Please note that it depends on the display driver which values for parameter IdFunc are supported or not.

LCD_DEVFUNC_FILLRECT

Can be used to set a custom function for filling operations. The function pointed by pDriverFunc should be of the following type:

```
void FillRect(int LayerIndex,
              int x0,
```

 © 2020 SEGGER Microcontroller GmbH

```
                int y0,
                int x1,
                int y1,
                U32 PixelIndex);
```

Parameter	Description
LayerIndex	Layer index.
x0	Leftmost coordinate to be filled in screen coordinates.
y0	Topmost coordinate to be filled in screen coordinates.
x1	Rightmost coordinate to be filled in screen coordinates.
y1	Bottommost coordinate to be filled in screen coordinates.
PixelIndex	Color index to be used to fill the specified area.

LCD_DEVFUNC_READMPIXELS

Can be used to set a custom defined routine for reading multiple pixels from the display controller. The function pointed by pDriverFunc should be one of the following types:

```
void _ReadMPixels(int   LayerIndex,
                  U16 * pBuffer,
                  U32   NumPixels);

void _ReadMPixels(int   LayerIndex,
                  U32 * pBuffer,
                  U32   NumPixels);
```

Parameter	Description
LayerIndex	Layer index.
pBuffer	Pointer to the buffer in which the pixel data has to be stored.
NumPixels	Number pixels to read.

The required function type depends on the configured color depth of the display driver. In 16bpp mode a U16 pointer is required for the buffer and for 18bpp up to 32bpp a U32 pointer is required.

LCD_DEVFUNC_READPIXEL

Can be used to set a custom defined routine for reading a single pixel from the display controller. The function pointed by pDriverFunc should be one of the following types:

```
U16 _ReadPixel(int LayerIndex);

U32 _ReadPixel(int LayerIndex);
```

Parameter	Description
LayerIndex	Layer index.

The required type of the return value depends on the configured color depth of the display driver. In 16bpp mode U16 is required and for 18bpp up to 32bpp U32 is required.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.10 LCD_SetMaxNumColors()

Description

Sets the maximum number of colors used in palette based bitmaps.

Prototype

```
int LCD_SetMaxNumColors(unsigned MaxNumColors);
```

Parameters

Parameter	Description
MaxNumColors	Maximum number of colors used in palette based bitmaps. Default is 256.

Return value

0 on success
1 on error.

Additional information

During the process of initialization emWin allocates a buffer required for converting color values of the bitmaps into index values for the controller. This buffer requires 4 bytes per color. If the system is short on RAM and only a few colors are used, this function could spare up to 1016 bytes of dynamically RAM. Per default the buffer uses 1024 bytes of RAM. But if for example only 2 colors are used (typically b/w-configuration) only 8 bytes for 2 colors are required. The function needs to be called by the routine `GUI_X_Config()`.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.11 LCD_SetSizeEx()

Description

Sets the physical size of the visible area of the given display/layer.

Prototype

```
int LCD_SetSizeEx(int LayerIndex,
                  int xSize,
                  int ySize);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
xSize	X-Size in pixels of the visible area of the given layer.
ySize	Y-Size in pixels of the visible area of the given layer.

Return value

0 on success
1 on error.

Additional information

The function requires a display driver which is able to manage dynamically changes of the display size. If the display driver does not support this feature the function fails.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.12 LCD_SetVRAMAddrEx()

Description

Sets the address of the video RAM.

Prototype

```
int LCD_SetVRAMAddrEx(int    LayerIndex,
                      void * pVRAM);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
pVRAM	Pointer to start address of video RAM.

Return value

0	on success
1	on error.

Additional information

The function requires a display driver which is able to manage dynamically changes of the video RAM address. If the display driver does not support this feature the function fails.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.3.13 LCD_SetVSizeEx()

Description

Sets the size of the virtual display area.

Prototype

```
int LCD_SetVSizeEx(int LayerIndex,
                   int xSize,
                   int ySize);
```

Parameters

Parameter	Description
LayerIndex	Layer index.
xSize	X-Size in pixels of the virtual area of the given layer.
ySize	Y-Size in pixels of the virtual area of the given layer.

Return value

0 on success.
1 on error.

Additional information

The function requires a display driver which is able to manage dynamically changes of the virtual display size. If the display driver does not support this feature the function fails.

 © 2020 SEGGER Microcontroller GmbH

34.8.1.4 Cache group

34.8.1.4.1 LCD_ControlCache()

Description

Locks, unlocks and flushes the cache of the display controller if it is supported.

Prototype

```
int LCD_ControlCache(int Cmd);
```

Parameters

Parameter	Description
Cmd	See table below.

Permitted values for element Cmd	
LCD_CC_FLUSH	Flushes the cache. The content of the cache which has changed since the last flushing operation is output to the display.
LCD_CC_LOCK	Locks the cache. Drawing operations are cached, but not output to the display.
LCD_CC_UNLOCK	Unlocks the cache. The cached data is flushed immediately. Further drawing operations are cached and output. (Write Through)

Return value

0 on success
1 on error.

Additional information

The function requires a display driver which is able to manage dynamically changes of the virtual display size. If the display driver does not support this feature the function fails. This function is automatically used for drawing operations of windows and strings.

 © 2020 SEGGER Microcontroller GmbH

Chapter 35

Touch drivers

A touch driver supports a particular family of touch controllers and all touch pads which are connected to one of these controllers. The drivers can be configured by modifying their configuration files whereas the driver itself does not need to be modified. The configuration files contain all required information for the driver including how the hardware is accessed and how the controller(s) are connected to the display. This chapter provides an overview of the touch drivers available for emWin. It explains the following in terms of each driver:

- Which touch controllers can be accessed and which interface can be used.
- RAM requirements.
- Driver specific functions.
- How to access the hardware.
- Special configuration switches.
- Special requirements for particular touch controllers.

 © 2020 SEGGER Microcontroller GmbH

35.1 GUIMTDRV_TangoC32

The driver is written for the multi touch controller TangoC32 from PIXCIR. It is delivered along with the emWin MultiTouch feature.
The controller can be accessed via I2C interface. It provides an interrupt line which needs to be used by the application to generate an interrupt. Once the driver has been initialized right it automatically fills up the multi touch buffer of emWin.

35.1.1 Supported hardware

This driver works with the following controller:

- PIXCIR Tango C32

35.1.2 Driver initialization

A good place for initializing the touch driver is the routine `LCD_X_Config()`. This makes sure, that the touch driver and the display driver has been initialized before emWin is used by the application.

First part

The first part of initializing the driver is calling the drivers configuration function. It sets up the function pointers for hardware communication.

Second part

To be able to do its work the drivers execution function needs to be called when touching the screen. That should be done via interrupt routine. For that case the touch controller provides an interrupt line which is active if a touch event occurs. The one and only thing which then should be done in the interrupt routine is calling the drivers execution function `GUIMTDRV_TangoC32_Exec()`.

35.1.3 GUIMTDRV_TangoC32 API

The following table shows the available functions of the driver.

Routine	Description
`GUIMTDRV_TangoC32_Init()`	Configuration function.
`GUIMTDRV_TangoC32_Exec()`	Execution function.

 © 2020 SEGGER Microcontroller GmbH

35.1.3.1 GUIMTDRV_TangoC32_Init()

Description

Passes a pointer to a GUIMTDRV_TANGOC32_CONFIG structure to the driver. This structure contains all required function pointers and values required by the driver.

Prototype

```
int GUIMTDRV_TangoC32_Init(GUIMTDRV_TANGOC32_CONFIG * pConfig);
```

Parameters

Parameter	Description
pConfig	Pointer to a GUIMTDRV_TANGOC32_CONFIG structure described below.

Elements of structure GUIMTDRV_TANGOC32_CONFIG

Data type	Element
void (*)(U8 SlaveAddr)	pf_I2C_Init
int (*)(U8 * pData, int Start, int Stop)	pf_I2C_Read
int (*)(U8 * pData, int NumItems, int Start, int Stop)	pf_I2C_ReadM
int (*)(U8 Data, int Start, int Stop)	pf_I2C_Write
int (*)(U8 * pData, int NumItems, int Start, int Stop)	pf_I2C_WriteM
U8	SlaveAddr

pf_I2C_Init()

Parameter	Description
SlaveAddr	I2C Slave address of touch controller to be used.

That pointer should point to a function which initializes the I2C communication. The element SlaveAddr is passed to the given function to set up the slave address of the touch controller device (normally 0x5C).

pf_I2C_Read()

Parameter	Description
pData	Pointer to an unsigned character to store the byte.
Start	Is set to 1 if bus communication starts, otherwise 0.
Stop	Is set to 1 if bus communication should end after the read operation, otherwise 0.

That function is responsible for reading one byte of data. The given pointer pData is used to store the value.
Returns 0 on success, otherwise 1.

pf_I2C_ReadM()

Parameter	Description
pData	Pointer to a buffer to be filled by the routine.
NumItems	Number of bytes to be read.
Start	Is set to 1 if bus communication starts, otherwise 0.
Stop	Is set to 1 if bus communication should end after the read operation, otherwise 0.

 © 2020 SEGGER Microcontroller GmbH

That function is responsible for reading multiple bytes of data. The given pointer pData is used to store the value.
Returns 0 on success, otherwise 1.

pf_I2C_Write()

Parameter	Description
Data	Byte to be written.
Start	Is set to 1 if bus communication starts, otherwise 0.
Stop	Is set to 1 if bus communication should end after the write operation, otherwise 0.

That function is responsible for writing one byte of data.
Returns 0 on success, otherwise 1.

pf_I2C_WriteM()

Parameter	Description
pData	Pointer to buffer to be written.
NumItems	Number of bytes to be written.
Start	Is set to 1 if bus communication starts, otherwise 0.
Stop	Is set to 1 if bus communication should end after the write operation, otherwise 0.

That function is responsible for writing multiple bytes of data. The given pointer pData is used to store the value.

Return value

Returns 0 on success, otherwise 1.

 © 2020 SEGGER Microcontroller GmbH

35.2 GUITDRV_ADS7846

35.2.1 Supported hardware

This driver works with the following controller:

- Texas Instruments ADS7846 touch screen controller

35.2.2 Driver initialization

A good place for initializing the touch driver is the routine `LCD_X_Config()`. This makes sure, that the touch driver and the display driver has been initialized before emWin is used by the application.

First part

The first part of initializing the driver is calling the drivers configuration function. It sets up the following things:

- Function pointers for hardware communication routines
- Touch panel orientation to be used
- Logical and physical AD values to be able to calculate the right position depending on the AD values of the controller

Second part

To be able to do its work the drivers execution function needs to be called periodically. We recommend an interval of 20-30 ms. The function call can be done from within a timer interrupt routine or from a separate task.

35.2.3 GUITDRV_ADS7846 API

The following table shows the available functions of the driver.

Routine	Description
`GUITDRV_ADS7846_Config()`	Configuration function.
`GUITDRV_ADS7846_Exec()`	Execution function.
`GUITDRV_ADS7846_GetLastVal()`	Retrieves the last stored values.

 © 2020 SEGGER Microcontroller GmbH

35.2.3.1 GUITDRV_ADS7846_Config()

Description

Passes a pointer to a GUITDRV_ADS7846_CONFIG structure to the driver. This structure contains all required function pointers and values required by the driver.

Prototype

```
void GUITDRV_ADS7846_Config(GUITDRV_ADS7846_CONFIG * pConfig);
```

Parameters

Parameter	Description
pConfig	Pointer to a GUITDRV_ADS7846_CONFIG structure described below.

Permitted values for element Orientation	
GUI_MIRROR_X	Mirroring the X-axis
GUI_MIRROR_Y	Mirroring the Y-axis
GUI_SWAP_XY	Swapping X- and Y-axis

Data type	Element	Description
void (*)(U8 Data)	pfSendCmd	Hardware routine for sending a byte to the controller via its SPI interface.
U16 (*)(void)	pfGetResult	Hardware routine for getting the AD conversion result of the controller via its SPI interface. The driver uses the 12 bit conversion mode. Per conversion the controller uses 16 clocks. Only the first 12 bits contain the result to be returned by this routine.
char (*)(void)	pfGetBusy	Hardware routine for getting the busy state of the controller. The routine should return 1 if the controller is busy and 0 if not.
void (*)(char OnOff)	pfSetCS	Routine for toggling the CS signal of the controller. When receiving 1 the signal should become high and vice versa.
unsigned	Orientation	One or more "OR" combined values of the table below.
int	xLog0	Logical X value 0 in pixels.
int	xLog1	Logical X value 1 in pixels.
int	xPhys0	A/D converter value for xLog0.
int	xPhys1	A/D converter value for xLog1.
int	yLog0	Logical Y value 0 in pixels.
int	yLog1	Logical Y value 1 in pixels.
int	yPhys0	A/D converter value for yLog0.
int	yPhys1	A/D converter value for yLog1.
char (*)(void)	pfGetPENIRQ	If the PENIRQ line of the touch controller is connected to a port of the target hardware a touch event can be detected by the driver. Upon polling the driver's exec routine the driver can check if a touch event is ready to be sampled by checking the PENIRQ line. Without PENIRQ line the driver will always try to sample

 © 2020 SEGGER Microcontroller GmbH

Data type	Element	Description
		a touch event even if no touch happened which will consume time even if not necessary. Without PENIRQ it is the responsibility of the user's `pfGetResult()` routine to return `0xFFFF` if the measured AD value is out of bounds. If both, the PENIRQ and the touch pressure recognition are enabled first the PENIRQ will signal that there is a touch event. Afterwards the touch pressure measurement is used to confirm that this was a valid touch and the touch had enough pressure to deliver good measurements. The routine should return 1 if a touch event is recognized and 0 if not.
`int`	`PressureMin`	Minimum pressure threshold. A measured pressure below this value means we do not have a valid touch event.
`int`	`PressureMax`	Maximum pressure threshold. A measured pressure above this value means we do not have a valid touch event.
`int`	`PlateResistanceX`	Resistance of the X-plate of the touch screen. This value is needed for calculation of the touch pressure.

 © 2020 SEGGER Microcontroller GmbH

35.2.3.2 GUITDRV_ADS7846_Exec()

Description

Execution function of the touch driver.

Prototype

```
char GUITDRV_ADS7846_Exec(void);
```

Return value

0	No update has occured.
1	Touch has been updated.

Additional information

We recommend to call the routine each 20-30 ms. If the routine detects a valid touch event it stores the result into the touch buffer via a function call to `GUI_TOUCH_StoreStateEx()`. Please note that the driver needs some function pointers to be filled correctly to be able to communicate with the external peripheral. The correct assignment of these function pointers is checked during driver configuration and leads to an abort to `GUI_ErrorOut()` on missing pointers.

 © 2020 SEGGER Microcontroller GmbH

35.2.3.3 GUITDRV_ADS7846_GetLastVal()

Description

Retrieves the last stored values for some internal variables that might be needed for calibration of the driver without knowing its internals.

Prototype

```
void GUITDRV_ADS7846_GetLastVal(GUITDRV_ADS7846_LAST_VAL * p);
```

Parameters

Parameter	Description
p	Pointer to a GUITDRV_ADS7846_LAST_VAL structure.

Elements of structure GUITDRV_ADS7846_LAST_VAL

Data type	Element	Description
int	xPhys	Last measured x value
int	yPhys	Last measured y value
int	z1Phys	Last measured z1 value
int	z2Phys	Last measured z2 value
int	PENIRQ	Last sampled PENIRQ state if PENIRQ callback has been set
int	Pressure	Last measured touch pressure if touch pressure measurement is enabled

Additional information

This function is an optional function and not required to be able to use the driver.

 © 2020 SEGGER Microcontroller GmbH

Chapter 36

VNC Server

The emWin VNC server can be used for administration of the embedded target and a variety of other purposes. It supports compressed (hextile) encoding. VNC stands for 'Virtual Network Computing'. It is a client server system based on a simple display protocol which allows the user to view and control a computing 'desktop' environment from anywhere on the Internet and from a wide variety of machine architectures, communicating via TCP/IP.

In other words: The display contents of the embedded device are visible on the screen of the machine running the client (for example, your PC); your mouse and keyboard can be used to control the target.

This feature is available in the emWin simulation and trial versions. emWin VNC support is available as a separate package and is therefore not included in the basic package. VNC support requires emWin color.

If a file system is available, it is possible to achieve file transfers between client and target together with the emWin VNC client.



 © 2020 SEGGER Microcontroller GmbH

36.1 Introduction

VNC consists of two types of components. A server, which generates a display, and a viewer, which actually draws the display on your screen. The remote machine (target or simulation) can not only be viewed, but also controlled via mouse or keyboard. The server and the viewer may be on different machines and on different architectures. The protocol (RFB V3.3) which connects the server and viewer is simple, open, and platform independent. No state is stored at the viewer. Breaking the viewer's connection to the server and then reconnecting will not result in any loss of data. Because the connection can be remade from somewhere else, you have easy mobility. Using the VNC server, you may control your target from anywhere and you can make screenshots (for example, for a manual) from a "live" system.

36.1.1 Filetransfer

In addition to the default functionality of RFB V3.3 the emWin VNC server supports file transfers. Please note that file transfer is not part of the RFB protocol.

Only supported client for file transfer is emVNC

There does not exist a standard for file transfer operations within the RFB protocol. Because of that it requires a non standard protocol extension which only works with the emVNC-client. Only emVNC could be used for file transfers between the emWin VNC server and the client machine.

36.1.2 Requirements

TCP/IP stack

Since the communication between the server and the viewer is based on a TCP/IP connection, VNC requires a TCP/IP stack. In the Win32 simulation environment, TCP/IP (Winsock) is normally present. In the target, a TCP/IP stack needs to be present. The TCP/IP stack is NOT part of emWin. The flexible interface ensures that any TCP/IP stack can be used.

Multi tasking

The VNC server needs to run as a separate thread. Therefore a multi tasking system is required to use the emWin VNC server.

File system (only for file transfers)

A file system is required only if the file transfer feature should be used.

36.1.3 Notes on this implementation

Supported client to server messages

The emWin VNC server supports pointer event messages and keyboard event messages.

Encoding

The server supports raw encoding and hextile encoding.

Performance

Most viewers support hextile encoding, which supports descent compression. A typical quarter VGA screen requires typically 20 - 50 KB of data.
The server handles incremental updates; in most cases the updated display area is a lot smaller than the entire display and less data needs to be transmitted.

The following table shows some performance examples:

 © 2020 SEGGER Microcontroller GmbH

Hardware / Configuration	ms / screen
STM32F4, 168MHz, internal RAM, WQVGA, 16bpp, HexTile	32 ms
STM32F4, 168MHz, internal RAM, WQVGA, 16bpp, Raw	76 ms
ARM7, 50MHz, external RAM cached, QVGA, 16bpp, HexTile	250 ms

Multiple servers

The implementation is fully thread safe and reentrant; multiple VNC-servers can be started on the same CPU for different layers or displays. If the target (of course the same holds true for the simulation) has multiple displays or multiple layers, this can be a useful option. Only one VNC server may be started per layer at any given time; once the connection to a viewer ends, another one can connect.

 © 2020 SEGGER Microcontroller GmbH

36.2 emVNC - client

The emVNC client is part of the emWin basic package and can be found in the tools folder as emVNC.exe. It can be used to establish a VNC connection from an MS Windows system to a VNC server. The viewer uses the RFB protocol 3.3. It has been tested with different VNC servers including the emWin VNC server, as well as TightVNC and RealVNC.

36.2.1 How to connect to a VNC-server

Once emVNC is started, it prompts for typing the network address of a VNC server to connect with:



Connecting to a VNC server using the simulation on the same PC

A VNC server running on the local host can be accessed by entering:

```
localhost
```

Alternatively connecting to `localhost` could be done by hitting the <RETURN> key or by pressing the "Connect" button while the text control is left empty.

Connecting to a VNC server running on a different PC or the target

In order to connect to a system in the network the IP address or the name has to be entered:

`192.168.1.14` or `Paul02`

Additionally the server index can be specified in order to connect to a certain server:

`192.168.1.14:1` or `Paul02:1`

Screenshot

The following screenshots show the viewer:

Connected to the simulation	Connected to the target
	

36.2.2 Opening the file transfer dialog

To spare a constantly visible menu bar in the VNC client, we added the menu option for opening the file transfer dialog to the system menu:

 © 2020 SEGGER Microcontroller GmbH



The system menu could be opened by a clicking on the upper left *emVNC* symbol or by the keyboard shortcut <ALT>+<SPACE>.

> **Note**
>
> The menu option 'Open file transfer window' is only available if the connected server has been started with file transfer support.

36.2.3 The file transfer window



The above shown file transfer window is divided into a server- and a client side. It shows the content of the currently selected directories of both sides. The following operations are available:

Selecting (multiple) files

Single clicking multiple files during <STRG> is pressed or moving the cursor with <UP> or <DOWN> to the desired file(s) and press <SPACE> while <STRG> is pressed.

Single file transfer

Double-clicking a file starts a single transfer to the opposite side.

Transfer selected files

The buttons **>>** and **<<** can be used for starting the transfer from client to server **>>** or from server to client **<<**.

Deleting selected files

The **Delete** buttons can be used to delete the selected files from server or client.

Refreshing content

Pressing the **Refresh** button updates the content.

 © 2020 SEGGER Microcontroller GmbH

Closing the file transfer window

Pressing <ESC> or the **Close** button

 © 2020 SEGGER Microcontroller GmbH

36.3 emWin VNC server

36.3.1 Starting the emWin VNC server

The one and only thing to start the VNC server is to call the function GUI_VNC_X_StartServer():

```
void MainTask(void) {
  GUI_Init();
  GUI_VNC_X_StartServer(0,   // Layer index
                        0);  // Server index
  ...
}
```

The above function call creates a thread which listens on port 5900 for an incoming connection. After a connection has been detected GUI_VNC_Process() will be called.

Ports

The VNC server listens on port 590x, where x is the server index. So for most PC servers, the port will be 5900, because they use display 0 by default.

36.3.2 Enabling file transfer support

File transfer is enabled by calling GUI_VNC_X_StartServerFT() instead of GUI_VNC_X_StartServer(). In addition to the task of starting the VNC-thread it sets an API-table containing function pointers for file access. Further it enables the RFB protocol extensions required for file transfers.

36.3.3 Starting the VNC server in the simulation

The simulation library contains a ready to use implementation of the function GUI_VNC_X_StartServer() which simply needs to be called by the application code. It creates a thread which listens on port 590x until an incoming connection is detected and then calls GUI_VNC_Process(), which is the implementation of the actual server.

36.3.4 Example of starting the VNC server on the target system

To be able to use the VNC server on the target it is required to have an implementation of GUI_VNC_X_StartServer() or GUI_VNC_X_StartServerFT() which works with the available IP library and in case of using file transfer also with the available file system. A ready to use implementation of that function which works with embOS/IP and emFile is available under Sample\GUI_X\GUI_VNC_X_StartServer.c. Since this example does not use dynamic memory allocation to allocate memory for the GUI_VNC_CONTEXT structure, this implementation allows starting only one server.
This sample could also be used as starting point for adapting it to other libraries than embOS/IP and emFile. Only small changes should be required in that case.

 © 2020 SEGGER Microcontroller GmbH

36.4 RAM and ROM requirements

ROM

About 4.9 KB on ARM7 with hextile encoding, about 3.5 KB without hextile encoding.

RAM

The VNC support does not use static data. For each instance one `GUI_VNC_CONTEXT` structure (approx. 60 bytes) is used.

Others

Each instance needs one TCP/IP socket and one thread.

 © 2020 SEGGER Microcontroller GmbH

36.5 VNC Server API

The following table lists the available VNC-related functions in alphabetical order. Detailed function descriptions follow:

Functions

Routine	Description
GUI_VNC_AttachToLayer()	Attaches a VNC server to a layer. Without a MultiLayer configuration the given index must be 0.
GUI_VNC_EnableFileTransfer()	Enables file transfer extension.
GUI_VNC_EnableKeyboardInput()	Enables or disables keyboard input via VNC.
GUI_VNC_GetNumConnections()	Returns the number of connections to the server.
GUI_VNC_Process()	The actual VNC server; initializes the communication with the viewer.
GUI_VNC_RingBell()	Rings a bell on the client if it has one.
GUI_VNC_SetFS_API()	Sets a function table used for file access.
GUI_VNC_SetLockFrame()	Configures the VNC server not to read the display while the GUI performs drawing operations.
GUI_VNC_SetPassword()	Sets the password required to connect with the server.
GUI_VNC_SetProgName()	Sets the text to be shown in the viewers title bar.
GUI_VNC_SetRetryCount()	Sets the number of additional trials in case of a write error.
GUI_VNC_SetSize()	Sets the area to be transmitted to the client.
GUI_VNC_X_StartServer()	Routine to be called to start a thread listening for an incoming connection and executing the VNC server.
GUI_VNC_X_StartServerFT()	Same as above with file transfer support.

Data structures

Structure	Description
IP_FS_API	Table containing the function pointers for file access.

 © 2020 SEGGER Microcontroller GmbH

36.5.1 Functions

36.5.1.1 GUI_VNC_AttachToLayer()

Description

This function attaches the given layer to the VNC server.

Prototype

```
void GUI_VNC_AttachToLayer(GUI_VNC_CONTEXT * pContext,
                           int               LayerIndex);
```

Parameters

Parameter	Description
pContext	Pointer to a GUI_VNC_CONTEXT structure.
LayerIndex	Zero-based index of layer to be handled by the server. Normally, with single layer configurations, this parameter should be 0.

Return value

= 0 if the function succeed
≠ 0 if the function fails.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.2 GUI_VNC_EnableFileTransfer()

Description

Enables or disables the file transfer extension.

Prototype

```
void GUI_VNC_EnableFileTransfer(unsigned OnOff);
```

Parameters

Parameter	Description
OnOff	1 for enabling keyboard input, 0 for disabling.

Return value

= 0 if the function succeeds.
≠ 0 if the function fails.

Additional information

This routine needs to be called by GUI_VNC_X_StartServerFT() for enabling file transfer in the protocoll. Please also refer to the sample code under Sample\GUI_X\GUI_VNC_X_StartServer.c which shows how to enable file transfer on the target.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.3 GUI_VNC_EnableKeyboardInput()

Description

Enables or disables keyboard input via VNC.

Prototype

```
void GUI_VNC_EnableKeyboardInput(int OnOff);
```

Parameters

Parameter	Description
OnOff	1 for enabling keyboard input, 0 for disabling.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.4 GUI_VNC_GetNumConnections()

Description

Returns the number of currently existing connections to the server.

Prototype

```
int GUI_VNC_GetNumConnections(void);
```

Return value

Number of connections.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.5 GUI_VNC_Process()

Description

The function sets the send and receive function used to send and receive data and starts the communication with the viewer.

Prototype

```
int GUI_VNC_Process(GUI_VNC_CONTEXT * pContext,
                    GUI_tSend         pfSend,
                    GUI_tRecv         pfReceive,
                    void            * pConnectInfo);
```

Parameters

Parameter	Description
pContext	Pointer to a GUI_VNC_CONTEXT structure.
pfSend	Pointer to the function to be used by the server to send data to the viewer.
pfReceive	Pointer to the function to be used by the server to read from the viewer.
pConnectInfo	Pointer to be passed to the send and receive function.

Additional information

The GUI_VNC_CONTEXT structure is used by the server to store connection state information. The send and receive functions should return the number of bytes successfully send/received to/from the viewer. The pointer pConnectInfo is passed to the send and receive routines. It can be used to pass a pointer to a structure containing connection information or to pass a socket number. The following types are used as function pointers to the routines used to send and receive bytes from/to the viewer:

```
typedef int (* GUI_tSend) (const U8 * pData,
             int                     len,
             void                  * pConnectInfo);

typedef int (* GUI_tReceive) (U8 * pData,
             int                   len,
             void                * pConnectInfo);
```

Example

```
static GUI_VNC_CONTEXT _Context; /* Data area for server */
static int _Send(const U8* buf, int len, void * pConnectionInfo) {
  SOCKET Socket = (SOCKET)pConnectionInfo;
 ...
}
static int _Recv(U8* buf, int len, void * pConnectionInfo) {
  SOCKET Socket = (SOCKET)pConnectionInfo;
  ...
}
static void _ServerTask(void) {
  int Socket;
  ...
  GUI_VNC_Process(&_Context, _Send, _Recv, (void *)Socket);
  ...
}
```

 © 2020 SEGGER Microcontroller GmbH

36.5.1.6 GUI_VNC_RingBell()

Description

Ring a bell on the client if it has one.

Prototype

```
void GUI_VNC_RingBell(void);
```

 © 2020 SEGGER Microcontroller GmbH

36.5.1.7 GUI_VNC_SetFS_API()

> **Note**
>
> The following description of the IP_FS_API structure is an excerpt of the document **UM07001 User & Reference Guide for embOS/IP** which is also available separately on www.segger.com.

Description

Sets a function table used for accessing files.

Prototype

```
void GUI_VNC_SetFS_API(const IP_FS_API * pFS_API);
```

Parameters

Parameter	Description
pFS_API	Pointer to an IP_FS_API structure containing function pointers for file access.

Additional information

This routine needs to be called by GUI_VNC_X_StartServerFT() for enabling file transfer in the protocol. Please also refer to the sample code under Sample\GUI_X\GUI_VNC_X_StartServer.c which shows how to enable file transfer on the target.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.8 GUI_VNC_SetLockFrame()

Description

Configures the VNC server not to read the display while the GUI performs drawing operations.

Prototype

```
void GUI_VNC_SetLockFrame(unsigned OnOff);
```

Parameters

Parameter	Description
OnOff	If set to a value >0 frame locking will be enabled. Default is enabled frame locking.

Additional information

This can be configured at compile time by using the compile time switch GUI_VNC_LOCK_FRAME.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.9 GUI_VNC_SetPassword()

Description

Sets a password required to connect to the server.

Prototype

```
void GUI_VNC_SetPassword(U8 * sPassword);
```

Parameters

Parameter	Description
sPassword	Password required to connect to the server.

Additional information

Per default no password is required. If a password is set the server creates a random challenge of 16 Bytes and encrypts it using DES. The unencrypted challenge is sent to the client and should return encrypted. If the client's response matches the encrypted challenge, authentification was successful.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.10 GUI_VNC_SetProgName()

Description

Sets the title to be displayed in the title bar of the client window.

Prototype

```
void GUI_VNC_SetProgName(const char * sProgName);
```

Parameters

Parameter	Description
sProgName	Title to be displayed in the title bar of the client window.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.11 GUI_VNC_SetRetryCount()

Description

Sets the number of additional trials in case of an error when trying to write data on the line.

Prototype

```
void GUI_VNC_SetRetryCount(unsigned Cnt);
```

Parameters

Parameter	Description
Cnt	Number of additional trials to be used in case of an error (default is 0).

 © 2020 SEGGER Microcontroller GmbH

36.5.1.12 GUI_VNC_SetSize()

Description

Sets the display size to be transmitted to the client.

Prototype

```
void GUI_VNC_SetSize(unsigned xSize,
                     unsigned ySize);
```

Parameters

Parameter	Description
xSize	X-size to be used.
ySize	Y-size to be used.

Additional information

Per default the server uses the layer size. The size passed to this function can be smaller or larger than the real display.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.13 GUI_VNC_X_StartServer()

Description

This function has to start a thread listening for an incoming connection. If a connection is established it has to execute the actual VNC server `GUI_VNC_Process()`. The function has to be supplied by the customer because the implementation depends on the used TCP/IP stack and on the used operating system. The emWin shipment contains an example implementation under `Sample\GUI_X\GUI_VNC_X_StartServer.c`. It could be used as a starting point for adapting it to other systems.

Prototype

```
int GUI_VNC_X_StartServer(int LayerIndex,
                          int ServerIndex);
```

Parameters

Parameter	Description
`LayerIndex`	Layer to be shown by the viewer.
`ServerIndex`	Server index.

Return value

Returns 0.

Additional information

There is no difference to start a VNC server in the simulation or on the target. In both cases you should call this function. The simulation contains an implementation of this function, the hardware implementation has to be done by the customer.

 © 2020 SEGGER Microcontroller GmbH

36.5.1.14 GUI_VNC_X_StartServerFT()

Description

Function which has to be implemented by the customer to start the VNC server with file transfer support. Additionally to starting a server thread the function has to enable the file transfer extensions by calling `GUI_VNC_EnableFileTransfer()` and it has to set a function table to be used for file access by `GUI_VNC_SetFS_API()`.

Prototype

```
int GUI_VNC_X_StartServerFT(int LayerIndex,
                            int ServerIndex);
```

Parameters

Parameter	Description
`LayerIndex`	Layer to be shown by the viewer.
`ServerIndex`	Server index.

Return value

Returns 0.

Additional information

Under `Sample\GUI_X\GUI_VNC_X_StartServer.c` a sample is available which shows a sample implementation using embOS/IP and emFile.

 © 2020 SEGGER Microcontroller GmbH

36.5.2 Data structures

36.5.2.1 IP_FS_API

Description

Table containing the function pointers for file access.

Type definition

```
typedef struct {
  void * (* pfOpenFile)             (const char  * sFilename,
                                     const char  * sOpenFlags            );
  int    (* pfCloseFile)            (      void  * hFile                );
  int    (* pfReadAt)               (      void  * hFile,
                                           void  * pBuffer,
                                           U32     Pos,
                                           U32     NumBytes             );
  long   (* pfGetLen)               (      void  * hFile                );
  void   (* pfForEachDirEntry)      (      void  * pContext,
                                     const char  * sDir,
                                           void (* pf) (void * pContext,
                                                        void * pFileEntry));
  void   (* pfGetDirEntryFileName)  (      void  * pFileEntry,
                                           char  * sFileName,
                                           U32     SizeOfBuffer         );
  U32    (* pfGetDirEntryFileSize)  (      void  * pFileEntry,
                                           U32   * pFileSizeHigh        );
  int    (* pfGetDirEntryFileTime)  (      void  * pFileEntry           );
  U32    (* pfGetDirEntryAttributes)(      void  * pFileEntry           );
  void * (* pfCreate)               (const char  * sFileName            );
  void * (* pfDeleteFile)           (const char  * sFilename            );
  int    (* pfRenameFile)           (const char  * sOldFilename,
                                     const char  * sNewFilename         );
  int    (* pfWriteAt)              (      void  * hFile,
                                           void  * pBuffer,
                                           U32     Pos,
                                           U32     NumBytes             );
  int    (* pfMKDir)                (const char  * sDirName             );
  int    (* pfRMDir)                (const char  * sDirName             );
  int    (* pfIsFolder)             (const char  * sPath                );
  int    (* pfMove)                 (const char  * sOldFilename,
                                     const char  * sNewFilename         );
} IP_FS_API;
```

Structure members

Function	Description
Read only file system functions (required)	
pfOpenFile	Pointer to a function that creates/opens a file and returns the handle of these file.
pfCloseFile	Pointer to a function that closes a file.
pfReadAt	Pointer to a function that reads a file.
pfGetLen	Pointer to a function that returns the length of a file.
Directory query operations	
pfForEachDirEntry	Pointer to a function which is called for each directory entry.
pfGetDirEntryFileName	Pointer to a function that returns the name of a file entry.
pfGetDirEntryFileSize	Pointer to a function that returns the size of a file.

 © 2020 SEGGER Microcontroller GmbH

Function	Description
pfGetDirEntryFileTime	Pointer to a function that returns the timestamp of a file.
pfGetDirEntryAttributes	Pointer to a function that returns the attributes of a directory entry.
Write file operations	
pfCreate	Pointer to a function that creates a file.
pfDeleteFile	Pointer to a function that deletes a file.
pfRenameFile	Pointer to a function that renames a file.
pfWriteAt	Pointer to a function that writes a file.
Additional directory operations (optional)	
pfMKDir	Pointer to a function that creates a directory.
pfRMDir	Pointer to a function that deletes a directory.
Additional operations (optional)	
pfIsFolder	Pointer to a function that checks if a path is a folder.
pfMove	Pointer to a function that moves a file or directory.

 © 2020 SEGGER Microcontroller GmbH

Chapter 37

Timing- and execution-related functions

Some widgets, as well as our demonstration code, require time-related functions. The other parts of the emWin graphic library do not require a time base.
The demonstration code makes heavy use of the routine `GUI_Delay()`, which delays for a given period of time. A unit of time is referred to as a tick.

 © 2020 SEGGER Microcontroller GmbH

37.1 Timing and execution API

The table below lists the available timing- and execution-related routines in alphabetical order. Detailed descriptions of the routines follow.

Routine	Description
GUI_Delay()	Delays for a specified period of time.
GUI_ErrorOut	Shows a message box and stops execution.
GUI_Exec()	Executes callback functions (typically redrawing of windows).
GUI_Exec1()	Executes a callback function (one job only; typically redrawing a window).
GUI_GetTime()	Returns the current system time.
GUI_GetTimeSlice()	Returns the currently set minimum time in milliseconds with which a GUI_X_Delay() will get called within GUI_Delay().
GUI_SetTimeSlice()	Sets the minimum time with which a GUI_X_Delay() gets called within GUI_Delay().

 © 2020 SEGGER Microcontroller GmbH

37.1.1 GUI_Delay()

Description

Delays for a specified period of time.

Prototype

```
void GUI_Delay(int Period);
```

Parameters

Parameter	Description
Period	Minimum period in ticks until function should return.

Additional information

The time unit (tick) is usually milliseconds (depending on GUI_X_ functions). GUI_Delay() only executes idle functions for the given period. If the Window Manager is used, the delay time is used for the updating of invalid windows (through execution of WM_Exec()). Please note that the given period is a minimum period. Larger drawing operations of the WM for example could take more time than the given period. This function will call GUI_X_Delay().

 © 2020 SEGGER Microcontroller GmbH

37.1.2 GUI_ErrorOut()

Description

This function is called by emWin in case of serious errors which causes the system to stop execution. It gets a pointer to a string which should contain a short error description. It should contain module and function where the error occurred and a short description. The simulation automatically shows a message box with error description in debug mode. To be able to intercept these major errors on the target system, the function `GUI_SetOnErrorFunc()` can be used to set up a custom routine which is called by `GUI_ErrorOut()`.

Prototype

```
void GUI_ErrorOut(const char * s);
```

Parameters

Parameter	Description
s	Error string which is passed on to the function `GUI_X_ErrorOut()` and to the user defined error handling function.

Additional information

Detailed information on how to set up a user defined error handling function can be found in the description of the function `GUI_SetOnErrorFunc()` in the chapter *Configuration* on page 2396.

 © 2020 SEGGER Microcontroller GmbH

37.1.3 GUI_Exec()

Description

Executes callback functions (typically redrawing of windows).

Prototype

```
int GUI_Exec(void);
```

Return value

0	if there were no jobs performed.
1	if a job was performed.

Additional information

This function will automatically call `GUI_Exec1()` repeatedly until it has completed all jobs —essentially until a 0 value is returned. Normally this function does not need to be called by the user application. It is called automatically by `GUI_Delay()`.

 © 2020 SEGGER Microcontroller GmbH

37.1.4 GUI_Exec1()

Description

Executes a callback function (one job only; typically redrawing a window).

Prototype

```
int GUI_Exec1(void);
```

Return value

0	if there were no jobs performed.
1	if a job was performed.

Additional information

This routine may be called repeatedly until 0 is returned, which means all jobs have been completed. This function is called automatically by `GUI_Exec()`.

 © 2020 SEGGER Microcontroller GmbH

37.1.5 GUI_GetTime()

Description

Returns the current system time.

Prototype

```
GUI_TIMER_TIME GUI_GetTime(void);
```

Return value

The current system time in ticks.

Additional information

This function calls `GUI_X_GetTime()`. `GUI_TIMER_TIME` is explained under ***GUI_TIMER_TIME***.

 © 2020 SEGGER Microcontroller GmbH

37.1.6 GUI_GetTimeSlice()

Description

Returns the currently set minimum time in milliseconds with which a `GUI_X_Delay()` will get called within `GUI_Delay()`.

Prototype

```
int GUI_GetTimeSlice(void);
```

Return value

Value set as time slice in ms.

Additional information

Prior to version 5.38 of emWin the minimum time a `GUI_Delay()` took was 5ms. With the function `GUI_SetTimeSlice()` the minimum time can be set.

 © 2020 SEGGER Microcontroller GmbH

37.1.7 GUI_SetTimeSlice()

Description

Sets the minimum time with which a `GUI_X_Delay()` gets called within `GUI_Delay()`.

Prototype

```
void GUI_SetTimeSlice(int TimeSlice);
```

Parameters

Parameter	Description
`TimeSlice`	Minimum time to be used within a `GUI_Delay()`.

Additional information

The default value for the minimum time is 5ms.

 © 2020 SEGGER Microcontroller GmbH

37.2 Timer API

The table below lists the available timer-related routines in alphabetical order. Detailed descriptions of the routines follow.

Routine	Description
GUI_TIMER_Create()	Creates a timer.
GUI_TIMER_Delete()	Deletes the given timer.
GUI_TIMER_Restart()	Restarts the given timer.
GUI_TIMER_SetPeriod()	Sets the timer period.

 © 2020 SEGGER Microcontroller GmbH

37.2.1 GUI_TIMER_Create()

Description

Creates a timer. When the timer expires the timer callback function is called.

Prototype

```
GUI_TIMER_HANDLE GUI_TIMER_Create(GUI_TIMER_CALLBACK * cb,
                                  GUI_TIMER_TIME       Time,
                                  PTR_ADDR             Context,
                                  U16                  Flags);
```

Parameters

Parameter	Description
cb	Pointer to the user defined timer callback function which is called when the timer expires. Prototype is shown below.
Time	Destination time. The created timer expires when the system time exceeds this value.
Context	Timer context which is returned unchanged via timer callback function.
Flags	Not used. Reserved for future use.

GUI_TIMER_CALLBACK

```
typedef void GUI_TIMER_CALLBACK(GUI_TIMER_MESSAGE * pTM);
```

Parameter	Description
pTM	Pointer to a GUI_TIMER_MESSAGE structure which is explained below. Changes which are done from within the callback function are not applied. In order to have another context, a new timer should be created.

Elements of structure GUI_TIMER_MESSAGE

Data type	Element	Description
GUI_TIMER_TIME	Time	Contains the time value when the timer expired.
U32	Context	User defined context value which was specified at creation of the timer.
GUI_TIMER_HANDLE	hTimer	Handle of the expired timer.

GUI_TIMER_TIME

This define can be set to the desired type in the file GUIConf.h. The default type is int.

> **Note**
>
> The data type must be signed.

Return value

Handle to the created timer. 0, if no timer was created.

Additional information

Timers are not deleted automatically. To delete a timer the function GUI_TIMER_Delete() can be used. Restarting a timer can be achieved with GUI_TIMER_Restart().

 © 2020 SEGGER Microcontroller GmbH

37.2.2 GUI_TIMER_Delete()

Description

Deletes the given timer.

Prototype

```
void GUI_TIMER_Delete(GUI_TIMER_HANDLE hObj);
```

Parameters

Parameter	Description
hObj	Timer handle.

Return value

Handle to the created timer. 0, if no timer was created.

Additional information

Timers are deleted immediately. After deleting a timer the according callback function will not be triggered.

 © 2020 SEGGER Microcontroller GmbH

37.2.3 GUI_TIMER_Restart()

Description

Restarts the given timer.

Prototype

```
void GUI_TIMER_Restart(GUI_TIMER_HANDLE hObj);
```

Parameters

Parameter	Description
hObj	Timer handle.

 © 2020 SEGGER Microcontroller GmbH

37.2.4 GUI_TIMER_SetPeriod()

Description

Sets the timer period. The period defines the time which has to pass until the callback function is triggered again.

Prototype

```
void GUI_TIMER_SetPeriod(GUI_TIMER_HANDLE hObj,
                         GUI_TIMER_TIME   Period);
```

Parameters

Parameter	Description
hObj	Timer handle.
Period	Timer period.

Additional information

This period is used only when the timer is restarted.

 © 2020 SEGGER Microcontroller GmbH

Chapter 38

Performance and Resource Usage

High performance combined with low resource usage has always been a major design consideration. emWin runs on 8/16/32-bit CPUs. Depending on which modules are being used, even single-chip systems with less than 64 KB ROM and 2 KB RAM can be supported by emWin. The actual performance and resource usage depends on many factors (CPU, compiler, memory model, optimization, configuration, display controller interface, etc.). This chapter contains benchmarks and information about resource usage in typical systems which can be used to obtain sufficient estimates for most target systems.

 © 2020 SEGGER Microcontroller GmbH

38.1 Performance

The following chapter shows driver benchmarks on different targets and performance values of image drawing operations.

38.1.1 Driver benchmark

We use a benchmark test to measure the speed of the display drivers on available targets. This benchmark is in no way complete, but it gives an approximation of the length of time required for common operations on various targets.

Configuration and performance table

CPU	LCD Controller (GUIDRV_...)	bpp	Bench1 Filling	Bench2 Small fonts	Bench3 Bit fonts	Bench4 Bitmap 1bpp	Bench5 Bitmap 2bpp	Bench6 Bitmap 4bpp	Bench7 Bitmap 8bpp	Bench8 DDP bitmap
ARM Cortex-A9										
RZA1 (360MHz)	(internal) ...LIN16	16	335M	15.9M	21.8M	32.6M	21.2M	19.8M	10.0M	62.4M
RZA1 (360MHz)	(internal) ...LIN32	32	182M	14.0M	20.3M	25.7M	24.2M	22.7M	12.7M	69.1M
ARM Cortex-M4										
ST-M32F429 (168MHz)	(internal) ...LIN8	8	182M	2.74M	3.67M	5.67M	2.02M	1.94M	2.30M	21.4M
ST-M32F429 (168MHz)	(internal) ...LIN16	16	131M	3.65M	5.19M	7.68M	4.08M	3.89M	20.64M	25.59M
ST-M32F429 (168MHz)	(internal) ...LIN32	32	67.7M	3.65M	5.22M	7.80M	5.68M	5.14M	20.98M	20.11M
ST-M32F407 (168MHz)	(external) FLEXCOLOR *1	16	5.9M	1.14M	1.75M	2.52M	2.04M	1.94M	1.14M	5.67M
MK66FN2 (168MHz)	(external) FLEXCOLOR *2	16	981.35K	504.36K	564.5K	635.68K	616.09K	604.03K	560.38K	876.54K
ARM720T										
ARM720T (50MHz)	(internal) (3200)	16	7.14M	581K	1.85M	1.96M	694K	645K	410K	2.94M
ARM9										
AR-M926EJ-S (200MHz)	(internal) (3200)	16	123M	3.79M	5.21M	7.59M	2.27M	2.21M	1.77M	15.2M

Legend

- **M** - Megapixels per second
- **K** - Kilopixels per second
- *1 - 16 bit parallel interface
- *2 - 8 bit serial interface

 © 2020 SEGGER Microcontroller GmbH

Bench1: Filling

Bench the speed of filling. An area of 64×64 pixels is filled with different colors.

Bench2: Small fonts

Bench the speed of small character output. An area of 60×64 pixels is filled with small-character text.

Bench3: Big fonts

Bench the speed of big character output. An area of 65×48 pixels is filled with big-character text.

Bench4: Bitmap 1bpp

Bench the speed of 1bbp bitmaps. An area of 58×8 pixels is filled with a 1bpp bitmap.

Bench 5: Bitmap 2bpp

Bench the speed of 2bbp bitmaps. An area of 32×11 pixels is filled with a 2bpp bitmap.

Bench6: Bitmap 4bpp

Bench the speed of 4bbp bitmaps. An area of 32×11 pixels is filled with a 4bpp bitmap.

Bench7: Bitmap 8bpp

Bench the speed of 8bbp bitmaps. An area of 32×11 pixels is filled with a 8bpp bitmap.

Bench8: Device-dependent bitmap, 8 or 16 bpp

Bench the speed of bitmaps 8 or 16 bits per pixel. An area of 64 pixels is filled with a bitmap. The color depth of the tested bitmap depends on the configuration. For configurations ≤ 8bpp, a bitmap with 8 bpp is used; 16bpp configurations use a 16-bpp bitmap.

38.1.2 Image drawing performance

The purpose of the following table is to show the drawing performance of the various image formats supported by emWin. The measurement for the following table has been done on an ARM Cortex-A9 (RZA1H) running with 360MHz and with 16bpp display color depth using `GUIDRV_LIN_16`:

Image format	Megapixels per second
Internal bitmap format: 1bpp C file	47.5
Internal bitmap format: 4bpp C file	27.5
Internal bitmap format: 8bpp C file	41.6
Internal bitmap format: 16bpp C file, high color	103
Internal bitmap format: 24bpp C file, true color 888	8.0
Internal bitmap format: RLE4 C file	14.5
Internal bitmap format: RLE8 C file	16.4
Internal bitmap format: RLE16 C file	10.3
BMP file 8bpp	44.6
BMP file 16bpp	4.6
BMP file 24bpp	5.7
BMP file 32bpp	5.6
BMP file RLE4	32.9
BMP file RLE8	23.2

 © 2020 SEGGER Microcontroller GmbH

Image format	Megapixels per second
GIF file	4.1
JPEG file, H1V1	1.3
JPEG file, H1V1, progressive	1.1
JPEG file, H2V2	1.8
JPEG file, H2V2, progressive	1.5

 © 2020 SEGGER Microcontroller GmbH

38.2 Memory requirements

The operation area of emWin varies widely, depending primarily on the application and features used. In the following sections, memory requirements of different modules are listed as well as memory requirement of example applications. The memory requirements of the GUI components have been measured on a system as follows:

- ARM7
- IAR Embedded Workbench V4.42A
- Thumb mode
- Size optimization

38.2.1 Memory requirements of the GUI components

The following table shows the memory requirements of the main components of emWin. These values depend a lot on the compiler options, the compiler version and the used CPU. Note that the listed values are the requirements of the basic functions of each module and that there are several additional functions available which have not been considered in the table:

Component	ROM	RAM	Description
Window Manager	+ 6.2 KB	+ 2.5 KB	Additional memory requirements of a 'Hello world' application when using the Window Manager.
Memory Devices	+ 4.7 KB	+ 7 KB	Additional memory requirements of a 'Hello world' application when using Memory Devices.
Antialiasing	+ 4.5 KB	+ 2 × LCD_XSIZE	Additional memory requirements for the anti-aliasing software item.
Driver	+ 2 - 8 KB	20 Bytes	The memory requirements of the driver depend on the configured driver and if a data cache is used or not. With a data cache, the driver requires more RAM. For details, refer to the chapter *Display drivers* on page 2608.
MultiLayer	+ 2 - 8 KB	-	If working with a MultiLayer or a Multi-Display configuration additional memory for each additional layer is required, because each layer requires its own driver.
Core	5.2 KB	80 Bytes	Memory requirements of a typical 'Hello world' application without using additional software items.
Core / JPEG	12 KB	38 KB	Basic routines for drawing JPEG files.
Core / GIF	3.3 KB	17 KB	Basic routines for drawing GIF files.
Core / Sprites	4.7 KB	16 Bytes	Routines for drawing sprites and cursors.
Core / Fonts	(see description)	-	Details of the ROM requirements of the standard fonts shipped with emWin can be found in the chapter *Fonts* on page 463.
Widgets	4.5 KB	-	This is the approximately basic ROM requirement for the widgets depending on the individual core functions used by the widgets.
Widget / BUTTON	1 KB	40 Bytes	*1

 © 2020 SEGGER Microcontroller GmbH

Component	ROM	RAM	Description
Widget / CHECKBOX	1 KB	52 Bytes	*1
Widget / DROPDOWN	1.8 KB	52 Bytes	*1
Widget / EDIT	2.2 KB	28 Bytes	*1
Widget / FRAMEWIN	2.2 KB	12 Bytes	*1
Widget / GRAPH	2.9 KB	48 Bytes	*1
Widget / GRAPH_DATA_XY	0.7 KB	-	*1
Widget / GRAPH_DATA_YT	0.6 KB	-	*1
Widget / HEADER	2.8 KB	32 Bytes	*1
Widget / LISTBOX	3.7 KB	56 Bytes	*1
Widget / LISTVIEW	3.6 KB	44 Bytes	*1
Widget / MENU	5.7 KB	52 Bytes	*1
Widget / MULTIEDIT	7.1 KB	16 Bytes	*1
Widget / MULTIPAGE	3.9 KB	32 Bytes	*1
Widget / PROGBAR	1.3 KB	20 Bytes	*1
Widget / RADIOBUTTON	1.4 KB	32 Bytes	*1
Widget / SCROLLBAR	2 KB	14 Bytes	*1
Widget / SLIDER	1.3 KB	16 Bytes	*1
Widget / TEXT	0.4 KB	16 Bytes	*1

Legend

1. The listed memory requirements of the widgets contain the basic routines required for creating and drawing the widget. Depending on the specific widget there are several additional functions available which are not listed in the table.

38.2.2 Stack requirements

The basic stack requirement is approximately 600 bytes. If using the Window Manager additional 600 bytes should be calculated. For Memory Devices further additional 200 bytes are recommended. Please note that the stack requirement also depends on the application, the used compiler and the CPU.

 © 2020 SEGGER Microcontroller GmbH

38.3 Memory requirements of example applications

This section shows the requirements of some example applications. The following table contains the summary of the memory requirements. The values are in bytes unless specified other:

Example	GUI core	Fonts	Application	Startup code	Library	Total	GUI core	Application	Stack	Total
	ROM						RAM			
Hello world	5.9 kB	1.8 kB	38 B	0.3 kB	0.1 kB	**8.1 kB**	62 B	-	272 B	**334 B**
Window application	43 kB	12.5 kB	2.7 kB	0.3 kB	1.5 kB	**60 kB**	5.2 kB	40 B	1.4 kB	**6.6 kB**

For details about the examples, refer to the following sections.

 © 2020 SEGGER Microcontroller GmbH

38.4 Optimizing Footprint

The amount of RAM and ROM required by emWin could be optimized in some cases. This chapter shows when it is possible to spare some RAM and/or ROM and how that could be achieved.

38.4.1 Optimizing RAM requirement

In general the application should not allocate much more memory as required by the application. But unfortunately it is not possible providing a simple formula which can be used for that. If the simulation is used it is possible to open a window which shows the current amount of used/free memory of the executing application by right-clicking the simulation window. For details please also refer to *View system info* on page 114. All of the below shown RAM optimizations can be done with a precompiled library.

Systems using bitmaps with less than 256 colors

If less than 256 colors are used by bitmaps the size of the buffer required for bitmap palette conversion could be reduced. Per default palettes with up to 256 colors can be converted. That requires 256 × 4 = 1024 bytes. If the bitmaps used by the application use less than 256 colors the size of the buffer could be reduced. That could be done by calling the function `LCD_SetMaxNumColors()` with the maximum number of colors used by bitmaps. Details can be found in the description of *`LCD_SetMaxNumColors`* on page 2813.

Systems using a display driver with indirect interface

If the system is short on RAM and a driver with indirect interface is used it is recommended not to use a display driver cache. If the display controller supports reading back frame buffer data it should be possible to use the driver without a cache. Details about cache configuration can be found in the respective display driver description.

Systems using multi tasking support (GUI_OS == 1)

If multiple tasks are configured emWin uses a maximum of 4 tasks per default. That requires approx. 110 bytes per task which makes 4 × 110 = 440 bytes. If less than 4 GUI-tasks are used that can be done by fine tuning the maximum number of tasks by calling the function `GUITASK_SetMaxTask()` from `GUI_X_Config()`. For details please also refer to the function *`GUITASK_SetMaxTask`* on page 2884.

38.4.2 Optimizing ROM requirement

In general here can not be done much on emWin side. But may some features could be disabled which spare a few KByte of ROM requirement. The below shown optimizations can only be done when compiling the source code of emWin.

Using the Window Manager without transparent windows

If the application does not require transparent windows the source of emWin can be compiled with the following option set in the configuration file `GUIConf.h`:

```
#define WM_SUPPORT_TRANSPARENCY 0
```

Disable text rotation

If the application does not use the functions for drawing rotated text the code required for that operations can be disabled by inserting the following define in the configuration file `GUIConf.h`:

```
#define GUI_SUPPORT_ROTATION 0
```

 © 2020 SEGGER Microcontroller GmbH

38.4.3 Features with appreciable additional RAM requirement

The following table shows the features requiring additional RAM:

Module	Description
Language module (GUI_LANG_...)	The amount of additional RAM requirement depends on the kind of use of the language model and on the size of the text files used.
Alpha blending	If alpha blending is used the module automatically allocates 3 buffers with the maximum virtual display size in x and a color depth of 32 bpp.
Orientation device	If a driver does not support changing the display orientation the orientation device could be used. But please note that this device uses a much memory as required to hold a copy of the complete frame buffer.

This table does not contain the RAM requirement of each single module but shows the most appreciable ones.

 © 2020 SEGGER Microcontroller GmbH

Chapter 39

Configuration

Before emWin can be used on a target system, the software needs to be configured. Configuring means modifying the configuration files which usually reside in the (sub)directory `Config`. We try to keep the configuration as simple as possible, but there are some configuration routines which need to be modified in order for the system to work properly.
The following items need to be configured:

- Memory area to be used by emWin
- Display driver to be used for drawing operations
- Color conversion routines to be used
- Display controller initialization
- Hardware acceleration
- Hardware JPEG decoding

The following chapter explains the configuration of emWin in detail.

 © 2020 SEGGER Microcontroller GmbH

39.1 What needs to be configured?

The configuration is basically divided into two parts: GUI-configuration and LCD-configuration. GUI-configuration means configuration of available features, default colors and -fonts and the configuration of available memory. The LCD-configuration is more hardware dependent and has to define the physical size of the display, the display driver and the color conversion routines to be used. For details about color conversion routines, refer to the chapter *Colors* on page 617.
If a hardware is used which offers acceleration features as for example available with the ChromeART accelerator of some of the STM32 devices, the chapter *Hardware acceleration* on page 2903 contains more information.
A further part is configuring the simulation. But this is not required for the target hardware and not part of this chapter. For details about configuring the simulation, refer to the chapter *Simulation* on page 109.

 © 2020 SEGGER Microcontroller GmbH

39.2 Run-time- and compile-time configuration

There are C and include files to be configured. The configuration in the header files is fixed at compile time and can not be changed whereas the configuration done in the C files can be changed at run-time. This makes it possible to create a library which is largely configuration independent and can be used with any display and any driver. This requires that the configuration routines described in this chapter are not part of the library but of the application.

 © 2020 SEGGER Microcontroller GmbH

39.3 Initialization process of emWin

The illustration shows the process of initialization. To initialize emWin, the application only has to call `GUI_Init()`. The configuration routines explained below are called during the internal initialization process.



GUI_X_Config()

It is called at the very first beginning of the initialization process to make sure that memory is assigned to emWin. Within this routine `GUI_ALLOC_AssignMemory()` must be called to assign a memory block to emWin. The functions are explained later in this chapter.

LCD_X_Config()

This function is called immediately after `GUI_X_Config()`. The main purpose of this routine is creating a display driver device and selecting the color conversion routines. Further it is responsible for setting the display size. If a touch screen is used it should also be configured here.

LCD_X_DisplayDriver()

At a later point of the initialization process the function `LCD_X_DisplayDriver()` is called. It is called directly by the display driver. During the initialization process the task of this routine is putting the display controller into operation. A detailed description of the routine follows later in this chapter.

 © 2020 SEGGER Microcontroller GmbH

39.4 Run-time configuration

The following table shows the available run-time configuration files located in the subfolder `Config`:

Configuration file	Purpose
`GUIConf.c`	Configuration of available memory.
`LCDConf.c`	Configuration of the display size, the display driver and the color conversion routines.
`SIMConf.c`	Configuration of the simulation (not part of this chapter).
`GUI_X.c`	Configuration of timing routines.

39.4.1 Customizing GUIConf.c

The purpose of this module is to provide emWin with the function `GUI_X_Config()` which is responsible for assigning a memory block to the memory management system. This requires knowledge about the memory requirement of the used components. The separate chapter Performance and Resource Usage contains a detailed description of the memory requirements (RAM and ROM) of the individual emWin modules.
Per default GUIConf.c is located in the (sub)directory and contains the routine `GUI_X_Config()` which is responsible to assign a memory block to emWin. It is not cogently required to leave it in the file `GUIConf.c`. The routine `GUI_X_Config()` can be located anywhere in the application.
Calling this function is the very first thing done during the process of initialization. It is responsible to assign a memory block to emWin. This block is managed by the internal memory management system. Please also refer to `GUI_ALLOC_AssignMemory()`.

39.4.1.1 API functions to be used in GUI_X_Config()

The following table shows the API functions which must be called within `GUI_X_Config()`:

Routine	Description
`GUI_ALLOC_AssignMemory()`	The function assigns the one and only memory block to emWin which is used by the internal memory management system.
`GUI_RegisterAfterInitHook()`	Registers a hook function which gets called after the GUI has been initialized.
`GUI_SetOnErrorFunc()`	Sets the hook function which is called from `GUI_ErrorOut()`.
`GUITASK_GetMaxTask()`	Returns the maximum number of possible tasks when multitasking is enabled.
`GUITASK_SetMaxTask()`	Sets the maximum number of tasks from which emWin can be accessed when multitasking is enabled.

 © 2020 SEGGER Microcontroller GmbH

39.4.1.1.1 GUI_ALLOC_AssignMemory()

Description

The function assigns the one and only memory block to emWin which is used by the internal memory management system. This function should be called typically from `GUI_X_Config()`.

Prototype

```
void GUI_ALLOC_AssignMemory(void * p,
                            U32    NumBytes);
```

Parameters

Parameter	Description
p	Pointer to the memory block which should be used by emWin.
NumBytes	Size of the memory block in bytes.

Additional information

Note that not the complete memory block can be used by the application, because a small overhead is used by the management system itself. Each memory block requires approximately 12 additional bytes for management purpose. The assigned memory block needs to be accessible 8, 16 and 32 bit wise. It is used by emWin internally for memory allocation. Instead of using malloc() and free() the internal memory management uses that block for memory allocation. It is not used as frame buffer.

 © 2020 SEGGER Microcontroller GmbH

39.4.1.1.2 GUI_RegisterAfterInitHook()

Description

Registers a hook function which gets called after the GUI has been initialized.

Prototype

```
void GUI_RegisterAfterInitHook(void                ( *pFunc)(),
                               GUI_REGISTER_INIT * pRegisterInit);
```

Parameters

Parameter	Description
pFunc	Pointer to a function to be called.
pRegisterInit	Pointer to a GUI_REGISTER_INIT structure.

Additional information

It is possible to set multiple function to be called after the GUI has been initialized. This requires a dedicated GUI_REGISTER_INIT structure for each function.

```
static void _Init0(void) {
}
static void _Init1(void) {
}
void GUI_X_Config(void) {
static GUI_REGISTER_INIT RegisterInit0;
static GUI_REGISTER_INIT RegisterInit1;

static U32 aMemory[GUI_NUMBYTES / 4];
GUI_ALLOC_AssignMemory(aMemory, GUI_NUMBYTES);
GUI_SetDefaultFont(&GUI_Font6x8);
GUI_RegisterAfterInitHook(_Init0, &RegisterInit0);
GUI_RegisterAfterInitHook(_Init1, &RegisterInit1);
}
```

 © 2020 SEGGER Microcontroller GmbH

39.4.1.1.3 GUI_SetOnErrorFunc()

Description

Sets the hook function which is called from `GUI_ErrorOur()`.

Prototype

```
void GUI_SetOnErrorFunc(void ( *pFunc)(const char * s ));
```

Parameters

Parameter	Description
pFunc	Pointer to the function which should be called by `GUI_ErrorOut()`.

Additional information

The hook function gets a short error description in the string passed to the routine. It should contain the module and the function where the error occurred and a short description. See also the description of `GUI_ErrorOut()`.

 © 2020 SEGGER Microcontroller GmbH

39.4.1.1.4 GUITASK_GetMaxTask()

Description

Returns the maximum number of possible tasks when multitasking is enabled.

Prototype

```
int GUITASK_GetMaxTask(void);
```

Return value

Maximum number of possible tasks.

 © 2020 SEGGER Microcontroller GmbH

39.4.1.1.5 GUITASK_SetMaxTask()

Description

Sets the maximum number of tasks from which emWin can be accessed when multitasking is enabled.

Prototype

```
void GUITASK_SetMaxTask(int MaxTask);
```

Parameters

Parameter	Description
MaxTask	Number of tasks from which emWin is used at most.

Additional information

This function is intended to be called from GUI_X_Config(). It is necessary to use this function when working with a pre-compiled library. Otherwise GUI_MAXTASK can be defined. Further information can be found under *GUI_MAXTASK* on page 769.

 © 2020 SEGGER Microcontroller GmbH

39.4.2 Customizing LCDConf.c

The purpose of this module is to provide emWin with the required display configuration routine and the callback function for the display driver. These are the following functions:

Routine	Description
LCD_X_Config()	Configuration routine for creating the display driver device, setting the color conversion routines and the display size.
LCD_X_DisplayDriver()	Callback routine called by the display driver for putting the display controller into operation.

 © 2020 SEGGER Microcontroller GmbH

39.4.2.1 LCD_X_Config()

Description

As described in the table above this routine is responsible to create a display driver device, set the right color conversion routines and for configuring the physical display size.

Prototype

```
void LCD_X_Config(void);
```

Additional information

Depending on the used display driver it could also be required to set the video RAM address, initialize a custom palette or some else. For information about any additional requirements, refer to *Detailed display driver descriptions* on page 2643. The functions available for configuration purpose in this routine are listed and explained later in this chapter.

Example

The following shows a typical example implementation:

```
//
// Set display driver and color conversion for 1st layer
//
GUI_DEVICE_CreateAndLink(GUIDRV_LIN_16, GUICC_565, 0, 0);
//
// Display driver configuration
//
LCD_SetSizeEx    (0, 320, 240);
LCD_SetVSizeEx   (0, 320, 240);
LCD_SetVRAMAddrEx(0, (void *)0x200000);
```

 © 2020 SEGGER Microcontroller GmbH

39.4.2.2 LCD_X_DisplayDriver()

Description

This is the callback function of the display driver. It is called by the display driver for several jobs. It passes a command and a pointer to a data structure to the callback routine. The command tells the callback function what should be done. If the command requires parameters they are passed through the data pointer `pData`. It points to a structure whose format depends on the command.

Prototype

```
int LCD_X_DisplayDriver(unsigned LayerIndex,
                        unsigned Cmd,
                        void   * pData);
```

Parameters

Parameter	Description
`LayerIndex`	Zero based layer index.
`Cmd`	Command to be executed. Detailed descriptions below.
`pData`	Pointer to a data structure.

Elements of structure LCD_X_SETVRAMADDR_INFO

Data type	Element	Description
`void *`	`pVRAM`	Pointer to the start address of the video RAM.

Return value

= 0 Command has been successfully executed.
= -1 Command is not handled by the function.
= -2 Error occured.

Additional information

For more information about the commands passed to the routine by the display driver, refer to *Display drivers* on page 2608.

Examples

The folder `Sample\LCDConf` contains a lot of example implementations of this routine which can be used as starting point.

 © 2020 SEGGER Microcontroller GmbH

39.4.2.3 API functions to be used in LCD_X_Config()

The following table shows the API functions which are available for configuration purpose within `LCD_X_Config()`:

Routine	Description
`GUI_DEVICE_CreateAndLink()`	Creates a display driver device and associates the color conversion routines to be used.
`GUI_TOUCH_SetOrientation()`	The function configures the touch screen orientation.
`GUI_TOUCH_Calibrate()`	Changes the calibration at runtime.
`LCD_SetLUTEx()`	Sets the look-up table for the given layer.
`LCD_SetSizeEx()`	Sets the physical size of the visible area of the given display/layer.
`LCD_SetVRAMAddrEx()`	Sets the address of the video RAM.
`LCD_SetVSizeEx()`	Sets the size of the virtual display area.

Aside from the function `LCD_SetLUTEx()` the descriptions of the `LCD_…()` functions can be found in the chapter *Display drivers* on page 2608.

The descriptions of the `GUI_TOUCH_…()` functions can be found in the chapter *Touch screen driver* on page 2446.

 © 2020 SEGGER Microcontroller GmbH

39.4.2.3.1 GUI_DEVICE_CreateAndLink()

Description

This routine creates the display driver device, sets the color conversion routines to be used for accessing the display and it links the driver device into the device list of the given layer. `LCD_X_Config()` is called immediately after `GUI_X_Config()`. This makes sure that the memory configuration already has been done and the driver is able to allocate memory. The required memory for a display driver device is approx. 50 bytes + the driver specific memory. For details about the memory requirements of the individual display drivers, refer to the chapter *Display drivers* on page 2608.

Prototype

```
GUI_DEVICE *GUI_DEVICE_CreateAndLink(const GUI_DEVICE_API     * pDeviceAPI,
                                     const LCD_API_COLOR_CONV * pColorConvAPI,
                                           U16                  Flags,
                                           int                  LayerIndex);
```

Parameters

Parameter	Description
`pDeviceAPI`	Pointer to the display driver to be used. The chapter *Display drivers* on page 2608 contains a table of the available display drivers.
`pColorConvAPI`	Pointer to the color conversion routines to be used. The chapter *Colors* on page 617 contains a table with the available color conversion routines.
`Flags`	Should be zero.
`LayerIndex`	Layer which should be managed by the driver.

Return value

On success the function returns a pointer to the created device object, otherwise it returns `NULL`.

Additional information

Note that the used driver also determines the display orientation in some cases. This differs from driver to driver. For details about the display orientation, refer to the chapter *Display drivers* on page 2608.

 © 2020 SEGGER Microcontroller GmbH

39.4.3 Customizing GUI_X.c

This file is the location of the timing routines, the debugging routines and the kernel interface routines:

39.4.3.1 Timing routines

39.4.3.1.1 GUI_X_Delay()

Description

Returns after a specified time period in milliseconds.

Prototype

```
void GUI_X_Delay(int Period);
```

Parameters

Parameter	Description
Period	Period in milliseconds.

 © 2020 SEGGER Microcontroller GmbH

39.4.3.1.2 GUI_X_ExecIdle()

Description

Called only from non-blocking functions of the Window Manager.

Prototype

```
void GUI_X_ExecIdle(void);
```

Additional information

Called when there are no longer any messages which require processing. In this case the GUI is up to date.

 © 2020 SEGGER Microcontroller GmbH

39.4.3.1.3 GUI_X_GetTime()

Description

Used by `GUI_GetTime()` to return the current system time in milliseconds.

Prototype

```
GUI_TIMER_TIME GUI_X_GetTime(void);
```

Return value

The current system time in milliseconds, of type integer.

 © 2020 SEGGER Microcontroller GmbH

39.4.3.2 Debug routines

39.4.3.2.1 GUI_X_ErrorOut()

39.4.3.2.2 GUI_X_Warn()

39.4.3.2.3 GUI_X_Log()

Description

These routines are called by emWin with debug information in higher debug levels in case a problem (Error) or potential problem is discovered. The routines can be blank; they are not required for the functionality of emWin. In a target system, they are typically not required in a release (production) build, since a production build typically uses a lower debug level.

- Fatal errors are output using `GUI_X_ErrorOut()` if (`GUI_DEBUG_LEVEL` ≥ 3)
- Warnings are output using `GUI_X_Warn()` if (`GUI_DEBUG_LEVEL` ≥ 4)
- Messages are output using `GUI_X_Log()` if (`GUI_DEBUG_LEVEL` ≥ 5)

Prototypes

```
void GUI_X_ErrorOut(const char * s);

void GUI_X_Warn(const char * s);

void GUI_X_Log(const char * s);
```

Parameters

Parameter	Description
s	Pointer to the string to be sent.

Additional information

This routine is called by emWin to transmit error messages or warnings, and is required if logging is enabled. The GUI calls this function depending on the configuration macro `GUI_DEBUG_LEVEL`. The following table lists the permitted values for `GUI_DEBUG_LEVEL`:

Value	Symbolic name	Description
0	GUI_DEBUG_LEVEL_NOCHECK	No run-time checks are performed.
1	GUI_DEBUG_LEVEL_CHECK_PARA	Parameter checks are performed to avoid crashes. (Default for target system)
2	GUI_DEBUG_LEVEL_CHECK_ALL	Parameter checks and consistency checks are performed.
3	GUI_DEBUG_LEVEL_LOG_ERRORS	Errors are recorded.
4	GUI_DEBUG_LEVEL_LOG_WARNINGS	Errors and warnings are recorded. (Default for PC-simulation)
5	GUI_DEBUG_LEVEL_LOG_ALL	Errors, warnings and messages are recorded.

 © 2020 SEGGER Microcontroller GmbH

39.4.3.3 Kernel interface routines

Detailed descriptions for these routines may be found in *Execution Model: Single Task / Multitask* on page 757.

39.4.4 Function replacement

The following table shows the API functions which are available for setting up custom defined functions for common purpose:

Routine	Description
GUI_SetpfMemcpy()	Sets a custom function for memcpy operations.
GUI_SetpfMemset()	Sets a custom function for memset operations.
GUI_SetpfStrcmp()	Sets a custom function for string compare operations.
GUI_SetpfStrcpy()	Sets a custom function for string copy operations.
GUI_SetpfStrlen()	Sets a custom function for getting the length of a string.

 © 2020 SEGGER Microcontroller GmbH

39.4.4.1 GUI_SetpfMemcpy()

Description

Sets a custom function for memcpy operations.

Prototype

```
void GUI_SetpfMemcpy
                (void * ( *pFunc)(void * pDest , const void * pSrc , size_t Cnt ));
```

Parameters

Parameter	Description
pFunc	Function to be used

 © 2020 SEGGER Microcontroller GmbH

39.4.4.2 GUI_SetpfMemset()

Description

Sets a custom function for memset operations.

Prototype

```
void GUI_SetpfMemset(void * ( *pFunc)(void * pDest , int c , size_t Cnt ));
```

Parameters

Parameter	Description
pFunc	Function to be used

 © 2020 SEGGER Microcontroller GmbH

39.4.4.3 GUI_SetpfStrcmp()

Description

Sets a custom function for string compare operations.

Prototype

```
void GUI_SetpfStrcmp(int ( *pFunc)(const char * , const char * ));
```

Parameters

Parameter	Description
pFunc	Function to be used

 © 2020 SEGGER Microcontroller GmbH

39.4.4.4 GUI_SetpfStrcpy()

Description

Sets a custom function for string copy operations.

Prototype

```
void GUI_SetpfStrcpy(char * ( *pFunc)(char * , const char * ));
```

Parameters

Parameter	Description
pFunc	Function to be used

 © 2020 SEGGER Microcontroller GmbH

39.4.4.5 GUI_SetpfStrlen()

Description

Sets a custom function for getting the length of a string.

Prototype

```
void GUI_SetpfStrlen(size_t ( *pFunc)(const char * ));
```

Parameters

Parameter	Description
pFunc	Function to be used

 © 2020 SEGGER Microcontroller GmbH

39.5 Compile time configuration

The following table shows the available compile time configuration files located in the sub-folder `Config`:

Configuration file	Purpose
`GUIConf.h`	Configuration of possible number of used layers, default fonts and colors and available features (e.g. Widgets).
`LCDConf.h`	Configuration of the used display driver(s).

In case a precompiled emWin library is used, changing the configuration files will not have any effect until the library is compiled again with the required settings. This applies to all of the defines explained in the following sections.

39.5.1 Customizing GUIConf.h

As described above the file should contain the configuration of available features and the configuration of the default font. Each emWin shipment comes with a `GUIConf.h` file which includes a basic configuration which can be used as a starting point.

39.5.1.1 Configuring the available features of emWin

The following table shows the available configuration macros:

Type	Macro	Default	Description
B	GUI_OS	0	Activate to enable multitasking support with multiple tasks calling emWin (see the chapter *Execution Model: Single Task / Multitask* on page 757).
B	GUI_SUPPORT_CURSOR	(see expl.)	Per default cursors are enabled if either `GUI_SUPPORT_TOUCH` or `GUI_SUPPORT_MOUSE` has been enabled. If cursors should be shown without enabling one of these options it should be set to 1.
B	GUI_SUPPORT_MEMDEV	0	Enables optional Memory Device support.
B	GUI_SUPPORT_MOUSE	0	Enables the optional mouse support.
B	GUI_SUPPORT_ROTATION	1	Enables text rotation support.
B	GUI_SUPPORT_SPY	0	Enables support for emWinSPY.
B	GUI_SUPPORT_TOUCH	0	Enables optional touch-screen support.
T	GUI_TIMER_TIME	int	Defines the type which is used for time values by the emWin Timer functionality.
B	GUI_WINSUPPORT	0	Enables optional Window Manager support.
B	GUI_SUPPORT_BIDI	1	Enables BiDi support for emWin. Set to 0 if not required and to save some ROM.

39.5.1.2 Default font and default color configuration

The following table shows the available configuration macros:

Type	Macro	Default	Description
N	GUI_DEFAULT_BKCOLOR	`GUI_BLACK`	Define the default background color.
N	GUI_DEFAULT_COLOR	`GUI_WHITE`	Define the default foreground color.
S	GUI_DEFAULT_FONT	`&GUI_Font6x8`	Defines which font is used per default after `GUI_Init()`. If you do not use the default font, it makes sense to change to a different default, as

 © 2020 SEGGER Microcontroller GmbH

Type	Macro	Default	Description
			the default font is referenced by the code and will therefore always be linked. Please also refer to `GUI_SetDefaultFont()` which can be used for runtime configuration of the default font.

The default colors and fonts of the widgets which are part of the optional Window Manager can also be configured. For details, refer to the chapter *Widgets (window objects)* on page 963.

39.5.1.3 Advanced GUI configuration options

The following table shows the available configuration macros:

Type	Macro	Default	Description
S	GUI_DEBUG_LEVEL	1 (target) 4 (simulation)	Defines the debug level, which determines how many checks (assertions) are performed by emWin and if debug errors, warnings and messages are output. Higher debug levels generate bigger code.
N	GUI_MAXTASK	4	Define the maximum number of tasks from which emWin is called to access the display when multitasking support is enabled (see the chapter *Execution Model: Single Task / Multitask* on page 757.
F	GUI_MEMCPY	memcpy	This macro allows replacement of the memcpy function.
F	GUI_MEMSET	memset	This macro allows replacement of the memset function
N	GUI_NUM_LAYERS	1	Defines the maximum of available layers/displays.
F	GUI_POST_INIT	-	Defines a function to be called at the end of `GUI_Init()`.
B	GUI_TRIAL_VERSION	0	Marks the compiler output as evaluation version.
B	GUI_WINSUPPORT	0	Enables optional Window Manager support.
N	GUI_PID_BUFFER_SIZE	5	Maximum number of PID events managed by the input buffer.
N	GUI_KEY_BUFFER_SIZE	10	Maximum number of key events managed by the input buffer.

39.5.1.3.1 GUI_MEMCPY (obsolete)

> **Note**
>
> Please refer to *GUI_SetpfMemcpy* on page 2895.

This macro allows replacement of the memcpy function of the GUI. On a lot of systems, memcpy takes up a considerable amount of time because it is not optimized by the compiler manufacturer. emWin contains an alternative memcpy routine, which has been optimized for 32 bit CPUs. On a lot of systems this routine should generate faster code than the default memcpy routine. However, this is still a generic C routine, which in a lot of systems can be replaced by faster code, typically using either a different C routine, which is better optimized for the particular CPU or by writing a routine in Assembly language.
To use the optimized emWin routine add the following define to the file `GUIConf.h`:

```
#define GUI_MEMCPY GUI__memcpy
```

 © 2020 SEGGER Microcontroller GmbH

39.5.1.3.2 GUI_MEMSET (obsolete)

> **Note**
>
> Please refer to *GUI_SetpfMemset* on page 2896.

This macro allows replacement of the memset function of the GUI. On a lot of systems, memset takes up a considerable amount of time because it is not optimized by the compiler manufacturer. We have tried to address this by using our own memset() Routine `GUI__memset`. However, this is still a generic C routine, which in a lot of systems can be replaced by faster code, typically using either a different C routine, which is better optimized for the particular CPU, by writing a routine in Assembly language or using the DMA.
If you want to use your own memset replacement routine, add the define to the `GUIConf.h` file.

39.5.1.3.3 GUI_POST_INIT

It could make sense to have a function which is called after the GUI has been completely initialized. To be able to have that the macro could be defined as follows:

Example

```
#define GUI_POST_INIT CustomFunction();
```

39.5.1.3.4 GUI_TRIAL_VERSION

This macro can be used to mark the compiler output as an evaluation build. It should be defined if the software is given to a third party for evaluation purpose (typically with evaluation boards).
Note that a special license is required to do this; the most common licenses do not permit redistribution of emWin in source or object code (relinkable) form. Contact sales@segger.com if you would like to do this.
If `GUI_TRIAL_VERSION` is defined, the following message is shown when calling `GUI_Init()`:

```
This software
contains an eval-
build of emWin.

A license is
required to use
it in a product.

www.segger.com
```

This message is always shown in the upper left corner of the display and is normally visible for 1 second. The timing is implemented by a call of `GUI_X_Delay(1000)`. The functionality of emWin is in no way limited if this switch is active.

Example

```
#define GUI_TRIAL_VERSION 1
```

39.5.2 Customizing LCDConf.h

This file contains general configuration options required for compiling the display driver(s) which need not to be changed at run-time. The available configuration options depend on the used display driver. For details about the available configuration options, refer to the chapter *Display drivers* on page 2608. The detailed driver description shows the available configuration options for each display driver.

 © 2020 SEGGER Microcontroller GmbH

39.6 Hardware acceleration

If a CPU or an LCD-controller offers hardware acceleration features, as available for example on the STM32F4-device with ChromeART accelerator, some or even most of them could be used by emWin for accelerating the process of drawing operations. To be able to achieve that different mechanisms need to be used dependent on the kind of hardware acceleration which should be used.
The following table shows a rough classification of the features which could be accelerated:

Group	Purpose
Color conversion	Some hardware like ChromeART offers the possibility of converting colors from one format to a different format. For that many of the color conversion routines offers the possibility to set a hardware function for the process of color conversion.
Fill, copy and bitmap drawing	Those operations could be accelerated by setting custom drawing functions using LCD_SetDevFunc().
Alpha blending	A custom function could be used to mix up the given foreground and background colors in accordance to the alpha values of the colors.
Mixing colors	A custom function could be used to mix up the given foreground and background colors with the given intensity.
Alpha text drawing	Drawing of anti-aliased text could be achieved by setting a custom function.
Palette conversion	Conversion of bitmap palettes could be done by a custom function.
Drawing bitmaps within memory devices	Some internal memory device operations could be accelerated by setting a custom function.

39.6.1 Using ChromeART accelerator

Nearly all functions available on the ChromeART accelerator of STM32F429 and STM32F439 can be used with emWin. Once configured right it could speed up many drawing operations drastically. The sample folder of emWin contains a configuration file which uses nearly features of the ChromeART accelerator. That sample can be found under Sample\LCDConf\GUIDRV_Lin\STM32F429. Please note that this sample is only available if the driver GUIDRV_Lin is licensed.

39.6.2 Available API functions

The following table shows the available routines:

Routine	Description
Color conversion	
GUICC_M1555I_SetCustColorConv() GUICC_M565_SetCustColorConv() GUICC_M4444I_SetCustColorConv() GUICC_M888_SetCustColorConv() GUICC_M8888I_SetCustColorConv()	Setting up custom color conversion routines for the according fixed palette modes.
Filling, copy operations and bitmap drawing	
LCD_SetDevFunc()	The function sets additional and / or user defined functions of the display driver.
Alpha blending	
GUI_AlphaEnableFillRectHW()	Enables filling a rectangle with a transparent color.
GUI_SetFuncAlphaBlending()	Setting up a custom defined function for doing alpha blending operations.
GUI_SetFuncDrawAlpha()	Sets two custom routines for drawing memory devices with alpha value into an-

 © 2020 SEGGER Microcontroller GmbH

Routine	Description
	other memory device and for drawing a bitmap with alpha value.
Mixing colors	
GUI_SetFuncMixColors()	Setting up a custom defined function for blending a single background color value with the given color using the given intensity.
GUI_SetFuncMixColorsBulk()	Setting up a custom defined function for bulk blending operations.
Alpha text drawing	
GUI_AA_SetpfDrawCharAA4()	Sets up a custom defined function for drawing alpha blending characters with 4 bits per pixel.
Palette conversion	
GUI_SetFuncGetpPalConvTable()	Sets a function pointer to a custom function, which converts an array of colors into an array of index values.
Drawing bitmaps within memory devices	
GUI_MEMDEV_SetDrawMemdev16bppFunc()	Sets a custom function for the above described job.

 © 2020 SEGGER Microcontroller GmbH

39.6.3 Color conversion

As explained in detail in *Colors* on page 617, color conversion in emWin is required for converting a color value into an index value and vice versa. That is done by the routines pointed by the fixed palette mode structures. These structures have pointers for converting single items and also for bulk conversion of multiple items. The most important color conversions offers the possibility for setting custom defined routines for bulk conversion.

39.6.3.1 GUICC_M1555I_SetCustColorConv()

39.6.3.2 GUICC_M565_SetCustColorConv()

39.6.3.3 GUICC_M4444I_SetCustColorConv()

39.6.3.4 GUICC_M888_SetCustColorConv()

39.6.3.5 GUICC_M8888I_SetCustColorConv()

Description

These routines can be used to set custom routines for bulk color conversion for the according color conversion.

Prototype

```
void GUICC_XXX_SetCustColorConv(tLCDDEV_Color2IndexBulk * pfColor2IndexBulk,
                                tLCDDEV_Index2ColorBulk * pfIndex2ColorBulk);
```

Parameters

Parameter	Description
pfColor2IndexBulk	Routine to be used for converting multiple colors into index values.
pfIndex2ColorBulk	Routine to be used for converting multiple index values into colors.

Additional information

The definition of `tLCDDEV_Color2IndexBulk` is as follows:

```
typedef void tLCDDEV_Color2IndexBulk(
  LCD_COLOR * pColor,
  void * pIndex,
  U32 NumItems,
  U8 SizeOfIndex
);
```

The definition of `tLCDDEV_Index2ColorBulk` is as follows:

```
typedef void tLCDDEV_Index2ColorBulk(
  void * pIndex,
  LCD_COLOR * pColor,
  U32 NumItems,
  U8 SizeOfIndex
);
```

 © 2020 SEGGER Microcontroller GmbH

39.6.4 Filling, copy operations and bitmap drawing

As already explained before that can be achieved by the function *LCD_SetDevFunc* on page 2809.

 © 2020 SEGGER Microcontroller GmbH

39.6.5 Alpha blending

39.6.5.1 GUI_AlphaEnableFillRectHW()

Description

Enables filling a rectangle with a transparent color.

Prototype

```
void GUI_AlphaEnableFillRectHW(int OnOff);
```

Parameters

Parameter	Description
OnOff	Turns filling a rectangle with a transparent color on or off.

Additional information

This function requires a function for filling a rectangle by the hardware. Please refer to LCD_SetDevFunc().

 © 2020 SEGGER Microcontroller GmbH

39.6.5.2 GUI_SetFuncAlphaBlending()

Description

Sets a custom defined routine for alpha blending operations. That routine is called by emWin if multiple foreground colors should be mixed up with the background.

Prototype

```
void ( * GUI_SetFuncAlphaBlending(void ( * pFunc)
                                  (LCD_COLOR                  * pColorFG,
                                   LCD_COLOR                  * pColorBG,
                                   LCD_COLOR                  * pColorDst,
                                   U32 NumItems))) (LCD_COLOR * pColorFG,
                                   LCD_COLOR                  * pColorBG,
                                   LCD_COLOR                  * pColorDst,
                                   U32                          NumItems);
```

Parameters

Parameter	Description
pFunc	Pointer to the function to be used.

Return value

Pointer to the previous used function.

Parameters of pFunc()

Data type	Parameter	Description
LCD_COLOR *	pColorFG	Pointer to the foreground color array.
LCD_COLOR *	pColorBG	Pointer to the background color array.
LCD_COLOR *	pColorDest	Pointer to a buffer for the result.
U32	NumItems	Number of colors to be mixed up.

 © 2020 SEGGER Microcontroller GmbH

39.6.5.3 GUI_SetFuncDrawAlpha()

Description

Sets two custom routines for drawing memory devices with alpha value into another memory device and for drawing a bitmap with alpha value.

Prototype

```
int GUI_SetFuncDrawAlpha(GUI_DRAWMEMDEV_FUNC * pfDrawAlphaMemdevFunc,
                         GUI_DRAWBITMAP_FUNC * pfDrawAlphaBitmapFunc);
```

Parameters

Parameter	Description
pfDrawAlphaMemdevFunc	Pointer to a function for drawing memory devices.
pfDrawAlphaBitmapFunc	Pointer to a function for drawing bitmaps.

Additional information

The prototype of the function used for memory devices is:

```
void GUI_DRAWMEMDEV_FUNC (      void * pDst,
                          const void * pSrc,
                                int    xSize,
                                int    ySize,
                                int    BytesPerLineDst,
                                int    BytesPerLineSrc);
```

The prototype of the function used for bitmaps is:

```
void GUI_DRAWBITMAP32_FUNC (int         LayerIndex,
                            int         x,
                            int         y,
                            U32 const * p,
                            int         xSize,
                            int         ySize,
                            int         BytesPerLine);
```

 © 2020 SEGGER Microcontroller GmbH

39.6.6 Mixing colors

Mixing up colors here means mixing up the given background with the given foreground using the given intensity.

39.6.6.1 GUI_SetFuncMixColors()

Description

Sets a custom defined routine for mixing up single colors.

Prototype

```
LCD_COLOR ( * GUI_SetFuncMixColors(LCD_COLOR ( * pFunc)
                                                (LCD_COLOR               Color,
                                                 LCD_COLOR               BkColor,
                                                 U8 Intens))) (LCD_COLOR Color,
                                                 LCD_COLOR               BkColor,
                                                 U8                      Intens);
```

Parameters

Parameter	Description
pFunc	Pointer to the function to be used.

Parameters of pFunc()

Data type	Parameter	Description
LCD_COLOR	Color	Color to be blended with the given intensity.
LCD_COLOR	BkColor	Color of background.
U8	Intens	Intensity to be used for the blending operation.

 © 2020 SEGGER Microcontroller GmbH

39.6.6.2 GUI_SetFuncMixColorsBulk()

Description

Sets up a custom defined function for bulk mixing operations. That is mainly used for fading memory devices. It mixes up the given background area with the given foreground area using the desired intensity.

Prototype

```
void ( * GUI_SetFuncMixColorsBulk(void ( * pFunc)(U32              * pFG,
                                                   U32              * pBG,
                                                   U32              * pDst,
                                                   unsigned           OffFG,
                                                   unsigned           OffBG,
                                                   unsigned           OffDest,
                                                   unsigned           xSize,
                                                   unsigned           ySize,
                                                   U8 Intens))) (U32 * pFG,
                                                   U32              * pBG,
                                                   U32              * pDst,
                                                   unsigned           OffFG,
                                                   unsigned           OffBG,
                                                   unsigned           OffDest,
                                                   unsigned           xSize,
                                                   unsigned           ySize,
                                                   U8                 Intens);
```

Parameters

Parameter	Description
pFunc	Pointer to the function to be used.

Parameters of pFunc()

Data type	Parameter	Description
U32 *	pFG	Pointer to the foreground color array.
U32 *	pBG	Pointer to the background color array.
U32 *	pDst	Pointer to the destination buffer for the result.
unsigned	OffFG	(currently not used)
unsigned	OffBG	Pointer to the destination buffer for the result.
unsigned	OffDest	Additional offset in pixels (xSizeBG - xSizeFG) to be added for incrementing the background pointer at the end of a line.
unsigned	xSize	X-size of area to be converted.
unsigned	ySize	Y-size of area to be converted.
U8	Intens	Intensity to be used when blending the foreground over the background.

Return value

Pointer to the previous used function.

 © 2020 SEGGER Microcontroller GmbH

39.6.7 Alpha text drawing

If transparent mode is active, no memory device is selected and no clipping is required a custom function could be used for drawing anti-aliased characters. In all other cases automatically the default function is used by emWin. Alpha text drawing means that the given character image consists of intensity values which need to be used to mix up the current background with the current foreground color.

39.6.7.1 GUI_AA_SetpfDrawCharAA4()

Description

Sets up a custom defined function for drawing alpha blending characters with 4 bits per pixel. The intensities to be used are stored in a byte array passed to the function. Each pixel is stored in one nibble. The leftmost pixel is stored in the uppermost nibble.

Prototype

```
void GUI_AA_SetpfDrawCharAA4
      (int ( *pfDrawChar)
(int LayerIndex , int x , int y , U8 const * p , int xSize , int ySize , int BytesPerLine ));
```

Parameters

Parameter	Description
pfDrawChar	Pointer to the function to be used.

Parameters of pfDrawChar()

Data type	Parameter	Description
int	LayerIndex	Destination layer of drawing operation.
int	xPos	X-Position in screen coordinates to be used.
int	yPos	Y-Position in screen coordinates to be used.
const U8 *	p	Pointer to an array of bytes containing the intensity values to be used.
int	xSize	X-size of character to be drawn.
int	ySize	Y-size of character to be drawn.
int	BytesPerLine	Bytes per line of the intensity array.

 © 2020 SEGGER Microcontroller GmbH

39.6.8 Palette conversion

Palettes need to be converted when drawing device independent bitmaps with a color depth of not more than 8 bits per pixel. The conversion routine converts the colors of the bitmap palette into index values to be used for drawing into the frame buffer. For that conversion process, normally done by emWin, a custom function can be set.

39.6.8.1 GUI_SetFuncGetpPalConvTable()

Description

Sets a function pointer to a custom function, which converts an array of colors into an array of index values. It should return a pointer to the first entry of the index table.

Prototype

```
void GUI_SetFuncGetpPalConvTable
      (LCD_PIXELINDEX * ( *pFunc)
(const LCD_LOGPALETTE * pLogPal , const GUI_BITMAP * pBitmap , int LayerIndex ));
```

Parameters

Parameter	Description
pFunc	Pointer to the function to be used.

Parameters of pfFunc()

Data type	Parameter	Description
const LCD_LOGPALETTE *	pLogPal	Pointer to the array of colors to be converted.
const GUI_BITMAP *	pBitmap	Pointer to the bitmap to be drawn.
int	LayerIndex	Layer index of drawing operation.

Elements of structure LCD_LOGPALETTE

Data type	Element	Description
int	NumEntries	Number of color values located in the palette.
char	HasTrans	0 - No transparency should be used. 1 - Pixels with index 0 are treated as transparent.
const LCD_COLOR *	pPalEntries	Pointer to the array of color values.

Return value

A pointer to the array of index values of type LCD_PIXELINDEX.

Additional information

The process of drawing a bitmap within emWin and the mechanism of color conversion should be well known when using that function.

 © 2020 SEGGER Microcontroller GmbH

39.6.9 Drawing bitmaps within memory devices

A custom function for drawing bitmaps with a color depth of 16bpp into memory devices with a color depth of 16bpp can be used. The task of that function is copying the data of the bitmap to be drawn into the destination memory device.

39.6.9.1 GUI_MEMDEV_SetDrawMemdev16bppFunc()

Description

Sets a custom function for the above described job.

Prototype

```
void GUI_MEMDEV_SetDrawMemdev16bppFunc
                              (GUI_DRAWMEMDEV_16BPP_FUNC * pfDrawMemdev16bppFunc);
```

Parameters

Parameter	Description
pfDrawMemdev16bppFunc	Pointer to the function to be used.

Additional information

The definition of GUI_DRAWMEMDEV_16BPP_FUNC is as follows:

```
typedef void GUI_DRAWMEMDEV_16BPP_FUNC (
void * pDst,
const void * pSrc,
int xSize,
int ySize,
int BytesPerLineDst,
int BytesPerLineSrc
);
```

Parameters of GUI_DRAWMEMDEV_16BPP_FUNC

Data type	Parameter	Description
void *	pDst	Destination pointer for upper left pixel to be drawn.
const void *	pSrc	Source pointer for upper left pixel to be drawn.
int	xSize	X-size in pixels of area to be drawn.
int	ySize	Y-size in pixels of area to be drawn.
int	BytesPerLineDst	Stride value in bytes of destination area.
int	BytesPerLineSrc	Stride value in bytes of source bitmap.

 © 2020 SEGGER Microcontroller GmbH

39.7 Hardware JPEG decoding

If the used MCU is capable of decoding JPEG files, emWin offers an interface to reroute the decoding and drawing operations to hardware routines.
This offers a huge performance boost when displaying JPEG files compared to a software only solution. Especially if a movie file should be displayed (.emf or .avi) it makes sense to use the hardware decoder of a MCU.
The interface between emWin and the hardware decoder was developed on a STM32F769 MCU but can be configured to work on other MCUs which come with a hardware JPEG decoder.

39.7.1 Using hardware JPEG decoding

Every emWin shipment comes with a sample configuration file which is located under `Sample\JPEGConf\STM32F769`. It requires embOS and the hardware abstraction layer provided by ST because it was made to be used on a STM32F769. Using the hardware decoding functionality is basically achieved by setting a function pointer. This function will manage the process of decoding and drawing. Every time one of the functions `GUI_JPEG_Draw()` or `GUI_JPEG_DrawEx()` are used the set function pointer gets called.
If the function gets called, it is necessary to call the GetData function to receive as many bytes as required to start the JPEG decoding process. After receiving the data they get passed to the hardware routines and the decoding process starts. If required the `GetData` function has to be called multiple times until the decoding process has been finished.
After the process of hardware decoding the data needs to be converted from YCbCr format into RGB data. Unfortunately the STM32F769 offers no function to do that conversion per hardware. The `JPEGConf.c` mentioned before is an example on how to do this.
Once the data is completely converted into RGB data it is shown on the display (depending on the currently selected device).

39.7.2 Available API functions

The following table shows the available routines:

Routine	Description
`GUI_JPEG_SetpfDrawEx()`	This function sets a function pointer to be used to decode and draw a JPEG file.

 © 2020 SEGGER Microcontroller GmbH

39.7.2.1 GUI_JPEG_SetpfDrawEx()

Description

This function sets a function pointer to be used to decode and draw a JPEG file.

Prototype

```
void GUI_JPEG_SetpfDrawEx
      (int ( *pfDrawEx)
(GUI_GET_DATA_FUNC * pfGetData , void * p , int x0 , int y0 ));
```

Parameters

Parameter	Description
pfDrawEx	Pointer to the function to be used.

Additional information

If set, the function pointer gets called if GUI_JPEG_Draw() or GUI_JPEG_DrawEx() gets called. The MOVIE module of emWin makes also use of this function. The function pointer is described below.

39.7.2.1.1 pfDrawEx()

Description

This function pointer gets called every time a JPEG should be displayed. Within this function data needs to be received by the GetData function, the decoding process has to be performed as well as the drawing of the completely decoded JPEG on the display.

Prototype

```
int ( * pfDrawEx)(GUI_GET_DATA_FUNC * pfGetData,
                  void              * p,
                  int                 x0,
                  int                 y0);
```

Parameters

Parameter	Description
pfGetData	Function pointer to a GetData function
p	Data pointer which is passed to the GetData function.
x0	x position the JPEG file should be displayed.
y0	y position the JPEG file should be displayed.

Return value

0 on success.
1 on error.

Additional information

An example of the GetData function can be found under *Getting data with the …Ex() functions* on page 436.
If this function returns 1 the default JPEG drawing routine of emWin gets called.

 © 2020 SEGGER Microcontroller GmbH

39.8 Drawing AA shapes with hardware

Some controller offer a dedicated hardware module for performing anti aliased drawing operations, for example the Dave2D Drawing Engine of the Renesas RX65N microcontroller. Because performing these operations in software only requires a lot of CPU time emWin offers an interface to route these operation to such a hardware module. The following will describe the offered API in detail.

39.8.1 How to use it

The API offers an API to set hardware routines which will get called instead of emWin AA drawing functions. These hardware routines should set up the hardware using the information about position and size of the shapes provided by emWin.

39.8.2 Available API functions

The following table shows the available routines:

Routine	Description
GUI_AA_SetFuncFillCircle()	This function sets a function pointer which gets called to fill an anti aliased circle.
GUI_AA_SetFuncFillPolygon()	This function sets a function pointer which gets called to fill an anti aliased polygon.
GUI_AA_SetFuncDrawCircle()	This function sets a function pointer which gets called to draw an anti aliased circle.
GUI_AA_SetFuncDrawLine()	This function sets a function pointer which gets called to draw an anti aliased line.
GUI_AA_SetFuncDrawPolyOutline()	This function sets a function pointer which gets called to draw an anti aliased polygon.
GUI_AA_SetFuncDrawArc()	This function sets a function pointer which gets called to draw an anti aliased arc.

 © 2020 SEGGER Microcontroller GmbH

39.8.2.1 GUI_AA_SetFuncFillCircle()

Description

This function sets a function pointer which gets called to fill an anti aliased circle.

Prototype

```
void GUI_AA_SetFuncFillCircle(int ( *pfFillCircle)(int x0 , int y0 , int r ));
```

Parameters

Parameter	Description
pfFillCircle	Function pointer to a function for filling a circle.

Parameters of pfFillCircle()

Data type	Parameter	Description
int	x0	x position of the center of the circle.
int	y0	y position of the center of the circle.
int	r	Radius of the circle.

 © 2020 SEGGER Microcontroller GmbH

39.8.2.2 GUI_AA_SetFuncFillPolygon()

Description

This function sets a function pointer which gets called to fill an anti aliased polygon.

Prototype

```
void GUI_AA_SetFuncFillPolygon
      (int ( *pfFillPolygon)
(const GUI_POINT * pPoints , int NumPoints , int x0 , int y0 ));
```

Parameters

Parameter	Description
pfFillPolygon	Function pointer to a function for filling a polygon.

Parameters of pfFillPolygon()

Data type	Parameter	Description
GUI_POINT *	pPoints	Pointer to a list of points.
int	NumPoints	Number of elements of pPoints.
int	x0	x position of the start of the polygon.
int	y0	y position of the start of the polygon.

 © 2020 SEGGER Microcontroller GmbH

39.8.2.3 GUI_AA_SetFuncDrawCircle()

Description

This function sets a function pointer which gets called to draw an anti aliased circle.

Prototype

```
void GUI_AA_SetFuncDrawCircle(int ( *pfDrawCircle)(int x0 , int y0 , int r ));
```

Parameters

Parameter	Description
pfDrawCircle	Function pointer to a function for drawing a circle.

Parameters of pfDrawCircle()

Data type	Parameter	Description
int	x0	x position of the center of the circle.
int	y0	y position of the center of the circle.
int	r	Radius of the circle.

 © 2020 SEGGER Microcontroller GmbH

39.8.2.4 GUI_AA_SetFuncDrawLine()

Description

This function sets a function pointer which gets called to draw an anti aliased line.

Prototype

```
void GUI_AA_SetFuncDrawLine
                          (int ( *pfDrawLine)(int x0 , int y0 , int x1 , int y1 ));
```

Parameters

Parameter	Description
pfDrawLine	Function pointer to a function for drawing a line.

Parameters of pfDrawLine()

Data type	Parameter	Description
int	x0	Start x position of the line.
int	y0	Start y position of the line.
int	x1	End x position of the line.
int	y1	End y position of the line.

 © 2020 SEGGER Microcontroller GmbH

39.8.2.5 GUI_AA_SetFuncDrawPolyOutline()

Description

This function sets a function pointer which gets called to draw an anti aliased polygon.

Prototype

```
void GUI_AA_SetFuncDrawPolyOutline
      (int ( *pfDrawPolyOutline)
(const GUI_POINT * pSrc , int NumPoints , int Thickness , int x , int y ));
```

Parameters

Parameter	Description
pfDrawPolyOutline	Function pointer to a function for drawing a polygon.

Parameters of pfDrawPolyOutline()

Data type	Parameter	Description
GUI_POINT *	pPoints	Pointer to a list of points.
int	NumPoints	Number of elements of pPoints.
int	Thickness	The thickness of the poly outline.
int	x0	x position of the start of the polygon.
int	y0	y position of the start of the polygon.

 © 2020 SEGGER Microcontroller GmbH

39.8.2.6 GUI_AA_SetFuncDrawArc()

Description

This function sets a function pointer which gets called to draw an anti aliased arc.

Prototype

```
void GUI_AA_SetFuncDrawArc
        (int ( *pfDrawArc)(int x0 , int y0 , int rx , int ry , I32 a0 , I32 a1 ));
```

Parameters

Parameter	Description
pfDrawArc	Function pointer to a function for drawing an arc.

Parameters of pfDrawArc()

Data type	Parameter	Description
int	x0	Center x position of the arc.
int	y0	Center y position of the arc.
int	rx	Radius in x direction.
int	ry	Radius in y direction.
int	a0	Start of the arc in degrees.
int	a1	End of the arc in degrees.

 © 2020 SEGGER Microcontroller GmbH

39.9 Framebuffer located in data cache area of CPU

If available it makes sense to enable a data cache on CPU side. That normally speeds up RAM access performance a lot. When using a direct addressable frame buffer (normally managed by GUIDRV_Lin) and if the frame buffer of the LCD-controller is located within a cached data memory area, it could happen, that the display shows some disturbance like shown on the screenshot to the right. Please note that this is not a malfunction of emWin. It is caused by the data cache of the CPU. The display driver (normally GUIDRV_Lin) writes into memory which is managed by the CPUs data cache. But unfortunately not all data is written directly into the RAM area of the frame buffer, but only into the data cache. In that case the LCD-controller does not have the correct data for generating the display signals. The following explains how to avoid that disturbance.



39.9.1 Requirements

To be able to use a data cache, it is required that either the cache could be configured to work in 'write-through' mode (please also refer to *GUIDRV_Lin* on page 2676) or multiple buffers should be used (please also refer to *Multiple Buffering* on page 2372). If a 'write-through' mode is available, nothing else needs to be considered.

39.9.2 Using multiple buffers and a data cache

If the cache is not configurable, multiple buffering must be enabled and a cache clearance function should be set with GUI_DCACHE_SetClearCacheHook().

39.9.2.1 How it works

To be able to see always a screen without cache disturbance, it is required that emWin makes sure, the cache is cleared before the frame buffer becomes visible. That is done by calling the cache clearance function immediately before the back buffer becomes visible. In detail it is called immediately before the display driver callback function gets the command LCD_X_SHOWBUFFER.

When using the Window Manager

To make sure that all drawing operations are done automatically within the back buffer, the application should not draw anything outside the WM_PAINT event of the window manager.

39.9.2.2 Animations and multiple buffering

The most recommended way to use animation functions is animating window content and invalidating the according windows within the animations. That makes sure, multi buffering is used automatically after enabled by WM_MULTIBUF_Enable(). If the window manager

 © 2020 SEGGER Microcontroller GmbH

is not available or when drawing with animations besides the Window Manager, a slice callback function using `GUI_MULTIBUF_Begin()` and `GUI_MULTIBUF_End()` should be used to make sure the DCache gets cleared. Please also refer to *Using a slice callback function* on page 598.

39.9.2.3 Memory device animation functions

> **Note**
>
> The following applies to functions listed in the following chapters:
> - *Animation functions* on page 732
> - *Animation functions (Window Manager required)* on page 736
> - *Blending, Blurring and Dithering functions* on page 741
> - *Blending and Blurring functions (Window Manager required)* on page 749

Normally those functions do not use multiple buffering. But in case of using a data cache, multiple buffering is required because all drawing operations need to be done within the back buffer before the cache is cleared and the back buffer becomes visible. For that case the function `GUI_MEMDEV_MULTIBUF_Enable()` should be used to enable that feature.

39.9.3 Available API-functions

The following functions are available:

Routine	Description
`GUI_DCACHE_Clear()`	Calls the hook function set with `GUI_DCACHE_SetClearCacheHook()`.
`GUI_DCACHE_SetClearCacheHook()`	Sets up a function for clearing the cache of the given layer.

 © 2020 SEGGER Microcontroller GmbH

39.9.3.1 GUI_DCACHE_Clear()

Description

Calls the hook function set with `GUI_DCACHE_SetClearCacheHook()`. Normally this function does not need to be called. It should be called automatically by emWin.

Prototype

```
void GUI_DCACHE_Clear(U32 LayerMask);
```

Parameters

Parameter	Description
`LayerMask`	Bit mask of layers to be cleared.

Additional information

Please refer to `GUI_DCACHE_SetClearCacheHook()`.

 © 2020 SEGGER Microcontroller GmbH

39.9.3.2 GUI_DCACHE_SetClearCacheHook()

Description

Sets up a function for clearing the cache of the given layer. That function is called immediately before a back buffer should become visible. That makes sure, no cache disturbance will be visible on the screen.

Prototype

```
void GUI_DCACHE_SetClearCacheHook(void ( *pFunc)(U32 LayerMask ));
```

Parameters

Parameter	Description
pFunc	Pointer to the function to be used.

Additional information

Parameter LayerMask passed to the hook function contains a bit mask of the layer(s) to be managed. The number of the bit represents the number of the layer. If for example the data cache of layer 2 should be cleared, bit 2 of the layer mask is set.

Example

The following shows a sample implementation of a clear cache function:

```
static void _ClearCacheHook(U32 LayerMask) {
  int i;
  for (i = 0; i < GUI_NUM_LAYERS; i++) {
    if (LayerMask & (1 << i)) {
      _CleanRange(_apVRAM[i], WIDTH * HEIGHT * NUM_BUFFERS * sizeof(U32));
    }
  }
}
```

 © 2020 SEGGER Microcontroller GmbH

39.10 Memory management

emWin comes with its own memory management system which makes it easy to calculate the total amount of memory required for emWin. Further, the user does not have to bother about allocating and freeing memory because emWin gets its own memory area.

39.10.1 Usage

With the function `GUI_ALLOC_AssignMemory()` the user spends emWin a block of memory which can reside in either internal or external memory. Once this block is allocated for emWin the user does not have to bother about memory management for emWin. emWin does only use the given memory area for allocating memory. This memory is used for Memory Devices, cache for indirect drivers, decompressing image data (e.g. JPEG, PNG) and many more operations which require a piece of memory. But, if using the `GUIDRV_Lin` driver, which requires a frame buffer, emWin does not allocate the memory for the frame buffer. This has to be done by the user.

The memory block gets manged by emWin and should not be accessed by the user directly. Otherwise it might come to unexpected behavior.

39.10.2 Block management

Memory in emWin get allocated in blocks. To manage these blocks emWin requires a few bytes of additional memory for each block. These bytes are located in a dedicated memory block. initially this block is quite small and can manage only a few memory blocks. Once emWin requires memory for the application (e.g. creating a window or a Memory Device) this block will grow up. This 'management'-memory gets reused if blocks are getting deleted and created again, but it will not get freed by emWin.
Sometimes it might look like a memory leak because the allocated 'management'-memory doesn't get freed but this is the normal behavior. Also, those bytes are not lost because they will get reused if possible.

39.10.3 Available API functions

The following functions allow control of memory usage at runtime. They can be used to e.g. prevent waste of memory.

Routine	Description
`GUI_ALLOC_GetMaxUsedBytes()`	This function returns the number of the maximum number of used bytes.
`GUI_ALLOC_GetNumFreeBytes()`	This function returns the number of bytes which can be used for emWin functions.
`GUI_ALLOC_GetMemInfo()`	This function fills the given info structure with information about the memory usage.
`GUI_ALLOC_GetNumUsedBytes()`	This function returns the number of bytes which are already used by emWin functions.

 © 2020 SEGGER Microcontroller GmbH

39.10.3.1 GUI_ALLOC_GetMaxUsedBytes()

Description

This function returns the number of the maximum number of used bytes. This function is used to get the peak of used bytes.

Prototype

```
GUI_ALLOC_DATATYPE GUI_ALLOC_GetMaxUsedBytes(void);
```

Return value

Maximum number of used bytes.

 © 2020 SEGGER Microcontroller GmbH

39.10.3.2 GUI_ALLOC_GetNumFreeBytes()

Description

This function returns the number of bytes which can be used for emWin functions.

Prototype

```
GUI_ALLOC_DATATYPE GUI_ALLOC_GetNumFreeBytes(void);
```

Return value

Number of free bytes.

 © 2020 SEGGER Microcontroller GmbH

39.10.3.3 GUI_ALLOC_GetMemInfo()

Description

This function fills the given info structure with information about the memory usage.

Prototype

```
void GUI_ALLOC_GetMemInfo(GUI_ALLOC_INFO * pInfo);
```

Parameters

Parameter	Description
pInfo	Pointer to to a GUI_ALLOC_INFO structure.

Elements of structure GUI_ALLOC_INFO

Data type	Element	Description
U32	TotalBytes	Total amount of bytes available.
U32	FreeBytes	Number of free bytes.
U32	UsedBytes	Number used bytes.
U32	AllocSize	Number of bytes available for memory management.
U32	NumFixed	Number of fixed bytes.
U32	MaxUsedBytes	The peak of used bytes.

 © 2020 SEGGER Microcontroller GmbH

39.10.3.4 GUI_ALLOC_GetNumUsedBytes()

Description

This function returns the number of bytes which are already used by emWin functions.

Prototype

```
GUI_ALLOC_DATATYPE GUI_ALLOC_GetNumUsedBytes(void);
```

Return value

Number of used bytes.

 © 2020 SEGGER Microcontroller GmbH

Chapter 40

Support

This chapter should help if any problem occurs. This could be a problem with the tool chain, with the hardware, the use of the GUI functions or with the performance and it describes how to contact emWin support.

 © 2020 SEGGER Microcontroller GmbH

40.1 Problems with tool chain (compiler, linker)

The following shows some of the problems that can occur with the use of your tool chain. The chapter tries to show what to do in case of a problem and how to contact the emWin support if needed.

40.1.1 Compiler crash

You ran into a tool chain (compiler) problem, not a problem of emWin. If one of the tools of your tool chain crashes, you should contact your compiler support:

```
"Tool internal error, please contact support"
```

40.1.2 Compiler warnings

The code of emWin has been tested on different target systems and with different compilers. We spend a lot of time on improving the quality of the code and we do our best to avoid compiler warnings. But the sensitivity of each compiler regarding warnings is different. So we can not avoid compiler warnings for unknown tools.

Warnings you should not see

These kinds of warnings should not occur:

```
"Function has no prototype"
"Incompatible pointer types"
"Variable used without having been initialized"
"Illegal redefinition of macro"
```

Warnings you may see

Warnings such as the ones below should be ignored:

```
"Integer conversion, may lose significant bits"
"Statement not reached"
"Descriptionless statements were deleted during optimization"
"Condition is always true/false"
"Unreachable code"
```

Most compilers offer a way to suppress selected warnings.

Warning "Parameter not used"

Depending of the used configuration sometimes not all of the parameters of the functions are used. To avoid compiler warnings regarding this problem you can define the macro `GUI_USE_PARA` in the file `GUIConf.h` like the following example:

```
#define GUI_USE_PARA(para) (void)para
```

emWin uses this macro wherever necessary to avoid this type of warning.

40.1.3 Compiler errors

emWin assumes that the used compiler is ANSI C compatible. The compiler should cover at least one of the following standards:

- ISO/IEC/ANSI 9899:1990 (C90) with support for C++ style comments (//)
- ISO/IEC 9899:1999 (C99)
- ISO/IEC 14882:1998 (C++)

 © 2020 SEGGER Microcontroller GmbH

Limited number of arguments in a function pointer call

But some compilers are not 100% ANSI C compatible and have for example a limitation regarding the number of arguments in a function pointer call:

```
typedef int tFunc(int a, int b, int c, int d, int e,
                  int f, int g, int h, int i, int j);
static int _Func(int a, int b, int c, int d, int e,
                 int f, int g, int h, int i, int j) {
  return a + b + c + d + e + f + g + h;
}
static void _Test(void) {
  int Result;
  tFunc * pFunc;
  pFunc = _Func;
  Result = pFunc(1, 2, 3, 4, 5, 6, 7, 8, 9, 10);
}
```

If the example above can not be compiled, only the core version of emWin can be used. The additional packages of emWin like the Window Manager or the Memory Device module sometimes need to pass up to 10 parameters with a function pointer call. The core package of emWin needs only up to 2 parameters in a function pointer call. But you can also use emWin if your compiler only supports one argument in a function pointer call. If so some functions are not available, for example rotating text or UTF-8 encoding.

40.1.4 Linker problems

Undefined externals

If your linker shows the error message "Undefined external symbols…", check if the following files have been included to the project or library:

- All source files shipped with emWin
- In case of a simple bus interface: One of the hardware routines located in the folder **Sample\LCD_X_Port** For details about this, refer to the chapter *Configuration* on page 2875.
- One of the files located in the folder **Sample\GUI_X**. Details about this can be found in the chapter *Configuration* on page 2875.

Executable to large

Some linkers are not able to link only the modules/functions referenced by the project. This results is an executable with a lot of unused code. In this case the use of a library would be very helpful. For details about how to build an emWin library, refer to the chapter *Getting Started* on page 94.

 © 2020 SEGGER Microcontroller GmbH

40.2 Problems with hardware/driver

If your tools are working fine but your display does not work may one of the following helps to find the problem.

Stack size to low?

Make sure that there have been configured enough stack. Unfortunately we can not estimate exactly how much stack will be used by your configuration and with your compiler. Further the required stack size depends a lot on the application.

Initialization of the display wrong?

Please check if the controller initialization has been adapted to your needs.

Display interface configured wrong?

When starting to work with emWin and the display does not show something you should use an oscilloscope to measure the pins connected with the display/controller. If there is a problem, check the following:

- If using a simple bus interface: Probably the hardware routines have not been configured correctly. If possible use an emulator and step through these routines.
- If using a full bus interface: Probably the register/memory access have not been configured correctly.

 © 2020 SEGGER Microcontroller GmbH

40.3 Problems with API functions

If your tool chain and your hardware works fine but the API functions do not function as documented, make a small example as described in *Contacting support* on page 2939. This allows us to easily reproduce the problem and solve it quickly.

 © 2020 SEGGER Microcontroller GmbH

40.4 Problems with the performance

If there is any performance problem with emWin it should be determined, which part of the software causes the problem.

Does the driver causes the problem?

To determine the cause of the problem the first step should be writing a small test routine which executes some test code and measures the time used to execute this code. Starting point should be the file `ProblemReport.c` described above. To measure the time used by the real hardware driver the shipment of emWin contains the driver `GUIDRV_NULL`. This driver can be used if no output to the hardware should be done. Selecting `GUIDRV_NULL` can be achieved by the same way as setting up a real driver:

```
GUI_DEVICE_CreateAndLink(GUIDRV_LIN_16, GUICC_565, 0, 0);
```

The difference between the used time by the real driver and `GUIDRV_NULL` shows the execution time spent in the real hardware driver.

Driver not optimized?

If there is a significant difference between the use of the real driver and `GUIDRV_NULL` the cause of the problem could be a not optimized driver mode. If working with a driver which does not use the default orientation (nothing mirrored, nothing swapped) the driver may not be optimized for the configured mode. In this case, please contact our support, we should be able to optimize the code.

Comparable results

To be able to measure the hardware performance for having a comparable result, emWin comes with 2 samples (located in the folder **Sample\Tutorial**) which could be used for measuring the hardware performance. The first one is `BASIC_DriverPerformance.c`. It measures the time required for different kinds of drawing operations which should be supported by each driver. The second one is `BASIC_Performance.c`. It calculates prime numbers and prints the result of reached loops/second. This sample could be used to check the basic configuration of the CPU.

 © 2020 SEGGER Microcontroller GmbH

40.5 Contacting support

If you need to contact the emWin support, send the following information to the support:

- A detailed description of the problem may written as comment in the example code.
- The configuration files `GUIConf.c`, `GUIConf.h`, `LCDConf.c`, `LCDConf.h`.
- An example source file which can be compiled in the simulation without any additional files as described in the following.
- If there are any problems with the tool chain, also send the error message of the compiler/linker.
- If there are any problems with the hardware/driver and a simple bus interface is used, also send the hardware routines including the configuration.

Problem report

The following file can be used as a starting point when creating a problem report. Also fill in the CPU, the used tool chain and the problem description. It can be found under **Sample\Tutorial\ProblemReport.c**:

```
/*********************************************************************
*                 SEGGER Microcontroller GmbH & Co. KG               *
*        Solutions for real time microcontroller applications        *
*                                                                    *
*                        emWin problem report                        *
*                                                                    *
**********************************************************************
----------------------------------------------------------------------
File                : ProblemReport.c
CPU                 :
Compiler/Tool chain :
Problem description :
----------------------------------------------------------------------
*/
#include "GUI.h"
/*  Add further GUI header files here as required. */
/*********************************************************************
*
*       Static code
*
**********************************************************************
*
* Please insert helper functions here if required.
*/
/*********************************************************************
*
*       MainTask
*/
void MainTask(void) {
  GUI_Init();
  /*
    To do:  Insert the code here which demonstrates the problem.
  */
  while (1);   /* Make sure program does not terminate */
}
```

 © 2020 SEGGER Microcontroller GmbH

40.6 FAQ

Q: *I use a different LCD controller. Can I still use emWin?*

A: Yes. The hardware access is done in the driver module and is completely independent of the rest of the GUI. The appropriate driver can be easily written for any controller (memory-mapped or bus-driven). Please get in touch with us.

Q: *Which CPUs can I use emWin with?*

A: emWin can be used with any CPU (or MPU) for which a C compiler exists. Of course, it will work faster on 16/32-bit CPUs than on 8-bit CPUs.

Q: *Is emWin flexible enough to do what I want to do in my application?*

A: emWin should be flexible enough for any application. If for some reason you do not think it is in your case, please contact us. Believe it or not, the source code is available.

Q: *Does emWin work in a multitask environment?*

A: Yes, it has been designed with multitask kernels in mind.

 © 2020 SEGGER Microcontroller GmbH

Chapter 41

Indexes

 © 2020 SEGGER Microcontroller GmbH

41.1 Function index

APPW_GetFont, **167**
APPW_GetVarData, **168**
APPW_SetVarData, **169**
BUTTON_Callback, 968
BUTTON_Create, **989**
BUTTON_CreateAsChild, **990**
BUTTON_CreateEx, **991**
BUTTON_CreateIndirect, 794, 794, **992**, 2224, 2231, 2231
BUTTON_CreateUser, **993**
BUTTON_GetBitmap, **994**
BUTTON_GetBkColor, **995**
BUTTON_GetDefaultBkColor, **996**
BUTTON_GetDefaultFont, **997**
BUTTON_GetDefaultTextAlign, **998**
BUTTON_GetDefaultTextColor, **999**
BUTTON_GetFont, **1000**
BUTTON_GetSkinFlexProps, 2295
BUTTON_GetText, **1001**
BUTTON_GetTextAlign, **1002**
BUTTON_GetTextColor, **1003**
BUTTON_GetUserData, **1004**
BUTTON_IsPressed, **1005**
BUTTON_SetBitmap, **1006**
BUTTON_SetBitmapEx, **1007**
BUTTON_SetBkColor, **1008**
BUTTON_SetBMP, **1009**
BUTTON_SetBMPEx, **1010**
BUTTON_SetDefaultBkColor, **1011**
BUTTON_SetDefaultFocusColor, **1012**
BUTTON_SetDefaultFont, **1013**
BUTTON_SetDefaultSkin, 2293
BUTTON_SetDefaultTextAlign, **1014**
BUTTON_SetDefaultTextColor, **1015**
BUTTON_SetFocusColor, **1016**
BUTTON_SetFont, **1018**
BUTTON_SetFrameColor, **1019**
BUTTON_SetPressed, **1020**
BUTTON_SetReactOnLevel, **1021**
BUTTON_SetReactOnTouch, **1022**
BUTTON_SetSkin, 2293
BUTTON_SetSkinFlexProps, 2295, **2309**
BUTTON_SetStreamedBitmap, **1023**, 1023
BUTTON_SetStreamedBitmapEx, **1024**
BUTTON_SetText, **1025**, 2225
BUTTON_SetTextAlign, **1026**
BUTTON_SetTextColor, **1027**
BUTTON_SetTextOffset, **1028**
BUTTON_SetUserData, **1029**
CALENDAR_AddKey, **2242**
CALENDAR_Create, **2243**
CALENDAR_GetDate, **2244**
CALENDAR_GetDaysOfMonth, **2245**
CALENDAR_GetSel, **2246**
CALENDAR_GetWeekday, **2247**
CALENDAR_SetDate, **2248**
CALENDAR_SetDefaultBkColor, **2250**
CALENDAR_SetDefaultColor, **2251**
CALENDAR_SetDefaultDays, **2252**
CALENDAR_SetDefaultFont, **2253**
CALENDAR_SetDefaultMonths, **2254**
CALENDAR_SetDefaultSize, **2255**
CALENDAR_SetSel, **2249**
CALENDAR_ShowDate, **2256**
CHECKBOX_Create, **1038**
CHECKBOX_CreateEx, **1039**
CHECKBOX_CreateIndirect, 2231, 2231
CHECKBOX_GetBkColor, **1042**
CHECKBOX_GetBoxBkColor, **1043**
CHECKBOX_GetDefaultAlign, **1044**
CHECKBOX_GetDefaultBkColor, **1045**
CHECKBOX_GetDefaultFont, **1046**
CHECKBOX_GetDefaultSpacing, **1047**
CHECKBOX_GetDefaultTextColor, **1049**
CHECKBOX_GetFocusColor, **1050**

 © 2020 SEGGER Microcontroller GmbH

CHECKBOX_GetFont, **1051**
CHECKBOX_GetImage, **1052**
CHECKBOX_GetSkinFlexButtonSize, **2314**
CHECKBOX_GetState, **1053**
CHECKBOX_GetText, **1054**
CHECKBOX_GetTextAlign, **1055**
CHECKBOX_GetTextColor, **1056**
CHECKBOX_IsChecked, **1058**
CHECKBOX_SetBkColor, **1059**
CHECKBOX_SetBoxBkColor, **1060**
CHECKBOX_SetDefaultAlign, **1061**
CHECKBOX_SetDefaultBkColor, **1062**
CHECKBOX_SetDefaultFocusColor, **1063**
CHECKBOX_SetDefaultFont, **1064**
CHECKBOX_SetDefaultImage, **1065**
CHECKBOX_SetDefaultSpacing, **1066**
CHECKBOX_SetDefaultTextColor, **1068**
CHECKBOX_SetFocusColor, **1069**
CHECKBOX_SetFont, **1070**
CHECKBOX_SetImage, **1071**
CHECKBOX_SetNumStates, **1072**
CHECKBOX_SetSkinFlexButtonSize, **2315**
CHECKBOX_SetSkinFlexProps, **2316**
CHECKBOX_SetSpacing, **1073**
CHECKBOX_SetState, **1074**
CHECKBOX_SetText, **1075**
CHECKBOX_SetTextAlign, **1076**
CHECKBOX_SetTextColor, **1077**
CHOOSECOLOR_Create, **2263**
CHOOSECOLOR_GetSel, **2264**
CHOOSECOLOR_SetDefaultBorder, **2268**
CHOOSECOLOR_SetDefaultButtonSize, **2269**
CHOOSECOLOR_SetDefaultColor, **2266**
CHOOSECOLOR_SetDefaultSpace, **2267**
CHOOSECOLOR_SetSel, **2265**
CHOOSEFILE_Create, **2273**
CHOOSEFILE_EnableToolTips, **2276**
CHOOSEFILE_SetButtonText, **2277**
CHOOSEFILE_SetDefaultButtonText, **2278**
CHOOSEFILE_SetDelim, **2279**
CHOOSEFILE_SetToolTips, **2280**
CHOOSEFILE_SetTopMode, **2281**
Draw, 725, 726, 2564, 2565
DROPDOWN_AddString, **1087**
DROPDOWN_Callback, 968
DROPDOWN_Collapse, **1088**
DROPDOWN_Create, **1089**
DROPDOWN_CreateEx, **1090**
DROPDOWN_CreateIndirect, **1091**
DROPDOWN_CreateUser, **1092**
DROPDOWN_DecSel, **1093**
DROPDOWN_DecSelExp, **1094**
DROPDOWN_DeleteItem, **1095**
DROPDOWN_Expand, **1096**
DROPDOWN_GetBkColor, **1097**
DROPDOWN_GetColor, **1098**
DROPDOWN_GetDefaultFont, **1099**
DROPDOWN_GetFont, **1100**
DROPDOWN_GetItemDisabled, **1101**
DROPDOWN_GetItemText, **1102**
DROPDOWN_GetListbox, **1103**
DROPDOWN_GetNumItems, **1104**
DROPDOWN_GetSel, **1105**
DROPDOWN_GetSelExp, **1106**
DROPDOWN_GetTextColor, **1107**
DROPDOWN_GetUserData, **1108**
DROPDOWN_IncSel, **1109**
DROPDOWN_IncSelExp, **1110**
DROPDOWN_InsertString, **1111**
DROPDOWN_SetAutoScroll, **1112**
DROPDOWN_SetBkColor, **1113**
DROPDOWN_SetColor, **1114**
DROPDOWN_SetDefaultColor, **1115**
DROPDOWN_SetDefaultFont, **1116**
DROPDOWN_SetDefaultScrollbarColor, **1117**
DROPDOWN_SetFont, **1118**

 © 2020 SEGGER Microcontroller GmbH

DROPDOWN_SetItemDisabled, **1119**
DROPDOWN_SetItemSpacing, **1120**
DROPDOWN_SetListHeight, **1121**
DROPDOWN_SetScrollbarColor, **1122**
DROPDOWN_SetScrollbarWidth, **1123**
DROPDOWN_SetSel, **1124**
DROPDOWN_SetSelExp, **1125**
DROPDOWN_SetSkinFlexProps, **2321**
DROPDOWN_SetTextAlign, **1126**
DROPDOWN_SetTextColor, **1127**
DROPDOWN_SetTextHeight, **1128**
DROPDOWN_SetUpMode, **1129**
DROPDOWN_SetUserData, **1130**
EDIT_AddKey, **1138**
EDIT_Create, **1139**
EDIT_CreateAsChild, **1140**
EDIT_CreateEx, **1141**
EDIT_CreateIndirect, **1142**, 2231, 2231, 2231, 2231
EDIT_CreateUser, **1143**
EDIT_EnableBlink, **1144**
EDIT_EnableInversion, **1145**
EDIT_GetBkColor, **1146**
EDIT_GetBorderSize, **1147**
EDIT_GetCharAtPixel, **1148**
EDIT_GetCursorCharPos, **1149**
EDIT_GetCursorPixelPos, **1150**
EDIT_GetDefaultBkColor, **1151**
EDIT_GetDefaultFont, **1152**
EDIT_GetDefaultTextAlign, **1153**
EDIT_GetDefaultTextColor, **1154**
EDIT_GetFloatValue, **1155**
EDIT_GetFont, **1156**
EDIT_GetNumChars, **1157**
EDIT_GetSel, **1158**
EDIT_GetSelText, **1159**
EDIT_GetText, **1160**
EDIT_GetTextAlign, **1161**
EDIT_GetTextColor, **1162**
EDIT_GetUserData, **1163**
EDIT_GetValue, **1164**
EDIT_SetBinMode, **1165**, 2232, 2233
EDIT_SetBkColor, **1166**
EDIT_SetCursorAtChar, **1167**
EDIT_SetCursorAtPixel, **1168**
EDIT_SetDecMode, **1169**
EDIT_SetDefaultBkColor, **1170**
EDIT_SetDefaultFont, **1171**
EDIT_SetDefaultTextAlign, **1172**
EDIT_SetDefaultTextColor, **1173**
EDIT_SetFloatMode, **1174**
EDIT_SetFloatValue, **1175**
EDIT_SetFont, **1177**
EDIT_SetHexMode, **1178**, 2232, 2233
EDIT_SetInsertMode, **1179**
EDIT_SetMaxLen, **1180**
EDIT_SetpfAddKeyEx, **1181**
EDIT_SetSel, **1182**, 1182, 1182, 1182
EDIT_SetText, **1183**, 2232, 2232, 2233, 2233
EDIT_SetTextAlign, **1184**, 2232, 2233
EDIT_SetTextColor, **1185**
EDIT_SetTextMode, **1186**
EDIT_SetUlongMode, **1188**
EDIT_SetUserData, **1189**
EDIT_SetValue, **1187**
FRAMEWIN_AddButton, **1203**
FRAMEWIN_AddCloseButton, **1204**
FRAMEWIN_AddMaxButton, **1205**
FRAMEWIN_AddMenu, **1206**
FRAMEWIN_AddMinButton, **1207**
FRAMEWIN_Create, **1208**
FRAMEWIN_CreateAsChild, **1209**
FRAMEWIN_CreateEx, **1210**
FRAMEWIN_CreateIndirect, 794, **1211**, 2224, 2231
FRAMEWIN_CreateUser, **1212**
FRAMEWIN_DrawSkinFlex, 2297, 2297
FRAMEWIN_GetActive, **1213**

 © 2020 SEGGER Microcontroller GmbH

FRAMEWIN_GetBarColor, **1214**
FRAMEWIN_GetBorderSize, **1215**
FRAMEWIN_GetDefaultBarColor, **1216**
FRAMEWIN_GetDefaultBorderSize, **1217**
FRAMEWIN_GetDefaultClientColor, **1218**
FRAMEWIN_GetDefaultFont, **1219**
FRAMEWIN_GetDefaultTextColor, **1220**
FRAMEWIN_GetDefaultTitleHeight, **1221**
FRAMEWIN_GetFont, **1222**, 1245
FRAMEWIN_GetText, **1223**, 1245, 2297
FRAMEWIN_GetTextAlign, **1224**, 1245
FRAMEWIN_GetTitleHeight, **1225**
FRAMEWIN_GetUserData, **1226**
FRAMEWIN_IsMaximized, **1228**
FRAMEWIN_IsMinimized, **1227**
FRAMEWIN_Maximize, **1229**
FRAMEWIN_Minimize, **1230**
FRAMEWIN_OwnerDraw, **1231**, 1245
FRAMEWIN_Restore, **1232**
FRAMEWIN_SetActive, **1233**
FRAMEWIN_SetBarColor, **1234**
FRAMEWIN_SetBorderSize, **1235**
FRAMEWIN_SetClientColor, **1236**
FRAMEWIN_SetDefaultBarColor, **1237**
FRAMEWIN_SetDefaultBorderSize, **1238**
FRAMEWIN_SetDefaultClientColor, **1239**
FRAMEWIN_SetDefaultFont, **1240**
FRAMEWIN_SetDefaultTextColor, **1241**
FRAMEWIN_SetDefaultTitleHeight, **1242**
FRAMEWIN_SetFont, **1243**, 2225
FRAMEWIN_SetMoveable, **1244**
FRAMEWIN_SetOwnerDraw, **1245**, 1245
FRAMEWIN_SetResizeable, **1247**
FRAMEWIN_SetSkin, 2297
FRAMEWIN_SetSkinFlexProps, **2326**
FRAMEWIN_SetText, **1248**, 2234, 2234
FRAMEWIN_SetTextAlign, **1249**, 2225
FRAMEWIN_SetTextColor, **1250**
FRAMEWIN_SetTextColorEx, **1251**
FRAMEWIN_SetTitleHeight, **1252**
FRAMEWIN_SetTitleVis, **1253**
FRAMEWIN_SetUserData, **1254**
GAUGE_CreateIndirect, **1261**
GAUGE_CreateUser, **1262**
GAUGE_GetValue, **1263**
GAUGE_SetAlign, **1264**
GAUGE_SetBkColor, **1265**
GAUGE_SetColor, **1266**
GAUGE_SetOffset, **1267**
GAUGE_SetRadius, **1268**
GAUGE_SetRange, **1269**
GAUGE_SetRoundedEnd, **1270**
GAUGE_SetRoundedValue, **1271**
GAUGE_SetValue, **1272**
GAUGE_SetValueRange, **1273**
GAUGE_SetWidth, **1274**
GRAPH_AttachData, 1277, **1282**
GRAPH_AttachScale, 1277, **1283**
GRAPH_CreateEx, 1277, **1284**, 1304, 1328
GRAPH_CreateIndirect, **1285**
GRAPH_CreateUser, **1286**
GRAPH_DATA_XY_AddPoint, **1317**
GRAPH_DATA_XY_Clear, **1318**
GRAPH_DATA_XY_Create, **1319**, 1328
GRAPH_DATA_XY_Delete, **1320**
GRAPH_DATA_XY_GetLineVis, **1321**
GRAPH_DATA_XY_GetPoint, **1322**
GRAPH_DATA_XY_GetPointVis, **1323**
GRAPH_DATA_XY_SetColor, **1324**
GRAPH_DATA_XY_SetLineStyle, **1325**
GRAPH_DATA_XY_SetLineVis, **1326**
GRAPH_DATA_XY_SetOffX, **1327**, 1327
GRAPH_DATA_XY_SetOffY, **1327**, 1327
GRAPH_DATA_XY_SetOwnerDraw, **1328**, 1328
GRAPH_DATA_XY_SetPenSize, **1329**
GRAPH_DATA_XY_SetPointVis, **1330**

 © 2020 SEGGER Microcontroller GmbH

GRAPH_DATA_YT_AddValue, **1308**
GRAPH_DATA_YT_Clear, **1309**
GRAPH_DATA_YT_Create, 1277, **1310**
GRAPH_DATA_YT_Delete, **1311**
GRAPH_DATA_YT_GetValue, **1312**
GRAPH_DATA_YT_MirrorX, **1313**
GRAPH_DATA_YT_SetAlign, **1314**
GRAPH_DATA_YT_SetColor, **1315**
GRAPH_DATA_YT_SetOffY, **1316**, 1316
GRAPH_DetachData, **1287**
GRAPH_DetachScale, **1288**
GRAPH_GetColor, **1289**
GRAPH_GetScrollValue, **1290**
GRAPH_GetUserData, **1291**
GRAPH_InvertScrollbar, **1292**
GRAPH_SCALE_Create, 1277, **1331**
GRAPH_SCALE_Delete, **1332**
GRAPH_SCALE_SetFactor, **1333**
GRAPH_SCALE_SetFont, **1334**
GRAPH_SCALE_SetNumDecs, **1335**
GRAPH_SCALE_SetOff, **1336**
GRAPH_SCALE_SetPos, **1337**
GRAPH_SCALE_SetTextColor, **1338**
GRAPH_SCALE_SetTickDist, **1339**
GRAPH_SetAutoScrollbar, **1293**
GRAPH_SetBorder, **1294**
GRAPH_SetColor, **1295**
GRAPH_SetGridDistX, **1296**
GRAPH_SetGridDistY, **1296**
GRAPH_SetGridFixedX, **1297**
GRAPH_SetGridOffX, **1298**
GRAPH_SetGridOffY, **1299**
GRAPH_SetGridVis, **1300**
GRAPH_SetLineStyleH, **1301**
GRAPH_SetLineStyleV, **1301**
GRAPH_SetScrollValue, **1302**
GRAPH_SetUserData, **1303**
GRAPH_SetUserDraw, **1304**, 1305
GRAPH_SetVSizeX, **1306**
GRAPH_SetVSizeY, **1306**
GUI__memcpy, 2901
GUI_AA_DisableHiRes, **2540**, 2565
GUI_AA_DrawArc, **2545**
GUI_AA_DrawCircle, **2546**
GUI_AA_DrawLine, 2537, 2537, **2547**, 2561, 2561, 2563
GUI_AA_DrawPolyOutline, **2548**, 2548
GUI_AA_DrawPolyOutlineEx, **2549**
GUI_AA_DrawRoundedRect, **2550**, 2550
GUI_AA_DrawRoundedRectEx, **2551**
GUI_AA_EnableGammaAA4, **2558**
GUI_AA_EnableHiRes, **2541**, 2563, 2565
GUI_AA_FillCircle, 700, **2552**
GUI_AA_FillEllipse, **2553**
GUI_AA_FillPolygon, **2554**, 2564, 2564
GUI_AA_FillRoundedRect, **2555**, 2555
GUI_AA_FillRoundedRectEx, **2556**
GUI_AA_GetFactor, **2542**
GUI_AA_GetGammaAA4, **2559**
GUI_AA_SetDrawMode, **2557**
GUI_AA_SetFactor, **2544**, 2561, 2561, 2563, 2565
GUI_AA_SetFuncDrawArc, **2923**
GUI_AA_SetFuncDrawCircle, **2920**
GUI_AA_SetFuncDrawLine, **2921**
GUI_AA_SetFuncDrawPolyOutline, **2922**
GUI_AA_SetFuncFillCircle, **2918**
GUI_AA_SetFuncFillPolygon, **2919**
GUI_AA_SetGammaAA4, **2560**
GUI_AA_SetpfDrawCharAA4, **2912**
GUI_AddRect, **251**
GUI_ALLOC_AssignMemory, **2880**, 2881
GUI_ALLOC_GetMaxUsedBytes, **2929**
GUI_ALLOC_GetMemInfo, **2931**
GUI_ALLOC_GetNumFreeBytes, **2930**
GUI_ALLOC_GetNumUsedBytes, **2932**
GUI_AlphaEnableFillRectHW, **2907**
GUI_ANIM_AddItem, 595, 597, **601**

 © 2020 SEGGER Microcontroller GmbH

GUI_ANIM_Create, 594, 598, 599, **602**
GUI_ANIM_Delete, **603**
GUI_ANIM_DeleteAll, **604**
GUI_ANIM_Exec, **605**, 605
GUI_ANIM_GetData, **606**
GUI_ANIM_GetFirst, **607**
GUI_ANIM_GetItemData, **608**
GUI_ANIM_GetNext, **609**
GUI_ANIM_GetNumItems, **610**
GUI_ANIM_IsRunning, **611**
GUI_ANIM_Start, **612**
GUI_ANIM_StartEx, 598, 599, **613**
GUI_ANIM_Stop, **614**
GUI_AssignCursorLayer, **2418**
GUI_BARCODE_Draw, **336**, 336, 336
GUI_BARCODE_GetXSize, **338**
GUI_BMP_Draw, **387**
GUI_BMP_DrawEx, **388**
GUI_BMP_DrawScaled, **389**
GUI_BMP_DrawScaledEx, **390**
GUI_BMP_EnableAlpha, **391**
GUI_BMP_GetXSize, **392**
GUI_BMP_GetXSizeEx, **393**
GUI_BMP_GetYSize, **394**
GUI_BMP_GetYSizeEx, **395**
GUI_BMP_Serialize, **396**, 396
GUI_BMP_SerializeEx, **397**
GUI_BMP_SerializeExBpp, **398**
GUI_CalcColorDist, **660**
GUI_CalcVisColorError, **661**
GUI_Clear, 150, 186, 231, 232, 258, **260**, 260, 286, 289, 322, 324, 326, 333, 622, 682, 683, 700, 700, 701, 706, 716, 786, 795, 795, 821, 828, 878, 884, 901, 901, 961, 961, 962, 2405, 2405, 2409, 2410, 2550, 2555, 2561, 2563
GUI_ClearKeyBuffer, **2499**
GUI_ClearRect, **261**, 2564, 2564
GUI_Color2Index, **662**
GUI_Color2VisColor, **663**
GUI_ColorIsAvailable, **664**
GUI_CopyRect, **262**
GUI_CreateBitmapFromStream, **298**, 298
GUI_CreateDialogBox, 794, 2225, **2236**
GUI_CURSOR_GetState, **2526**
GUI_CURSOR_Hide, **2527**
GUI_CURSOR_Select, **2528**
GUI_CURSOR_SelectAnim, **2529**
GUI_CURSOR_SetPosition, **2530**
GUI_CURSOR_Show, **2531**
GUI_DCACHE_Clear, **2926**
GUI_DCACHE_SetClearCacheHook, **2927**
GUI_Delay, 191, 260, 271, 327, 333, 598, 683, 701, 795, 795, 829, 884, 961, 962, 962, 962, 2228, 2405, 2407, 2475, 2562, 2563, 2565, 2569, **2854**
GUI_DEVICE_Create, 2647, 2651, 2651, 2652, 2652
GUI_DEVICE_CreateAndLink, 641, 2377, 2377, 2411, 2411, 2413, 2413, 2415, 2618, 2643, 2646, 2647, 2647, 2651, 2652, 2653, 2655, 2673, 2677, 2679, 2681, 2685, 2689, 2689, 2696, 2699, 2701, 2705, 2707, 2716, 2718, 2724, 2727, 2741, 2742, 2745, 2746, 2749, 2751, 2757, 2761, 2762, 2764, 2767, 2770, 2773, 2776, 2886, **2889**, 2938
GUI_DIRTYDEVICE_Create, **353**
GUI_DIRTYDEVICE_CreateEx, **354**
GUI_DIRTYDEVICE_Delete, **355**
GUI_DIRTYDEVICE_DeleteEx, **356**
GUI_DIRTYDEVICE_Fetch, **357**
GUI_DIRTYDEVICE_FetchEx, **358**
GUI_DispBin, **238**, 238
GUI_DispBinAt, **239**, 239
GUI_DispCEOL, **191**, 191
GUI_DispChar, **192**, 192, 901, 901, 2577, 2577
GUI_DispCharAt, **193**, 193
GUI_DispChars, **194**, 194
GUI_DispDec, **225**, 225, 225, 504, 731, 731, 731, 731
GUI_DispDecAt, 108, 213, **226**
GUI_DispDecMin, **227**, 227, 901, 901
GUI_DispDecShift, **228**
GUI_DispDecSpace, **229**, 229
GUI_DispFloat, **232**, 232, 232
GUI_DispFloatFix, 232, 232, **234**
GUI_DispFloatMin, 232, 232, **235**

 © 2020 SEGGER Microcontroller GmbH

GUI_DispHex, **240**, 240
GUI_DispHexAt, **241**, 241
GUI_DispNextLine, **214**, 2569
GUI_DispSDec, **230**
GUI_DispSDecShift, **231**, 231
GUI_DispSFloatFix, 232, 232, **236**
GUI_DispSFloatMin, 232, 232, **237**
GUI_DispString, 108, 108, 185, **195**, 195, 195, 215, 225, 225, 227, 229, 242, 476, 479, 479, 502, 504, 686, 716, 731, 731, 731, 731, 795, 795, 961, 2318, 2563, 2563, 2563, 2563, 2563, 2567, 2568, 2569
GUI_DispStringAt, 151, 191, 191, **196**, 196, 231, 232, 232, 232, 232, 232, 260, 326, 326, 504, 504, 504, 716, 786, 961, 966, 2398, 2398, 2398, 2563
GUI_DispStringAtCEOL, **197**
GUI_DispStringHCenterAt, 186, 186, 186, 186, 187, **198**, 286, 289, 290, 334, 2405, 2405, 2409, 2561, 2561, 2561, 2564, 2564
GUI_DispStringInRect, **199**, 199, 706, 1245, 2297
GUI_DispStringInRectEx, **200**, 200, 701
GUI_DispStringInRectWrap, **201**, 201
GUI_DispStringInRectWrapEx, **202**
GUI_DispStringLen, **203**
GUI_DrawArc, **333**, 333
GUI_DrawBitmap, 290, **292**, 292, 298, 1428, 2297
GUI_DrawBitmapEx, **293**
GUI_DrawBitmapMag, **294**
GUI_DrawCircle, **328**, 328
GUI_DrawEllipse, **330**, 332
GUI_DrawEllipseXL, **331**
GUI_DrawGradientH, **263**, 263, 683, 1245
GUI_DrawGradientHEx, **264**
GUI_DrawGradientMH, **271**, 271
GUI_DrawGradientMHEx, **272**
GUI_DrawGradientMV, **271**
GUI_DrawGradientMVEx, **272**
GUI_DrawGradientRoundedH, **267**, 267
GUI_DrawGradientRoundedHEx, **268**
GUI_DrawGradientRoundedV, **269**, 269
GUI_DrawGradientRoundedVEx, **270**
GUI_DrawGradientV, **265**, 265, 682, 700, 706
GUI_DrawGradientVEx, **266**
GUI_DrawGraph, **335**, 335
GUI_DrawHLine, 290, **311**, 1650, 1650, 2410
GUI_DrawLine, 186, 186, **312**, 396, 670, 682, 682, 701, 731, 2561
GUI_DrawLineRel, **313**
GUI_DrawLineTo, **314**
GUI_DrawPie, **344**, 344
GUI_DrawPixel, **273**
GUI_DrawPoint, **274**, 333, 2475
GUI_DrawPolygon, **321**
GUI_DrawPolyLine, **315**
GUI_DrawRect, **275**, 706, 1328
GUI_DrawRectEx, **276**
GUI_DrawRoundedFrame, **277**
GUI_DrawRoundedFrameEx, **278**
GUI_DrawRoundedRect, **279**
GUI_DrawRoundedRectEx, **280**
GUI_DrawStreamedBitmap, **302**
GUI_DrawStreamedBitmapAuto, **303**
GUI_DrawStreamedBitmapEx, **304**
GUI_DrawStreamedBitmapExAuto, **305**
GUI_DrawVLine, **316**
GUI_EditBin, **1190**
GUI_EditDec, **1191**
GUI_EditFloat, **1192**
GUI_EditHex, **1193**
GUI_EditString, **1194**
GUI_EnableAlpha, 286, 286, **287**, 289
GUI_EndDialog, 2234, 2234, 2234, 2234, **2239**
GUI_EnlargePolygon, **322**, 322
GUI_ErrorOut, **2855**
GUI_Exec, 759, 763, 768, 927, **2856**
GUI_Exec1, **2857**
GUI_ExecCreatedDialog, **2237**
GUI_ExecDialogBox, 2231, **2238**
GUI_Exit, **106**
GUI_FillCircle, 258, 258, 290, **329**, 329, 2409, 2410
GUI_FillEllipse, **332**, 332, 332
GUI_FillPolygon, 322, 322, **323**, 324, 326

 © 2020 SEGGER Microcontroller GmbH

GUI_FillRect, **281**, 286, 286, 286, 289, 289, 289, 2398, 2398, 2398, 2405, 2409, 2409, 2409, 2409, 2409
GUI_FillRectEx, 200, 201, **282**
GUI_FillRoundedRect, **283**
GUI_FillRoundedRectEx, **284**
GUI_GCACHE_4_Create, **368**
GUI_GCACHE_4_CreateEx, **369**
GUI_GetBkColor, **648**
GUI_GetBkColorIndex, **649**
GUI_GetCharDistX, **489**
GUI_GetCharFromPos, **204**
GUI_GetClientRect, 199, **252**
GUI_GetClipRect, **253**
GUI_GetColor, **650**
GUI_GetColorIndex, **651**
GUI_GetDefaultBkColor, **653**
GUI_GetDefaultColor, **652**
GUI_GetDefaultFont, **490**
GUI_GetDispPosX, **216**
GUI_GetDispPosY, **217**
GUI_GetDrawMode, **254**
GUI_GetFont, **491**
GUI_GetFontDistY, **492**
GUI_GetFontInfo, **493**, 493
GUI_GetFontSizeY, **494**
GUI_GetKey, **2500**
GUI_GetKeyState, **2501**
GUI_GetLayerPosEx, **2419**
GUI_GetLeadingBlankCols, **495**
GUI_GetLineStyle, **317**
GUI_GetOrg, **2402**
GUI_GetPenSize, **255**
GUI_GetPixelIndex, **256**
GUI_GetStreamedBitmapInfo, **307**
GUI_GetStreamedBitmapInfoEx, **308**
GUI_GetStringDistX, **496**
GUI_GetStringDistXEx, **497**
GUI_GetTextAlign, **211**
GUI_GetTextExtend, **498**
GUI_GetTextMode, **207**
GUI_GetTime, **2858**
GUI_GetTimeSlice, **2859**
GUI_GetTrailingBlankCols, **499**
GUI_GetVersionString, **242**, 242
GUI_GetYDistOfFont, **500**
GUI_GetYSizeOfFont, **501**
GUI_GIF_Draw, **411**
GUI_GIF_DrawEx, **412**
GUI_GIF_DrawSub, **413**
GUI_GIF_DrawSubEx, **414**
GUI_GIF_DrawSubScaled, **415**
GUI_GIF_DrawSubScaledEx, **416**
GUI_GIF_GetComment, **417**
GUI_GIF_GetCommentEx, **418**
GUI_GIF_GetImageInfo, **419**
GUI_GIF_GetImageInfoEx, **420**
GUI_GIF_GetInfo, **421**
GUI_GIF_GetInfoEx, **422**
GUI_GIF_GetXSize, **423**
GUI_GIF_GetXSizeEx, **424**
GUI_GIF_GetYSize, **425**
GUI_GIF_GetYSizeEx, **426**
GUI_GotoX, **215**, 232, 232, 232, 232, 232
GUI_GotoXY, **215**, 215, 901, 901
GUI_GotoY, **215**
GUI_Index2Color, **665**
GUI_Init, **104**, 108, 108, 150, 231, 271, 292, 327, 335, 396, 399, 682, 700, 716, 731, 734, 759, 795, 828, 884, 962, 1328, 1374, 2228, 2405, 2474, 2475, 2550, 2555, 2562, 2563, 2565, 2569, 2833, 2939
GUI_InvertRect, **285**
GUI_IsInFont, **502**, 502
GUI_IsInitialized, **105**
GUI_JPEG_Draw, 399, **402**, 695
GUI_JPEG_DrawEx, **403**
GUI_JPEG_DrawScaled, **404**
GUI_JPEG_DrawScaledEx, **405**
GUI_JPEG_GetInfo, **406**
GUI_JPEG_GetInfoEx, **407**

 © 2020 SEGGER Microcontroller GmbH

GUI_JPEG_SetpfDrawEx, **2916**
GUI_LANG_Clear, **2589**
GUI_LANG_GetLang, **2590**
GUI_LANG_GetNumItems, **2591**
GUI_LANG_GetText, **2592**
GUI_LANG_GetTextBuffered, **2593**
GUI_LANG_GetTextBufferedEx, **2594**
GUI_LANG_GetTextEx, **2595**
GUI_LANG_GetTextLen, **2596**
GUI_LANG_GetTextLenEx, **2597**
GUI_LANG_LoadCSV, **2587**
GUI_LANG_LoadCSVEx, **2588**
GUI_LANG_LoadText, **2585**
GUI_LANG_LoadTextEx, **2586**
GUI_LANG_SetLang, **2598**
GUI_LANG_SetMaxNumLang, **2599**
GUI_LANG_SetSep, **2600**
GUI_MagnifyPolygon, **324**, 324
GUI_MEASDEV_ClearRect, **727**
GUI_MEASDEV_Create, **728**, 731
GUI_MEASDEV_Delete, **729**, 731
GUI_MEASDEV_GetRect, **730**, 731
GUI_MEASDEV_Select, **731**, 731
GUI_MEMDEV_BlendColor32, **741**
GUI_MEMDEV_BlendWinBk, **749**
GUI_MEMDEV_BlurAndBlendWinBk, **750**
GUI_MEMDEV_BlurWinBk, **751**
GUI_MEMDEV_Clear, **681**
GUI_MEMDEV_ClearAlpha, **682**, 683
GUI_MEMDEV_CopyFromLCD, **684**
GUI_MEMDEV_CopyToLCD, 670, **685**, 716
GUI_MEMDEV_CopyToLCDAA, **686**, 686
GUI_MEMDEV_CopyToLCDAt, **687**, 695, 695, 695, 706, 706
GUI_MEMDEV_Create, 670, 686, **688**, 716, 716
GUI_MEMDEV_CreateAuto, **723**, 726, 2564
GUI_MEMDEV_CreateBlurredDevice32, **742**
GUI_MEMDEV_CreateBlurredDevice32HQ, **744**
GUI_MEMDEV_CreateBlurredDevice32LQ, **745**
GUI_MEMDEV_CreateCopy, **689**
GUI_MEMDEV_CreateEx, **690**
GUI_MEMDEV_CreateFixed, 682, 683, **691**, 691, 695, 695, 695, 700, 701, 706, 706
GUI_MEMDEV_CreateFixed32, **692**
GUI_MEMDEV_Delete, **693**
GUI_MEMDEV_DeleteAuto, **724**, 726
GUI_MEMDEV_Dither32, **746**
GUI_MEMDEV_Draw, **721**
GUI_MEMDEV_DrawAuto, **725**, 726, 2565, 2565
GUI_MEMDEV_DrawPerspectiveX, **694**, 695, 695
GUI_MEMDEV_FadeInDevices, **732**
GUI_MEMDEV_FadeInWindow, **736**
GUI_MEMDEV_FadeOutDevices, **733**
GUI_MEMDEV_FadeOutWindow, **736**
GUI_MEMDEV_GetDataPtr, **696**
GUI_MEMDEV_GetXSize, **697**
GUI_MEMDEV_GetYSize, **698**
GUI_MEMDEV_MarkDirty, **699**
GUI_MEMDEV_MoveInWindow, **737**
GUI_MEMDEV_MoveOutWindow, **737**
GUI_MEMDEV_MULTIBUF_Enable, **752**
GUI_MEMDEV_PunchOutDevice, **700**, 701
GUI_MEMDEV_ReduceYSize, **702**
GUI_MEMDEV_Select, 670, 670, 682, 682, 683, 683, 686, 691, 695, 695, 695, 700, 701, 701, 706, 706, 706, **708**, 716, 716
GUI_MEMDEV_SerializeBMP, **709**
GUI_MEMDEV_SetAnimationCallback, **734**, 734
GUI_MEMDEV_SetBlurHQ, **747**
GUI_MEMDEV_SetBlurLQ, **748**
GUI_MEMDEV_SetDrawMemdev16bppFunc, **2914**
GUI_MEMDEV_SetOrg, **710**
GUI_MEMDEV_SetTimePerFrame, **735**
GUI_MEMDEV_ShiftInWindow, **739**
GUI_MEMDEV_ShiftOutWindow, **739**
GUI_MEMDEV_SwapWindow, **740**
GUI_MEMDEV_Write, 683, 701, **711**
GUI_MEMDEV_WriteAlpha, **712**
GUI_MEMDEV_WriteAlphaAt, **713**

 © 2020 SEGGER Microcontroller GmbH

GUI_MEMDEV_WriteAt, **714**
GUI_MEMDEV_WriteEx, **715**
GUI_MEMDEV_WriteExAt, **716**, 716
GUI_MEMDEV_WriteOpaque, **717**
GUI_MEMDEV_WriteOpaqueAt, **718**
GUI_MessageBox, **2286**
GUI_MOUSE_DRIVER_PS2_Init, **2444**
GUI_MOUSE_DRIVER_PS2_OnRx, 2443, **2445**
GUI_MOUSE_GetState, **2441**
GUI_MOUSE_StoreState, **2442**, 2442
GUI_MoveRel, **318**
GUI_MoveTo, **319**
GUI_MOVIE_Create, **573**
GUI_MOVIE_CreateEx, **574**
GUI_MOVIE_Delete, **575**
GUI_MOVIE_DrawFrame, **576**
GUI_MOVIE_GetFrameIndex, **577**
GUI_MOVIE_GetInfo, **578**
GUI_MOVIE_GetInfoEx, **579**
GUI_MOVIE_GetInfoH, **580**
GUI_MOVIE_GetNumFrames, **581**
GUI_MOVIE_GetPos, **582**
GUI_MOVIE_GotoFrame, **583**
GUI_MOVIE_Pause, **584**
GUI_MOVIE_Play, **585**
GUI_MOVIE_SetPeriod, **586**
GUI_MOVIE_SetpfNotify, **587**
GUI_MOVIE_SetPos, **588**
GUI_MOVIE_Show, **589**
GUI_MTOUCH_Enable, 2474, 2475, **2481**
GUI_MTOUCH_GetEvent, 2475, **2482**
GUI_MTOUCH_GetTouchInput, 2475, **2483**
GUI_MTOUCH_IsEmpty, **2484**
GUI_MTOUCH_SetOrientation, **2485**
GUI_MTOUCH_StoreEvent, **2486**
GUI_MULTIBUF_Begin, 598, **2382**
GUI_MULTIBUF_BeginEx, **2383**
GUI_MULTIBUF_Config, 2377, 2377, **2384**
GUI_MULTIBUF_ConfigEx, **2385**
GUI_MULTIBUF_Confirm, 2378, 2379, **2386**
GUI_MULTIBUF_ConfirmEx, **2387**
GUI_MULTIBUF_End, 598, **2388**
GUI_MULTIBUF_EndEx, **2389**
GUI_MULTIBUF_GetNumBuffers, **2390**
GUI_MULTIBUF_GetNumBuffersEx, **2391**
GUI_MULTIBUF_UseSingleBuffer, **2392**
GUI_PID_GetCurrentState, **2434**
GUI_PID_GetState, **2435**, 2435, 2470
GUI_PID_IsEmpty, **2436**
GUI_PID_IsPressed, **2437**
GUI_PID_SetHook, **2438**
GUI_PID_StoreState, **2439**, 2471
GUI_PNG_Draw, **430**
GUI_PNG_DrawEx, **431**
GUI_PNG_GetXSize, **432**
GUI_PNG_GetXSizeEx, **433**
GUI_PNG_GetYSize, **434**
GUI_PNG_GetYSizeEx, **435**
GUI_PreserveTrans, **288**
GUI_QR_Create, **339**
GUI_QR_CreateFramed, **340**
GUI_QR_Delete, **341**
GUI_QR_Draw, **342**
GUI_QR_GetInfo, **343**
GUI_RegisterAfterInitHook, **2881**, 2881, 2881
GUI_RestoreContext, **351**
GUI_RestoreUserAlpha, **289**, 289
GUI_RotatePolygon, **326**, 326, 2565, 2565
GUI_SaveContext, **352**
GUI_SelectLayer, 670, 670, 2405, 2409, 2409, 2410, **2420**
GUI_SelectLCD, **719**, 731
GUI_SendKeyMsg, **2497**
GUI_SetAfterInitHook, **370**
GUI_SetAlphaMask8888, **295**
GUI_SetBkColor, 186, 186, 286, 289, 326, 333, 336, 622, **654**, 682, 700, 700, 701, 716, 786, 795, 795, 828, 878, 884, 901, 901, 961, 2405, 2405, 2409, 2410, 2550, 2555, 2561, 2562

 © 2020 SEGGER Microcontroller GmbH

GUI_SetBkColorIndex, **655**
GUI_SetClearTextRectMode, **208**
GUI_SetClipRect, **257**, 257, 257
GUI_SetColor, 150, 186, 186, 201, 201, 286, 286, 286, 286, 289, 289, 289, 289, 290, 290, 290, 324, 326, 326, 332, 332, 332, 333, 336, 344, **656**, 700, 701, 706, 901, 901, 1245, 1650, 2297, 2398, 2398, 2398, 2398, 2405, 2405, 2409, 2409, 2409, 2409, 2409, 2410, 2410, 2550, 2555, 2561, 2563
GUI_SetColorIndex, **657**
GUI_SetControlHook, **371**
GUI_SetDefaultBkColor, **659**
GUI_SetDefaultColor, **658**
GUI_SetDefaultFont, **503**, 2881
GUI_SetDrawMode, **258**, 258, 258, 322, 700
GUI_SetFont, 151, 186, 231, 232, 290, 326, 333, 479, 479, **504**, 504, 504, 504, 504, 504, 504, 686, 706, 1245, 2569
GUI_SetFuncDrawAlpha, **2909**
GUI_SetFuncGetpPalConvTable, **2913**
GUI_SetLayerAlphaEx, **2421**
GUI_SetLayerPosEx, **2422**
GUI_SetLayerSizeEx, **2423**
GUI_SetLayerVisEx, **2424**
GUI_SetLBorder, **212**, 2563
GUI_SetLineStyle, **320**
GUI_SetOnErrorFunc, **2882**
GUI_SetOrg, 2398, 2398, **2403**
GUI_SetOrientation, **2636**
GUI_SetOrientationEx, **2637**
GUI_SetPenSize, 186, **259**, 333, 333, 333, 682, 701, 2475, 2550, 2561, 2561, 2561, 2563
GUI_SetpfMemcpy, **2895**
GUI_SetpfMemset, **2896**
GUI_SetpfStrcmp, **2897**
GUI_SetpfStrcpy, **2898**
GUI_SetpfStrlen, **2899**
GUI_SetRefreshHook, **372**
GUI_SetSignalEventFunc, **765**, 765
GUI_SetStreamedBitmapHook, **309**
GUI_SetTextAlign, **213**, 213, 333
GUI_SetTextMode, 186, 186, 186, 186, 186, 200, 201, **209**, 290, 333, 706, 716, 1245, 2398, 2405
GUI_SetTextStyle, **210**
GUI_SetTimeSlice, **2860**
GUI_SetUserAlpha, 289, **291**
GUI_SetWaitEventFunc, **766**, 766
GUI_SetWaitEventTimedFunc, **767**, 767
GUI_ShowMissingCharacters, **205**
GUI_SIF_CreateFont, **476**, 476, 477
GUI_SIF_DeleteFont, **477**, 477
GUI_SOFTLAYER_Enable, 2416, **2426**
GUI_SOFTLAYER_MULTIBUF_Enable, **2429**
GUI_SOFTLAYER_Refresh, **2427**
GUI_SOFTLAYER_SetCompositeColor, **2428**
GUI_SPLINE_Create, **345**
GUI_SPLINE_Delete, **346**
GUI_SPLINE_Draw, **347**
GUI_SPLINE_DrawAA, **348**
GUI_SPLINE_GetXSize, **350**
GUI_SPLINE_GetY, **349**
GUI_SPRITE_Create, **2507**
GUI_SPRITE_CreateAnim, **2508**
GUI_SPRITE_CreateEx, **2509**
GUI_SPRITE_CreateExAnim, **2510**
GUI_SPRITE_CreateHidden, **2511**
GUI_SPRITE_CreateHiddenEx, **2512**
GUI_SPRITE_Delete, **2513**
GUI_SPRITE_GetState, **2514**
GUI_SPRITE_Hide, **2515**
GUI_SPRITE_SetBitmap, **2516**
GUI_SPRITE_SetBitmapAndPosition, **2517**
GUI_SPRITE_SetLoop, **2518**
GUI_SPRITE_SetPosition, **2519**
GUI_SPRITE_Show, **2520**
GUI_SPRITE_StartAnim, **2521**
GUI_SPRITE_StopAnim, **2522**
GUI_SPY_Process, **179**, 179
GUI_SPY_SetMemHandler, **180**
GUI_SPY_StartServer, **181**
GUI_SPY_StartServerEx, **182**
GUI_SPY_X_StartServer, **183**

 © 2020 SEGGER Microcontroller GmbH

GUI_StoreKey, **2502**
GUI_StoreKeyMsg, **2496**
GUI_TIMER_Create, **2862**
GUI_TIMER_Delete, **2863**
GUI_TIMER_Restart, **2864**
GUI_TIMER_SetPeriod, **2865**
GUI_TOUCH_CalcCoefficients, **2466**
GUI_TOUCH_Calibrate, 2452, 2452, **2458**, 2462, 2462
GUI_TOUCH_CalibratePoint, **2467**
GUI_TOUCH_EnableCalibration, **2468**
GUI_TOUCH_Exec, **2459**
GUI_TOUCH_GetState, **2447**
GUI_TOUCH_GetxPhys, **2460**
GUI_TOUCH_GetyPhys, **2460**
GUI_TOUCH_SetOrientation, 2452, **2461**, 2462
GUI_TOUCH_StoreState, **2448**, 2448
GUI_TOUCH_StoreStateEx, **2449**, 2449
GUI_TOUCH_TransformPoint, **2469**
GUI_TTF_CreateFont, **478**, 479, 479
GUI_TTF_CreateFontAA, **480**
GUI_TTF_DestroyCache, **481**
GUI_TTF_Done, **482**
GUI_TTF_GetFamilyName, **483**
GUI_TTF_GetStyleName, **484**
GUI_TTF_SetCacheSize, **485**
GUI_UC_ConvertUC2UTF8, **2570**
GUI_UC_ConvertUTF82UC, **2571**
GUI_UC_DispString, **2582**
GUI_UC_EnableBIDI, **2572**, 2604
GUI_UC_EnableThai, **2573**
GUI_UC_Encode, **2574**
GUI_UC_GetBaseDir, **2575**
GUI_UC_GetCharCode, **2576**, 2577, 2577
GUI_UC_GetCharSize, **2577**, 2577
GUI_UC_SetBaseDir, **2578**
GUI_UC_SetEncodeNone, **2580**
GUI_UC_SetEncodeSJIS, **2579**
GUI_UC_SetEncodeUTF8, 2567, 2568, 2569, **2581**
GUI_VNC_AttachToLayer, **2836**
GUI_VNC_EnableFileTransfer, **2837**
GUI_VNC_EnableKeyboardInput, **2838**
GUI_VNC_GetNumConnections, **2839**
GUI_VNC_Process, **2840**, 2840
GUI_VNC_RingBell, **2841**
GUI_VNC_SetFS_API, **2842**
GUI_VNC_SetLockFrame, **2843**
GUI_VNC_SetPassword, **2844**
GUI_VNC_SetProgName, **2845**
GUI_VNC_SetRetryCount, **2846**
GUI_VNC_SetSize, **2847**
GUI_VNC_X_StartServer, 2833, **2848**
GUI_VNC_X_StartServerFT, **2849**
GUI_WaitEvent, **768**, 768
GUI_WaitKey, **2503**
GUI_WrapGetNumLines, **206**
GUI_X_Delay, 605, **2890**
GUI_X_ExecIdle, 763, **2891**
GUI_X_GetTaskId, **772**, 779, 779, 780
GUI_X_GetTime, **2892**
GUI_X_InitOS, **773**, 779, 779, 780
GUI_X_Lock, **774**, 779, 779, 780
GUI_X_SignalEvent, 765, 770, **775**, 779, 779
GUI_X_Unlock, **776**, 779, 779, 780
GUI_X_WaitEvent, 766, 770, **777**, 779, 779
GUI_X_WaitEventTimed, 767, 770, **778**, 779
GUI_XBF_CreateFont, **486**, 487
GUI_XBF_DeleteFont, **488**
GUI_YUV_Create, **359**
GUI_YUV_CreateEx, **360**
GUI_YUV_Delete, **361**
GUI_YUV_DeleteEx, **362**
GUI_YUV_GetpData, **363**
GUI_YUV_GetpDataEx, **364**
GUI_YUV_InvalidateArea, **365**
GUI_YUV_SetPeriod, **366**
GUI_YUV_SetPeriodEx, **367**

 © 2020 SEGGER Microcontroller GmbH

GUICC_M1555I_SetCustColorConv, **2905**
GUICC_M4444I_SetCustColorConv, **2905**
GUICC_M565_SetCustColorConv, **2905**
GUICC_M8888I_SetCustColorConv, **2905**
GUICC_M888_SetCustColorConv, **2905**
GUIDRV_BitPlains_Config, **2646**
GUIDRV_DCache_AddDriver, 2648, **2649**
GUIDRV_DCache_SetMode1bpp, 2647, **2650**
GUIDRV_Dist_AddDriver, 2651, 2651, **2652**, 2652, 2652
GUIDRV_FlexColor_Config, 2655, **2661**
GUIDRV_FlexColor_SetFunc, 2656, **2657**
GUIDRV_FlexColor_SetOrientation, **2662**
GUIDRV_FlexColor_SetReadFunc66709_B16, **2665**
GUIDRV_FlexColor_SetReadFunc66720_B16, **2670**
GUIDRV_FlexColor_SetReadFunc66772_B16, **2672**
GUIDRV_FlexColor_SetReadFunc66772_B8, **2671**
GUIDRV_IST3088_SetBus16, **2675**
GUIDRV_S1D13513_Config, **2683**
GUIDRV_S1D13513_SetBus16, **2684**
GUIDRV_S1D13748_Config, **2687**
GUIDRV_S1D13748_SetBus16, **2688**
GUIDRV_S1D13781_Config, **2692**
GUIDRV_S1D13781_SetBusSPI, **2693**
GUIDRV_S1D13781_SetOrientation, **2694**
GUIDRV_S1D13L01_Config, **2692**
GUIDRV_S1D13L01_SetBusSPI, **2693**
GUIDRV_S1D13L01_SetOrientation, **2694**
GUIDRV_S1D13L02_Config, **2687**
GUIDRV_S1D13L02_SetBus16, **2688**
GUIDRV_S1D13L04_Config, **2683**
GUIDRV_S1D13L04_SetBus16, **2684**
GUIDRV_S1D15G00_Config, **2698**, 2699
GUIDRV_S1D15G00_SetBus8, **2699**, 2699
GUIDRV_SH_MEM_3_Config, **2703**
GUIDRV_SH_MEM_3_SetBus8, **2704**
GUIDRV_SH_MEM_Config, **2703**, 2705
GUIDRV_SH_MEM_SetBus8, **2704**, 2705
GUIDRV_SLin_Config, 2618, 2716
GUIDRV_SLin_SetBus8, 2619, 2716
GUIDRV_SLin_SetS1D13700, 2619, **2711**, 2716
GUIDRV_SLin_SetSSD1325, **2712**
GUIDRV_SLin_SetSSD1848, **2713**
GUIDRV_SLin_SetT6963, **2714**
GUIDRV_SLin_SetUC1617, **2715**
GUIDRV_SLinEPD_Config, **2720**, 2724
GUIDRV_SLinEPD_EnablePartialMode, **2721**
GUIDRV_SLinEPD_SetBus8, **2722**, 2724
GUIDRV_SLinEPD_SetSSD1673, **2723**, 2724
GUIDRV_SPage_Config, **2729**, 2741
GUIDRV_SPage_Set1502, **2731**
GUIDRV_SPage_Set1510, **2732**
GUIDRV_SPage_Set1512, **2733**
GUIDRV_SPage_SetBus8, **2730**, 2741
GUIDRV_SPage_SetST75256, **2734**
GUIDRV_SPage_SetST75320, **2735**
GUIDRV_SPage_SetST7591, **2736**
GUIDRV_SPage_SetUC1610, **2737**
GUIDRV_SPage_SetUC1611, **2738**, 2741
GUIDRV_SPage_SetUC1628, **2739**
GUIDRV_SPage_SetUC1638, **2740**
GUIDRV_SSD1322_Config, **2743**, 2745
GUIDRV_SSD1322_SetBus8, **2744**, 2745
GUIDRV_SSD1926_Config, **2748**, 2750
GUIDRV_SSD1926_SetBus16, **2749**, 2750
GUIDRV_UC1698G_Config, **2753**
GUIDRV_UC1698G_SetBus16, **2755**
GUIDRV_UC1698G_SetBus8, **2754**
GUIMTDRV_TangoC32_Init, **2820**
GUITASK_GetMaxTask, **2883**
GUITASK_SetMaxTask, **2884**
GUITDRV_ADS7846_Config, **2823**
GUITDRV_ADS7846_Exec, **2825**
GUITDRV_ADS7846_GetLastVal, **2826**
HEADER_AddItem, **1350**, 1374, 1374
HEADER_Create, **1351**, 1374
HEADER_CreateAttached, **1352**

 © 2020 SEGGER Microcontroller GmbH

HEADER_CreateEx, **1353**
HEADER_CreateIndirect, **1354**
HEADER_CreateUser, **1355**
HEADER_DeleteItem, **1356**
HEADER_GetBkColor, **1357**
HEADER_GetColumnFromPos, **1358**
HEADER_GetDefaultBkColor, **1359**
HEADER_GetDefaultBorderH, **1360**
HEADER_GetDefaultBorderV, **1361**
HEADER_GetDefaultCursor, **1362**
HEADER_GetDefaultFont, **1363**
HEADER_GetDefaultTextColor, **1364**
HEADER_GetFont, **1365**
HEADER_GetHeight, **1366**
HEADER_GetItemText, **1367**
HEADER_GetItemWidth, **1368**
HEADER_GetNumItems, **1369**
HEADER_GetSel, **1370**
HEADER_GetTextColor, **1371**
HEADER_GetUserData, **1372**
HEADER_SetBitmap, **1373**
HEADER_SetBitmapEx, **1374**, 1374, 1374
HEADER_SetBkColor, **1375**
HEADER_SetBMP, **1376**
HEADER_SetBMPEx, **1377**
HEADER_SetDefaultBkColor, **1378**
HEADER_SetDefaultBorderH, **1379**
HEADER_SetDefaultBorderV, **1380**
HEADER_SetDefaultCursor, **1381**
HEADER_SetDefaultFont, 1374, **1382**
HEADER_SetDefaultTextColor, 1374, **1383**
HEADER_SetDragLimit, **1384**
HEADER_SetFixed, **1385**
HEADER_SetFont, **1386**
HEADER_SetHeight, **1387**
HEADER_SetItemText, **1388**
HEADER_SetItemWidth, **1389**
HEADER_SetScrollPos, **1390**
HEADER_SetSkinFlexProps, **2331**
HEADER_SetStreamedBitmap, **1391**
HEADER_SetStreamedBitmapEx, **1392**
HEADER_SetTextAlign, **1393**
HEADER_SetTextColor, **1394**, 1566
HEADER_SetUserData, **1395**
ICONVIEW_AddBitmapItem, **1401**
ICONVIEW_AddStreamedBitmapItem, **1402**
ICONVIEW_CreateEx, **1403**
ICONVIEW_CreateIndirect, **1404**
ICONVIEW_CreateUser, **1405**
ICONVIEW_DeleteItem, **1406**
ICONVIEW_GetBkColor, **1408**
ICONVIEW_GetFont, **1409**
ICONVIEW_GetItemBitmap, **1410**
ICONVIEW_GetItemText, **1411**
ICONVIEW_GetItemUserData, **1412**
ICONVIEW_GetNumItems, **1413**
ICONVIEW_GetReleasedItem, **1414**
ICONVIEW_GetSel, **1415**
ICONVIEW_GetTextColor, **1416**
ICONVIEW_GetUserData, **1417**
ICONVIEW_InsertBitmapItem, **1418**
ICONVIEW_InsertStreamedBitmapItem, **1419**
ICONVIEW_OwnerDraw, **1420**, 1428
ICONVIEW_SetBitmapItem, **1421**
ICONVIEW_SetBkColor, **1422**
ICONVIEW_SetFont, **1423**
ICONVIEW_SetFrame, **1424**
ICONVIEW_SetIconAlign, **1425**
ICONVIEW_SetItemText, **1426**
ICONVIEW_SetItemUserData, **1427**
ICONVIEW_SetOwnerDraw, **1428**
ICONVIEW_SetSel, **1429**
ICONVIEW_SetSpace, **1430**
ICONVIEW_SetStreamedBitmapItem, **1431**
ICONVIEW_SetTextAlign, **1432**
ICONVIEW_SetTextColor, **1433**

 © 2020 SEGGER Microcontroller GmbH

ICONVIEW_SetUserData, **1434**
ICONVIEW_SetWrapMode, **1435**
IMAGE_CreateEx, **1442**
IMAGE_CreateIndirect, **1443**
IMAGE_CreateUser, **1444**
IMAGE_GetImageSize, **1445**
IMAGE_GetUserData, **1446**
IMAGE_SetBitmap, **1447**
IMAGE_SetBMP, **1448**
IMAGE_SetBMPEx, **1449**
IMAGE_SetDTA, **1448**
IMAGE_SetDTAEx, **1449**
IMAGE_SetGIF, **1448**
IMAGE_SetGIFEx, **1449**
IMAGE_SetJPEG, **1448**
IMAGE_SetJPEGEx, **1449**
IMAGE_SetPNG, **1448**
IMAGE_SetPNGEx, **1449**
IMAGE_SetTiled, **1450**
IMAGE_SetUserData, **1451**
KNOB_AddValue, **1456**
KNOB_CreateEx, **1457**
KNOB_CreateIndirect, **1458**
KNOB_CreateUser, **1459**
KNOB_GetUserData, **1460**
KNOB_GetValue, **1461**
KNOB_SetBkColor, **1462**
KNOB_SetBkDevice, **1463**
KNOB_SetDevice, **1464**
KNOB_SetInvert, **1465**
KNOB_SetKeyValue, **1466**
KNOB_SetOffset, **1467**
KNOB_SetPeriod, **1468**
KNOB_SetPos, **1469**
KNOB_SetRange, **1470**
KNOB_SetRotateHQ, **1471**
KNOB_SetRotateLQ, **1471**
KNOB_SetSnap, **1472**
KNOB_SetTickSize, **1473**
KNOB_SetUserData, **1474**
LCD_ControlCache, **2817**
LCD_GetBitsPerPixel, **2782**
LCD_GetBitsPerPixelEx, **2783**
LCD_GetMirrorX, 2452
LCD_GetMirrorXEx, 2462
LCD_GetMirrorY, 2452
LCD_GetMirrorYEx, 2462
LCD_GetNumColors, **2784**
LCD_GetNumColorsEx, **2785**
LCD_GetNumLayers, **2425**
LCD_GetPosEx, **2786**
LCD_GetSwapXY, 2452, 2646, 2705, 2724, 2741, 2745
LCD_GetSwapXYEx, 2462
LCD_GetVRAMAddr, **2787**
LCD_GetVRAMAddrEx, **2788**
LCD_GetVXSize, **2789**
LCD_GetVXSizeEx, **2790**
LCD_GetVYSize, **2789**
LCD_GetVYSizeEx, **2790**
LCD_GetXMag, **2791**
LCD_GetXMagEx, **2792**
LCD_GetXSize, 2470, **2793**
LCD_GetXSizeEx, **2794**
LCD_GetYMag, **2791**
LCD_GetYMagEx, **2792**
LCD_GetYSize, 2470, **2793**
LCD_GetYSizeEx, **2794**
LCD_OffEx, **2804**
LCD_On, **2805**
LCD_OnEx, **2806**
LCD_Refresh, **2807**
LCD_RefreshEx, **2808**
LCD_ROTATE_AddDriver, **2626**
LCD_ROTATE_AddDriverEx, **2627**
LCD_ROTATE_DecSel, **2628**
LCD_ROTATE_DecSelEx, **2629**

 © 2020 SEGGER Microcontroller GmbH

LCD_ROTATE_IncSel, **2630**
LCD_ROTATE_IncSelEx, **2631**
LCD_ROTATE_SetCallback, **2632**
LCD_ROTATE_SetSel, **2633**
LCD_ROTATE_SetSelEx, **2634**
LCD_SetAlphaEx, **2795**
LCD_SetAlphaModeEx, **2796**
LCD_SetBufferPtr, **2801**, 2801
LCD_SetBufferPtrEx, 2378, **2802**
LCD_SetChromaEx, **2797**
LCD_SetChromaModeEx, **2798**
LCD_SetDevFunc, 2378, **2809**
LCD_SetLUT, **643**
LCD_SetLUTEntryEx, **645**
LCD_SetLUTEx, 642, **644**, 2408
LCD_SetMaxNumColors, **2813**
LCD_SetPosEx, **2799**
LCD_SetSizeEx, 2398, 2411, 2411, 2413, 2413, 2416, 2618, 2646, 2646, 2647, 2652, 2655, 2680, 2699, 2705, 2705, 2716, 2724, 2724, 2741, 2741, 2745, 2745, 2749, 2761, **2814**, 2886
LCD_SetVisEx, **2800**
LCD_SetVRAMAddrEx, 2411, 2411, 2413, 2416, 2646, 2680, **2815**, 2886
LCD_SetVSizeEx, **2816**, 2398, 2416, 2618, 2646, 2646, 2647, 2652, 2655, 2680, 2699, 2716, 2724, 2724, 2741, 2741, 2745, 2745, 2749, **2816**, 2886
LISTBOX_AddString, **1479**
LISTBOX_Callback, 968
LISTBOX_Create, **1480**, 1916
LISTBOX_CreateAsChild, **1481**
LISTBOX_CreateEx, **1482**
LISTBOX_CreateIndirect, **1483**, 2231
LISTBOX_CreateUser, **1484**
LISTBOX_DecSel, **1485**
LISTBOX_DeleteItem, **1486**
LISTBOX_EnableMotion, **1487**
LISTBOX_EnableWrapMode, **1488**
LISTBOX_GetBkColor, **1489**
LISTBOX_GetDefaultBkColor, **1490**
LISTBOX_GetDefaultFont, **1491**
LISTBOX_GetDefaultScrollStepH, **1492**
LISTBOX_GetDefaultTextAlign, **1493**
LISTBOX_GetDefaultTextColor, **1494**
LISTBOX_GetFont, **1495**
LISTBOX_GetItemDisabled, **1496**
LISTBOX_GetItemSel, **1497**
LISTBOX_GetItemSpacing, **1498**
LISTBOX_GetItemText, **1499**
LISTBOX_GetMulti, **1500**
LISTBOX_GetNumItems, **1501**
LISTBOX_GetOwner, **1502**
LISTBOX_GetScrollStepH, **1503**
LISTBOX_GetSel, **1504**
LISTBOX_GetTextAlign, **1505**
LISTBOX_GetTextColor, **1506**
LISTBOX_GetUserData, **1507**
LISTBOX_IncSel, **1508**
LISTBOX_InsertString, **1509**
LISTBOX_InvalidateItem, **1510**
LISTBOX_OwnerDraw, **1511**, 1526, 1526
LISTBOX_SetAutoScrollH, **1512**
LISTBOX_SetAutoScrollV, **1513**
LISTBOX_SetBkColor, **1514**
LISTBOX_SetDefaultBkColor, **1515**
LISTBOX_SetDefaultFont, **1516**
LISTBOX_SetDefaultScrollStepH, **1517**
LISTBOX_SetDefaultTextAlign, **1518**
LISTBOX_SetDefaultTextColor, **1519**
LISTBOX_SetFixedScrollPos, **1520**
LISTBOX_SetFont, **1521**
LISTBOX_SetItemDisabled, **1522**
LISTBOX_SetItemSel, **1523**
LISTBOX_SetItemSpacing, **1524**
LISTBOX_SetMulti, **1525**
LISTBOX_SetOwnerDraw, **1526**
LISTBOX_SetScrollbarColor, **1528**
LISTBOX_SetScrollbarWidth, **1529**
LISTBOX_SetScrollStepH, **1530**
LISTBOX_SetSel, **1531**

 © 2020 SEGGER Microcontroller GmbH

LISTBOX_SetString, **1532**
LISTBOX_SetText, 2232, 2233
LISTBOX_SetTextAlign, **1533**
LISTBOX_SetTextColor, **1534**
LISTBOX_SetUserData, **1535**
LISTVIEW_AddColumn, **1545**
LISTVIEW_AddRow, **1546**
LISTVIEW_CompareDec, **1547**
LISTVIEW_CompareText, **1548**
LISTVIEW_Create, **1549**, 1566
LISTVIEW_CreateAttached, **1550**
LISTVIEW_CreateEx, **1551**
LISTVIEW_CreateIndirect, **1552**
LISTVIEW_CreateUser, **1553**
LISTVIEW_DecSel, **1554**
LISTVIEW_DeleteAllRows, **1555**
LISTVIEW_DeleteColumn, **1556**
LISTVIEW_DeleteRow, **1557**
LISTVIEW_DisableRow, **1558**
LISTVIEW_DisableSort, **1559**
LISTVIEW_EnableCellSelect, **1560**
LISTVIEW_EnableMotion, **1561**
LISTVIEW_EnableRow, **1562**
LISTVIEW_EnableSort, **1563**
LISTVIEW_GetBkColor, **1564**
LISTVIEW_GetFont, **1565**
LISTVIEW_GetHeader, **1566**, 1566
LISTVIEW_GetItemRect, **1567**
LISTVIEW_GetItemText, **1568**
LISTVIEW_GetItemTextLen, **1569**
LISTVIEW_GetItemTextSorted, **1570**
LISTVIEW_GetLBorder, **1571**
LISTVIEW_GetNumColumns, **1572**
LISTVIEW_GetNumRows, **1573**
LISTVIEW_GetRBorder, **1574**
LISTVIEW_GetSel, **1575**
LISTVIEW_GetSelCol, **1576**
LISTVIEW_GetSelUnsorted, **1577**
LISTVIEW_GetTextAlign, **1578**
LISTVIEW_GetTextColor, **1579**
LISTVIEW_GetUserData, **1580**
LISTVIEW_GetUserDataRow, **1581**
LISTVIEW_GetWrapMode, **1582**
LISTVIEW_IncSel, **1583**
LISTVIEW_InsertRow, **1584**
LISTVIEW_OwnerDraw, **1585**
LISTVIEW_RowIsDisabled, **1586**
LISTVIEW_SetAutoScrollH, **1587**
LISTVIEW_SetAutoScrollV, **1588**
LISTVIEW_SetBkColor, **1589**
LISTVIEW_SetColumnWidth, **1590**
LISTVIEW_SetCompareFunc, **1591**, 1591
LISTVIEW_SetDefaultBkColor, **1593**
LISTVIEW_SetDefaultFont, **1594**
LISTVIEW_SetDefaultGridColor, **1595**
LISTVIEW_SetDefaultTextColor, **1596**
LISTVIEW_SetFixed, **1597**
LISTVIEW_SetFont, **1598**
LISTVIEW_SetGridVis, **1599**
LISTVIEW_SetHeaderHeight, **1600**
LISTVIEW_SetItemBitmap, **1601**
LISTVIEW_SetItemBkColor, **1602**
LISTVIEW_SetItemText, **1603**
LISTVIEW_SetItemTextColor, **1604**
LISTVIEW_SetItemTextSorted, **1605**
LISTVIEW_SetLBorder, **1606**
LISTVIEW_SetOwnerDraw, **1607**
LISTVIEW_SetRBorder, **1608**
LISTVIEW_SetRowHeight, **1609**
LISTVIEW_SetSel, **1610**
LISTVIEW_SetSelCol, **1611**
LISTVIEW_SetSelUnsorted, **1612**
LISTVIEW_SetSort, **1613**
LISTVIEW_SetTextAlign, **1614**
LISTVIEW_SetTextColor, **1615**
LISTVIEW_SetUserData, **1616**

 © 2020 SEGGER Microcontroller GmbH

LISTVIEW_SetUserDataRow, **1617**
LISTVIEW_SetWrapMode, **1618**
LISTWHEEL_AddString, **1624**
LISTWHEEL_CreateEx, **1625**, 1625
LISTWHEEL_CreateIndirect, **1626**
LISTWHEEL_CreateUser, **1627**
LISTWHEEL_GetBkColor, **1628**
LISTWHEEL_GetFont, **1629**
LISTWHEEL_GetItemFromPos, **1630**
LISTWHEEL_GetItemText, **1631**
LISTWHEEL_GetLBorder, **1632**
LISTWHEEL_GetLineHeight, **1633**
LISTWHEEL_GetNumItems, **1634**
LISTWHEEL_GetPos, **1635**
LISTWHEEL_GetRBorder, **1636**
LISTWHEEL_GetSel, **1637**
LISTWHEEL_GetSnapPosition, **1638**
LISTWHEEL_GetTextAlign, **1639**
LISTWHEEL_GetTextColor, **1640**
LISTWHEEL_GetUserData, **1641**
LISTWHEEL_IsMoving, **1642**
LISTWHEEL_MoveToPos, **1643**
LISTWHEEL_OwnerDraw, **1644**, 1650
LISTWHEEL_SetBkColor, **1645**
LISTWHEEL_SetDeceleration, **1646**
LISTWHEEL_SetFont, **1647**
LISTWHEEL_SetLBorder, **1648**
LISTWHEEL_SetLineHeight, **1649**
LISTWHEEL_SetOwnerDraw, **1650**
LISTWHEEL_SetPos, **1651**
LISTWHEEL_SetRBorder, **1652**
LISTWHEEL_SetSel, **1653**
LISTWHEEL_SetSnapPosition, **1654**
LISTWHEEL_SetText, **1655**, 1655
LISTWHEEL_SetTextAlign, **1656**
LISTWHEEL_SetTextColor, **1657**
LISTWHEEL_SetTimerPeriod, **1658**
LISTWHEEL_SetUserData, **1659**
LISTWHEEL_SetVelocity, **1660**
MENU_AddItem, **1667**
MENU_Attach, **1668**
MENU_Callback, 1663
MENU_CreateEx, **1669**
MENU_CreateIndirect, **1670**
MENU_CreateUser, **1671**
MENU_DeleteItem, **1672**
MENU_DisableItem, **1673**
MENU_EnableItem, **1674**
MENU_GetBkColor, **1675**
MENU_GetDefaultBkColor, **1676**
MENU_GetDefaultBorderSize, **1677**
MENU_GetDefaultEffect, **1678**
MENU_GetDefaultFont, **1679**
MENU_GetDefaultTextColor, **1680**
MENU_GetFont, **1681**
MENU_GetItem, **1682**
MENU_GetItemText, **1683**
MENU_GetNumItems, **1684**
MENU_GetOwner, **1685**
MENU_GetTextColor, **1686**
MENU_GetUserData, **1687**
MENU_InsertItem, **1688**
MENU_Popup, **1689**
MENU_SetBkColor, **1690**
MENU_SetBorderSize, **1691**, 1691, 1691, 1691
MENU_SetDefaultBkColor, **1692**
MENU_SetDefaultBorderSize, **1693**
MENU_SetDefaultEffect, **1694**
MENU_SetDefaultFont, **1695**
MENU_SetDefaultTextColor, **1696**
MENU_SetFont, **1697**
MENU_SetItem, **1698**
MENU_SetOwner, **1699**
MENU_SetSel, **1700**
MENU_SetSkinFlexProps, **2337**
MENU_SetTextColor, **1701**

 © 2020 SEGGER Microcontroller GmbH

MENU_SetUserData, **1702**
MENU_SkinEnableArrow, **2338**
MESSAGEBOX_Create, **2287**
MULTIEDIT_AddKey, **1715**
MULTIEDIT_AddText, **1716**
MULTIEDIT_Create, **1717**
MULTIEDIT_CreateEx, **1718**, 1730, 1731
MULTIEDIT_CreateIndirect, **1719**
MULTIEDIT_CreateUser, **1720**
MULTIEDIT_EnableBlink, **1721**
MULTIEDIT_GetBkColor, **1722**
MULTIEDIT_GetCursorCharPos, **1723**
MULTIEDIT_GetCursorPixelPos, **1724**
MULTIEDIT_GetFont, **1725**
MULTIEDIT_GetNumChars, **1726**
MULTIEDIT_GetPrompt, **1727**
MULTIEDIT_GetText, **1728**
MULTIEDIT_GetTextColor, **1729**
MULTIEDIT_GetTextFromLine, **1730**, 1730, 1730
MULTIEDIT_GetTextFromPos, **1731**, 1731, 1731, 1731
MULTIEDIT_GetTextSize, **1732**
MULTIEDIT_GetUserData, **1733**
MULTIEDIT_SetAutoScrollH, **1734**
MULTIEDIT_SetAutoScrollV, **1735**
MULTIEDIT_SetBkColor, **1736**
MULTIEDIT_SetBufferSize, **1737**
MULTIEDIT_SetCursorCharPos, **1738**
MULTIEDIT_SetCursorOffset, **1739**
MULTIEDIT_SetCursorPixelPos, **1740**
MULTIEDIT_SetFocusable, **1741**
MULTIEDIT_SetFont, **1742**
MULTIEDIT_SetHBorder, **1743**
MULTIEDIT_SetInsertMode, **1744**
MULTIEDIT_SetMaxNumChars, **1745**
MULTIEDIT_SetPasswordMode, **1746**
MULTIEDIT_SetPrompt, **1747**
MULTIEDIT_SetReadOnly, **1748**
MULTIEDIT_SetText, **1749**
MULTIEDIT_SetTextAlign, **1750**
MULTIEDIT_SetTextColor, **1751**
MULTIEDIT_SetUserData, **1752**
MULTIEDIT_SetWrapChar, **1753**
MULTIEDIT_SetWrapNone, **1754**
MULTIEDIT_SetWrapWord, **1755**
MULTIEDIT_ShowCursor, **1756**
MULTIPAGE_AddEmptyPage, **1765**
MULTIPAGE_AddPage, **1766**
MULTIPAGE_AttachWindow, **1767**
MULTIPAGE_CreateEx, **1768**
MULTIPAGE_CreateIndirect, **1769**
MULTIPAGE_CreateUser, **1770**
MULTIPAGE_DeletePage, **1771**
MULTIPAGE_DisablePage, **1772**
MULTIPAGE_EnablePage, **1773**
MULTIPAGE_EnableScrollbar, **1774**
MULTIPAGE_GetBkColor, **1775**
MULTIPAGE_GetDefaultAlign, **1776**
MULTIPAGE_GetDefaultBkColor, **1777**
MULTIPAGE_GetDefaultFont, **1778**
MULTIPAGE_GetDefaultTextColor, **1779**
MULTIPAGE_GetFont, **1780**
MULTIPAGE_GetNumTabs, **1781**
MULTIPAGE_GetPageText, **1782**
MULTIPAGE_GetSelection, **1783**
MULTIPAGE_GetTabHeight, **1784**
MULTIPAGE_GetTabWidth, **1785**
MULTIPAGE_GetTextColor, **1786**
MULTIPAGE_GetUserData, **1787**
MULTIPAGE_GetWindow, **1788**
MULTIPAGE_IsPageEnabled, **1789**
MULTIPAGE_SelectPage, **1790**
MULTIPAGE_SetAlign, **1791**
MULTIPAGE_SetBitmap, **1792**
MULTIPAGE_SetBitmapEx, **1793**
MULTIPAGE_SetBkColor, **1794**
MULTIPAGE_SetDefaultAlign, **1795**

 © 2020 SEGGER Microcontroller GmbH

MULTIPAGE_SetDefaultBkColor, **1796**
MULTIPAGE_SetDefaultBorderSizeX, **1797**
MULTIPAGE_SetDefaultBorderSizeY, **1798**
MULTIPAGE_SetDefaultFont, **1799**
MULTIPAGE_SetDefaultTextColor, **1800**
MULTIPAGE_SetFont, **1801**
MULTIPAGE_SetRotation, **1802**
MULTIPAGE_SetSkinFlexProps, **2343**
MULTIPAGE_SetTabHeight, **1803**
MULTIPAGE_SetTabWidth, **1804**
MULTIPAGE_SetText, **1805**
MULTIPAGE_SetTextAlign, **1806**
MULTIPAGE_SetTextColor, **1807**
MULTIPAGE_SetUserData, **1808**
PROGBAR_Create, 966, **1816**
PROGBAR_CreateAsChild, **1817**
PROGBAR_CreateEx, **1818**
PROGBAR_CreateIndirect, **1819**
PROGBAR_CreateUser, **1820**
PROGBAR_GetBarColor, **1821**
PROGBAR_GetFont, **1822**
PROGBAR_GetMinMax, **1823**
PROGBAR_GetTextColor, **1824**
PROGBAR_GetUserData, **1825**
PROGBAR_GetValue, **1826**
PROGBAR_SetBarColor, 967, 967, **1827**
PROGBAR_SetFont, **1828**
PROGBAR_SetMinMax, **1829**
PROGBAR_SetSkinFlexProps, **2348**
PROGBAR_SetText, **1830**
PROGBAR_SetTextAlign, **1831**
PROGBAR_SetTextColor, **1832**
PROGBAR_SetTextPos, **1833**
PROGBAR_SetUserData, **1834**
PROGBAR_SetValue, 967, **1835**
QRCODE_CreateIndirect, **1840**
QRCODE_CreateUser, **1841**
QRCODE_SetEccLevel, **1842**
QRCODE_SetPixelSize, **1844**
QRCODE_SetText, **1845**
QRCODE_SetWiFiText, **1846**
RADIO_Create, **1851**
RADIO_CreateEx, **1852**, 1876, 1876
RADIO_CreateIndirect, **1853**
RADIO_CreateUser, **1854**
RADIO_Dec, **1855**
RADIO_GetBkColor, **1856**
RADIO_GetDefaultFont, **1857**
RADIO_GetDefaultTextColor, **1858**
RADIO_GetFocusColor, **1859**
RADIO_GetFont, **1860**
RADIO_GetImage, **1861**
RADIO_GetNumItems, **1862**
RADIO_GetSpacing, **1863**
RADIO_GetText, **1864**
RADIO_GetTextColor, **1865**
RADIO_GetUserData, **1866**
RADIO_GetValue, **1867**
RADIO_Inc, **1868**
RADIO_SetBkColor, **1869**
RADIO_SetDefaultFocusColor, **1870**
RADIO_SetDefaultFont, **1871**
RADIO_SetDefaultImage, **1872**
RADIO_SetDefaultTextColor, **1873**
RADIO_SetFocusColor, **1874**
RADIO_SetFont, **1875**
RADIO_SetGroupId, **1876**, 1876, 1876
RADIO_SetImage, **1877**
RADIO_SetSkinFlexProps, **2353**
RADIO_SetSpacing, **1878**
RADIO_SetText, 1876, 1876, 1876, 1876, 1876, 1876, **1879**, 1879, 1879, 1879
RADIO_SetTextColor, **1880**
RADIO_SetUserData, **1881**
RADIO_SetValue, **1882**
ROTARY_AddAngle, **1888**
ROTARY_AddValue, **1889**

 © 2020 SEGGER Microcontroller GmbH

ROTARY_CreateEx, **1890**
ROTARY_CreateIndirect, **1891**
ROTARY_CreateUser, **1892**
ROTARY_GetAngle, **1893**
ROTARY_GetImageSize, **1894**
ROTARY_GetMarkerSize, **1895**
ROTARY_GetUserData, **1896**
ROTARY_GetValue, **1897**
ROTARY_SetAngle, **1898**
ROTARY_SetBitmap, **1899**
ROTARY_SetDoRotate, **1900**
ROTARY_SetMarker, **1901**
ROTARY_SetOffset, **1902**
ROTARY_SetPeriod, **1903**
ROTARY_SetRadius, **1904**
ROTARY_SetRange, **1905**
ROTARY_SetSnap, **1906**
ROTARY_SetTickSize, **1907**
ROTARY_SetUserData, **1908**
ROTARY_SetValue, **1909**
ROTARY_SetValueRange, **1910**
SCROLLBAR_AddValue, **1914**
SCROLLBAR_Create, **1915**
SCROLLBAR_CreateAttached, **1916**, 1916
SCROLLBAR_CreateEx, **1917**
SCROLLBAR_CreateIndirect, **1918**
SCROLLBAR_CreateUser, **1919**
SCROLLBAR_Dec, **1920**
SCROLLBAR_GetColor, **1921**
SCROLLBAR_GetDefaultWidth, **1922**
SCROLLBAR_GetNumItems, **1923**
SCROLLBAR_GetPageSize, **1924**
SCROLLBAR_GetThumbSizeMin, **1925**
SCROLLBAR_GetUserData, **1926**
SCROLLBAR_GetValue, **1927**
SCROLLBAR_Inc, **1928**
SCROLLBAR_SetColor, **1929**
SCROLLBAR_SetDefaultColor, **1930**
SCROLLBAR_SetDefaultWidth, **1931**
SCROLLBAR_SetNumItems, **1932**
SCROLLBAR_SetPageSize, **1933**
SCROLLBAR_SetSkinFlexProps, **2358**
SCROLLBAR_SetState, **1934**
SCROLLBAR_SetThumbSizeMin, **1935**
SCROLLBAR_SetUserData, **1936**
SCROLLBAR_SetValue, **1937**
SCROLLBAR_SetWidth, **1938**
SIM_GUI_CreateLCDInfoWindow, **152**, 152
SIM_GUI_CreateLCDWindow, 149, 150, **153**
SIM_GUI_Delay, **120**
SIM_GUI_Enable, 148, 150, **154**
SIM_GUI_ExecIdle, **121**
SIM_GUI_Exit, 149, **155**
SIM_GUI_GetCompositeTouch, **122**
SIM_GUI_GetTime, **123**
SIM_GUI_HandleKeyEvents, 148
SIM_GUI_Init, 149, 150, **156**
SIM_GUI_SaveBMP, **124**
SIM_GUI_SaveBMPEx, **125**
SIM_GUI_SaveCompositeBMP, **126**
SIM_GUI_SetCallback, **127**
SIM_GUI_SetCompositeColor, **128**
SIM_GUI_SetCompositeSize, **129**, 2414
SIM_GUI_SetCompositeTouch, **130**
SIM_GUI_SetLCDColorBlack, **131**, 131, 131
SIM_GUI_SetLCDColorWhite, **131**, 131, 131
SIM_GUI_SetLCDPos, 118, 131, 131, **133**
SIM_GUI_SetLCDWindowHook, **157**
SIM_GUI_SetMag, **134**
SIM_GUI_SetTransColor, **135**
SIM_GUI_SetTransMode, **136**, 2414, 2414, 2414
SIM_GUI_ShowDevice, **137**
SIM_GUI_UseCustomBitmaps, **138**
SIM_HARDKEY_GetNum, **142**
SIM_HARDKEY_GetState, **143**
SIM_HARDKEY_SetCallback, **144**

 © 2020 SEGGER Microcontroller GmbH

SIM_HARDKEY_SetMode, **145**
SIM_HARDKEY_SetState, **146**
SLIDER_Create, **1945**
SLIDER_CreateEx, **1946**
SLIDER_CreateIndirect, **1947**, 2231, 2231
SLIDER_CreateUser, **1948**
SLIDER_Dec, **1949**
SLIDER_EnableFocusRect, **1950**
SLIDER_GetBkColor, **1951**
SLIDER_GetFocusColor, **1952**
SLIDER_GetRange, **1953**
SLIDER_GetUserData, **1954**
SLIDER_GetValue, **1955**
SLIDER_Inc, **1956**
SLIDER_SetBkColor, **1957**
SLIDER_SetDefaultFocusColor, **1958**
SLIDER_SetFocusColor, **1959**
SLIDER_SetInvertDir, **1960**
SLIDER_SetNumTicks, **1961**, 1962
SLIDER_SetRange, **1962**, 1962, 1962, 1962
SLIDER_SetSkinFlexProps, **2364**
SLIDER_SetUserData, **1963**
SLIDER_SetValue, **1964**, 2232, 2233
SLIDER_SetWidth, **1965**, 2232, 2233
SPINBOX_CreateEx, **1972**
SPINBOX_CreateIndirect, **1973**
SPINBOX_CreateUser, **1974**
SPINBOX_EnableBlink, **1975**
SPINBOX_GetBkColor, **1976**
SPINBOX_GetButtonBkColor, **1977**
SPINBOX_GetDefaultButtonSize, **1978**
SPINBOX_GetEditHandle, **1979**
SPINBOX_GetFont, **1980**
SPINBOX_GetTextColor, **1981**
SPINBOX_GetUserData, **1982**
SPINBOX_GetValue, **1983**
SPINBOX_SetBkColor, **1984**
SPINBOX_SetButtonBkColor, **1985**
SPINBOX_SetButtonSize, **1986**
SPINBOX_SetDefaultButtonSize, **1987**
SPINBOX_SetEdge, **1988**
SPINBOX_SetEditMode, **1989**
SPINBOX_SetFont, **1990**
SPINBOX_SetRange, **1991**
SPINBOX_SetSkinFlexProps, **2369**
SPINBOX_SetStep, **1992**
SPINBOX_SetTextColor, **1993**
SPINBOX_SetTimerPeriod, **1994**
SPINBOX_SetUserData, **1995**
SPINBOX_SetValue, **1996**
SWIPELIST_AddItem, **2010**
SWIPELIST_AddItemText, **2011**
SWIPELIST_AddSepItem, **2012**
SWIPELIST_CreateEx, **2013**
SWIPELIST_CreateIndirect, **2014**
SWIPELIST_CreateUser, **2015**
SWIPELIST_DeleteItem, **2016**
SWIPELIST_GetBitmap, **2017**
SWIPELIST_GetBitmapSpace, **2018**
SWIPELIST_GetBkColor, **2019**
SWIPELIST_GetBorderSize, **2020**
SWIPELIST_GetDefaultBitmapSpace, **2021**
SWIPELIST_GetDefaultBkColor, **2022**
SWIPELIST_GetDefaultBorderSize, **2023**
SWIPELIST_GetDefaultFont, **2024**
SWIPELIST_GetDefaultSepColor, **2025**
SWIPELIST_GetDefaultSepSize, **2026**
SWIPELIST_GetDefaultTextAlign, **2028**
SWIPELIST_GetDefaultTextColor, **2027**
SWIPELIST_GetDefaultThreshold, **2029**
SWIPELIST_GetFont, **2030**
SWIPELIST_GetItemSize, **2031**
SWIPELIST_GetItemUserData, **2032**
SWIPELIST_GetNumItems, **2033**
SWIPELIST_GetNumText, **2034**
SWIPELIST_GetReleasedItem, **2035**

 © 2020 SEGGER Microcontroller GmbH

SWIPELIST_GetScrollPos, **2036**
SWIPELIST_GetSelItem, **2037**
SWIPELIST_GetSepColor, **2038**
SWIPELIST_GetSepSize, **2039**
SWIPELIST_GetText, **2040**
SWIPELIST_GetTextAlign, **2041**
SWIPELIST_GetTextColor, **2042**
SWIPELIST_GetThreshold, **2043**
SWIPELIST_GetUserData, **2044**
SWIPELIST_IsSepItem, **2045**
SWIPELIST_ItemAttachWindow, **2046**
SWIPELIST_ItemDetachWindow, **2047**
SWIPELIST_OwnerDraw, **2048**
SWIPELIST_SetAttachedWindowPos, **2049**
SWIPELIST_SetBitmap, **2050**
SWIPELIST_SetBitmapSpace, **2051**
SWIPELIST_SetBkColor, **2052**
SWIPELIST_SetBorderSize, **2053**
SWIPELIST_SetDefaultBitmapSpace, **2054**
SWIPELIST_SetDefaultBkColor, **2055**
SWIPELIST_SetDefaultBorderSize, **2056**
SWIPELIST_SetDefaultFont, **2057**
SWIPELIST_SetDefaultSepColor, **2058**
SWIPELIST_SetDefaultSepSize, **2059**
SWIPELIST_SetDefaultTextAlign, **2061**
SWIPELIST_SetDefaultTextColor, **2060**
SWIPELIST_SetDefaultThreshold, **2062**
SWIPELIST_SetFont, **2063**
SWIPELIST_SetItemSize, **2064**
SWIPELIST_SetItemUserData, **2065**
SWIPELIST_SetOwnerDraw, **2066**
SWIPELIST_SetScrollPos, **2067**
SWIPELIST_SetScrollPosItem, **2068**
SWIPELIST_SetSepColor, **2069**
SWIPELIST_SetSepSize, **2070**
SWIPELIST_SetText, **2071**
SWIPELIST_SetTextAlign, **2072**
SWIPELIST_SetTextColor, **2073**
SWIPELIST_SetThreshold, **2074**
SWIPELIST_SetUserData, **2075**
SWITCH_AnimState, **2084**
SWITCH_CreateIndirect, **2085**
SWITCH_CreateUser, **2086**
SWITCH_GetDefaultFont, **2087**
SWITCH_GetDefaultPeriod, **2088**
SWITCH_GetDefaultTextColor, **2089**
SWITCH_GetState, **2090**
SWITCH_GetUserData, **2091**
SWITCH_SetBitmap, **2092**
SWITCH_SetDefaultFont, **2093**
SWITCH_SetDefaultPeriod, **2094**
SWITCH_SetDefaultTextColor, **2095**
SWITCH_SetFont, **2096**
SWITCH_SetMode, **2097**
SWITCH_SetPeriod, **2098**
SWITCH_SetState, **2099**
SWITCH_SetText, **2100**
SWITCH_SetTextColor, **2101**
SWITCH_SetUserData, **2102**
SWITCH_Toggle, **2103**
TEXT_Create, **2112**
TEXT_CreateAsChild, **2113**
TEXT_CreateEx, **2114**
TEXT_CreateIndirect, **2115**, 2231, 2231, 2231, 2231
TEXT_CreateUser, **2116**
TEXT_GetBkColor, **2117**
TEXT_GetDefaultFont, **2118**
TEXT_GetDefaultRotation, **2119**
TEXT_GetDefaultTextColor, **2120**
TEXT_GetDefaultWrapMode, **2121**
TEXT_GetFont, **2122**
TEXT_GetNumLines, **2123**
TEXT_GetRotation, **2124**
TEXT_GetText, **2125**
TEXT_GetTextAlign, **2126**
TEXT_GetTextColor, **2127**

 © 2020 SEGGER Microcontroller GmbH

TEXT_GetTextOffset, **2128**
TEXT_GetUserData, **2129**
TEXT_GetWrapMode, **2130**
TEXT_SetBkColor, **2131**
TEXT_SetDec, **2132**
TEXT_SetDefaultFont, **2133**
TEXT_SetDefaultRotation, **2134**
TEXT_SetDefaultTextColor, **2135**
TEXT_SetDefaultWrapMode, **2136**
TEXT_SetFont, **2137**
TEXT_SetRotation, **2138**
TEXT_SetText, **2139**
TEXT_SetTextAlign, **2140**
TEXT_SetTextColor, **2141**
TEXT_SetTextOffset, **2142**
TEXT_SetUserData, **2143**
TEXT_SetWrapMode, **2144**
TREEVIEW_AttachItem, **2153**
TREEVIEW_CreateEx, **2154**
TREEVIEW_CreateIndirect, **2155**
TREEVIEW_CreateUser, **2156**
TREEVIEW_DecSel, **2157**
TREEVIEW_GetDefaultBkColor, **2158**
TREEVIEW_GetDefaultFont, **2159**
TREEVIEW_GetDefaultLineColor, **2160**
TREEVIEW_GetDefaultTextColor, **2161**
TREEVIEW_GetItem, **2162**
TREEVIEW_GetSel, **2163**
TREEVIEW_GetUserData, **2164**
TREEVIEW_IncSel, **2165**
TREEVIEW_InsertItem, **2166**
TREEVIEW_ITEM_Collapse, **2187**
TREEVIEW_ITEM_CollapseAll, **2188**
TREEVIEW_ITEM_Create, **2189**
TREEVIEW_ITEM_Delete, **2190**
TREEVIEW_ITEM_Detach, **2191**
TREEVIEW_ITEM_Expand, **2192**
TREEVIEW_ITEM_ExpandAll, **2193**
TREEVIEW_ITEM_GetInfo, **2194**
TREEVIEW_ITEM_GetText, **2195**
TREEVIEW_ITEM_GetUserData, **2196**
TREEVIEW_ITEM_SetImage, **2197**
TREEVIEW_ITEM_SetText, **2198**
TREEVIEW_ITEM_SetUserData, **2199**
TREEVIEW_ScrollToSel, **2167**
TREEVIEW_SetAutoScrollH, **2168**
TREEVIEW_SetAutoScrollV, **2169**
TREEVIEW_SetBitmapOffset, **2170**
TREEVIEW_SetBkColor, **2171**
TREEVIEW_SetDefaultBkColor, **2172**
TREEVIEW_SetDefaultFont, **2173**
TREEVIEW_SetDefaultLineColor, **2174**
TREEVIEW_SetDefaultTextColor, **2175**
TREEVIEW_SetFont, **2176**
TREEVIEW_SetHasLines, **2177**
TREEVIEW_SetImage, **2178**
TREEVIEW_SetIndent, **2179**
TREEVIEW_SetLineColor, **2180**
TREEVIEW_SetOwnerDraw, **2181**
TREEVIEW_SetSel, **2182**
TREEVIEW_SetSelMode, **2183**
TREEVIEW_SetTextColor, **2184**
TREEVIEW_SetTextIndent, **2185**
TREEVIEW_SetUserData, **2186**
WIDGET_GetDefaultEffect, **979**
WIDGET_SetDefaultEffect, **980**
WIDGET_SetEffect, **981**
WIDGET_SetFocusable, **982**
WINDOW_CreateEx, **2210**
WINDOW_CreateIndirect, **2211**
WINDOW_CreateUser, **2212**
WINDOW_GetUserData, **2213**
WINDOW_SetBkColor, **2214**
WINDOW_SetDefaultBkColor, **2215**
WINDOW_SetUserData, **2216**
WM_Activate, **811**

 © 2020 SEGGER Microcontroller GmbH

WM_AttachWindow, **812**, 2407
WM_AttachWindowAt, **813**
WM_BringToBottom, **814**
WM_BringToTop, **815**
WM_BroadcastMessage, **816**
WM_ClrHasTrans, **817**
WM_CreateTimer, **927**, 927
WM_CreateWindow, 795, **818**, 818, 818, 828, 884, 927, 961, 962
WM_CreateWindowAsChild, 790, 795, **819**, 828, 828, 2406, 2406, 2406, 2406, 2406, 2406
WM_Deactivate, **820**
WM_DefaultProc, 786, **821**, 821, 828, 884, 927, 961, 961, 2225, 2231, 2233, 2234
WM_DeleteTimer, **928**
WM_DeleteWindow, **822**, 961, 962, 1277
WM_DetachWindow, **823**
WM_DisableMemdev, **925**
WM_DisableWindow, **824**, 2232, 2233
WM_EnableMemdev, **926**
WM_EnableWindow, **825**
WM_Exec, **826**, 826
WM_Exec1, **827**
WM_ForEachDesc, **828**, 829
WM_GetActiveWindow, **830**
WM_GetCallback, **831**, 968
WM_GetClientRect, **832**
WM_GetClientRectEx, **833**
WM_GetClientWindow, 798, **931**
WM_GetDesktopWindow, **834**
WM_GetDesktopWindowEx, **835**, 2406, 2406, 2406, 2406, 2406, 2407, 2407
WM_GetDialogItem, **836**, 2225, 2232, 2232, 2232, 2232, 2232, 2232, 2232, 2232, 2232, 2232, 2232, 2232, 2232, 2232, 2233, 2233, 2233, 2233, 2233, 2233, 2233, 2233, 2233, 2233
WM_GetFirstChild, **837**
WM_GetFocusedWindow, **838**
WM_GetHasTrans, **839**
WM_GetId, **932**, 2225, 2234
WM_GetInsideRect, **933**
WM_GetInsideRectEx, **934**
WM_GetInvalidRect, **840**
WM_GetModalLayer, **841**
WM_GetModalWindow, **842**
WM_GetNextSibling, **843**
WM_GetNumInvalidWindows, 826, **844**
WM_GetOrgX, **845**
WM_GetOrgY, **845**
WM_GetParent, **846**
WM_GetPrevSibling, **847**
WM_GetScrollbarH, **935**
WM_GetScrollbarV, **936**
WM_GetScrollPosH, **937**
WM_GetScrollPosV, **938**
WM_GetScrollState, **939**
WM_GetStayOnTop, **848**
WM_GetTimerId, **929**
WM_GetUserData, 828, **849**
WM_GetWindowOrgX, **850**
WM_GetWindowOrgY, **850**
WM_GetWindowRect, **851**
WM_GetWindowRectEx, **852**
WM_GetWindowSizeX, **853**
WM_GetWindowSizeY, **853**
WM_HasCaptured, **854**
WM_HasFocus, **855**
WM_HideWindow, **856**
WM_InvalidateArea, **857**
WM_InvalidateRect, **858**
WM_InvalidateWindow, **859**, 2295
WM_IsCompletelyCovered, **860**
WM_IsCompletelyVisible, 798, **861**
WM_IsEnabled, **862**
WM_IsVisible, **863**
WM_IsWindow, **864**
WM_MakeModal, **865**
WM_MOTION_Enable, **910**
WM_MOTION_SetDeceleration, **911**
WM_MOTION_SetDefaultPeriod, **912**
WM_MOTION_SetMotion, **913**
WM_MOTION_SetMoveable, **914**

 © 2020 SEGGER Microcontroller GmbH

WM_MOTION_SetMovement, **915**
WM_MOTION_SetSpeed, **916**
WM_MOTION_SetThreshold, **917**
WM_MoveChildTo, **866**
WM_MoveTo, **867**
WM_MoveWindow, 828, **868**
WM_MULTIBUF_Enable, **924**
WM_NotifyParent, **869**
WM_Paint, **870**
WM_Rect2Client, **872**
WM_Rect2Screen, **873**
WM_ReleaseCapture, **874**
WM_ResizeWindow, **875**
WM_RestartTimer, 927, **930**
WM_Screen2hWin, **876**
WM_Screen2hWinEx, **877**
WM_SelectWindow, **878**, 878
WM_SendMessage, **879**
WM_SendMessageNoPara, **880**
WM_SendToParent, **881**
WM_SetCallback, **882**, 962, 962
WM_SetCapture, **883**
WM_SetCaptureMove, **884**, 884
WM_SetCreateFlags, **885**, 885
WM_SetDesktopColor, 795, 828, 884, **886**
WM_SetDesktopColorEx, **887**
WM_SetEnableState, **888**
WM_SetFocus, **889**
WM_SetHasTrans, **890**
WM_SetId, **891**
WM_SetModalLayer, **892**
WM_SetpfPollPID, **893**, 893
WM_SetScrollPosH, **940**
WM_SetScrollPosV, **941**
WM_SetScrollState, **942**
WM_SetSize, **894**
WM_SetStayOnTop, **899**
WM_SetTransState, **900**
WM_SetUntouchable, **895**
WM_SetUserClipRect, **901**, 901, 901
WM_SetUserData, 828, 829, 829, **902**
WM_SetWindowPos, **896**
WM_SetXSize, **897**
WM_SetYSize, **898**
WM_ShowWindow, **903**
WM_TOOLTIP_AddTool, 795, **918**
WM_TOOLTIP_Create, 795, 795, **919**
WM_TOOLTIP_Delete, **920**
WM_TOOLTIP_SetDefaultColor, **921**
WM_TOOLTIP_SetDefaultFont, **922**
WM_TOOLTIP_SetDefaultPeriod, **923**
WM_Update, **904**
WM_ValidateRect, **906**
WM_ValidateWindow, **907**
WM_XY2Client, **909**
WM_XY2Screen, **908**

 © 2020 SEGGER Microcontroller GmbH

41.2 Type index

CALENDAR_DATE, **2257**
CHOOSEFILE_INFO, 2274, **2282**, 2282, 2282
GRAPH_DATA_Handle, 1277, 1328
GRAPH_SCALE_Handle, 1277
GUI_ALPHA_STATE, 289, **373**
GUI_ANIM_INFO, 595, **615**
GUI_AUTODEV, 725, 2564
GUI_AUTODEV_INFO, 725, 725, 2564
GUI_BITMAP, 290, 292, 298, 455, 455, 455, 461, 461, 462, 462
GUI_BITMAP_STREAM, 1023
GUI_BITMAPSTREAM_INFO, **374**
GUI_BITMAPSTREAM_PARAM, 309, **375**
GUI_CALLBACK_VOID_U8_P, 397, 398
GUI_CHARINFO, 556, 558, 559
GUI_CHARINFO_EXT, 560
GUI_COLOR, 150, 344, 455, 461, 462, 620, 620, 828, 828, 946
GUI_CURSOR_ANIM, 455, **2532**
GUI_DEVICE, 2618, 2699, 2705, 2716, 2724, 2741, 2745, 2749
GUI_DIRTYDEVICE_INFO, **376**
GUI_DRAWMEMDEV_16BPP_FUNC, 2914
GUI_FONT, 472, 472, 472, 472, 472, 476, 477, 478, 487, 504, 556, 557, 557, 558, 558, 559, 559, 560
GUI_FONT_PROP, 556, 556, 556, 558, 558, 558, 559, 559, 559
GUI_FONT_PROP_EXT, 560, 560, 560
GUI_FONTINFO, 493, **505**
GUI_GIF_IMAGE_INFO, **427**
GUI_GIF_INFO, **428**
GUI_GRADIENT_INFO, 271, **377**
GUI_HWIN, 961
GUI_JPEG_INFO, **408**
GUI_LOGPALETTE, 298, 455, 461, 462
GUI_MEASDEV_Handle, 731
GUI_MEMDEV_Handle, 682, 682, 686, 691, 695, 700, 700, 706, 706, 716
GUI_MOVIE_INFO, **590**
GUI_MTOUCH_EVENT, 2475, **2487**
GUI_MTOUCH_INPUT, 2475, **2488**
GUI_PID_STATE, 801, 884, 884, **943**, 2435, 2442, 2449, 2470
GUI_POINT, 322, 322, 324, 324, 326, 326, **378**, 378, 2548, 2564, 2564, 2564
GUI_PORT_API, 2618, 2699, 2705, 2705, 2716, 2724, 2741, 2745, 2749
GUI_QR_INFO, **379**
GUI_RECT, 199, 200, 201, 257, **380**, 380, 700, 706, 706, 731, 1245, 2297
GUI_SIGNAL_EVENT_FUNC, 765
GUI_SOFTLAYER_CONFIG, 2415, **2430**
GUI_TTF_CS, 478, **506**
GUI_TTF_DATA, 478, **507**
GUI_VNC_CONTEXT, 2840
GUI_WAIT_EVENT_FUNC, 766
GUI_WAIT_EVENT_TIMED_FUNC, 767
GUI_WIDGET_CREATE_FUNC, 974
GUI_WRAPMODE, 201, **222**
GUI_XBF_DATA, 487
HEADER_Handle, 1374, 1566
IP_FS_API, **2850**, 2850
LCD_API_COLOR_CONV, 641
LCD_COLOR, 641, 641, 641, 642, 2408, 2905, 2905
LCD_PHYSPALETTE, 642, 2408
LCD_X_SHOWBUFFER_INFO, 2378, 2378, 2379, 2379
LISTBOX_Handle, 1916
LISTVIEW_Handle, 1566
MENU_ITEM_DATA, **1703**
MENU_MSG_DATA, 1663, 1663, **1704**
PROGBAR_Handle, 966
SCROLLBAR_SKINFLEX_INFO, 2361, 2361
SIM_GUI_INFO, **139**
tLCDDEV_Color2IndexBulk, 2905
tLCDDEV_Index2ColorBulk, 2905
TOOLTIP_INFO, 794, **944**
TREEVIEW_ITEM_INFO, **2200**
WIDGET, 787, 2296
WIDGET_ITEM_DRAW_INFO, 1245, 1328, 1428, 1526, 1650, 2296, 2297, 2361
WM_CALLBACK, 968
WM_GESTURE_INFO, **2489**
WM_KEY_INFO, **945**, 2234
WM_MESSAGE, 786, 795, 795, 801, 821, 828, 884, 927, **946**, 946, 961, 961, 1663, 2225, 2231, 2232, 2233
WM_MOTION_INFO, 792, **947**

 © 2020 SEGGER Microcontroller GmbH

WM_MOVE_INFO, **948**
WM_PID_STATE_CHANGED_INFO, **949**
WM_SCROLL_STATE, **950**
WM_tfPollPID, 893
WM_TOOLTIP_HANDLE, 794, 795
WM_ZOOM_INFO, **2490**

 © 2020 SEGGER Microcontroller GmbH