# DATA SHEET

## **CBTD16212**

24-bit level shifting bus exchange switch with 12-bit output enables

Product data 2001 Sep 28

File under Integrated Ciruits ICL03





# 24-bit level shifting bus exchange switch with 12-bit output enables

**CBTD16212** 

### **FEATURES**

- 5  $\Omega$  switch connection between two ports
- TTL compatible control input levels
- Designed to be used in level shifting applications
- Latch-up testing is done to JESDEC Standard JESD78 which exceeds 100 mA
- ESD protection exceeds 1500 V HBM per JESD22-114A and 1000 V CDM per JESD22-C101

### **DESCRIPTION**

The CBTD16212 provides 24 bits of high-speed TTL-compatible bus switching or exchanging. The low on-state resistance of the switch allows connections to be made with minimal propagation delay.

A diode to  $\rm V_{CC}$  is integrated into the circuit to allow for level shifting between 5 V inputs and 3.3 V outputs.

The CBTD16212 operates as 24-bit bus switch or a 12-bit bus exchanger, which provides data exchanging between the four signal ports via the data-select (S0–S2) terminals.

The CBT16212 is characterized for operation from -40 to +85 °C.

### **QUICK REFERENCE DATA**

SYMBOL	PARAMETER	CONDITIONS T <sub>amb</sub> = 25 °C; GND = 0 V	TYPICAL	UNIT
t <sub>pd</sub>	Propagation delay An to Bn	$C_L = 50 \text{ pF}; V_{CC} = 5 \text{ V}$	0.25	ns
C <sub>IN</sub>	Input capacitance	$V_I = 0 \text{ V or } V_{CC}$	4.5	pF
C <sub>OUT</sub>	Output capacitance	Outputs disabled; $V_O = 0 \text{ V or } V_{CC}$	11.5	pF
r <sub>on</sub>	A1 to A2	$V_{CC} = 5.5 \text{ V}; V_{I} = 0 \text{ V}$	5	Ω

### ORDERING INFORMATION

PACKAGES	TEMPERATURE RANGE	ORDER CODE	DWG NUMBER	
56-Pin Plastic SSOP	−40 to +85 °C	CBTD16212DL	SOT371-1	
56-Pin Plastic TSSOP	–40 to +85 °C	CBTD16212DGG	SOT364-1	

### NOTE:

### **FUNCTION TABLE**


S2	S1	S0	A1	A2	FUNCTION
L	L	L	Z	Z	Disconnect
L	L	Н	B1	Z	A1 = B1
L	Н	L	B2	Z	A1 = B2
L	Н	Н	Z	B1	A2 = B1
Н	L	L	Z	B2	A2 = B2
Н	L	Н	Z	Z	Disconnect
Н	Н	L	B1	B2	A1 = B1, A2 = B2
Н	Н	Н	B2	B1	A1 = B2, A2 = B1

H = High voltage level

L = Low voltage level

Z = High impedance "off" state

### **LOGIC SYMBOL**




<sup>1.</sup> Standard packing quantities and other packaging data is available at www.philipslogic.com/support/packages.

# 24-bit level shifting bus exchange switch with 12-bit output enables

### CBTD16212

### **PIN CONFIGURATION**



### **PIN DESCRIPTION**

PIN NUMBER	SYMBOL	NAME AND FUNCTION
1, 56, 55	S0, S1, S2	Data select
2, 4, 6, 9, 11, 13, 15, 18, 21, 23, 25, 27	1A1-12A1	A1 channel
3, 5, 7, 10, 12, 14, 16, 20, 22, 24, 26, 28	1A2-12A2	A2 channel
54, 52, 50, 47, 45, 43, 41, 39, 36, 34, 32, 30	1B1, 12B1	B1 channel
53, 51, 48, 46, 44, 42, 40, 37, 35, 33, 31, 29	1B2, 12B2	B2 channel
8, 19, 38, 49	GND	Ground (0 V)
17	V <sub>CC</sub>	Positive supply voltage

## 24-bit level shifting bus exchange switch with 12-bit output enables

CBTD16212

### ABSOLUTE MAXIMUM RATINGS1, 2

SYMBOL	PARAMETER	CONDITIONS	RATING	UNIT
V <sub>CC</sub>	DC supply voltage		-0.5 to +7.0	V
I <sub>IK</sub>	DC input diode current	V <sub>I</sub> < 0	-50	mA
V <sub>I</sub>	DC input voltage <sup>3</sup>		-0.5 to +7.0	V
V <sub>OUT</sub>	DC output voltage <sup>3</sup>	output in Off or High state	-0.5 to +5.5	V
I <sub>OUT</sub>	DC output current	output in Low state	128	mA
T <sub>stg</sub>	Storage temperature range		-65 to 150	°C

- 1. Stresses beyond those listed may cause permanent damage to the device. These are stress ratings only and functional operation of the device at these or any other conditions beyond those indicated under "recommended operating conditions" is not implied. Exposure to absolute-maximum-rated conditions for extended periods may affect device reliability.
- The performance capability of a high-performance integrated circuit in conjunction with its thermal environment can create junction temperatures which are detrimental to reliability. The maximum junction temperature of this integrated circuit should not exceed 150°C.
- 3. The input and output voltage ratings may be exceeded if the input and output current ratings are observed.

### RECOMMENDED OPERATING CONDITIONS

SYMBOL	PARAMETER	LIM	UNIT	
STWIBUL	PARAMETER	Min	Max	UNIT
V <sub>CC</sub>	DC supply voltage	4.5	5.5	V
V <sub>IH</sub>	High-level input voltage	2.0		V
V <sub>IL</sub>	Low-level Input voltage	_	0.8	V
T <sub>amb</sub>	Operating free-air temperature range	-40	+85	°C

### DC ELECTRICAL CHARACTERISTICS

				LIMITS		
SYMBOL	PARAMETER	TEST CONDITIONS	T <sub>amb</sub>	UNIT		
			Min	Typ <sup>1</sup>	Max	]
V <sub>IK</sub>	Input clamp voltage	$V_{CC} = 4.5 \text{ V}; I_I = -18 \text{ mA}$	_	_	-1.2	V
V <sub>P</sub>	Output high pass voltage	See Figure 1, page 6	_	_	-1.2	V
	land lands as summed	V <sub>CC</sub> = 0 V; V <sub>I</sub> = 5.5 V	_	_	10	
l <sub>l</sub>	Input leakage current	V <sub>CC</sub> = 5.5 V; V <sub>I</sub> = GND or 5.5 V	_	_	±1	μΑ
I <sub>CC</sub>	Quiescent supply current	$V_{CC} = 5.5 \text{ V}; I_O = 0, V_I = V_{CC} \text{ or GND}$	_	_	3.5	mA
Δl <sub>CC</sub>	Additional supply current per input pin <sup>2</sup>	$V_{CC}$ = 5.5 V, one input at 3.4 V, other inputs at $V_{CC}$ or GND	_	_	2.5	mA
Cl	Control pins	V <sub>I</sub> = 3 V or 0 V	_	4.5	_	pF
C <sub>IO(OFF)</sub>	Port OFF capacitance	V <sub>O</sub> = 3 V or 0 V; S0, S1, S2 = 0 V	_	11.5	_	pF
		V <sub>CC</sub> = 4.5 V; V <sub>1</sub> = 0 V; I <sub>I</sub> = 64 mA	_	5	8	
r <sub>on</sub> 3	A1 to A2	V <sub>CC</sub> = 4.5 V; V <sub>1</sub> = 0 V; I <sub>I</sub> = 30 mA		5	8	Ω
		V <sub>CC</sub> = 4.5 V; V <sub>1</sub> = 2.4 V; I <sub>I</sub> = 15 mA	<u> </u>	16	35	1

- 1. All typical values are at  $V_{CC} = 5 \text{ V}$ ,  $T_{amb} = 25 \text{ °C}$ 2. This is the increase in supply current for each input that is at the specified TTL voltage level rather than  $V_{CC}$  or GND.
- Measured by the voltage drop between the A and the B terminals at the indicated current through the switch. On-state resistance is determined by the lowest voltage of the two (A or B) terminals.

# 24-bit level shifting bus exchange switch with 12-bit output enables

CBTD16212


### **AC CHARACTERISTICS**


 $GND = 0 V; t_{R;} C_{L} = 50 pF$ 

SYMBOL	PARAMETER	FROM (INPUT)	то	$V_{CC} = 5.0$	UNIT	
STMBOL	TANAMETER	TROW (NY 01)	(OUTPUT)	Min	Max	ONIT
t <sub>pd</sub>	Propagation delay <sup>1</sup>	A or B	B or A	_	0.25	ns
t <sub>en</sub>	Output enable time to High and Low level	S	A or B	2	11.5	ns
t <sub>dis</sub>	Output disable time from High and Low level	S	A or B	1.5	8.5	ns


### NOTE:

### **AC WAVEFORMS**






Waveform 1. Input (An) to Output (Yn) Propagation Delays



Waveform 2. 3-State Output Enable and Disable Times

### **TEST CIRCUIT AND WAVEFORMS**



<sup>1.</sup> This parameter is warranted but not production tested. The propagation delay is based on the RC time constant of the typical on-state resistance of the switch and a load capacitance of 50 pF, when driven by an ideal voltage source (zero output impedance).

# 24-bit level shifting bus exchange switch with 12-bit output enables

### CBTD16212





Figure 1. Typical characteristics

2001 Sep 28 6

### SSOP56: plastic shrink small outline package; 56 leads; body width 7.5 mm

SOT371-1



### **DIMENSIONS (mm are the original dimensions)**

UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	b <sub>p</sub>	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	HE	L	Lp	Q	v	w	у	Z <sup>(1)</sup>	θ
mm	2.8	0.4 0.2	2.35 2.20	0.25	0.3 0.2	0.22 0.13	18.55 18.30	7.6 7.4	0.635	10.4 10.1	1.4	1.0 0.6	1.2 1.0	0.25	0.18	0.1	0.85 0.40	8° 0°

#### Note


1. Plastic or metal protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	EUROPEAN	ISSUE DATE		
VERSION	IEC	IEC JEDEC			PROJECTION	ISSUE DATE
SOT371-1		MO-118				<del>95-02-04</del> 99-12-27

2001 Sep 28 7

### TSSOP56: plastic thin shrink small outline package; 56 leads; body width 6.1 mm

SOT364-1



### DIMENSIONS (mm are the original dimensions).

UNIT	A max.	Α1	A <sub>2</sub>	A <sub>3</sub>	bp	С	D <sup>(1)</sup>	E <sup>(2)</sup>	е	HE	L	Lp	Q	v	w	у	Z	θ
mm	1.2	0.15 0.05	1.05 0.85	0.25	0.28 0.17	0.2 0.1	14.1 13.9	6.2 6.0	0.5	8.3 7.9	1.0	0.8 0.4	0.50 0.35	0.25	0.08	0.1	0.5 0.1	8° 0°

#### Notes

- 1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.
- 2. Plastic interlead protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	RENCES		EUROPEAN	ISSUE DATE
VERSION	IEC	JEDEC	EIAJ		PROJECTION	ISSUE DATE
SOT364-1		MO-153				<del>-95-02-10-</del> 99-12-27

24-bit level shifting bus exchange switch with 12-bit output enables

CBTD16212

**NOTES** 

# 24-bit level shifting bus exchange switch with 12-bit output enables

CBTD16212

#### Data sheet status

Data sheet status <sup>[1]</sup>	Product status <sup>[2]</sup>	Definitions
Objective data	Development	This data sheet contains data from the objective specification for product development.  Philips Semiconductors reserves the right to change the specification in any manner without notice.
Preliminary data	Qualification	This data sheet contains data from the preliminary specification. Supplementary data will be published at a later date. Philips Semiconductors reserves the right to change the specification without notice, in order to improve the design and supply the best possible product.
Product data	Production	This data sheet contains data from the product specification. Philips Semiconductors reserves the right to make changes at any time in order to improve the design, manufacturing and supply. Changes will be communicated according to the Customer Product/Process Change Notification (CPCN) procedure SNW-SQ-650A.

<sup>[1]</sup> Please consult the most recently issued data sheet before initiating or completing a design.

#### **Definitions**

**Short-form specification** — The data in a short-form specification is extracted from a full data sheet with the same type number and title. For detailed information see the relevant data sheet or data handbook.

Limiting values definition — Limiting values given are in accordance with the Absolute Maximum Rating System (IEC 60134). Stress above one or more of the limiting values may cause permanent damage to the device. These are stress ratings only and operation of the device at these or at any other conditions above those given in the Characteristics sections of the specification is not implied. Exposure to limiting values for extended periods may affect device reliability.

**Application information** — Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors make no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

### **Disclaimers**

**Life support** — These products are not designed for use in life support appliances, devices or systems where malfunction of these products can reasonably be expected to result in personal injury. Philips Semiconductors customers using or selling these products for use in such applications do so at their own risk and agree to fully indemnify Philips Semiconductors for any damages resulting from such application.

Right to make changes — Philips Semiconductors reserves the right to make changes, without notice, in the products, including circuits, standard cells, and/or software, described or contained herein in order to improve design and/or performance. Philips Semiconductors assumes no responsibility or liability for the use of any of these products, conveys no license or title under any patent, copyright, or mask work right to these products, and makes no representations or warranties that these products are free from patent, copyright, or mask work right infringement, unless otherwise specified.

### **Contact information**

For additional information please visit

http://www.semiconductors.philips.com. Fax: +31 40 27 24825

For sales offices addresses send e-mail to: sales.addresses@www.semiconductors.philips.com.

© Koninklijke Philips Electronics N.V. 2001 All rights reserved. Printed in U.S.A.

Date of release: 09-01

Document order number: 9397 750 08907

Let's make things better.

Philips Semiconductors





<sup>[2]</sup> The product status of the device(s) described in this data sheet may have changed since this data sheet was published. The latest information is available on the Internet at URL http://www.semiconductors.philips.com.